
Python Library Reference

Release 2.5.2

Guido van Rossum
Fred L. Drake, Jr., editor

21st February, 2008

Python Software Foundation

Email: docs@python.org

Copyright © 2001-2008 Python Software Foundation. All rights reserved.

Copyright © 2000 BeOpen.com. All rights reserved.

Copyright © 1995-2000 Corporation for National Research Initiatives. All rights reserved.

Copyright © 1991-1995 Stichting Mathematisch Centrum. All rights reserved.

See the end of this document for complete license and permissions information.

Abstract

Python is an extensible, interpreted, object-oriented programming language. It supports a wide range of applications, from simple text processing scripts to interactive Web browsers.

While the *Python Reference Manual* describes the exact syntax and semantics of the language, it does not describe the standard library that is distributed with the language, and which greatly enhances its immediate usability. This library contains built-in modules (written in C) that provide access to system functionality such as file I/O that would otherwise be inaccessible to Python programmers, as well as modules written in Python that provide standardized solutions for many problems that occur in everyday programming. Some of these modules are explicitly designed to encourage and enhance the portability of Python programs.

This library reference manual documents Python's standard library, as well as many optional library modules (which may or may not be available, depending on whether the underlying platform supports them and on the configuration choices made at compile time). It also documents the standard types of the language and its built-in functions and exceptions, many of which are not or incompletely documented in the Reference Manual.

This manual assumes basic knowledge about the Python language. For an informal introduction to Python, see the *Python Tutorial*; the *Python Reference Manual* remains the highest authority on syntactic and semantic questions. Finally, the manual entitled *Extending and Embedding the Python Interpreter* describes how to add new extensions to Python and how to embed it in other applications.

CONTENTS

1	Introduction	1
2	Built-in Objects	3
2.1	Built-in Functions	3
2.2	Non-essential Built-in Functions	16
2.3	Built-in Exceptions	17
2.4	Built-in Constants	22
3	Built-in Types	23
3.1	Truth Value Testing	23
3.2	Boolean Operations — <code>and</code> , <code>or</code> , <code>not</code>	23
3.3	Comparisons	24
3.4	Numeric Types — <code>int</code> , <code>float</code> , <code>long</code> , <code>complex</code>	25
3.5	Iterator Types	26
3.6	Sequence Types — <code>str</code> , <code>unicode</code> , <code>list</code> , <code>tuple</code> , <code>buffer</code> , <code>xrange</code>	27
3.7	Set Types — <code>set</code> , <code>frozenset</code>	36
3.8	Mapping Types — <code>dict</code>	37
3.9	File Objects	39
3.10	Context Manager Types	42
3.11	Other Built-in Types	42
3.12	Special Attributes	45
4	String Services	47
4.1	<code>string</code> — Common string operations	47
4.2	<code>re</code> — Regular expression operations	52
4.3	<code>struct</code> — Interpret strings as packed binary data	62
4.4	<code>difflib</code> — Helpers for computing deltas	65
4.5	<code>StringIO</code> — Read and write strings as files	74
4.6	<code>cStringIO</code> — Faster version of <code>StringIO</code>	75
4.7	<code>textwrap</code> — Text wrapping and filling	75
4.8	<code>codecs</code> — Codec registry and base classes	77
4.9	<code>unicodedata</code> — Unicode Database	90
4.10	<code>stringprep</code> — Internet String Preparation	91
4.11	<code>fpformat</code> — Floating point conversions	93
5	Data Types	95
5.1	<code>datetime</code> — Basic date and time types	95
5.2	<code>calendar</code> — General calendar-related functions	113
5.3	<code>collections</code> — High-performance container datatypes	116

5.4	heapq — Heap queue algorithm	121
5.5	bisect — Array bisection algorithm	124
5.6	array — Efficient arrays of numeric values	125
5.7	sets — Unordered collections of unique elements	128
5.8	sched — Event scheduler	131
5.9	mutex — Mutual exclusion support	132
5.10	Queue — A synchronized queue class	133
5.11	weakref — Weak references	134
5.12	UserDict — Class wrapper for dictionary objects	138
5.13	UserList — Class wrapper for list objects	139
5.14	UserString — Class wrapper for string objects	140
5.15	types — Names for built-in types	140
5.16	new — Creation of runtime internal objects	143
5.17	copy — Shallow and deep copy operations	143
5.18	pprint — Data pretty printer	144
5.19	repr — Alternate repr() implementation	147
6	Numeric and Mathematical Modules	149
6.1	math — Mathematical functions	149
6.2	cmath — Mathematical functions for complex numbers	151
6.3	decimal — Decimal floating point arithmetic	153
6.4	random — Generate pseudo-random numbers	169
6.5	itertools — Functions creating iterators for efficient looping	172
6.6	functools — Higher order functions and operations on callable objects.	181
6.7	operator — Standard operators as functions.	182
7	Internet Data Handling	189
7.1	email — An email and MIME handling package	189
7.2	mailcap — Mailcap file handling.	218
7.3	mailbox — Manipulate mailboxes in various formats	218
7.4	mhlib — Access to MH mailboxes	237
7.5	mimetools — Tools for parsing MIME messages	239
7.6	mimetypes — Map filenames to MIME types	241
7.7	MimeWriter — Generic MIME file writer	243
7.8	mimify — MIME processing of mail messages	244
7.9	multifile — Support for files containing distinct parts	245
7.10	rfc822 — Parse RFC 2822 mail headers	247
7.11	base64 — RFC 3548: Base16, Base32, Base64 Data Encodings	251
7.12	binhex — Encode and decode binhex4 files	253
7.13	binascii — Convert between binary and ASCII	253
7.14	quopri — Encode and decode MIME quoted-printable data	255
7.15	uu — Encode and decode uuencode files	256
8	Structured Markup Processing Tools	257
8.1	HTMLParser — Simple HTML and XHTML parser	257
8.2	sgmllib — Simple SGML parser	259
8.3	htmllib — A parser for HTML documents	262
8.4	htmlentitydefs — Definitions of HTML general entities	264
8.5	xml.parsers.expat — Fast XML parsing using Expat	264
8.6	xml.dom — The Document Object Model API	272
8.7	xml.dom.minidom — Lightweight DOM implementation	282
8.8	xml.dom.pulldom — Support for building partial DOM trees	287
8.9	xml.sax — Support for SAX2 parsers	288
8.10	xml.sax.handler — Base classes for SAX handlers	289

8.11	<code>xml.sax.saxutils</code> — SAX Utilities	293
8.12	<code>xml.sax.xmlreader</code> — Interface for XML parsers	294
8.13	<code>xml.etree.ElementTree</code> — The ElementTree XML API	298
9	File Formats	303
9.1	<code>csv</code> — CSV File Reading and Writing	303
9.2	<code>ConfigParser</code> — Configuration file parser	310
9.3	<code>robotparser</code> — Parser for robots.txt	313
9.4	<code>netrc</code> — netrc file processing	314
9.5	<code>xdrlib</code> — Encode and decode XDR data	315
10	Cryptographic Services	319
10.1	<code>hashlib</code> — Secure hashes and message digests	319
10.2	<code>hmac</code> — Keyed-Hashing for Message Authentication	321
10.3	<code>md5</code> — MD5 message digest algorithm	321
10.4	<code>sha</code> — SHA-1 message digest algorithm	322
11	File and Directory Access	325
11.1	<code>os.path</code> — Common pathname manipulations	325
11.2	<code>fileinput</code> — Iterate over lines from multiple input streams	328
11.3	<code>stat</code> — Interpreting <code>stat()</code> results	330
11.4	<code>statvfs</code> — Constants used with <code>os.statvfs()</code>	332
11.5	<code>filecmp</code> — File and Directory Comparisons	333
11.6	<code>tempfile</code> — Generate temporary files and directories	334
11.7	<code>glob</code> — UNIX style pathname pattern expansion	336
11.8	<code>fnmatch</code> — UNIX filename pattern matching	337
11.9	<code>linecache</code> — Random access to text lines	338
11.10	<code>shutil</code> — High-level file operations	338
11.11	<code>dircache</code> — Cached directory listings	340
12	Data Compression and Archiving	343
12.1	<code>zlib</code> — Compression compatible with gzip	343
12.2	<code>gzip</code> — Support for gzip files	345
12.3	<code>bz2</code> — Compression compatible with bzip2	346
12.4	<code>zipfile</code> — Work with ZIP archives	348
12.5	<code>tarfile</code> — Read and write tar archive files	351
13	Data Persistence	359
13.1	<code>pickle</code> — Python object serialization	359
13.2	<code>cPickle</code> — A faster <code>pickle</code>	370
13.3	<code>copy_reg</code> — Register <code>pickle</code> support functions	371
13.4	<code>shelve</code> — Python object persistence	371
13.5	<code>marshal</code> — Internal Python object serialization	373
13.6	<code>anydbm</code> — Generic access to DBM-style databases	375
13.7	<code>whichdb</code> — Guess which DBM module created a database	376
13.8	<code>dbm</code> — Simple “database” interface	376
13.9	<code>gdbm</code> — GNU’s reinterpretation of <code>dbm</code>	377
13.10	<code>dbhash</code> — DBM-style interface to the BSD database library	378
13.11	<code>bsddb</code> — Interface to Berkeley DB library	379
13.12	<code>dumbdbm</code> — Portable DBM implementation	382
13.13	<code>sqlite3</code> — DB-API 2.0 interface for SQLite databases	383
14	Generic Operating System Services	395
14.1	<code>os</code> — Miscellaneous operating system interfaces	395
14.2	<code>time</code> — Time access and conversions	415

14.3	<code>optparse</code> — More powerful command line option parser	420
14.4	<code>getopt</code> — Parser for command line options	447
14.5	<code>logging</code> — Logging facility for Python	450
14.6	<code>getpass</code> — Portable password input	472
14.7	<code>curses</code> — Terminal handling for character-cell displays	472
14.8	<code>curses.textpad</code> — Text input widget for <code>curses</code> programs	487
14.9	<code>curses.wrapper</code> — Terminal handler for <code>curses</code> programs	488
14.10	<code>curses.ascii</code> — Utilities for ASCII characters	488
14.11	<code>curses.panel</code> — A panel stack extension for <code>curses</code> .	491
14.12	<code>platform</code> — Access to underlying platform's identifying data.	492
14.13	<code>errno</code> — Standard <code>errno</code> system symbols	494
14.14	<code>ctypes</code> — A foreign function library for Python.	500
15	Optional Operating System Services	535
15.1	<code>select</code> — Waiting for I/O completion	535
15.2	<code>thread</code> — Multiple threads of control	536
15.3	<code>threading</code> — Higher-level threading interface	538
15.4	<code>dummy_thread</code> — Drop-in replacement for the <code>thread</code> module	546
15.5	<code>dummy_threading</code> — Drop-in replacement for the <code>threading</code> module	547
15.6	<code>mmap</code> — Memory-mapped file support	547
15.7	<code>readline</code> — GNU readline interface	549
15.8	<code>rlcompleter</code> — Completion function for GNU readline	551
16	Unix Specific Services	553
16.1	<code>posix</code> — The most common POSIX system calls	553
16.2	<code>pwd</code> — The password database	554
16.3	<code>spwd</code> — The shadow password database	555
16.4	<code>grp</code> — The group database	556
16.5	<code>crypt</code> — Function to check UNIX passwords	556
16.6	<code>dl</code> — Call C functions in shared objects	557
16.7	<code>termios</code> — POSIX style tty control	558
16.8	<code>tty</code> — Terminal control functions	559
16.9	<code>pty</code> — Pseudo-terminal utilities	560
16.10	<code>fcntl</code> — The <code>fcntl()</code> and <code>ioctl()</code> system calls	560
16.11	<code>pipes</code> — Interface to shell pipelines	562
16.12	<code>posixfile</code> — File-like objects with locking support	563
16.13	<code>resource</code> — Resource usage information	565
16.14	<code>nis</code> — Interface to Sun's NIS (Yellow Pages)	567
16.15	<code>syslog</code> — UNIX syslog library routines	568
16.16	<code>commands</code> — Utilities for running commands	569
17	Interprocess Communication and Networking	571
17.1	<code>subprocess</code> — Subprocess management	571
17.2	<code>socket</code> — Low-level networking interface	577
17.3	<code>signal</code> — Set handlers for asynchronous events	588
17.4	<code>popen2</code> — Subprocesses with accessible I/O streams	590
17.5	<code>asyncore</code> — Asynchronous socket handler	592
17.6	<code>asynchat</code> — Asynchronous socket command/response handler	595
18	Internet Protocols and Support	599
18.1	<code>webbrowser</code> — Convenient Web-browser controller	599
18.2	<code>cgi</code> — Common Gateway Interface support.	602
18.3	<code>cgitb</code> — Traceback manager for CGI scripts	609
18.4	<code>wsgiref</code> — WSGI Utilities and Reference Implementation	610
18.5	<code>urllib</code> — Open arbitrary resources by URL	617

18.6	<code>urllib2</code> — extensible library for opening URLs	622
18.7	<code>httpplib</code> — HTTP protocol client	632
18.8	<code>ftplib</code> — FTP protocol client	636
18.9	<code>gopherlib</code> — Gopher protocol client	640
18.10	<code>poplib</code> — POP3 protocol client	640
18.11	<code>imaplib</code> — IMAP4 protocol client	642
18.12	<code>nntplib</code> — NNTP protocol client	647
18.13	<code>smtplib</code> — SMTP protocol client	651
18.14	<code>smtpd</code> — SMTP Server	655
18.15	<code>telnetlib</code> — Telnet client	656
18.16	<code>uuid</code> — UUID objects according to RFC 4122	658
18.17	<code>urlparse</code> — Parse URLs into components	661
18.18	<code>SocketServer</code> — A framework for network servers	664
18.19	<code>BaseHTTPServer</code> — Basic HTTP server	667
18.20	<code>SimpleHTTPServer</code> — Simple HTTP request handler	670
18.21	<code>CGIHTTPServer</code> — CGI-capable HTTP request handler	671
18.22	<code>cookielib</code> — Cookie handling for HTTP clients	672
18.23	<code>Cookie</code> — HTTP state management	680
18.24	<code>xmlrpclib</code> — XML-RPC client access	684
18.25	<code>SimpleXMLRPCServer</code> — Basic XML-RPC server	688
18.26	<code>DocXMLRPCServer</code> — Self-documenting XML-RPC server	691
19	Multimedia Services	693
19.1	<code>audioop</code> — Manipulate raw audio data	693
19.2	<code>imageop</code> — Manipulate raw image data	696
19.3	<code>aifc</code> — Read and write AIFF and AIFC files	697
19.4	<code>sunau</code> — Read and write Sun AU files	699
19.5	<code>wave</code> — Read and write WAV files	702
19.6	<code>chunk</code> — Read IFF chunked data	704
19.7	<code>colorsys</code> — Conversions between color systems	705
19.8	<code>rgbimg</code> — Read and write “SGI RGB” files	705
19.9	<code>imghdr</code> — Determine the type of an image	706
19.10	<code>sndhdr</code> — Determine type of sound file	707
19.11	<code>ossaudiodev</code> — Access to OSS-compatible audio devices	707
20	Graphical User Interfaces with Tk	713
20.1	<code>Tkinter</code> — Python interface to Tcl/Tk	713
20.2	<code>Tix</code> — Extension widgets for Tk	725
20.3	<code>ScrolledText</code> — Scrolled Text Widget	729
20.4	<code>turtle</code> — Turtle graphics for Tk	730
20.5	<code>Idle</code>	733
20.6	Other Graphical User Interface Packages	736
21	Internationalization	739
21.1	<code>gettext</code> — Multilingual internationalization services	739
21.2	<code>locale</code> — Internationalization services	749
22	Program Frameworks	757
22.1	<code>cmd</code> — Support for line-oriented command interpreters	757
22.2	<code>shlex</code> — Simple lexical analysis	759
23	Development Tools	763
23.1	<code>pydoc</code> — Documentation generator and online help system	763
23.2	<code>doctest</code> — Test interactive Python examples	764
23.3	<code>unittest</code> — Unit testing framework	789

23.4	<code>test</code> — Regression tests package for Python	801
23.5	<code>test.test_support</code> — Utility functions for tests	803
24	The Python Debugger	805
24.1	Debugger Commands	806
24.2	How It Works	809
25	The Python Profilers	811
25.1	Introduction to the profilers	811
25.2	Instant User's Manual	812
25.3	What Is Deterministic Profiling?	814
25.4	Reference Manual — <code>profile</code> and <code>cProfile</code>	814
25.5	Limitations	817
25.6	Calibration	817
25.7	Extensions — Deriving Better Profilers	818
25.8	<code>hotshot</code> — High performance logging profiler	819
25.9	<code>timeit</code> — Measure execution time of small code snippets	821
25.10	<code>trace</code> — Trace or track Python statement execution	823
26	Python Runtime Services	827
26.1	<code>sys</code> — System-specific parameters and functions	827
26.2	<code>__builtin__</code> — Built-in objects	833
26.3	<code>__main__</code> — Top-level script environment	834
26.4	<code>warnings</code> — Warning control	834
26.5	<code>contextlib</code> — Utilities for <code>with</code> -statement contexts.	837
26.6	<code>atexit</code> — Exit handlers	839
26.7	<code>traceback</code> — Print or retrieve a stack traceback	840
26.8	<code>__future__</code> — Future statement definitions	842
26.9	<code>gc</code> — Garbage Collector interface	842
26.10	<code>inspect</code> — Inspect live objects	844
26.11	<code>site</code> — Site-specific configuration hook	850
26.12	<code>user</code> — User-specific configuration hook	851
26.13	<code>fpectl</code> — Floating point exception control	852
27	Custom Python Interpreters	855
27.1	<code>code</code> — Interpreter base classes	855
27.2	<code>codeop</code> — Compile Python code	857
28	Restricted Execution	859
28.1	<code>rexec</code> — Restricted execution framework	860
28.2	<code>Bastion</code> — Restricting access to objects	863
29	Importing Modules	865
29.1	<code>imp</code> — Access the <code>import</code> internals	865
29.2	<code>zipimport</code> — Import modules from Zip archives	868
29.3	<code>pkgutil</code> — Package extension utility	870
29.4	<code>modulefinder</code> — Find modules used by a script	870
29.5	<code>runpy</code> — Locating and executing Python modules.	871
30	Python Language Services	873
30.1	<code>parser</code> — Access Python parse trees	873
30.2	<code>symbol</code> — Constants used with Python parse trees	882
30.3	<code>token</code> — Constants used with Python parse trees	883
30.4	<code>keyword</code> — Testing for Python keywords	883
30.5	<code>tokenize</code> — Tokenizer for Python source	883

30.6	<code>tabnanny</code> — Detection of ambiguous indentation	885
30.7	<code>pyclbr</code> — Python class browser support	886
30.8	<code>py_compile</code> — Compile Python source files	887
30.9	<code>compileall</code> — Byte-compile Python libraries	887
30.10	<code>dis</code> — Disassembler for Python byte code	888
30.11	<code>pickletools</code> — Tools for pickle developers.	896
30.12	<code>distutils</code> — Building and installing Python modules	896
31	Python compiler package	897
31.1	The basic interface	897
31.2	Limitations	898
31.3	Python Abstract Syntax	898
31.4	Using Visitors to Walk ASTs	903
31.5	Bytecode Generation	904
32	Abstract Syntax Trees	905
32.1	Abstract Grammar	905
33	Miscellaneous Services	909
33.1	<code>formatter</code> — Generic output formatting	909
34	SGI IRIX Specific Services	913
34.1	<code>al</code> — Audio functions on the SGI	913
34.2	<code>AL</code> — Constants used with the <code>al</code> module	915
34.3	<code>cd</code> — CD-ROM access on SGI systems	915
34.4	<code>fl</code> — FORMS library for graphical user interfaces	919
34.5	<code>FL</code> — Constants used with the <code>fl</code> module	923
34.6	<code>flp</code> — Functions for loading stored FORMS designs	924
34.7	<code>fm</code> — <i>Font Manager</i> interface	924
34.8	<code>gl</code> — <i>Graphics Library</i> interface	925
34.9	<code>DEVICE</code> — Constants used with the <code>gl</code> module	927
34.10	<code>GL</code> — Constants used with the <code>gl</code> module	927
34.11	<code>imgfile</code> — Support for SGI <code>imglib</code> files	927
34.12	<code>jpeg</code> — Read and write JPEG files	928
35	SunOS Specific Services	931
35.1	<code>sunaudiodev</code> — Access to Sun audio hardware	931
35.2	<code>SUNAUDIODEV</code> — Constants used with <code>sunaudiodev</code>	932
36	MS Windows Specific Services	933
36.1	<code>msilib</code> — Read and write Microsoft Installer files	933
36.2	<code>msvcrt</code> — Useful routines from the MS VC++ runtime	939
36.3	<code>_winreg</code> — Windows registry access	940
36.4	<code>winsound</code> — Sound-playing interface for Windows	945
A	Undocumented Modules	947
A.1	Frameworks	947
A.2	Miscellaneous useful utilities	947
A.3	Platform specific modules	947
A.4	Multimedia	947
A.5	Obsolete	948
A.6	SGI-specific Extension modules	948
B	Reporting Bugs	949

C History and License	951
C.1 History of the software	951
C.2 Terms and conditions for accessing or otherwise using Python	952
C.3 Licenses and Acknowledgements for Incorporated Software	955
Module Index	965
Index	969

Introduction

The “Python library” contains several different kinds of components.

It contains data types that would normally be considered part of the “core” of a language, such as numbers and lists. For these types, the Python language core defines the form of literals and places some constraints on their semantics, but does not fully define the semantics. (On the other hand, the language core does define syntactic properties like the spelling and priorities of operators.)

The library also contains built-in functions and exceptions — objects that can be used by all Python code without the need of an `import` statement. Some of these are defined by the core language, but many are not essential for the core semantics and are only described here.

The bulk of the library, however, consists of a collection of modules. There are many ways to dissect this collection. Some modules are written in C and built in to the Python interpreter; others are written in Python and imported in source form. Some modules provide interfaces that are highly specific to Python, like printing a stack trace; some provide interfaces that are specific to particular operating systems, such as access to specific hardware; others provide interfaces that are specific to a particular application domain, like the World Wide Web. Some modules are available in all versions and ports of Python; others are only available when the underlying system supports or requires them; yet others are available only when a particular configuration option was chosen at the time when Python was compiled and installed.

This manual is organized “from the inside out:” it first describes the built-in data types, then the built-in functions and exceptions, and finally the modules, grouped in chapters of related modules. The ordering of the chapters as well as the ordering of the modules within each chapter is roughly from most relevant to least important.

This means that if you start reading this manual from the start, and skip to the next chapter when you get bored, you will get a reasonable overview of the available modules and application areas that are supported by the Python library. Of course, you don’t *have* to read it like a novel — you can also browse the table of contents (in front of the manual), or look for a specific function, module or term in the index (in the back). And finally, if you enjoy learning about random subjects, you choose a random page number (see module [random](#)) and read a section or two. Regardless of the order in which you read the sections of this manual, it helps to start with chapter 2, “Built-in Types, Exceptions and Functions,” as the remainder of the manual assumes familiarity with this material.

Let the show begin!

Built-in Objects

Names for built-in exceptions and functions and a number of constants are found in a separate symbol table. This table is searched last when the interpreter looks up the meaning of a name, so local and global user-defined names can override built-in names. Built-in types are described together here for easy reference.¹

The tables in this chapter document the priorities of operators by listing them in order of ascending priority (within a table) and grouping operators that have the same priority in the same box. Binary operators of the same priority group from left to right. (Unary operators group from right to left, but there you have no real choice.) See chapter 5 of the *Python Reference Manual* for the complete picture on operator priorities.

2.1 Built-in Functions

The Python interpreter has a number of functions built into it that are always available. They are listed here in alphabetical order.

`__import__(name[, globals[, locals[, fromlist[, level]]])`

This function is invoked by the `import` statement. It mainly exists so that you can replace it with another function that has a compatible interface, in order to change the semantics of the `import` statement. For examples of why and how you would do this, see the standard library modules `ihooks` and `rexec`. See also the built-in module `imp`, which defines some useful operations out of which you can build your own `__import__()` function.

For example, the statement `'import spam'` results in the following call: `__import__('spam', globals(), locals(), [], -1)`; the statement `'from spam.ham import eggs'` results in `'__import__('spam.ham', globals(), locals(), ['eggs'], -1)'`. Note that even though `locals()` and `['eggs']` are passed in as arguments, the `__import__()` function does not set the local variable named `eggs`; this is done by subsequent code that is generated for the `import` statement. (In fact, the standard implementation does not use its `locals` argument at all, and uses its `globals` only to determine the package context of the `import` statement.)

When the `name` variable is of the form `package.module`, normally, the top-level package (the name up till the first dot) is returned, *not* the module named by `name`. However, when a non-empty `fromlist` argument is given, the module named by `name` is returned. This is done for compatibility with the bytecode generated for the different kinds of import statement; when using `'import spam.ham.eggs'`, the top-level package `spam` must be placed in the importing namespace, but when using `'from spam.ham import eggs'`, the `spam.ham` subpackage must be used to find the `eggs` variable. As a workaround for this behavior, use `getattr()` to extract the desired components. For example, you could define the following helper:

¹Most descriptions sorely lack explanations of the exceptions that may be raised — this will be fixed in a future version of this manual.

```
def my_import(name):
    mod = __import__(name)
    components = name.split('.')
    for comp in components[1:]:
        mod = getattr(mod, comp)
    return mod
```

level specifies whether to use absolute or relative imports. The default is `-1` which indicates both absolute and relative imports will be attempted. `0` means only perform absolute imports. Positive values for *level* indicate the number of parent directories to search relative to the directory of the module calling `__import__`. Changed in version 2.5: The *level* parameter was added. Changed in version 2.5: Keyword support for parameters was added.

abs(*x*)

Return the absolute value of a number. The argument may be a plain or long integer or a floating point number. If the argument is a complex number, its magnitude is returned.

all(*iterable*)

Return True if all elements of the *iterable* are true. Equivalent to:

```
def all(iterable):
    for element in iterable:
        if not element:
            return False
    return True
```

New in version 2.5.

any(*iterable*)

Return True if any element of the *iterable* is true. Equivalent to:

```
def any(iterable):
    for element in iterable:
        if element:
            return True
    return False
```

New in version 2.5.

basestring()

This abstract type is the superclass for `str` and `unicode`. It cannot be called or instantiated, but it can be used to test whether an object is an instance of `str` or `unicode`. `isinstance(obj, basestring)` is equivalent to `isinstance(obj, (str, unicode))`. New in version 2.3.

bool(*[x]*)

Convert a value to a Boolean, using the standard truth testing procedure. If *x* is false or omitted, this returns False; otherwise it returns True. `bool` is also a class, which is a subclass of `int`. Class `bool` cannot be subclassed further. Its only instances are `False` and `True`.

New in version 2.2.1. Changed in version 2.3: If no argument is given, this function returns `False`.

callable(*object*)

Return true if the *object* argument appears callable, false if not. If this returns true, it is still possible that a call fails, but if it is false, calling *object* will never succeed. Note that classes are callable (calling a class returns a new instance); class instances are callable if they have a `__call__()` method.

chr(*i*)

Return a string of one character whose ASCII code is the integer *i*. For example, `chr(97)` returns the string `'a'`. This is the inverse of `ord()`. The argument must be in the range `[0..255]`, inclusive; `ValueError` will be raised if *i* is outside that range.

classmethod (*function*)

Return a class method for *function*.

A class method receives the class as implicit first argument, just like an instance method receives the instance. To declare a class method, use this idiom:

```
class C:
    @classmethod
    def f(cls, arg1, arg2, ...): ...
```

The `@classmethod` form is a function decorator – see the description of function definitions in chapter 7 of the [Python Reference Manual](#) for details.

It can be called either on the class (such as `C.f()`) or on an instance (such as `C().f()`). The instance is ignored except for its class. If a class method is called for a derived class, the derived class object is passed as the implied first argument.

Class methods are different than C++ or Java static methods. If you want those, see `staticmethod()` in this section.

For more information on class methods, consult the documentation on the standard type hierarchy in chapter 3 of the [Python Reference Manual](#) (at the bottom). New in version 2.2. Changed in version 2.4: Function decorator syntax added.

cmp (*x*, *y*)

Compare the two objects *x* and *y* and return an integer according to the outcome. The return value is negative if *x* < *y*, zero if *x* == *y* and strictly positive if *x* > *y*.

compile (*string*, *filename*, *kind*[, *flags*[, *dont_inherit*]])

Compile the *string* into a code object. Code objects can be executed by an `exec` statement or evaluated by a call to `eval()`. The *filename* argument should give the file from which the code was read; pass some recognizable value if it wasn't read from a file (`'<string>'` is commonly used). The *kind* argument specifies what kind of code must be compiled; it can be `'exec'` if *string* consists of a sequence of statements, `'eval'` if it consists of a single expression, or `'single'` if it consists of a single interactive statement (in the latter case, expression statements that evaluate to something else than `None` will be printed).

When compiling multi-line statements, two caveats apply: line endings must be represented by a single newline character (`'\n'`), and the input must be terminated by at least one newline character. If line endings are represented by `'\r\n'`, use the string `replace()` method to change them into `'\n'`.

The optional arguments *flags* and *dont_inherit* (which are new in Python 2.2) control which future statements (see PEP 236) affect the compilation of *string*. If neither is present (or both are zero) the code is compiled with those future statements that are in effect in the code that is calling `compile`. If the *flags* argument is given and *dont_inherit* is not (or is zero) then the future statements specified by the *flags* argument are used in addition to those that would be used anyway. If *dont_inherit* is a non-zero integer then the *flags* argument is it – the future statements in effect around the call to `compile` are ignored.

Future statements are specified by bits which can be bitwise or-ed together to specify multiple statements. The bitfield required to specify a given feature can be found as the `compiler_flag` attribute on the `_Feature` instance in the `__future__` module.

complex ([*real*[, *imag*]])

Create a complex number with the value *real* + *imag**j or convert a string or number to a complex number. If the first parameter is a string, it will be interpreted as a complex number and the function must be called without a second parameter. The second parameter can never be a string. Each argument may be any numeric type (including complex). If *imag* is omitted, it defaults to zero and the function serves as a numeric conversion function like `int()`, `long()` and `float()`. If both arguments are omitted, returns `0j`.

delattr(*object*, *name*)

This is a relative of `setattr()`. The arguments are an object and a string. The string must be the name of one of the object's attributes. The function deletes the named attribute, provided the object allows it. For example, `delattr(x, 'foobar')` is equivalent to `del x.foobar`.

dict([*arg*])

Return a new dictionary initialized from an optional positional argument or from a set of keyword arguments. If no arguments are given, return a new empty dictionary. If the positional argument *arg* is a mapping object, return a dictionary mapping the same keys to the same values as does the mapping object. Otherwise the positional argument must be a sequence, a container that supports iteration, or an iterator object. The elements of the argument must each also be of one of those kinds, and each must in turn contain exactly two objects. The first is used as a key in the new dictionary, and the second as the key's value. If a given key is seen more than once, the last value associated with it is retained in the new dictionary.

If keyword arguments are given, the keywords themselves with their associated values are added as items to the dictionary. If a key is specified both in the positional argument and as a keyword argument, the value associated with the keyword is retained in the dictionary. For example, these all return a dictionary equal to `{"one": 2, "two": 3}`:

```
•dict({'one': 2, 'two': 3})
•dict({'one': 2, 'two': 3}.items())
•dict({'one': 2, 'two': 3}.iteritems())
•dict(zip(['one', 'two'], (2, 3)))
•dict(['two', 3], ['one', 2])
•dict(one=2, two=3)
•dict([(['one', 'two'][i-2], i) for i in (2, 3)])
```

New in version 2.2. Changed in version 2.3: Support for building a dictionary from keyword arguments added.

dir([*object*])

Without arguments, return the list of names in the current local symbol table. With an argument, attempts to return a list of valid attributes for that object. This information is gleaned from the object's `__dict__` attribute, if defined, and from the class or type object. The list is not necessarily complete. If the object is a module object, the list contains the names of the module's attributes. If the object is a type or class object, the list contains the names of its attributes, and recursively of the attributes of its bases. Otherwise, the list contains the object's attributes' names, the names of its class's attributes, and recursively of the attributes of its class's base classes. The resulting list is sorted alphabetically. For example:

```
>>> import struct
>>> dir()
['__builtins__', '__doc__', '__name__', 'struct']
>>> dir(struct)
['__doc__', '__name__', 'calcsize', 'error', 'pack', 'unpack']
```

Note: Because `dir()` is supplied primarily as a convenience for use at an interactive prompt, it tries to supply an interesting set of names more than it tries to supply a rigorously or consistently defined set of names, and its detailed behavior may change across releases.

divmod(*a*, *b*)

Take two (non complex) numbers as arguments and return a pair of numbers consisting of their quotient and remainder when using long division. With mixed operand types, the rules for binary arithmetic operators apply. For plain and long integers, the result is the same as $(a // b, a \% b)$. For floating point numbers the result is $(q, a \% b)$, where q is usually `math.floor(a / b)` but may be 1 less than that. In any case $q * b + a \% b$ is very close to a , if $a \% b$ is non-zero it has the same sign as b , and $0 \leq \text{abs}(a \% b) < \text{abs}(b)$.

Changed in version 2.3: Using `divmod()` with complex numbers is deprecated.

enumerate (*iterable*)

Return an enumerate object. *iterable* must be a sequence, an iterator, or some other object which supports iteration. The `next()` method of the iterator returned by `enumerate()` returns a tuple containing a count (from zero) and the corresponding value obtained from iterating over *iterable*. `enumerate()` is useful for obtaining an indexed series: `(0, seq[0]), (1, seq[1]), (2, seq[2]), ...`. New in version 2.3.

eval (*expression*[, *globals*[, *locals*]])

The arguments are a string and optional globals and locals. If provided, *globals* must be a dictionary. If provided, *locals* can be any mapping object. Changed in version 2.4: formerly *locals* was required to be a dictionary.

The *expression* argument is parsed and evaluated as a Python expression (technically speaking, a condition list) using the *globals* and *locals* dictionaries as global and local name space. If the *globals* dictionary is present and lacks `'__builtins__'`, the current globals are copied into *globals* before *expression* is parsed. This means that *expression* normally has full access to the standard `__builtin__` module and restricted environments are propagated. If the *locals* dictionary is omitted it defaults to the *globals* dictionary. If both dictionaries are omitted, the expression is executed in the environment where `eval` is called. The return value is the result of the evaluated expression. Syntax errors are reported as exceptions. Example:

```
>>> x = 1
>>> print eval('x+1')
2
```

This function can also be used to execute arbitrary code objects (such as those created by `compile()`). In this case pass a code object instead of a string. The code object must have been compiled passing `'eval'` as the *kind* argument.

Hints: dynamic execution of statements is supported by the `exec` statement. Execution of statements from a file is supported by the `execfile()` function. The `globals()` and `locals()` functions returns the current global and local dictionary, respectively, which may be useful to pass around for use by `eval()` or `execfile()`.

execfile (*filename*[, *globals*[, *locals*]])

This function is similar to the `exec` statement, but parses a file instead of a string. It is different from the `import` statement in that it does not use the module administration — it reads the file unconditionally and does not create a new module.²

The arguments are a file name and two optional dictionaries. The file is parsed and evaluated as a sequence of Python statements (similarly to a module) using the *globals* and *locals* dictionaries as global and local namespace. If provided, *locals* can be any mapping object. Changed in version 2.4: formerly *locals* was required to be a dictionary. If the *locals* dictionary is omitted it defaults to the *globals* dictionary. If both dictionaries are omitted, the expression is executed in the environment where `execfile()` is called. The return value is `None`.

Warning: The default *locals* act as described for function `locals()` below: modifications to the default *locals* dictionary should not be attempted. Pass an explicit *locals* dictionary if you need to see effects of the code on *locals* after function `execfile()` returns. `execfile()` cannot be used reliably to modify a function's *locals*.

file (*filename*[, *mode*[, *bufsize*]])

Constructor function for the `file` type, described further in section 3.9, “[File Objects](#)”. The constructor's arguments are the same as those of the `open()` built-in function described below.

When opening a file, it's preferable to use `open()` instead of invoking this constructor directly. `file` is more suited to type testing (for example, writing `'isinstance(f, file)'`).

New in version 2.2.

filter (*function*, *iterable*)

Construct a list from those elements of *iterable* for which *function* returns true. *iterable* may be either a se-

²It is used relatively rarely so does not warrant being made into a statement.

quence, a container which supports iteration, or an iterator. If *iterable* is a string or a tuple, the result also has that type; otherwise it is always a list. If *function* is `None`, the identity function is assumed, that is, all elements of *iterable* that are false are removed.

Note that `filter(function, iterable)` is equivalent to `[item for item in iterable if function(item)]` if *function* is not `None` and `[item for item in iterable if item]` if *function* is `None`.

float ([*x*])

Convert a string or a number to floating point. If the argument is a string, it must contain a possibly signed decimal or floating point number, possibly embedded in whitespace. Otherwise, the argument may be a plain or long integer or a floating point number, and a floating point number with the same value (within Python's floating point precision) is returned. If no argument is given, returns `0.0`.

Note: When passing in a string, values for NaN and Infinity may be returned, depending on the underlying C library. The specific set of strings accepted which cause these values to be returned depends entirely on the C library and is known to vary.

frozenset ([*iterable*])

Return a frozenset object whose elements are taken from *iterable*. Frozensets are sets that have no update methods but can be hashed and used as members of other sets or as dictionary keys. The elements of a frozenset must be immutable themselves. To represent sets of sets, the inner sets should also be frozenset objects. If *iterable* is not specified, returns a new empty set, `frozenset([])`. New in version 2.4.

getattr (*object*, *name* [, *default*])

Return the value of the named attribute of *object*. *name* must be a string. If the string is the name of one of the object's attributes, the result is the value of that attribute. For example, `getattr(x, 'foobar')` is equivalent to `x.foobar`. If the named attribute does not exist, *default* is returned if provided, otherwise `AttributeError` is raised.

globals ()

Return a dictionary representing the current global symbol table. This is always the dictionary of the current module (inside a function or method, this is the module where it is defined, not the module from which it is called).

hasattr (*object*, *name*)

The arguments are an object and a string. The result is `True` if the string is the name of one of the object's attributes, `False` if not. (This is implemented by calling `getattr(object, name)` and seeing whether it raises an exception or not.)

hash (*object*)

Return the hash value of the object (if it has one). Hash values are integers. They are used to quickly compare dictionary keys during a dictionary lookup. Numeric values that compare equal have the same hash value (even if they are of different types, as is the case for `1` and `1.0`).

help ([*object*])

Invoke the built-in help system. (This function is intended for interactive use.) If no argument is given, the interactive help system starts on the interpreter console. If the argument is a string, then the string is looked up as the name of a module, function, class, method, keyword, or documentation topic, and a help page is printed on the console. If the argument is any other kind of object, a help page on the object is generated. New in version 2.2.

hex (*x*)

Convert an integer number (of any size) to a hexadecimal string. The result is a valid Python expression. Changed in version 2.4: Formerly only returned an unsigned literal.

id (*object*)

Return the "identity" of an object. This is an integer (or long integer) which is guaranteed to be unique and constant for this object during its lifetime. Two objects with non-overlapping lifetimes may have the same `id()` value. (Implementation note: this is the address of the object.)

input (*[prompt]*)

Equivalent to `eval (raw_input (prompt))`. **Warning:** This function is not safe from user errors! It expects a valid Python expression as input; if the input is not syntactically valid, a `SyntaxError` will be raised. Other exceptions may be raised if there is an error during evaluation. (On the other hand, sometimes this is exactly what you need when writing a quick script for expert use.)

If the `readline` module was loaded, then `input ()` will use it to provide elaborate line editing and history features.

Consider using the `raw_input ()` function for general input from users.

int (*[x[, radix]]*)

Convert a string or number to a plain integer. If the argument is a string, it must contain a possibly signed decimal number representable as a Python integer, possibly embedded in whitespace. The *radix* parameter gives the base for the conversion (which is 10 by default) and may be any integer in the range [2, 36], or zero. If *radix* is zero, the proper radix is guessed based on the contents of string; the interpretation is the same as for integer literals. If *radix* is specified and *x* is not a string, `TypeError` is raised. Otherwise, the argument may be a plain or long integer or a floating point number. Conversion of floating point numbers to integers truncates (towards zero). If the argument is outside the integer range a long object will be returned instead. If no arguments are given, returns 0.

isinstance (*object, classinfo*)

Return true if the *object* argument is an instance of the *classinfo* argument, or of a (direct or indirect) subclass thereof. Also return true if *classinfo* is a type object (new-style class) and *object* is an object of that type or of a (direct or indirect) subclass thereof. If *object* is not a class instance or an object of the given type, the function always returns false. If *classinfo* is neither a class object nor a type object, it may be a tuple of class or type objects, or may recursively contain other such tuples (other sequence types are not accepted). If *classinfo* is not a class, type, or tuple of classes, types, and such tuples, a `TypeError` exception is raised. Changed in version 2.2: Support for a tuple of type information was added.

issubclass (*class, classinfo*)

Return true if *class* is a subclass (direct or indirect) of *classinfo*. A class is considered a subclass of itself. *classinfo* may be a tuple of class objects, in which case every entry in *classinfo* will be checked. In any other case, a `TypeError` exception is raised. Changed in version 2.3: Support for a tuple of type information was added.

iter (*o[, sentinel]*)

Return an iterator object. The first argument is interpreted very differently depending on the presence of the second argument. Without a second argument, *o* must be a collection object which supports the iteration protocol (the `__iter__()` method), or it must support the sequence protocol (the `__getitem__()` method with integer arguments starting at 0). If it does not support either of those protocols, `TypeError` is raised. If the second argument, *sentinel*, is given, then *o* must be a callable object. The iterator created in this case will call *o* with no arguments for each call to its `next()` method; if the value returned is equal to *sentinel*, `StopIteration` will be raised, otherwise the value will be returned. New in version 2.2.

len (*s*)

Return the length (the number of items) of an object. The argument may be a sequence (string, tuple or list) or a mapping (dictionary).

list (*[iterable]*)

Return a list whose items are the same and in the same order as *iterable*'s items. *iterable* may be either a sequence, a container that supports iteration, or an iterator object. If *iterable* is already a list, a copy is made and returned, similar to *iterable*[:]. For instance, `list ('abc')` returns `['a', 'b', 'c']` and `list (1, 2, 3)` returns `[1, 2, 3]`. If no argument is given, returns a new empty list, `[]`.

locals ()

Update and return a dictionary representing the current local symbol table. **Warning:** The contents of this dictionary should not be modified; changes may not affect the values of local variables used by the interpreter.

long (*[x[, radix]]*)

Convert a string or number to a long integer. If the argument is a string, it must contain a possibly signed number of arbitrary size, possibly embedded in whitespace. The *radix* argument is interpreted in the same way as for `int()`, and may only be given when *x* is a string. Otherwise, the argument may be a plain or long integer or a floating point number, and a long integer with the same value is returned. Conversion of floating point numbers to integers truncates (towards zero). If no arguments are given, returns 0L.

map (*function*, *iterable*, ...)

Apply *function* to every item of *iterable* and return a list of the results. If additional *iterable* arguments are passed, *function* must take that many arguments and is applied to the items from all iterables in parallel. If one iterable is shorter than another it is assumed to be extended with `None` items. If *function* is `None`, the identity function is assumed; if there are multiple arguments, `map()` returns a list consisting of tuples containing the corresponding items from all iterables (a kind of transpose operation). The *iterable* arguments may be a sequence or any iterable object; the result is always a list.

max (*iterable*[, *args...*][*key*])

With a single argument *iterable*, return the largest item of a non-empty iterable (such as a string, tuple or list). With more than one argument, return the largest of the arguments.

The optional *key* argument specifies a one-argument ordering function like that used for `list.sort()`. The *key* argument, if supplied, must be in keyword form (for example, '`max(a,b,c,key=func)`'). Changed in version 2.5: Added support for the optional *key* argument.

min (*iterable*[, *args...*][*key*])

With a single argument *iterable*, return the smallest item of a non-empty iterable (such as a string, tuple or list). With more than one argument, return the smallest of the arguments.

The optional *key* argument specifies a one-argument ordering function like that used for `list.sort()`. The *key* argument, if supplied, must be in keyword form (for example, '`min(a,b,c,key=func)`'). Changed in version 2.5: Added support for the optional *key* argument.

object ()

Return a new featureless object. `object` is a base for all new style classes. It has the methods that are common to all instances of new style classes. New in version 2.2.

Changed in version 2.3: This function does not accept any arguments. Formerly, it accepted arguments but ignored them.

oct (*x*)

Convert an integer number (of any size) to an octal string. The result is a valid Python expression. Changed in version 2.4: Formerly only returned an unsigned literal.

open (*filename*[, *mode*[, *bufsize*]])

Open a file, returning an object of the `file` type described in section 3.9, “[File Objects](#)”. If the file cannot be opened, `IOError` is raised. When opening a file, it's preferable to use `open()` instead of invoking the `file` constructor directly.

The first two arguments are the same as for `stdio`'s `fopen()`: *filename* is the file name to be opened, and *mode* is a string indicating how the file is to be opened.

The most commonly-used values of *mode* are '`r`' for reading, '`w`' for writing (truncating the file if it already exists), and '`a`' for appending (which on *some* UNIX systems means that *all* writes append to the end of the file regardless of the current seek position). If *mode* is omitted, it defaults to '`r`'. When opening a binary file, you should append '`b`' to the *mode* value to open the file in binary mode, which will improve portability. (Appending '`b`' is useful even on systems that don't treat binary and text files differently, where it serves as documentation.) See below for more possible values of *mode*.

The optional *bufsize* argument specifies the file's desired buffer size: 0 means unbuffered, 1 means line buffered, any other positive value means use a buffer of (approximately) that size. A negative *bufsize* means to use the system default, which is usually line buffered for tty devices and fully buffered for other files. If omitted, the system default is used.³

³Specifying a buffer size currently has no effect on systems that don't have `setvbuf()`. The interface to specify the buffer size is not done

Modes `'r+'`, `'w+'` and `'a+'` open the file for updating (note that `'w+'` truncates the file). Append `'b'` to the mode to open the file in binary mode, on systems that differentiate between binary and text files; on systems that don't have this distinction, adding the `'b'` has no effect.

In addition to the standard `fopen()` values *mode* may be `'U'` or `'rU'`. Python is usually built with universal newline support; supplying `'U'` opens the file as a text file, but lines may be terminated by any of the following: the UNIX end-of-line convention `'\n'`, the Macintosh convention `'\r'`, or the Windows convention `'\r\n'`. All of these external representations are seen as `'\n'` by the Python program. If Python is built without universal newline support a *mode* with `'U'` is the same as normal text mode. Note that file objects so opened also have an attribute called `newlines` which has a value of `None` (if no newlines have yet been seen), `'\n'`, `'\r'`, `'\r\n'`, or a tuple containing all the newline types seen.

Python enforces that the mode, after stripping `'U'`, begins with `'r'`, `'w'` or `'a'`.

Changed in version 2.5: Restriction on first letter of mode string introduced.

ord(c)

Given a string of length one, return an integer representing the Unicode code point of the character when the argument is a unicode object, or the value of the byte when the argument is an 8-bit string. For example, `ord('a')` returns the integer 97, `ord(u'\u2020')` returns 8224. This is the inverse of `chr()` for 8-bit strings and of `unichr()` for unicode objects. If a unicode argument is given and Python was built with UCS2 Unicode, then the character's code point must be in the range [0..65535] inclusive; otherwise the string length is two, and a `TypeError` will be raised.

pow(x, y[, z])

Return *x* to the power *y*; if *z* is present, return *x* to the power *y*, modulo *z* (computed more efficiently than `pow(x, y) % z`). The two-argument form `pow(x, y)` is equivalent to using the power operator: `x**y`.

The arguments must have numeric types. With mixed operand types, the coercion rules for binary arithmetic operators apply. For int and long int operands, the result has the same type as the operands (after coercion) unless the second argument is negative; in that case, all arguments are converted to float and a float result is delivered. For example, `10**2` returns 100, but `10**-2` returns 0.01. (This last feature was added in Python 2.2. In Python 2.1 and before, if both arguments were of integer types and the second argument was negative, an exception was raised.) If the second argument is negative, the third argument must be omitted. If *z* is present, *x* and *y* must be of integer types, and *y* must be non-negative. (This restriction was added in Python 2.2. In Python 2.1 and before, floating 3-argument `pow()` returned platform-dependent results depending on floating-point rounding accidents.)

property([fget[, fset[, fdel[, doc]]]])

Return a property attribute for new-style classes (classes that derive from `object`).

fget is a function for getting an attribute value, likewise *fset* is a function for setting, and *fdel* a function for del'ing, an attribute. Typical use is to define a managed attribute *x*:

```
class C(object):
    def __init__(self): self._x = None
    def getx(self): return self._x
    def setx(self, value): self._x = value
    def delx(self): del self._x
    x = property(getx, setx, delx, "I'm the 'x' property.")
```

If given, *doc* will be the docstring of the property attribute. Otherwise, the property will copy *fget*'s docstring (if it exists). This makes it possible to create read-only properties easily using `property()` as a decorator:

using a method that calls `setvbuf()`, because that may dump core when called after any I/O has been performed, and there's no reliable way to determine whether this is the case.

```

class Parrot(object):
    def __init__(self):
        self._voltage = 100000

    @property
    def voltage(self):
        """Get the current voltage."""
        return self._voltage

```

turns the `voltage()` method into a “getter” for a read-only attribute with the same name.

New in version 2.2. Changed in version 2.5: Use `fget`’s docstring if no `doc` given.

range (*[start,] stop[, step]*)

This is a versatile function to create lists containing arithmetic progressions. It is most often used in `for` loops. The arguments must be plain integers. If the `step` argument is omitted, it defaults to 1. If the `start` argument is omitted, it defaults to 0. The full form returns a list of plain integers `[start, start + step, start + 2 * step, ...]`. If `step` is positive, the last element is the largest `start + i * step` less than `stop`; if `step` is negative, the last element is the smallest `start + i * step` greater than `stop`. `step` must not be zero (or else `ValueError` is raised). Example:

```

>>> range(10)
[0, 1, 2, 3, 4, 5, 6, 7, 8, 9]
>>> range(1, 11)
[1, 2, 3, 4, 5, 6, 7, 8, 9, 10]
>>> range(0, 30, 5)
[0, 5, 10, 15, 20, 25]
>>> range(0, 10, 3)
[0, 3, 6, 9]
>>> range(0, -10, -1)
[0, -1, -2, -3, -4, -5, -6, -7, -8, -9]
>>> range(0)
[]
>>> range(1, 0)
[]

```

raw_input (*[prompt]*)

If the *prompt* argument is present, it is written to standard output without a trailing newline. The function then reads a line from input, converts it to a string (stripping a trailing newline), and returns that. When EOF is read, `EOFError` is raised. Example:

```

>>> s = raw_input('--> ')
--> Monty Python's Flying Circus
>>> s
"Monty Python's Flying Circus"

```

If the `readline` module was loaded, then `raw_input()` will use it to provide elaborate line editing and history features.

reduce (*function, iterable[, initializer]*)

Apply *function* of two arguments cumulatively to the items of *iterable*, from left to right, so as to reduce the iterable to a single value. For example, `reduce(lambda x, y: x+y, [1, 2, 3, 4, 5])` calculates `(((1+2)+3)+4)+5`. The left argument, *x*, is the accumulated value and the right argument, *y*, is the update value from the *iterable*. If the optional *initializer* is present, it is placed before the items of the iterable in the calculation, and serves as a default when the iterable is empty. If *initializer* is not given and *iterable* contains only one item, the first item is returned.

reload(*module*)

Reload a previously imported *module*. The argument must be a module object, so it must have been successfully imported before. This is useful if you have edited the module source file using an external editor and want to try out the new version without leaving the Python interpreter. The return value is the module object (the same as the *module* argument).

When `reload(module)` is executed:

- Python modules' code is recompiled and the module-level code reexecuted, defining a new set of objects which are bound to names in the module's dictionary. The `init` function of extension modules is not called a second time.
- As with all other objects in Python the old objects are only reclaimed after their reference counts drop to zero.
- The names in the module namespace are updated to point to any new or changed objects.
- Other references to the old objects (such as names external to the module) are not rebound to refer to the new objects and must be updated in each namespace where they occur if that is desired.

There are a number of other caveats:

If a module is syntactically correct but its initialization fails, the first `import` statement for it does not bind its name locally, but does store a (partially initialized) module object in `sys.modules`. To reload the module you must first `import` it again (this will bind the name to the partially initialized module object) before you can `reload()` it.

When a module is reloaded, its dictionary (containing the module's global variables) is retained. Redefinitions of names will override the old definitions, so this is generally not a problem. If the new version of a module does not define a name that was defined by the old version, the old definition remains. This feature can be used to the module's advantage if it maintains a global table or cache of objects — with a `try` statement it can test for the table's presence and skip its initialization if desired:

```
try:
    cache
except NameError:
    cache = {}
```

It is legal though generally not very useful to reload built-in or dynamically loaded modules, except for `sys`, `__main__` and `__builtin__`. In many cases, however, extension modules are not designed to be initialized more than once, and may fail in arbitrary ways when reloaded.

If a module imports objects from another module using `from... import...`, calling `reload()` for the other module does not redefine the objects imported from it — one way around this is to re-execute the `from` statement, another is to use `import` and qualified names (*module.name*) instead.

If a module instantiates instances of a class, reloading the module that defines the class does not affect the method definitions of the instances — they continue to use the old class definition. The same is true for derived classes.

repr(*object*)

Return a string containing a printable representation of an object. This is the same value yielded by conversions (reverse quotes). It is sometimes useful to be able to access this operation as an ordinary function. For many types, this function makes an attempt to return a string that would yield an object with the same value when passed to `eval()`.

reversed(*seq*)

Return a reverse iterator. *seq* must be an object which supports the sequence protocol (the `__len__()` method and the `__getitem__()` method with integer arguments starting at 0). New in version 2.4.

round (*x*, *n*)

Return the floating point value *x* rounded to *n* digits after the decimal point. If *n* is omitted, it defaults to zero. The result is a floating point number. Values are rounded to the closest multiple of 10 to the power minus *n*; if two multiples are equally close, rounding is done away from 0 (so. for example, `round(0.5)` is 1.0 and `round(-0.5)` is -1.0).

set ([*iterable*])

Return a set whose elements are taken from *iterable*. The elements must be immutable. To represent sets of sets, the inner sets should be `frozenset` objects. If *iterable* is not specified, returns a new empty set, `set()`. New in version 2.4.

setattr (*object*, *name*, *value*)

This is the counterpart of `getattr()`. The arguments are an object, a string and an arbitrary value. The string may name an existing attribute or a new attribute. The function assigns the value to the attribute, provided the object allows it. For example, `setattr(x, 'foobar', 123)` is equivalent to `x.foobar = 123`.

slice ([*start*,] *stop*, [*step*])

Return a slice object representing the set of indices specified by `range(start, stop, step)`. The *start* and *step* arguments default to `None`. Slice objects have read-only data attributes *start*, *stop* and *step* which merely return the argument values (or their default). They have no other explicit functionality; however they are used by Numerical Python and other third party extensions. Slice objects are also generated when extended indexing syntax is used. For example: `a[start:stop:step]` or `a[start:stop, i]`.

sorted (*iterable*, [*cmp*, *key*, *reverse*]])

Return a new sorted list from the items in *iterable*.

The optional arguments *cmp*, *key*, and *reverse* have the same meaning as those for the `list.sort()` method (described in section 3.6.4).

cmp specifies a custom comparison function of two arguments (iterable elements) which should return a negative, zero or positive number depending on whether the first argument is considered smaller than, equal to, or larger than the second argument: `'cmp=lambda x,y: cmp(x.lower(), y.lower())'`

key specifies a function of one argument that is used to extract a comparison key from each list element: `'key=str.lower'`

reverse is a boolean value. If set to `True`, then the list elements are sorted as if each comparison were reversed.

In general, the *key* and *reverse* conversion processes are much faster than specifying an equivalent *cmp* function. This is because *cmp* is called multiple times for each list element while *key* and *reverse* touch each element only once.

New in version 2.4.

staticmethod (*function*)

Return a static method for *function*.

A static method does not receive an implicit first argument. To declare a static method, use this idiom:

```
class C:
    @staticmethod
    def f(arg1, arg2, ...): ...
```

The `@staticmethod` form is a function decorator – see the description of function definitions in chapter 7 of the [Python Reference Manual](#) for details.

It can be called either on the class (such as `C.f()`) or on an instance (such as `C().f()`). The instance is ignored except for its class.

Static methods in Python are similar to those found in Java or C++. For a more advanced concept, see `classmethod()` in this section.

For more information on static methods, consult the documentation on the standard type hierarchy in chapter 3 of the *Python Reference Manual* (at the bottom). New in version 2.2. Changed in version 2.4: Function decorator syntax added.

str(*[object]*)

Return a string containing a nicely printable representation of an object. For strings, this returns the string itself. The difference with `repr(object)` is that `str(object)` does not always attempt to return a string that is acceptable to `eval()`; its goal is to return a printable string. If no argument is given, returns the empty string, `''`.

sum(*iterable*, *start*)

Sums *start* and the items of an *iterable* from left to right and returns the total. *start* defaults to 0. The *iterable*'s items are normally numbers, and are not allowed to be strings. The fast, correct way to concatenate a sequence of strings is by calling `''.join(sequence)`. Note that `sum(range(n), m)` is equivalent to `reduce(operator.add, range(n), m)`. New in version 2.3.

super(*type*, *object-or-type*)

Return the superclass of *type*. If the second argument is omitted the super object returned is unbound. If the second argument is an object, `isinstance(obj, type)` must be true. If the second argument is a type, `issubclass(type2, type)` must be true. `super()` only works for new-style classes.

A typical use for calling a cooperative superclass method is:

```
class C(B):
    def meth(self, arg):
        super(C, self).meth(arg)
```

Note that `super` is implemented as part of the binding process for explicit dotted attribute lookups such as `'super(C, self).__getitem__(name)'`. Accordingly, `super` is undefined for implicit lookups using statements or operators such as `'super(C, self)[name]'`. New in version 2.2.

tuple(*[iterable]*)

Return a tuple whose items are the same and in the same order as *iterable*'s items. *iterable* may be a sequence, a container that supports iteration, or an iterator object. If *iterable* is already a tuple, it is returned unchanged. For instance, `tuple('abc')` returns `('a', 'b', 'c')` and `tuple([1, 2, 3])` returns `(1, 2, 3)`. If no argument is given, returns a new empty tuple, `()`.

type(*object*)

Return the type of an *object*. The return value is a type object. The `isinstance()` built-in function is recommended for testing the type of an object.

With three arguments, `type` functions as a constructor as detailed below.

type(*name*, *bases*, *dict*)

Return a new type object. This is essentially a dynamic form of the `class` statement. The *name* string is the class name and becomes the `__name__` attribute; the *bases* tuple itemizes the base classes and becomes the `__bases__` attribute; and the *dict* dictionary is the namespace containing definitions for class body and becomes the `__dict__` attribute. For example, the following two statements create identical type objects:

```
>>> class X(object):
...     a = 1
...
>>> X = type('X', (object,), dict(a=1))
```

New in version 2.2.

unichr(*i*)

Return the Unicode string of one character whose Unicode code is the integer *i*. For example, `unichr(97)` returns the string `u'a'`. This is the inverse of `ord()` for Unicode strings. The valid range for the argument depends how Python was configured – it may be either UCS2 `[0..0xFFFF]` or UCS4 `[0..0x10FFFF]`. `ValueError`

is raised otherwise. New in version 2.0.

unicode ([*object* [, *encoding* [, *errors*]]])

Return the Unicode string version of *object* using one of the following modes:

If *encoding* and/or *errors* are given, `unicode()` will decode the object which can either be an 8-bit string or a character buffer using the codec for *encoding*. The *encoding* parameter is a string giving the name of an encoding; if the encoding is not known, `LookupError` is raised. Error handling is done according to *errors*; this specifies the treatment of characters which are invalid in the input encoding. If *errors* is 'strict' (the default), a `ValueError` is raised on errors, while a value of 'ignore' causes errors to be silently ignored, and a value of 'replace' causes the official Unicode replacement character, U+FFFD, to be used to replace input characters which cannot be decoded. See also the `codecs` module.

If no optional parameters are given, `unicode()` will mimic the behaviour of `str()` except that it returns Unicode strings instead of 8-bit strings. More precisely, if *object* is a Unicode string or subclass it will return that Unicode string without any additional decoding applied.

For objects which provide a `__unicode__()` method, it will call this method without arguments to create a Unicode string. For all other objects, the 8-bit string version or representation is requested and then converted to a Unicode string using the codec for the default encoding in 'strict' mode.

New in version 2.0. Changed in version 2.2: Support for `__unicode__()` added.

vars ([*object*])

Without arguments, return a dictionary corresponding to the current local symbol table. With a module, class or class instance object as argument (or anything else that has a `__dict__` attribute), returns a dictionary corresponding to the object's symbol table. The returned dictionary should not be modified: the effects on the corresponding symbol table are undefined.⁴

xrange ([*start*,] *stop* [, *step*])

This function is very similar to `range()`, but returns an "xrange object" instead of a list. This is an opaque sequence type which yields the same values as the corresponding list, without actually storing them all simultaneously. The advantage of `xrange()` over `range()` is minimal (since `xrange()` still has to create the values when asked for them) except when a very large range is used on a memory-starved machine or when all of the range's elements are never used (such as when the loop is usually terminated with `break`).

Note: `xrange()` is intended to be simple and fast. Implementations may impose restrictions to achieve this. The C implementation of Python restricts all arguments to native C longs ("short" Python integers), and also requires that the number of elements fit in a native C long.

zip ([*iterable*, ...])

This function returns a list of tuples, where the *i*-th tuple contains the *i*-th element from each of the argument sequences or iterables. The returned list is truncated in length to the length of the shortest argument sequence. When there are multiple arguments which are all of the same length, `zip()` is similar to `map()` with an initial argument of `None`. With a single sequence argument, it returns a list of 1-tuples. With no arguments, it returns an empty list. New in version 2.0.

Changed in version 2.4: Formerly, `zip()` required at least one argument and `zip()` raised a `TypeError` instead of returning an empty list.

2.2 Non-essential Built-in Functions

There are several built-in functions that are no longer essential to learn, know or use in modern Python programming. They have been kept here to maintain backwards compatibility with programs written for older versions of Python.

Python programmers, trainers, students and bookwriters should feel free to bypass these functions without concerns about missing something important.

⁴In the current implementation, local variable bindings cannot normally be affected this way, but variables retrieved from other scopes (such as modules) can be. This may change.

apply (*function*, *args*[, *keywords*])

The *function* argument must be a callable object (a user-defined or built-in function or method, or a class object) and the *args* argument must be a sequence. The *function* is called with *args* as the argument list; the number of arguments is the length of the tuple. If the optional *keywords* argument is present, it must be a dictionary whose keys are strings. It specifies keyword arguments to be added to the end of the argument list. Calling `apply()` is different from just calling `function(args)`, since in that case there is always exactly one argument. The use of `apply()` is exactly equivalent to `function(*args, **keywords)`.

Deprecated since release 2.3. Use the extended call syntax with `*args` and `**keywords` instead.

buffer (*object*[, *offset*[, *size*]])

The *object* argument must be an object that supports the buffer call interface (such as strings, arrays, and buffers). A new buffer object will be created which references the *object* argument. The buffer object will be a slice from the beginning of *object* (or from the specified *offset*). The slice will extend to the end of *object* (or will have a length given by the *size* argument).

coerce (*x*, *y*)

Return a tuple consisting of the two numeric arguments converted to a common type, using the same rules as used by arithmetic operations. If coercion is not possible, raise `TypeError`.

intern (*string*)

Enter *string* in the table of “interned” strings and return the interned string – which is *string* itself or a copy. Interning strings is useful to gain a little performance on dictionary lookup – if the keys in a dictionary are interned, and the lookup key is interned, the key comparisons (after hashing) can be done by a pointer compare instead of a string compare. Normally, the names used in Python programs are automatically interned, and the dictionaries used to hold module, class or instance attributes have interned keys. Changed in version 2.3: Interned strings are not immortal (like they used to be in Python 2.2 and before); you must keep a reference to the return value of `intern()` around to benefit from it.

2.3 Built-in Exceptions

Exceptions should be class objects. The exceptions are defined in the module `exceptions`. This module never needs to be imported explicitly: the exceptions are provided in the built-in namespace as well as the `exceptions` module.

Note: In past versions of Python string exceptions were supported. In Python 1.5 and newer versions, all standard exceptions have been converted to class objects and users are encouraged to do the same. String exceptions will raise a `DeprecationWarning` in Python 2.5 and newer. In future versions, support for string exceptions will be removed.

Two distinct string objects with the same value are considered different exceptions. This is done to force programmers to use exception names rather than their string value when specifying exception handlers. The string value of all built-in exceptions is their name, but this is not a requirement for user-defined exceptions or exceptions defined by library modules.

For class exceptions, in a `try` statement with an `except` clause that mentions a particular class, that clause also handles any exception classes derived from that class (but not exception classes from which *it* is derived). Two exception classes that are not related via subclassing are never equivalent, even if they have the same name.

The built-in exceptions listed below can be generated by the interpreter or built-in functions. Except where mentioned, they have an “associated value” indicating the detailed cause of the error. This may be a string or a tuple containing several items of information (e.g., an error code and a string explaining the code). The associated value is the second argument to the `raise` statement. For string exceptions, the associated value itself will be stored in the variable named as the second argument of the `except` clause (if any). For class exceptions, that variable receives the exception instance. If the exception class is derived from the standard root class `BaseException`, the associated value is present as the exception instance’s `args` attribute. If there is a single argument (as is preferred), it is bound to the `message` attribute.

User code can raise built-in exceptions. This can be used to test an exception handler or to report an error condition “just like” the situation in which the interpreter raises the same exception; but beware that there is nothing to prevent user code from raising an inappropriate error.

The built-in exception classes can be sub-classed to define new exceptions; programmers are encouraged to at least derive new exceptions from the `Exception` class and not `BaseException`. More information on defining exceptions is available in the [Python Tutorial](#) under the heading “User-defined Exceptions.”

The following exceptions are only used as base classes for other exceptions.

exception `BaseException`

The base class for all built-in exceptions. It is not meant to be directly inherited by user-defined classes (for that use `Exception`). If `str()` or `unicode()` is called on an instance of this class, the representation of the argument(s) to the instance are returned or the empty string when there were no arguments. If only a single argument is passed in, it is stored in the `message` attribute. If more than one argument is passed in, `message` is set to the empty string. These semantics are meant to reflect the fact that `message` is to store a text message explaining why the exception had been raised. If more data needs to be attached to the exception, attach it through arbitrary attributes on the instance. All arguments are also stored in `args` as a tuple, but it will eventually be deprecated and thus its use is discouraged. New in version 2.5.

exception `Exception`

All built-in, non-system-exiting exceptions are derived from this class. All user-defined exceptions should also be derived from this class. Changed in version 2.5: Changed to inherit from `BaseException`.

exception `StandardError`

The base class for all built-in exceptions except `StopIteration`, `GeneratorExit`, `KeyboardInterrupt` and `SystemExit`. `StandardError` itself is derived from `Exception`.

exception `ArithmeticError`

The base class for those built-in exceptions that are raised for various arithmetic errors: `OverflowError`, `ZeroDivisionError`, `FloatingPointError`.

exception `LookupError`

The base class for the exceptions that are raised when a key or index used on a mapping or sequence is invalid: `IndexError`, `KeyError`. This can be raised directly by `sys.setdefaultencoding()`.

exception `EnvironmentError`

The base class for exceptions that can occur outside the Python system: `IOError`, `OSError`. When exceptions of this type are created with a 2-tuple, the first item is available on the instance’s `errno` attribute (it is assumed to be an error number), and the second item is available on the `strerror` attribute (it is usually the associated error message). The tuple itself is also available on the `args` attribute. New in version 1.5.2.

When an `EnvironmentError` exception is instantiated with a 3-tuple, the first two items are available as above, while the third item is available on the `filename` attribute. However, for backwards compatibility, the `args` attribute contains only a 2-tuple of the first two constructor arguments.

The `filename` attribute is `None` when this exception is created with other than 3 arguments. The `errno` and `strerror` attributes are also `None` when the instance was created with other than 2 or 3 arguments. In this last case, `args` contains the verbatim constructor arguments as a tuple.

The following exceptions are the exceptions that are actually raised.

exception `AssertionError`

Raised when an `assert` statement fails.

exception `AttributeError`

Raised when an attribute reference or assignment fails. (When an object does not support attribute references or attribute assignments at all, `TypeError` is raised.)

exception `EOFError`

Raised when one of the built-in functions (`input()` or `raw_input()`) hits an end-of-file condition (EOF) without reading any data. (N.B.: the `read()` and `readline()` methods of file objects return an empty string

when they hit EOF.)

exception FloatingPointError

Raised when a floating point operation fails. This exception is always defined, but can only be raised when Python is configured with the `--with-fpectl` option, or the `WANT_SIGFPE_HANDLER` symbol is defined in the `'pyconfig.h'` file.

exception GeneratorExit

Raise when a generator's `close()` method is called. It directly inherits from `Exception` instead of `StandardError` since it is technically not an error. New in version 2.5.

exception IOError

Raised when an I/O operation (such as a `print` statement, the built-in `open()` function or a method of a file object) fails for an I/O-related reason, e.g., “file not found” or “disk full”.

This class is derived from `EnvironmentError`. See the discussion above for more information on exception instance attributes.

exception ImportError

Raised when an `import` statement fails to find the module definition or when a `from ... import` fails to find a name that is to be imported.

exception IndexError

Raised when a sequence subscript is out of range. (Slice indices are silently truncated to fall in the allowed range; if an index is not a plain integer, `TypeError` is raised.)

exception KeyError

Raised when a mapping (dictionary) key is not found in the set of existing keys.

exception KeyboardInterrupt

Raised when the user hits the interrupt key (normally `Control-C` or `Delete`). During execution, a check for interrupts is made regularly. Interrupts typed when a built-in function `input()` or `raw_input()` is waiting for input also raise this exception. The exception inherits from `BaseException` so as to not be accidentally caught by code that catches `Exception` and thus prevent the interpreter from exiting. Changed in version 2.5: Changed to inherit from `BaseException`.

exception MemoryError

Raised when an operation runs out of memory but the situation may still be rescued (by deleting some objects). The associated value is a string indicating what kind of (internal) operation ran out of memory. Note that because of the underlying memory management architecture (C's `malloc()` function), the interpreter may not always be able to completely recover from this situation; it nevertheless raises an exception so that a stack traceback can be printed, in case a run-away program was the cause.

exception NameError

Raised when a local or global name is not found. This applies only to unqualified names. The associated value is an error message that includes the name that could not be found.

exception NotImplementedError

This exception is derived from `RuntimeError`. In user defined base classes, abstract methods should raise this exception when they require derived classes to override the method. New in version 1.5.2.

exception OSError

This class is derived from `EnvironmentError` and is used primarily as the `os` module's `os.error` exception. See `EnvironmentError` above for a description of the possible associated values. New in version 1.5.2.

exception OverflowError

Raised when the result of an arithmetic operation is too large to be represented. This cannot occur for long integers (which would rather raise `MemoryError` than give up). Because of the lack of standardization of floating point exception handling in C, most floating point operations also aren't checked. For plain integers, all operations that can overflow are checked except left shift, where typical applications prefer to drop bits than

raise an exception.

exception ReferenceError

This exception is raised when a weak reference proxy, created by the `weakref.proxy()` function, is used to access an attribute of the referent after it has been garbage collected. For more information on weak references, see the `weakref` module. New in version 2.2: Previously known as the `weakref.ReferenceError` exception.

exception RuntimeError

Raised when an error is detected that doesn't fall in any of the other categories. The associated value is a string indicating what precisely went wrong. (This exception is mostly a relic from a previous version of the interpreter; it is not used very much any more.)

exception StopIteration

Raised by an iterator's `next()` method to signal that there are no further values. This is derived from `Exception` rather than `StandardError`, since this is not considered an error in its normal application. New in version 2.2.

exception SyntaxError

Raised when the parser encounters a syntax error. This may occur in an `import` statement, in an `exec` statement, in a call to the built-in function `eval()` or `input()`, or when reading the initial script or standard input (also interactively).

Instances of this class have attributes `filename`, `lineno`, `offset` and `text` for easier access to the details. `str()` of the exception instance returns only the message.

exception SystemError

Raised when the interpreter finds an internal error, but the situation does not look so serious to cause it to abandon all hope. The associated value is a string indicating what went wrong (in low-level terms).

You should report this to the author or maintainer of your Python interpreter. Be sure to report the version of the Python interpreter (`sys.version`; it is also printed at the start of an interactive Python session), the exact error message (the exception's associated value) and if possible the source of the program that triggered the error.

exception SystemExit

This exception is raised by the `sys.exit()` function. When it is not handled, the Python interpreter exits; no stack traceback is printed. If the associated value is a plain integer, it specifies the system exit status (passed to C's `exit()` function); if it is `None`, the exit status is zero; if it has another type (such as a string), the object's value is printed and the exit status is one.

Instances have an attribute `code` which is set to the proposed exit status or error message (defaulting to `None`). Also, this exception derives directly from `BaseException` and not `StandardError`, since it is not technically an error.

A call to `sys.exit()` is translated into an exception so that clean-up handlers (`finally` clauses of `try` statements) can be executed, and so that a debugger can execute a script without running the risk of losing control. The `os._exit()` function can be used if it is absolutely positively necessary to exit immediately (for example, in the child process after a call to `fork()`).

The exception inherits from `BaseException` instead of `StandardError` or `Exception` so that it is not accidentally caught by code that catches `Exception`. This allows the exception to properly propagate up and cause the interpreter to exit. Changed in version 2.5: Changed to inherit from `BaseException`.

exception TypeError

Raised when an operation or function is applied to an object of inappropriate type. The associated value is a string giving details about the type mismatch.

exception UnboundLocalError

Raised when a reference is made to a local variable in a function or method, but no value has been bound to that variable. This is a subclass of `NameError`. New in version 2.0.

exception UnicodeError

Raised when a Unicode-related encoding or decoding error occurs. It is a subclass of `ValueError`. New in version 2.0.

exception UnicodeEncodeError

Raised when a Unicode-related error occurs during encoding. It is a subclass of `UnicodeError`. New in version 2.3.

exception UnicodeDecodeError

Raised when a Unicode-related error occurs during decoding. It is a subclass of `UnicodeError`. New in version 2.3.

exception UnicodeTranslateError

Raised when a Unicode-related error occurs during translating. It is a subclass of `UnicodeError`. New in version 2.3.

exception ValueError

Raised when a built-in operation or function receives an argument that has the right type but an inappropriate value, and the situation is not described by a more precise exception such as `IndexError`.

exception WindowsError

Raised when a Windows-specific error occurs or when the error number does not correspond to an `errno` value. The `winerror` and `strerror` values are created from the return values of the `GetLastError()` and `FormatMessage()` functions from the Windows Platform API. The `errno` value maps the `winerror` value to corresponding `errno.h` values. This is a subclass of `OSError`. New in version 2.0. Changed in version 2.5: Previous versions put the `GetLastError()` codes into `errno`.

exception ZeroDivisionError

Raised when the second argument of a division or modulo operation is zero. The associated value is a string indicating the type of the operands and the operation.

The following exceptions are used as warning categories; see the [warnings](#) module for more information.

exception Warning

Base class for warning categories.

exception UserWarning

Base class for warnings generated by user code.

exception DeprecationWarning

Base class for warnings about deprecated features.

exception PendingDeprecationWarning

Base class for warnings about features which will be deprecated in the future.

exception SyntaxWarning

Base class for warnings about dubious syntax

exception RuntimeWarning

Base class for warnings about dubious runtime behavior.

exception FutureWarning

Base class for warnings about constructs that will change semantically in the future.

exception ImportWarning

Base class for warnings about probable mistakes in module imports. New in version 2.5.

exception UnicodeWarning

Base class for warnings related to Unicode. New in version 2.5.

The class hierarchy for built-in exceptions is:

`_hierarchy.txt`

2.4 Built-in Constants

A small number of constants live in the built-in namespace. They are:

False

The false value of the `bool` type. New in version 2.3.

True

The true value of the `bool` type. New in version 2.3.

None

The sole value of `types.NoneType`. `None` is frequently used to represent the absence of a value, as when default arguments are not passed to a function.

NotImplemented

Special value which can be returned by the “rich comparison” special methods (`__eq__()`, `__lt__()`, and friends), to indicate that the comparison is not implemented with respect to the other type.

Ellipsis

Special value used in conjunction with extended slicing syntax.

Built-in Types

The following sections describe the standard types that are built into the interpreter. **Note:** Historically (until release 2.2), Python’s built-in types have differed from user-defined types because it was not possible to use the built-in types as the basis for object-oriented inheritance. This limitation does not exist any longer.

The principal built-in types are numerics, sequences, mappings, files, classes, instances and exceptions.

Some operations are supported by several object types; in particular, practically all objects can be compared, tested for truth value, and converted to a string (with the `repr()` function or the slightly different `str()` function). The latter function is implicitly used when an object is written by the `print` statement. (Information on the [print statement](#) and other language statements can be found in the [Python Reference Manual](#) and the [Python Tutorial](#).)

3.1 Truth Value Testing

Any object can be tested for truth value, for use in an `if` or `while` condition or as operand of the Boolean operations below. The following values are considered false:

- `None`
- `False`
- zero of any numeric type, for example, `0`, `0L`, `0.0`, `0j`.
- any empty sequence, for example, `''`, `()`, `[]`.
- any empty mapping, for example, `{}`.
- instances of user-defined classes, if the class defines a `__nonzero__()` or `__len__()` method, when that method returns the integer zero or bool value `False`.¹

All other values are considered true — so objects of many types are always true.

Operations and built-in functions that have a Boolean result always return `0` or `False` for false and `1` or `True` for true, unless otherwise stated. (Important exception: the Boolean operations ‘or’ and ‘and’ always return one of their operands.)

3.2 Boolean Operations — and, or, not

These are the Boolean operations, ordered by ascending priority:

¹ Additional information on these special methods may be found in the [Python Reference Manual](#).

Operation	Result	Notes
<code>x or y</code>	if <code>x</code> is false, then <code>y</code> , else <code>x</code>	(1)
<code>x and y</code>	if <code>x</code> is false, then <code>x</code> , else <code>y</code>	(1)
<code>not x</code>	if <code>x</code> is false, then <code>True</code> , else <code>False</code>	(2)

Notes:

- (1) These only evaluate their second argument if needed for their outcome.
- (2) ‘not’ has a lower priority than non-Boolean operators, so `not a == b` is interpreted as `not (a == b)`, and `a == not b` is a syntax error.

3.3 Comparisons

Comparison operations are supported by all objects. They all have the same priority (which is higher than that of the Boolean operations). Comparisons can be chained arbitrarily; for example, `x < y <= z` is equivalent to `x < y` and `y <= z`, except that `y` is evaluated only once (but in both cases `z` is not evaluated at all when `x < y` is found to be false).

This table summarizes the comparison operations:

Operation	Meaning	Notes
<code><</code>	strictly less than	
<code><=</code>	less than or equal	
<code>></code>	strictly greater than	
<code>>=</code>	greater than or equal	
<code>==</code>	equal	
<code>!=</code>	not equal	(1)
<code><></code>	not equal	(1)
<code>is</code>	object identity	
<code>is not</code>	negated object identity	

Notes:

- (1) `<>` and `!=` are alternate spellings for the same operator. `!=` is the preferred spelling; `<>` is obsolescent.

Objects of different types, except different numeric types and different string types, never compare equal; such objects are ordered consistently but arbitrarily (so that sorting a heterogeneous array yields a consistent result). Furthermore, some types (for example, file objects) support only a degenerate notion of comparison where any two objects of that type are unequal. Again, such objects are ordered arbitrarily but consistently. The `<`, `<=`, `>` and `>=` operators will raise a `TypeError` exception when any operand is a complex number.

Instances of a class normally compare as non-equal unless the class defines the `__cmp__()` method. Refer to the [Python Reference Manual](#) for information on the use of this method to effect object comparisons.

Implementation note: Objects of different types except numbers are ordered by their type names; objects of the same types that don’t support proper comparison are ordered by their address.

Two more operations with the same syntactic priority, ‘in’ and ‘not in’, are supported only by sequence types (below).

3.4 Numeric Types — int, float, long, complex

There are four distinct numeric types: *plain integers*, *long integers*, *floating point numbers*, and *complex numbers*. In addition, Booleans are a subtype of plain integers. Plain integers (also just called *integers*) are implemented using `long` in C, which gives them at least 32 bits of precision (`sys.maxint` is always set to the maximum plain integer value for the current platform, the minimum value is `-sys.maxint - 1`). Long integers have unlimited precision. Floating point numbers are implemented using `double` in C. All bets on their precision are off unless you happen to know the machine you are working with.

Complex numbers have a real and imaginary part, which are each implemented using `double` in C. To extract these parts from a complex number `z`, use `z.real` and `z.imag`.

Numbers are created by numeric literals or as the result of built-in functions and operators. Unadorned integer literals (including hex and octal numbers) yield plain integers unless the value they denote is too large to be represented as a plain integer, in which case they yield a long integer. Integer literals with an ‘L’ or ‘l’ suffix yield long integers (‘L’ is preferred because ‘11’ looks too much like eleven!). Numeric literals containing a decimal point or an exponent sign yield floating point numbers. Appending ‘j’ or ‘J’ to a numeric literal yields a complex number with a zero real part. A complex numeric literal is the sum of a real and an imaginary part.

Python fully supports mixed arithmetic: when a binary arithmetic operator has operands of different numeric types, the operand with the “narrower” type is widened to that of the other, where plain integer is narrower than long integer is narrower than floating point is narrower than complex. Comparisons between numbers of mixed type use the same rule.² The constructors `int()`, `long()`, `float()`, and `complex()` can be used to produce numbers of a specific type.

All numeric types (except complex) support the following operations, sorted by ascending priority (operations in the same box have the same priority; all numeric operations have a higher priority than comparison operations):

Operation	Result	Notes
<code>x + y</code>	sum of <i>x</i> and <i>y</i>	
<code>x - y</code>	difference of <i>x</i> and <i>y</i>	
<code>x * y</code>	product of <i>x</i> and <i>y</i>	
<code>x / y</code>	quotient of <i>x</i> and <i>y</i>	(1)
<code>x // y</code>	(floored) quotient of <i>x</i> and <i>y</i>	(5)
<code>x % y</code>	remainder of <i>x</i> / <i>y</i>	(4)
<code>-x</code>	<i>x</i> negated	
<code>+x</code>	<i>x</i> unchanged	
<code>abs(x)</code>	absolute value or magnitude of <i>x</i>	
<code>int(x)</code>	<i>x</i> converted to integer	(2)
<code>long(x)</code>	<i>x</i> converted to long integer	(2)
<code>float(x)</code>	<i>x</i> converted to floating point	
<code>complex(re, im)</code>	a complex number with real part <i>re</i> , imaginary part <i>im</i> . <i>im</i> defaults to zero.	
<code>c.conjugate()</code>	conjugate of the complex number <i>c</i>	
<code>divmod(x, y)</code>	the pair (<i>x</i> // <i>y</i> , <i>x</i> % <i>y</i>)	(3)(4)
<code>pow(x, y)</code>	<i>x</i> to the power <i>y</i>	
<code>x ** y</code>	<i>x</i> to the power <i>y</i>	

Notes:

(1) For (plain or long) integer division, the result is an integer. The result is always rounded towards minus infinity: $1/2$ is 0, $(-1)/2$ is -1, $1/(-2)$ is -1, and $(-1)/(-2)$ is 0. Note that the result is a long integer if either operand is a long integer, regardless of the numeric value.

(2) Conversion from floating point to (long or plain) integer may round or truncate as in C; see functions `floor()` and `ceil()` in the [math](#) module for well-defined conversions.

²As a consequence, the list `[1, 2]` is considered equal to `[1.0, 2.0]`, and similarly for tuples.

- (3) See section 2.1, “Built-in Functions,” for a full description.
- (4) Complex floor division operator, modulo operator, and `divmod()`.
Deprecated since release 2.3. Instead convert to float using `abs()` if appropriate.
- (5) Also referred to as integer division. The resultant value is a whole integer, though the result’s type is not necessarily `int`.

3.4.1 Bit-string Operations on Integer Types

Plain and long integer types support additional operations that make sense only for bit-strings. Negative numbers are treated as their 2’s complement value (for long integers, this assumes a sufficiently large number of bits that no overflow occurs during the operation).

The priorities of the binary bit-wise operations are all lower than the numeric operations and higher than the comparisons; the unary operation ‘`~`’ has the same priority as the other unary numeric operations (‘`+`’ and ‘`-`’).

This table lists the bit-string operations sorted in ascending priority (operations in the same box have the same priority):

Operation	Result	Notes
$x \mid y$	bitwise <i>or</i> of x and y	(1), (2) (1), (3)
$x \wedge y$	bitwise <i>exclusive or</i> of x and y	
$x \& y$	bitwise <i>and</i> of x and y	
$x \ll n$	x shifted left by n bits	
$x \gg n$	x shifted right by n bits	
$\sim x$	the bits of x inverted	

Notes:

- (1) Negative shift counts are illegal and cause a `ValueError` to be raised.
- (2) A left shift by n bits is equivalent to multiplication by `pow(2, n)` without overflow check.
- (3) A right shift by n bits is equivalent to division by `pow(2, n)` without overflow check.

3.5 Iterator Types

New in version 2.2.

Python supports a concept of iteration over containers. This is implemented using two distinct methods; these are used to allow user-defined classes to support iteration. Sequences, described below in more detail, always support the iteration methods.

One method needs to be defined for container objects to provide iteration support:

`__iter__()`

Return an iterator object. The object is required to support the iterator protocol described below. If a container supports different types of iteration, additional methods can be provided to specifically request iterators for those iteration types. (An example of an object supporting multiple forms of iteration would be a tree structure which supports both breadth-first and depth-first traversal.) This method corresponds to the `tp_iter` slot of the type structure for Python objects in the Python/C API.

The iterator objects themselves are required to support the following two methods, which together form the *iterator protocol*:

`__iter__()`

Return the iterator object itself. This is required to allow both containers and iterators to be used with the `for` and `in` statements. This method corresponds to the `tp_iter` slot of the type structure for Python objects in the Python/C API.

`next()`

Return the next item from the container. If there are no further items, raise the `StopIteration` exception. This method corresponds to the `tp_iternext` slot of the type structure for Python objects in the Python/C API.

Python defines several iterator objects to support iteration over general and specific sequence types, dictionaries, and other more specialized forms. The specific types are not important beyond their implementation of the iterator protocol.

The intention of the protocol is that once an iterator's `next()` method raises `StopIteration`, it will continue to do so on subsequent calls. Implementations that do not obey this property are deemed broken. (This constraint was added in Python 2.3; in Python 2.2, various iterators are broken according to this rule.)

Python's generators provide a convenient way to implement the iterator protocol. If a container object's `__iter__()` method is implemented as a generator, it will automatically return an iterator object (technically, a generator object) supplying the `__iter__()` and `next()` methods.

3.6 Sequence Types — `str`, `unicode`, `list`, `tuple`, `buffer`, `xrange`

There are six sequence types: strings, Unicode strings, lists, tuples, buffers, and xrange objects.

String literals are written in single or double quotes: `'xyzzy'`, `"frobozz"`. See chapter 2 of the [Python Reference Manual](#) for more about string literals. Unicode strings are much like strings, but are specified in the syntax using a preceding `'u'` character: `u'abc'`, `u"def"`. Lists are constructed with square brackets, separating items with commas: `[a, b, c]`. Tuples are constructed by the comma operator (not within square brackets), with or without enclosing parentheses, but an empty tuple must have the enclosing parentheses, such as `a, b, c` or `()`. A single item tuple must have a trailing comma, such as `(d,)`.

Buffer objects are not directly supported by Python syntax, but can be created by calling the builtin function `buffer()`. They don't support concatenation or repetition.

Xrange objects are similar to buffers in that there is no specific syntax to create them, but they are created using the `xrange()` function. They don't support slicing, concatenation or repetition, and using `in`, `not in`, `min()` or `max()` on them is inefficient.

Most sequence types support the following operations. The `'in'` and `'not in'` operations have the same priorities as the comparison operations. The `'+'` and `'*'` operations have the same priority as the corresponding numeric operations.³

This table lists the sequence operations sorted in ascending priority (operations in the same box have the same priority). In the table, *s* and *t* are sequences of the same type; *n*, *i* and *j* are integers:

³They must have since the parser can't tell the type of the operands.

Operation	Result	Notes
<code>x in s</code>	True if an item of <i>s</i> is equal to <i>x</i> , else False	(1)
<code>x not in s</code>	False if an item of <i>s</i> is equal to <i>x</i> , else True	(1)
<code>s + t</code>	the concatenation of <i>s</i> and <i>t</i>	(6)
<code>s * n, n * s</code>	<i>n</i> shallow copies of <i>s</i> concatenated	(2)
<code>s[i]</code>	<i>i</i> 'th item of <i>s</i> , origin 0	(3)
<code>s[i:j]</code>	slice of <i>s</i> from <i>i</i> to <i>j</i>	(3), (4)
<code>s[i:j:k]</code>	slice of <i>s</i> from <i>i</i> to <i>j</i> with step <i>k</i>	(3), (5)
<code>len(s)</code>	length of <i>s</i>	
<code>min(s)</code>	smallest item of <i>s</i>	
<code>max(s)</code>	largest item of <i>s</i>	

Notes:

- (1) When *s* is a string or Unicode string object the `in` and `not in` operations act like a substring test. In Python versions before 2.3, *x* had to be a string of length 1. In Python 2.3 and beyond, *x* may be a string of any length.
- (2) Values of *n* less than 0 are treated as 0 (which yields an empty sequence of the same type as *s*). Note also that the copies are shallow; nested structures are not copied. This often haunts new Python programmers; consider:

```
>>> lists = [[]] * 3
>>> lists
[[], [], []]
>>> lists[0].append(3)
>>> lists
[[3], [3], [3]]
```

What has happened is that `[[]]` is a one-element list containing an empty list, so all three elements of `[[]] * 3` are (pointers to) this single empty list. Modifying any of the elements of `lists` modifies this single list. You can create a list of different lists this way:

```
>>> lists = [[] for i in range(3)]
>>> lists[0].append(3)
>>> lists[1].append(5)
>>> lists[2].append(7)
>>> lists
[[3], [5], [7]]
```

- (3) If *i* or *j* is negative, the index is relative to the end of the string: `len(s) + i` or `len(s) + j` is substituted. But note that `-0` is still 0.
- (4) The slice of *s* from *i* to *j* is defined as the sequence of items with index *k* such that $i \leq k < j$. If *i* or *j* is greater than `len(s)`, use `len(s)`. If *i* is omitted or None, use 0. If *j* is omitted or None, use `len(s)`. If *i* is greater than or equal to *j*, the slice is empty.
- (5) The slice of *s* from *i* to *j* with step *k* is defined as the sequence of items with index $x = i + n*k$ such that $0 \leq n < \frac{j-i}{k}$. In other words, the indices are *i*, *i*+*k*, *i*+2**k*, *i*+3**k* and so on, stopping when *j* is reached (but never including *j*). If *i* or *j* is greater than `len(s)`, use `len(s)`. If *i* or *j* are omitted or None, they become “end” values (which end depends on the sign of *k*). Note, *k* cannot be zero. If *k* is None, it is treated like 1.
- (6) If *s* and *t* are both strings, some Python implementations such as CPython can usually perform an in-place optimization for assignments of the form `s=s+t` or `s+=t`. When applicable, this optimization makes quadratic run-time much less likely. This optimization is both version and implementation dependent. For performance sensitive code, it is preferable to use the `str.join()` method which assures consistent linear concatenation

performance across versions and implementations. Changed in version 2.4: Formerly, string concatenation never occurred in-place.

3.6.1 String Methods

These are the string methods which both 8-bit strings and Unicode objects support:

capitalize()

Return a copy of the string with only its first character capitalized.

For 8-bit strings, this method is locale-dependent.

center(*width*[, *fillchar*])

Return centered in a string of length *width*. Padding is done using the specified *fillchar* (default is a space).

Changed in version 2.4: Support for the *fillchar* argument.

count(*sub*[, *start*[, *end*]])

Return the number of occurrences of substring *sub* in string *S*[*start*:*end*]. Optional arguments *start* and *end* are interpreted as in slice notation.

decode([*encoding*[, *errors*]])

Decodes the string using the codec registered for *encoding*. *encoding* defaults to the default string encoding. *errors* may be given to set a different error handling scheme. The default is 'strict', meaning that encoding errors raise `UnicodeError`. Other possible values are 'ignore', 'replace' and any other name registered via `codecs.register_error`, see section 4.8.1. New in version 2.2. Changed in version 2.3: Support for other error handling schemes added.

encode([*encoding*[, *errors*]])

Return an encoded version of the string. Default encoding is the current default string encoding. *errors* may be given to set a different error handling scheme. The default for *errors* is 'strict', meaning that encoding errors raise a `UnicodeError`. Other possible values are 'ignore', 'replace', 'xmlcharrefreplace', 'backslashreplace' and any other name registered via `codecs.register_error`, see section 4.8.1. For a list of possible encodings, see section 4.8.3. New in version 2.0. Changed in version 2.3: Support for 'xmlcharrefreplace' and 'backslashreplace' and other error handling schemes added.

endswith(*suffix*[, *start*[, *end*]])

Return `True` if the string ends with the specified *suffix*, otherwise return `False`. *suffix* can also be a tuple of suffixes to look for. With optional *start*, test beginning at that position. With optional *end*, stop comparing at that position.

Changed in version 2.5: Accept tuples as *suffix*.

expandtabs([*tabsize*])

Return a copy of the string where all tab characters are expanded using spaces. If *tabsize* is not given, a tab size of 8 characters is assumed.

find(*sub*[, *start*[, *end*]])

Return the lowest index in the string where substring *sub* is found, such that *sub* is contained in the range [*start*, *end*]. Optional arguments *start* and *end* are interpreted as in slice notation. Return -1 if *sub* is not found.

index(*sub*[, *start*[, *end*]])

Like `find()`, but raise `ValueError` when the substring is not found.

isalnum()

Return true if all characters in the string are alphanumeric and there is at least one character, false otherwise.

For 8-bit strings, this method is locale-dependent.

isalpha()

Return true if all characters in the string are alphabetic and there is at least one character, false otherwise.

For 8-bit strings, this method is locale-dependent.

isdigit()

Return true if all characters in the string are digits and there is at least one character, false otherwise.

For 8-bit strings, this method is locale-dependent.

islower()

Return true if all cased characters in the string are lowercase and there is at least one cased character, false otherwise.

For 8-bit strings, this method is locale-dependent.

isspace()

Return true if there are only whitespace characters in the string and there is at least one character, false otherwise.

For 8-bit strings, this method is locale-dependent.

istitle()

Return true if the string is a titlecased string and there is at least one character, for example uppercase characters may only follow uncased characters and lowercase characters only cased ones. Return false otherwise.

For 8-bit strings, this method is locale-dependent.

isupper()

Return true if all cased characters in the string are uppercase and there is at least one cased character, false otherwise.

For 8-bit strings, this method is locale-dependent.

join(seq)

Return a string which is the concatenation of the strings in the sequence *seq*. The separator between elements is the string providing this method.

ljust(width[, fillchar])

Return the string left justified in a string of length *width*. Padding is done using the specified *fillchar* (default is a space). The original string is returned if *width* is less than `len(s)`. Changed in version 2.4: Support for the *fillchar* argument.

lower()

Return a copy of the string converted to lowercase.

For 8-bit strings, this method is locale-dependent.

lstrip([chars])

Return a copy of the string with leading characters removed. The *chars* argument is a string specifying the set of characters to be removed. If omitted or `None`, the *chars* argument defaults to removing whitespace. The *chars* argument is not a prefix; rather, all combinations of its values are stripped:

```
>>> '  spacious  '.lstrip()
'spacious  '
>>> 'www.example.com'.lstrip('cmowz.')
'example.com'
```

Changed in version 2.2.2: Support for the *chars* argument.

partition(sep)

Split the string at the first occurrence of *sep*, and return a 3-tuple containing the part before the separator, the separator itself, and the part after the separator. If the separator is not found, return a 3-tuple containing the string itself, followed by two empty strings. New in version 2.5.

replace(old, new[, count])

Return a copy of the string with all occurrences of substring *old* replaced by *new*. If the optional argument *count* is given, only the first *count* occurrences are replaced.

rfind (*sub* [, *start* [, *end*]])

Return the highest index in the string where substring *sub* is found, such that *sub* is contained within *s*[*start*,*end*]. Optional arguments *start* and *end* are interpreted as in slice notation. Return *-1* on failure.

rindex (*sub* [, *start* [, *end*]])

Like *rfind* () but raises *ValueError* when the substring *sub* is not found.

rjust (*width* [, *fillchar*])

Return the string right justified in a string of length *width*. Padding is done using the specified *fillchar* (default is a space). The original string is returned if *width* is less than *len* (*s*) . Changed in version 2.4: Support for the *fillchar* argument.

rpartition (*sep*)

Split the string at the last occurrence of *sep*, and return a 3-tuple containing the part before the separator, the separator itself, and the part after the separator. If the separator is not found, return a 3-tuple containing two empty strings, followed by the string itself. New in version 2.5.

rsplit ([*sep* [, *maxsplit*]])

Return a list of the words in the string, using *sep* as the delimiter string. If *maxsplit* is given, at most *maxsplit* splits are done, the *rightmost* ones. If *sep* is not specified or *None*, any whitespace string is a separator. Except for splitting from the right, *rsplit* () behaves like *split* () which is described in detail below. New in version 2.4.

rstrip ([*chars*])

Return a copy of the string with trailing characters removed. The *chars* argument is a string specifying the set of characters to be removed. If omitted or *None*, the *chars* argument defaults to removing whitespace. The *chars* argument is not a suffix; rather, all combinations of its values are stripped:

```
>>> '   spacious   '.rstrip()
'   spacious'
>>> 'mississippi'.rstrip('ipz')
'mississ'
```

Changed in version 2.2.2: Support for the *chars* argument.

split ([*sep* [, *maxsplit*]])

Return a list of the words in the string, using *sep* as the delimiter string. If *maxsplit* is given, at most *maxsplit* splits are done. (thus, the list will have at most *maxsplit*+1 elements). If *maxsplit* is not specified, then there is no limit on the number of splits (all possible splits are made). Consecutive delimiters are not grouped together and are deemed to delimit empty strings (for example, *'1, , 2'.split(',')* returns *['1', ' ', '2']*). The *sep* argument may consist of multiple characters (for example, *'1, 2, 3'.split(',')* returns *['1', '2', '3']*). Splitting an empty string with a specified separator returns *['']*.

If *sep* is not specified or is *None*, a different splitting algorithm is applied. First, whitespace characters (spaces, tabs, newlines, returns, and formfeeds) are stripped from both ends. Then, words are separated by arbitrary length strings of whitespace characters. Consecutive whitespace delimiters are treated as a single delimiter (*'1 2 3'.split()* returns *['1', '2', '3']*). Splitting an empty string or a string consisting of just whitespace returns an empty list.

splitlines ([*keepends*])

Return a list of the lines in the string, breaking at line boundaries. Line breaks are not included in the resulting list unless *keepends* is given and true.

startswith (*prefix* [, *start* [, *end*]])

Return *True* if string starts with the *prefix*, otherwise return *False*. *prefix* can also be a tuple of prefixes to look for. With optional *start*, test string beginning at that position. With optional *end*, stop comparing string at that position.

Changed in version 2.5: Accept tuples as *prefix*.

strip ([*chars*])

Return a copy of the string with the leading and trailing characters removed. The *chars* argument is a string specifying the set of characters to be removed. If omitted or `None`, the *chars* argument defaults to removing whitespace. The *chars* argument is not a prefix or suffix; rather, all combinations of its values are stripped:

```
>>> '   spacious   '.strip()
'spacious'
>>> 'www.example.com'.strip('cmowz.')
'example'
```

Changed in version 2.2.2: Support for the *chars* argument.

swapcase()

Return a copy of the string with uppercase characters converted to lowercase and vice versa.

For 8-bit strings, this method is locale-dependent.

title()

Return a titlecased version of the string: words start with uppercase characters, all remaining cased characters are lowercase.

For 8-bit strings, this method is locale-dependent.

translate(table[, deletechars])

Return a copy of the string where all characters occurring in the optional argument *deletechars* are removed, and the remaining characters have been mapped through the given translation table, which must be a string of length 256.

You can use the `maketrans()` helper function in the `string` module to create a translation table.

For Unicode objects, the `translate()` method does not accept the optional *deletechars* argument. Instead, it returns a copy of the *s* where all characters have been mapped through the given translation table which must be a mapping of Unicode ordinals to Unicode ordinals, Unicode strings or `None`. Unmapped characters are left untouched. Characters mapped to `None` are deleted. Note, a more flexible approach is to create a custom character mapping codec using the `codecs` module (see `encodings.cp1251` for an example).

upper()

Return a copy of the string converted to uppercase.

For 8-bit strings, this method is locale-dependent.

zfill(width)

Return the numeric string left filled with zeros in a string of length *width*. The original string is returned if *width* is less than `len(s)`. New in version 2.2.2.

3.6.2 String Formatting Operations

String and Unicode objects have one unique built-in operation: the `%` operator (modulo). This is also known as the string *formatting* or *interpolation* operator. Given *format % values* (where *format* is a string or Unicode object), `%` conversion specifications in *format* are replaced with zero or more elements of *values*. The effect is similar to the using `sprintf()` in the C language. If *format* is a Unicode object, or if any of the objects being converted using the *%s* conversion are Unicode objects, the result will also be a Unicode object.

If *format* requires a single argument, *values* may be a single non-tuple object.⁴ Otherwise, *values* must be a tuple with exactly the number of items specified by the format string, or a single mapping object (for example, a dictionary).

A conversion specifier contains two or more characters and has the following components, which must occur in this order:

1. The `'%'` character, which marks the start of the specifier.

⁴To format only a tuple you should therefore provide a singleton tuple whose only element is the tuple to be formatted.

2. Mapping key (optional), consisting of a parenthesised sequence of characters (for example, (somename)).
3. Conversion flags (optional), which affect the result of some conversion types.
4. Minimum field width (optional). If specified as an '*' (asterisk), the actual width is read from the next element of the tuple in *values*, and the object to convert comes after the minimum field width and optional precision.
5. Precision (optional), given as a '.' (dot) followed by the precision. If specified as '*' (an asterisk), the actual width is read from the next element of the tuple in *values*, and the value to convert comes after the precision.
6. Length modifier (optional).
7. Conversion type.

When the right argument is a dictionary (or other mapping type), then the formats in the string *must* include a parenthesised mapping key into that dictionary inserted immediately after the '%' character. The mapping key selects the value to be formatted from the mapping. For example:

```
>>> print '%(language)s has %(#)03d quote types.' % \
        {'language': "Python", "#": 2}
Python has 002 quote types.
```

In this case no * specifiers may occur in a format (since they require a sequential parameter list).

The conversion flag characters are:

Flag	Meaning
'#'	The value conversion will use the “alternate form” (where defined below).
'0'	The conversion will be zero padded for numeric values.
'-'	The converted value is left adjusted (overrides the '0' conversion if both are given).
' '	(a space) A blank should be left before a positive number (or empty string) produced by a signed conversion.
'+'	A sign character ('+' or '-') will precede the conversion (overrides a "space" flag).

A length modifier (h, l, or L) may be present, but is ignored as it is not necessary for Python.

The conversion types are:

Conversion	Meaning
'd'	Signed integer decimal.
'i'	Signed integer decimal.
'o'	Unsigned octal.
'u'	Unsigned decimal.
'x'	Unsigned hexadecimal (lowercase).
'X'	Unsigned hexadecimal (uppercase).
'e'	Floating point exponential format (lowercase).
'E'	Floating point exponential format (uppercase).
'f'	Floating point decimal format.
'F'	Floating point decimal format.
'g'	Floating point format. Uses exponential format if exponent is greater than -4 or less than precision, decimal format otherwise.
'G'	Floating point format. Uses exponential format if exponent is greater than -4 or less than precision, decimal format otherwise.
'c'	Single character (accepts integer or single character string).
'r'	String (converts any python object using repr()).
's'	String (converts any python object using str()).
'%'	No argument is converted, results in a '%' character in the result.

Notes:

- (1) The alternate form causes a leading zero ('0') to be inserted between left-hand padding and the formatting of the number if the leading character of the result is not already a zero.
- (2) The alternate form causes a leading '0x' or '0X' (depending on whether the 'x' or 'X' format was used) to be inserted between left-hand padding and the formatting of the number if the leading character of the result is not already a zero.
- (3) The alternate form causes the result to always contain a decimal point, even if no digits follow it.
The precision determines the number of digits after the decimal point and defaults to 6.
- (4) The alternate form causes the result to always contain a decimal point, and trailing zeroes are not removed as they would otherwise be.
The precision determines the number of significant digits before and after the decimal point and defaults to 6.
- (5) The %r conversion was added in Python 2.0.
The precision determines the maximal number of characters used.
- (6) If the object or format provided is a `unicode` string, the resulting string will also be `unicode`.
The precision determines the maximal number of characters used.

Since Python strings have an explicit length, %s conversions do not assume that '\0' is the end of the string.

For safety reasons, floating point precisions are clipped to 50; %f conversions for numbers whose absolute value is over 1e25 are replaced by %g conversions.⁵ All other errors raise exceptions.

Additional string operations are defined in standard modules `string` and `re`.

3.6.3 xrange Type

The `xrange` type is an immutable sequence which is commonly used for looping. The advantage of the `xrange` type is that an `xrange` object will always take the same amount of memory, no matter the size of the range it represents. There are no consistent performance advantages.

`XRange` objects have very little behavior: they only support indexing, iteration, and the `len()` function.

3.6.4 Mutable Sequence Types

List objects support additional operations that allow in-place modification of the object. Other mutable sequence types (when added to the language) should also support these operations. Strings and tuples are immutable sequence types: such objects cannot be modified once created. The following operations are defined on mutable sequence types (where `x` is an arbitrary object):

⁵These numbers are fairly arbitrary. They are intended to avoid printing endless strings of meaningless digits without hampering correct use and without having to know the exact precision of floating point values on a particular machine.

Operation	Result	Notes
<code>s[i] = x</code>	item <i>i</i> of <i>s</i> is replaced by <i>x</i>	
<code>s[i:j] = t</code>	slice of <i>s</i> from <i>i</i> to <i>j</i> is replaced by the contents of the iterable <i>t</i>	
<code>del s[i:j]</code>	same as <code>s[i:j] = []</code>	
<code>s[i:j:k] = t</code>	the elements of <code>s[i:j:k]</code> are replaced by those of <i>t</i>	(1)
<code>del s[i:j:k]</code>	removes the elements of <code>s[i:j:k]</code> from the list	
<code>s.append(x)</code>	same as <code>s[len(s):len(s)] = [x]</code>	(2)
<code>s.extend(x)</code>	same as <code>s[len(s):len(s)] = x</code>	(3)
<code>s.count(x)</code>	return number of <i>i</i> 's for which <code>s[i] == x</code>	
<code>s.index(x[, i[, j]])</code>	return smallest <i>k</i> such that <code>s[k] == x</code> and <code>i <= k < j</code>	(4)
<code>s.insert(i, x)</code>	same as <code>s[i:i] = [x]</code>	(5)
<code>s.pop([i])</code>	same as <code>x = s[i]; del s[i]; return x</code>	(6)
<code>s.remove(x)</code>	same as <code>del s[s.index(x)]</code>	(4)
<code>s.reverse()</code>	reverses the items of <i>s</i> in place	(7)
<code>s.sort([cmp[, key[, reverse]]])</code>	sort the items of <i>s</i> in place	(7), (8), (9), (10)

Notes:

- (1) *t* must have the same length as the slice it is replacing.
- (2) The C implementation of Python has historically accepted multiple parameters and implicitly joined them into a tuple; this no longer works in Python 2.0. Use of this misfeature has been deprecated since Python 1.4.
- (3) *x* can be any iterable object.
- (4) Raises `ValueError` when *x* is not found in *s*. When a negative index is passed as the second or third parameter to the `index()` method, the list length is added, as for slice indices. If it is still negative, it is truncated to zero, as for slice indices. Changed in version 2.3: Previously, `index()` didn't have arguments for specifying start and stop positions.
- (5) When a negative index is passed as the first parameter to the `insert()` method, the list length is added, as for slice indices. If it is still negative, it is truncated to zero, as for slice indices. Changed in version 2.3: Previously, all negative indices were truncated to zero.
- (6) The `pop()` method is only supported by the list and array types. The optional argument *i* defaults to `-1`, so that by default the last item is removed and returned.
- (7) The `sort()` and `reverse()` methods modify the list in place for economy of space when sorting or reversing a large list. To remind you that they operate by side effect, they don't return the sorted or reversed list.
- (8) The `sort()` method takes optional arguments for controlling the comparisons.
cmp specifies a custom comparison function of two arguments (list items) which should return a negative, zero or positive number depending on whether the first argument is considered smaller than, equal to, or larger than the second argument: `'cmp=lambda x,y: cmp(x.lower(), y.lower())'`
key specifies a function of one argument that is used to extract a comparison key from each list element: `'key=str.lower'`
reverse is a boolean value. If set to `True`, then the list elements are sorted as if each comparison were reversed.
In general, the *key* and *reverse* conversion processes are much faster than specifying an equivalent *cmp* function. This is because *cmp* is called multiple times for each list element while *key* and *reverse* touch each element only once.
Changed in version 2.3: Support for `None` as an equivalent to omitting *cmp* was added.
Changed in version 2.4: Support for *key* and *reverse* was added.

- (9) Starting with Python 2.3, the `sort()` method is guaranteed to be stable. A sort is stable if it guarantees not to change the relative order of elements that compare equal — this is helpful for sorting in multiple passes (for example, sort by department, then by salary grade).
- (10) While a list is being sorted, the effect of attempting to mutate, or even inspect, the list is undefined. The C implementation of Python 2.3 and newer makes the list appear empty for the duration, and raises `ValueError` if it can detect that the list has been mutated during a sort.

3.7 Set Types — `set`, `frozenset`

A *set* object is an unordered collection of distinct hashable objects. Common uses include membership testing, removing duplicates from a sequence, and computing mathematical operations such as intersection, union, difference, and symmetric difference. New in version 2.4.

Like other collections, sets support `x in set`, `len(set)`, and `for x in set`. Being an unordered collection, sets do not record element position or order of insertion. Accordingly, sets do not support indexing, slicing, or other sequence-like behavior.

There are currently two builtin set types, `set` and `frozenset`. The `set` type is mutable — the contents can be changed using methods like `add()` and `remove()`. Since it is mutable, it has no hash value and cannot be used as either a dictionary key or as an element of another set. The `frozenset` type is immutable and hashable — its contents cannot be altered after it is created; however, it can be used as a dictionary key or as an element of another set.

Instances of `set` and `frozenset` provide the following operations:

Operation	Equivalent	Result
<code>len(s)</code>		cardinality of set <i>s</i>
<code>x in s</code>		test <i>x</i> for membership in <i>s</i>
<code>x not in s</code>		test <i>x</i> for non-membership in <i>s</i>
<code>s.issubset(t)</code>	$s \leq t$	test whether every element in <i>s</i> is in <i>t</i>
<code>s.issuperset(t)</code>	$s \geq t$	test whether every element in <i>t</i> is in <i>s</i>
<code>s.union(t)</code>	$s \cup t$	new set with elements from both <i>s</i> and <i>t</i>
<code>s.intersection(t)</code>	$s \cap t$	new set with elements common to <i>s</i> and <i>t</i>
<code>s.difference(t)</code>	$s - t$	new set with elements in <i>s</i> but not in <i>t</i>
<code>s.symmetric_difference(t)</code>	$s \oplus t$	new set with elements in either <i>s</i> or <i>t</i> but not both
<code>s.copy()</code>		new set with a shallow copy of <i>s</i>

Note, the non-operator versions of `union()`, `intersection()`, `difference()`, and `symmetric_difference()`, `issubset()`, and `issuperset()` methods will accept any iterable as an argument. In contrast, their operator based counterparts require their arguments to be sets. This precludes error-prone constructions like `set('abc') & 'cbs'` in favor of the more readable `set('abc').intersection('cbs')`.

Both `set` and `frozenset` support set to set comparisons. Two sets are equal if and only if every element of each set is contained in the other (each is a subset of the other). A set is less than another set if and only if the first set is a proper subset of the second set (is a subset, but is not equal). A set is greater than another set if and only if the first set is a proper superset of the second set (is a superset, but is not equal).

Instances of `set` are compared to instances of `frozenset` based on their members. For example, `set('abc') == frozenset('abc')` returns `True`.

The subset and equality comparisons do not generalize to a complete ordering function. For example, any two disjoint sets are not equal and are not subsets of each other, so *all* of the following return `False`: `a < b`, `a == b`, or `a > b`. Accordingly, sets do not implement the `__cmp__` method.

Since sets only define partial ordering (subset relationships), the output of the `list.sort()` method is undefined for lists of sets.

Set elements are like dictionary keys; they need to define both `__hash__` and `__eq__` methods.

Binary operations that mix `set` instances with `frozenset` return the type of the first operand. For example: `'frozenset('ab') | set('bc')` returns an instance of `frozenset`.

The following table lists operations available for `set` that do not apply to immutable instances of `frozenset`:

Operation	Equivalent	Result
<code>s.update(t)</code>	<code>s = t</code>	update set <i>s</i> , adding elements from <i>t</i>
<code>s.intersection_update(t)</code>	<code>s &= t</code>	update set <i>s</i> , keeping only elements found in both <i>s</i> and <i>t</i>
<code>s.difference_update(t)</code>	<code>s -= t</code>	update set <i>s</i> , removing elements found in <i>t</i>
<code>s.symmetric_difference_update(t)</code>	<code>s ^= t</code>	update set <i>s</i> , keeping only elements found in either <i>s</i> or <i>t</i> but not in both
<code>s.add(x)</code>		add element <i>x</i> to set <i>s</i>
<code>s.remove(x)</code>		remove <i>x</i> from set <i>s</i> ; raises <code>KeyError</code> if not present
<code>s.discard(x)</code>		removes <i>x</i> from set <i>s</i> if present
<code>s.pop()</code>		remove and return an arbitrary element from <i>s</i> ; raises <code>KeyError</code> if empty
<code>s.clear()</code>		remove all elements from set <i>s</i>

Note, the non-operator versions of the `update()`, `intersection_update()`, `difference_update()`, and `symmetric_difference_update()` methods will accept any iterable as an argument.

The design of the set types was based on lessons learned from the `sets` module.

See Also:

[Comparison to the built-in set types](#)

Differences between the `sets` module and the built-in set types.

3.8 Mapping Types — dict

A *mapping* object maps immutable values to arbitrary objects. Mappings are mutable objects. There is currently only one standard mapping type, the *dictionary*. A dictionary's keys are almost arbitrary values. Only values containing lists, dictionaries or other mutable types (that are compared by value rather than by object identity) may not be used as keys. Numeric types used for keys obey the normal rules for numeric comparison: if two numbers compare equal (such as 1 and 1.0) then they can be used interchangeably to index the same dictionary entry.

Dictionaries are created by placing a comma-separated list of *key: value* pairs within braces, for example: `{'jack': 4098, 'sjoerd': 4127}` or `{4098: 'jack', 4127: 'sjoerd'}`.

The following operations are defined on mappings (where *a* and *b* are mappings, *k* is a key, and *v* and *x* are arbitrary objects):

Operation	Result	Notes
<code>len(a)</code>	the number of items in <i>a</i>	(1), (10)
<code>a[k]</code>	the item of <i>a</i> with key <i>k</i>	
<code>a[k] = v</code>	set <i>a[k]</i> to <i>v</i>	(1)
<code>del a[k]</code>	remove <i>a[k]</i> from <i>a</i>	
<code>a.clear()</code>	remove all items from <i>a</i>	(2)
<code>a.copy()</code>	a (shallow) copy of <i>a</i>	
<code>k in a</code>	True if <i>a</i> has a key <i>k</i> , else False	(2)
<code>k not in a</code>	Equivalent to <code>not k in a</code>	(2)
<code>a.has_key(k)</code>	Equivalent to <code>k in a</code> , use that form in new code	(3)
<code>a.items()</code>	a copy of <i>a</i> 's list of (<i>key</i> , <i>value</i>) pairs	
<code>a.keys()</code>	a copy of <i>a</i> 's list of keys	(3)
<code>a.update([b])</code>	updates <i>a</i> with key/value pairs from <i>b</i> , overwriting existing keys, returns None	(9)
<code>a.fromkeys(seq[, value])</code>	Creates a new dictionary with keys from <i>seq</i> and values set to <i>value</i>	(7)
<code>a.values()</code>	a copy of <i>a</i> 's list of values	(3)
<code>a.get(k[, x])</code>	<i>a[k]</i> if <i>k</i> in <i>a</i> , else <i>x</i>	(4)
<code>a.setdefault(k[, x])</code>	<i>a[k]</i> if <i>k</i> in <i>a</i> , else <i>x</i> (also setting it)	(5)
<code>a.pop(k[, x])</code>	<i>a[k]</i> if <i>k</i> in <i>a</i> , else <i>x</i> (and remove <i>k</i>)	(8)
<code>a.popitem()</code>	remove and return an arbitrary (<i>key</i> , <i>value</i>) pair	(6)
<code>a.iteritems()</code>	return an iterator over (<i>key</i> , <i>value</i>) pairs	(2), (3)
<code>a.iterkeys()</code>	return an iterator over the mapping's keys	(2), (3)
<code>a.itervalues()</code>	return an iterator over the mapping's values	(2), (3)

Notes:

- (1) Raises a `KeyError` exception if *k* is not in the map.
- (2) New in version 2.2.
- (3) Keys and values are listed in an arbitrary order which is non-random, varies across Python implementations, and depends on the dictionary's history of insertions and deletions. If `items()`, `keys()`, `values()`, `iteritems()`, `iterkeys()`, and `itervalues()` are called with no intervening modifications to the dictionary, the lists will directly correspond. This allows the creation of (*value*, *key*) pairs using `zip()`: `'pairs = zip(a.values(), a.keys())'`. The same relationship holds for the `iterkeys()` and `itervalues()` methods: `'pairs = zip(a.itervalues(), a.iterkeys())'` provides the same value for pairs. Another way to create the same list is `'pairs = [(v, k) for (k, v) in a.iteritems()]'`.
- (4) Never raises an exception if *k* is not in the map, instead it returns *x*. *x* is optional; when *x* is not provided and *k* is not in the map, None is returned.
- (5) `setdefault()` is like `get()`, except that if *k* is missing, *x* is both returned and inserted into the dictionary as the value of *k*. *x* defaults to None.
- (6) `popitem()` is useful to destructively iterate over a dictionary, as often used in set algorithms. If the dictionary is empty, calling `popitem()` raises a `KeyError`.
- (7) `fromkeys()` is a class method that returns a new dictionary. *value* defaults to None. New in version 2.3.
- (8) `pop()` raises a `KeyError` when no default value is given and the key is not found. New in version 2.3.
- (9) `update()` accepts either another mapping object or an iterable of key/value pairs (as a tuple or other iterable of length two). If keyword arguments are specified, the mapping is then is updated with those key/value pairs: `'d.update(red=1, blue=2)'`. Changed in version 2.4: Allowed the argument to be an iterable of key/value pairs and allowed keyword arguments.

- (10) If a subclass of dict defines a method `__missing__`, if the key *k* is not present, the *a[k]* operation calls that method with the key *k* as argument. The *a[k]* operation then returns or raises whatever is returned or raised by the `__missing__(k)` call if the key is not present. No other operations or methods invoke `__missing__()`. If `__missing__` is not defined, `KeyError` is raised. `__missing__` must be a method; it cannot be an instance variable. For an example, see `collections.defaultdict`. New in version 2.5.

3.9 File Objects

File objects are implemented using C’s `stdio` package and can be created with the built-in constructor `file()` described in section 2.1, “Built-in Functions.”⁶ File objects are also returned by some other built-in functions and methods, such as `os.popen()` and `os.fdopen()` and the `makefile()` method of socket objects.

When a file operation fails for an I/O-related reason, the exception `IOError` is raised. This includes situations where the operation is not defined for some reason, like `seek()` on a tty device or writing a file opened for reading.

Files have the following methods:

`close()`

Close the file. A closed file cannot be read or written any more. Any operation which requires that the file be open will raise a `ValueError` after the file has been closed. Calling `close()` more than once is allowed.

As of Python 2.5, you can avoid having to call this method explicitly if you use the `with` statement. For example, the following code will automatically close *f* when the `with` block is exited:

```
from __future__ import with_statement

with open("hello.txt") as f:
    for line in f:
        print line
```

In older versions of Python, you would have needed to do this to get the same effect:

```
f = open("hello.txt")
try:
    for line in f:
        print line
finally:
    f.close()
```

Note: Not all “file-like” types in Python support use as a context manager for the `with` statement. If your code is intended to work with any file-like object, you can use the `closing()` function in the `contextlib` module instead of using the object directly. See section 26.5 for details.

`flush()`

Flush the internal buffer, like `stdio`’s `fflush()`. This may be a no-op on some file-like objects.

`fileno()`

Return the integer “file descriptor” that is used by the underlying implementation to request I/O operations from the operating system. This can be useful for other, lower level interfaces that use file descriptors, such as the `fcntl` module or `os.read()` and friends. **Note:** File-like objects which do not have a real file descriptor should *not* provide this method!

`isatty()`

Return `True` if the file is connected to a tty(-like) device, else `False`. **Note:** If a file-like object is not associated with a real file, this method should *not* be implemented.

⁶`file()` is new in Python 2.2. The older built-in `open()` is an alias for `file()`.

next()

A file object is its own iterator, for example `iter(f)` returns `f` (unless `f` is closed). When a file is used as an iterator, typically in a `for` loop (for example, `for line in f: print line`), the `next()` method is called repeatedly. This method returns the next input line, or raises `StopIteration` when EOF is hit when the file is open for reading (behavior is undefined when the file is open for writing). In order to make a `for` loop the most efficient way of looping over the lines of a file (a very common operation), the `next()` method uses a hidden read-ahead buffer. As a consequence of using a read-ahead buffer, combining `next()` with other file methods (like `readline()`) does not work right. However, using `seek()` to reposition the file to an absolute position will flush the read-ahead buffer. New in version 2.3.

read([size])

Read at most *size* bytes from the file (less if the read hits EOF before obtaining *size* bytes). If the *size* argument is negative or omitted, read all data until EOF is reached. The bytes are returned as a string object. An empty string is returned when EOF is encountered immediately. (For certain files, like ttys, it makes sense to continue reading after an EOF is hit.) Note that this method may call the underlying C function `fread()` more than once in an effort to acquire as close to *size* bytes as possible. Also note that when in non-blocking mode, less data than what was requested may be returned, even if no *size* parameter was given.

readline([size])

Read one entire line from the file. A trailing newline character is kept in the string (but may be absent when a file ends with an incomplete line).⁷ If the *size* argument is present and non-negative, it is a maximum byte count (including the trailing newline) and an incomplete line may be returned. An empty string is returned *only* when EOF is encountered immediately. **Note:** Unlike `stdio`'s `fgets()`, the returned string contains null characters (`'\0'`) if they occurred in the input.

readlines([sizehint])

Read until EOF using `readline()` and return a list containing the lines thus read. If the optional *sizehint* argument is present, instead of reading up to EOF, whole lines totalling approximately *sizehint* bytes (possibly after rounding up to an internal buffer size) are read. Objects implementing a file-like interface may choose to ignore *sizehint* if it cannot be implemented, or cannot be implemented efficiently.

xreadlines()

This method returns the same thing as `iter(f)`. New in version 2.1. **Deprecated since release 2.3.** Use `'for line in file'` instead.

seek([offset[, whence]])

Set the file's current position, like `stdio`'s `fseek()`. The *whence* argument is optional and defaults to `os.SEEK_SET` or 0 (absolute file positioning); other values are `os.SEEK_CUR` or 1 (seek relative to the current position) and `os.SEEK_END` or 2 (seek relative to the file's end). There is no return value. Note that if the file is opened for appending (mode `'a'` or `'a+'`), any `seek()` operations will be undone at the next write. If the file is only opened for writing in append mode (mode `'a'`), this method is essentially a no-op, but it remains useful for files opened in append mode with reading enabled (mode `'a+'`). If the file is opened in text mode (without `'b'`), only offsets returned by `tell()` are legal. Use of other offsets causes undefined behavior.

Note that not all file objects are seekable.

tell()

Return the file's current position, like `stdio`'s `ftell()`.

Note: On Windows, `tell()` can return illegal values (after an `fgets()`) when reading files with UNIX-style line-endings. Use binary mode (`'rb'`) to circumvent this problem.

truncate([size])

Truncate the file's size. If the optional *size* argument is present, the file is truncated to (at most) that size. The size defaults to the current position. The current file position is not changed. Note that if a specified size

⁷The advantage of leaving the newline on is that returning an empty string is then an unambiguous EOF indication. It is also possible (in cases where it might matter, for example, if you want to make an exact copy of a file while scanning its lines) to tell whether the last line of a file ended in a newline or not (yes this happens!).

exceeds the file's current size, the result is platform-dependent: possibilities include that the file may remain unchanged, increase to the specified size as if zero-filled, or increase to the specified size with undefined new content. Availability: Windows, many UNIX variants.

write (*str*)

Write a string to the file. There is no return value. Due to buffering, the string may not actually show up in the file until the `flush()` or `close()` method is called.

writelines (*sequence*)

Write a sequence of strings to the file. The sequence can be any iterable object producing strings, typically a list of strings. There is no return value. (The name is intended to match `readlines()`; `writelines()` does not add line separators.)

Files support the iterator protocol. Each iteration returns the same result as `file.readline()`, and iteration ends when the `readline()` method returns an empty string.

File objects also offer a number of other interesting attributes. These are not required for file-like objects, but should be implemented if they make sense for the particular object.

closed

bool indicating the current state of the file object. This is a read-only attribute; the `close()` method changes the value. It may not be available on all file-like objects.

encoding

The encoding that this file uses. When Unicode strings are written to a file, they will be converted to byte strings using this encoding. In addition, when the file is connected to a terminal, the attribute gives the encoding that the terminal is likely to use (that information might be incorrect if the user has misconfigured the terminal). The attribute is read-only and may not be present on all file-like objects. It may also be `None`, in which case the file uses the system default encoding for converting Unicode strings.

New in version 2.3.

mode

The I/O mode for the file. If the file was created using the `open()` built-in function, this will be the value of the `mode` parameter. This is a read-only attribute and may not be present on all file-like objects.

name

If the file object was created using `open()`, the name of the file. Otherwise, some string that indicates the source of the file object, of the form '<...>'. This is a read-only attribute and may not be present on all file-like objects.

newlines

If Python was built with the **--with-universal-newlines** option to **configure** (the default) this read-only attribute exists, and for files opened in universal newline read mode it keeps track of the types of newlines encountered while reading the file. The values it can take are `'\r'`, `'\n'`, `'\r\n'`, `None` (unknown, no newlines read yet) or a tuple containing all the newline types seen, to indicate that multiple newline conventions were encountered. For files not opened in universal newline read mode the value of this attribute will be `None`.

softspace

Boolean that indicates whether a space character needs to be printed before another value when using the `print` statement. Classes that are trying to simulate a file object should also have a writable `softspace` attribute, which should be initialized to zero. This will be automatic for most classes implemented in Python (care may be needed for objects that override attribute access); types implemented in C will have to provide a writable `softspace` attribute. **Note:** This attribute is not used to control the `print` statement, but to allow the implementation of `print` to keep track of its internal state.

3.10 Context Manager Types

New in version 2.5.

Python's `with` statement supports the concept of a runtime context defined by a context manager. This is implemented using two separate methods that allow user-defined classes to define a runtime context that is entered before the statement body is executed and exited when the statement ends.

The *context management protocol* consists of a pair of methods that need to be provided for a context manager object to define a runtime context:

`__enter__()`

Enter the runtime context and return either this object or another object related to the runtime context. The value returned by this method is bound to the identifier in the `as` clause of `with` statements using this context manager.

An example of a context manager that returns itself is a file object. File objects return themselves from `__enter__()` to allow `open()` to be used as the context expression in a `with` statement.

An example of a context manager that returns a related object is the one returned by `decimal.Context.get_manager()`. These managers set the active decimal context to a copy of the original decimal context and then return the copy. This allows changes to be made to the current decimal context in the body of the `with` statement without affecting code outside the `with` statement.

`__exit__(exc_type, exc_val, exc_tb)`

Exit the runtime context and return a Boolean flag indicating if any exception that occurred should be suppressed. If an exception occurred while executing the body of the `with` statement, the arguments contain the exception type, value and traceback information. Otherwise, all three arguments are `None`.

Returning a true value from this method will cause the `with` statement to suppress the exception and continue execution with the statement immediately following the `with` statement. Otherwise the exception continues propagating after this method has finished executing. Exceptions that occur during execution of this method will replace any exception that occurred in the body of the `with` statement.

The exception passed in should never be reraised explicitly - instead, this method should return a false value to indicate that the method completed successfully and does not want to suppress the raised exception. This allows context management code (such as `contextlib.nested`) to easily detect whether or not an `__exit__()` method has actually failed.

Python defines several context managers to support easy thread synchronisation, prompt closure of files or other objects, and simpler manipulation of the active decimal arithmetic context. The specific types are not treated specially beyond their implementation of the context management protocol.

Python's generators and the `contextlib.contextfactory` decorator provide a convenient way to implement these protocols. If a generator function is decorated with the `contextlib.contextfactory` decorator, it will return a context manager implementing the necessary `__enter__()` and `__exit__()` methods, rather than the iterator produced by an undecorated generator function.

Note that there is no specific slot for any of these methods in the type structure for Python objects in the Python/C API. Extension types wanting to define these methods must provide them as a normal Python accessible method. Compared to the overhead of setting up the runtime context, the overhead of a single class dictionary lookup is negligible.

3.11 Other Built-in Types

The interpreter supports several other kinds of objects. Most of these support only one or two operations.

3.11.1 Modules

The only special operation on a module is attribute access: `m.name`, where `m` is a module and `name` accesses a name defined in `m`'s symbol table. Module attributes can be assigned to. (Note that the `import` statement is not, strictly speaking, an operation on a module object; `import foo` does not require a module object named `foo` to exist, rather it requires an (external) *definition* for a module named `foo` somewhere.)

A special member of every module is `__dict__`. This is the dictionary containing the module's symbol table. Modifying this dictionary will actually change the module's symbol table, but direct assignment to the `__dict__`-attribute is not possible (you can write `m.__dict__['a'] = 1`, which defines `m.a` to be 1, but you can't write `m.__dict__ = {}`). Modifying `__dict__` directly is not recommended.

Modules built into the interpreter are written like this: `<module 'sys' (built-in)>`. If loaded from a file, they are written as `<module 'os' from '/usr/local/lib/python2.5/os.pyc'>`.

3.11.2 Classes and Class Instances

See chapters 3 and 7 of the [Python Reference Manual](#) for these.

3.11.3 Functions

Function objects are created by function definitions. The only operation on a function object is to call it: `func(argument-list)`.

There are really two flavors of function objects: built-in functions and user-defined functions. Both support the same operation (to call the function), but the implementation is different, hence the different object types.

See the [Python Reference Manual](#) for more information.

3.11.4 Methods

Methods are functions that are called using the attribute notation. There are two flavors: built-in methods (such as `append()` on lists) and class instance methods. Built-in methods are described with the types that support them.

The implementation adds two special read-only attributes to class instance methods: `m.im_self` is the object on which the method operates, and `m.im_func` is the function implementing the method. Calling `m(arg-1, arg-2, ..., arg-n)` is completely equivalent to calling `m.im_func(m.im_self, arg-1, arg-2, ..., arg-n)`.

Class instance methods are either *bound* or *unbound*, referring to whether the method was accessed through an instance or a class, respectively. When a method is unbound, its `im_self` attribute will be `None` and if called, an explicit `self` object must be passed as the first argument. In this case, `self` must be an instance of the unbound method's class (or a subclass of that class), otherwise a `TypeError` is raised.

Like function objects, methods objects support getting arbitrary attributes. However, since method attributes are actually stored on the underlying function object (`meth.im_func`), setting method attributes on either bound or unbound methods is disallowed. Attempting to set a method attribute results in a `TypeError` being raised. In order to set a method attribute, you need to explicitly set it on the underlying function object:

```
class C:
    def method(self):
        pass

c = C()
c.method.im_func.whoami = 'my name is c'
```

See the [Python Reference Manual](#) for more information.

3.11.5 Code Objects

Code objects are used by the implementation to represent “pseudo-compiled” executable Python code such as a function body. They differ from function objects because they don’t contain a reference to their global execution environment. Code objects are returned by the built-in `compile()` function and can be extracted from function objects through their `func_code` attribute.

A code object can be executed or evaluated by passing it (instead of a source string) to the `exec` statement or the built-in `eval()` function.

See the [Python Reference Manual](#) for more information.

3.11.6 Type Objects

Type objects represent the various object types. An object’s type is accessed by the built-in function `type()`. There are no special operations on types. The standard module `types` defines names for all standard built-in types.

Types are written like this: `<type 'int'>`.

3.11.7 The Null Object

This object is returned by functions that don’t explicitly return a value. It supports no special operations. There is exactly one null object, named `None` (a built-in name).

It is written as `None`.

3.11.8 The Ellipsis Object

This object is used by extended slice notation (see the [Python Reference Manual](#)). It supports no special operations. There is exactly one ellipsis object, named `Ellipsis` (a built-in name).

It is written as `Ellipsis`.

3.11.9 Boolean Values

Boolean values are the two constant objects `False` and `True`. They are used to represent truth values (although other values can also be considered false or true). In numeric contexts (for example when used as the argument to an arithmetic operator), they behave like the integers 0 and 1, respectively. The built-in function `bool()` can be used to cast any value to a Boolean, if the value can be interpreted as a truth value (see section Truth Value Testing above).

They are written as `False` and `True`, respectively.

3.11.10 Internal Objects

See the [Python Reference Manual](#) for this information. It describes stack frame objects, traceback objects, and slice objects.

3.12 Special Attributes

The implementation adds a few special read-only attributes to several object types, where they are relevant. Some of these are not reported by the `dir()` built-in function.

`__dict__`

A dictionary or other mapping object used to store an object's (writable) attributes.

`__methods__`

Deprecated since release 2.2. Use the built-in function `dir()` to get a list of an object's attributes. This attribute is no longer available.

`__members__`

Deprecated since release 2.2. Use the built-in function `dir()` to get a list of an object's attributes. This attribute is no longer available.

`__class__`

The class to which a class instance belongs.

`__bases__`

The tuple of base classes of a class object. If there are no base classes, this will be an empty tuple.

`__name__`

The name of the class or type.

String Services

The modules described in this chapter provide a wide range of string manipulation operations. Here's an overview:

<code>string</code>	Common string operations.
<code>re</code>	Regular expression search and match operations with a Perl-style expression syntax.
<code>struct</code>	Interpret strings as packed binary data.
<code>difflib</code>	Helpers for computing differences between objects.
<code>StringIO</code>	Read and write strings as if they were files.
<code>cStringIO</code>	Faster version of <code>StringIO</code> , but not subclassable.
<code>textwrap</code>	Text wrapping and filling
<code>encodings.utf-8-sig</code>	UTF-8 codec with BOM signature
<code>unicodedata</code>	Access the Unicode Database.
<code>stringprep</code>	String preparation, as per RFC 3453
<code>fpformat</code>	General floating point formatting functions.

Information on the methods of string objects can be found in section 3.6.1, “String Methods.”

4.1 `string` — Common string operations

The `string` module contains a number of useful constants and classes, as well as some deprecated legacy functions that are also available as methods on strings. See the module `re` for string functions based on regular expressions.

4.1.1 String constants

The constants defined in this module are:

`ascii_letters`

The concatenation of the `ascii_lowercase` and `ascii_uppercase` constants described below. This value is not locale-dependent.

`ascii_lowercase`

The lowercase letters `'abcdefghijklmnopqrstuvwxyz'`. This value is not locale-dependent and will not change.

`ascii_uppercase`

The uppercase letters `'ABCDEFGHIJKLMNOPQRSTUVWXYZ'`. This value is not locale-dependent and will not change.

`digits`

The string `'0123456789'`.

`hexdigits`

The string `'0123456789abcdefABCDEF'`.

letters

The concatenation of the strings `lowercase` and `uppercase` described below. The specific value is locale-dependent, and will be updated when `locale.setlocale()` is called.

lowercase

A string containing all the characters that are considered lowercase letters. On most systems this is the string `'abcdefghijklmnopqrstuvwxyz'`. Do not change its definition — the effect on the routines `upper()` and `swapcase()` is undefined. The specific value is locale-dependent, and will be updated when `locale.setlocale()` is called.

octdigits

The string `'01234567'`.

punctuation

String of ASCII characters which are considered punctuation characters in the `'C'` locale.

printable

String of characters which are considered printable. This is a combination of digits, letters, punctuation, and whitespace.

uppercase

A string containing all the characters that are considered uppercase letters. On most systems this is the string `'ABCDEFGHIJKLMNOPQRSTUVWXYZ'`. Do not change its definition — the effect on the routines `lower()` and `swapcase()` is undefined. The specific value is locale-dependent, and will be updated when `locale.setlocale()` is called.

whitespace

A string containing all characters that are considered whitespace. On most systems this includes the characters space, tab, linefeed, return, formfeed, and vertical tab. Do not change its definition — the effect on the routines `strip()` and `split()` is undefined.

4.1.2 Template strings

Templates provide simpler string substitutions as described in PEP 292. Instead of the normal `'%'`-based substitutions, Templates support `'$'`-based substitutions, using the following rules:

- `'$$'` is an escape; it is replaced with a single `'$'`.
- `'$identifier'` names a substitution placeholder matching a mapping key of `"identifier"`. By default, `"identifier"` must spell a Python identifier. The first non-identifier character after the `'$'` character terminates this placeholder specification.
- `'${identifier}'` is equivalent to `'$identifier'`. It is required when valid identifier characters follow the placeholder but are not part of the placeholder, such as `"${noun}ification"`.

Any other appearance of `'$'` in the string will result in a `ValueError` being raised.

New in version 2.4.

The `string` module provides a `Template` class that implements these rules. The methods of `Template` are:

class Template (*template*)

The constructor takes a single argument which is the template string.

substitute (*mapping* [, ***kws*])

Performs the template substitution, returning a new string. *mapping* is any dictionary-like object with keys that match the placeholders in the template. Alternatively, you can provide keyword arguments, where the keywords

are the placeholders. When both *mapping* and *kws* are given and there are duplicates, the placeholders from *kws* take precedence.

safe_substitute(*mapping*[, ***kws*])

Like `substitute()`, except that if placeholders are missing from *mapping* and *kws*, instead of raising a `KeyError` exception, the original placeholder will appear in the resulting string intact. Also, unlike with `substitute()`, any other appearances of the '\$' will simply return '\$' instead of raising `ValueError`.

While other exceptions may still occur, this method is called “safe” because substitutions always tries to return a usable string instead of raising an exception. In another sense, `safe_substitute()` may be anything other than safe, since it will silently ignore malformed templates containing dangling delimiters, unmatched braces, or placeholders that are not valid Python identifiers.

Template instances also provide one public data attribute:

template

This is the object passed to the constructor’s *template* argument. In general, you shouldn’t change it, but read-only access is not enforced.

Here is an example of how to use a Template:

```
>>> from string import Template
>>> s = Template('$who likes $what')
>>> s.substitute(who='tim', what='kung pao')
'tim likes kung pao'
>>> d = dict(who='tim')
>>> Template('Give $who $100').substitute(d)
Traceback (most recent call last):
[...]
ValueError: Invalid placeholder in string: line 1, col 10
>>> Template('$who likes $what').substitute(d)
Traceback (most recent call last):
[...]
KeyError: 'what'
>>> Template('$who likes $what').safe_substitute(d)
'tim likes $what'
```

Advanced usage: you can derive subclasses of `Template` to customize the placeholder syntax, delimiter character, or the entire regular expression used to parse template strings. To do this, you can override these class attributes:

- *delimiter* – This is the literal string describing a placeholder introducing delimiter. The default value '\$'. Note that this should *not* be a regular expression, as the implementation will call `re.escape()` on this string as needed.
- *idpattern* – This is the regular expression describing the pattern for non-braced placeholders (the braces will be added automatically as appropriate). The default value is the regular expression `'[_a-z][_a-z0-9]*'`.

Alternatively, you can provide the entire regular expression pattern by overriding the class attribute *pattern*. If you do this, the value must be a regular expression object with four named capturing groups. The capturing groups correspond to the rules given above, along with the invalid placeholder rule:

- *escaped* – This group matches the escape sequence, e.g. '\$\$', in the default pattern.
- *named* – This group matches the unbraced placeholder name; it should not include the delimiter in capturing group.
- *braced* – This group matches the brace enclosed placeholder name; it should not include either the delimiter or braces in the capturing group.

- *invalid* – This group matches any other delimiter pattern (usually a single delimiter), and it should appear last in the regular expression.

4.1.3 String functions

The following functions are available to operate on string and Unicode objects. They are not available as string methods.

capwords (*s*)

Split the argument into words using `split()`, capitalize each word using `capitalize()`, and join the capitalized words using `join()`. Note that this replaces runs of whitespace characters by a single space, and removes leading and trailing whitespace.

maketrans (*from*, *to*)

Return a translation table suitable for passing to `translate()`, that will map each character in *from* into the character at the same position in *to*; *from* and *to* must have the same length.

Warning: Don't use strings derived from `lowercase` and `uppercase` as arguments; in some locales, these don't have the same length. For case conversions, always use `lower()` and `upper()`.

4.1.4 Deprecated string functions

The following list of functions are also defined as methods of string and Unicode objects; see “String Methods” (section 3.6.1) for more information on those. You should consider these functions as deprecated, although they will not be removed until Python 3.0. The functions defined in this module are:

atof (*s*)

Deprecated since release 2.0. Use the `float()` built-in function.

Convert a string to a floating point number. The string must have the standard syntax for a floating point literal in Python, optionally preceded by a sign ('+' or '-'). Note that this behaves identical to the built-in function `float()` when passed a string.

Note: When passing in a string, values for NaN and Infinity may be returned, depending on the underlying C library. The specific set of strings accepted which cause these values to be returned depends entirely on the C library and is known to vary.

atoi (*s* [, *base*])

Deprecated since release 2.0. Use the `int()` built-in function.

Convert string *s* to an integer in the given *base*. The string must consist of one or more digits, optionally preceded by a sign ('+' or '-'). The *base* defaults to 10. If it is 0, a default base is chosen depending on the leading characters of the string (after stripping the sign): '0x' or '0X' means 16, '0' means 8, anything else means 10. If *base* is 16, a leading '0x' or '0X' is always accepted, though not required. This behaves identically to the built-in function `int()` when passed a string. (Also note: for a more flexible interpretation of numeric literals, use the built-in function `eval()`.)

atol (*s* [, *base*])

Deprecated since release 2.0. Use the `long()` built-in function.

Convert string *s* to a long integer in the given *base*. The string must consist of one or more digits, optionally preceded by a sign ('+' or '-'). The *base* argument has the same meaning as for `atoi()`. A trailing 'l' or 'L' is not allowed, except if the base is 0. Note that when invoked without *base* or with *base* set to 10, this behaves identical to the built-in function `long()` when passed a string.

capitalize (*word*)

Return a copy of *word* with only its first character capitalized.

expandtabs (*s* [, *tabsize*])

Expand tabs in a string replacing them by one or more spaces, depending on the current column and the given

tab size. The column number is reset to zero after each newline occurring in the string. This doesn't understand other non-printing characters or escape sequences. The tab size defaults to 8.

find (*s*, *sub*[, *start*[, *end*]])

Return the lowest index in *s* where the substring *sub* is found such that *sub* is wholly contained in *s*[*start*:*end*]. Return -1 on failure. Defaults for *start* and *end* and interpretation of negative values is the same as for slices.

rfind (*s*, *sub*[, *start*[, *end*]])

Like **find**() but find the highest index.

index (*s*, *sub*[, *start*[, *end*]])

Like **find**() but raise `ValueError` when the substring is not found.

rindex (*s*, *sub*[, *start*[, *end*]])

Like **rfind**() but raise `ValueError` when the substring is not found.

count (*s*, *sub*[, *start*[, *end*]])

Return the number of (non-overlapping) occurrences of substring *sub* in string *s*[*start*:*end*]. Defaults for *start* and *end* and interpretation of negative values are the same as for slices.

lower (*s*)

Return a copy of *s*, but with upper case letters converted to lower case.

split (*s*[, *sep*[, *maxsplit*]])

Return a list of the words of the string *s*. If the optional second argument *sep* is absent or `None`, the words are separated by arbitrary strings of whitespace characters (space, tab, newline, return, formfeed). If the second argument *sep* is present and not `None`, it specifies a string to be used as the word separator. The returned list will then have one more item than the number of non-overlapping occurrences of the separator in the string. The optional third argument *maxsplit* defaults to 0. If it is nonzero, at most *maxsplit* number of splits occur, and the remainder of the string is returned as the final element of the list (thus, the list will have at most *maxsplit*+1 elements).

The behavior of **split** on an empty string depends on the value of *sep*. If *sep* is not specified, or specified as `None`, the result will be an empty list. If *sep* is specified as any string, the result will be a list containing one element which is an empty string.

rsplit (*s*[, *sep*[, *maxsplit*]])

Return a list of the words of the string *s*, scanning *s* from the end. To all intents and purposes, the resulting list of words is the same as returned by **split**(), except when the optional third argument *maxsplit* is explicitly specified and nonzero. When *maxsplit* is nonzero, at most *maxsplit* number of splits – the *rightmost* ones – occur, and the remainder of the string is returned as the first element of the list (thus, the list will have at most *maxsplit*+1 elements). New in version 2.4.

splitfields (*s*[, *sep*[, *maxsplit*]])

This function behaves identically to **split**(). (In the past, **split**() was only used with one argument, while **splitfields**() was only used with two arguments.)

join (*words*[, *sep*])

Concatenate a list or tuple of words with intervening occurrences of *sep*. The default value for *sep* is a single space character. It is always true that `'string.join(string.split(s, sep), sep)'` equals *s*.

joinfields (*words*[, *sep*])

This function behaves identically to **join**(). (In the past, **join**() was only used with one argument, while **joinfields**() was only used with two arguments.) Note that there is no **joinfields**() method on string objects; use the **join**() method instead.

lstrip (*s*[, *chars*])

Return a copy of the string with leading characters removed. If *chars* is omitted or `None`, whitespace characters are removed. If given and not `None`, *chars* must be a string; the characters in the string will be stripped from the beginning of the string this method is called on. Changed in version 2.2.3: The *chars* parameter was added. The *chars* parameter cannot be passed in earlier 2.2 versions.

rstrip (*s* [, *chars*])

Return a copy of the string with trailing characters removed. If *chars* is omitted or `None`, whitespace characters are removed. If given and not `None`, *chars* must be a string; the characters in the string will be stripped from the end of the string this method is called on. Changed in version 2.2.3: The *chars* parameter was added. The *chars* parameter cannot be passed in earlier 2.2 versions.

strip (*s* [, *chars*])

Return a copy of the string with leading and trailing characters removed. If *chars* is omitted or `None`, whitespace characters are removed. If given and not `None`, *chars* must be a string; the characters in the string will be stripped from the both ends of the string this method is called on. Changed in version 2.2.3: The *chars* parameter was added. The *chars* parameter cannot be passed in earlier 2.2 versions.

swapcase (*s*)

Return a copy of *s*, but with lower case letters converted to upper case and vice versa.

translate (*s*, *table* [, *deletechars*])

Delete all characters from *s* that are in *deletechars* (if present), and then translate the characters using *table*, which must be a 256-character string giving the translation for each character value, indexed by its ordinal.

upper (*s*)

Return a copy of *s*, but with lower case letters converted to upper case.

ljust (*s*, *width*)

rjust (*s*, *width*)

center (*s*, *width*)

These functions respectively left-justify, right-justify and center a string in a field of given width. They return a string that is at least *width* characters wide, created by padding the string *s* with spaces until the given width on the right, left or both sides. The string is never truncated.

zfill (*s*, *width*)

Pad a numeric string on the left with zero digits until the given width is reached. Strings starting with a sign are handled correctly.

replace (*str*, *old*, *new* [, *maxreplace*])

Return a copy of string *str* with all occurrences of substring *old* replaced by *new*. If the optional argument *maxreplace* is given, the first *maxreplace* occurrences are replaced.

4.2 re — Regular expression operations

This module provides regular expression matching operations similar to those found in Perl. Regular expression pattern strings may not contain null bytes, but can specify the null byte using the `\number` notation. Both patterns and strings to be searched can be Unicode strings as well as 8-bit strings. The `re` module is always available.

Regular expressions use the backslash character (`'\'`) to indicate special forms or to allow special characters to be used without invoking their special meaning. This collides with Python's usage of the same character for the same purpose in string literals; for example, to match a literal backslash, one might have to write `'\\\\'` as the pattern string, because the regular expression must be `'\\'`, and each backslash must be expressed as `'\\'` inside a regular Python string literal.

The solution is to use Python's raw string notation for regular expression patterns; backslashes are not handled in any special way in a string literal prefixed with `'r'`. So `r"\n"` is a two-character string containing `'\'` and `'n'`, while `"\n"` is a one-character string containing a newline. Usually patterns will be expressed in Python code using this raw string notation.

See Also:

Mastering Regular Expressions

Book on regular expressions by Jeffrey Friedl, published by O'Reilly. The second edition of the book no longer

covers Python at all, but the first edition covered writing good regular expression patterns in great detail.

4.2.1 Regular Expression Syntax

A regular expression (or RE) specifies a set of strings that matches it; the functions in this module let you check if a particular string matches a given regular expression (or if a given regular expression matches a particular string, which comes down to the same thing).

Regular expressions can be concatenated to form new regular expressions; if *A* and *B* are both regular expressions, then *AB* is also a regular expression. In general, if a string *p* matches *A* and another string *q* matches *B*, the string *pq* will match *AB*. This holds unless *A* or *B* contain low precedence operations; boundary conditions between *A* and *B*; or have numbered group references. Thus, complex expressions can easily be constructed from simpler primitive expressions like the ones described here. For details of the theory and implementation of regular expressions, consult the Friedl book referenced above, or almost any textbook about compiler construction.

A brief explanation of the format of regular expressions follows. For further information and a gentler presentation, consult the Regular Expression HOWTO, accessible from <http://www.python.org/doc/howto/>.

Regular expressions can contain both special and ordinary characters. Most ordinary characters, like 'A', 'a', or '0', are the simplest regular expressions; they simply match themselves. You can concatenate ordinary characters, so `last` matches the string 'last'. (In the rest of this section, we'll write RE's in `this special style`, usually without quotes, and strings to be matched 'in single quotes'.)

Some characters, like '|' or '(', are special. Special characters either stand for classes of ordinary characters, or affect how the regular expressions around them are interpreted.

The special characters are:

- '.' (Dot.) In the default mode, this matches any character except a newline. If the `DOTALL` flag has been specified, this matches any character including a newline.
- '^' (Caret.) Matches the start of the string, and in `MULTILINE` mode also matches immediately after each newline.
- '\$' Matches the end of the string or just before the newline at the end of the string, and in `MULTILINE` mode also matches before a newline. `foo` matches both 'foo' and 'foobar', while the regular expression `foo$` matches only 'foo'. More interestingly, searching for `foo.$` in 'foo1\nfoo2\n' matches 'foo2' normally, but 'foo1' in `MULTILINE` mode.
- '*' Causes the resulting RE to match 0 or more repetitions of the preceding RE, as many repetitions as are possible. `ab*` will match 'a', 'ab', or 'a' followed by any number of 'b's.
- '+' Causes the resulting RE to match 1 or more repetitions of the preceding RE. `ab+` will match 'a' followed by any non-zero number of 'b's; it will not match just 'a'.
- '?' Causes the resulting RE to match 0 or 1 repetitions of the preceding RE. `ab?` will match either 'a' or 'ab'.
- *?, +?, ??** The '*', '+', and '?' qualifiers are all *greedy*; they match as much text as possible. Sometimes this behaviour isn't desired; if the RE `<.*>` is matched against '`<H1>title</H1>`', it will match the entire string, and not just '`<H1>`'. Adding '?' after the qualifier makes it perform the match in *non-greedy* or *minimal* fashion; as few characters as possible will be matched. Using `.*?` in the previous expression will match only '`<H1>`'.
- {m}** Specifies that exactly *m* copies of the previous RE should be matched; fewer matches cause the entire RE not to match. For example, `a{6}` will match exactly six 'a' characters, but not five.
- {m,n}** Causes the resulting RE to match from *m* to *n* repetitions of the preceding RE, attempting to match as many repetitions as possible. For example, `a{3,5}` will match from 3 to 5 'a' characters. Omitting *m* specifies a lower bound of zero, and omitting *n* specifies an infinite upper bound. As an example, `a{4,}b` will match `aaaab` or a thousand 'a' characters followed by a b, but not `aaab`. The comma may not be omitted or the modifier would be confused with the previously described form.

{*m*,*n*}? Causes the resulting RE to match from *m* to *n* repetitions of the preceding RE, attempting to match as *few* repetitions as possible. This is the non-greedy version of the previous qualifier. For example, on the 6-character string 'aaaaaa', '[a{3,5}]' will match 5 'a' characters, while '[a{3,5}?]' will only match 3 characters.

'\' Either escapes special characters (permitting you to match characters like '*', '?', and so forth), or signals a special sequence; special sequences are discussed below.

If you're not using a raw string to express the pattern, remember that Python also uses the backslash as an escape sequence in string literals; if the escape sequence isn't recognized by Python's parser, the backslash and subsequent character are included in the resulting string. However, if Python would recognize the resulting sequence, the backslash should be repeated twice. This is complicated and hard to understand, so it's highly recommended that you use raw strings for all but the simplest expressions.

[] Used to indicate a set of characters. Characters can be listed individually, or a range of characters can be indicated by giving two characters and separating them by a '-'. Special characters are not active inside sets. For example, '[akm\$]' will match any of the characters 'a', 'k', 'm', or '\$'; '[a-z]' will match any lowercase letter, and '[a-zA-Z0-9]' matches any letter or digit. Character classes such as `\w` or `\S` (defined below) are also acceptable inside a range. If you want to include a ']' or a '-' inside a set, precede it with a backslash, or place it as the first character. The pattern '[]]' will match '] ', for example.

You can match the characters not within a range by *complementing* the set. This is indicated by including a '^' as the first character of the set; '^' elsewhere will simply match the '^' character. For example, '[^5]' will match any character except '5', and '[^^]' will match any character except '^'.

'|' A|B, where A and B can be arbitrary REs, creates a regular expression that will match either A or B. An arbitrary number of REs can be separated by the '|' in this way. This can be used inside groups (see below) as well. As the target string is scanned, REs separated by '|' are tried from left to right. When one pattern completely matches, that branch is accepted. This means that once A matches, B will not be tested further, even if it would produce a longer overall match. In other words, the '|' operator is never greedy. To match a literal '|', use '\|', or enclose it inside a character class, as in '[|]'.

(...) Matches whatever regular expression is inside the parentheses, and indicates the start and end of a group; the contents of a group can be retrieved after a match has been performed, and can be matched later in the string with the `\number` special sequence, described below. To match the literals '(' or ')', use '\(' or '\)', or enclose them inside a character class: '[()]'.

(?...) This is an extension notation (a '?' following a '(' is not meaningful otherwise). The first character after the '?' determines what the meaning and further syntax of the construct is. Extensions usually do not create a new group; '(?P<name>...)' is the only exception to this rule. Following are the currently supported extensions.

(?iLmsux) (One or more letters from the set 'i', 'L', 'm', 's', 'u', 'x'.) The group matches the empty string; the letters set the corresponding flags (`re.I`, `re.L`, `re.M`, `re.S`, `re.U`, `re.X`) for the entire regular expression. This is useful if you wish to include the flags as part of the regular expression, instead of passing a *flag* argument to the `compile()` function.

Note that the '(?x)' flag changes how the expression is parsed. It should be used first in the expression string, or after one or more whitespace characters. If there are non-whitespace characters before the flag, the results are undefined.

(?:...) A non-grouping version of regular parentheses. Matches whatever regular expression is inside the parentheses, but the substring matched by the group *cannot* be retrieved after performing a match or referenced later in the pattern.

(?P<name>...) Similar to regular parentheses, but the substring matched by the group is accessible via the symbolic group name *name*. Group names must be valid Python identifiers, and each group name must be defined only once within a regular expression. A symbolic group is also a numbered group, just as if the group were not named. So the group named 'id' in the example above can also be referenced as the numbered group 1.

For example, if the pattern is '(?P<id>[a-zA-Z_]\w*)', the group can be referenced by its name in arguments to methods of match objects, such as `m.group('id')` or `m.end('id')`, and also by name in pattern text (for example, '(?P=id)' and replacement text (such as `\g<id>`).

(?P=name) Matches whatever text was matched by the earlier group named *name*.

(?#...) A comment; the contents of the parentheses are simply ignored.

(?=...) Matches if `[...]` matches next, but doesn't consume any of the string. This is called a *lookahead assertion*. For example, `Isaac (?=Asimov)` will match `'Isaac '` only if it's followed by `'Asimov'`.

(?!...) Matches if `[...]` doesn't match next. This is a *negative lookahead assertion*. For example, `Isaac (?!Asimov)` will match `'Isaac '` only if it's *not* followed by `'Asimov'`.

(?<=...) Matches if the current position in the string is preceded by a match for `[...]` that ends at the current position. This is called a *positive lookbehind assertion*. `(?<=abc) def` will find a match in `'abcdef'`, since the lookbehind will back up 3 characters and check if the contained pattern matches. The contained pattern must only match strings of some fixed length, meaning that `[abc]` or `[a|b]` are allowed, but `[a*]` and `[a{3,4}]` are not. Note that patterns which start with positive lookbehind assertions will never match at the beginning of the string being searched; you will most likely want to use the `search()` function rather than the `match()` function:

```
>>> import re
>>> m = re.search('(?<=abc)def', 'abcdef')
>>> m.group(0)
'def'
```

This example looks for a word following a hyphen:

```
>>> m = re.search('(?!<=)\w+', 'spam-egg')
>>> m.group(0)
'egg'
```

(?!...) Matches if the current position in the string is not preceded by a match for `[...]`. This is called a *negative lookbehind assertion*. Similar to positive lookbehind assertions, the contained pattern must only match strings of some fixed length. Patterns which start with negative lookbehind assertions may match at the beginning of the string being searched.

(?(id/name)yes-pattern|no-pattern) Will try to match with `[yes-pattern]` if the group with given *id* or *name* exists, and with `[no-pattern]` if it doesn't. `[no-pattern]` is optional and can be omitted. For example, `((<)(\w+@\w+(?:\.\w+)+)(?(1)>))` is a poor email matching pattern, which will match with `'<user@host.com>'` as well as `'user@host.com'`, but not with `'<user@host.com'`. New in version 2.4.

The special sequences consist of `'\'` and a character from the list below. If the ordinary character is not on the list, then the resulting RE will match the second character. For example, `[\$]` matches the character `'$'`.

\number Matches the contents of the group of the same number. Groups are numbered starting from 1. For example, `(.+)\1` matches `'the the'` or `'55 55'`, but not `'the end'` (note the space after the group). This special sequence can only be used to match one of the first 99 groups. If the first digit of *number* is 0, or *number* is 3 octal digits long, it will not be interpreted as a group match, but as the character with octal value *number*. Inside the `'[]'` of a character class, all numeric escapes are treated as characters.

\A Matches only at the start of the string.

\b Matches the empty string, but only at the beginning or end of a word. A word is defined as a sequence of alphanumeric or underscore characters, so the end of a word is indicated by whitespace or a non-alphanumeric, non-underscore character. Note that `\b` is defined as the boundary between `\w` and `\W`, so the precise set of characters deemed to be alphanumeric depends on the values of the `UNICODE` and `LOCALE` flags. Inside a character range, `[\b]` represents the backspace character, for compatibility with Python's string literals.

- \B** Matches the empty string, but only when it is *not* at the beginning or end of a word. This is just the opposite of `\b`, so is also subject to the settings of `LOCALE` and `UNICODE`.
- \d** When the `UNICODE` flag is not specified, matches any decimal digit; this is equivalent to the set `[0-9]`. With `UNICODE`, it will match whatever is classified as a digit in the Unicode character properties database.
- \D** When the `UNICODE` flag is not specified, matches any non-digit character; this is equivalent to the set `[^0-9]`. With `UNICODE`, it will match anything other than character marked as digits in the Unicode character properties database.
- \s** When the `LOCALE` and `UNICODE` flags are not specified, matches any whitespace character; this is equivalent to the set `[\t\n\r\f\v]`. With `LOCALE`, it will match this set plus whatever characters are defined as space for the current locale. If `UNICODE` is set, this will match the characters `[\t\n\r\f\v]` plus whatever is classified as space in the Unicode character properties database.
- \S** When the `LOCALE` and `UNICODE` flags are not specified, matches any non-whitespace character; this is equivalent to the set `[^\t\n\r\f\v]`. With `LOCALE`, it will match any character not in this set, and not defined as space in the current locale. If `UNICODE` is set, this will match anything other than `[\t\n\r\f\v]` and characters marked as space in the Unicode character properties database.
- \w** When the `LOCALE` and `UNICODE` flags are not specified, matches any alphanumeric character and the underscore; this is equivalent to the set `[a-zA-Z0-9_]`. With `LOCALE`, it will match the set `[0-9_]` plus whatever characters are defined as alphanumeric for the current locale. If `UNICODE` is set, this will match the characters `[0-9_]` plus whatever is classified as alphanumeric in the Unicode character properties database.
- \W** When the `LOCALE` and `UNICODE` flags are not specified, matches any non-alphanumeric character; this is equivalent to the set `[^a-zA-Z0-9_]`. With `LOCALE`, it will match any character not in the set `[0-9_]`, and not defined as alphanumeric for the current locale. If `UNICODE` is set, this will match anything other than `[0-9_]` and characters marked as alphanumeric in the Unicode character properties database.
- \Z** Matches only at the end of the string.

Most of the standard escapes supported by Python string literals are also accepted by the regular expression parser:

```

\a      \b      \f      \n
\r      \t      \v      \x
\\

```

Octal escapes are included in a limited form: If the first digit is a 0, or if there are three octal digits, it is considered an octal escape. Otherwise, it is a group reference. As for string literals, octal escapes are always at most three digits in length.

4.2.2 Matching vs Searching

Python offers two different primitive operations based on regular expressions: `match` and `search`. If you are accustomed to Perl's semantics, the `search` operation is what you're looking for. See the `search()` function and corresponding method of compiled regular expression objects.

Note that `match` may differ from `search` using a regular expression beginning with `^`: `^` matches only at the start of the string, or in `MULTILINE` mode also immediately following a newline. The “match” operation succeeds only if the pattern matches at the start of the string regardless of mode, or at the starting position given by the optional *pos* argument regardless of whether a newline precedes it.

```

re.compile("a").match("ba", 1)           # succeeds
re.compile("a").search("ba", 1)          # fails; 'a' not at start
re.compile("^a").search("\na", 1)        # fails; 'a' not at start
re.compile("^a", re.M).search("\na", 1)  # succeeds
re.compile("^a", re.M).search("ba", 1)   # fails; no preceding \n

```

4.2.3 Module Contents

The module defines several functions, constants, and an exception. Some of the functions are simplified versions of the full featured methods for compiled regular expressions. Most non-trivial applications always use the compiled form.

compile (*pattern* [, *flags*])

Compile a regular expression pattern into a regular expression object, which can be used for matching using its `match()` and `search()` methods, described below.

The expression's behaviour can be modified by specifying a *flags* value. Values can be any of the following variables, combined using bitwise OR (the `|` operator).

The sequence

```

prog = re.compile(pat)
result = prog.match(str)

```

is equivalent to

```

result = re.match(pat, str)

```

but the version using `compile()` is more efficient when the expression will be used several times in a single program.

I

IGNORECASE

Perform case-insensitive matching; expressions like `[A-Z]` will match lowercase letters, too. This is not affected by the current locale.

L

LOCALE

Make `\w`, `\W`, `\b`, `\B`, `\s` and `\S` dependent on the current locale.

M

MULTILINE

When specified, the pattern character `^` matches at the beginning of the string and at the beginning of each line (immediately following each newline); and the pattern character `$` matches at the end of the string and at the end of each line (immediately preceding each newline). By default, `^` matches only at the beginning of the string, and `$` only at the end of the string and immediately before the newline (if any) at the end of the string.

S

DOTALL

Make the `.` special character match any character at all, including a newline; without this flag, `.` will match anything *except* a newline.

U

UNICODE

Make `\w`, `\W`, `\b`, `\B`, `\d`, `\D`, `\s` and `\S` dependent on the Unicode character properties database. New in version 2.0.

X

VERBOSE

This flag allows you to write regular expressions that look nicer. Whitespace within the pattern is ignored, except when in a character class or preceded by an unescaped backslash, and, when a line contains a '#' neither in a character class or preceded by an unescaped backslash, all characters from the leftmost such '#' through the end of the line are ignored.

search (*pattern*, *string* [, *flags*])

Scan through *string* looking for a location where the regular expression *pattern* produces a match, and return a corresponding `MatchObject` instance. Return `None` if no position in the string matches the pattern; note that this is different from finding a zero-length match at some point in the string.

match (*pattern*, *string* [, *flags*])

If zero or more characters at the beginning of *string* match the regular expression *pattern*, return a corresponding `MatchObject` instance. Return `None` if the string does not match the pattern; note that this is different from a zero-length match.

Note: If you want to locate a match anywhere in *string*, use `search()` instead.

split (*pattern*, *string* [, *maxsplit* = 0])

Split *string* by the occurrences of *pattern*. If capturing parentheses are used in *pattern*, then the text of all groups in the pattern are also returned as part of the resulting list. If *maxsplit* is nonzero, at most *maxsplit* splits occur, and the remainder of the string is returned as the final element of the list. (Incompatibility note: in the original Python 1.5 release, *maxsplit* was ignored. This has been fixed in later releases.)

```
>>> re.split('\W+', 'Words, words, words.')
['Words', 'words', 'words', '']
>>> re.split('(\W+)', 'Words, words, words.')
['Words', ', ', ', ', 'words', ', ', ', ', 'words', ', ', '']
>>> re.split('\W+', 'Words, words, words.', 1)
['Words', 'words, words.']
```

findall (*pattern*, *string* [, *flags*])

Return a list of all non-overlapping matches of *pattern* in *string*. If one or more groups are present in the pattern, return a list of groups; this will be a list of tuples if the pattern has more than one group. Empty matches are included in the result unless they touch the beginning of another match. New in version 1.5.2. Changed in version 2.4: Added the optional flags argument.

finditer (*pattern*, *string* [, *flags*])

Return an iterator over all non-overlapping matches for the RE *pattern* in *string*. For each match, the iterator returns a match object. Empty matches are included in the result unless they touch the beginning of another match. New in version 2.2. Changed in version 2.4: Added the optional flags argument.

sub (*pattern*, *repl*, *string* [, *count*])

Return the string obtained by replacing the leftmost non-overlapping occurrences of *pattern* in *string* by the replacement *repl*. If the pattern isn't found, *string* is returned unchanged. *repl* can be a string or a function; if it is a string, any backslash escapes in it are processed. That is, '\n' is converted to a single newline character, '\r' is converted to a linefeed, and so forth. Unknown escapes such as '\j' are left alone. Backreferences, such as '\6', are replaced with the substring matched by group 6 in the pattern. For example:

```
>>> re.sub(r'def\s+([a-zA-Z_][a-zA-Z_0-9]*)\s*(\s*):',
...       r'static PyObject*\np_\1(void)\n{',
...       'def myfunc():')
'static PyObject*\np_myfunc(void)\n{'
```

If *repl* is a function, it is called for every non-overlapping occurrence of *pattern*. The function takes a single match object argument, and returns the replacement string. For example:

```
>>> def dashrepl(matchobj):
...     if matchobj.group(0) == '-': return ' '
...     else: return '-'
>>> re.sub('-{1,2}', dashrepl, 'pro---gram-files')
'pro--gram files'
```

The pattern may be a string or an RE object; if you need to specify regular expression flags, you must use a RE object, or use embedded modifiers in a pattern; for example, `'sub("(?i)b+", "x", "bbbb BBBB")'` returns `'x x'`.

The optional argument *count* is the maximum number of pattern occurrences to be replaced; *count* must be a non-negative integer. If omitted or zero, all occurrences will be replaced. Empty matches for the pattern are replaced only when not adjacent to a previous match, so `'sub('x*', '-', 'abc')'` returns `'-a-b-c-'`.

In addition to character escapes and backreferences as described above, `'\g<name>'` will use the substring matched by the group named 'name', as defined by the `'(P<name>...)'` syntax. `'\g<number>'` uses the corresponding group number; `'\g<2>'` is therefore equivalent to `'\2'`, but isn't ambiguous in a replacement such as `'\g<2>0'`. `'\20'` would be interpreted as a reference to group 20, not a reference to group 2 followed by the literal character '0'. The backreference `'\g<0>'` substitutes in the entire substring matched by the RE.

subn (*pattern*, *repl*, *string* [, *count*])

Perform the same operation as `sub()`, but return a tuple (*new_string*, *number_of_subs_made*).

escape (*string*)

Return *string* with all non-alphanumerics backslashed; this is useful if you want to match an arbitrary literal string that may have regular expression metacharacters in it.

exception error

Exception raised when a string passed to one of the functions here is not a valid regular expression (for example, it might contain unmatched parentheses) or when some other error occurs during compilation or matching. It is never an error if a string contains no match for a pattern.

4.2.4 Regular Expression Objects

Compiled regular expression objects support the following methods and attributes:

match (*string* [, *pos* [, *endpos*]])

If zero or more characters at the beginning of *string* match this regular expression, return a corresponding `MatchObject` instance. Return `None` if the string does not match the pattern; note that this is different from a zero-length match.

Note: If you want to locate a match anywhere in *string*, use `search()` instead.

The optional second parameter *pos* gives an index in the string where the search is to start; it defaults to 0. This is not completely equivalent to slicing the string; the `'^'` pattern character matches at the real beginning of the string and at positions just after a newline, but not necessarily at the index where the search is to start.

The optional parameter *endpos* limits how far the string will be searched; it will be as if the string is *endpos* characters long, so only the characters from *pos* to *endpos* - 1 will be searched for a match. If *endpos* is less than *pos*, no match will be found, otherwise, if *rx* is a compiled regular expression object, `rx.match(string, 0, 50)` is equivalent to `rx.match(string[:50], 0)`.

search (*string* [, *pos* [, *endpos*]])

Scan through *string* looking for a location where this regular expression produces a match, and return a corresponding `MatchObject` instance. Return `None` if no position in the string matches the pattern; note that this is different from finding a zero-length match at some point in the string.

The optional *pos* and *endpos* parameters have the same meaning as for the `match()` method.

split (*string* [, *maxsplit* = 0])

Identical to the `split()` function, using the compiled pattern.

findall (*string* [, *pos* [, *endpos*]])

Identical to the `findall()` function, using the compiled pattern.

finditer (*string* [, *pos* [, *endpos*]])

Identical to the `finditer()` function, using the compiled pattern.

sub (*repl*, *string* [, *count* = 0])

Identical to the `sub()` function, using the compiled pattern.

subn (*repl*, *string* [, *count* = 0])

Identical to the `subn()` function, using the compiled pattern.

flags

The flags argument used when the RE object was compiled, or 0 if no flags were provided.

groupindex

A dictionary mapping any symbolic group names defined by `(?P<id>)` to group numbers. The dictionary is empty if no symbolic groups were used in the pattern.

pattern

The pattern string from which the RE object was compiled.

4.2.5 Match Objects

`MatchObject` instances support the following methods and attributes:

expand (*template*)

Return the string obtained by doing backslash substitution on the template string *template*, as done by the `sub()` method. Escapes such as `'\n'` are converted to the appropriate characters, and numeric backreferences (`'\1'`, `'\2'`) and named backreferences (`'\g<1>'`, `'\g<name>'`) are replaced by the contents of the corresponding group.

group ([*group1*, ...])

Returns one or more subgroups of the match. If there is a single argument, the result is a single string; if there are multiple arguments, the result is a tuple with one item per argument. Without arguments, *group1* defaults to zero (the whole match is returned). If a *groupN* argument is zero, the corresponding return value is the entire matching string; if it is in the inclusive range [1..99], it is the string matching the corresponding parenthesized group. If a group number is negative or larger than the number of groups defined in the pattern, an `IndexError` exception is raised. If a group is contained in a part of the pattern that did not match, the corresponding result is `None`. If a group is contained in a part of the pattern that matched multiple times, the last match is returned.

If the regular expression uses the `(?P<name>...)` syntax, the *groupN* arguments may also be strings identifying groups by their group name. If a string argument is not used as a group name in the pattern, an `IndexError` exception is raised.

A moderately complicated example:

```
m = re.match(r"(?P<int>\d+)\.(\d*)", '3.14')
```

After performing this match, `m.group(1)` is `'3'`, as is `m.group('int')`, and `m.group(2)` is `'14'`.

groups ([*default*])

Return a tuple containing all the subgroups of the match, from 1 up to however many groups are in the pattern. The *default* argument is used for groups that did not participate in the match; it defaults to `None`. (Compatibility note: in the original Python 1.5 release, if the tuple was one element long, a string would be returned instead. In later versions (from 1.5.1 on), a singleton tuple is returned in such cases.)

groupdict ([*default*])

Return a dictionary containing all the *named* subgroups of the match, keyed by the subgroup name. The *default* argument is used for groups that did not participate in the match; it defaults to `None`.

start ([*group*])

end ([*group*])

Return the indices of the start and end of the substring matched by *group*; *group* defaults to zero (meaning the whole matched substring). Return `-1` if *group* exists but did not contribute to the match. For a match object *m*, and a group *g* that did contribute to the match, the substring matched by group *g* (equivalent to `m.group(g)`) is

```
m.string[m.start(g):m.end(g)]
```

Note that `m.start(group)` will equal `m.end(group)` if *group* matched a null string. For example, after `m = re.search('b(c?)', 'cba')`, `m.start(0)` is 1, `m.end(0)` is 2, `m.start(1)` and `m.end(1)` are both 2, and `m.start(2)` raises an `IndexError` exception.

span ([*group*])

For `MatchObject` *m*, return the 2-tuple `(m.start(group), m.end(group))`. Note that if *group* did not contribute to the match, this is `(-1, -1)`. Again, *group* defaults to zero.

pos

The value of *pos* which was passed to the `search()` or `match()` method of the `RegexObject`. This is the index into the string at which the RE engine started looking for a match.

endpos

The value of *endpos* which was passed to the `search()` or `match()` method of the `RegexObject`. This is the index into the string beyond which the RE engine will not go.

lastindex

The integer index of the last matched capturing group, or `None` if no group was matched at all. For example, the expressions `「(a)b」`, `「(a)(b)」`, and `「(ab)」` will have `lastindex == 1` if applied to the string `'ab'`, while the expression `「(a)(b)」` will have `lastindex == 2`, if applied to the same string.

lastgroup

The name of the last matched capturing group, or `None` if the group didn't have a name, or if no group was matched at all.

re

The regular expression object whose `match()` or `search()` method produced this `MatchObject` instance.

string

The string passed to `match()` or `search()`.

4.2.6 Examples

Simulating `scanf()`

Python does not currently have an equivalent to `scanf()`. Regular expressions are generally more powerful, though also more verbose, than `scanf()` format strings. The table below offers some more-or-less equivalent mappings between `scanf()` format tokens and regular expressions.

scanf () Token	Regular Expression
%c	<code>[.]</code>
%5c	<code>[.]{5}</code>
%d	<code>[+]? \d+</code>
%e, %E, %f, %g	<code>[+]? (\d+ (\.\d*)? \.\d+) ([eE] [+]? \d+)?</code>
%i	<code>[+]? (0[xX] [\dA-Fa-f] + 0[0-7]* \d+)</code>
%o	<code>0[0-7]*</code>
%s	<code>[S]</code>
%u	<code>[d]</code>
%x, %X	<code>0[xX] [\dA-Fa-f] +</code>

To extract the filename and numbers from a string like

```
/usr/sbin/sendmail - 0 errors, 4 warnings
```

you would use a `scanf()` format like

```
%s - %d errors, %d warnings
```

The equivalent regular expression would be

```
(\S+) - (\d+) errors, (\d+) warnings
```

Avoiding recursion

If you create regular expressions that require the engine to perform a lot of recursion, you may encounter a `RuntimeError` exception with the message `maximum recursion limit exceeded`. For example,

```
>>> import re
>>> s = 'Begin ' + 1000*'a very long string ' + 'end'
>>> re.match('Begin (\w| )*? end', s).end()
Traceback (most recent call last):
  File "<stdin>", line 1, in ?
  File "/usr/local/lib/python2.5/re.py", line 132, in match
    return _compile(pattern, flags).match(string)
RuntimeError: maximum recursion limit exceeded
```

You can often restructure your regular expression to avoid recursion.

Starting with Python 2.3, simple uses of the `[*?]` pattern are special-cased to avoid recursion. Thus, the above regular expression can avoid recursion by being recast as `Begin [a-zA-Z0-9_]*?end`. As a further benefit, such regular expressions will run faster than their recursive equivalents.

4.3 struct — Interpret strings as packed binary data

This module performs conversions between Python values and C structs represented as Python strings. It uses *format strings* (explained below) as compact descriptions of the lay-out of the C structs and the intended conversion to/from Python values. This can be used in handling binary data stored in files or from network connections, among other sources.

The module defines the following exception and functions:

exception error

Exception raised on various occasions; argument is a string describing what is wrong.

pack (*fmt*, *v1*, *v2*, ...)

Return a string containing the values *v1*, *v2*, ... packed according to the given format. The arguments must match the values required by the format exactly.

pack_into (*fmt*, *buffer*, *offset*, *v1*, *v2*, ...)

Pack the values *v1*, *v2*, ... according to the given format, write the packed bytes into the writable *buffer* starting at *offset*. Note that the offset is not an optional argument.

New in version 2.5.

unpack (*fmt*, *string*)

Unpack the string (presumably packed by `pack (fmt, ...)`) according to the given format. The result is a tuple even if it contains exactly one item. The string must contain exactly the amount of data required by the format (`len (string)` must equal `calcsiz (fmt)`).

unpack_from (*fmt*, *buffer* [, *offset* = 0])

Unpack the *buffer* according to the given format. The result is a tuple even if it contains exactly one item. The *buffer* must contain at least the amount of data required by the format (`len (buffer [offset:])` must be at least `calcsiz (fmt)`).

New in version 2.5.

calcsiz (*fmt*)

Return the size of the struct (and hence of the string) corresponding to the given format.

Format characters have the following meaning; the conversion between C and Python values should be obvious given their types:

Format	C Type	Python	Notes
'x'	pad byte	no value	
'c'	char	string of length 1	
'b'	signed char	integer	
'B'	unsigned char	integer	
'h'	short	integer	
'H'	unsigned short	integer	
'i'	int	integer	
'I'	unsigned int	long	
'l'	long	integer	
'L'	unsigned long	long	
'q'	long long	long	(1)
'Q'	unsigned long long	long	(1)
'f'	float	float	
'd'	double	float	
's'	char[]	string	
'p'	char[]	string	
'P'	void *	integer	

Notes:

(1) The 'q' and 'Q' conversion codes are available in native mode only if the platform C compiler supports C long long, or, on Windows, __int64. They are always available in standard modes. New in version 2.2.

A format character may be preceded by an integral repeat count. For example, the format string '4h' means exactly the same as 'hhhh'.

Whitespace characters between formats are ignored; a count and its format must not contain whitespace though.

For the 's' format character, the count is interpreted as the size of the string, not a repeat count like for the other format characters; for example, '10s' means a single 10-byte string, while '10c' means 10 characters. For packing, the string is truncated or padded with null bytes as appropriate to make it fit. For unpacking, the resulting string always has exactly the specified number of bytes. As a special case, '0s' means a single, empty string (while '0c' means 0 characters).

The 'p' format character encodes a "Pascal string", meaning a short variable-length string stored in a fixed number of bytes. The count is the total number of bytes stored. The first byte stored is the length of the string, or 255, whichever is smaller. The bytes of the string follow. If the string passed in to `pack()` is too long (longer than the count minus 1), only the leading count-1 bytes of the string are stored. If the string is shorter than count-1, it is padded with null bytes so that exactly count bytes in all are used. Note that for `unpack()`, the 'p' format character consumes count bytes, but that the string returned can never contain more than 255 characters.

For the 'I', 'L', 'q' and 'Q' format characters, the return value is a Python long integer.

For the 'P' format character, the return value is a Python integer or long integer, depending on the size needed to hold a pointer when it has been cast to an integer type. A NULL pointer will always be returned as the Python integer 0. When packing pointer-sized values, Python integer or long integer objects may be used. For example, the Alpha and Merced processors use 64-bit pointer values, meaning a Python long integer will be used to hold the pointer; other platforms use 32-bit pointers and will use a Python integer.

By default, C numbers are represented in the machine's native format and byte order, and properly aligned by skipping pad bytes if necessary (according to the rules used by the C compiler).

Alternatively, the first character of the format string can be used to indicate the byte order, size and alignment of the packed data, according to the following table:

Character	Byte order	Size and alignment
'@'	native	native
'='	native	standard
'<'	little-endian	standard
'>'	big-endian	standard
'!'	network (= big-endian)	standard

If the first character is not one of these, '@' is assumed.

Native byte order is big-endian or little-endian, depending on the host system. For example, Motorola and Sun processors are big-endian; Intel and DEC processors are little-endian.

Native size and alignment are determined using the C compiler's `sizeof` expression. This is always combined with native byte order.

Standard size and alignment are as follows: no alignment is required for any type (so you have to use pad bytes); `short` is 2 bytes; `int` and `long` are 4 bytes; `long long` (`__int64` on Windows) is 8 bytes; `float` and `double` are 32-bit and 64-bit IEEE floating point numbers, respectively.

Note the difference between '@' and '=': both use native byte order, but the size and alignment of the latter is standardized.

The form '!' is available for those poor souls who claim they can't remember whether network byte order is big-endian or little-endian.

There is no way to indicate non-native byte order (force byte-swapping); use the appropriate choice of '<' or '>'.

The 'P' format character is only available for the native byte ordering (selected as the default or with the '@' byte order character). The byte order character '=' chooses to use little- or big-endian ordering based on the host system. The `struct` module does not interpret this as native ordering, so the 'P' format is not available.

Examples (all using native byte order, size and alignment, on a big-endian machine):

```

>>> from struct import *
>>> pack('hhl', 1, 2, 3)
'\x00\x01\x00\x02\x00\x00\x00\x03'
>>> unpack('hhl', '\x00\x01\x00\x02\x00\x00\x00\x03')
(1, 2, 3)
>>> calcsize('hhl')
8

```

Hint: to align the end of a structure to the alignment requirement of a particular type, end the format with the code for that type with a repeat count of zero. For example, the format `'llh0l'` specifies two pad bytes at the end, assuming longs are aligned on 4-byte boundaries. This only works when native size and alignment are in effect; standard size and alignment does not enforce any alignment.

See Also:

[Module `array`](#) (section 5.6):

Packed binary storage of homogeneous data.

[Module `xdrlib`](#) (section 9.5):

Packing and unpacking of XDR data.

4.3.1 Struct Objects

The `struct` module also defines the following type:

class `Struct` (*format*)

Return a new `Struct` object which writes and reads binary data according to the format string *format*. Creating a `Struct` object once and calling its methods is more efficient than calling the `struct` functions with the same format since the format string only needs to be compiled once.

New in version 2.5.

Compiled `Struct` objects support the following methods and attributes:

`pack` (*v1*, *v2*, ...)

Identical to the `pack()` function, using the compiled format. (`len(result)` will equal `self.size`.)

`pack_into` (*buffer*, *offset*, *v1*, *v2*, ...)

Identical to the `pack_into()` function, using the compiled format.

`unpack` (*string*)

Identical to the `unpack()` function, using the compiled format. (`len(string)` must equal `self.size`.)

`unpack_from` (*buffer*, [*offset* = 0])

Identical to the `unpack_from()` function, using the compiled format. (`len(buffer[offset:])` must be at least `self.size`.)

`format`

The format string used to construct this `Struct` object.

4.4 difflib — Helpers for computing deltas

New in version 2.1.

class `SequenceMatcher`

This is a flexible class for comparing pairs of sequences of any type, so long as the sequence elements are hashable. The basic algorithm predates, and is a little fancier than, an algorithm published in the late 1980's by

Ratcliff and Obershelp under the hyperbolic name “gestalt pattern matching.” The idea is to find the longest contiguous matching subsequence that contains no “junk” elements (the Ratcliff and Obershelp algorithm doesn’t address junk). The same idea is then applied recursively to the pieces of the sequences to the left and to the right of the matching subsequence. This does not yield minimal edit sequences, but does tend to yield matches that “look right” to people.

Timing: The basic Ratcliff-Obershelp algorithm is cubic time in the worst case and quadratic time in the expected case. `SequenceMatcher` is quadratic time for the worst case and has expected-case behavior dependent in a complicated way on how many elements the sequences have in common; best case time is linear.

class `Differ`

This is a class for comparing sequences of lines of text, and producing human-readable differences or deltas. `Differ` uses `SequenceMatcher` both to compare sequences of lines, and to compare sequences of characters within similar (near-matching) lines.

Each line of a `Differ` delta begins with a two-letter code:

Code	Meaning
' - '	line unique to sequence 1
' + '	line unique to sequence 2
' '	line common to both sequences
' ? '	line not present in either input sequence

Lines beginning with ‘ ? ’ attempt to guide the eye to intraline differences, and were not present in either input sequence. These lines can be confusing if the sequences contain tab characters.

class `HtmlDiff`

This class can be used to create an HTML table (or a complete HTML file containing the table) showing a side by side, line by line comparison of text with inter-line and intra-line change highlights. The table can be generated in either full or contextual difference mode.

The constructor for this class is:

`__init__` ([*tabsize*][, *wrapcolumn*][, *linejunk*][, *charjunk*])

Initializes instance of `HtmlDiff`.

tabsize is an optional keyword argument to specify tab stop spacing and defaults to 8.

wrapcolumn is an optional keyword to specify column number where lines are broken and wrapped, defaults to `None` where lines are not wrapped.

linejunk and *charjunk* are optional keyword arguments passed into `ndiff()` (used by `HtmlDiff` to generate the side by side HTML differences). See `ndiff()` documentation for argument default values and descriptions.

The following methods are public:

`make_file` (*fromlines*, *tolines* [, *fromdesc*][, *todesc*][, *context*][, *numlines*])

Compares *fromlines* and *tolines* (lists of strings) and returns a string which is a complete HTML file containing a table showing line by line differences with inter-line and intra-line changes highlighted.

fromdesc and *todesc* are optional keyword arguments to specify from/to file column header strings (both default to an empty string).

context and *numlines* are both optional keyword arguments. Set *context* to `True` when contextual differences are to be shown, else the default is `False` to show the full files. *numlines* defaults to 5. When *context* is `True` *numlines* controls the number of context lines which surround the difference highlights. When *context* is `False` *numlines* controls the number of lines which are shown before a difference highlight when using the “next” hyperlinks (setting to zero would cause the “next” hyperlinks to place the next difference highlight at the top of the browser without any leading context).

`make_table` (*fromlines*, *tolines* [, *fromdesc*][, *todesc*][, *context*][, *numlines*])

Compares *fromlines* and *tolines* (lists of strings) and returns a string which is a complete HTML table showing line by line differences with inter-line and intra-line changes highlighted.

The arguments for this method are the same as those for the `make_file()` method.

‘Tools/scripts/diff.py’ is a command-line front-end to this class and contains a good example of its use.

New in version 2.4.

context_diff (*a*, *b*[[, *fromfile*]], *tofile*[[, *fromfiledate*]], *tofiledate*[[, *n*]], *lineterm*])

Compare *a* and *b* (lists of strings); return a delta (a generator generating the delta lines) in context diff format.

Context diffs are a compact way of showing just the lines that have changed plus a few lines of context. The changes are shown in a before/after style. The number of context lines is set by *n* which defaults to three.

By default, the diff control lines (those with *** or ---) are created with a trailing newline. This is helpful so that inputs created from `file.readlines()` result in diffs that are suitable for use with `file.writelines()` since both the inputs and outputs have trailing newlines.

For inputs that do not have trailing newlines, set the *lineterm* argument to "" so that the output will be uniformly newline free.

The context diff format normally has a header for filenames and modification times. Any or all of these may be specified using strings for *fromfile*, *tofile*, *fromfiledate*, and *tofiledate*. The modification times are normally expressed in the format returned by `time.ctime()`. If not specified, the strings default to blanks.

‘Tools/scripts/diff.py’ is a command-line front-end for this function.

New in version 2.3.

get_close_matches (*word*, *possibilities*[[, *n*]], *cutoff*])

Return a list of the best “good enough” matches. *word* is a sequence for which close matches are desired (typically a string), and *possibilities* is a list of sequences against which to match *word* (typically a list of strings).

Optional argument *n* (default 3) is the maximum number of close matches to return; *n* must be greater than 0.

Optional argument *cutoff* (default 0.6) is a float in the range [0, 1]. Possibilities that don’t score at least that similar to *word* are ignored.

The best (no more than *n*) matches among the possibilities are returned in a list, sorted by similarity score, most similar first.

```
>>> get_close_matches('appel', ['ape', 'apple', 'peach', 'puppy'])
['apple', 'ape']
>>> import keyword
>>> get_close_matches('wheel', keyword.kwlist)
['while']
>>> get_close_matches('apple', keyword.kwlist)
[]
>>> get_close_matches('accept', keyword.kwlist)
['except']
```

ndiff (*a*, *b*[[, *linejunk*]], *charjunk*])

Compare *a* and *b* (lists of strings); return a Differ-style delta (a generator generating the delta lines).

Optional keyword parameters *linejunk* and *charjunk* are for filter functions (or None):

linejunk: A function that accepts a single string argument, and returns true if the string is junk, or false if not. The default is (None), starting with Python 2.3. Before then, the default was the module-level function `IS_LINE_JUNK()`, which filters out lines without visible characters, except for at most one pound character (‘#’). As of Python 2.3, the underlying `SequenceMatcher` class does a dynamic analysis of which lines are so frequent as to constitute noise, and this usually works better than the pre-2.3 default.

charjunk: A function that accepts a character (a string of length 1), and returns if the character is junk, or false if not. The default is module-level function `IS_CHARACTER_JUNK()`, which filters out whitespace characters (a blank or tab; note: bad idea to include newline in this!).

‘Tools/scripts/ndiff.py’ is a command-line front-end to this function.

```
>>> diff = ndiff('one\ntwo\nthree\n'.splitlines(1),
...              'ore\ntree\nemu\n'.splitlines(1))
>>> print ''.join(diff),
- one
? ^
+ ore
? ^
- two
- three
? -
+ tree
+ emu
```

restore (*sequence*, *which*)

Return one of the two sequences that generated a delta.

Given a *sequence* produced by `Differ.compare()` or `ndiff()`, extract lines originating from file 1 or 2 (parameter *which*), stripping off line prefixes.

Example:

```
>>> diff = ndiff('one\ntwo\nthree\n'.splitlines(1),
...              'ore\ntree\nemu\n'.splitlines(1))
>>> diff = list(diff) # materialize the generated delta into a list
>>> print ''.join(restore(diff, 1)),
one
two
three
>>> print ''.join(restore(diff, 2)),
ore
tree
emu
```

unified_diff (*a*, *b*[[, *fromfile*]], *tofile*[[, *fromfiledate*]], *tofiledate*[[, *n*]], *lineterm*])

Compare *a* and *b* (lists of strings); return a delta (a generator generating the delta lines) in unified diff format.

Unified diffs are a compact way of showing just the lines that have changed plus a few lines of context. The changes are shown in a inline style (instead of separate before/after blocks). The number of context lines is set by *n* which defaults to three.

By default, the diff control lines (those with ---, +++, or @@) are created with a trailing newline. This is helpful so that inputs created from `file.readlines()` result in diffs that are suitable for use with `file.writelines()` since both the inputs and outputs have trailing newlines.

For inputs that do not have trailing newlines, set the *lineterm* argument to "" so that the output will be uniformly newline free.

The context diff format normally has a header for filenames and modification times. Any or all of these may be specified using strings for *fromfile*, *tofile*, *fromfiledate*, and *tofiledate*. The modification times are normally expressed in the format returned by `time.ctime()`. If not specified, the strings default to blanks.

'Tools/scripts/diff.py' is a command-line front-end for this function.

New in version 2.3.

IS_LINE_JUNK (*line*)

Return true for ignorable lines. The line *line* is ignorable if *line* is blank or contains a single '#', otherwise it is not ignorable. Used as a default for parameter *linejunk* in `ndiff()` before Python 2.3.

IS_CHARACTER_JUNK (*ch*)

Return true for ignorable characters. The character *ch* is ignorable if *ch* is a space or tab, otherwise it is not ignorable. Used as a default for parameter *charjunk* in `ndiff()`.

See Also:

Pattern Matching: The Gestalt Approach

(<http://www.ddj.com/184407970?pgno=5>)

Discussion of a similar algorithm by John W. Ratcliff and D. E. Metzener. This was published in *Dr. Dobb's Journal* in July, 1988.

4.4.1 SequenceMatcher Objects

The `SequenceMatcher` class has this constructor:

class `SequenceMatcher` (`[isjunk[, a[, b]]]`)

Optional argument `isjunk` must be `None` (the default) or a one-argument function that takes a sequence element and returns true if and only if the element is “junk” and should be ignored. Passing `None` for `isjunk` is equivalent to passing `lambda x: 0`; in other words, no elements are ignored. For example, pass:

```
lambda x: x in " \t"
```

if you’re comparing lines as sequences of characters, and don’t want to synch up on blanks or hard tabs.

The optional arguments `a` and `b` are sequences to be compared; both default to empty strings. The elements of both sequences must be hashable.

`SequenceMatcher` objects have the following methods:

`set_seqs` (`a`, `b`)

Set the two sequences to be compared.

`SequenceMatcher` computes and caches detailed information about the second sequence, so if you want to compare one sequence against many sequences, use `set_seq2()` to set the commonly used sequence once and call `set_seq1()` repeatedly, once for each of the other sequences.

`set_seq1` (`a`)

Set the first sequence to be compared. The second sequence to be compared is not changed.

`set_seq2` (`b`)

Set the second sequence to be compared. The first sequence to be compared is not changed.

`find_longest_match` (`alo`, `ahi`, `blo`, `bhi`)

Find longest matching block in `a[alo:ahi]` and `b[blo:bhi]`.

If `isjunk` was omitted or `None`, `get_longest_match()` returns `(i, j, k)` such that `a[i:i+k]` is equal to `b[j:j+k]`, where `alo <= i <= i+k <= ahi` and `blo <= j <= j+k <= bhi`. For all `(i', j', k')` meeting those conditions, the additional conditions `k >= k'`, `i <= i'`, and if `i == i'`, `j <= j'` are also met. In other words, of all maximal matching blocks, return one that starts earliest in `a`, and of all those maximal matching blocks that start earliest in `a`, return the one that starts earliest in `b`.

```
>>> s = SequenceMatcher(None, " abcd", "abcd abcd")
>>> s.find_longest_match(0, 5, 0, 9)
(0, 4, 5)
```

If `isjunk` was provided, first the longest matching block is determined as above, but with the additional restriction that no junk element appears in the block. Then that block is extended as far as possible by matching (only) junk elements on both sides. So the resulting block never matches on junk except as identical junk happens to be adjacent to an interesting match.

Here’s the same example as before, but considering blanks to be junk. That prevents ‘ abcd’ from matching the ‘ abcd’ at the tail end of the second sequence directly. Instead only the ‘ abcd’ can match, and matches the leftmost ‘ abcd’ in the second sequence:

```
>>> s = SequenceMatcher(lambda x: x==" ", " abcd", "abcd abcd")
>>> s.find_longest_match(0, 5, 0, 9)
(1, 0, 4)
```

If no blocks match, this returns `(alo, blo, 0)`.

get_matching_blocks()

Return list of triples describing matching subsequences. Each triple is of the form `(i, j, n)`, and means that `a[i:i+n] == b[j:j+n]`. The triples are monotonically increasing in *i* and *j*.

The last triple is a dummy, and has the value `(len(a), len(b), 0)`. It is the only triple with *n* == 0.

If `(i, j, n)` and `(i', j', n)` are adjacent triples in the list, and the second is not the last triple in the list, then `i+n != i'` or `j+n != j'`; in other words, adjacent triples always describe non-adjacent equal blocks. Changed in version 2.5: The guarantee that adjacent triples always describe non-adjacent blocks was implemented.

```
>>> s = SequenceMatcher(None, "abxcd", "abcd")
>>> s.get_matching_blocks()
[(0, 0, 2), (3, 2, 2), (5, 4, 0)]
```

get_opcodes()

Return list of 5-tuples describing how to turn *a* into *b*. Each tuple is of the form `(tag, i1, i2, j1, j2)`. The first tuple has `i1 == j1 == 0`, and remaining tuples have *i1* equal to the *i2* from the preceding tuple, and, likewise, *j1* equal to the previous *j2*.

The *tag* values are strings, with these meanings:

Value	Meaning
'replace'	<code>a[<i>i1</i>:<i>i2</i>]</code> should be replaced by <code>b[<i>j1</i>:<i>j2</i>]</code> .
'delete'	<code>a[<i>i1</i>:<i>i2</i>]</code> should be deleted. Note that <code><i>j1</i> == <i>j2</i></code> in this case.
'insert'	<code>b[<i>j1</i>:<i>j2</i>]</code> should be inserted at <code>a[<i>i1</i>:<i>i1</i>]</code> . Note that <code><i>i1</i> == <i>i2</i></code> in this case.
'equal'	<code>a[<i>i1</i>:<i>i2</i>] == b[<i>j1</i>:<i>j2</i>]</code> (the sub-sequences are equal).

For example:

```
>>> a = "qabxcd"
>>> b = "abycdf"
>>> s = SequenceMatcher(None, a, b)
>>> for tag, i1, i2, j1, j2 in s.get_opcodes():
...     print ("%7s a[%d:%d] (%s) b[%d:%d] (%s)" %
...             (tag, i1, i2, a[i1:i2], j1, j2, b[j1:j2]))
delete a[0:1] (q) b[0:0] ()
equal a[1:3] (ab) b[0:2] (ab)
replace a[3:4] (x) b[2:3] (y)
equal a[4:6] (cd) b[3:5] (cd)
insert a[6:6] () b[5:6] (f)
```

get_grouped_opcodes([*n*])

Return a generator of groups with up to *n* lines of context.

Starting with the groups returned by `get_opcodes()`, this method splits out smaller change clusters and eliminates intervening ranges which have no changes.

The groups are returned in the same format as `get_opcodes()`. New in version 2.3.

ratio()

Return a measure of the sequences' similarity as a float in the range [0, 1].

Where *T* is the total number of elements in both sequences, and *M* is the number of matches, this is `2.0*M / T`. Note that this is 1.0 if the sequences are identical, and 0.0 if they have nothing in common.

This is expensive to compute if `get_matching_blocks()` or `get_opcodes()` hasn't already been called, in which case you may want to try `quick_ratio()` or `real_quick_ratio()` first to get an upper bound.

`quick_ratio()`

Return an upper bound on `ratio()` relatively quickly.

This isn't defined beyond that it is an upper bound on `ratio()`, and is faster to compute.

`real_quick_ratio()`

Return an upper bound on `ratio()` very quickly.

This isn't defined beyond that it is an upper bound on `ratio()`, and is faster to compute than either `ratio()` or `quick_ratio()`.

The three methods that return the ratio of matching to total characters can give different results due to differing levels of approximation, although `quick_ratio()` and `real_quick_ratio()` are always at least as large as `ratio()`:

```
>>> s = SequenceMatcher(None, "abcd", "bcde")
>>> s.ratio()
0.75
>>> s.quick_ratio()
0.75
>>> s.real_quick_ratio()
1.0
```

4.4.2 SequenceMatcher Examples

This example compares two strings, considering blanks to be “junk:”

```
>>> s = SequenceMatcher(lambda x: x == " ",
...                       "private Thread currentThread;",
...                       "private volatile Thread currentThread;")
```

`ratio()` returns a float in $[0, 1]$, measuring the similarity of the sequences. As a rule of thumb, a `ratio()` value over 0.6 means the sequences are close matches:

```
>>> print round(s.ratio(), 3)
0.866
```

If you're only interested in where the sequences match, `get_matching_blocks()` is handy:

```
>>> for block in s.get_matching_blocks():
...     print "a[%d] and b[%d] match for %d elements" % block
a[0] and b[0] match for 8 elements
a[8] and b[17] match for 6 elements
a[14] and b[23] match for 15 elements
a[29] and b[38] match for 0 elements
```

Note that the last tuple returned by `get_matching_blocks()` is always a dummy, `(len(a), len(b), 0)`, and this is the only case in which the last tuple element (number of elements matched) is 0.

If you want to know how to change the first sequence into the second, use `get_opcodes()`:

```
>>> for opcode in s.get_opcodes():
...     print "%6s a[%d:%d] b[%d:%d]" % opcode
equal a[0:8] b[0:8]
insert a[8:8] b[8:17]
equal a[8:14] b[17:23]
equal a[14:29] b[23:38]
```

See also the function `get_close_matches()` in this module, which shows how simple code building on `SequenceMatcher` can be used to do useful work.

4.4.3 Differ Objects

Note that `Differ`-generated deltas make no claim to be **minimal** diffs. To the contrary, minimal diffs are often counter-intuitive, because they synch up anywhere possible, sometimes accidental matches 100 pages apart. Restricting synch points to contiguous matches preserves some notion of locality, at the occasional cost of producing a longer diff.

The `Differ` class has this constructor:

```
class Differ ([linejunk [, charjunk ]])
```

Optional keyword parameters *linejunk* and *charjunk* are for filter functions (or `None`):

linejunk: A function that accepts a single string argument, and returns true if the string is junk. The default is `None`, meaning that no line is considered junk.

charjunk: A function that accepts a single character argument (a string of length 1), and returns true if the character is junk. The default is `None`, meaning that no character is considered junk.

`Differ` objects are used (deltas generated) via a single method:

```
compare (a, b)
```

Compare two sequences of lines, and generate the delta (a sequence of lines).

Each sequence must contain individual single-line strings ending with newlines. Such sequences can be obtained from the `readlines()` method of file-like objects. The delta generated also consists of newline-terminated strings, ready to be printed as-is via the `writelines()` method of a file-like object.

4.4.4 Differ Example

This example compares two texts. First we set up the texts, sequences of individual single-line strings ending with newlines (such sequences can also be obtained from the `readlines()` method of file-like objects):

```

>>> text1 = ''' 1. Beautiful is better than ugly.
... 2. Explicit is better than implicit.
... 3. Simple is better than complex.
... 4. Complex is better than complicated.
... '''.splitlines(1)
>>> len(text1)
4
>>> text1[0][-1]
'\n'
>>> text2 = ''' 1. Beautiful is better than ugly.
... 3. Simple is better than complex.
... 4. Complicated is better than complex.
... 5. Flat is better than nested.
... '''.splitlines(1)

```

Next we instantiate a Differ object:

```

>>> d = Differ()

```

Note that when instantiating a Differ object we may pass functions to filter out line and character “junk.” See the Differ() constructor for details.

Finally, we compare the two:

```

>>> result = list(d.compare(text1, text2))

```

result is a list of strings, so let’s pretty-print it:

```

>>> from pprint import pprint
>>> pprint(result)
[' 1. Beautiful is better than ugly.\n',
'- 2. Explicit is better than implicit.\n',
'- 3. Simple is better than complex.\n',
'+ 3. Simple is better than complex.\n',
'? ++ \n',
'- 4. Complex is better than complicated.\n',
'? ^ ---- ^ \n',
'+ 4. Complicated is better than complex.\n',
'? ++++ ^ ^ \n',
'+ 5. Flat is better than nested.\n']

```

As a single multi-line string it looks like this:

```

>>> import sys
>>> sys.stdout.writelines(result)
1. Beautiful is better than ugly.
- 2. Explicit is better than implicit.
- 3. Simple is better than complex.
+ 3. Simple is better than complex.
?   ++
- 4. Complex is better than complicated.
?   ^           ---- ^
+ 4. Complicated is better than complex.
?   ++++ ^           ^
+ 5. Flat is better than nested.

```

4.5 StringIO — Read and write strings as files

This module implements a file-like class, `StringIO`, that reads and writes a string buffer (also known as *memory files*). See the description of file objects for operations (section 3.9).

class `StringIO`(`[buffer]`)

When a `StringIO` object is created, it can be initialized to an existing string by passing the string to the constructor. If no string is given, the `StringIO` will start empty. In both cases, the initial file position starts at zero.

The `StringIO` object can accept either Unicode or 8-bit strings, but mixing the two may take some care. If both are used, 8-bit strings that cannot be interpreted as 7-bit ASCII (that use the 8th bit) will cause a `UnicodeError` to be raised when `getvalue()` is called.

The following methods of `StringIO` objects require special mention:

`getvalue()`

Retrieve the entire contents of the “file” at any time before the `StringIO` object’s `close()` method is called. See the note above for information about mixing Unicode and 8-bit strings; such mixing can cause this method to raise `UnicodeError`.

`close()`

Free the memory buffer.

Example usage:

```

import StringIO

output = StringIO.StringIO()
output.write('First line.\n')
print >>output, 'Second line.'

# Retrieve file contents -- this will be
# 'First line.\nSecond line.\n'
contents = output.getvalue()

# Close object and discard memory buffer --
# .getvalue() will now raise an exception.
output.close()

```

4.6 cStringIO — Faster version of StringIO

The module `cStringIO` provides an interface similar to that of the `StringIO` module. Heavy use of `StringIO.StringIO` objects can be made more efficient by using the function `StringIO()` from this module instead.

Since this module provides a factory function which returns objects of built-in types, there's no way to build your own version using subclassing. Use the original `StringIO` module in that case.

Unlike the memory files implemented by the `StringIO` module, those provided by this module are not able to accept Unicode strings that cannot be encoded as plain ASCII strings.

Calling `StringIO()` with a Unicode string parameter populates the object with the buffer representation of the Unicode string, instead of encoding the string.

Another difference from the `StringIO` module is that calling `StringIO()` with a string parameter creates a read-only object. Unlike an object created without a string parameter, it does not have write methods. These objects are not generally visible. They turn up in tracebacks as `StringI` and `StringO`.

The following data objects are provided as well:

InputType

The type object of the objects created by calling `StringIO` with a string parameter.

OutputType

The type object of the objects returned by calling `StringIO` with no parameters.

There is a C API to the module as well; refer to the module source for more information.

Example usage:

```
import cStringIO

output = cStringIO.StringIO()
output.write('First line.\n')
print >>output, 'Second line.'

# Retrieve file contents -- this will be
# 'First line.\nSecond line.\n'
contents = output.getvalue()

# Close object and discard memory buffer --
# .getvalue() will now raise an exception.
output.close()
```

4.7 textwrap — Text wrapping and filling

New in version 2.3.

The `textwrap` module provides two convenience functions, `wrap()` and `fill()`, as well as `TextWrapper`, the class that does all the work, and a utility function `dedent()`. If you're just wrapping or filling one or two text strings, the convenience functions should be good enough; otherwise, you should use an instance of `TextWrapper` for efficiency.

wrap(*text*[, *width*[, ...]])

Wraps the single paragraph in *text* (a string) so every line is at most *width* characters long. Returns a list of output lines, without final newlines.

Optional keyword arguments correspond to the instance attributes of `TextWrapper`, documented below. *width*

defaults to 70.

fill (*text* [, *width* [, ...]])

Wraps the single paragraph in *text*, and returns a single string containing the wrapped paragraph. `fill()` is shorthand for

```
"\n".join(wrap(text, ...))
```

In particular, `fill()` accepts exactly the same keyword arguments as `wrap()`.

Both `wrap()` and `fill()` work by creating a `TextWrapper` instance and calling a single method on it. That instance is not reused, so for applications that wrap/fill many text strings, it will be more efficient for you to create your own `TextWrapper` object.

An additional utility function, `dedent()`, is provided to remove indentation from strings that have unwanted whitespace to the left of the text.

dedent (*text*)

Remove any common leading whitespace from every line in *text*.

This can be used to make triple-quoted strings line up with the left edge of the display, while still presenting them in the source code in indented form.

Note that tabs and spaces are both treated as whitespace, but they are not equal: the lines " hello" and "\thello" are considered to have no common leading whitespace. (This behaviour is new in Python 2.5; older versions of this module incorrectly expanded tabs before searching for common leading whitespace.)

For example:

```
def test():
    # end first line with \ to avoid the empty line!
    s = '''\
hello
    world
'''
    print repr(s)          # prints 'hello\n    world\n'
    print repr(dedent(s))  # prints 'hello\n world\n'
```

class TextWrapper (...)

The `TextWrapper` constructor accepts a number of optional keyword arguments. Each argument corresponds to one instance attribute, so for example

```
wrapper = TextWrapper(initial_indent="* ")
```

is the same as

```
wrapper = TextWrapper()
wrapper.initial_indent = "* "
```

You can re-use the same `TextWrapper` object many times, and you can change any of its options through direct assignment to instance attributes between uses.

The `TextWrapper` instance attributes (and keyword arguments to the constructor) are as follows:

width

(default: 70) The maximum length of wrapped lines. As long as there are no individual words in the input text longer than `width`, `TextWrapper` guarantees that no output line will be longer than `width` characters.

expand_tabs

(default: True) If true, then all tab characters in *text* will be expanded to spaces using the `expandtabs()` method of *text*.

replace_whitespace

(default: `True`) If true, each whitespace character (as defined by `string.whitespace`) remaining after tab expansion will be replaced by a single space. **Note:** If `expand_tabs` is false and `replace_whitespace` is true, each tab character will be replaced by a single space, which is *not* the same as tab expansion.

initial_indent

(default: `' '`) String that will be prepended to the first line of wrapped output. Counts towards the length of the first line.

subsequent_indent

(default: `' '`) String that will be prepended to all lines of wrapped output except the first. Counts towards the length of each line except the first.

fix_sentence_endings

(default: `False`) If true, `TextWrapper` attempts to detect sentence endings and ensure that sentences are always separated by exactly two spaces. This is generally desired for text in a monospaced font. However, the sentence detection algorithm is imperfect: it assumes that a sentence ending consists of a lowercase letter followed by one of `'.'`, `','`, or `'?'`, possibly followed by one of `"'"` or `'\''`, followed by a space. One problem with this algorithm is that it is unable to detect the difference between “Dr.” in

```
[...] Dr. Frankenstein's monster [...]
```

and “Spot.” in

```
[...] See Spot. See Spot run [...]
```

`fix_sentence_endings` is false by default.

Since the sentence detection algorithm relies on `string.lowercase` for the definition of “lowercase letter,” and a convention of using two spaces after a period to separate sentences on the same line, it is specific to English-language texts.

break_long_words

(default: `True`) If true, then words longer than `width` will be broken in order to ensure that no lines are longer than `width`. If it is false, long words will not be broken, and some lines may be longer than `width`. (Long words will be put on a line by themselves, in order to minimize the amount by which `width` is exceeded.)

`TextWrapper` also provides two public methods, analogous to the module-level convenience functions:

wrap (*text*)

Wraps the single paragraph in *text* (a string) so every line is at most `width` characters long. All wrapping options are taken from instance attributes of the `TextWrapper` instance. Returns a list of output lines, without final newlines.

fill (*text*)

Wraps the single paragraph in *text*, and returns a single string containing the wrapped paragraph.

4.8 codecs — Codec registry and base classes

This module defines base classes for standard Python codecs (encoders and decoders) and provides access to the internal Python codec registry which manages the codec and error handling lookup process.

It defines the following functions:

register (*search_function*)

Register a codec search function. Search functions are expected to take one argument, the encoding name in all lower case letters, and return a `CodecInfo` object having the following attributes:

- name** The name of the encoding;
- encoder** The stateless encoding function;
- decoder** The stateless decoding function;
- incrementalencoder** An incremental encoder class or factory function;
- incrementaldecoder** An incremental decoder class or factory function;
- streamwriter** A stream writer class or factory function;
- streamreader** A stream reader class or factory function.

The various functions or classes take the following arguments:

encoder and *decoder*: These must be functions or methods which have the same interface as the `encode()/decode()` methods of Codec instances (see Codec Interface). The functions/methods are expected to work in a stateless mode.

incrementalencoder and *incrementaldecoder*: These have to be factory functions providing the following interface:

```
factory(errors='strict')
```

The factory functions must return objects providing the interfaces defined by the base classes `IncrementalEncoder` and `IncrementalDecoder`, respectively. Incremental codecs can maintain state.

streamreader and *streamwriter*: These have to be factory functions providing the following interface:

```
factory(stream, errors='strict')
```

The factory functions must return objects providing the interfaces defined by the base classes `StreamWriter` and `StreamReader`, respectively. Stream codecs can maintain state.

Possible values for errors are `'strict'` (raise an exception in case of an encoding error), `'replace'` (replace malformed data with a suitable replacement marker, such as '?'), `'ignore'` (ignore malformed data and continue without further notice), `'xmlcharrefreplace'` (replace with the appropriate XML character reference (for encoding only)) and `'backslashreplace'` (replace with backslashed escape sequences (for encoding only)) as well as any other error handling name defined via `register_error()`.

In case a search function cannot find a given encoding, it should return `None`.

lookup (*encoding*)

Looks up the codec info in the Python codec registry and returns a `CodecInfo` object as defined above.

Encodings are first looked up in the registry's cache. If not found, the list of registered search functions is scanned. If no `CodecInfo` object is found, a `LookupError` is raised. Otherwise, the `CodecInfo` object is stored in the cache and returned to the caller.

To simplify access to the various codecs, the module provides these additional functions which use `lookup()` for the codec lookup:

getencoder (*encoding*)

Look up the codec for the given encoding and return its encoder function.

Raises a `LookupError` in case the encoding cannot be found.

getdecoder (*encoding*)

Look up the codec for the given encoding and return its decoder function.

Raises a `LookupError` in case the encoding cannot be found.

getincrementalencoder (*encoding*)

Look up the codec for the given encoding and return its incremental encoder class or factory function.

Raises a `LookupError` in case the encoding cannot be found or the codec doesn't support an incremental encoder. New in version 2.5.

getincrementaldecoder (*encoding*)

Look up the codec for the given encoding and return its incremental decoder class or factory function.

Raises a `LookupError` in case the encoding cannot be found or the codec doesn't support an incremental decoder. New in version 2.5.

getreader (*encoding*)

Look up the codec for the given encoding and return its `StreamReader` class or factory function.

Raises a `LookupError` in case the encoding cannot be found.

getwriter (*encoding*)

Look up the codec for the given encoding and return its `StreamWriter` class or factory function.

Raises a `LookupError` in case the encoding cannot be found.

register_error (*name*, *error_handler*)

Register the error handling function *error_handler* under the name *name*. *error_handler* will be called during encoding and decoding in case of an error, when *name* is specified as the *errors* parameter.

For encoding *error_handler* will be called with a `UnicodeEncodeError` instance, which contains information about the location of the error. The error handler must either raise this or a different exception or return a tuple with a replacement for the unencodable part of the input and a position where encoding should continue. The encoder will encode the replacement and continue encoding the original input at the specified position. Negative position values will be treated as being relative to the end of the input string. If the resulting position is out of bound an `IndexError` will be raised.

Decoding and translating works similar, except `UnicodeDecodeError` or `UnicodeTranslateError` will be passed to the handler and that the replacement from the error handler will be put into the output directly.

lookup_error (*name*)

Return the error handler previously registered under the name *name*.

Raises a `LookupError` in case the handler cannot be found.

strict_errors (*exception*)

Implements the `strict` error handling.

replace_errors (*exception*)

Implements the `replace` error handling.

ignore_errors (*exception*)

Implements the `ignore` error handling.

xmlcharrefreplace_errors_errors (*exception*)

Implements the `xmlcharrefreplace` error handling.

backslashreplace_errors_errors (*exception*)

Implements the `backslashreplace` error handling.

To simplify working with encoded files or stream, the module also defines these utility functions:

open (*filename*, *mode* [, *encoding* [, *errors* [, *buffering*]]])

Open an encoded file using the given *mode* and return a wrapped version providing transparent encoding/decoding.

Note: The wrapped version will only accept the object format defined by the codecs, i.e. Unicode objects for most built-in codecs. Output is also codec-dependent and will usually be Unicode as well.

encoding specifies the encoding which is to be used for the file.

errors may be given to define the error handling. It defaults to `'strict'` which causes a `ValueError` to be raised in case an encoding error occurs.

buffering has the same meaning as for the built-in `open()` function. It defaults to line buffered.

EncodedFile (*file*, *input*[, *output*[, *errors*]])

Return a wrapped version of file which provides transparent encoding translation.

Strings written to the wrapped file are interpreted according to the given *input* encoding and then written to the original file as strings using the *output* encoding. The intermediate encoding will usually be Unicode but depends on the specified codecs.

If *output* is not given, it defaults to *input*.

errors may be given to define the error handling. It defaults to 'strict', which causes `ValueError` to be raised in case an encoding error occurs.

iterencode (*iterable*, *encoding*[, *errors*])

Uses an incremental encoder to iteratively encode the input provided by *iterable*. This function is a generator. *errors* (as well as any other keyword argument) is passed through to the incremental encoder. New in version 2.5.

iterdecode (*iterable*, *encoding*[, *errors*])

Uses an incremental decoder to iteratively decode the input provided by *iterable*. This function is a generator. *errors* (as well as any other keyword argument) is passed through to the incremental encoder. New in version 2.5.

The module also provides the following constants which are useful for reading and writing to platform dependent files:

BOM

BOM_BE

BOM_LE

BOM_UTF8

BOM_UTF16

BOM_UTF16_BE

BOM_UTF16_LE

BOM_UTF32

BOM_UTF32_BE

BOM_UTF32_LE

These constants define various encodings of the Unicode byte order mark (BOM) used in UTF-16 and UTF-32 data streams to indicate the byte order used in the stream or file and in UTF-8 as a Unicode signature. `BOM_UTF16` is either `BOM_UTF16_BE` or `BOM_UTF16_LE` depending on the platform's native byte order, `BOM` is an alias for `BOM_UTF16`, `BOM_LE` for `BOM_UTF16_LE` and `BOM_BE` for `BOM_UTF16_BE`. The others represent the BOM in UTF-8 and UTF-32 encodings.

4.8.1 Codec Base Classes

The `codecs` module defines a set of base classes which define the interface and can also be used to easily write your own codecs for use in Python.

Each codec has to define four interfaces to make it usable as codec in Python: stateless encoder, stateless decoder, stream reader and stream writer. The stream reader and writers typically reuse the stateless encoder/decoder to implement the file protocols.

The `Codec` class defines the interface for stateless encoders/decoders.

To simplify and standardize error handling, the `encode()` and `decode()` methods may implement different error handling schemes by providing the *errors* string argument. The following string values are defined and implemented by all standard Python codecs:

Value	Meaning
'strict'	Raise <code>UnicodeError</code> (or a subclass); this is the default.
'ignore'	Ignore the character and continue with the next.
'replace'	Replace with a suitable replacement character; Python will use the official U+FFFD REPLACEMENT CHARACTER.
'xmlcharrefreplace'	Replace with the appropriate XML character reference (only for encoding).
'backslashreplace'	Replace with backslashed escape sequences (only for encoding).

The set of allowed values can be extended via `register_error`.

Codec Objects

The `Codec` class defines these methods which also define the function interfaces of the stateless encoder and decoder:

`encode` (*input* [, *errors*])

Encodes the object *input* and returns a tuple (output object, length consumed). While codecs are not restricted to use with Unicode, in a Unicode context, encoding converts a Unicode object to a plain string using a particular character set encoding (e.g., `cp1252` or `iso-8859-1`).

errors defines the error handling to apply. It defaults to 'strict' handling.

The method may not store state in the `Codec` instance. Use `StreamCodec` for codecs which have to keep state in order to make encoding/decoding efficient.

The encoder must be able to handle zero length input and return an empty object of the output object type in this situation.

`decode` (*input* [, *errors*])

Decodes the object *input* and returns a tuple (output object, length consumed). In a Unicode context, decoding converts a plain string encoded using a particular character set encoding to a Unicode object.

input must be an object which provides the `bf_getreadbuf` buffer slot. Python strings, buffer objects and memory mapped files are examples of objects providing this slot.

errors defines the error handling to apply. It defaults to 'strict' handling.

The method may not store state in the `Codec` instance. Use `StreamCodec` for codecs which have to keep state in order to make encoding/decoding efficient.

The decoder must be able to handle zero length input and return an empty object of the output object type in this situation.

The `IncrementalEncoder` and `IncrementalDecoder` classes provide the basic interface for incremental encoding and decoding. Encoding/decoding the input isn't done with one call to the stateless encoder/decoder function, but with multiple calls to the `encode/decode` method of the incremental encoder/decoder. The incremental encoder/decoder keeps track of the encoding/decoding process during method calls.

The joined output of calls to the `encode/decode` method is the same as if all the single inputs were joined into one, and this input was encoded/decoded with the stateless encoder/decoder.

IncrementalEncoder Objects

New in version 2.5.

The `IncrementalEncoder` class is used for encoding an input in multiple steps. It defines the following methods which every incremental encoder must define in order to be compatible with the Python codec registry.

`class IncrementalEncoder` ([*errors*])

Constructor for an `IncrementalEncoder` instance.

All incremental encoders must provide this constructor interface. They are free to add additional keyword arguments, but only the ones defined here are used by the Python codec registry.

The `IncrementalEncoder` may implement different error handling schemes by providing the *errors* keyword argument. These parameters are predefined:

- *'strict'* Raise `ValueError` (or a subclass); this is the default.
- *'ignore'* Ignore the character and continue with the next.
- *'replace'* Replace with a suitable replacement character
- *'xmlcharrefreplace'* Replace with the appropriate XML character reference
- *'backslashreplace'* Replace with backslashed escape sequences.

The *errors* argument will be assigned to an attribute of the same name. Assigning to this attribute makes it possible to switch between different error handling strategies during the lifetime of the `IncrementalEncoder` object.

The set of allowed values for the *errors* argument can be extended with `register_error()`.

encode (*object* [, *final*])

Encodes *object* (taking the current state of the encoder into account) and returns the resulting encoded object. If this is the last call to `encode` *final* must be true (the default is false).

reset ()

Reset the encoder to the initial state.

IncrementalDecoder Objects

The `IncrementalDecoder` class is used for decoding an input in multiple steps. It defines the following methods which every incremental decoder must define in order to be compatible with the Python codec registry.

class IncrementalDecoder ([*errors*])

Constructor for an `IncrementalDecoder` instance.

All incremental decoders must provide this constructor interface. They are free to add additional keyword arguments, but only the ones defined here are used by the Python codec registry.

The `IncrementalDecoder` may implement different error handling schemes by providing the *errors* keyword argument. These parameters are predefined:

- *'strict'* Raise `ValueError` (or a subclass); this is the default.
- *'ignore'* Ignore the character and continue with the next.
- *'replace'* Replace with a suitable replacement character.

The *errors* argument will be assigned to an attribute of the same name. Assigning to this attribute makes it possible to switch between different error handling strategies during the lifetime of the `IncrementalEncoder` object.

The set of allowed values for the *errors* argument can be extended with `register_error()`.

decode (*object* [, *final*])

Decodes *object* (taking the current state of the decoder into account) and returns the resulting decoded object. If this is the last call to `decode` *final* must be true (the default is false). If *final* is true the decoder must decode the input completely and must flush all buffers. If this isn't possible (e.g. because of incomplete byte sequences at the end of the input) it must initiate error handling just like in the stateless case (which might raise an exception).

reset ()

Reset the decoder to the initial state.

The `StreamWriter` and `StreamReader` classes provide generic working interfaces which can be used to implement new encoding submodules very easily. See `encodings.utf_8` for an example of how this is done.

StreamWriter Objects

The `StreamWriter` class is a subclass of `Codec` and defines the following methods which every stream writer must define in order to be compatible with the Python codec registry.

class `StreamWriter` (*stream* [, *errors*])

Constructor for a `StreamWriter` instance.

All stream writers must provide this constructor interface. They are free to add additional keyword arguments, but only the ones defined here are used by the Python codec registry.

stream must be a file-like object open for writing binary data.

The `StreamWriter` may implement different error handling schemes by providing the *errors* keyword argument. These parameters are predefined:

- 'strict' Raise `ValueError` (or a subclass); this is the default.
- 'ignore' Ignore the character and continue with the next.
- 'replace' Replace with a suitable replacement character
- 'xmlcharrefreplace' Replace with the appropriate XML character reference
- 'backslashreplace' Replace with backslashed escape sequences.

The *errors* argument will be assigned to an attribute of the same name. Assigning to this attribute makes it possible to switch between different error handling strategies during the lifetime of the `StreamWriter` object.

The set of allowed values for the *errors* argument can be extended with `register_error()`.

write (*object*)

Writes the object's contents encoded to the stream.

writelines (*list*)

Writes the concatenated list of strings to the stream (possibly by reusing the `write()` method).

reset ()

Flushes and resets the codec buffers used for keeping state.

Calling this method should ensure that the data on the output is put into a clean state that allows appending of new fresh data without having to rescan the whole stream to recover state.

In addition to the above methods, the `StreamWriter` must also inherit all other methods and attributes from the underlying stream.

StreamReader Objects

The `StreamReader` class is a subclass of `Codec` and defines the following methods which every stream reader must define in order to be compatible with the Python codec registry.

class `StreamReader` (*stream* [, *errors*])

Constructor for a `StreamReader` instance.

All stream readers must provide this constructor interface. They are free to add additional keyword arguments, but only the ones defined here are used by the Python codec registry.

stream must be a file-like object open for reading (binary) data.

The `StreamReader` may implement different error handling schemes by providing the *errors* keyword argument. These parameters are defined:

- 'strict' Raise `ValueError` (or a subclass); this is the default.
- 'ignore' Ignore the character and continue with the next.

- `'replace'` Replace with a suitable replacement character.

The `errors` argument will be assigned to an attribute of the same name. Assigning to this attribute makes it possible to switch between different error handling strategies during the lifetime of the `StreamReader` object.

The set of allowed values for the `errors` argument can be extended with `register_error()`.

`read` (`[size[, chars, [firstline]]]`)

Decodes data from the stream and returns the resulting object.

`chars` indicates the number of characters to read from the stream. `read()` will never return more than `chars` characters, but it might return less, if there are not enough characters available.

`size` indicates the approximate maximum number of bytes to read from the stream for decoding purposes. The decoder can modify this setting as appropriate. The default value -1 indicates to read and decode as much as possible. `size` is intended to prevent having to decode huge files in one step.

`firstline` indicates that it would be sufficient to only return the first line, if there are decoding errors on later lines.

The method should use a greedy read strategy meaning that it should read as much data as is allowed within the definition of the encoding and the given size, e.g. if optional encoding endings or state markers are available on the stream, these should be read too.

Changed in version 2.4: `chars` argument added. Changed in version 2.4.2: `firstline` argument added.

`readline` (`[size[, keepends]]`)

Read one line from the input stream and return the decoded data.

`size`, if given, is passed as `size` argument to the stream's `readline()` method.

If `keepends` is false line-endings will be stripped from the lines returned.

Changed in version 2.4: `keepends` argument added.

`readlines` (`[sizehint[, keepends]]`)

Read all lines available on the input stream and return them as a list of lines.

Line-endings are implemented using the codec's decoder method and are included in the list entries if `keepends` is true.

`sizehint`, if given, is passed as the `size` argument to the stream's `read()` method.

`reset` ()

Resets the codec buffers used for keeping state.

Note that no stream repositioning should take place. This method is primarily intended to be able to recover from decoding errors.

In addition to the above methods, the `StreamReader` must also inherit all other methods and attributes from the underlying stream.

The next two base classes are included for convenience. They are not needed by the codec registry, but may provide useful in practice.

StreamReaderWriter Objects

The `StreamReaderWriter` allows wrapping streams which work in both read and write modes.

The design is such that one can use the factory functions returned by the `lookup()` function to construct the instance.

`class StreamReaderWriter` (`stream, Reader, Writer, errors`)

Creates a `StreamReaderWriter` instance. `stream` must be a file-like object. `Reader` and `Writer` must be factory functions or classes providing the `StreamReader` and `StreamWriter` interface resp. Error handling is done in the same way as defined for the stream readers and writers.

`StreamReaderWriter` instances define the combined interfaces of `StreamReader` and `StreamWriter` classes. They inherit all other methods and attributes from the underlying stream.

StreamRecorder Objects

The `StreamRecorder` provide a frontend - backend view of encoding data which is sometimes useful when dealing with different encoding environments.

The design is such that one can use the factory functions returned by the `lookup()` function to construct the instance.

class `StreamRecorder` (*stream, encode, decode, Reader, Writer, errors*)

Creates a `StreamRecorder` instance which implements a two-way conversion: *encode* and *decode* work on the frontend (the input to `read()` and output of `write()`) while *Reader* and *Writer* work on the backend (reading and writing to the stream).

You can use these objects to do transparent direct recordings from e.g. Latin-1 to UTF-8 and back.

stream must be a file-like object.

encode, *decode* must adhere to the `Codec` interface. *Reader*, *Writer* must be factory functions or classes providing objects of the `StreamReader` and `StreamWriter` interface respectively.

encode and *decode* are needed for the frontend translation, *Reader* and *Writer* for the backend translation. The intermediate format used is determined by the two sets of codecs, e.g. the Unicode codecs will use Unicode as the intermediate encoding.

Error handling is done in the same way as defined for the stream readers and writers.

`StreamRecorder` instances define the combined interfaces of `StreamReader` and `StreamWriter` classes. They inherit all other methods and attributes from the underlying stream.

4.8.2 Encodings and Unicode

Unicode strings are stored internally as sequences of codepoints (to be precise as `Py_UNICODE` arrays). Depending on the way Python is compiled (either via `--enable-unicode=ucs2` or `--enable-unicode=ucs4`, with the former being the default) `Py_UNICODE` is either a 16-bit or 32-bit data type. Once a Unicode object is used outside of CPU and memory, CPU endianness and how these arrays are stored as bytes become an issue. Transforming a unicode object into a sequence of bytes is called encoding and recreating the unicode object from the sequence of bytes is known as decoding. There are many different methods for how this transformation can be done (these methods are also called encodings). The simplest method is to map the codepoints 0-255 to the bytes `0x0-0xff`. This means that a unicode object that contains codepoints above `U+00FF` can't be encoded with this method (which is called 'latin-1' or 'iso-8859-1'). `unicode.encode()` will raise a `UnicodeEncodeError` that looks like this: `'UnicodeEncodeError: 'latin-1' codec can't encode character u'\u1234' in position 3: ordinal not in range(256)'`.

There's another group of encodings (the so called charmap encodings) that choose a different subset of all unicode code points and how these codepoints are mapped to the bytes `0x0-0xff`. To see how this is done simply open e.g. `'encodings/cp1252.py'` (which is an encoding that is used primarily on Windows). There's a string constant with 256 characters that shows you which character is mapped to which byte value.

All of these encodings can only encode 256 of the 65536 (or 1114111) codepoints defined in unicode. A simple and straightforward way that can store each Unicode code point, is to store each codepoint as two consecutive bytes. There are two possibilities: Store the bytes in big endian or in little endian order. These two encodings are called UTF-16-BE and UTF-16-LE respectively. Their disadvantage is that if e.g. you use UTF-16-BE on a little endian machine you will always have to swap bytes on encoding and decoding. UTF-16 avoids this problem: Bytes will always be in natural endianness. When these bytes are read by a CPU with a different endianness, then bytes have to be swapped though. To be able to detect the endianness of a UTF-16 byte sequence, there's the so called BOM (the "Byte Order Mark"). This is the Unicode character `U+FEFF`. This character will be prepended to every UTF-16 byte sequence. The byte swapped version of this character (`0xFFFE`) is an illegal character that may not appear in a Unicode text. So when the first character in an UTF-16 byte sequence appears to be a `U+FFFE` the bytes have to be swapped on decoding. Unfortunately upto Unicode 4.0 the character `U+FEFF` had a second purpose as a 'ZERO WIDTH NO-BREAK SPACE': A character that has no width and doesn't allow a word to be split. It can e.g. be used

to give hints to a ligature algorithm. With Unicode 4.0 using U+FEFF as a ‘ZERO WIDTH NO-BREAK SPACE’ has been deprecated (with U+2060 (‘WORD JOINER’) assuming this role). Nevertheless Unicode software still must be able to handle U+FEFF in both roles: As a BOM it’s a device to determine the storage layout of the encoded bytes, and vanishes once the byte sequence has been decoded into a Unicode string; as a ‘ZERO WIDTH NO-BREAK SPACE’ it’s a normal character that will be decoded like any other.

There’s another encoding that is able to encoding the full range of Unicode characters: UTF-8. UTF-8 is an 8-bit encoding, which means there are no issues with byte order in UTF-8. Each byte in a UTF-8 byte sequence consists of two parts: Marker bits (the most significant bits) and payload bits. The marker bits are a sequence of zero to six 1 bits followed by a 0 bit. Unicode characters are encoded like this (with x being payload bits, which when concatenated give the Unicode character):

Range	Encoding
U-00000000 ... U-0000007F	0xxxxxxx
U-00000080 ... U-000007FF	110xxxxx 10xxxxxx
U-00000800 ... U-0000FFFF	1110xxxx 10xxxxxx 10xxxxxx
U-00010000 ... U-001FFFFF	11110xxx 10xxxxxx 10xxxxxx 10xxxxxx
U-00200000 ... U-03FFFFFF	111110xx 10xxxxxx 10xxxxxx 10xxxxxx 10xxxxxx
U-04000000 ... U-7FFFFFFF	1111110x 10xxxxxx 10xxxxxx 10xxxxxx 10xxxxxx 10xxxxxx

The least significant bit of the Unicode character is the rightmost x bit.

As UTF-8 is an 8-bit encoding no BOM is required and any U+FEFF character in the decoded Unicode string (even if it’s the first character) is treated as a ‘ZERO WIDTH NO-BREAK SPACE’.

Without external information it’s impossible to reliably determine which encoding was used for encoding a Unicode string. Each charmap encoding can decode any random byte sequence. However that’s not possible with UTF-8, as UTF-8 byte sequences have a structure that doesn’t allow arbitrary byte sequence. To increase the reliability with which a UTF-8 encoding can be detected, Microsoft invented a variant of UTF-8 (that Python 2.5 calls "utf-8-sig") for its Notepad program: Before any of the Unicode characters is written to the file, a UTF-8 encoded BOM (which looks like this as a byte sequence: 0xef, 0xbb, 0xbf) is written. As it’s rather improbable that any charmap encoded file starts with these byte values (which would e.g. map to

LATIN SMALL LETTER I WITH DIAERESIS
RIGHT-POINTING DOUBLE ANGLE QUOTATION MARK
INVERTED QUESTION MARK

in iso-8859-1), this increases the probability that a utf-8-sig encoding can be correctly guessed from the byte sequence. So here the BOM is not used to be able to determine the byte order used for generating the byte sequence, but as a signature that helps in guessing the encoding. On encoding the utf-8-sig codec will write 0xef, 0xbb, 0xbf as the first three bytes to the file. On decoding utf-8-sig will skip those three bytes if they appear as the first three bytes in the file.

4.8.3 Standard Encodings

Python comes with a number of codecs built-in, either implemented as C functions or with dictionaries as mapping tables. The following table lists the codecs by name, together with a few common aliases, and the languages for which the encoding is likely used. Neither the list of aliases nor the list of languages is meant to be exhaustive. Notice that spelling alternatives that only differ in case or use a hyphen instead of an underscore are also valid aliases.

Many of the character sets support the same languages. They vary in individual characters (e.g. whether the EURO SIGN is supported or not), and in the assignment of characters to code positions. For the European languages in particular, the following variants typically exist:

- an ISO 8859 codeset

- a Microsoft Windows code page, which is typically derived from a 8859 codeset, but replaces control characters with additional graphic characters
- an IBM EBCDIC code page
- an IBM PC code page, which is ASCII compatible

Codec	Aliases	Languages
ascii	646, us-ascii	English
big5	big5-tw, csbig5	Traditional Chinese
big5hkscs	big5-hkscs, hkscs	Traditional Chinese
cp037	IBM037, IBM039	English
cp424	EBCDIC-CP-HE, IBM424	Hebrew
cp437	437, IBM437	English
cp500	EBCDIC-CP-BE, EBCDIC-CP-CH, IBM500	Western Europe
cp737		Greek
cp775	IBM775	Baltic languages
cp850	850, IBM850	Western Europe
cp852	852, IBM852	Central and Eastern Europe
cp855	855, IBM855	Bulgarian, Byelorussian
cp856		Hebrew
cp857	857, IBM857	Turkish
cp860	860, IBM860	Portuguese
cp861	861, CP-IS, IBM861	Icelandic
cp862	862, IBM862	Hebrew
cp863	863, IBM863	Canadian
cp864	IBM864	Arabic
cp865	865, IBM865	Danish, Norwegian
cp866	866, IBM866	Russian
cp869	869, CP-GR, IBM869	Greek
cp874		Thai
cp875		Greek
cp932	932, ms932, mskanji, ms-kanji	Japanese
cp949	949, ms949, uhc	Korean
cp950	950, ms950	Traditional Chinese
cp1006		Urdu
cp1026	ibm1026	Turkish
cp1140	ibm1140	Western Europe
cp1250	windows-1250	Central and Eastern Europe
cp1251	windows-1251	Bulgarian, Byelorussian
cp1252	windows-1252	Western Europe
cp1253	windows-1253	Greek
cp1254	windows-1254	Turkish
cp1255	windows-1255	Hebrew
cp1256	windows1256	Arabic
cp1257	windows-1257	Baltic languages
cp1258	windows-1258	Vietnamese
euc_jp	eucjp, ujis, u-jis	Japanese
euc_jis_2004	jisx0213, eucjis2004	Japanese
euc_jisx0213	eucjisx0213	Japanese
euc_kr	euckr, korean, ksc5601, ks_c-5601, ks_c-5601-1987, ksx1001, ks_x-1001	Korean
gb2312	chinese, csiso58gb231280, euc-cn, euccn, eucgb2312-cn, gb2312-1980, gb2312-80, iso-ir-58	Simplified Chinese
gbk	936, cp936, ms936	Unified Chinese
gb18030	gb18030-2000	Unified Chinese

Codec	Aliases	Languages
hz	hzgb, hz-gb, hz-gb-2312	Simplified Chinese
iso2022_jp	csiso2022jp, iso2022jp, iso-2022-jp	Japanese
iso2022_jp_1	iso2022jp-1, iso-2022-jp-1	Japanese
iso2022_jp_2	iso2022jp-2, iso-2022-jp-2	Japanese, Korean,
iso2022_jp_2004	iso2022jp-2004, iso-2022-jp-2004	Japanese
iso2022_jp_3	iso2022jp-3, iso-2022-jp-3	Japanese
iso2022_jp_ext	iso2022jp-ext, iso-2022-jp-ext	Japanese
iso2022_kr	csiso2022kr, iso2022kr, iso-2022-kr	Korean
latin_1	iso-8859-1, iso8859-1, 8859, cp819, latin, latin1, L1	West Europe
iso8859_2	iso-8859-2, latin2, L2	Central and Eastern Europe
iso8859_3	iso-8859-3, latin3, L3	Esperanto, Maltese
iso8859_4	iso-8859-4, latin4, L4	Baltic languages
iso8859_5	iso-8859-5, cyrillic	Bulgarian, Byelorussian
iso8859_6	iso-8859-6, arabic	Arabic
iso8859_7	iso-8859-7, greek, greek8	Greek
iso8859_8	iso-8859-8, hebrew	Hebrew
iso8859_9	iso-8859-9, latin5, L5	Turkish
iso8859_10	iso-8859-10, latin6, L6	Nordic languages
iso8859_13	iso-8859-13	Baltic languages
iso8859_14	iso-8859-14, latin8, L8	Celtic languages
iso8859_15	iso-8859-15	Western Europe
johab	cp1361, ms1361	Korean
koi8_r		Russian
koi8_u		Ukrainian
mac_cyrillic	maccyrillic	Bulgarian, Byelorussian
mac_greek	macgreek	Greek
mac_iceland	maciceland	Icelandic
mac_latin2	maclatin2, maccentraleurope	Central and Eastern Europe
mac_roman	macroman	Western Europe
mac_turkish	macturkish	Turkish
ptcp154	csptcp154, pt154, cp154, cyrillic-asian	Kazakh
shift_jis	csshiftjis, shiftjis, sjis, s_jis	Japanese
shift_jis_2004	shiftjis2004, sjis_2004, sjis2004	Japanese
shift_jisx0213	shiftjisx0213, sjisx0213, s_jisx0213	Japanese
utf_16	U16, utf16	all languages
utf_16_be	UTF-16BE	all languages (Big Endian)
utf_16_le	UTF-16LE	all languages (Little Endian)
utf_7	U7, unicode-1-1-utf-7	all languages
utf_8	U8, UTF, utf8	all languages
utf_8_sig		all languages

A number of codecs are specific to Python, so their codec names have no meaning outside Python. Some of them don't convert from Unicode strings to byte strings, but instead use the property of the Python codecs machinery that any bijective function with one argument can be considered as an encoding.

For the codecs listed below, the result in the “encoding” direction is always a byte string. The result of the “decoding” direction is listed as operand type in the table.

Codec	Aliases	Operand type	Purpose
<code>base64_codec</code>	<code>base64</code> , <code>base-64</code>	byte string	Convert operand to MIME base64
<code>bz2_codec</code>	<code>bz2</code>	byte string	Compress the operand using bz2
<code>hex_codec</code>	<code>hex</code>	byte string	Convert operand to hexadecimal representation, v
<code>idna</code>		Unicode string	Implements RFC 3490. New in version 2.3. See
<code>mbcs</code>	<code>dbcs</code>	Unicode string	Windows only: Encode operand according to the
<code>palmos</code>		Unicode string	Encoding of PalmOS 3.5
<code>punycode</code>		Unicode string	Implements RFC 3492. New in version 2.3.
<code>quopri_codec</code>	<code>quopri</code> , <code>quoted-printable</code> , <code>quotedprintable</code>	byte string	Convert operand to MIME quoted printable
<code>raw_unicode_escape</code>		Unicode string	Produce a string that is suitable as raw Unicode l
<code>rot_13</code>	<code>rot13</code>	Unicode string	Returns the Caesar-cypher encryption of the oper
<code>string_escape</code>		byte string	Produce a string that is suitable as string literal in
<code>undefined</code>		any	Raise an exception for all conversions. Can be us
<code>unicode_escape</code>		Unicode string	Produce a string that is suitable as Unicode litera
<code>unicode_internal</code>		Unicode string	Return the internal representation of the operand
<code>uu_codec</code>	<code>uu</code>	byte string	Convert the operand using uuencode
<code>zlib_codec</code>	<code>zip</code> , <code>zlib</code>	byte string	Compress the operand using gzip

4.8.4 `encodings.idna` — Internationalized Domain Names in Applications

New in version 2.3.

This module implements RFC 3490 (Internationalized Domain Names in Applications) and RFC 3492 (Nameprep: A Stringprep Profile for Internationalized Domain Names (IDN)). It builds upon the `punycode` encoding and `stringprep`.

These RFCs together define a protocol to support non-ASCII characters in domain names. A domain name containing non-ASCII characters (such as “`www.Alliancefranaise.nu`”) is converted into an ASCII-compatible encoding (ACE, such as “`www.xn--alliancefranaise-npb.nu`”). The ACE form of the domain name is then used in all places where arbitrary characters are not allowed by the protocol, such as DNS queries, HTTP Host: fields, and so on. This conversion is carried out in the application; if possible invisible to the user: The application should transparently convert Unicode domain labels to IDNA on the wire, and convert back ACE labels to Unicode before presenting them to the user.

Python supports this conversion in several ways: The `idna` codec allows to convert between Unicode and the ACE. Furthermore, the `socket` module transparently converts Unicode host names to ACE, so that applications need not be concerned about converting host names themselves when they pass them to the `socket` module. On top of that, modules that have host names as function parameters, such as `httpplib` and `ftplib`, accept Unicode host names (`httpplib` then also transparently sends an IDNA hostname in the Host: field if it sends that field at all).

When receiving host names from the wire (such as in reverse name lookup), no automatic conversion to Unicode is performed: Applications wishing to present such host names to the user should decode them to Unicode.

The module `encodings.idna` also implements the nameprep procedure, which performs certain normalizations on host names, to achieve case-insensitivity of international domain names, and to unify similar characters. The nameprep functions can be used directly if desired.

nameprep (*label*)

Return the nameprepped version of *label*. The implementation currently assumes query strings, so `AllowUnassigned` is `true`.

ToASCII (*label*)

Convert a label to ASCII, as specified in RFC 3490. `UseSTD3ASCIIRules` is assumed to be `false`.

ToUnicode (*label*)

Convert a label to Unicode, as specified in RFC 3490.

4.8.5 `encodings.utf_8_sig` — UTF-8 codec with BOM signature

New in version 2.5.

This module implements a variant of the UTF-8 codec: On encoding a UTF-8 encoded BOM will be prepended to the UTF-8 encoded bytes. For the stateful encoder this is only done once (on the first write to the byte stream). For decoding an optional UTF-8 encoded BOM at the start of the data will be skipped.

4.9 `unicodedata` — Unicode Database

This module provides access to the Unicode Character Database which defines character properties for all Unicode characters. The data in this database is based on the ‘UnicodeData.txt’ file version 4.1.0 which is publicly available from <http://ftp.unicode.org/>.

The module uses the same names and symbols as defined by the UnicodeData File Format 4.1.0 (see <http://www.unicode.org/Public/4.1.0/ucd/UCD.html>). It defines the following functions:

lookup (*name*)

Look up character by name. If a character with the given name is found, return the corresponding Unicode character. If not found, `KeyError` is raised.

name (*unichr* [, *default*])

Returns the name assigned to the Unicode character *unichr* as a string. If no name is defined, *default* is returned, or, if not given, `ValueError` is raised.

decimal (*unichr* [, *default*])

Returns the decimal value assigned to the Unicode character *unichr* as integer. If no such value is defined, *default* is returned, or, if not given, `ValueError` is raised.

digit (*unichr* [, *default*])

Returns the digit value assigned to the Unicode character *unichr* as integer. If no such value is defined, *default* is returned, or, if not given, `ValueError` is raised.

numeric (*unichr* [, *default*])

Returns the numeric value assigned to the Unicode character *unichr* as float. If no such value is defined, *default* is returned, or, if not given, `ValueError` is raised.

category (*unichr*)

Returns the general category assigned to the Unicode character *unichr* as string.

bidirectional (*unichr*)

Returns the bidirectional category assigned to the Unicode character *unichr* as string. If no such value is defined, an empty string is returned.

combining (*unichr*)

Returns the canonical combining class assigned to the Unicode character *unichr* as integer. Returns 0 if no combining class is defined.

east_asian_width (*unichr*)

Returns the east asian width assigned to the Unicode character *unichr* as string. New in version 2.4.

mirrored (*unichr*)

Returns the mirrored property assigned to the Unicode character *unichr* as integer. Returns 1 if the character has been identified as a “mirrored” character in bidirectional text, 0 otherwise.

decomposition (*unichr*)

Returns the character decomposition mapping assigned to the Unicode character *unichr* as string. An empty string is returned in case no such mapping is defined.

normalize (*form*, *unistr*)

Return the normal form *form* for the Unicode string *unistr*. Valid values for *form* are 'NFC', 'NFKC', 'NFD', and 'NFKD'.

The Unicode standard defines various normalization forms of a Unicode string, based on the definition of canonical equivalence and compatibility equivalence. In Unicode, several characters can be expressed in various ways. For example, the character U+00C7 (LATIN CAPITAL LETTER C WITH CEDILLA) can also be expressed as the sequence U+0043 (LATIN CAPITAL LETTER C) U+0327 (COMBINING CEDILLA).

For each character, there are two normal forms: normal form C and normal form D. Normal form D (NFD) is also known as canonical decomposition, and translates each character into its decomposed form. Normal form C (NFC) first applies a canonical decomposition, then composes pre-combined characters again.

In addition to these two forms, there are two additional normal forms based on compatibility equivalence. In Unicode, certain characters are supported which normally would be unified with other characters. For example, U+2160 (ROMAN NUMERAL ONE) is really the same thing as U+0049 (LATIN CAPITAL LETTER I). However, it is supported in Unicode for compatibility with existing character sets (e.g. gb2312).

The normal form KD (NFKD) will apply the compatibility decomposition, i.e. replace all compatibility characters with their equivalents. The normal form KC (NFKC) first applies the compatibility decomposition, followed by the canonical composition.

New in version 2.3.

In addition, the module exposes the following constant:

unicdata_version

The version of the Unicode database used in this module.

New in version 2.3.

ucd_3_2_0

This is an object that has the same methods as the entire module, but uses the Unicode database version 3.2 instead, for applications that require this specific version of the Unicode database (such as IDNA).

New in version 2.5.

Examples:

```
>>> unicodedata.lookup('LEFT CURLY BRACKET')
u'{'
>>> unicodedata.name(u'/' )
'SOLIDUS'
>>> unicodedata.decimal(u'9')
9
>>> unicodedata.decimal(u'a')
Traceback (most recent call last):
  File "<stdin>", line 1, in ?
ValueError: not a decimal
>>> unicodedata.category(u'A') # 'L'etter, 'u'ppercase
'Lu'
>>> unicodedata.bidirectional(u'\u0660') # 'A'rabic, 'N'umber
'AN'
```

4.10 stringprep — Internet String Preparation

New in version 2.3.

When identifying things (such as host names) in the internet, it is often necessary to compare such identifications for “equality”. Exactly how this comparison is executed may depend on the application domain, e.g. whether it should

be case-insensitive or not. It may be also necessary to restrict the possible identifications, to allow only identifications consisting of “printable” characters.

RFC 3454 defines a procedure for “preparing” Unicode strings in internet protocols. Before passing strings onto the wire, they are processed with the preparation procedure, after which they have a certain normalized form. The RFC defines a set of tables, which can be combined into profiles. Each profile must define which tables it uses, and what other optional parts of the `stringprep` procedure are part of the profile. One example of a `stringprep` profile is `nameprep`, which is used for internationalized domain names.

The module `stringprep` only exposes the tables from RFC 3454. As these tables would be very large to represent them as dictionaries or lists, the module uses the Unicode character database internally. The module source code itself was generated using the `mkstringprep.py` utility.

As a result, these tables are exposed as functions, not as data structures. There are two kinds of tables in the RFC: sets and mappings. For a set, `stringprep` provides the “characteristic function”, i.e. a function that returns true if the parameter is part of the set. For mappings, it provides the mapping function: given the key, it returns the associated value. Below is a list of all functions available in the module.

`in_table_a1` (*code*)

Determine whether *code* is in tableA.1 (Unassigned code points in Unicode 3.2).

`in_table_b1` (*code*)

Determine whether *code* is in tableB.1 (Commonly mapped to nothing).

`map_table_b2` (*code*)

Return the mapped value for *code* according to tableB.2 (Mapping for case-folding used with NFKC).

`map_table_b3` (*code*)

Return the mapped value for *code* according to tableB.3 (Mapping for case-folding used with no normalization).

`in_table_c11` (*code*)

Determine whether *code* is in tableC.1.1 (ASCII space characters).

`in_table_c12` (*code*)

Determine whether *code* is in tableC.1.2 (Non-ASCII space characters).

`in_table_c11_c12` (*code*)

Determine whether *code* is in tableC.1 (Space characters, union of C.1.1 and C.1.2).

`in_table_c21` (*code*)

Determine whether *code* is in tableC.2.1 (ASCII control characters).

`in_table_c22` (*code*)

Determine whether *code* is in tableC.2.2 (Non-ASCII control characters).

`in_table_c21_c22` (*code*)

Determine whether *code* is in tableC.2 (Control characters, union of C.2.1 and C.2.2).

`in_table_c3` (*code*)

Determine whether *code* is in tableC.3 (Private use).

`in_table_c4` (*code*)

Determine whether *code* is in tableC.4 (Non-character code points).

`in_table_c5` (*code*)

Determine whether *code* is in tableC.5 (Surrogate codes).

`in_table_c6` (*code*)

Determine whether *code* is in tableC.6 (Inappropriate for plain text).

`in_table_c7` (*code*)

Determine whether *code* is in tableC.7 (Inappropriate for canonical representation).

`in_table_c8` (*code*)

Determine whether *code* is in tableC.8 (Change display properties or are deprecated).

in_table_c9(*code*)

Determine whether *code* is in tableC.9 (Tagging characters).

in_table_d1(*code*)

Determine whether *code* is in tableD.1 (Characters with bidirectional property “R” or “AL”).

in_table_d2(*code*)

Determine whether *code* is in tableD.2 (Characters with bidirectional property “L”).

4.11 `fpformat` — Floating point conversions

The `fpformat` module defines functions for dealing with floating point numbers representations in 100% pure Python. **Note:** This module is unneeded: everything here could be done via the `%` string interpolation operator.

The `fpformat` module defines the following functions and an exception:

fix(*x*, *digs*)

Format *x* as `[-]ddd.ddd` with *digs* digits after the point and at least one digit before. If *digs* \leq 0, the decimal point is suppressed.

x can be either a number or a string that looks like one. *digs* is an integer.

Return value is a string.

sci(*x*, *digs*)

Format *x* as `[-]d.dddE[+-]ddd` with *digs* digits after the point and exactly one digit before. If *digs* \leq 0, one digit is kept and the point is suppressed.

x can be either a real number, or a string that looks like one. *digs* is an integer.

Return value is a string.

exception NotANumber

Exception raised when a string passed to `fix()` or `sci()` as the *x* parameter does not look like a number. This is a subclass of `ValueError` when the standard exceptions are strings. The exception value is the improperly formatted string that caused the exception to be raised.

Example:

```
>>> import fpformat
>>> fpformat.fix(1.23, 1)
'1.2'
```


Data Types

The modules described in this chapter provide a variety of specialized data types such as dates and times, fixed-type arrays, heap queues, synchronized queues, and sets.

The following modules are documented in this chapter:

<code>datetime</code>	Basic date and time types.
<code>calendar</code>	Functions for working with calendars, including some emulation of the UNIX <code>cal</code> program.
<code>collections</code>	High-performance datatypes
<code>heapq</code>	Heap queue algorithm (a.k.a. priority queue).
<code>bisect</code>	Array bisection algorithms for binary searching.
<code>array</code>	Efficient arrays of uniformly typed numeric values.
<code>sets</code>	Implementation of sets of unique elements.
<code>sched</code>	General purpose event scheduler.
<code>mutex</code>	Lock and queue for mutual exclusion.
<code>Queue</code>	A synchronized queue class.
<code>weakref</code>	Support for weak references and weak dictionaries.
<code>UserDict</code>	Class wrapper for dictionary objects.
<code>UserList</code>	Class wrapper for list objects.
<code>UserString</code>	Class wrapper for string objects.
<code>types</code>	Names for built-in types.
<code>new</code>	Interface to the creation of runtime implementation objects.
<code>copy</code>	Shallow and deep copy operations.
<code>pprint</code>	Data pretty printer.
<code>repr</code>	Alternate <code>repr()</code> implementation with size limits.

5.1 `datetime` — Basic date and time types

New in version 2.3.

The `datetime` module supplies classes for manipulating dates and times in both simple and complex ways. While date and time arithmetic is supported, the focus of the implementation is on efficient member extraction for output formatting and manipulation.

There are two kinds of date and time objects: “naive” and “aware”. This distinction refers to whether the object has any notion of time zone, daylight saving time, or other kind of algorithmic or political time adjustment. Whether a naive `datetime` object represents Coordinated Universal Time (UTC), local time, or time in some other timezone is purely up to the program, just like it’s up to the program whether a particular number represents metres, miles, or mass. Naive `datetime` objects are easy to understand and to work with, at the cost of ignoring some aspects of reality.

For applications requiring more, `datetime` and `time` objects have an optional time zone information member,

`tzinfo`, that can contain an instance of a subclass of the abstract `tzinfo` class. These `tzinfo` objects capture information about the offset from UTC time, the time zone name, and whether Daylight Saving Time is in effect. Note that no concrete `tzinfo` classes are supplied by the `datetime` module. Supporting timezones at whatever level of detail is required is up to the application. The rules for time adjustment across the world are more political than rational, and there is no standard suitable for every application.

The `datetime` module exports the following constants:

MINYEAR

The smallest year number allowed in a `date` or `datetime` object. `MINYEAR` is 1.

MAXYEAR

The largest year number allowed in a `date` or `datetime` object. `MAXYEAR` is 9999.

See Also:

Module `calendar` (section 5.2):

General calendar related functions.

Module `time` (section 14.2):

Time access and conversions.

5.1.1 Available Types

class `date`

An idealized naive date, assuming the current Gregorian calendar always was, and always will be, in effect. Attributes: `year`, `month`, and `day`.

class `time`

An idealized time, independent of any particular day, assuming that every day has exactly 24*60*60 seconds (there is no notion of "leap seconds" here). Attributes: `hour`, `minute`, `second`, `microsecond`, and `tzinfo`.

class `datetime`

A combination of a date and a time. Attributes: `year`, `month`, `day`, `hour`, `minute`, `second`, `microsecond`, and `tzinfo`.

class `timedelta`

A duration expressing the difference between two `date`, `time`, or `datetime` instances to microsecond resolution.

class `tzinfo`

An abstract base class for time zone information objects. These are used by the `datetime` and `time` classes to provide a customizable notion of time adjustment (for example, to account for time zone and/or daylight saving time).

Objects of these types are immutable.

Objects of the `date` type are always naive.

An object *d* of type `time` or `datetime` may be naive or aware. *d* is aware if *d*.`tzinfo` is not `None` and *d*.`tzinfo.utcoffset(d)` does not return `None`. If *d*.`tzinfo` is `None`, or if *d*.`tzinfo` is not `None` but *d*.`tzinfo.utcoffset(d)` returns `None`, *d* is naive.

The distinction between naive and aware doesn't apply to `timedelta` objects.

Subclass relationships:

```

object
  timedelta
  tzinfo
  time
  date
  datetime

```

5.1.2 timedelta Objects

A `timedelta` object represents a duration, the difference between two dates or times.

class `timedelta` (`[days[, seconds[, microseconds[, milliseconds[, minutes[, hours[, weeks]]]]]]])`)

All arguments are optional and default to 0. Arguments may be ints, longs, or floats, and may be positive or negative.

Only *days*, *seconds* and *microseconds* are stored internally. Arguments are converted to those units:

- A millisecond is converted to 1000 microseconds.
- A minute is converted to 60 seconds.
- An hour is converted to 3600 seconds.
- A week is converted to 7 days.

and days, seconds and microseconds are then normalized so that the representation is unique, with

- $0 \leq \text{microseconds} < 1000000$
- $0 \leq \text{seconds} < 3600 \times 24$ (the number of seconds in one day)
- $-999999999 \leq \text{days} \leq 999999999$

If any argument is a float and there are fractional microseconds, the fractional microseconds left over from all arguments are combined and their sum is rounded to the nearest microsecond. If no argument is a float, the conversion and normalization processes are exact (no information is lost).

If the normalized value of days lies outside the indicated range, `OverflowError` is raised.

Note that normalization of negative values may be surprising at first. For example,

```

>>> d = timedelta(microseconds=-1)
>>> (d.days, d.seconds, d.microseconds)
(-1, 86399, 999999)

```

Class attributes are:

min

The most negative `timedelta` object, `timedelta(-999999999)`.

max

The most positive `timedelta` object, `timedelta(days=999999999, hours=23, minutes=59, seconds=59, microseconds=999999)`.

resolution

The smallest possible difference between non-equal `timedelta` objects, `timedelta(microseconds=1)`.

Note that, because of normalization, `timedelta.max > -timedelta.min`. `-timedelta.max` is not representable as a `timedelta` object.

Instance attributes (read-only):

Attribute	Value
<code>days</code>	Between -999999999 and 999999999 inclusive
<code>seconds</code>	Between 0 and 86399 inclusive
<code>microseconds</code>	Between 0 and 999999 inclusive

Supported operations:

Operation	Result
$t1 = t2 + t3$	Sum of $t2$ and $t3$. Afterwards $t1 - t2 == t3$ and $t1 - t3 == t2$ are true. (1)
$t1 = t2 - t3$	Difference of $t2$ and $t3$. Afterwards $t1 == t2 - t3$ and $t2 == t1 + t3$ are true. (1)
$t1 = t2 * i$ or $t1 = i * t2$	Delta multiplied by an integer or long. Afterwards $t1 // i == t2$ is true, provided $i \neq 0$. In general, $t1 * i == t1 * (i-1) + t1$ is true. (1)
$t1 = t2 // i$	The floor is computed and the remainder (if any) is thrown away. (3)
$+t1$	Returns a <code>timedelta</code> object with the same value. (2)
$-t1$	equivalent to <code>timedelta(-t1.days, -t1.seconds, -t1.microseconds)</code> , and to $t1 * -1$. (1)(4)
$\text{abs}(t)$	equivalent to $+t$ when $t.days \geq 0$, and to $-t$ when $t.days < 0$. (2)

Notes:

- (1) This is exact, but may overflow.
- (2) This is exact, and cannot overflow.
- (3) Division by 0 raises `ZeroDivisionError`.
- (4) `-timedelta.max` is not representable as a `timedelta` object.

In addition to the operations listed above `timedelta` objects support certain additions and subtractions with `date` and `datetime` objects (see below).

Comparisons of `timedelta` objects are supported with the `timedelta` object representing the smaller duration considered to be the smaller `timedelta`. In order to stop mixed-type comparisons from falling back to the default comparison by object address, when a `timedelta` object is compared to an object of a different type, `TypeError` is raised unless the comparison is `==` or `!=`. The latter cases return `False` or `True`, respectively.

`timedelta` objects are hashable (usable as dictionary keys), support efficient pickling, and in Boolean contexts, a `timedelta` object is considered to be true if and only if it isn't equal to `timedelta(0)`.

5.1.3 date Objects

A `date` object represents a date (year, month and day) in an idealized calendar, the current Gregorian calendar indefinitely extended in both directions. January 1 of year 1 is called day number 1, January 2 of year 1 is called day number 2, and so on. This matches the definition of the "proleptic Gregorian" calendar in Dershowitz and Reingold's book *Calendrical Calculations*, where it's the base calendar for all computations. See the book for algorithms for converting between proleptic Gregorian ordinals and many other calendar systems.

class `date` (*year, month, day*)

All arguments are required. Arguments may be ints or longs, in the following ranges:

• `MINYEAR <= year <= MAXYEAR`

- `1 <= month <= 12`
- `1 <= day <= number of days in the given month and year`

If an argument outside those ranges is given, `ValueError` is raised.

Other constructors, all class methods:

today()

Return the current local date. This is equivalent to `date.fromtimestamp(time.time())`.

fromtimestamp(timestamp)

Return the local date corresponding to the POSIX timestamp, such as is returned by `time.time()`. This may raise `ValueError`, if the timestamp is out of the range of values supported by the platform `C localtime()` function. It's common for this to be restricted to years from 1970 through 2038. Note that on non-POSIX systems that include leap seconds in their notion of a timestamp, leap seconds are ignored by `fromtimestamp()`.

fromordinal(ordinal)

Return the date corresponding to the proleptic Gregorian ordinal, where January 1 of year 1 has ordinal 1. `ValueError` is raised unless `1 <= ordinal <= date.max.toordinal()`. For any date *d*, `date.fromordinal(d.toordinal()) == d`.

Class attributes:

min

The earliest representable date, `date(MINYEAR, 1, 1)`.

max

The latest representable date, `date(MAXYEAR, 12, 31)`.

resolution

The smallest possible difference between non-equal date objects, `timedelta(days=1)`.

Instance attributes (read-only):

year

Between `MINYEAR` and `MAXYEAR` inclusive.

month

Between 1 and 12 inclusive.

day

Between 1 and the number of days in the given month of the given year.

Supported operations:

Operation	Result
<code>date2 = date1 + timedelta</code>	<code>date2</code> is <code>timedelta.days</code> days removed from <code>date1</code> . (1)
<code>date2 = date1 - timedelta</code>	Computes <code>date2</code> such that <code>date2 + timedelta == date1</code> . (2)
<code>timedelta = date1 - date2</code>	(3)
<code>date1 < date2</code>	<code>date1</code> is considered less than <code>date2</code> when <code>date1</code> precedes <code>date2</code> in time. (4)

Notes:

- (1) `date2` is moved forward in time if `timedelta.days > 0`, or backward if `timedelta.days < 0`. Afterward `date2 - date1 == timedelta.days`. `timedelta.seconds` and `timedelta.microseconds` are ignored. `OverflowError` is raised if `date2.year` would be smaller than `MINYEAR` or larger than `MAXYEAR`.
- (2) This isn't quite equivalent to `date1 + (-timedelta)`, because `-timedelta` in isolation can overflow in cases where `date1 - timedelta` does not. `timedelta.seconds` and `timedelta.microseconds` are ignored.
- (3) This is exact, and cannot overflow. `timedelta.seconds` and `timedelta.microseconds` are 0, and `date2 + timedelta == date1` after.

- (4) In other words, `date1 < date2` if and only if `date1.toordinal() < date2.toordinal()`. In order to stop comparison from falling back to the default scheme of comparing object addresses, date comparison normally raises `TypeError` if the other comparand isn't also a date object. However, `NotImplemented` is returned instead if the other comparand has a `timetuple` attribute. This hook gives other kinds of date objects a chance at implementing mixed-type comparison. If not, when a date object is compared to an object of a different type, `TypeError` is raised unless the comparison is `==` or `!=`. The latter cases return `False` or `True`, respectively.

Dates can be used as dictionary keys. In Boolean contexts, all date objects are considered to be true.

Instance methods:

replace(*year, month, day*)

Return a date with the same value, except for those members given new values by whichever keyword arguments are specified. For example, if `d == date(2002, 12, 31)`, then `d.replace(day=26) == date(2002, 12, 26)`.

timetuple()

Return a `time.struct_time` such as returned by `time.localtime()`. The hours, minutes and seconds are 0, and the DST flag is -1. `d.timetuple()` is equivalent to `time.struct_time((d.year, d.month, d.day, 0, 0, 0, d.weekday(), d.toordinal() - date(d.year, 1, 1).toordinal() + 1, -1))`

toordinal()

Return the proleptic Gregorian ordinal of the date, where January 1 of year 1 has ordinal 1. For any date object `d`, `date.fromordinal(d.toordinal()) == d`.

weekday()

Return the day of the week as an integer, where Monday is 0 and Sunday is 6. For example, `date(2002, 12, 4).weekday() == 2`, a Wednesday. See also `isoweekday()`.

isoweekday()

Return the day of the week as an integer, where Monday is 1 and Sunday is 7. For example, `date(2002, 12, 4).isoweekday() == 3`, a Wednesday. See also `weekday()`, `isocalendar()`.

isocalendar()

Return a 3-tuple, (ISO year, ISO week number, ISO weekday).

The ISO calendar is a widely used variant of the Gregorian calendar. See <http://www.phys.uu.nl/vgent/calendar/isocalendar.htm> for a good explanation.

The ISO year consists of 52 or 53 full weeks, and where a week starts on a Monday and ends on a Sunday. The first week of an ISO year is the first (Gregorian) calendar week of a year containing a Thursday. This is called week number 1, and the ISO year of that Thursday is the same as its Gregorian year.

For example, 2004 begins on a Thursday, so the first week of ISO year 2004 begins on Monday, 29 Dec 2003 and ends on Sunday, 4 Jan 2004, so that `date(2003, 12, 29).isocalendar() == (2004, 1, 1)` and `date(2004, 1, 4).isocalendar() == (2004, 1, 7)`.

isoformat()

Return a string representing the date in ISO 8601 format, 'YYYY-MM-DD'. For example, `date(2002, 12, 4).isoformat() == '2002-12-04'`.

__str__()

For a date `d`, `str(d)` is equivalent to `d.isoformat()`.

ctime()

Return a string representing the date, for example `date(2002, 12, 4).ctime() == 'Wed Dec 4 00:00:00 2002'`. `d.ctime()` is equivalent to `time.ctime(time.mktime(d.timetuple()))` on platforms where the native C `ctime()` function (which `time.ctime()` invokes, but which `date.ctime()` does not invoke) conforms to the C standard.

strftime (*format*)

Return a string representing the date, controlled by an explicit format string. Format codes referring to hours, minutes or seconds will see 0 values. See section 5.1.7 – `strftime()` behavior.

5.1.4 datetime Objects

A `datetime` object is a single object containing all the information from a `date` object and a `time` object. Like a `date` object, `datetime` assumes the current Gregorian calendar extended in both directions; like a `time` object, `datetime` assumes there are exactly 3600×24 seconds in every day.

Constructor:

class datetime (*year*, *month*, *day* [, *hour* [, *minute* [, *second* [, *microsecond* [, *tzinfo*]]]])

The year, month and day arguments are required. *tzinfo* may be `None`, or an instance of a `tzinfo` subclass. The remaining arguments may be ints or longs, in the following ranges:

- `MINYEAR <= year <= MAXYEAR`
- `1 <= month <= 12`
- `1 <= day <= number of days in the given month and year`
- `0 <= hour < 24`
- `0 <= minute < 60`
- `0 <= second < 60`
- `0 <= microsecond < 1000000`

If an argument outside those ranges is given, `ValueError` is raised.

Other constructors, all class methods:

today ()

Return the current local `datetime`, with *tzinfo* `None`. This is equivalent to `datetime.fromtimestamp(time.time())`. See also `now()`, `fromtimestamp()`.

now ([*tz*])

Return the current local date and time. If optional argument *tz* is `None` or not specified, this is like `today()`, but, if possible, supplies more precision than can be gotten from going through a `time.time()` timestamp (for example, this may be possible on platforms supplying the `C gettimeofday()` function).

Else *tz* must be an instance of a class `tzinfo` subclass, and the current date and time are converted to *tz*'s time zone. In this case the result is equivalent to `tz.fromutc(datetime.utcnow().replace(tzinfo=tz))`. See also `today()`, `utcnow()`.

utcnow ()

Return the current UTC date and time, with *tzinfo* `None`. This is like `now()`, but returns the current UTC date and time, as a naive `datetime` object. See also `now()`.

fromtimestamp (*timestamp* [, *tz*])

Return the local date and time corresponding to the POSIX timestamp, such as is returned by `time.time()`. If optional argument *tz* is `None` or not specified, the timestamp is converted to the platform's local date and time, and the returned `datetime` object is naive.

Else *tz* must be an instance of a class `tzinfo` subclass, and the timestamp is converted to *tz*'s time zone. In this case the result is equivalent to `tz.fromutc(datetime.utcfromtimestamp(timestamp).replace(tzinfo=tz))`.

`fromtimestamp()` may raise `ValueError`, if the timestamp is out of the range of values supported by the platform `C localtime()` or `gmtime()` functions. It's common for this to be restricted to years in 1970 through 2038. Note that on non-POSIX systems that include leap seconds in their notion of a timestamp, leap

seconds are ignored by `fromtimestamp()`, and then it's possible to have two timestamps differing by a second that yield identical `datetime` objects. See also `utcfromtimestamp()`.

`utcfromtimestamp(timestamp)`

Return the UTC `datetime` corresponding to the POSIX timestamp, with `tzinfo` `None`. This may raise `ValueError`, if the timestamp is out of the range of values supported by the platform `C` `gmtime()` function. It's common for this to be restricted to years in 1970 through 2038. See also `fromtimestamp()`.

`fromordinal(ordinal)`

Return the `datetime` corresponding to the proleptic Gregorian ordinal, where January 1 of year 1 has ordinal 1. `ValueError` is raised unless `1 <= ordinal <= datetime.max.toordinal()`. The hour, minute, second and microsecond of the result are all 0, and `tzinfo` is `None`.

`combine(date, time)`

Return a new `datetime` object whose date members are equal to the given date object's, and whose time and `tzinfo` members are equal to the given time object's. For any `datetime` object `d`, `d == datetime.combine(d.date(), d.timetz())`. If `date` is a `datetime` object, its time and `tzinfo` members are ignored.

`strptime(date_string, format)`

Return a `datetime` corresponding to `date_string`, parsed according to `format`. This is equivalent to `datetime(*(time.strptime(date_string, format)[0:6]))`. `ValueError` is raised if the `date_string` and `format` can't be parsed by `time.strptime()` or if it returns a value which isn't a time tuple.

New in version 2.5.

Class attributes:

`min`

The earliest representable `datetime`, `datetime(MINYEAR, 1, 1, tzinfo=None)`.

`max`

The latest representable `datetime`, `datetime(MAXYEAR, 12, 31, 23, 59, 59, 999999, tzinfo=None)`.

`resolution`

The smallest possible difference between non-equal `datetime` objects, `timedelta(microseconds=1)`.

Instance attributes (read-only):

`year`

Between `MINYEAR` and `MAXYEAR` inclusive.

`month`

Between 1 and 12 inclusive.

`day`

Between 1 and the number of days in the given month of the given year.

`hour`

In range (24).

`minute`

In range (60).

`second`

In range (60).

`microsecond`

In range (1000000).

`tzinfo`

The object passed as the `tzinfo` argument to the `datetime` constructor, or `None` if none was passed.

Supported operations:

Operation	Result
$datetime2 = datetime1 + timedelta$	(1)
$datetime2 = datetime1 - timedelta$	(2)
$timedelta = datetime1 - datetime2$	(3)
$datetime1 < datetime2$	Compares datetime to datetime. (4)

- (1) `datetime2` is a duration of `timedelta` removed from `datetime1`, moving forward in time if `timedelta.days > 0`, or backward if `timedelta.days < 0`. The result has the same `tzinfo` member as the input datetime, and `datetime2 - datetime1 == timedelta` after. `OverflowError` is raised if `datetime2.year` would be smaller than `MINYEAR` or larger than `MAXYEAR`. Note that no time zone adjustments are done even if the input is an aware object.
- (2) Computes the `datetime2` such that `datetime2 + timedelta == datetime1`. As for addition, the result has the same `tzinfo` member as the input datetime, and no time zone adjustments are done even if the input is aware. This isn't quite equivalent to `datetime1 + (-timedelta)`, because `-timedelta` in isolation can overflow in cases where `datetime1 - timedelta` does not.
- (3) Subtraction of a datetime from a datetime is defined only if both operands are naive, or if both are aware. If one is aware and the other is naive, `TypeError` is raised.

If both are naive, or both are aware and have the same `tzinfo` member, the `tzinfo` members are ignored, and the result is a `timedelta` object `t` such that `datetime2 + t == datetime1`. No time zone adjustments are done in this case.

If both are aware and have different `tzinfo` members, `a-b` acts as if `a` and `b` were first converted to naive UTC datetimes first. The result is `(a.replace(tzinfo=None) - a.utcoffset()) - (b.replace(tzinfo=None) - b.utcoffset())` except that the implementation never overflows.
- (4) `datetime1` is considered less than `datetime2` when `datetime1` precedes `datetime2` in time.

If one comparand is naive and the other is aware, `TypeError` is raised. If both comparands are aware, and have the same `tzinfo` member, the common `tzinfo` member is ignored and the base datetimes are compared. If both comparands are aware and have different `tzinfo` members, the comparands are first adjusted by subtracting their UTC offsets (obtained from `self.utcoffset()`). **Note:** In order to stop comparison from falling back to the default scheme of comparing object addresses, datetime comparison normally raises `TypeError` if the other comparand isn't also a datetime object. However, `NotImplemented` is returned instead if the other comparand has a `timetuple` attribute. This hook gives other kinds of date objects a chance at implementing mixed-type comparison. If not, when a datetime object is compared to an object of a different type, `TypeError` is raised unless the comparison is `==` or `!=`. The latter cases return `False` or `True`, respectively.

`datetime` objects can be used as dictionary keys. In Boolean contexts, all `datetime` objects are considered to be true.

Instance methods:

date()

Return date object with same year, month and day.

time()

Return time object with same hour, minute, second and microsecond. `tzinfo` is `None`. See also method `timetz()`.

timetz()

Return time object with same hour, minute, second, microsecond, and `tzinfo` members. See also method `time()`.

replace ([*year*, *month*, *day*, *hour*, *minute*, *second*, *microsecond*, *tzinfo*]]]]]]])

Return a datetime with the same members, except for those members given new values by whichever keyword arguments are specified. Note that *tzinfo*=None can be specified to create a naive datetime from an aware datetime with no conversion of date and time members.

astimezone (*tz*)

Return a datetime object with new *tzinfo* member *tz*, adjusting the date and time members so the result is the same UTC time as *self*, but in *tz*'s local time.

tz must be an instance of a *tzinfo* subclass, and its *utcoffset*() and *dst*() methods must not return None. *self* must be aware (*self*.*tzinfo* must not be None, and *self*.*utcoffset*() must not return None).

If *self*.*tzinfo* is *tz*, *self*.*astimezone*(*tz*) is equal to *self*: no adjustment of date or time members is performed. Else the result is local time in time zone *tz*, representing the same UTC time as *self*: after *astz* = *dt*.*astimezone*(*tz*), *astz* - *astz*.*utcoffset*() will usually have the same date and time members as *dt* - *dt*.*utcoffset*(). The discussion of class *tzinfo* explains the cases at Daylight Saving Time transition boundaries where this cannot be achieved (an issue only if *tz* models both standard and daylight time).

If you merely want to attach a time zone object *tz* to a datetime *dt* without adjustment of date and time members, use *dt*.*replace*(*tzinfo*=*tz*). If you merely want to remove the time zone object from an aware datetime *dt* without conversion of date and time members, use *dt*.*replace*(*tzinfo*=None).

Note that the default *tzinfo*.*fromutc*() method can be overridden in a *tzinfo* subclass to affect the result returned by *astimezone*(). Ignoring error cases, *astimezone*() acts like:

```
def astimezone(self, tz):
    if self.tzinfo is tz:
        return self
    # Convert self to UTC, and attach the new time zone object.
    utc = (self - self.utcoffset()).replace(tzinfo=tz)
    # Convert from UTC to tz's local time.
    return tz.fromutc(utc)
```

utcoffset ()

If *tzinfo* is None, returns None, else returns *self*.*tzinfo*.*utcoffset*(*self*), and raises an exception if the latter doesn't return None, or a *timedelta* object representing a whole number of minutes with magnitude less than one day.

dst ()

If *tzinfo* is None, returns None, else returns *self*.*tzinfo*.*dst*(*self*), and raises an exception if the latter doesn't return None, or a *timedelta* object representing a whole number of minutes with magnitude less than one day.

tzname ()

If *tzinfo* is None, returns None, else returns *self*.*tzinfo*.*tzname*(*self*), raises an exception if the latter doesn't return None or a string object,

timetuple ()

Return a *time.struct_time* such as returned by *time.localtime*(). *d*.*timetuple*() is equivalent to *time.struct_time*((*d*.*year*, *d*.*month*, *d*.*day*, *d*.*hour*, *d*.*minute*, *d*.*second*, *d*.*weekday*(), *d*.*toordinal*() - *date*(*d*.*year*, 1, 1).*toordinal*() + 1, *dst*)). The *tm_isdst* flag of the result is set according to the *dst*() method: *tzinfo* is None or *dst*() returns None, *tm_isdst* is set to -1; else if *dst*() returns a non-zero value, *tm_isdst* is set to 1; else *tm_isdst* is set to 0.

utctimetuple ()

If datetime instance *d* is naive, this is the same as *d*.*timetuple*() except that *tm_isdst* is forced to 0 regardless of what *d*.*dst*() returns. DST is never in effect for a UTC time.

If *d* is aware, *d* is normalized to UTC time, by subtracting *d.utcoffset()*, and a `time.struct_time` for the normalized time is returned. `tm_isdst` is forced to 0. Note that the result's `tm_year` member may be `MINYEAR-1` or `MAXYEAR+1`, if *d.year* was `MINYEAR` or `MAXYEAR` and UTC adjustment spills over a year boundary.

toordinal()

Return the proleptic Gregorian ordinal of the date. The same as `self.date().toordinal()`.

weekday()

Return the day of the week as an integer, where Monday is 0 and Sunday is 6. The same as `self.date().weekday()`. See also `isoweekday()`.

isoweekday()

Return the day of the week as an integer, where Monday is 1 and Sunday is 7. The same as `self.date().isoweekday()`. See also `weekday()`, `isocalendar()`.

isocalendar()

Return a 3-tuple, (ISO year, ISO week number, ISO weekday). The same as `self.date().isocalendar()`.

isoformat([sep])

Return a string representing the date and time in ISO 8601 format, `YYYY-MM-DDTHH:MM:SS.mmmmmm` or, if `microsecond` is 0, `YYYY-MM-DDTHH:MM:SS`

If `utcoffset()` does not return `None`, a 6-character string is appended, giving the UTC offset in (signed) hours and minutes: `YYYY-MM-DDTHH:MM:SS.mmmmmm+HH:MM` or, if `microsecond` is 0 `YYYY-MM-DDTHH:MM:SS+HH:MM`

The optional argument *sep* (default `'T'`) is a one-character separator, placed between the date and time portions of the result. For example,

```
>>> from datetime import tzinfo, timedelta, datetime
>>> class TZ(tzinfo):
...     def utcoffset(self, dt): return timedelta(minutes=-399)
...
>>> datetime(2002, 12, 25, tzinfo=TZ()).isoformat(' ')
'2002-12-25 00:00:00-06:39'
```

__str__()

For a `datetime` instance *d*, `str(d)` is equivalent to `d.isoformat(' ')`.

ctime()

Return a string representing the date and time, for example `datetime(2002, 12, 4, 20, 30, 40).ctime() == 'Wed Dec 4 20:30:40 2002'`. `d.ctime()` is equivalent to `time.ctime(time.mktime(d.timetuple()))` on platforms where the native C `ctime()` function (which `time.ctime()` invokes, but which `datetime.ctime()` does not invoke) conforms to the C standard.

strftime(format)

Return a string representing the date and time, controlled by an explicit format string. See section 5.1.7 – `strftime()` behavior.

5.1.5 time Objects

A time object represents a (local) time of day, independent of any particular day, and subject to adjustment via a `tzinfo` object.

class time(hour[, minute[, second[, microsecond[, tzinfo]]]])

All arguments are optional. *tzinfo* may be `None`, or an instance of a `tzinfo` subclass. The remaining arguments

may be ints or longs, in the following ranges:

- $0 \leq \text{hour} < 24$
- $0 \leq \text{minute} < 60$
- $0 \leq \text{second} < 60$
- $0 \leq \text{microsecond} < 1000000$.

If an argument outside those ranges is given, `ValueError` is raised. All default to 0 except `tzinfo`, which defaults to `None`.

Class attributes:

min

The earliest representable time, `time(0, 0, 0, 0)`.

max

The latest representable time, `time(23, 59, 59, 999999)`.

resolution

The smallest possible difference between non-equal time objects, `timedelta(microseconds=1)`, although note that arithmetic on time objects is not supported.

Instance attributes (read-only):

hour

In range(24).

minute

In range(60).

second

In range(60).

microsecond

In range(1000000).

tzinfo

The object passed as the `tzinfo` argument to the `time` constructor, or `None` if none was passed.

Supported operations:

- comparison of `time` to `time`, where *a* is considered less than *b* when *a* precedes *b* in time. If one comparand is naive and the other is aware, `TypeError` is raised. If both comparands are aware, and have the same `tzinfo` member, the common `tzinfo` member is ignored and the base times are compared. If both comparands are aware and have different `tzinfo` members, the comparands are first adjusted by subtracting their UTC offsets (obtained from `self.utcoffset()`). In order to stop mixed-type comparisons from falling back to the default comparison by object address, when a `time` object is compared to an object of a different type, `TypeError` is raised unless the comparison is `==` or `!=`. The latter cases return `False` or `True`, respectively.
- hash, use as dict key
- efficient pickling
- in Boolean contexts, a `time` object is considered to be true if and only if, after converting it to minutes and subtracting `utcoffset()` (or 0 if that's `None`), the result is non-zero.

Instance methods:

replace ([*hour* [, *minute* [, *second* [, *microsecond* [, *tzinfo*]]]]])

Return a time with the same value, except for those members given new values by whichever keyword arguments are specified. Note that *tzinfo*=None can be specified to create a naive time from an aware time, without conversion of the time members.

isoformat ()

Return a string representing the time in ISO 8601 format, HH:MM:SS.mmmmmm or, if *self.microsecond* is 0, HH:MM:SS. If *utcoffset* () does not return None, a 6-character string is appended, giving the UTC offset in (signed) hours and minutes: HH:MM:SS.mmmmmm+HH:MM or, if *self.microsecond* is 0, HH:MM:SS+HH:MM

__str__ ()

For a time *t*, *str* (*t*) is equivalent to *t.isoformat* ().

strftime (*format*)

Return a string representing the time, controlled by an explicit format string. See section 5.1.7 – *strftime* () behavior.

utcoffset ()

If *tzinfo* is None, returns None, else returns *self.tzinfo.utcoffset* (None), and raises an exception if the latter doesn't return None or a *timedelta* object representing a whole number of minutes with magnitude less than one day.

dst ()

If *tzinfo* is None, returns None, else returns *self.tzinfo.dst* (None), and raises an exception if the latter doesn't return None, or a *timedelta* object representing a whole number of minutes with magnitude less than one day.

tzname ()

If *tzinfo* is None, returns None, else returns *self.tzinfo.tzname* (None), or raises an exception if the latter doesn't return None or a string object.

5.1.6 tzinfo Objects

tzinfo is an abstract base class, meaning that this class should not be instantiated directly. You need to derive a concrete subclass, and (at least) supply implementations of the standard *tzinfo* methods needed by the *datetime* methods you use. The *datetime* module does not supply any concrete subclasses of *tzinfo*.

An instance of (a concrete subclass of) *tzinfo* can be passed to the constructors for *datetime* and *time* objects. The latter objects view their members as being in local time, and the *tzinfo* object supports methods revealing offset of local time from UTC, the name of the time zone, and DST offset, all relative to a date or time object passed to them.

Special requirement for pickling: A *tzinfo* subclass must have an *__init__* method that can be called with no arguments, else it can be pickled but possibly not unpickled again. This is a technical requirement that may be relaxed in the future.

A concrete subclass of *tzinfo* may need to implement the following methods. Exactly which methods are needed depends on the uses made of aware *datetime* objects. If in doubt, simply implement all of them.

utcoffset (*self*, *dt*)

Return offset of local time from UTC, in minutes east of UTC. If local time is west of UTC, this should be negative. Note that this is intended to be the total offset from UTC; for example, if a *tzinfo* object represents both time zone and DST adjustments, *utcoffset* () should return their sum. If the UTC offset isn't known, return None. Else the value returned must be a *timedelta* object specifying a whole number of minutes in the range -1439 to 1439 inclusive (1440 = 24*60; the magnitude of the offset must be less than one day). Most implementations of *utcoffset* () will probably look like one of these two:

```

return CONSTANT                # fixed-offset class
return CONSTANT + self.dst(dt) # daylight-aware class

```

If `utcoffset()` does not return `None`, `dst()` should not return `None` either.

The default implementation of `utcoffset()` raises `NotImplementedError`.

dst (*self*, *dt*)

Return the daylight saving time (DST) adjustment, in minutes east of UTC, or `None` if DST information isn't known. Return `timedelta(0)` if DST is not in effect. If DST is in effect, return the offset as a `timedelta` object (see `utcoffset()` for details). Note that DST offset, if applicable, has already been added to the UTC offset returned by `utcoffset()`, so there's no need to consult `dst()` unless you're interested in obtaining DST info separately. For example, `datetime.timetuple()` calls its `tzinfo` member's `dst()` method to determine how the `tm_isdst` flag should be set, and `tzinfo.fromutc()` calls `dst()` to account for DST changes when crossing time zones.

An instance *tz* of a `tzinfo` subclass that models both standard and daylight times must be consistent in this sense:

```
tz.utcoffset(dt) - tz.dst(dt)
```

must return the same result for every `datetime dt` with `dt.tzinfo == tz`. For sane `tzinfo` subclasses, this expression yields the time zone's "standard offset", which should not depend on the date or the time, but only on geographic location. The implementation of `datetime.astimezone()` relies on this, but cannot detect violations; it's the programmer's responsibility to ensure it. If a `tzinfo` subclass cannot guarantee this, it may be able to override the default implementation of `tzinfo.fromutc()` to work correctly with `astimezone()` regardless.

Most implementations of `dst()` will probably look like one of these two:

```

def dst(self):
    # a fixed-offset class: doesn't account for DST
    return timedelta(0)

```

or

```

def dst(self):
    # Code to set dston and dstoff to the time zone's DST
    # transition times based on the input dt.year, and expressed
    # in standard local time. Then

    if dston <= dt.replace(tzinfo=None) < dstoff:
        return timedelta(hours=1)
    else:
        return timedelta(0)

```

The default implementation of `dst()` raises `NotImplementedError`.

tzname (*self*, *dt*)

Return the time zone name corresponding to the `datetime` object *dt*, as a string. Nothing about string names is defined by the `datetime` module, and there's no requirement that it mean anything in particular. For example, "GMT", "UTC", "-500", "-5:00", "EDT", "US/Eastern", "America/New York" are all valid replies. Return `None` if a string name isn't known. Note that this is a method rather than a fixed string primarily because some `tzinfo` subclasses will wish to return different names depending on the specific value of *dt* passed, especially if the `tzinfo` class is accounting for daylight time.

The default implementation of `tzname()` raises `NotImplementedError`.

These methods are called by a `datetime` or `time` object, in response to their methods of the same names. A `datetime` object passes itself as the argument, and a `time` object passes `None` as the argument. A `tzinfo`

subclass's methods should therefore be prepared to accept a *dt* argument of `None`, or of class `datetime`.

When `None` is passed, it's up to the class designer to decide the best response. For example, returning `None` is appropriate if the class wishes to say that time objects don't participate in the `tzinfo` protocols. It may be more useful for `utcoffset(None)` to return the standard UTC offset, as there is no other convention for discovering the standard offset.

When a `datetime` object is passed in response to a `datetime` method, `dt.tzinfo` is the same object as *self*. `tzinfo` methods can rely on this, unless user code calls `tzinfo` methods directly. The intent is that the `tzinfo` methods interpret *dt* as being in local time, and not need worry about objects in other timezones.

There is one more `tzinfo` method that a subclass may wish to override:

`fromutc(self, dt)`

This is called from the default `datetime.astimezone()` implementation. When called from that, `dt.tzinfo` is *self*, and *dt*'s date and time members are to be viewed as expressing a UTC time. The purpose of `fromutc()` is to adjust the date and time members, returning an equivalent `datetime` in *self*'s local time.

Most `tzinfo` subclasses should be able to inherit the default `fromutc()` implementation without problems. It's strong enough to handle fixed-offset time zones, and time zones accounting for both standard and daylight time, and the latter even if the DST transition times differ in different years. An example of a time zone the default `fromutc()` implementation may not handle correctly in all cases is one where the standard offset (from UTC) depends on the specific date and time passed, which can happen for political reasons. The default implementations of `astimezone()` and `fromutc()` may not produce the result you want if the result is one of the hours straddling the moment the standard offset changes.

Skipping code for error cases, the default `fromutc()` implementation acts like:

```
def fromutc(self, dt):
    # raise ValueError error if dt.tzinfo is not self
    dtoff = dt.utcoffset()
    dtdst = dt.dst()
    # raise ValueError if dtoff is None or dtdst is None
    delta = dtoff - dtdst  # this is self's standard offset
    if delta:
        dt += delta  # convert to standard local time
        dtdst = dt.dst()
        # raise ValueError if dtdst is None
    if dtdst:
        return dt + dtdst
    else:
        return dt
```

Example `tzinfo` classes:

```
from datetime import tzinfo, timedelta, datetime

ZERO = timedelta(0)
HOUR = timedelta(hours=1)

# A UTC class.

class UTC(tzinfo):
    """UTC"""

    def utcoffset(self, dt):
        return ZERO
```

```

    def tzname(self, dt):
        return "UTC"

    def dst(self, dt):
        return ZERO

utc = UTC()

# A class building tzinfo objects for fixed-offset time zones.
# Note that FixedOffset(0, "UTC") is a different way to build a
# UTC tzinfo object.

class FixedOffset(tzinfo):
    """Fixed offset in minutes east from UTC."""

    def __init__(self, offset, name):
        self.__offset = timedelta(minutes = offset)
        self.__name = name

    def utcoffset(self, dt):
        return self.__offset

    def tzname(self, dt):
        return self.__name

    def dst(self, dt):
        return ZERO

# A class capturing the platform's idea of local time.

import time as _time

STDOFFSET = timedelta(seconds = -_time.timezone)
if _time.daylight:
    DSTOFFSET = timedelta(seconds = -_time.altzone)
else:
    DSTOFFSET = STDOFFSET

DSTDIFF = DSTOFFSET - STDOFFSET

class LocalTimezone(tzinfo):

    def utcoffset(self, dt):
        if self._isdst(dt):
            return DSTOFFSET
        else:
            return STDOFFSET

    def dst(self, dt):
        if self._isdst(dt):
            return DSTDIFF
        else:
            return ZERO

    def tzname(self, dt):
        return _time.tzname[self._isdst(dt)]

    def _isdst(self, dt):
        tt = (dt.year, dt.month, dt.day,
```

```

        dt.hour, dt.minute, dt.second,
        dt.weekday(), 0, -1)
    stamp = _time.mktime(tt)
    tt = _time.localtime(stamp)
    return tt.tm_isdst > 0

Local = LocalTimezone()

# A complete implementation of current DST rules for major US time zones.

def first_sunday_on_or_after(dt):
    days_to_go = 6 - dt.weekday()
    if days_to_go:
        dt += timedelta(days_to_go)
    return dt

# In the US, DST starts at 2am (standard time) on the first Sunday in April.
DSTSTART = datetime(1, 4, 1, 2)
# and ends at 2am (DST time; 1am standard time) on the last Sunday of Oct.
# which is the first Sunday on or after Oct 25.
DSTEND = datetime(1, 10, 25, 1)

class USTimeZone(tzinfo):

    def __init__(self, hours, reprname, stdname, dstname):
        self.stdoffset = timedelta(hours=hours)
        self.reprname = reprname
        self.stdname = stdname
        self.dstname = dstname

    def __repr__(self):
        return self.reprname

    def tzname(self, dt):
        if self.dst(dt):
            return self.dstname
        else:
            return self.stdname

    def utcoffset(self, dt):
        return self.stdoffset + self.dst(dt)

    def dst(self, dt):
        if dt is None or dt.tzinfo is None:
            # An exception may be sensible here, in one or both cases.
            # It depends on how you want to treat them. The default
            # fromutc() implementation (called by the default astimezone()
            # implementation) passes a datetime with dt.tzinfo is self.
            return ZERO
        assert dt.tzinfo is self

        # Find first Sunday in April & the last in October.
        start = first_sunday_on_or_after(DSTSTART.replace(year=dt.year))
        end = first_sunday_on_or_after(DSTEND.replace(year=dt.year))

        # Can't compare naive to aware objects, so strip the timezone from
        # dt first.
        if start <= dt.replace(tzinfo=None) < end:

```

```

        return HOUR
    else:
        return ZERO

    Eastern = USTimeZone(-5, "Eastern", "EST", "EDT")
    Central = USTimeZone(-6, "Central", "CST", "CDT")
    Mountain = USTimeZone(-7, "Mountain", "MST", "MDT")
    Pacific = USTimeZone(-8, "Pacific", "PST", "PDT")

```

Note that there are unavoidable subtleties twice per year in a `tzinfo` subclass accounting for both standard and daylight time, at the DST transition points. For concreteness, consider US Eastern (UTC -0500), where EDT begins the minute after 1:59 (EST) on the first Sunday in April, and ends the minute after 1:59 (EDT) on the last Sunday in October:

UTC	3:MM	4:MM	5:MM	6:MM	7:MM	8:MM
EST	22:MM	23:MM	0:MM	1:MM	2:MM	3:MM
EDT	23:MM	0:MM	1:MM	2:MM	3:MM	4:MM
start	22:MM	23:MM	0:MM	1:MM	3:MM	4:MM
end	23:MM	0:MM	1:MM	1:MM	2:MM	3:MM

When DST starts (the "start" line), the local wall clock leaps from 1:59 to 3:00. A wall time of the form 2:MM doesn't really make sense on that day, so `astimezone(Eastern)` won't deliver a result with `hour == 2` on the day DST begins. In order for `astimezone()` to make this guarantee, the `tzinfo.dst()` method must consider times in the "missing hour" (2:MM for Eastern) to be in daylight time.

When DST ends (the "end" line), there's a potentially worse problem: there's an hour that can't be spelled unambiguously in local wall time: the last hour of daylight time. In Eastern, that's times of the form 5:MM UTC on the day daylight time ends. The local wall clock leaps from 1:59 (daylight time) back to 1:00 (standard time) again. Local times of the form 1:MM are ambiguous. `astimezone()` mimics the local clock's behavior by mapping two adjacent UTC hours into the same local hour then. In the Eastern example, UTC times of the form 5:MM and 6:MM both map to 1:MM when converted to Eastern. In order for `astimezone()` to make this guarantee, the `tzinfo.dst()` method must consider times in the "repeated hour" to be in standard time. This is easily arranged, as in the example, by expressing DST switch times in the time zone's standard local time.

Applications that can't bear such ambiguities should avoid using hybrid `tzinfo` subclasses; there are no ambiguities when using UTC, or any other fixed-offset `tzinfo` subclass (such as a class representing only EST (fixed offset -5 hours), or only EDT (fixed offset -4 hours)).

5.1.7 `strftime()` Behavior

`date`, `datetime`, and `time` objects all support a `strftime(format)` method, to create a string representing the time under the control of an explicit format string. Broadly speaking, `d.strftime(fmt)` acts like the `time` module's `time.strftime(fmt, d.timetuple())` although not all objects support a `timetuple()` method.

For `time` objects, the format codes for year, month, and day should not be used, as `time` objects have no such values. If they're used anyway, 1900 is substituted for the year, and 0 for the month and day.

For `date` objects, the format codes for hours, minutes, and seconds should not be used, as `date` objects have no such values. If they're used anyway, 0 is substituted for them.

For a naive object, the `%z` and `%Z` format codes are replaced by empty strings.

For an aware object:

`%z` `utcoffset()` is transformed into a 5-character string of the form `+HHMM` or `-HHMM`, where `HH` is a 2-digit string giving the number of UTC offset hours, and `MM` is a 2-digit string giving the number of UTC offset minutes. For example, if `utcoffset()` returns `timedelta(hours=-3, minutes=-30)`, `%z` is replaced with the string `'-0330'`.

`%Z` If `tzname()` returns `None`, `%Z` is replaced by an empty string. Otherwise `%Z` is replaced by the returned value, which must be a string.

The full set of format codes supported varies across platforms, because Python calls the platform C library's `strftime()` function, and platform variations are common. The documentation for Python's `time` module lists the format codes that the C standard (1989 version) requires, and those work on all platforms with a standard C implementation. Note that the 1999 version of the C standard added additional format codes.

The exact range of years for which `strftime()` works also varies across platforms. Regardless of platform, years before 1900 cannot be used.

5.2 calendar — General calendar-related functions

This module allows you to output calendars like the UNIX `cal` program, and provides additional useful functions related to the calendar. By default, these calendars have Monday as the first day of the week, and Sunday as the last (the European convention). Use `setfirstweekday()` to set the first day of the week to Sunday (6) or to any other weekday. Parameters that specify dates are given as integers.

Most of these functions and classes rely on the `datetime` module which uses an idealized calendar, the current Gregorian calendar indefinitely extended in both directions. This matches the definition of the "proleptic Gregorian" calendar in Dershowitz and Reingold's book "Calendrical Calculations", where it's the base calendar for all computations.

class `Calendar` (`[firstweekday]`)

Creates a `Calendar` object. *firstweekday* is an integer specifying the first day of the week. 0 is Monday (the default), 6 is Sunday.

A `Calendar` object provides several methods that can be used for preparing the calendar data for formatting. This class doesn't do any formatting itself. This is the job of subclasses. New in version 2.5.

`Calendar` instances have the following methods:

iterweekdays (*weekday*)

Return an iterator for the week day numbers that will be used for one week. The first value from the iterator will be the same as the value of the `firstweekday` property.

itermonthdates (*year*, *month*)

Return an iterator for the month *month* (1-12) in the year *year*. This iterator will return all days (as `datetime.date` objects) for the month and all days before the start of the month or after the end of the month that are required to get a complete week.

itermonthdays2 (*year*, *month*)

Return an iterator for the month *month* in the year *year* similar to `itermonthdates()`. Days returned will be tuples consisting of a day number and a week day number.

itermonthdays (*year*, *month*)

Return an iterator for the month *month* in the year *year* similar to `itermonthdates()`. Days returned will simply be day numbers.

monthdatescalendar (*year*, *month*)

Return a list of the weeks in the month *month* of the year *year* as full weeks. Weeks are lists of seven `datetime.date` objects.

monthdays2calendar (*year*, *month*)

Return a list of the weeks in the month *month* of the *year* as full weeks. Weeks are lists of seven tuples of day numbers and weekday numbers.

monthdayscalendar (*year*, *month*)

Return a list of the weeks in the month *month* of the *year* as full weeks. Weeks are lists of seven day numbers.

yeardatescalendar (*year*[, *width*])

Return the data for the specified year ready for formatting. The return value is a list of month rows. Each month row contains up to *width* months (defaulting to 3). Each month contains between 4 and 6 weeks and each week contains 1–7 days. Days are `datetime.date` objects.

yeardays2calendar (*year*[, *width*])

Return the data for the specified year ready for formatting (similar to `yeardatescalendar()`). Entries in the week lists are tuples of day numbers and weekday numbers. Day numbers outside this month are zero.

yeardayscalendar (*year*[, *width*])

Return the data for the specified year ready for formatting (similar to `yeardatescalendar()`). Entries in the week lists are day numbers. Day numbers outside this month are zero.

class TextCalendar ([*firstweekday*])

This class can be used to generate plain text calendars.

New in version 2.5.

`TextCalendar` instances have the following methods:

formatmonth (*theyear*, *themoth*[, *w*[, *l*]])

Return a month's calendar in a multi-line string. If *w* is provided, it specifies the width of the date columns, which are centered. If *l* is given, it specifies the number of lines that each week will use. Depends on the first weekday as specified in the constructor or set by the `setfirstweekday()` method.

prmonth (*theyear*, *themoth*[, *w*[, *l*]])

Print a month's calendar as returned by `formatmonth()`.

formatyear (*theyear*, *themoth*[, *w*[, *l*[, *c*[, *m*]]]])

Return a *m*-column calendar for an entire year as a multi-line string. Optional parameters *w*, *l*, and *c* are for date column width, lines per week, and number of spaces between month columns, respectively. Depends on the first weekday as specified in the constructor or set by the `setfirstweekday()` method. The earliest year for which a calendar can be generated is platform-dependent.

pryear (*theyear*[, *w*[, *l*[, *c*[, *m*]]]])

Print the calendar for an entire year as returned by `formatyear()`.

class HTMLCalendar ([*firstweekday*])

This class can be used to generate HTML calendars.

New in version 2.5.

`HTMLCalendar` instances have the following methods:

formatmonth (*theyear*, *themoth*[, *withyear*])

Return a month's calendar as an HTML table. If *withyear* is true the year will be included in the header, otherwise just the month name will be used.

formatyear (*theyear*, *themoth*[, *width*])

Return a year's calendar as an HTML table. *width* (defaulting to 3) specifies the number of months per row.

formatyearpage (*theyear*, *themoth*[, *width*[, *css*[, *encoding*]]])

Return a year's calendar as a complete HTML page. *width* (defaulting to 3) specifies the number of months per row. *css* is the name for the cascading style sheet to be used. `None` can be passed if no style sheet should be used. *encoding* specifies the encoding to be used for the output (defaulting to the system default encoding).

class LocaleTextCalendar ([*firstweekday*[, *locale*]])

This subclass of `TextCalendar` can be passed a locale name in the constructor and will return month and weekday names in the specified locale. If this locale includes an encoding all strings containing month and weekday names will be returned as unicode. New in version 2.5.

class `LocaleHTMLCalendar` (`[firstweekday[, locale]]`)

This subclass of `HTMLCalendar` can be passed a locale name in the constructor and will return month and weekday names in the specified locale. If this locale includes an encoding all strings containing month and weekday names will be returned as unicode. New in version 2.5.

For simple text calendars this module provides the following functions.

setfirstweekday (`weekday`)

Sets the weekday (0 is Monday, 6 is Sunday) to start each week. The values `MONDAY`, `TUESDAY`, `WEDNESDAY`, `THURSDAY`, `FRIDAY`, `SATURDAY`, and `SUNDAY` are provided for convenience. For example, to set the first weekday to Sunday:

```
import calendar
calendar.setfirstweekday(calendar.SUNDAY)
```

New in version 2.0.

firstweekday ()

Returns the current setting for the weekday to start each week. New in version 2.0.

isleap (`year`)

Returns True if `year` is a leap year, otherwise False.

leapdays (`y1`, `y2`)

Returns the number of leap years in the range [`y1`...`y2`), where `y1` and `y2` are years. Changed in version 2.0: This function didn't work for ranges spanning a century change in Python 1.5.2.

weekday (`year`, `month`, `day`)

Returns the day of the week (0 is Monday) for `year` (1970-...), `month` (1-12), `day` (1-31).

weekheader (`n`)

Return a header containing abbreviated weekday names. `n` specifies the width in characters for one weekday.

monthrange (`year`, `month`)

Returns weekday of first day of the month and number of days in month, for the specified `year` and `month`.

monthcalendar (`year`, `month`)

Returns a matrix representing a month's calendar. Each row represents a week; days outside of the month are represented by zeros. Each week begins with Monday unless set by `setfirstweekday()`.

prmonth (`theyear`, `themoth`[, `w`[, `l`]])

Prints a month's calendar as returned by `month()`.

month (`theyear`, `themoth`[, `w`[, `l`]])

Returns a month's calendar in a multi-line string using the `formatmonth` of the `TextCalendar` class. New in version 2.0.

prcal (`year`[, `w`[, `l`[`c`]]])

Prints the calendar for an entire year as returned by `calendar()`.

calendar (`year`[, `w`[, `l`[`c`]]])

Returns a 3-column calendar for an entire year as a multi-line string using the `formatyear` of the `TextCalendar` class. New in version 2.0.

timegm (`tuple`)

An unrelated but handy function that takes a time tuple such as returned by the `gmtime()` function in the `time` module, and returns the corresponding UNIX timestamp value, assuming an epoch of 1970, and the POSIX encoding. In fact, `time.gmtime()` and `timegm()` are each others' inverse. New in version 2.0.

The `calendar` module exports the following data attributes:

day_name

An array that represents the days of the week in the current locale.

day_abbr

An array that represents the abbreviated days of the week in the current locale.

month_name

An array that represents the months of the year in the current locale. This follows normal convention of January being month number 1, so it has a length of 13 and `month_name[0]` is the empty string.

month_abbr

An array that represents the abbreviated months of the year in the current locale. This follows normal convention of January being month number 1, so it has a length of 13 and `month_abbr[0]` is the empty string.

See Also:

[Module `datetime`](#) (section 5.1):

Object-oriented interface to dates and times with similar functionality to the `time` module.

[Module `time`](#) (section 14.2):

Low-level time related functions.

5.3 collections — High-performance container datatypes

New in version 2.4.

This module implements high-performance container datatypes. Currently, there are two datatypes, `deque` and `defaultdict`. Future additions may include balanced trees and ordered dictionaries. Changed in version 2.5: Added `defaultdict`.

5.3.1 deque objects

deque (*[iterable]*)

Returns a new deque object initialized left-to-right (using `append()`) with data from *iterable*. If *iterable* is not specified, the new deque is empty.

Deques are a generalization of stacks and queues (the name is pronounced “deck” and is short for “double-ended queue”). Deques support thread-safe, memory efficient appends and pops from either side of the deque with approximately the same $O(1)$ performance in either direction.

Though `list` objects support similar operations, they are optimized for fast fixed-length operations and incur $O(n)$ memory movement costs for `pop(0)` and `insert(0, v)` operations which change both the size and position of the underlying data representation. New in version 2.4.

Deque objects support the following methods:

append (*x*)

Add *x* to the right side of the deque.

appendleft (*x*)

Add *x* to the left side of the deque.

clear ()

Remove all elements from the deque leaving it with length 0.

extend (*iterable*)

Extend the right side of the deque by appending elements from the *iterable* argument.

extendleft (*iterable*)

Extend the left side of the deque by appending elements from *iterable*. Note, the series of left appends results in reversing the order of elements in the iterable argument.

pop ()

Remove and return an element from the right side of the deque. If no elements are present, raises an `IndexError`.

popleft ()

Remove and return an element from the left side of the deque. If no elements are present, raises an `IndexError`.

remove (*value*)

Removed the first occurrence of *value*. If not found, raises a `ValueError`. New in version 2.5.

rotate (*n*)

Rotate the deque *n* steps to the right. If *n* is negative, rotate to the left. Rotating one step to the right is equivalent to: `'d.appendleft(d.pop())'`.

In addition to the above, deques support iteration, pickling, `'len(d)'`, `'reversed(d)'`, `'copy.copy(d)'`, `'copy.deepcopy(d)'`, membership testing with the `in` operator, and subscript references such as `'d[-1]'`.

Example:

```

>>> from collections import deque
>>> d = deque('ghi')           # make a new deque with three items
>>> for elem in d:             # iterate over the deque's elements
...     print elem.upper()
G
H
I

>>> d.append('j')              # add a new entry to the right side
>>> d.appendleft('f')          # add a new entry to the left side
>>> d                          # show the representation of the deque
deque(['f', 'g', 'h', 'i', 'j'])

>>> d.pop()                   # return and remove the rightmost item
'j'
>>> d.popleft()               # return and remove the leftmost item
'f'
>>> list(d)                   # list the contents of the deque
['g', 'h', 'i']
>>> d[0]                      # peek at leftmost item
'g'
>>> d[-1]                     # peek at rightmost item
'i'

>>> list(reversed(d))         # list the contents of a deque in reverse
['i', 'h', 'g']
>>> 'h' in d                  # search the deque
True
>>> d.extend('jkl')           # add multiple elements at once
>>> d
deque(['g', 'h', 'i', 'j', 'k', 'l'])
>>> d.rotate(1)                # right rotation
>>> d
deque(['l', 'g', 'h', 'i', 'j', 'k'])
>>> d.rotate(-1)              # left rotation
>>> d
deque(['g', 'h', 'i', 'j', 'k', 'l'])

>>> deque(reversed(d))         # make a new deque in reverse order
deque(['l', 'k', 'j', 'i', 'h', 'g'])
>>> d.clear()                  # empty the deque
>>> d.pop()                    # cannot pop from an empty deque
Traceback (most recent call last):
  File "<pyshell#6>", line 1, in <module>
    d.pop()
IndexError: pop from an empty deque

>>> d.extendleft('abc')        # extendleft() reverses the input order
>>> d
deque(['c', 'b', 'a'])

```

Recipes

This section shows various approaches to working with deques.

The `rotate()` method provides a way to implement deque slicing and deletion. For example, a pure python implementation of `del d[n]` relies on the `rotate()` method to position elements to be popped:

```
def delete_nth(d, n):
    d.rotate(-n)
    d.popleft()
    d.rotate(n)
```

To implement deque slicing, use a similar approach applying `rotate()` to bring a target element to the left side of the deque. Remove old entries with `popleft()`, add new entries with `extend()`, and then reverse the rotation.

With minor variations on that approach, it is easy to implement Forth style stack manipulations such as `dup`, `drop`, `swap`, `over`, `pick`, `rot`, and `roll`.

A roundrobin task server can be built from a deque using `popleft()` to select the current task and `append()` to add it back to the tasklist if the input stream is not exhausted:

```
def roundrobin(*iterables):
    pending = deque(iter(i) for i in iterables)
    while pending:
        task = pending.popleft()
        try:
            yield task.next()
        except StopIteration:
            continue
        pending.append(task)

>>> for value in roundrobin('abc', 'd', 'efgh'):
...     print value

a
d
e
b
f
c
g
h
```

Multi-pass data reduction algorithms can be succinctly expressed and efficiently coded by extracting elements with multiple calls to `popleft()`, applying the reduction function, and calling `append()` to add the result back to the queue.

For example, building a balanced binary tree of nested lists entails reducing two adjacent nodes into one by grouping them in a list:

```
def maketree(iterable):
    d = deque(iterable)
    while len(d) > 1:
        pair = [d.popleft(), d.popleft()]
        d.append(pair)
    return list(d)

>>> print maketree('abcdefgh')
[[[['a', 'b'], ['c', 'd']], [['e', 'f'], ['g', 'h']]]]
```

5.3.2 defaultdict objects

defaultdict ([*default_factory*[, ...]])

Returns a new dictionary-like object. `defaultdict` is a subclass of the builtin `dict` class. It overrides one method and adds one writable instance variable. The remaining functionality is the same as for the `dict` class and is not documented here.

The first argument provides the initial value for the `default_factory` attribute; it defaults to `None`. All remaining arguments are treated the same as if they were passed to the `dict` constructor, including keyword arguments.

New in version 2.5.

`defaultdict` objects support the following method in addition to the standard `dict` operations:

`__missing__` (*key*)

If the `default_factory` attribute is `None`, this raises an `KeyError` exception with the *key* as argument.

If `default_factory` is not `None`, it is called without arguments to provide a default value for the given *key*, this value is inserted in the dictionary for the *key*, and returned.

If calling `default_factory` raises an exception this exception is propagated unchanged.

This method is called by the `__getitem__` method of the `dict` class when the requested key is not found; whatever it returns or raises is then returned or raised by `__getitem__`.

`defaultdict` objects support the following instance variable:

`default_factory`

This attribute is used by the `__missing__` method; it is initialized from the first argument to the constructor, if present, or to `None`, if absent.

`defaultdict` Examples

Using `list` as the `default_factory`, it is easy to group a sequence of key-value pairs into a dictionary of lists:

```
>>> s = [('yellow', 1), ('blue', 2), ('yellow', 3), ('blue', 4), ('red', 1)]
>>> d = defaultdict(list)
>>> for k, v in s:
    d[k].append(v)

>>> d.items()
[('blue', [2, 4]), ('red', [1]), ('yellow', [1, 3])]
```

When each key is encountered for the first time, it is not already in the mapping; so an entry is automatically created using the `default_factory` function which returns an empty list. The `list.append()` operation then

attaches the value to the new list. When keys are encountered again, the look-up proceeds normally (returning the list for that key) and the `list.append()` operation adds another value to the list. This technique is simpler and faster than an equivalent technique using `dict.setdefault()`:

```
>>> d = {}
>>> for k, v in s:
    d.setdefault(k, []).append(v)

>>> d.items()
[('blue', [2, 4]), ('red', [1]), ('yellow', [1, 3])]
```

Setting the `default_factory` to `int` makes the `defaultdict` useful for counting (like a bag or multiset in other languages):

```
>>> s = 'mississippi'
>>> d = defaultdict(int)
>>> for k in s:
    d[k] += 1

>>> d.items()
[('i', 4), ('p', 2), ('s', 4), ('m', 1)]
```

When a letter is first encountered, it is missing from the mapping, so the `default_factory` function calls `int()` to supply a default count of zero. The increment operation then builds up the count for each letter.

The function `int()` which always returns zero is just a special case of constant functions. A faster and more flexible way to create constant functions is to use `itertools.repeat()` which can supply any constant value (not just zero):

```
>>> def constant_factory(value):
...     return itertools.repeat(value).next
>>> d = defaultdict(constant_factory('<missing>'))
>>> d.update(name='John', action='ran')
>>> '%(name)s %(action)s to %(object)s' % d
'John ran to <missing>'
```

Setting the `default_factory` to `set` makes the `defaultdict` useful for building a dictionary of sets:

```
>>> s = [('red', 1), ('blue', 2), ('red', 3), ('blue', 4), ('red', 1), ('blue', 4)]
>>> d = defaultdict(set)
>>> for k, v in s:
    d[k].add(v)

>>> d.items()
[('blue', set([2, 4])), ('red', set([1, 3]))]
```

5.4 heapq — Heap queue algorithm

New in version 2.3.

This module provides an implementation of the heap queue algorithm, also known as the priority queue algorithm.

Heaps are arrays for which $\text{heap}[k] \leq \text{heap}[2*k+1]$ and $\text{heap}[k] \leq \text{heap}[2*k+2]$ for all k , counting elements from zero. For the sake of comparison, non-existing elements are considered to be infinite. The interesting property of a heap is that $\text{heap}[0]$ is always its smallest element.

The API below differs from textbook heap algorithms in two aspects: (a) We use zero-based indexing. This makes the relationship between the index for a node and the indexes for its children slightly less obvious, but is more suitable since Python uses zero-based indexing. (b) Our pop method returns the smallest item, not the largest (called a "min heap" in textbooks; a "max heap" is more common in texts because of its suitability for in-place sorting).

These two make it possible to view the heap as a regular Python list without surprises: $\text{heap}[0]$ is the smallest item, and $\text{heap.sort}()$ maintains the heap invariant!

To create a heap, use a list initialized to `[]`, or you can transform a populated list into a heap via function `heapify()`.

The following functions are provided:

heappush (*heap*, *item*)

Push the value *item* onto the *heap*, maintaining the heap invariant.

heappop (*heap*)

Pop and return the smallest item from the *heap*, maintaining the heap invariant. If the heap is empty, `IndexError` is raised.

heapify (*x*)

Transform list *x* into a heap, in-place, in linear time.

heapreplace (*heap*, *item*)

Pop and return the smallest item from the *heap*, and also push the new *item*. The heap size doesn't change. If the heap is empty, `IndexError` is raised. This is more efficient than `heappop()` followed by `heappush()`, and can be more appropriate when using a fixed-size heap. Note that the value returned may be larger than *item*! That constrains reasonable uses of this routine unless written as part of a conditional replacement:

```
if item > heap[0]:
    item = heapreplace(heap, item)
```

Example of use:

```
>>> from heapq import heappush, heappop
>>> heap = []
>>> data = [1, 3, 5, 7, 9, 2, 4, 6, 8, 0]
>>> for item in data:
...     heappush(heap, item)
...
>>> ordered = []
>>> while heap:
...     ordered.append(heappop(heap))
...
>>> print ordered
[0, 1, 2, 3, 4, 5, 6, 7, 8, 9]
>>> data.sort()
>>> print data == ordered
True
>>>
```

The module also offers two general purpose functions based on heaps.

nlargest (*n*, *iterable*[, *key*])

Return a list with the *n* largest elements from the dataset defined by *iterable*. *key*, if provided, specifies

a function of one argument that is used to extract a comparison key from each element in the iterable: `'key=str.lower'` Equivalent to: `'sorted(iterable, key=key, reverse=True)[:n]'` New in version 2.4. Changed in version 2.5: Added the optional *key* argument.

nsmallest (*n*, *iterable*[, *key*])

Return a list with the *n* smallest elements from the dataset defined by *iterable*. *key*, if provided, specifies a function of one argument that is used to extract a comparison key from each element in the iterable: `'key=str.lower'` Equivalent to: `'sorted(iterable, key=key)[:n]'` New in version 2.4. Changed in version 2.5: Added the optional *key* argument.


Both functions perform best for smaller values of *n*. For larger values, it is more efficient to use the `sorted()` function. Also, when *n*==1, it is more efficient to use the builtin `min()` and `max()` functions.

5.4.1 Theory

(This explanation is due to Franois Pinard. The Python code for this module was contributed by Kevin O'Connor.)

Heaps are arrays for which $a[k] \leq a[2*k+1]$ and $a[k] \leq a[2*k+2]$ for all *k*, counting elements from 0. For the sake of comparison, non-existing elements are considered to be infinite. The interesting property of a heap is that $a[0]$ is always its smallest element.

The strange invariant above is meant to be an efficient memory representation for a tournament. The numbers below are *k*, not $a[k]$:



In the tree above, each cell *k* is topping $2*k+1$ and $2*k+2$. In an usual binary tournament we see in sports, each cell is the winner over the two cells it tops, and we can trace the winner down the tree to see all opponents s/he had. However, in many computer applications of such tournaments, we do not need to trace the history of a winner. To be more memory efficient, when a winner is promoted, we try to replace it by something else at a lower level, and the rule becomes that a cell and the two cells it tops contain three different items, but the top cell "wins" over the two topped cells.

If this heap invariant is protected at all time, index 0 is clearly the overall winner. The simplest algorithmic way to remove it and find the "next" winner is to move some loser (let's say cell 30 in the diagram above) into the 0 position, and then percolate this new 0 down the tree, exchanging values, until the invariant is re-established. This is clearly logarithmic on the total number of items in the tree. By iterating over all items, you get an $O(n \log n)$ sort.

A nice feature of this sort is that you can efficiently insert new items while the sort is going on, provided that the inserted items are not "better" than the last 0'th element you extracted. This is especially useful in simulation contexts, where the tree holds all incoming events, and the "win" condition means the smallest scheduled time. When an event schedule other events for execution, they are scheduled into the future, so they can easily go into the heap. So, a heap is a good structure for implementing schedulers (this is what I used for my MIDI sequencer :-).

Various structures for implementing schedulers have been extensively studied, and heaps are good for this, as they are reasonably speedy, the speed is almost constant, and the worst case is not much different than the average case. However, there are other representations which are more efficient overall, yet the worst cases might be terrible.

Heaps are also very useful in big disk sorts. You most probably all know that a big sort implies producing "runs"

(which are pre-sorted sequences, which size is usually related to the amount of CPU memory), followed by a merging passes for these runs, which merging is often very cleverly organised¹. It is very important that the initial sort produces the longest runs possible. Tournaments are a good way to that. If, using all the memory available to hold a tournament, you replace and percolate items that happen to fit the current run, you'll produce runs which are twice the size of the memory for random input, and much better for input fuzzily ordered.

Moreover, if you output the 0'th item on disk and get an input which may not fit in the current tournament (because the value "wins" over the last output value), it cannot fit in the heap, so the size of the heap decreases. The freed memory could be cleverly reused immediately for progressively building a second heap, which grows at exactly the same rate the first heap is melting. When the first heap completely vanishes, you switch heaps and start a new run. Clever and quite effective!

In a word, heaps are useful memory structures to know. I use them in a few applications, and I think it is good to keep a 'heap' module around. :-)

5.5 `bisect` — Array bisection algorithm

This module provides support for maintaining a list in sorted order without having to sort the list after each insertion. For long lists of items with expensive comparison operations, this can be an improvement over the more common approach. The module is called `bisect` because it uses a basic bisection algorithm to do its work. The source code may be most useful as a working example of the algorithm (the boundary conditions are already right!).

The following functions are provided:

`bisect_left` (*list*, *item*[, *lo*[, *hi*]])

Locate the proper insertion point for *item* in *list* to maintain sorted order. The parameters *lo* and *hi* may be used to specify a subset of the list which should be considered; by default the entire list is used. If *item* is already present in *list*, the insertion point will be before (to the left of) any existing entries. The return value is suitable for use as the first parameter to *list.insert()*. This assumes that *list* is already sorted. New in version 2.1.

`bisect_right` (*list*, *item*[, *lo*[, *hi*]])

Similar to `bisect_left()`, but returns an insertion point which comes after (to the right of) any existing entries of *item* in *list*. New in version 2.1.

`bisect` (...)

Alias for `bisect_right()`.

`insort_left` (*list*, *item*[, *lo*[, *hi*]])

Insert *item* in *list* in sorted order. This is equivalent to `list.insert(bisect.bisect_left(list, item, lo, hi), item)`. This assumes that *list* is already sorted. New in version 2.1.

`insort_right` (*list*, *item*[, *lo*[, *hi*]])

Similar to `insort_left()`, but inserting *item* in *list* after any existing entries of *item*. New in version 2.1.

`insort` (...)

Alias for `insort_right()`.

5.5.1 Examples

The `bisect()` function is generally useful for categorizing numeric data. This example uses `bisect()` to look up a letter grade for an exam total (say) based on a set of ordered numeric breakpoints: 85 and up is an 'A', 75..84 is a 'B', etc.

¹The disk balancing algorithms which are current, nowadays, are more annoying than clever, and this is a consequence of the seeking capabilities of the disks. On devices which cannot seek, like big tape drives, the story was quite different, and one had to be very clever to ensure (far in advance) that each tape movement will be the most effective possible (that is, will best participate at "progressing" the merge). Some tapes were even able to read backwards, and this was also used to avoid the rewinding time. Believe me, real good tape sorts were quite spectacular to watch! From all times, sorting has always been a Great Art! :-)


```

>>> grades = "FEDCBA"
>>> breakpoints = [30, 44, 66, 75, 85]
>>> from bisect import bisect
>>> def grade(total):
...     return grades[bisect(breakpoints, total)]
...
>>> grade(66)
'C'
>>> map(grade, [33, 99, 77, 44, 12, 88])
['E', 'A', 'B', 'D', 'F', 'A']

```

5.6 array — Efficient arrays of numeric values

This module defines an object type which can efficiently represent an array of basic values: characters, integers, floating point numbers. Arrays are sequence types and behave very much like lists, except that the type of objects stored in them is constrained. The type is specified at object creation time by using a *type code*, which is a single character. The following type codes are defined:

Type code	C Type	Python Type	Minimum size in bytes
'c'	char	character	1
'b'	signed char	int	1
'B'	unsigned char	int	1
'u'	Py_UNICODE	Unicode character	2
'h'	signed short	int	2
'H'	unsigned short	int	2
'i'	signed int	int	2
'I'	unsigned int	long	2
'l'	signed long	int	4
'L'	unsigned long	long	4
'f'	float	float	4
'd'	double	float	8

The actual representation of values is determined by the machine architecture (strictly speaking, by the C implementation). The actual size can be accessed through the `itemsize` attribute. The values stored for 'L' and 'I' items will be represented as Python long integers when retrieved, because Python's plain integer type cannot represent the full range of C's unsigned (long) integers.

The module defines the following type:

array (*typecode* [, *initializer*])

Return a new array whose items are restricted by *typecode*, and initialized from the optional *initializer* value, which must be a list, string, or iterable over elements of the appropriate type. Changed in version 2.4: Formerly, only lists or strings were accepted. If given a list or string, the initializer is passed to the new array's `fromlist()`, `fromstring()`, or `fromunicode()` method (see below) to add initial items to the array. Otherwise, the iterable initializer is passed to the `extend()` method.

ArrayType

Obsolete alias for `array`.

Array objects support the ordinary sequence operations of indexing, slicing, concatenation, and multiplication. When using slice assignment, the assigned value must be an array object with the same type code; in all other cases,

`TypeError` is raised. Array objects also implement the buffer interface, and may be used wherever buffer objects are supported.

The following data items and methods are also supported:

typecode

The typecode character used to create the array.

itemsize

The length in bytes of one array item in the internal representation.

append(*x*)

Append a new item with value *x* to the end of the array.

buffer_info()

Return a tuple (*address*, *length*) giving the current memory address and the length in elements of the buffer used to hold array's contents. The size of the memory buffer in bytes can be computed as `array.buffer_info()[1] * array.itemsize`. This is occasionally useful when working with low-level (and inherently unsafe) I/O interfaces that require memory addresses, such as certain `ioctl()` operations. The returned numbers are valid as long as the array exists and no length-changing operations are applied to it.

Note: When using array objects from code written in C or C++ (the only way to effectively make use of this information), it makes more sense to use the buffer interface supported by array objects. This method is maintained for backward compatibility and should be avoided in new code. The buffer interface is documented in the [Python/C API Reference Manual](#).

byteswap()

“Byteswap” all items of the array. This is only supported for values which are 1, 2, 4, or 8 bytes in size; for other types of values, `RuntimeError` is raised. It is useful when reading data from a file written on a machine with a different byte order.

count(*x*)

Return the number of occurrences of *x* in the array.

extend(*iterable*)

Append items from *iterable* to the end of the array. If *iterable* is another array, it must have *exactly* the same type code; if not, `TypeError` will be raised. If *iterable* is not an array, it must be iterable and its elements must be the right type to be appended to the array. Changed in version 2.4: Formerly, the argument could only be another array.

fromfile(*f*, *n*)

Read *n* items (as machine values) from the file object *f* and append them to the end of the array. If less than *n* items are available, `EOFError` is raised, but the items that were available are still inserted into the array. *f* must be a real built-in file object; something else with a `read()` method won't do.

fromlist(*list*)

Append items from the list. This is equivalent to ‘for *x* in *list*: *a*.append(*x*)’ except that if there is a type error, the array is unchanged.

fromstring(*s*)

Appends items from the string, interpreting the string as an array of machine values (as if it had been read from a file using the `fromfile()` method).

fromunicode(*s*)

Extends this array with data from the given unicode string. The array must be a type ‘u’ array; otherwise a `ValueError` is raised. Use ‘`array.fromstring(ustr.decode(enc))`’ to append Unicode data to an array of some other type.

index(*x*)

Return the smallest *i* such that *i* is the index of the first occurrence of *x* in the array.

insert(*i*, *x*)

Insert a new item with value *x* in the array before position *i*. Negative values are treated as being relative to the end of the array.

pop (*[i]*)

Removes the item with the index *i* from the array and returns it. The optional argument defaults to `-1`, so that by default the last item is removed and returned.

read (*f, n*)

Deprecated since release 1.5.1. Use the `fromfile()` method.

Read *n* items (as machine values) from the file object *f* and append them to the end of the array. If less than *n* items are available, `EOFError` is raised, but the items that were available are still inserted into the array. *f* must be a real built-in file object; something else with a `read()` method won't do.

remove (*x*)

Remove the first occurrence of *x* from the array.

reverse ()

Reverse the order of the items in the array.

tofile (*f*)

Write all items (as machine values) to the file object *f*.

tolist ()

Convert the array to an ordinary list with the same items.

tostring ()

Convert the array to an array of machine values and return the string representation (the same sequence of bytes that would be written to a file by the `tofile()` method.)

tounicode ()

Convert the array to a unicode string. The array must be a type `'u'` array; otherwise a `ValueError` is raised. Use `'array.tostring().decode(enc)'` to obtain a unicode string from an array of some other type.

write (*f*)

Deprecated since release 1.5.1. Use the `tofile()` method.

Write all items (as machine values) to the file object *f*.

When an array object is printed or converted to a string, it is represented as `array(typecode, initializer)`. The *initializer* is omitted if the array is empty, otherwise it is a string if the *typecode* is `'c'`, otherwise it is a list of numbers. The string is guaranteed to be able to be converted back to an array with the same type and value using reverse quotes (```), so long as the `array()` function has been imported using `from array import array`. Examples:

```
array('l')
array('c', 'hello world')
array('u', u'hello \textbackslash u2641')
array('l', [1, 2, 3, 4, 5])
array('d', [1.0, 2.0, 3.14])
```

See Also:

[Module struct](#) (section 4.3):

Packing and unpacking of heterogeneous binary data.

[Module xdrlib](#) (section 9.5):

Packing and unpacking of External Data Representation (XDR) data as used in some remote procedure call systems.

The Numerical Python Manual

(<http://numpy.sourceforge.net/numdoc/HTML/numdoc.htm>)

The Numeric Python extension (NumPy) defines another array type; see <http://numpy.sourceforge.net/> for further information about Numerical Python. (A PDF version of the NumPy manual is available at <http://numpy.sourceforge.net/numdoc/numdoc.pdf>).

5.7 sets — Unordered collections of unique elements

New in version 2.3.

The `sets` module provides classes for constructing and manipulating unordered collections of unique elements. Common uses include membership testing, removing duplicates from a sequence, and computing standard math operations on sets such as intersection, union, difference, and symmetric difference.

Like other collections, sets support `x in set`, `len(set)`, and `for x in set`. Being an unordered collection, sets do not record element position or order of insertion. Accordingly, sets do not support indexing, slicing, or other sequence-like behavior.

Most set applications use the `Set` class which provides every set method except for `__hash__()`. For advanced applications requiring a hash method, the `ImmutableSet` class adds a `__hash__()` method but omits methods which alter the contents of the set. Both `Set` and `ImmutableSet` derive from `BaseSet`, an abstract class useful for determining whether something is a set: `isinstance(obj, BaseSet)`.

The set classes are implemented using dictionaries. Accordingly, the requirements for set elements are the same as those for dictionary keys; namely, that the element defines both `__eq__` and `__hash__`. As a result, sets cannot contain mutable elements such as lists or dictionaries. However, they can contain immutable collections such as tuples or instances of `ImmutableSet`. For convenience in implementing sets of sets, inner sets are automatically converted to immutable form, for example, `Set([Set(['dog'])])` is transformed to `Set([ImmutableSet(['dog'])])`.

class `Set` (`[iterable]`)

Constructs a new empty `Set` object. If the optional `iterable` parameter is supplied, updates the set with elements obtained from iteration. All of the elements in `iterable` should be immutable or be transformable to an immutable using the protocol described in section 5.7.3.

class `ImmutableSet` (`[iterable]`)

Constructs a new empty `ImmutableSet` object. If the optional `iterable` parameter is supplied, updates the set with elements obtained from iteration. All of the elements in `iterable` should be immutable or be transformable to an immutable using the protocol described in section 5.7.3.

Because `ImmutableSet` objects provide a `__hash__()` method, they can be used as set elements or as dictionary keys. `ImmutableSet` objects do not have methods for adding or removing elements, so all of the elements must be known when the constructor is called.

5.7.1 Set Objects

Instances of `Set` and `ImmutableSet` both provide the following operations:

Operation	Equivalent	Result
<code>len(s)</code>		cardinality of set <i>s</i>
<code>x in s</code>		test <i>x</i> for membership in <i>s</i>
<code>x not in s</code>		test <i>x</i> for non-membership in <i>s</i>
<code>s.issubset(t)</code>	$s \leq t$	test whether every element in <i>s</i> is in <i>t</i>
<code>s.issuperset(t)</code>	$s \geq t$	test whether every element in <i>t</i> is in <i>s</i>
<code>s.union(t)</code>	$s \mid t$	new set with elements from both <i>s</i> and <i>t</i>
<code>s.intersection(t)</code>	$s \& t$	new set with elements common to <i>s</i> and <i>t</i>
<code>s.difference(t)</code>	$s - t$	new set with elements in <i>s</i> but not in <i>t</i>
<code>s.symmetric_difference(t)</code>	$s \wedge t$	new set with elements in either <i>s</i> or <i>t</i> but not both
<code>s.copy()</code>		new set with a shallow copy of <i>s</i>

Note, the non-operator versions of `union()`, `intersection()`, `difference()`, and `symmetric_difference()` will accept any iterable as an argument. In contrast, their operator based counterparts require their arguments to be sets. This precludes error-prone constructions like `Set('abc') & 'cbs'` in favor of the more readable `Set('abc').intersection('cbs')`. Changed in version 2.3.1: Formerly all arguments were required to be sets.

In addition, both `Set` and `ImmutableSet` support set to set comparisons. Two sets are equal if and only if every element of each set is contained in the other (each is a subset of the other). A set is less than another set if and only if the first set is a proper subset of the second set (is a subset, but is not equal). A set is greater than another set if and only if the first set is a proper superset of the second set (is a superset, but is not equal).

The subset and equality comparisons do not generalize to a complete ordering function. For example, any two disjoint sets are not equal and are not subsets of each other, so *all* of the following return `False`: $a < b$, $a == b$, or $a > b$. Accordingly, sets do not implement the `__cmp__` method.

Since sets only define partial ordering (subset relationships), the output of the `list.sort()` method is undefined for lists of sets.

The following table lists operations available in `ImmutableSet` but not found in `Set`:

Operation	Result
<code>hash(s)</code>	returns a hash value for <i>s</i>

The following table lists operations available in `Set` but not found in `ImmutableSet`:

Operation	Equivalent	Result
<code>s.update(t)</code>	$s \mid= t$	return set <i>s</i> with elements added from <i>t</i>
<code>s.intersection_update(t)</code>	$s \&= t$	return set <i>s</i> keeping only elements also found in <i>t</i>
<code>s.difference_update(t)</code>	$s -= t$	return set <i>s</i> after removing elements found in <i>t</i>
<code>s.symmetric_difference_update(t)</code>	$s \wedge= t$	return set <i>s</i> with elements from <i>s</i> or <i>t</i> but not both
<code>s.add(x)</code>		add element <i>x</i> to set <i>s</i>
<code>s.remove(x)</code>		remove <i>x</i> from set <i>s</i> ; raises <code>KeyError</code> if not present
<code>s.discard(x)</code>		removes <i>x</i> from set <i>s</i> if present
<code>s.pop()</code>		remove and return an arbitrary element from <i>s</i> ; raises <code>KeyError</code> if empty
<code>s.clear()</code>		remove all elements from set <i>s</i>

Note, the non-operator versions of `update()`, `intersection_update()`, `difference_update()`, and `symmetric_difference_update()` will accept any iterable as an argument. Changed in version 2.3.1: Formerly all arguments were required to be sets.

Also note, the module also includes a `union_update()` method which is an alias for `update()`. The method is included for backwards compatibility. Programmers should prefer the `update()` method because it is supported by the builtin `set()` and `frozenset()` types.

5.7.2 Example

```
>>> from sets import Set
>>> engineers = Set(['John', 'Jane', 'Jack', 'Janice'])
>>> programmers = Set(['Jack', 'Sam', 'Susan', 'Janice'])
>>> managers = Set(['Jane', 'Jack', 'Susan', 'Zack'])
>>> employees = engineers | programmers | managers           # union
>>> engineering_management = engineers & managers           # intersection
>>> fulltime_management = managers - engineers - programmers # difference
>>> engineers.add('Marvin')                                  # add element
>>> print engineers
Set(['Jane', 'Marvin', 'Janice', 'John', 'Jack'])
>>> employees.issuperset(engineers)                          # superset test
False
>>> employees.update(engineers)                              # update from another set
>>> employees.issuperset(engineers)
True
>>> for group in [engineers, programmers, managers, employees]:
...     group.discard('Susan')                               # unconditionally remove element
...     print group
...
Set(['Jane', 'Marvin', 'Janice', 'John', 'Jack'])
Set(['Janice', 'Jack', 'Sam'])
Set(['Jane', 'Zack', 'Jack'])
Set(['Jack', 'Sam', 'Jane', 'Marvin', 'Janice', 'John', 'Zack'])
```

5.7.3 Protocol for automatic conversion to immutable

Sets can only contain immutable elements. For convenience, mutable `Set` objects are automatically copied to an `ImmutableSet` before being added as a set element.

The mechanism is to always add a hashable element, or if it is not hashable, the element is checked to see if it has an `__as_immutable__()` method which returns an immutable equivalent.

Since `Set` objects have a `__as_immutable__()` method returning an instance of `ImmutableSet`, it is possible to construct sets of sets.

A similar mechanism is needed by the `__contains__()` and `remove()` methods which need to hash an element to check for membership in a set. Those methods check an element for hashability and, if not, check for a `__as_temporarily_immutable__()` method which returns the element wrapped by a class that provides temporary methods for `__hash__()`, `__eq__()`, and `__ne__()`.

The alternate mechanism spares the need to build a separate copy of the original mutable object.

`Set` objects implement the `__as_temporarily_immutable__()` method which returns the `Set` object wrapped by a new class `_TemporarilyImmutableSet`.

The two mechanisms for adding hashability are normally invisible to the user; however, a conflict can arise in a multi-threaded environment where one thread is updating a set while another has temporarily wrapped it in `_TemporarilyImmutableSet`. In other words, sets of mutable sets are not thread-safe.

5.7.4 Comparison to the built-in `set` types

The built-in `set` and `frozenset` types were designed based on lessons learned from the `sets` module. The key differences are:

- `Set` and `ImmutableSet` were renamed to `set` and `frozenset`.
- There is no equivalent to `BaseSet`. Instead, use `isinstance(x, (set, frozenset))`.
- The hash algorithm for the built-ins performs significantly better (fewer collisions) for most datasets.
- The built-in versions have more space efficient pickles.
- The built-in versions do not have a `union_update()` method. Instead, use the `update()` method which is equivalent.
- The built-in versions do not have a `__repr(sorted=True)` method. Instead, use the built-in `repr()` and `sorted()` functions: `repr(sorted(s))`.
- The built-in version does not have a protocol for automatic conversion to immutable. Many found this feature to be confusing and no one in the community reported having found real uses for it.

5.8 sched — Event scheduler

The `sched` module defines a class which implements a general purpose event scheduler:

class `scheduler` (*timefunc*, *delayfunc*)

The `scheduler` class defines a generic interface to scheduling events. It needs two functions to actually deal with the “outside world” — *timefunc* should be callable without arguments, and return a number (the “time”, in any units whatsoever). The *delayfunc* function should be callable with one argument, compatible with the output of *timefunc*, and should delay that many time units. *delayfunc* will also be called with the argument 0 after each event is run to allow other threads an opportunity to run in multi-threaded applications.

Example:

```
>>> import sched, time
>>> s=sched.scheduler(time.time, time.sleep)
>>> def print_time(): print "From print_time", time.time()
...
>>> def print_some_times():
...     print time.time()
...     s.enter(5, 1, print_time, ())
...     s.enter(10, 1, print_time, ())
...     s.run()
...     print time.time()
...
>>> print_some_times()
930343690.257
From print_time 930343695.274
From print_time 930343700.273
930343700.276
```

5.8.1 Scheduler Objects

`scheduler` instances have the following methods:

enterabs (*time*, *priority*, *action*, *argument*)

Schedule a new event. The *time* argument should be a numeric type compatible with the return value of the

timefunc function passed to the constructor. Events scheduled for the same *time* will be executed in the order of their *priority*.

Executing the event means executing *action* (**argument*) . *argument* must be a sequence holding the parameters for *action*.

Return value is an event which may be used for later cancellation of the event (see `cancel()`).

enter (*delay*, *priority*, *action*, *argument*)

Schedule an event for *delay* more time units. Other than the relative time, the other arguments, the effect and the return value are the same as those for `enterabs()`.

cancel (*event*)

Remove the event from the queue. If *event* is not an event currently in the queue, this method will raise a `RuntimeError`.

empty ()

Return true if the event queue is empty.

run ()

Run all scheduled events. This function will wait (using the `delayfunc` function passed to the constructor) for the next event, then execute it and so on until there are no more scheduled events.

Either *action* or *delayfunc* can raise an exception. In either case, the scheduler will maintain a consistent state and propagate the exception. If an exception is raised by *action*, the event will not be attempted in future calls to `run()`.

If a sequence of events takes longer to run than the time available before the next event, the scheduler will simply fall behind. No events will be dropped; the calling code is responsible for canceling events which are no longer pertinent.

5.9 mutex — Mutual exclusion support

The `mutex` module defines a class that allows mutual-exclusion via acquiring and releasing locks. It does not require (or imply) threading or multi-tasking, though it could be useful for those purposes.

The `mutex` module defines the following class:

class `mutex` ()

Create a new (unlocked) mutex.

A mutex has two pieces of state — a “locked” bit and a queue. When the mutex is not locked, the queue is empty. Otherwise, the queue contains zero or more (*function*, *argument*) pairs representing functions (or methods) waiting to acquire the lock. When the mutex is unlocked while the queue is not empty, the first queue entry is removed and its *function* (*argument*) pair called, implying it now has the lock.

Of course, no multi-threading is implied – hence the funny interface for `lock()`, where a function is called once the lock is acquired.

5.9.1 Mutex Objects

`mutex` objects have following methods:

test ()

Check whether the mutex is locked.

testandset ()

“Atomic” test-and-set, grab the lock if it is not set, and return `True`, otherwise, return `False`.

lock (*function*, *argument*)

Execute *function* (*argument*) , unless the mutex is locked. In the case it is locked, place the function and argument on the queue. See `unlock` for explanation of when *function* (*argument*) is executed in that case.

unlock ()

Unlock the mutex if queue is empty, otherwise execute the first element in the queue.

5.10 Queue — A synchronized queue class

The `Queue` module implements a multi-producer, multi-consumer FIFO queue. It is especially useful in threads programming when information must be exchanged safely between multiple threads. The `Queue` class in this module implements all the required locking semantics. It depends on the availability of thread support in Python.

The `Queue` module defines the following class and exception:

class Queue (*maxsize*)

Constructor for the class. *maxsize* is an integer that sets the upperbound limit on the number of items that can be placed in the queue. Insertion will block once this size has been reached, until queue items are consumed. If *maxsize* is less than or equal to zero, the queue size is infinite.

exception Empty

Exception raised when non-blocking `get` () (or `get_nowait` ()) is called on a `Queue` object which is empty.

exception Full

Exception raised when non-blocking `put` () (or `put_nowait` ()) is called on a `Queue` object which is full.

5.10.1 Queue Objects

Class `Queue` implements queue objects and has the methods described below. This class can be derived from in order to implement other queue organizations (e.g. `stack`) but the inheritable interface is not described here. See the source code for details. The public methods are:

qsize ()

Return the approximate size of the queue. Because of multithreading semantics, this number is not reliable.

empty ()

Return `True` if the queue is empty, `False` otherwise. Because of multithreading semantics, this is not reliable.

full ()

Return `True` if the queue is full, `False` otherwise. Because of multithreading semantics, this is not reliable.

put (*item* [, *block* [, *timeout*]])

Put *item* into the queue. If optional args *block* is true and *timeout* is `None` (the default), block if necessary until a free slot is available. If *timeout* is a positive number, it blocks at most *timeout* seconds and raises the `Full` exception if no free slot was available within that time. Otherwise (*block* is false), put an item on the queue if a free slot is immediately available, else raise the `Full` exception (*timeout* is ignored in that case).

New in version 2.3: the *timeout* parameter.

put_nowait (*item*)

Equivalent to `put` (*item*, `False`).

get ([*block* [, *timeout*]])

Remove and return an item from the queue. If optional args *block* is true and *timeout* is `None` (the default), block if necessary until an item is available. If *timeout* is a positive number, it blocks at most *timeout* seconds and raises the `Empty` exception if no item was available within that time. Otherwise (*block* is false), return an item if one is immediately available, else raise the `Empty` exception (*timeout* is ignored in that case).

New in version 2.3: the *timeout* parameter.

get_nowait()

Equivalent to `get(False)`.

Two methods are offered to support tracking whether enqueued tasks have been fully processed by daemon consumer threads.

task_done()

Indicate that a formerly enqueued task is complete. Used by queue consumer threads. For each `get()` used to fetch a task, a subsequent call to `task_done()` tells the queue that the processing on the task is complete.

If a `join()` is currently blocking, it will resume when all items have been processed (meaning that a `task_done()` call was received for every item that had been `put()` into the queue).

Raises a `ValueError` if called more times than there were items placed in the queue. New in version 2.5.

join()

Blocks until all items in the queue have been gotten and processed.

The count of unfinished tasks goes up whenever an item is added to the queue. The count goes down whenever a consumer thread calls `task_done()` to indicate that the item was retrieved and all work on it is complete. When the count of unfinished tasks drops to zero, `join()` unblocks. New in version 2.5.

Example of how to wait for enqueued tasks to be completed:

```
def worker():
    while True:
        item = q.get()
        do_work(item)
        q.task_done()

q = Queue()
for i in range(num_worker_threads):
    t = Thread(target=worker)
    t.setDaemon(True)
    t.start()

for item in source():
    q.put(item)

q.join()          # block until all tasks are done
```

5.11 weakref — Weak references

New in version 2.1.

The `weakref` module allows the Python programmer to create *weak references* to objects.

In the following, the term *referent* means the object which is referred to by a weak reference.

A weak reference to an object is not enough to keep the object alive: when the only remaining references to a referent are weak references, garbage collection is free to destroy the referent and reuse its memory for something else. A primary use for weak references is to implement caches or mappings holding large objects, where it's desired that a large object not be kept alive solely because it appears in a cache or mapping. For example, if you have a number of large binary image objects, you may wish to associate a name with each. If you used a Python dictionary to map names to images, or images to names, the image objects would remain alive just because they appeared as values or keys in the dictionaries. The `WeakKeyDictionary` and `WeakValueDictionary` classes supplied by the `weakref` module are an alternative, using weak references to construct mappings that don't keep objects alive solely because

they appear in the mapping objects. If, for example, an image object is a value in a `WeakValueDictionary`, then when the last remaining references to that image object are the weak references held by weak mappings, garbage collection can reclaim the object, and its corresponding entries in weak mappings are simply deleted.

`WeakKeyDictionary` and `WeakValueDictionary` use weak references in their implementation, setting up callback functions on the weak references that notify the weak dictionaries when a key or value has been reclaimed by garbage collection. Most programs should find that using one of these weak dictionary types is all they need – it’s not usually necessary to create your own weak references directly. The low-level machinery used by the weak dictionary implementations is exposed by the `weakref` module for the benefit of advanced uses.

Not all objects can be weakly referenced; those objects which can include class instances, functions written in Python (but not in C), methods (both bound and unbound), sets, frozensets, file objects, generators, type objects, `DBcursor` objects from the `bsddb` module, sockets, arrays, dequeues, and regular expression pattern objects. Changed in version 2.4: Added support for files, sockets, arrays, and patterns.

Several builtin types such as `list` and `dict` do not directly support weak references but can add support through subclassing:

```
class Dict(dict):
    pass

obj = Dict(red=1, green=2, blue=3)    # this object is weak referencable
```

Extension types can easily be made to support weak references; see “[Weak Reference Support](#)” in *Extending and Embedding the Python Interpreter*.

class `ref` (`object`[, `callback`])

Return a weak reference to `object`. The original object can be retrieved by calling the reference object if the referent is still alive; if the referent is no longer alive, calling the reference object will cause `None` to be returned. If `callback` is provided and not `None`, and the returned weakref object is still alive, the callback will be called when the object is about to be finalized; the weak reference object will be passed as the only parameter to the callback; the referent will no longer be available.

It is allowable for many weak references to be constructed for the same object. Callbacks registered for each weak reference will be called from the most recently registered callback to the oldest registered callback.

Exceptions raised by the callback will be noted on the standard error output, but cannot be propagated; they are handled in exactly the same way as exceptions raised from an object’s `__del__()` method.

Weak references are hashable if the `object` is hashable. They will maintain their hash value even after the `object` was deleted. If `hash()` is called the first time only after the `object` was deleted, the call will raise `TypeError`.

Weak references support tests for equality, but not ordering. If the referents are still alive, two references have the same equality relationship as their referents (regardless of the `callback`). If either referent has been deleted, the references are equal only if the reference objects are the same object.

Changed in version 2.4: This is now a subclassable type rather than a factory function; it derives from `object`.

proxy (`object`[, `callback`])

Return a proxy to `object` which uses a weak reference. This supports use of the proxy in most contexts instead of requiring the explicit dereferencing used with weak reference objects. The returned object will have a type of either `ProxyType` or `CallableProxyType`, depending on whether `object` is callable. Proxy objects are not hashable regardless of the referent; this avoids a number of problems related to their fundamentally mutable nature, and prevent their use as dictionary keys. `callback` is the same as the parameter of the same name to the `ref()` function.

getweakrefcount (`object`)

Return the number of weak references and proxies which refer to `object`.

getweakrefs (`object`)

Return a list of all weak reference and proxy objects which refer to *object*.

class WeakKeyDictionary (*[dict]*)

Mapping class that references keys weakly. Entries in the dictionary will be discarded when there is no longer a strong reference to the key. This can be used to associate additional data with an object owned by other parts of an application without adding attributes to those objects. This can be especially useful with objects that override attribute accesses.

Note: Caution: Because a `WeakKeyDictionary` is built on top of a Python dictionary, it must not change size when iterating over it. This can be difficult to ensure for a `WeakKeyDictionary` because actions performed by the program during iteration may cause items in the dictionary to vanish "by magic" (as a side effect of garbage collection).

`WeakKeyDictionary` objects have the following additional methods. These expose the internal references directly. The references are not guaranteed to be "live" at the time they are used, so the result of calling the references needs to be checked before being used. This can be used to avoid creating references that will cause the garbage collector to keep the keys around longer than needed.

iterkeyrefs ()

Return an iterator that yields the weak references to the keys. New in version 2.5.

keyrefs ()

Return a list of weak references to the keys. New in version 2.5.

class WeakValueDictionary (*[dict]*)

Mapping class that references values weakly. Entries in the dictionary will be discarded when no strong reference to the value exists any more.

Note: Caution: Because a `WeakValueDictionary` is built on top of a Python dictionary, it must not change size when iterating over it. This can be difficult to ensure for a `WeakValueDictionary` because actions performed by the program during iteration may cause items in the dictionary to vanish "by magic" (as a side effect of garbage collection).

`WeakValueDictionary` objects have the following additional methods. These method have the same issues as the `iterkeyrefs()` and `keyrefs()` methods of `WeakKeyDictionary` objects.

itervaluerefs ()

Return an iterator that yields the weak references to the values. New in version 2.5.

valuerefs ()

Return a list of weak references to the values. New in version 2.5.

ReferenceType

The type object for weak references objects.

ProxyType

The type object for proxies of objects which are not callable.

CallableProxyType

The type object for proxies of callable objects.

ProxyTypes

Sequence containing all the type objects for proxies. This can make it simpler to test if an object is a proxy without being dependent on naming both proxy types.

exception ReferenceError

Exception raised when a proxy object is used but the underlying object has been collected. This is the same as the standard `ReferenceError` exception.

See Also:

PEP 0205, "Weak References"

The proposal and rationale for this feature, including links to earlier implementations and information about

similar features in other languages.

5.11.1 Weak Reference Objects

Weak reference objects have no attributes or methods, but do allow the referent to be obtained, if it still exists, by calling it:

```
>>> import weakref
>>> class Object:
...     pass
...
>>> o = Object()
>>> r = weakref.ref(o)
>>> o2 = r()
>>> o is o2
True
```

If the referent no longer exists, calling the reference object returns `None`:

```
>>> del o, o2
>>> print r()
None
```

Testing that a weak reference object is still live should be done using the expression `ref() is not None`. Normally, application code that needs to use a reference object should follow this pattern:

```
# r is a weak reference object
o = r()
if o is None:
    # referent has been garbage collected
    print "Object has been deallocated; can't frobnicate."
else:
    print "Object is still live!"
    o.do_something_useful()
```

Using a separate test for “liveness” creates race conditions in threaded applications; another thread can cause a weak reference to become invalidated before the weak reference is called; the idiom shown above is safe in threaded applications as well as single-threaded applications.

Specialized versions of `ref` objects can be created through subclassing. This is used in the implementation of the `WeakValueDictionary` to reduce the memory overhead for each entry in the mapping. This may be most useful to associate additional information with a reference, but could also be used to insert additional processing on calls to retrieve the referent.

This example shows how a subclass of `ref` can be used to store additional information about an object and affect the value that’s returned when the referent is accessed:

```

import weakref

class ExtendedRef(weakref.ref):
    def __init__(self, ob, callback=None, **annotations):
        super(ExtendedRef, self).__init__(ob, callback)
        self.__counter = 0
        for k, v in annotations.iteritems():
            setattr(self, k, v)

    def __call__(self):
        """Return a pair containing the referent and the number of
        times the reference has been called.
        """
        ob = super(ExtendedRef, self).__call__()
        if ob is not None:
            self.__counter += 1
            ob = (ob, self.__counter)
        return ob

```

5.11.2 Example

This simple example shows how an application can use objects IDs to retrieve objects that it has seen before. The IDs of the objects can then be used in other data structures without forcing the objects to remain alive, but the objects can still be retrieved by ID if they do.

```

import weakref

_id2obj_dict = weakref.WeakValueDictionary()

def remember(obj):
    oid = id(obj)
    _id2obj_dict[oid] = obj
    return oid

def id2obj(oid):
    return _id2obj_dict[oid]

```

5.12 UserDict — Class wrapper for dictionary objects

The module defines a mixin, `DictMixin`, defining all dictionary methods for classes that already have a minimum mapping interface. This greatly simplifies writing classes that need to be substitutable for dictionaries (such as the `shelve` module).

This also module defines a class, `UserDict`, that acts as a wrapper around dictionary objects. The need for this class has been largely supplanted by the ability to subclass directly from `dict` (a feature that became available starting with Python version 2.2). Prior to the introduction of `dict`, the `UserDict` class was used to create dictionary-like sub-classes that obtained new behaviors by overriding existing methods or adding new ones.

The `UserDict` module defines the `UserDict` class and `DictMixin`:

```
class UserDict ([initialdata])
```

Class that simulates a dictionary. The instance's contents are kept in a regular dictionary, which is accessible via the `data` attribute of `UserDict` instances. If *initialdata* is provided, `data` is initialized with its contents; note that a reference to *initialdata* will not be kept, allowing it be used for other purposes. **Note:** For backward compatibility, instances of `UserDict` are not iterable.

class `IterableUserDict` (*[initialdata]*)

Subclass of `UserDict` that supports direct iteration (e.g. `for key in myDict`).

In addition to supporting the methods and operations of mappings (see section 3.8), `UserDict` and `IterableUserDict` instances provide the following attribute:

data

A real dictionary used to store the contents of the `UserDict` class.

class `DictMixin` ()

Mixin defining all dictionary methods for classes that already have a minimum dictionary interface including `__getitem__()`, `__setitem__()`, `__delitem__()`, and `keys()`.

This mixin should be used as a superclass. Adding each of the above methods adds progressively more functionality. For instance, defining all but `__delitem__` will preclude only `pop` and `popitem` from the full interface.

In addition to the four base methods, progressively more efficiency comes with defining `__contains__()`, `__iter__()`, and `iteritems()`.

Since the mixin has no knowledge of the subclass constructor, it does not define `__init__()` or `copy()`.

5.13 `UserList` — Class wrapper for list objects

Note: This module is available for backward compatibility only. If you are writing code that does not need to work with versions of Python earlier than Python 2.2, please consider subclassing directly from the built-in `list` type.

This module defines a class that acts as a wrapper around list objects. It is a useful base class for your own list-like classes, which can inherit from them and override existing methods or add new ones. In this way one can add new behaviors to lists.

The `UserList` module defines the `UserList` class:

class `UserList` (*[list]*)

Class that simulates a list. The instance's contents are kept in a regular list, which is accessible via the `data` attribute of `UserList` instances. The instance's contents are initially set to a copy of *list*, defaulting to the empty list `[]`. *list* can be either a regular Python list, or an instance of `UserList` (or a subclass).

In addition to supporting the methods and operations of mutable sequences (see section 3.6), `UserList` instances provide the following attribute:

data

A real Python list object used to store the contents of the `UserList` class.

Subclassing requirements: Subclasses of `UserList` are expected to offer a constructor which can be called with either no arguments or one argument. List operations which return a new sequence attempt to create an instance of the actual implementation class. To do so, it assumes that the constructor can be called with a single parameter, which is a sequence object used as a data source.

If a derived class does not wish to comply with this requirement, all of the special methods supported by this class will need to be overridden; please consult the sources for information about the methods which need to be provided in that case.

Changed in version 2.0: Python versions 1.5.2 and 1.6 also required that the constructor be callable with no parameters, and offer a mutable `data` attribute. Earlier versions of Python did not attempt to create instances of the derived class.

5.14 UserString — Class wrapper for string objects

Note: This `UserString` class from this module is available for backward compatibility only. If you are writing code that does not need to work with versions of Python earlier than Python 2.2, please consider subclassing directly from the built-in `str` type instead of using `UserString` (there is no built-in equivalent to `MutableString`).

This module defines a class that acts as a wrapper around string objects. It is a useful base class for your own string-like classes, which can inherit from them and override existing methods or add new ones. In this way one can add new behaviors to strings.

It should be noted that these classes are highly inefficient compared to real string or Unicode objects; this is especially the case for `MutableString`.

The `UserString` module defines the following classes:

class `UserString` (`[sequence]`)

Class that simulates a string or a Unicode string object. The instance's content is kept in a regular string or Unicode string object, which is accessible via the `data` attribute of `UserString` instances. The instance's contents are initially set to a copy of *sequence*. *sequence* can be either a regular Python string or Unicode string, an instance of `UserString` (or a subclass) or an arbitrary sequence which can be converted into a string using the built-in `str()` function.

class `MutableString` (`[sequence]`)

This class is derived from the `UserString` above and redefines strings to be *mutable*. Mutable strings can't be used as dictionary keys, because dictionaries require *immutable* objects as keys. The main intention of this class is to serve as an educational example for inheritance and necessity to remove (override) the `__hash__()` method in order to trap attempts to use a mutable object as dictionary key, which would be otherwise very error prone and hard to track down.

In addition to supporting the methods and operations of string and Unicode objects (see section 3.6.1, “String Methods”), `UserString` instances provide the following attribute:

data

A real Python string or Unicode object used to store the content of the `UserString` class.

5.15 types — Names for built-in types

This module defines names for some object types that are used by the standard Python interpreter, but not for the types defined by various extension modules. Also, it does not include some of the types that arise during processing such as the `listiterator` type. It is safe to use `from types import *` — the module does not export any names besides the ones listed here. New names exported by future versions of this module will all end in `'Type'`.

Typical use is for functions that do different things depending on their argument types, like the following:

```
from types import *
def delete(mylist, item):
    if type(item) is IntType:
        del mylist[item]
    else:
        mylist.remove(item)
```

Starting in Python 2.2, built-in factory functions such as `int()` and `str()` are also names for the corresponding types. This is now the preferred way to access the type instead of using the `types` module. Accordingly, the example above should be written as follows:


```
def delete(mylist, item):
    if isinstance(item, int):
        del mylist[item]
    else:
        mylist.remove(item)
```

The module defines the following names:

NoneType

The type of `None`.

TypeType

The type of type objects (such as returned by `type()`).

BooleanType

The type of the `bool` values `True` and `False`; this is an alias of the built-in `bool()` function. New in version 2.3.

IntType

The type of integers (e.g. `1`).

LongType

The type of long integers (e.g. `1L`).

FloatType

The type of floating point numbers (e.g. `1.0`).

ComplexType

The type of complex numbers (e.g. `1.0j`). This is not defined if Python was built without complex number support.

StringType

The type of character strings (e.g. `'Spam'`).

UnicodeType

The type of Unicode character strings (e.g. `u'Spam'`). This is not defined if Python was built without Unicode support.

TupleType

The type of tuples (e.g. `(1, 2, 3, 'Spam')`).

ListType

The type of lists (e.g. `[0, 1, 2, 3]`).

DictType

The type of dictionaries (e.g. `{'Bacon': 1, 'Ham': 0}`).

DictionaryType

An alternate name for `DictType`.

FunctionType

The type of user-defined functions and lambdas.

LambdaType

An alternate name for `FunctionType`.

GeneratorType

The type of generator-iterator objects, produced by calling a generator function. New in version 2.2.

CodeType

The type for code objects such as returned by `compile()`.

ClassType

The type of user-defined classes.

InstanceType

The type of instances of user-defined classes.

MethodType

The type of methods of user-defined class instances.

UnboundMethodType

An alternate name for `MethodType`.

BuiltinFunctionType

The type of built-in functions like `len()` or `sys.exit()`.

BuiltinMethodType

An alternate name for `BuiltinFunction`.

ModuleType

The type of modules.

FileType

The type of open file objects such as `sys.stdout`.

XRangeType

The type of range objects returned by `xrange()`.

SliceType

The type of objects returned by `slice()`.

EllipsisType

The type of `Ellipsis`.

TracebackType

The type of traceback objects such as found in `sys.exc_traceback`.

FrameType

The type of frame objects such as found in `tb.tb_frame` if `tb` is a traceback object.

BufferType

The type of buffer objects created by the `buffer()` function.

DictProxyType

The type of dict proxies, such as `TypeType.__dict__`.

NotImplementedType

The type of `NotImplemented`

GetSetDescriptorType

The type of objects defined in extension modules with `PyGetSetDef`, such as `FrameType.f_locals` or `array.array.typecode`. This constant is not defined in implementations of Python that do not have such extension types, so for portable code use `hasattr(types, 'GetSetDescriptorType')`. New in version 2.5.

MemberDescriptorType

The type of objects defined in extension modules with `PyMemberDef`, such as `datetime.timedelta.days`. This constant is not defined in implementations of Python that do not have such extension types, so for portable code use `hasattr(types, 'MemberDescriptorType')`. New in version 2.5.

StringTypes

A sequence containing `StringType` and `UnicodeType` used to facilitate easier checking for any string object. Using this is more portable than using a sequence of the two string types constructed elsewhere since it only

contains `UnicodeType` if it has been built in the running version of Python. For example: `isinstance(s, types.StringTypes)`. New in version 2.2.

5.16 `new` — Creation of runtime internal objects

The `new` module allows an interface to the interpreter object creation functions. This is for use primarily in marshal-type functions, when a new object needs to be created “magically” and not by using the regular creation functions. This module provides a low-level interface to the interpreter, so care must be exercised when using this module. It is possible to supply non-sensical arguments which crash the interpreter when the object is used.

The `new` module defines the following functions:

instance (*class* [, *dict*])

This function creates an instance of *class* with dictionary *dict* without calling the `__init__()` constructor. If *dict* is omitted or `None`, a new, empty dictionary is created for the new instance. Note that there are no guarantees that the object will be in a consistent state.

instancemethod (*function*, *instance*, *class*)

This function will return a method object, bound to *instance*, or unbound if *instance* is `None`. *function* must be callable.

function (*code*, *globals* [, *name* [, *argdefs* [, *closure*]]])

Returns a (Python) function with the given code and globals. If *name* is given, it must be a string or `None`. If it is a string, the function will have the given name, otherwise the function name will be taken from `code.co_name`. If *argdefs* is given, it must be a tuple and will be used to determine the default values of parameters. If *closure* is given, it must be `None` or a tuple of cell objects containing objects to bind to the names in `code.co_freevars`.

code (*argcount*, *nlocals*, *stacksize*, *flags*, *codestring*, *constants*, *names*, *varnames*, *filename*, *name*, *firstlineno*, *lnotab*)

This function is an interface to the `PyCode_New()` C function.

module (*name* [, *doc*])

This function returns a new module object with name *name*. *name* must be a string. The optional *doc* argument can have any type.

classobj (*name*, *baseclasses*, *dict*)

This function returns a new class object, with name *name*, derived from *baseclasses* (which should be a tuple of classes) and with namespace *dict*.

5.17 `copy` — Shallow and deep copy operations

This module provides generic (shallow and deep) copying operations.

Interface summary:

```
import copy

x = copy.copy(y)           # make a shallow copy of y
x = copy.deepcopy(y)       # make a deep copy of y
```

For module specific errors, `copy.error` is raised.

The difference between shallow and deep copying is only relevant for compound objects (objects that contain other objects, like lists or class instances):

- A *shallow copy* constructs a new compound object and then (to the extent possible) inserts *references* into it to the objects found in the original.
- A *deep copy* constructs a new compound object and then, recursively, inserts *copies* into it of the objects found in the original.

Two problems often exist with deep copy operations that don't exist with shallow copy operations:

- Recursive objects (compound objects that, directly or indirectly, contain a reference to themselves) may cause a recursive loop.
- Because deep copy copies *everything* it may copy too much, e.g., administrative data structures that should be shared even between copies.

The `deepcopy()` function avoids these problems by:

- keeping a “memo” dictionary of objects already copied during the current copying pass; and
- letting user-defined classes override the copying operation or the set of components copied.

This module does not copy types like module, method, stack trace, stack frame, file, socket, window, array, or any similar types. It does “copy” functions and classes (shallow and deeply), by returning the original object unchanged; this is compatible with the way these are treated by the `pickle` module. Changed in version 2.5: Added copying functions.

Classes can use the same interfaces to control copying that they use to control pickling. See the description of module `pickle` for information on these methods. The `copy` module does not use the `copy_reg` registration module.

In order for a class to define its own copy implementation, it can define special methods `__copy__()` and `__deepcopy__()`. The former is called to implement the shallow copy operation; no additional arguments are passed. The latter is called to implement the deep copy operation; it is passed one argument, the memo dictionary. If the `__deepcopy__()` implementation needs to make a deep copy of a component, it should call the `deepcopy()` function with the component as first argument and the memo dictionary as second argument.

See Also:

[Module `pickle`](#) (section 13.1):

Discussion of the special methods used to support object state retrieval and restoration.

5.18 pprint — Data pretty printer

The `pprint` module provides a capability to “pretty-print” arbitrary Python data structures in a form which can be used as input to the interpreter. If the formatted structures include objects which are not fundamental Python types, the representation may not be loadable. This may be the case if objects such as files, sockets, classes, or instances are included, as well as many other builtin objects which are not representable as Python constants.

The formatted representation keeps objects on a single line if it can, and breaks them onto multiple lines if they don't fit within the allowed width. Construct `PrettyPrinter` objects explicitly if you need to adjust the width constraint.

Changed in version 2.5: Dictionaries are sorted by key before the display is computed; before 2.5, a dictionary was sorted only if its display required more than one line, although that wasn't documented.

The `pprint` module defines one class:

class `PrettyPrinter` (...)

Construct a `PrettyPrinter` instance. This constructor understands several keyword parameters. An output

stream may be set using the *stream* keyword; the only method used on the stream object is the file protocol's `write()` method. If not specified, the `PrettyPrinter` adopts `sys.stdout`. Three additional parameters may be used to control the formatted representation. The keywords are *indent*, *depth*, and *width*. The amount of indentation added for each recursive level is specified by *indent*; the default is one. Other values can cause output to look a little odd, but can make nesting easier to spot. The number of levels which may be printed is controlled by *depth*; if the data structure being printed is too deep, the next contained level is replaced by `'...'`. By default, there is no constraint on the depth of the objects being formatted. The desired output width is constrained using the *width* parameter; the default is eighty characters. If a structure cannot be formatted within the constrained width, a best effort will be made.

```
>>> import pprint, sys
>>> stuff = sys.path[:]
>>> stuff.insert(0, stuff[:])
>>> pp = pprint.PrettyPrinter(indent=4)
>>> pp.pprint(stuff)
[ [ '',
  '/usr/local/lib/python1.5',
  '/usr/local/lib/python1.5/test',
  '/usr/local/lib/python1.5/sunos5',
  '/usr/local/lib/python1.5/sharedmodules',
  '/usr/local/lib/python1.5/tkinter' ],
  '',
  '/usr/local/lib/python1.5',
  '/usr/local/lib/python1.5/test',
  '/usr/local/lib/python1.5/sunos5',
  '/usr/local/lib/python1.5/sharedmodules',
  '/usr/local/lib/python1.5/tkinter' ]
>>>
>>> import parser
>>> tup = parser.ast2tuple(
...     parser.suite(open('pprint.py').read()))[1][1][1]
>>> pp = pprint.PrettyPrinter(depth=6)
>>> pp.pprint(tup)
(266, (267, (307, (287, (288, (...)))))
```

The `PrettyPrinter` class supports several derivative functions:

ppformat (*object* [, *indent* [, *width* [, *depth*]]])

Return the formatted representation of *object* as a string. *indent*, *width* and *depth* will be passed to the `PrettyPrinter` constructor as formatting parameters. Changed in version 2.4: The parameters *indent*, *width* and *depth* were added.

pprint (*object* [, *stream* [, *indent* [, *width* [, *depth*]]]])

Prints the formatted representation of *object* on *stream*, followed by a newline. If *stream* is omitted, `sys.stdout` is used. This may be used in the interactive interpreter instead of a `print` statement for inspecting values. *indent*, *width* and *depth* will be passed to the `PrettyPrinter` constructor as formatting parameters.

```
>>> stuff = sys.path[:]
>>> stuff.insert(0, stuff)
>>> pprint.pprint(stuff)
[<Recursion on list with id=869440>,
 ',
 '/usr/local/lib/python1.5',
 '/usr/local/lib/python1.5/test',
 '/usr/local/lib/python1.5/sunos5',
 '/usr/local/lib/python1.5/sharedmodules',
 '/usr/local/lib/python1.5/tkinter']
```

Changed in version 2.4: The parameters *indent*, *width* and *depth* were added.

isreadable (*object*)

Determine if the formatted representation of *object* is “readable,” or can be used to reconstruct the value using `eval()`. This always returns `False` for recursive objects.

```
>>> pprint.isreadable(stuff)
False
```

isrecursive (*object*)

Determine if *object* requires a recursive representation.

One more support function is also defined:

saferepr (*object*)

Return a string representation of *object*, protected against recursive data structures. If the representation of *object* exposes a recursive entry, the recursive reference will be represented as ‘<Recursion on *typename* with *id=number*>’. The representation is not otherwise formatted.

```
>>> pprint.saferepr(stuff)
"[<Recursion on list with id=682968>, ', '/usr/local/lib/python1.5', '/usr/local/lib/python1.5/test', '/usr/local/lib/python1.5/sunos5', '/usr/local/lib/python1.5/sharedmodules', '/usr/local/lib/python1.5/tkinter']"
```

5.18.1 PrettyPrinter Objects

`PrettyPrinter` instances have the following methods:

pformat (*object*)

Return the formatted representation of *object*. This takes into account the options passed to the `PrettyPrinter` constructor.

pprint (*object*)

Print the formatted representation of *object* on the configured stream, followed by a newline.

The following methods provide the implementations for the corresponding functions of the same names. Using these methods on an instance is slightly more efficient since new `PrettyPrinter` objects don’t need to be created.

isreadable (*object*)

Determine if the formatted representation of the object is “readable,” or can be used to reconstruct the value using `eval()`. Note that this returns `False` for recursive objects. If the *depth* parameter of the `PrettyPrinter` is set and the object is deeper than allowed, this returns `False`.

isrecursive (*object*)

Determine if the object requires a recursive representation.

This method is provided as a hook to allow subclasses to modify the way objects are converted to strings. The default implementation uses the internals of the `saferepr()` implementation.

format (*object*, *context*, *maxlevels*, *level*)

Returns three values: the formatted version of *object* as a string, a flag indicating whether the result is readable, and a flag indicating whether recursion was detected. The first argument is the object to be presented. The second is a dictionary which contains the `id()` of objects that are part of the current presentation context (direct and indirect containers for *object* that are affecting the presentation) as the keys; if an object needs to be presented which is already represented in *context*, the third return value should be `True`. Recursive calls to the `format()` method should add additional entries for containers to this dictionary. The third argument, *maxlevels*, gives the requested limit to recursion; this will be 0 if there is no requested limit. This argument should be passed unmodified to recursive calls. The fourth argument, *level*, gives the current level; recursive calls should be passed a value less than that of the current call. New in version 2.3.

5.19 repr — Alternate `repr()` implementation

The `repr` module provides a means for producing object representations with limits on the size of the resulting strings. This is used in the Python debugger and may be useful in other contexts as well.

This module provides a class, an instance, and a function:

class Repr ()

Class which provides formatting services useful in implementing functions similar to the built-in `repr()`; size limits for different object types are added to avoid the generation of representations which are excessively long.

aRepr

This is an instance of `Repr` which is used to provide the `repr()` function described below. Changing the attributes of this object will affect the size limits used by `repr()` and the Python debugger.

repr (*obj*)

This is the `repr()` method of `aRepr`. It returns a string similar to that returned by the built-in function of the same name, but with limits on most sizes.

5.19.1 Repr Objects

`Repr` instances provide several members which can be used to provide size limits for the representations of different object types, and methods which format specific object types.

maxlevel

Depth limit on the creation of recursive representations. The default is 6.

maxdict

maxlist

maxtuple

maxset

maxfrozenset

maxdeque

maxarray

Limits on the number of entries represented for the named object type. The default is 4 for `maxdict`, 5 for `maxarray`, and 6 for the others. New in version 2.4: `maxset`, `maxfrozenset`, and `set`.

maxlong

Maximum number of characters in the representation for a long integer. Digits are dropped from the middle. The default is 40.

maxstring

Limit on the number of characters in the representation of the string. Note that the “normal” representation of the string is used as the character source: if escape sequences are needed in the representation, these may be mangled when the representation is shortened. The default is 30.

maxother

This limit is used to control the size of object types for which no specific formatting method is available on the `Repr` object. It is applied in a similar manner as `maxstring`. The default is 20.

repr (*obj*)

The equivalent to the built-in `repr()` that uses the formatting imposed by the instance.

repr1 (*obj*, *level*)

Recursive implementation used by `repr()`. This uses the type of *obj* to determine which formatting method to call, passing it *obj* and *level*. The type-specific methods should call `repr1()` to perform recursive formatting, with *level* - 1 for the value of *level* in the recursive call.

repr_type (*obj*, *level*)

Formatting methods for specific types are implemented as methods with a name based on the type name. In the method name, *type* is replaced by `string.join(string.split(type(obj).__name__, '_-'))`. Dispatch to these methods is handled by `repr1()`. Type-specific methods which need to recursively format a value should call `'self.repr1(subobj, level - 1)'`.

5.19.2 Subclassing Repr Objects

The use of dynamic dispatching by `Repr.repr1()` allows subclasses of `Repr` to add support for additional built-in object types or to modify the handling of types already supported. This example shows how special support for file objects could be added:

```
import repr
import sys

class MyRepr(repr.Repr):
    def repr_file(self, obj, level):
        if obj.name in ['<stdin>', '<stdout>', '<stderr>']:
            return obj.name
        else:
            return 'obj'

aRepr = MyRepr()
print aRepr.repr(sys.stdin)          # prints '<stdin>'
```


Numeric and Mathematical Modules

The modules described in this chapter provide numeric and math-related functions and data types. The `math` and `cmath` contain various mathematical functions for floating-point and complex numbers. For users more interested in decimal accuracy than in speed, the `decimal` module supports exact representations of decimal numbers.

The following modules are documented in this chapter:

<code>math</code>	Mathematical functions (<code>sin()</code> etc.).
<code>cmath</code>	Mathematical functions for complex numbers.
<code>decimal</code>	Implementation of the General Decimal Arithmetic Specification.
<code>random</code>	Generate pseudo-random numbers with various common distributions.
<code>itertools</code>	Functions creating iterators for efficient looping.
<code>functools</code>	Higher-order functions and operations on callable objects.
<code>operator</code>	All Python's standard operators as built-in functions.

6.1 `math` — Mathematical functions

This module is always available. It provides access to the mathematical functions defined by the C standard.

These functions cannot be used with complex numbers; use the functions of the same name from the `cmath` module if you require support for complex numbers. The distinction between functions which support complex numbers and those which don't is made since most users do not want to learn quite as much mathematics as required to understand complex numbers. Receiving an exception instead of a complex result allows earlier detection of the unexpected complex number used as a parameter, so that the programmer can determine how and why it was generated in the first place.

The following functions are provided by this module. Except when explicitly noted otherwise, all return values are floats.

Number-theoretic and representation functions:

`ceil` (*x*)

Return the ceiling of *x* as a float, the smallest integer value greater than or equal to *x*.

`fabs` (*x*)

Return the absolute value of *x*.

`floor` (*x*)

Return the floor of *x* as a float, the largest integer value less than or equal to *x*.

`fmod` (*x*, *y*)

Return `fmod(x, y)`, as defined by the platform C library. Note that the Python expression `x % y` may not return the same result. The intent of the C standard is that `fmod(x, y)` be exactly (mathematically; to infinite precision) equal to $x - n*y$ for some integer *n* such that the result has the same sign as *x* and magnitude less than `abs(y)`. Python's `x % y` returns a result with the sign of *y* instead, and may not be exactly computable for

float arguments. For example, `fmod(-1e-100, 1e100)` is `-1e-100`, but the result of Python's `-1e-100 % 1e100` is `1e100-1e-100`, which cannot be represented exactly as a float, and rounds to the surprising `1e100`. For this reason, function `fmod()` is generally preferred when working with floats, while Python's `x % y` is preferred when working with integers.

frexp (*x*)

Return the mantissa and exponent of *x* as the pair (*m*, *e*). *m* is a float and *e* is an integer such that $x == m * 2^{**e}$ exactly. If *x* is zero, returns (0.0, 0), otherwise $0.5 \leq \text{abs}(m) < 1$. This is used to "pick apart" the internal representation of a float in a portable way.

ldexp (*x*, *i*)

Return $x * (2^{**i})$. This is essentially the inverse of function `frexp()`.

modf (*x*)

Return the fractional and integer parts of *x*. Both results carry the sign of *x*, and both are floats.

Note that `frexp()` and `modf()` have a different call/return pattern than their C equivalents: they take a single argument and return a pair of values, rather than returning their second return value through an 'output parameter' (there is no such thing in Python).

For the `ceil()`, `floor()`, and `modf()` functions, note that *all* floating-point numbers of sufficiently large magnitude are exact integers. Python floats typically carry no more than 53 bits of precision (the same as the platform C double type), in which case any float *x* with $\text{abs}(x) \geq 2^{**52}$ necessarily has no fractional bits.

Power and logarithmic functions:

exp (*x*)

Return e^{**x} .

log (*x*[, *base*])

Return the logarithm of *x* to the given *base*. If the *base* is not specified, return the natural logarithm of *x* (that is, the logarithm to base *e*). Changed in version 2.3: *base* argument added.

log10 (*x*)

Return the base-10 logarithm of *x*.

pow (*x*, *y*)

Return x^{**y} .

sqrt (*x*)

Return the square root of *x*.

Trigonometric functions:

acos (*x*)

Return the arc cosine of *x*, in radians.

asin (*x*)

Return the arc sine of *x*, in radians.

atan (*x*)

Return the arc tangent of *x*, in radians.

atan2 (*y*, *x*)

Return `atan(y / x)`, in radians. The result is between `-pi` and `pi`. The vector in the plane from the origin to point (*x*, *y*) makes this angle with the positive X axis. The point of `atan2()` is that the signs of both inputs are known to it, so it can compute the correct quadrant for the angle. For example, `atan(1)` and `atan2(1, 1)` are both `pi/4`, but `atan2(-1, -1)` is `-3*pi/4`.

cos (*x*)

Return the cosine of *x* radians.

hypot (*x*, *y*)

Return the Euclidean norm, `sqrt(x*x + y*y)`. This is the length of the vector from the origin to point (x, y) .

sin(*x*)

Return the sine of *x* radians.

tan(*x*)

Return the tangent of *x* radians.

Angular conversion:

degrees(*x*)

Converts angle *x* from radians to degrees.

radians(*x*)

Converts angle *x* from degrees to radians.

Hyperbolic functions:

cosh(*x*)

Return the hyperbolic cosine of *x*.

sinh(*x*)

Return the hyperbolic sine of *x*.

tanh(*x*)

Return the hyperbolic tangent of *x*.

The module also defines two mathematical constants:

pi

The mathematical constant *pi*.

e

The mathematical constant *e*.

Note: The `math` module consists mostly of thin wrappers around the platform C math library functions. Behavior in exceptional cases is loosely specified by the C standards, and Python inherits much of its math-function error-reporting behavior from the platform C implementation. As a result, the specific exceptions raised in error cases (and even whether some arguments are considered to be exceptional at all) are not defined in any useful cross-platform or cross-release way. For example, whether `math.log(0)` returns `-Inf` or raises `ValueError` or `OverflowError` isn't defined, and in cases where `math.log(0)` raises `OverflowError`, `math.log(0L)` may raise `ValueError` instead.

See Also:

[Module `cmath`](#) (section 6.2):

Complex number versions of many of these functions.

6.2 `cmath` — Mathematical functions for complex numbers

This module is always available. It provides access to mathematical functions for complex numbers. The functions are:

acos(*x*)

Return the arc cosine of *x*. There are two branch cuts: One extends right from 1 along the real axis to ∞ , continuous from below. The other extends left from -1 along the real axis to $-\infty$, continuous from above.

acosh(*x*)

Return the hyperbolic arc cosine of *x*. There is one branch cut, extending left from 1 along the real axis to $-\infty$, continuous from above.

asin (*x*)

Return the arc sine of *x*. This has the same branch cuts as `acos()`.

asinh (*x*)

Return the hyperbolic arc sine of *x*. There are two branch cuts, extending left from $\pm 1j$ to $\pm \infty j$, both continuous from above. These branch cuts should be considered a bug to be corrected in a future release. The correct branch cuts should extend along the imaginary axis, one from $1j$ up to ∞j and continuous from the right, and one from $-1j$ down to $-\infty j$ and continuous from the left.

atan (*x*)

Return the arc tangent of *x*. There are two branch cuts: One extends from $1j$ along the imaginary axis to ∞j , continuous from the left. The other extends from $-1j$ along the imaginary axis to $-\infty j$, continuous from the left. (This should probably be changed so the upper cut becomes continuous from the other side.)

atanh (*x*)

Return the hyperbolic arc tangent of *x*. There are two branch cuts: One extends from 1 along the real axis to ∞ , continuous from above. The other extends from -1 along the real axis to $-\infty$, continuous from above. (This should probably be changed so the right cut becomes continuous from the other side.)

cos (*x*)

Return the cosine of *x*.

cosh (*x*)

Return the hyperbolic cosine of *x*.

exp (*x*)

Return the exponential value e^{*x} .

log (*x* [, *base*])

Returns the logarithm of *x* to the given *base*. If the *base* is not specified, returns the natural logarithm of *x*. There is one branch cut, from 0 along the negative real axis to $-\infty$, continuous from above. Changed in version 2.4: *base* argument added.

log10 (*x*)

Return the base-10 logarithm of *x*. This has the same branch cut as `log()`.

sin (*x*)

Return the sine of *x*.

sinh (*x*)

Return the hyperbolic sine of *x*.

sqrt (*x*)

Return the square root of *x*. This has the same branch cut as `log()`.

tan (*x*)

Return the tangent of *x*.

tanh (*x*)

Return the hyperbolic tangent of *x*.

The module also defines two mathematical constants:

pi

The mathematical constant π , as a real.

e

The mathematical constant e , as a real.

Note that the selection of functions is similar, but not identical, to that in module `math`. The reason for having two modules is that some users aren't interested in complex numbers, and perhaps don't even know what they are. They would rather have `math.sqrt(-1)` raise an exception than return a complex number. Also note that the functions defined in `cmath` always return a complex number, even if the answer can be expressed as a real number (in which

case the complex number has an imaginary part of zero).

A note on branch cuts: They are curves along which the given function fails to be continuous. They are a necessary feature of many complex functions. It is assumed that if you need to compute with complex functions, you will understand about branch cuts. Consult almost any (not too elementary) book on complex variables for enlightenment. For information of the proper choice of branch cuts for numerical purposes, a good reference should be the following:

See Also:

Kahan, W: Branch cuts for complex elementary functions; or, Much ado about nothing's sign bit. In Iserles, A., and Powell, M. (eds.), *The state of the art in numerical analysis*. Clarendon Press (1987) pp165-211.

6.3 decimal — Decimal floating point arithmetic

New in version 2.4.

The `decimal` module provides support for decimal floating point arithmetic. It offers several advantages over the `float()` datatype:

- Decimal numbers can be represented exactly. In contrast, numbers like `1.1` do not have an exact representation in binary floating point. End users typically would not expect `1.1` to display as `1.1000000000000001` as it does with binary floating point.
- The exactness carries over into arithmetic. In decimal floating point, `'0.1 + 0.1 + 0.1 - 0.3'` is exactly equal to zero. In binary floating point, result is `5.5511151231257827e-017`. While near to zero, the differences prevent reliable equality testing and differences can accumulate. For this reason, decimal would be preferred in accounting applications which have strict equality invariants.
- The decimal module incorporates a notion of significant places so that `'1.30 + 1.20'` is `2.50`. The trailing zero is kept to indicate significance. This is the customary presentation for monetary applications. For multiplication, the “schoolbook” approach uses all the figures in the multiplicands. For instance, `'1.3 * 1.2'` gives `1.56` while `'1.30 * 1.20'` gives `1.5600`.
- Unlike hardware based binary floating point, the decimal module has a user settable precision (defaulting to 28 places) which can be as large as needed for a given problem:

```
>>> getcontext().prec = 6
>>> Decimal(1) / Decimal(7)
Decimal("0.142857")
>>> getcontext().prec = 28
>>> Decimal(1) / Decimal(7)
Decimal("0.1428571428571428571428571428571429")
```

- Both binary and decimal floating point are implemented in terms of published standards. While the built-in `float` type exposes only a modest portion of its capabilities, the decimal module exposes all required parts of the standard. When needed, the programmer has full control over rounding and signal handling.

The module design is centered around three concepts: the decimal number, the context for arithmetic, and signals.

A decimal number is immutable. It has a sign, coefficient digits, and an exponent. To preserve significance, the coefficient digits do not truncate trailing zeroes. Decimals also include special values such as `Infinity`, `-Infinity`, and `NaN`. The standard also differentiates `-0` from `+0`.

The context for arithmetic is an environment specifying precision, rounding rules, limits on exponents, flags indicating the results of operations, and trap enablers which determine whether signals are treated as exceptions. Rounding options include `ROUND_CEILING`, `ROUND_DOWN`, `ROUND_FLOOR`, `ROUND_HALF_DOWN`, `ROUND_HALF_EVEN`, `ROUND_HALF_UP`, and `ROUND_UP`.

Signals are groups of exceptional conditions arising during the course of computation. Depending on the needs of the application, signals may be ignored, considered as informational, or treated as exceptions. The signals in the decimal module are: `Clamped`, `InvalidOperation`, `DivisionByZero`, `Inexact`, `Rounded`, `Subnormal`, `Overflow`, and `Underflow`.

For each signal there is a flag and a trap enabler. When a signal is encountered, its flag is incremented from zero and, then, if the trap enabler is set to one, an exception is raised. Flags are sticky, so the user needs to reset them before monitoring a calculation.

See Also:

IBM's General Decimal Arithmetic Specification, [The General Decimal Arithmetic Specification](#).

IEEE standard 854-1987, [Unofficial IEEE 854 Text](#).

6.3.1 Quick-start Tutorial

The usual start to using decimals is importing the module, viewing the current context with `getcontext()` and, if necessary, setting new values for precision, rounding, or enabled traps:

```
>>> from decimal import *
>>> getcontext()
Context(prec=28, rounding=ROUND_HALF_EVEN, Emin=-999999999, Emax=999999999,
        capitals=1, flags=[], traps=[Overflow, InvalidOperation,
        DivisionByZero])

>>> getcontext().prec = 7          # Set a new precision
```

Decimal instances can be constructed from integers, strings, or tuples. To create a Decimal from a `float`, first convert it to a string. This serves as an explicit reminder of the details of the conversion (including representation error). Decimal numbers include special values such as `NaN` which stands for “Not a number”, positive and negative `Infinity`, and `-0`.

```
>>> Decimal(10)
Decimal("10")
>>> Decimal("3.14")
Decimal("3.14")
>>> Decimal((0, (3, 1, 4), -2))
Decimal("3.14")
>>> Decimal(str(2.0 ** 0.5))
Decimal("1.41421356237")
>>> Decimal("NaN")
Decimal("NaN")
>>> Decimal("-Infinity")
Decimal("-Infinity")
```

The significance of a new Decimal is determined solely by the number of digits input. Context precision and rounding only come into play during arithmetic operations.

```

>>> getcontext().prec = 6
>>> Decimal('3.0')
Decimal("3.0")
>>> Decimal('3.1415926535')
Decimal("3.1415926535")
>>> Decimal('3.1415926535') + Decimal('2.7182818285')
Decimal("5.85987")
>>> getcontext().rounding = ROUND_UP
>>> Decimal('3.1415926535') + Decimal('2.7182818285')
Decimal("5.85988")

```

Decimals interact well with much of the rest of Python. Here is a small decimal floating point flying circus:

```

>>> data = map(Decimal, '1.34 1.87 3.45 2.35 1.00 0.03 9.25'.split())
>>> max(data)
Decimal("9.25")
>>> min(data)
Decimal("0.03")
>>> sorted(data)
[Decimal("0.03"), Decimal("1.00"), Decimal("1.34"), Decimal("1.87"),
 Decimal("2.35"), Decimal("3.45"), Decimal("9.25")]
>>> sum(data)
Decimal("19.29")
>>> a,b,c = data[:3]
>>> str(a)
'1.34'
>>> float(a)
1.3400000000000001
>>> round(a, 1)      # round() first converts to binary floating point
1.3
>>> int(a)
1
>>> a * 5
Decimal("6.70")
>>> a * b
Decimal("2.5058")
>>> c % a
Decimal("0.77")

```

The `quantize()` method rounds a number to a fixed exponent. This method is useful for monetary applications that often round results to a fixed number of places:

```

>>> Decimal('7.325').quantize(Decimal('.01'), rounding=ROUND_DOWN)
Decimal("7.32")
>>> Decimal('7.325').quantize(Decimal('1.'), rounding=ROUND_UP)
Decimal("8")

```

As shown above, the `getcontext()` function accesses the current context and allows the settings to be changed. This approach meets the needs of most applications.

For more advanced work, it may be useful to create alternate contexts using the `Context()` constructor. To make an alternate active, use the `setcontext()` function.

In accordance with the standard, the `Decimal` module provides two ready to use standard contexts, `BasicContext` and `ExtendedContext`. The former is especially useful for debugging because many of the traps are enabled:

```

>>> myothercontext = Context(prec=60, rounding=ROUND_HALF_DOWN)
>>> setcontext(myothercontext)
>>> Decimal(1) / Decimal(7)
Decimal("0.142857142857142857142857142857142857142857142857142857")

>>> ExtendedContext
Context(prec=9, rounding=ROUND_HALF_EVEN, Emin=-999999999, Emax=999999999,
        capitals=1, flags=[], traps=[])
>>> setcontext(ExtendedContext)
>>> Decimal(1) / Decimal(7)
Decimal("0.142857143")
>>> Decimal(42) / Decimal(0)
Decimal("Infinity")

>>> setcontext(BasicContext)
>>> Decimal(42) / Decimal(0)
Traceback (most recent call last):
  File "<pyshell#143>", line 1, in <module>
    Decimal(42) / Decimal(0)
DivisionByZero: x / 0

```

Contexts also have signal flags for monitoring exceptional conditions encountered during computations. The flags remain set until explicitly cleared, so it is best to clear the flags before each set of monitored computations by using the `clear_flags()` method.

```

>>> setcontext(ExtendedContext)
>>> getcontext().clear_flags()
>>> Decimal(355) / Decimal(113)
Decimal("3.14159292")
>>> getcontext()
Context(prec=9, rounding=ROUND_HALF_EVEN, Emin=-999999999, Emax=999999999,
        capitals=1, flags=[Inexact, Rounded], traps=[])

```

The *flags* entry shows that the rational approximation to Pi was rounded (digits beyond the context precision were thrown away) and that the result is inexact (some of the discarded digits were non-zero).

Individual traps are set using the dictionary in the `traps` field of a context:

```

>>> Decimal(1) / Decimal(0)
Decimal("Infinity")
>>> getcontext().traps[DivisionByZero] = 1
>>> Decimal(1) / Decimal(0)
Traceback (most recent call last):
  File "<pyshell#112>", line 1, in <module>
    Decimal(1) / Decimal(0)
DivisionByZero: x / 0

```

Most programs adjust the current context only once, at the beginning of the program. And, in many applications, data is converted to `Decimal` with a single cast inside a loop. With context set and decimals created, the bulk of the program manipulates the data no differently than with other Python numeric types.

6.3.2 Decimal objects

class `Decimal` (`[value [, context]]`)

Constructs a new `Decimal` object based from `value`.

`value` can be an integer, string, tuple, or another `Decimal` object. If no `value` is given, returns `Decimal("0")`.

If `value` is a string, it should conform to the decimal numeric string syntax:

```
sign           ::= '+' | '-'
digit          ::= '0' | '1' | '2' | '3' | '4' | '5' | '6' | '7' | '8' | '9'
indicator      ::= 'e' | 'E'
digits         ::= digit [digit]...
decimal-part   ::= digits '.' [digits] | ['.'] digits
exponent-part  ::= indicator [sign] digits
infinity      ::= 'Infinity' | 'Inf'
nan           ::= 'NaN' [digits] | 'sNaN' [digits]
numeric-value  ::= decimal-part [exponent-part] | infinity
numeric-string ::= [sign] numeric-value | [sign] nan
```

If `value` is a tuple, it should have three components, a sign (0 for positive or 1 for negative), a tuple of digits, and an integer exponent. For example, `Decimal((0, (1, 4, 1, 4), -3))` returns `Decimal("1.414")`.

The `context` precision does not affect how many digits are stored. That is determined exclusively by the number of digits in `value`. For example, `Decimal("3.00000")` records all five zeroes even if the context precision is only three.

The purpose of the `context` argument is determining what to do if `value` is a malformed string. If the context traps `InvalidOperation`, an exception is raised; otherwise, the constructor returns a new `Decimal` with the value of NaN.

Once constructed, `Decimal` objects are immutable.

Decimal floating point objects share many properties with the other builtin numeric types such as `float` and `int`. All of the usual math operations and special methods apply. Likewise, decimal objects can be copied, pickled, printed, used as dictionary keys, used as set elements, compared, sorted, and coerced to another type (such as `float` or `long`).

In addition to the standard numeric properties, decimal floating point objects also have a number of specialized methods:

adjusted()

Return the adjusted exponent after shifting out the coefficient's rightmost digits until only the lead digit remains: `Decimal("321e+5").adjusted()` returns seven. Used for determining the position of the most significant digit with respect to the decimal point.

as_tuple()

Returns a tuple representation of the number: `'(sign, digittuple, exponent)'`.

compare(`other` [, `context`])

Compares like `__cmp__()` but returns a decimal instance:

```
a or b is a NaN ==> Decimal("NaN")
a < b           ==> Decimal("-1")
a == b          ==> Decimal("0")
a > b           ==> Decimal("1")
```

max(`other` [, `context`])

Like `'max(self, other)'` except that the context rounding rule is applied before returning and that NaN

values are either signalled or ignored (depending on the context and whether they are signaling or quiet).

min (*other* [, *context*])

Like 'min(*self*, *other*)' except that the context rounding rule is applied before returning and that NaN values are either signalled or ignored (depending on the context and whether they are signaling or quiet).

normalize ([*context*])

Normalize the number by stripping the rightmost trailing zeroes and converting any result equal to Decimal("0") to Decimal("0e0"). Used for producing canonical values for members of an equivalence class. For example, Decimal("32.100") and Decimal("0.321000e+2") both normalize to the equivalent value Decimal("32.1").

quantize (*exp* [, *rounding* [, *context* [, *watchexp*]]])

Quantize makes the exponent the same as *exp*. Searches for a rounding method in *rounding*, then in *context*, and then in the current context.

If *watchexp* is set (default), then an error is returned whenever the resulting exponent is greater than Emax or less than Etiny.

remainder_near (*other* [, *context*])

Computes the modulo as either a positive or negative value depending on which is closest to zero. For instance, 'Decimal(10).remainder_near(6)' returns Decimal("-2") which is closer to zero than Decimal("4").

If both are equally close, the one chosen will have the same sign as *self*.

same_quantum (*other* [, *context*])

Test whether self and other have the same exponent or whether both are NaN.

sqrt ([*context*])

Return the square root to full precision.

to_eng_string ([*context*])

Convert to an engineering-type string.

Engineering notation has an exponent which is a multiple of 3, so there are up to 3 digits left of the decimal place. For example, converts Decimal('123E+1') to Decimal("1.23E+3")

to_integral ([*rounding* [, *context*]])

Rounds to the nearest integer without signaling Inexact or Rounded. If given, applies *rounding*; otherwise, uses the rounding method in either the supplied *context* or the current context.

6.3.3 Context objects

Contexts are environments for arithmetic operations. They govern precision, set rules for rounding, determine which signals are treated as exceptions, and limit the range for exponents.

Each thread has its own current context which is accessed or changed using the `getcontext()` and `setcontext()` functions:

getcontext ()

Return the current context for the active thread.

setcontext (*c*)

Set the current context for the active thread to *c*.

Beginning with Python 2.5, you can also use the `with` statement and the `localcontext()` function to temporarily change the active context.

localcontext ([*c*])

Return a context manager that will set the current context for the active thread to a copy of *c* on entry to the with-statement and restore the previous context when exiting the with-statement. If no context is specified, a

copy of the current context is used. New in version 2.5.

For example, the following code sets the current decimal precision to 42 places, performs a calculation, and then automatically restores the previous context:

```
from __future__ import with_statement
from decimal import localcontext

with localcontext() as ctx:
    ctx.prec = 42 # Perform a high precision calculation
    s = calculate_something()
s = +s # Round the final result back to the default precision
```

New contexts can also be created using the `Context` constructor described below. In addition, the module provides three pre-made contexts:

class BasicContext

This is a standard context defined by the General Decimal Arithmetic Specification. Precision is set to nine. Rounding is set to `ROUND_HALF_UP`. All flags are cleared. All traps are enabled (treated as exceptions) except `Inexact`, `Rounded`, and `Subnormal`.

Because many of the traps are enabled, this context is useful for debugging.

class ExtendedContext

This is a standard context defined by the General Decimal Arithmetic Specification. Precision is set to nine. Rounding is set to `ROUND_HALF_EVEN`. All flags are cleared. No traps are enabled (so that exceptions are not raised during computations).

Because the trapped are disabled, this context is useful for applications that prefer to have result value of `NaN` or `Infinity` instead of raising exceptions. This allows an application to complete a run in the presence of conditions that would otherwise halt the program.

class DefaultContext

This context is used by the `Context` constructor as a prototype for new contexts. Changing a field (such as a precision) has the effect of changing the default for new contexts creating by the `Context` constructor.

This context is most useful in multi-threaded environments. Changing one of the fields before threads are started has the effect of setting system-wide defaults. Changing the fields after threads have started is not recommended as it would require thread synchronization to prevent race conditions.

In single threaded environments, it is preferable to not use this context at all. Instead, simply create contexts explicitly as described below.

The default values are precision=28, rounding=`ROUND_HALF_EVEN`, and enabled traps for `Overflow`, `InvalidOperation`, and `DivisionByZero`.

In addition to the three supplied contexts, new contexts can be created with the `Context` constructor.

class Context (*prec=None, rounding=None, traps=None, flags=None, Emin=None, Emax=None, capitals=1*)

Creates a new context. If a field is not specified or is `None`, the default values are copied from the `DefaultContext`. If the *flags* field is not specified or is `None`, all flags are cleared.

The *prec* field is a positive integer that sets the precision for arithmetic operations in the context.

The *rounding* option is one of:

- `ROUND_CEILING` (towards `Infinity`),
- `ROUND_DOWN` (towards zero),
- `ROUND_FLOOR` (towards `-Infinity`),
- `ROUND_HALF_DOWN` (to nearest with ties going towards zero),
- `ROUND_HALF_EVEN` (to nearest with ties going to nearest even integer),

- `ROUND_HALF_UP` (to nearest with ties going away from zero), or
- `ROUND_UP` (away from zero).

The *traps* and *flags* fields list any signals to be set. Generally, new contexts should only set traps and leave the flags clear.

The *Emin* and *Emax* fields are integers specifying the outer limits allowable for exponents.

The *capitals* field is either 0 or 1 (the default). If set to 1, exponents are printed with a capital E; otherwise, a lowercase e is used: `Decimal('6.02e+23')`.

The `Context` class defines several general purpose methods as well as a large number of methods for doing arithmetic directly in a given context.

`clear_flags()`

Resets all of the flags to 0.

`copy()`

Return a duplicate of the context.

`create_decimal(num)`

Creates a new `Decimal` instance from *num* but using *self* as context. Unlike the `Decimal` constructor, the context precision, rounding method, flags, and traps are applied to the conversion.

This is useful because constants are often given to a greater precision than is needed by the application. Another benefit is that rounding immediately eliminates unintended effects from digits beyond the current precision. In the following example, using unrounded inputs means that adding zero to a sum can change the result:

```
>>> getcontext().prec = 3
>>> Decimal("3.4445") + Decimal("1.0023")
Decimal("4.45")
>>> Decimal("3.4445") + Decimal(0) + Decimal("1.0023")
Decimal("4.44")
```

`Etiny()`

Returns a value equal to `'Emin - prec + 1'` which is the minimum exponent value for subnormal results. When underflow occurs, the exponent is set to `Etiny`.

`Etop()`

Returns a value equal to `'Emax - prec + 1'`.

The usual approach to working with decimals is to create `Decimal` instances and then apply arithmetic operations which take place within the current context for the active thread. An alternate approach is to use context methods for calculating within a specific context. The methods are similar to those for the `Decimal` class and are only briefly recounted here.

`abs(x)`

Returns the absolute value of *x*.

`add(x, y)`

Return the sum of *x* and *y*.

`compare(x, y)`

Compares values numerically.

Like `__cmp__()` but returns a decimal instance:

```

a or b is a NaN ==> Decimal("NaN")
a < b           ==> Decimal("-1")
a == b          ==> Decimal("0")
a > b           ==> Decimal("1")

```

divide (*x*, *y*)

Return *x* divided by *y*.

divmod (*x*, *y*)

Divides two numbers and returns the integer part of the result.

max (*x*, *y*)

Compare two values numerically and return the maximum.

If they are numerically equal then the left-hand operand is chosen as the result.

min (*x*, *y*)

Compare two values numerically and return the minimum.

If they are numerically equal then the left-hand operand is chosen as the result.

minus (*x*)

Minus corresponds to the unary prefix minus operator in Python.

multiply (*x*, *y*)

Return the product of *x* and *y*.

normalize (*x*)

Normalize reduces an operand to its simplest form.

Essentially a `plus` operation with all trailing zeros removed from the result.

plus (*x*)

Plus corresponds to the unary prefix plus operator in Python. This operation applies the context precision and rounding, so it is *not* an identity operation.

power (*x*, *y* [, *modulo*])

Return '*x* ** *y*' to the *modulo* if given.

The right-hand operand must be a whole number whose integer part (after any exponent has been applied) has no more than 9 digits and whose fractional part (if any) is all zeros before any rounding. The operand may be positive, negative, or zero; if negative, the absolute value of the power is used, and the left-hand operand is inverted (divided into 1) before use.

If the increased precision needed for the intermediate calculations exceeds the capabilities of the implementation then an `InvalidOperation` condition is signaled.

If, when raising to a negative power, an underflow occurs during the division into 1, the operation is not halted at that point but continues.

quantize (*x*, *y*)

Returns a value equal to *x* after rounding and having the exponent of *y*.

Unlike other operations, if the length of the coefficient after the quantize operation would be greater than precision, then an `InvalidOperation` is signaled. This guarantees that, unless there is an error condition, the quantized exponent is always equal to that of the right-hand operand.

Also unlike other operations, quantize never signals Underflow, even if the result is subnormal and inexact.

remainder (*x*, *y*)

Returns the remainder from integer division.

The sign of the result, if non-zero, is the same as that of the original dividend.

remainder_near (*x*, *y*)

Computed the modulo as either a positive or negative value depending on which is closest to zero. For instance, `Decimal(10).remainder_near(6)` returns `Decimal("-2")` which is closer to zero than `Decimal("4")`.

If both are equally close, the one chosen will have the same sign as *self*.

same_quantum (*x*, *y*)

Test whether *x* and *y* have the same exponent or whether both are NaN.

sqrt (*x*)

Return the square root of *x* to full precision.

subtract (*x*, *y*)

Return the difference between *x* and *y*.

to_eng_string ()

Convert to engineering-type string.

Engineering notation has an exponent which is a multiple of 3, so there are up to 3 digits left of the decimal place. For example, converts `Decimal('123E+1')` to `Decimal("1.23E+3")`

to_integral (*x*)

Rounds to the nearest integer without signaling `Inexact` or `Rounded`.

to_sci_string (*x*)

Converts a number to a string using scientific notation.

6.3.4 Signals

Signals represent conditions that arise during computation. Each corresponds to one context flag and one context trap enabler.

The context flag is incremented whenever the condition is encountered. After the computation, flags may be checked for informational purposes (for instance, to determine whether a computation was exact). After checking the flags, be sure to clear all flags before starting the next computation.

If the context's trap enabler is set for the signal, then the condition causes a Python exception to be raised. For example, if the `DivisionByZero` trap is set, then a `DivisionByZero` exception is raised upon encountering the condition.

class Clamped

Altered an exponent to fit representation constraints.

Typically, clamping occurs when an exponent falls outside the context's `Emin` and `Emax` limits. If possible, the exponent is reduced to fit by adding zeroes to the coefficient.

class DecimalException

Base class for other signals and a subclass of `ArithmeticError`.

class DivisionByZero

Signals the division of a non-infinite number by zero.

Can occur with division, modulo division, or when raising a number to a negative power. If this signal is not trapped, returns `Infinity` or `-Infinity` with the sign determined by the inputs to the calculation.

class Inexact

Indicates that rounding occurred and the result is not exact.

Signals when non-zero digits were discarded during rounding. The rounded result is returned. The signal flag or trap is used to detect when results are inexact.

class InvalidOperation

An invalid operation was performed.

Indicates that an operation was requested that does not make sense. If not trapped, returns NaN. Possible causes include:

```
Infinity - Infinity
0 * Infinity
Infinity / Infinity
x % 0
Infinity % x
x._rescale( non-integer )
sqrt(-x) and x > 0
0 ** 0
x ** (non-integer)
x ** Infinity
```

class Overflow

Numerical overflow.

Indicates the exponent is larger than `Emax` after rounding has occurred. If not trapped, the result depends on the rounding mode, either pulling inward to the largest representable finite number or rounding outward to `Infinity`. In either case, `Inexact` and `Rounded` are also signaled.

class Rounded

Rounding occurred though possibly no information was lost.

Signaled whenever rounding discards digits; even if those digits are zero (such as rounding 5.00 to 5.0). If not trapped, returns the result unchanged. This signal is used to detect loss of significant digits.

class Subnormal

Exponent was lower than `Emin` prior to rounding.

Occurs when an operation result is subnormal (the exponent is too small). If not trapped, returns the result unchanged.

class Underflow

Numerical underflow with result rounded to zero.

Occurs when a subnormal result is pushed to zero by rounding. `Inexact` and `Subnormal` are also signaled.

The following table summarizes the hierarchy of signals:

```
exceptions.ArithmeticError(exceptions.StandardError)
    DecimalException
        Clamped
        DivisionByZero(DecimalException, exceptions.ZeroDivisionError)
        Inexact
            Overflow(Inexact, Rounded)
            Underflow(Inexact, Rounded, Subnormal)
        InvalidOperation
        Rounded
        Subnormal
```

6.3.5 Floating Point Notes

Mitigating round-off error with increased precision

The use of decimal floating point eliminates decimal representation error (making it possible to represent 0.1 exactly); however, some operations can still incur round-off error when non-zero digits exceed the fixed precision.

The effects of round-off error can be amplified by the addition or subtraction of nearly offsetting quantities resulting in loss of significance. Knuth provides two instructive examples where rounded floating point arithmetic with insufficient precision causes the breakdown of the associative and distributive properties of addition:

```
# Examples from Seminumerical Algorithms, Section 4.2.2.
>>> from decimal import Decimal, getcontext
>>> getcontext().prec = 8

>>> u, v, w = Decimal(11111113), Decimal(-11111111), Decimal('7.51111111')
>>> (u + v) + w
Decimal("9.5111111")
>>> u + (v + w)
Decimal("10")

>>> u, v, w = Decimal(20000), Decimal(-6), Decimal('6.0000003')
>>> (u*v) + (u*w)
Decimal("0.01")
>>> u * (v+w)
Decimal("0.0060000")
```

The decimal module makes it possible to restore the identities by expanding the precision sufficiently to avoid loss of significance:

```
>>> getcontext().prec = 20
>>> u, v, w = Decimal(11111113), Decimal(-11111111), Decimal('7.51111111')
>>> (u + v) + w
Decimal("9.51111111")
>>> u + (v + w)
Decimal("9.51111111")
>>>
>>> u, v, w = Decimal(20000), Decimal(-6), Decimal('6.0000003')
>>> (u*v) + (u*w)
Decimal("0.0060000")
>>> u * (v+w)
Decimal("0.0060000")
```

Special values

The number system for the decimal module provides special values including NaN, sNaN, -Infinity, Infinity, and two zeroes, +0 and -0.

Infinities can be constructed directly with: `Decimal('Infinity')`. Also, they can arise from dividing by zero when the `DivisionByZero` signal is not trapped. Likewise, when the `Overflow` signal is not trapped, infinity can result from rounding beyond the limits of the largest representable number.

The infinities are signed (affine) and can be used in arithmetic operations where they get treated as very large, indeterminate numbers. For instance, adding a constant to infinity gives another infinite result.

Some operations are indeterminate and return NaN, or if the `InvalidOperation` signal is trapped, raise an exception. For example, `0/0` returns NaN which means “not a number”. This variety of NaN is quiet and, once created, will flow through other computations always resulting in another NaN. This behavior can be useful for a series of computations that occasionally have missing inputs — it allows the calculation to proceed while flagging specific results as invalid.

A variant is `sNaN` which signals rather than remaining quiet after every operation. This is a useful return value when an invalid result needs to interrupt a calculation for special handling.

The signed zeros can result from calculations that underflow. They keep the sign that would have resulted if the calculation had been carried out to greater precision. Since their magnitude is zero, both positive and negative zeros are treated as equal and their sign is informational.

In addition to the two signed zeros which are distinct yet equal, there are various representations of zero with differing precisions yet equivalent in value. This takes a bit of getting used to. For an eye accustomed to normalized floating point representations, it is not immediately obvious that the following calculation returns a value equal to zero:

```
>>> 1 / Decimal('Infinity')
Decimal("0E-10000000026")
```

6.3.6 Working with threads

The `getcontext()` function accesses a different `Context` object for each thread. Having separate thread contexts means that threads may make changes (such as `getcontext().prec=10`) without interfering with other threads.

Likewise, the `setcontext()` function automatically assigns its target to the current thread.

If `setcontext()` has not been called before `getcontext()`, then `getcontext()` will automatically create a new context for use in the current thread.

The new context is copied from a prototype context called *DefaultContext*. To control the defaults so that each thread will use the same values throughout the application, directly modify the *DefaultContext* object. This should be done *before* any threads are started so that there won't be a race condition between threads calling `getcontext()`. For example:

```
# Set applicationwide defaults for all threads about to be launched
DefaultContext.prec = 12
DefaultContext.rounding = ROUND_DOWN
DefaultContext.traps = ExtendedContext.traps.copy()
DefaultContext.traps[InvalidOperation] = 1
setcontext(DefaultContext)

# Afterwards, the threads can be started
t1.start()
t2.start()
t3.start()
. . .
```

6.3.7 Recipes

Here are a few recipes that serve as utility functions and that demonstrate ways to work with the `Decimal` class:

```

def moneyfmt(value, places=2, curr='', sep=',', dp='.',
             pos='', neg='-', trailneg=''):
    """Convert Decimal to a money formatted string.

    places:  required number of places after the decimal point
    curr:    optional currency symbol before the sign (may be blank)
    sep:     optional grouping separator (comma, period, space, or blank)
    dp:      decimal point indicator (comma or period)
             only specify as blank when places is zero
    pos:     optional sign for positive numbers: '+', space or blank
    neg:     optional sign for negative numbers: '-', '(', space or blank
    trailneg: optional trailing minus indicator: '- ', ' )', space or blank

    >>> d = Decimal('-1234567.8901')
    >>> moneyfmt(d, curr='$')
    '-$1,234,567.89'
    >>> moneyfmt(d, places=0, sep='.', dp='', neg='', trailneg='-')
    '1.234.568-'
    >>> moneyfmt(d, curr='$', neg='(', trailneg=')')
    '($1,234,567.89)'
    >>> moneyfmt(Decimal(123456789), sep=' ')
    '123 456 789.00'
    >>> moneyfmt(Decimal('-0.02'), neg='<', trailneg='>')
    '<.02>'

    """
    q = Decimal((0, (1,), -places))    # 2 places --> '0.01'
    sign, digits, exp = value.quantize(q).as_tuple()
    assert exp == -places
    result = []
    digits = map(str, digits)
    build, next = result.append, digits.pop
    if sign:
        build(trailneg)
    for i in range(places):
        if digits:
            build(next())
        else:
            build('0')
    build(dp)
    i = 0
    while digits:
        build(next())
        i += 1
        if i == 3 and digits:
            i = 0
            build(sep)
    build(curr)
    if sign:
        build(neg)
    else:
        build(pos)
    result.reverse()
    return ''.join(result)

def pi():
    """Compute Pi to the current precision.

    >>> print pi()
    3.141592653589793238462643383

```

6.3.8 Decimal FAQ

Q. It is cumbersome to type `decimal.Decimal('1234.5')`. Is there a way to minimize typing when using the interactive interpreter?

A. Some users abbreviate the constructor to just a single letter:

```
>>> D = decimal.Decimal
>>> D('1.23') + D('3.45')
Decimal("4.68")
```

Q. In a fixed-point application with two decimal places, some inputs have many places and need to be rounded. Others are not supposed to have excess digits and need to be validated. What methods should be used?

A. The `quantize()` method rounds to a fixed number of decimal places. If the `Inexact` trap is set, it is also useful for validation:

```
>>> TWOPLACES = Decimal(10) ** -2          # same as Decimal('0.01')

>>> # Round to two places
>>> Decimal("3.214").quantize(TWOPLACES)
Decimal("3.21")

>>> # Validate that a number does not exceed two places
>>> Decimal("3.21").quantize(TWOPLACES, context=Context(traps=[Inexact]))
Decimal("3.21")

>>> Decimal("3.214").quantize(TWOPLACES, context=Context(traps=[Inexact]))
Traceback (most recent call last):
...
Inexact: Changed in rounding
```

Q. Once I have valid two place inputs, how do I maintain that invariant throughout an application?

A. Some operations like addition and subtraction automatically preserve fixed point. Others, like multiplication and division, change the number of decimal places and need to be followed-up with a `quantize()` step.

Q. There are many ways to express the same value. The numbers 200, 200.000, 2E2, and .02E+4 all have the same value at various precisions. Is there a way to transform them to a single recognizable canonical value?

A. The `normalize()` method maps all equivalent values to a single representative:

```
>>> values = map(Decimal, '200 200.000 2E2 .02E+4'.split())
>>> [v.normalize() for v in values]
[Decimal("2E+2"), Decimal("2E+2"), Decimal("2E+2"), Decimal("2E+2")]
```

Q. Some decimal values always print with exponential notation. Is there a way to get a non-exponential representation?

A. For some values, exponential notation is the only way to express the number of significant places in the coefficient. For example, expressing 5.0E+3 as 5000 keeps the value constant but cannot show the original's two-place significance.

Q. Is there a way to convert a regular float to a `Decimal`?

A. Yes, all binary floating point numbers can be exactly expressed as a `Decimal`. An exact conversion may take more precision than intuition would suggest, so trapping `Inexact` will signal a need for more precision:

```

def floatToDecimal(f):
    "Convert a floating point number to a Decimal with no loss of information"
    # Transform (exactly) a float to a mantissa (0.5 <= abs(m) < 1.0) and an
    # exponent. Double the mantissa until it is an integer. Use the integer
    # mantissa and exponent to compute an equivalent Decimal. If this cannot
    # be done exactly, then retry with more precision.

    mantissa, exponent = math.frexp(f)
    while mantissa != int(mantissa):
        mantissa *= 2.0
        exponent -= 1
    mantissa = int(mantissa)

    oldcontext = getcontext()
    setcontext(Context(traps=[Inexact]))
    try:
        while True:
            try:
                return mantissa * Decimal(2) ** exponent
            except Inexact:
                getcontext().prec += 1
    finally:
        setcontext(oldcontext)

```

Q. Why isn't the `floatToDecimal()` routine included in the module?

A. There is some question about whether it is advisable to mix binary and decimal floating point. Also, its use requires some care to avoid the representation issues associated with binary floating point:

```

>>> floatToDecimal(1.1)
Decimal("1.1000000000000000088817841970012523233890533447265625")

```

Q. Within a complex calculation, how can I make sure that I haven't gotten a spurious result because of insufficient precision or rounding anomalies.

A. The decimal module makes it easy to test results. A best practice is to re-run calculations using greater precision and with various rounding modes. Widely differing results indicate insufficient precision, rounding mode issues, ill-conditioned inputs, or a numerically unstable algorithm.

Q. I noticed that context precision is applied to the results of operations but not to the inputs. Is there anything to watch out for when mixing values of different precisions?

A. Yes. The principle is that all values are considered to be exact and so is the arithmetic on those values. Only the results are rounded. The advantage for inputs is that "what you type is what you get". A disadvantage is that the results can look odd if you forget that the inputs haven't been rounded:

```

>>> getcontext().prec = 3
>>> Decimal('3.104') + D('2.104')
Decimal("5.21")
>>> Decimal('3.104') + D('0.000') + D('2.104')
Decimal("5.20")

```

The solution is either to increase precision or to force rounding of inputs using the unary plus operation:

```
>>> getcontext().prec = 3
>>> +Decimal('1.23456789')      # unary plus triggers rounding
Decimal("1.23")
```

Alternatively, inputs can be rounded upon creation using the `Context.create_decimal()` method:

```
>>> Context(prec=5, rounding=ROUND_DOWN).create_decimal('1.2345678')
Decimal("1.2345")
```

6.4 random — Generate pseudo-random numbers

This module implements pseudo-random number generators for various distributions.

For integers, uniform selection from a range. For sequences, uniform selection of a random element, a function to generate a random permutation of a list in-place, and a function for random sampling without replacement.

On the real line, there are functions to compute uniform, normal (Gaussian), lognormal, negative exponential, gamma, and beta distributions. For generating distributions of angles, the von Mises distribution is available.

Almost all module functions depend on the basic function `random()`, which generates a random float uniformly in the semi-open range `[0.0, 1.0)`. Python uses the Mersenne Twister as the core generator. It produces 53-bit precision floats and has a period of $2^{19937}-1$. The underlying implementation in C is both fast and threadsafe. The Mersenne Twister is one of the most extensively tested random number generators in existence. However, being completely deterministic, it is not suitable for all purposes, and is completely unsuitable for cryptographic purposes.

The functions supplied by this module are actually bound methods of a hidden instance of the `random.Random` class. You can instantiate your own instances of `Random` to get generators that don't share state. This is especially useful for multi-threaded programs, creating a different instance of `Random` for each thread, and using the `jumpahead()` method to make it likely that the generated sequences seen by each thread don't overlap.

Class `Random` can also be subclassed if you want to use a different basic generator of your own devising: in that case, override the `random()`, `seed()`, `getstate()`, `setstate()` and `jumpahead()` methods. Optionally, a new generator can supply a `getrandbits()` method — this allows `randrange()` to produce selections over an arbitrarily large range. New in version 2.4: the `getrandbits()` method.

As an example of subclassing, the `random` module provides the `WichmannHill` class that implements an alternative generator in pure Python. The class provides a backward compatible way to reproduce results from earlier versions of Python, which used the Wichmann-Hill algorithm as the core generator. Note that this Wichmann-Hill generator can no longer be recommended: its period is too short by contemporary standards, and the sequence generated is known to fail some stringent randomness tests. See the references below for a recent variant that repairs these flaws. Changed in version 2.3: Substituted MersenneTwister for Wichmann-Hill.

Bookkeeping functions:

seed (`[x]`)

Initialize the basic random number generator. Optional argument `x` can be any hashable object. If `x` is omitted or `None`, current system time is used; current system time is also used to initialize the generator when the module is first imported. If randomness sources are provided by the operating system, they are used instead of the system time (see the `os.urandom()` function for details on availability). Changed in version 2.4: formerly, operating system resources were not used. If `x` is not `None` or an int or long, `hash(x)` is used instead. If `x` is an int or long, `x` is used directly.

getstate ()

Return an object capturing the current internal state of the generator. This object can be passed to `setstate()` to restore the state. New in version 2.1.

setstate (*state*)

state should have been obtained from a previous call to `getstate()`, and `setstate()` restores the internal state of the generator to what it was at the time `setstate()` was called. New in version 2.1.

jumpahead (*n*)

Change the internal state to one different from and likely far away from the current state. *n* is a non-negative integer which is used to scramble the current state vector. This is most useful in multi-threaded programs, in conjunction with multiple instances of the `Random` class: `setstate()` or `seed()` can be used to force all instances into the same internal state, and then `jumpahead()` can be used to force the instances' states far apart. New in version 2.1. Changed in version 2.3: Instead of jumping to a specific state, *n* steps ahead, `jumpahead(n)` jumps to another state likely to be separated by many steps.

getrandbits (*k*)

Returns a python `long` int with *k* random bits. This method is supplied with the MersenneTwister generator and some other generators may also provide it as an optional part of the API. When available, `getrandbits()` enables `randrange()` to handle arbitrarily large ranges. New in version 2.4.

Functions for integers:

randrange ([*start*,] *stop* [, *step*])

Return a randomly selected element from `range(start, stop, step)`. This is equivalent to `choice(range(start, stop, step))`, but doesn't actually build a range object. New in version 1.5.2.

randint (*a*, *b*)

Return a random integer *N* such that $a \leq N \leq b$.

Functions for sequences:

choice (*seq*)

Return a random element from the non-empty sequence *seq*. If *seq* is empty, raises `IndexError`.

shuffle (*x* [, *random*])

Shuffle the sequence *x* in place. The optional argument *random* is a 0-argument function returning a random float in [0.0, 1.0); by default, this is the function `random()`.

Note that for even rather small `len(x)`, the total number of permutations of *x* is larger than the period of most random number generators; this implies that most permutations of a long sequence can never be generated.

sample (*population*, *k*)

Return a *k* length list of unique elements chosen from the population sequence. Used for random sampling without replacement. New in version 2.3.

Returns a new list containing elements from the population while leaving the original population unchanged. The resulting list is in selection order so that all sub-slices will also be valid random samples. This allows raffle winners (the sample) to be partitioned into grand prize and second place winners (the subslices).

Members of the population need not be hashable or unique. If the population contains repeats, then each occurrence is a possible selection in the sample.

To choose a sample from a range of integers, use an `xrange()` object as an argument. This is especially fast and space efficient for sampling from a large population: `sample(xrange(10000000), 60)`.

The following functions generate specific real-valued distributions. Function parameters are named after the corresponding variables in the distribution's equation, as used in common mathematical practice; most of these equations can be found in any statistics text.

random ()

Return the next random floating point number in the range [0.0, 1.0).

uniform (*a*, *b*)

Return a random real number *N* such that $a \leq N < b$.

betavariate (*alpha*, *beta*)

Beta distribution. Conditions on the parameters are *alpha* > 0 and *beta* > 0. Returned values range between 0 and 1.

expovariate (*lambd*)

Exponential distribution. *lambd* is 1.0 divided by the desired mean. (The parameter would be called “lambda”, but that is a reserved word in Python.) Returned values range from 0 to positive infinity.

gammavariate (*alpha*, *beta*)

Gamma distribution. (*Not* the gamma function!) Conditions on the parameters are *alpha* > 0 and *beta* > 0.

gauss (*mu*, *sigma*)

Gaussian distribution. *mu* is the mean, and *sigma* is the standard deviation. This is slightly faster than the `normalvariate()` function defined below.

lognormvariate (*mu*, *sigma*)

Log normal distribution. If you take the natural logarithm of this distribution, you’ll get a normal distribution with mean *mu* and standard deviation *sigma*. *mu* can have any value, and *sigma* must be greater than zero.

normalvariate (*mu*, *sigma*)

Normal distribution. *mu* is the mean, and *sigma* is the standard deviation.

vonmisesvariate (*mu*, *kappa*)

mu is the mean angle, expressed in radians between 0 and 2π , and *kappa* is the concentration parameter, which must be greater than or equal to zero. If *kappa* is equal to zero, this distribution reduces to a uniform random angle over the range 0 to 2π .

paretovariate (*alpha*)

Pareto distribution. *alpha* is the shape parameter.

weibullvariate (*alpha*, *beta*)

Weibull distribution. *alpha* is the scale parameter and *beta* is the shape parameter.

Alternative Generators:

class WichmannHill ([*seed*])

Class that implements the Wichmann-Hill algorithm as the core generator. Has all of the same methods as `Random` plus the `whseed()` method described below. Because this class is implemented in pure Python, it is not threadsafe and may require locks between calls. The period of the generator is 6,953,607,871,644 which is small enough to require care that two independent random sequences do not overlap.

whseed ([*x*])

This is obsolete, supplied for bit-level compatibility with versions of Python prior to 2.1. See `seed()` for details. `whseed()` does not guarantee that distinct integer arguments yield distinct internal states, and can yield no more than about 2^{24} distinct internal states in all.

class SystemRandom ([*seed*])

Class that uses the `os.urandom()` function for generating random numbers from sources provided by the operating system. Not available on all systems. Does not rely on software state and sequences are not reproducible. Accordingly, the `seed()` and `jumpahead()` methods have no effect and are ignored. The `getstate()` and `setstate()` methods raise `NotImplementedError` if called. New in version 2.4.

Examples of basic usage:

```

>>> random.random()          # Random float x, 0.0 <= x < 1.0
0.37444887175646646
>>> random.uniform(1, 10)    # Random float x, 1.0 <= x < 10.0
1.1800146073117523
>>> random.randint(1, 10)    # Integer from 1 to 10, endpoints included
7
>>> random.randrange(0, 101, 2) # Even integer from 0 to 100
26
>>> random.choice('abcdefghij') # Choose a random element
'c'

>>> items = [1, 2, 3, 4, 5, 6, 7]
>>> random.shuffle(items)
>>> items
[7, 3, 2, 5, 6, 4, 1]

>>> random.sample([1, 2, 3, 4, 5], 3) # Choose 3 elements
[4, 1, 5]

```

See Also:

M. Matsumoto and T. Nishimura, “Mersenne Twister: A 623-dimensionally equidistributed uniform pseudorandom number generator”, *ACM Transactions on Modeling and Computer Simulation* Vol. 8, No. 1, January pp.3-30 1998.

Wichmann, B. A. & Hill, I. D., “Algorithm AS 183: An efficient and portable pseudo-random number generator”, *Applied Statistics* 31 (1982) 188-190.

<http://www.npl.co.uk/ssfm/download/abstracts.html#196>

A modern variation of the Wichmann-Hill generator that greatly increases the period, and passes now-standard statistical tests that the original generator failed.

6.5 `itertools` — Functions creating iterators for efficient looping

New in version 2.3.

This module implements a number of iterator building blocks inspired by constructs from the Haskell and SML programming languages. Each has been recast in a form suitable for Python.

The module standardizes a core set of fast, memory efficient tools that are useful by themselves or in combination. Standardization helps avoid the readability and reliability problems which arise when many different individuals create their own slightly varying implementations, each with their own quirks and naming conventions.

The tools are designed to combine readily with one another. This makes it easy to construct more specialized tools succinctly and efficiently in pure Python.

For instance, SML provides a tabulation tool: `tabulate(f)` which produces a sequence `f(0), f(1), ...`. This toolbox provides `imap()` and `count()` which can be combined to form `imap(f, count())` and produce an equivalent result.

Likewise, the functional tools are designed to work well with the high-speed functions provided by the [operator](#) module.

The module author welcomes suggestions for other basic building blocks to be added to future versions of the module.

Whether cast in pure python form or compiled code, tools that use iterators are more memory efficient (and faster) than their list based counterparts. Adopting the principles of just-in-time manufacturing, they create data when and

where needed instead of consuming memory with the computer equivalent of “inventory”.

The performance advantage of iterators becomes more acute as the number of elements increases – at some point, lists grow large enough to severely impact memory cache performance and start running slowly.

See Also:

The Standard ML Basis Library, [The Standard ML Basis Library](#).

Haskell, A Purely Functional Language, [Definition of Haskell and the Standard Libraries](#).

6.5.1 Itertool functions

The following module functions all construct and return iterators. Some provide streams of infinite length, so they should only be accessed by functions or loops that truncate the stream.

chain (*iterables)

Make an iterator that returns elements from the first iterable until it is exhausted, then proceeds to the next iterable, until all of the iterables are exhausted. Used for treating consecutive sequences as a single sequence. Equivalent to:

```
def chain(*iterables):
    for it in iterables:
        for element in it:
            yield element
```

count ([*n*])

Make an iterator that returns consecutive integers starting with *n*. If not specified *n* defaults to zero. Does not currently support python long integers. Often used as an argument to `imap()` to generate consecutive data points. Also, used with `izip()` to add sequence numbers. Equivalent to:

```
def count(n=0):
    while True:
        yield n
        n += 1
```

Note, `count()` does not check for overflow and will return negative numbers after exceeding `sys.maxint`. This behavior may change in the future.

cycle (iterable)

Make an iterator returning elements from the iterable and saving a copy of each. When the iterable is exhausted, return elements from the saved copy. Repeats indefinitely. Equivalent to:

```
def cycle(iterable):
    saved = []
    for element in iterable:
        yield element
        saved.append(element)
    while saved:
        for element in saved:
            yield element
```

Note, this member of the toolkit may require significant auxiliary storage (depending on the length of the iterable).

dropwhile (*predicate, iterable*)

Make an iterator that drops elements from the iterable as long as the predicate is true; afterwards, returns every element. Note, the iterator does not produce *any* output until the predicate first becomes false, so it may have a lengthy start-up time. Equivalent to:

```
def dropwhile(predicate, iterable):
    iterable = iter(iterable)
    for x in iterable:
        if not predicate(x):
            yield x
            break
    for x in iterable:
        yield x
```

groupby (*iterable*[, *key*])

Make an iterator that returns consecutive keys and groups from the *iterable*. The *key* is a function computing a key value for each element. If not specified or is None, *key* defaults to an identity function and returns the element unchanged. Generally, the iterable needs to already be sorted on the same key function.

The returned group is itself an iterator that shares the underlying iterable with `groupby()`. Because the source is shared, when the `groupby` object is advanced, the previous group is no longer visible. So, if that data is needed later, it should be stored as a list:

```
groups = []
uniquekeys = []
for k, g in groupby(data, keyfunc):
    groups.append(list(g))      # Store group iterator as a list
    uniquekeys.append(k)
```

`groupby()` is equivalent to:

```
class groupby(object):
    def __init__(self, iterable, key=None):
        if key is None:
            key = lambda x: x
        self.keyfunc = key
        self.it = iter(iterable)
        self.tgtkey = self.currkey = self.currvalue = xrange(0)
    def __iter__(self):
        return self
    def next(self):
        while self.currkey == self.tgtkey:
            self.currvalue = self.it.next() # Exit on StopIteration
            self.currkey = self.keyfunc(self.currvalue)
            self.tgtkey = self.currkey
        return (self.currkey, self._grouper(self.tgtkey))
    def _grouper(self, tgtkey):
        while self.currkey == tgtkey:
            yield self.currvalue
            self.currvalue = self.it.next() # Exit on StopIteration
            self.currkey = self.keyfunc(self.currvalue)
```

New in version 2.4.

ifilter (*predicate, iterable*)

Make an iterator that filters elements from iterable returning only those for which the predicate is `True`. If *predicate* is `None`, return the items that are true. Equivalent to:

```
def ifilter(predicate, iterable):
    if predicate is None:
        predicate = bool
    for x in iterable:
        if predicate(x):
            yield x
```

`ifilterfalse` (*predicate, iterable*)

Make an iterator that filters elements from iterable returning only those for which the predicate is `False`. If *predicate* is `None`, return the items that are false. Equivalent to:

```
def ifilterfalse(predicate, iterable):
    if predicate is None:
        predicate = bool
    for x in iterable:
        if not predicate(x):
            yield x
```

`imap` (*function, *iterables*)

Make an iterator that computes the function using arguments from each of the iterables. If *function* is set to `None`, then `imap()` returns the arguments as a tuple. Like `map()` but stops when the shortest iterable is exhausted instead of filling in `None` for shorter iterables. The reason for the difference is that infinite iterator arguments are typically an error for `map()` (because the output is fully evaluated) but represent a common and useful way of supplying arguments to `imap()`. Equivalent to:

```
def imap(function, *iterables):
    iterables = map(iter, iterables)
    while True:
        args = [i.next() for i in iterables]
        if function is None:
            yield tuple(args)
        else:
            yield function(*args)
```

`islice` (*iterable, [start,] stop [, step]*)

Make an iterator that returns selected elements from the iterable. If *start* is non-zero, then elements from the iterable are skipped until *start* is reached. Afterward, elements are returned consecutively unless *step* is set higher than one which results in items being skipped. If *stop* is `None`, then iteration continues until the iterator is exhausted, if at all; otherwise, it stops at the specified position. Unlike regular slicing, `islice()` does not support negative values for *start*, *stop*, or *step*. Can be used to extract related fields from data where the internal structure has been flattened (for example, a multi-line report may list a name field on every third line). Equivalent to:

```
def islice(iterable, *args):
    s = slice(*args)
    it = iter(xrange(s.start or 0, s.stop or sys.maxint, s.step or 1))
    nexti = it.next()
    for i, element in enumerate(iterable):
        if i == nexti:
            yield element
            nexti = it.next()
```

If *start* is None, then iteration starts at zero. If *step* is None, then the step defaults to one. Changed in version 2.5: accept None values for default *start* and *step*.

izip(**iterables*)

Make an iterator that aggregates elements from each of the iterables. Like `zip()` except that it returns an iterator instead of a list. Used for lock-step iteration over several iterables at a time. Equivalent to:

```
def izip(*iterables):
    iterables = map(iter, iterables)
    while iterables:
        result = [it.next() for it in iterables]
        yield tuple(result)
```

Changed in version 2.4: When no iterables are specified, returns a zero length iterator instead of raising a `TypeError` exception.

Note, the left-to-right evaluation order of the iterables is guaranteed. This makes possible an idiom for clustering a data series into n-length groups using `'izip(*[iter(s)]*n)'`. For data that doesn't fit n-length groups exactly, the last tuple can be pre-padded with fill values using `'izip(*[chain(s, [None]*(n-1))]*n)'`.

Note, when `izip()` is used with unequal length inputs, subsequent iteration over the longer iterables cannot reliably be continued after `izip()` terminates. Potentially, up to one entry will be missing from each of the left-over iterables. This occurs because a value is fetched from each iterator in-turn, but the process ends when one of the iterators terminates. This leaves the last fetched values in limbo (they cannot be returned in a final, incomplete tuple and they are cannot be pushed back into the iterator for retrieval with `it.next()`). In general, `izip()` should only be used with unequal length inputs when you don't care about trailing, unmatched values from the longer iterables.

repeat(*object*[, *times*])

Make an iterator that returns *object* over and over again. Runs indefinitely unless the *times* argument is specified. Used as argument to `imap()` for invariant parameters to the called function. Also used with `izip()` to create an invariant part of a tuple record. Equivalent to:

```
def repeat(object, times=None):
    if times is None:
        while True:
            yield object
    else:
        for i in xrange(times):
            yield object
```

starmap(*function*, *iterable*)

Make an iterator that computes the function using arguments tuples obtained from the iterable. Used instead of `imap()` when argument parameters are already grouped in tuples from a single iterable (the data has been “pre-zipped”). The difference between `imap()` and `starmap()` parallels the distinction between

`function(a,b)` and `function(*c)`. Equivalent to:

```
def starmap(function, iterable):
    iterable = iter(iterable)
    while True:
        yield function(*iterable.next())
```

`takewhile` (*predicate, iterable*)

Make an iterator that returns elements from the iterable as long as the predicate is true. Equivalent to:

```
def takewhile(predicate, iterable):
    for x in iterable:
        if predicate(x):
            yield x
        else:
            break
```

`tee` (*iterable* [, *n=2*])

Return *n* independent iterators from a single iterable. The case where *n*==2 is equivalent to:

```
def tee(iterable):
    def gen(next, data={}, cnt=[0]):
        for i in count():
            if i == cnt[0]:
                item = data[i] = next()
                cnt[0] += 1
            else:
                item = data.pop(i)
            yield item
    it = iter(iterable)
    return (gen(it.next), gen(it.next))
```

Note, once `tee()` has made a split, the original *iterable* should not be used anywhere else; otherwise, the *iterable* could get advanced without the tee objects being informed.

Note, this member of the toolkit may require significant auxiliary storage (depending on how much temporary data needs to be stored). In general, if one iterator is going to use most or all of the data before the other iterator, it is faster to use `list()` instead of `tee()`. New in version 2.4.

6.5.2 Examples

The following examples show common uses for each tool and demonstrate ways they can be combined.

```

>>> amounts = [120.15, 764.05, 823.14]
>>> for checknum, amount in izip(count(1200), amounts):
...     print 'Check %d is for $%.2f' % (checknum, amount)
...
Check 1200 is for $120.15
Check 1201 is for $764.05
Check 1202 is for $823.14

>>> import operator
>>> for cube in imap(operator.pow, xrange(1,5), repeat(3)):
...     print cube
...
1
8
27
64

>>> reportlines = ['EuroPython', 'Roster', '', 'alex', '', 'laura',
...                 '', 'martin', '', 'walter', '', 'mark']
>>> for name in islice(reportlines, 3, None, 2):
...     print name.title()
...
Alex
Laura
Martin
Walter
Mark

# Show a dictionary sorted and grouped by value
>>> from operator import itemgetter
>>> d = dict(a=1, b=2, c=1, d=2, e=1, f=2, g=3)
>>> di = sorted(d.iteritems(), key=itemgetter(1))
>>> for k, g in groupby(di, key=itemgetter(1)):
...     print k, map(itemgetter(0), g)
...
1 ['a', 'c', 'e']
2 ['b', 'd', 'f']
3 ['g']

# Find runs of consecutive numbers using groupby. The key to the solution
# is differencing with a range so that consecutive numbers all appear in
# same group.
>>> data = [ 1, 4,5,6, 10, 15,16,17,18, 22, 25,26,27,28]
>>> for k, g in groupby(enumerate(data), lambda (i,x):i-x):
...     print map(operator.itemgetter(1), g)
...
[1]
[4, 5, 6]
[10]
[15, 16, 17, 18]
[22]
[25, 26, 27, 28]

```

6.5.3 Recipes

This section shows recipes for creating an extended toolset using the existing `itertools` as building blocks.

The extended tools offer the same high performance as the underlying toolset. The superior memory performance is kept by processing elements one at a time rather than bringing the whole iterable into memory all at once. Code volume is kept small by linking the tools together in a functional style which helps eliminate temporary variables. High speed is retained by preferring “vectorized” building blocks over the use of for-loops and generators which incur interpreter overhead.

```

def take(n, seq):
    return list(islice(seq, n))

def enumerate(iterable):
    return izip(count(), iterable)

def tabulate(function):
    "Return function(0), function(1), ..."
    return imap(function, count())

def iteritems(mapping):
    return izip(mapping.iterkeys(), mapping.itervalues())

def nth(iterable, n):
    "Returns the nth item or raise StopIteration"
    return islice(iterable, n, None).next()

def all(seq, pred=None):
    "Returns True if pred(x) is true for every element in the iterable"
    for elem in ifilterfalse(pred, seq):
        return False
    return True

def any(seq, pred=None):
    "Returns True if pred(x) is true for at least one element in the iterable"
    for elem in ifilter(pred, seq):
        return True
    return False

def no(seq, pred=None):
    "Returns True if pred(x) is false for every element in the iterable"
    for elem in ifilter(pred, seq):
        return False
    return True

def quantify(seq, pred=None):
    "Count how many times the predicate is true in the sequence"
    return sum(imap(pred, seq))

def padnone(seq):
    """Returns the sequence elements and then returns None indefinitely.

    Useful for emulating the behavior of the built-in map() function.
    """
    return chain(seq, repeat(None))

def ncycles(seq, n):
    "Returns the sequence elements n times"
    return chain(*repeat(seq, n))

def dotproduct(vec1, vec2):
    return sum(imap(operator.mul, vec1, vec2))

def flatten(listOfLists):
    return list(chain(*listOfLists))

def repeatfunc(func, times=None, *args):
    """Repeat calls to func with specified arguments.

    Example: repeatfunc(random.random)
    """
    if times is None:
        return starmap(func, repeat(args))
    else:
        return starmap(func, repeat(args, times))

```


6.6 `functools` — Higher order functions and operations on callable objects.

New in version 2.5.

The `functools` module is for higher-order functions: functions that act on or return other functions. In general, any callable object can be treated as a function for the purposes of this module.

The `functools` module defines the following function:

`partial(func[, *args][, **keywords])`

Return a new `partial` object which when called will behave like `func` called with the positional arguments `args` and keyword arguments `keywords`. If more arguments are supplied to the call, they are appended to `args`. If additional keyword arguments are supplied, they extend and override `keywords`. Roughly equivalent to:

```
def partial(func, *args, **keywords):
    def newfunc(*fargs, **fkeywords):
        newkeywords = keywords.copy()
        newkeywords.update(fkeywords)
        return func(*(args + fargs), **newkeywords)
    newfunc.func = func
    newfunc.args = args
    newfunc.keywords = keywords
    return newfunc
```

The `partial` is used for partial function application which “freezes” some portion of a function’s arguments and/or keywords resulting in a new object with a simplified signature. For example, `partial` can be used to create a callable that behaves like the `int` function where the *base* argument defaults to two:

```
>>> basetwo = partial(int, base=2)
>>> basetwo.__doc__ = 'Convert base 2 string to an int.'
>>> basetwo('10010')
18
```

`update_wrapper(wrapper, wrapped[, assigned][, updated])`

Update a *wrapper* function to look like the *wrapped* function. The optional arguments are tuples to specify which attributes of the original function are assigned directly to the matching attributes on the wrapper function and which attributes of the wrapper function are updated with the corresponding attributes from the original function. The default values for these arguments are the module level constants `WRAPPER_ASSIGNMENTS` (which assigns to the wrapper function’s `__name__`, `__module__` and `__doc__`, the documentation string) and `WRAPPER_UPDATES` (which updates the wrapper function’s `__dict__`, i.e. the instance dictionary).

The main intended use for this function is in decorator functions which wrap the decorated function and return the wrapper. If the wrapper function is not updated, the metadata of the returned function will reflect the wrapper definition rather than the original function definition, which is typically less than helpful.

`wraps(wrapped[, assigned][, updated])`

This is a convenience function for invoking `partial(update_wrapper, wrapped=wrapped, assigned=assigned, updated=updated)` as a function decorator when defining a wrapper function. For example:

```

>>> def my_decorator(f):
...     @wraps(f)
...     def wrapper(*args, **kwds):
...         print 'Calling decorated function'
...         return f(*args, **kwds)
...     return wrapper
...
>>> @my_decorator
... def example():
...     """Docstring"""
...     print 'Called example function'
...
>>> example()
Calling decorated function
Called example function
>>> example.__name__
'example'
>>> example.__doc__
'Docstring'

```

Without the use of this decorator factory, the name of the example function would have been 'wrapper', and the docstring of the original example() would have been lost.

6.6.1 partial Objects

partial objects are callable objects created by partial(). They have three read-only attributes:

func

A callable object or function. Calls to the partial object will be forwarded to func with new arguments and keywords.

args

The leftmost positional arguments that will be prepended to the positional arguments provided to a partial object call.

keywords

The keyword arguments that will be supplied when the partial object is called.

partial objects are like function objects in that they are callable, weak referencable, and can have attributes. There are some important differences. For instance, the __name__ and __doc__ attributes are not created automatically. Also, partial objects defined in classes behave like static methods and do not transform into bound methods during instance attribute look-up.

6.7 operator — Standard operators as functions.

The operator module exports a set of functions implemented in C corresponding to the intrinsic operators of Python. For example, operator.add(x, y) is equivalent to the expression x+y. The function names are those used for special class methods; variants without leading and trailing '__' are also provided for convenience.

The functions fall into categories that perform object comparisons, logical operations, mathematical operations, sequence operations, and abstract type tests.

The object comparison functions are useful for all objects, and are named after the rich comparison operators they support:

```

lt(a, b)
le(a, b)
eq(a, b)
ne(a, b)
ge(a, b)
gt(a, b)
__lt__(a, b)
__le__(a, b)
__eq__(a, b)
__ne__(a, b)
__ge__(a, b)
__gt__(a, b)

```

Perform “rich comparisons” between a and b . Specifically, `lt(a, b)` is equivalent to $a < b$, `le(a, b)` is equivalent to $a \leq b$, `eq(a, b)` is equivalent to $a == b$, `ne(a, b)` is equivalent to $a != b$, `gt(a, b)` is equivalent to $a > b$ and `ge(a, b)` is equivalent to $a \geq b$. Note that unlike the built-in `cmp()`, these functions can return any value, which may or may not be interpretable as a Boolean value. See the [Python Reference Manual](#) for more information about rich comparisons. New in version 2.2.

The logical operations are also generally applicable to all objects, and support truth tests, identity tests, and boolean operations:

```

not_(o)
__not__(o)

```

Return the outcome of `not o`. (Note that there is no `__not__()` method for object instances; only the interpreter core defines this operation. The result is affected by the `__nonzero__()` and `__len__()` methods.)

```

truth(o)

```

Return `True` if o is true, and `False` otherwise. This is equivalent to using the `bool` constructor.

```

is_(a, b)

```

Return a is b . Tests object identity. New in version 2.3.

```

is_not(a, b)

```

Return a is not b . Tests object identity. New in version 2.3.

The mathematical and bitwise operations are the most numerous:

```

abs(o)

```

```

__abs__(o)

```

Return the absolute value of o .

```

add(a, b)

```

```

__add__(a, b)

```

Return $a + b$, for a and b numbers.

```

and_(a, b)

```

```

__and__(a, b)

```

Return the bitwise and of a and b .

```

div(a, b)

```

```

__div__(a, b)

```

Return a / b when `__future__.division` is not in effect. This is also known as “classic” division.

```

floordiv(a, b)

```

```

__floordiv__(a, b)

```

Return $a // b$. New in version 2.2.

```

inv(o)

```

```

invert(o)

```

```

__inv__(o)

```

__invert__ (*o*)
Return the bitwise inverse of the number *o*. This is equivalent to $\sim o$. The names `invert()` and `__invert__` (*o*) were added in Python 2.0.

lshift (*a*, *b*)
__lshift__ (*a*, *b*)
Return *a* shifted left by *b*.

mod (*a*, *b*)
__mod__ (*a*, *b*)
Return $a \% b$.

mul (*a*, *b*)
__mul__ (*a*, *b*)
Return $a * b$, for *a* and *b* numbers.

neg (*o*)
__neg__ (*o*)
Return *o* negated.

or_ (*a*, *b*)
__or__ (*a*, *b*)
Return the bitwise or of *a* and *b*.

pos (*o*)
__pos__ (*o*)
Return *o* positive.

pow (*a*, *b*)
__pow__ (*a*, *b*)
Return $a ** b$, for *a* and *b* numbers. New in version 2.3.

rshift (*a*, *b*)
__rshift__ (*a*, *b*)
Return *a* shifted right by *b*.

sub (*a*, *b*)
__sub__ (*a*, *b*)
Return $a - b$.

truediv (*a*, *b*)
__truediv__ (*a*, *b*)
Return a / b when `__future__.division` is in effect. This is also known as “true” division. New in version 2.2.

xor (*a*, *b*)
__xor__ (*a*, *b*)
Return the bitwise exclusive or of *a* and *b*.

index (*a*)
__index__ (*a*)
Return *a* converted to an integer. Equivalent to $a.\text{__index__}()$. New in version 2.5.

Operations which work with sequences include:

concat (*a*, *b*)
__concat__ (*a*, *b*)
Return $a + b$ for *a* and *b* sequences.

contains (*a*, *b*)
__contains__ (*a*, *b*)
Return the outcome of the test $b \text{ in } a$. Note the reversed operands. The name `__contains__()` was added

in Python 2.0.

countOf (*a*, *b*)

Return the number of occurrences of *b* in *a*.

delitem (*a*, *b*)

__delitem__ (*a*, *b*)

Remove the value of *a* at index *b*.

delslice (*a*, *b*, *c*)

__delslice__ (*a*, *b*, *c*)

Delete the slice of *a* from index *b* to index *c*-1.

getitem (*a*, *b*)

__getitem__ (*a*, *b*)

Return the value of *a* at index *b*.

getslice (*a*, *b*, *c*)

__getslice__ (*a*, *b*, *c*)

Return the slice of *a* from index *b* to index *c*-1.

indexOf (*a*, *b*)

Return the index of the first of occurrence of *b* in *a*.

repeat (*a*, *b*)

__repeat__ (*a*, *b*)

Return *a* * *b* where *a* is a sequence and *b* is an integer.

sequenceIncludes (...)

Deprecated since release 2.0. Use `contains()` instead.

Alias for `contains()`.

setitem (*a*, *b*, *c*)

__setitem__ (*a*, *b*, *c*)

Set the value of *a* at index *b* to *c*.

setslice (*a*, *b*, *c*, *v*)

__setslice__ (*a*, *b*, *c*, *v*)

Set the slice of *a* from index *b* to index *c*-1 to the sequence *v*.

Many operations have an “in-place” version. The following functions provide a more primitive access to in-place operators than the usual syntax does; for example, the statement `x += y` is equivalent to `x = operator.iadd(x, y)`. Another way to put it is to say that `z = operator.iadd(x, y)` is equivalent to the compound statement `z = x; z += y`.

iadd (*a*, *b*)

__iadd__ (*a*, *b*)

`a = iadd(a, b)` is equivalent to `a += b`. New in version 2.5.

iand (*a*, *b*)

__iand__ (*a*, *b*)

`a = iand(a, b)` is equivalent to `a &= b`. New in version 2.5.

iconcat (*a*, *b*)

__iconcat__ (*a*, *b*)

`a = iconcat(a, b)` is equivalent to `a += b` for *a* and *b* sequences. New in version 2.5.

idiv (*a*, *b*)

__idiv__ (*a*, *b*)

`a = idiv(a, b)` is equivalent to `a /= b` when `__future__.division` is not in effect. New in version 2.5.

```

ifloordiv(a, b)
__ifloordiv__(a, b)
    a = ifloordiv(a, b) is equivalent to a // b. New in version 2.5.

ilshift(a, b)
__ilshift__(a, b)
    a = ilshift(a, b) is equivalent to a << b. New in version 2.5.

imod(a, b)
__imod__(a, b)
    a = imod(a, b) is equivalent to a % b. New in version 2.5.

imul(a, b)
__imul__(a, b)
    a = imul(a, b) is equivalent to a * b. New in version 2.5.

ior(a, b)
__ior__(a, b)
    a = ior(a, b) is equivalent to a | b. New in version 2.5.

ipow(a, b)
__ipow__(a, b)
    a = ipow(a, b) is equivalent to a ** b. New in version 2.5.

irepeat(a, b)
__irepeat__(a, b)
    a = irepeat(a, b) is equivalent to a * b where a is a sequence and b is an integer. New in version 2.5.

irshift(a, b)
__irshift__(a, b)
    a = irshift(a, b) is equivalent to a >> b. New in version 2.5.

isub(a, b)
__isub__(a, b)
    a = isub(a, b) is equivalent to a - b. New in version 2.5.

itruediv(a, b)
__itruediv__(a, b)
    a = itruediv(a, b) is equivalent to a / b when __future__.division is in effect. New in version 2.5.

ixor(a, b)
__ixor__(a, b)
    a = ixor(a, b) is equivalent to a ^ b. New in version 2.5.

```

The `operator` module also defines a few predicates to test the type of objects. **Note:** Be careful not to misinterpret the results of these functions; only `isCallable()` has any measure of reliability with instance objects. For example:

```

>>> class C:
...     pass
...
>>> import operator
>>> o = C()
>>> operator.isMappingType(o)
True

```

isCallable(*o*)

Deprecated since release 2.0. Use the `callable()` built-in function instead.

Returns true if the object *o* can be called like a function, otherwise it returns false. True is returned for functions, bound and unbound methods, class objects, and instance objects which support the `__call__()` method.

isMappingType (*o*)

Returns true if the object *o* supports the mapping interface. This is true for dictionaries and all instance objects defining `__getitem__`. **Warning:** There is no reliable way to test if an instance supports the complete mapping protocol since the interface itself is ill-defined. This makes this test less useful than it otherwise might be.

isNumberType (*o*)

Returns true if the object *o* represents a number. This is true for all numeric types implemented in C. **Warning:** There is no reliable way to test if an instance supports the complete numeric interface since the interface itself is ill-defined. This makes this test less useful than it otherwise might be.

isSequenceType (*o*)

Returns true if the object *o* supports the sequence protocol. This returns true for all objects which define sequence methods in C, and for all instance objects defining `__getitem__`. **Warning:** There is no reliable way to test if an instance supports the complete sequence interface since the interface itself is ill-defined. This makes this test less useful than it otherwise might be.

Example: Build a dictionary that maps the ordinals from 0 to 255 to their character equivalents.

```
>>> import operator
>>> d = {}
>>> keys = range(256)
>>> vals = map(chr, keys)
>>> map(operator.setitem, [d]*len(keys), keys, vals)
```

The `operator` module also defines tools for generalized attribute and item lookups. These are useful for making fast field extractors as arguments for `map()`, `sorted()`, `itertools.groupby()`, or other functions that expect a function argument.

attrgetter (*attr*[, *args...*])

Return a callable object that fetches *attr* from its operand. If more than one attribute is requested, returns a tuple of attributes. After, `'f=attrgetter('name')'`, the call `'f(b)'` returns `'b.name'`. After, `'f=attrgetter('name', 'date')'`, the call `'f(b)'` returns `'(b.name, b.date)'`. New in version 2.4. Changed in version 2.5: Added support for multiple attributes.

itemgetter (*item*[, *args...*])

Return a callable object that fetches *item* from its operand. If more than one item is requested, returns a tuple of items. After, `'f=itemgetter(2)'`, the call `'f(b)'` returns `'b[2]'`. After, `'f=itemgetter(2, 5, 3)'`, the call `'f(b)'` returns `'(b[2], b[5], b[3])'`. New in version 2.4. Changed in version 2.5: Added support for multiple item extraction.

Examples:

```
>>> from operator import itemgetter
>>> inventory = [('apple', 3), ('banana', 2), ('pear', 5), ('orange', 1)]
>>> getcount = itemgetter(1)
>>> map(getcount, inventory)
[3, 2, 5, 1]
>>> sorted(inventory, key=getcount)
[('orange', 1), ('banana', 2), ('apple', 3), ('pear', 5)]
```

6.7.1 Mapping Operators to Functions

This table shows how abstract operations correspond to operator symbols in the Python syntax and the functions in the `operator` module.

Operation	Syntax	Function
Addition	$a + b$	<code>add(a, b)</code>
Concatenation	$seq1 + seq2$	<code>concat(seq1, seq2)</code>
Containment Test	$o \text{ in } seq$	<code>contains(seq, o)</code>
Division	a / b	<code>div(a, b)</code> # without <code>__future__.division</code>
Division	a / b	<code>truediv(a, b)</code> # with <code>__future__.division</code>
Division	$a // b$	<code>floordiv(a, b)</code>
Bitwise And	$a \& b$	<code>and_(a, b)</code>
Bitwise Exclusive Or	$a \wedge b$	<code>xor(a, b)</code>
Bitwise Inversion	$\sim a$	<code>invert(a)</code>
Bitwise Or	$a b$	<code>or_(a, b)</code>
Exponentiation	$a ** b$	<code>pow(a, b)</code>
Identity	$a \text{ is } b$	<code>is_(a, b)</code>
Identity	$a \text{ is not } b$	<code>is_not(a, b)</code>
Indexed Assignment	$o[k] = v$	<code>setitem(o, k, v)</code>
Indexed Deletion	<code>del o[k]</code>	<code>delitem(o, k)</code>
Indexing	$o[k]$	<code>getitem(o, k)</code>
Left Shift	$a \ll b$	<code>lshift(a, b)</code>
Modulo	$a \% b$	<code>mod(a, b)</code>
Multiplication	$a * b$	<code>mul(a, b)</code>
Negation (Arithmetic)	$-a$	<code>neg(a)</code>
Negation (Logical)	<code>not a</code>	<code>not_(a)</code>
Right Shift	$a \gg b$	<code>rshift(a, b)</code>
Sequence Repitition	$seq * i$	<code>repeat(seq, i)</code>
Slice Assignment	$seq[i:j] = values$	<code>setslice(seq, i, j, values)</code>
Slice Deletion	<code>del seq[i:j]</code>	<code>delslice(seq, i, j)</code>
Slicing	$seq[i:j]$	<code>getslice(seq, i, j)</code>
String Formatting	$s \% o$	<code>mod(s, o)</code>
Subtraction	$a - b$	<code>sub(a, b)</code>
Truth Test	o	<code>truth(o)</code>
Ordering	$a < b$	<code>lt(a, b)</code>
Ordering	$a \leq b$	<code>le(a, b)</code>
Equality	$a == b$	<code>eq(a, b)</code>
Difference	$a \neq b$	<code>ne(a, b)</code>
Ordering	$a \geq b$	<code>ge(a, b)</code>
Ordering	$a > b$	<code>gt(a, b)</code>

Internet Data Handling

This chapter describes modules which support handling data formats commonly used on the Internet.

<code>email.iterators</code>	Iterate over a message object tree.
<code>mailcap</code>	Mailcap file handling.
<code>mailbox</code>	Manipulate mailboxes in various formats
<code>mhlib</code>	Manipulate MH mailboxes from Python.
<code>mimertools</code>	Tools for parsing MIME-style message bodies.
<code>mimetypes</code>	Mapping of filename extensions to MIME types.
<code>MimeWriter</code>	Generic MIME file writer.
<code>mimify</code>	Mimification and unmimification of mail messages.
<code>multifile</code>	Support for reading files which contain distinct parts, such as some MIME data.
<code>rfc822</code>	Parse RFC 2822 style mail messages.
<code>base64</code>	RFC 3548: Base16, Base32, Base64 Data Encodings
<code>binhex</code>	Encode and decode files in binhex4 format.
<code>binascii</code>	Tools for converting between binary and various ASCII-encoded binary representations.
<code>quopri</code>	Encode and decode files using the MIME quoted-printable encoding.
<code>uu</code>	Encode and decode files in uuencode format.

7.1 `email` — An email and MIME handling package

New in version 2.2.

The `email` package is a library for managing email messages, including MIME and other RFC 2822-based message documents. It subsumes most of the functionality in several older standard modules such as `rfc822`, `mimertools`, `multifile`, and other non-standard packages such as `mimecntl`. It is specifically *not* designed to do any sending of email messages to SMTP (RFC 2821), NNTP, or other servers; those are functions of modules such as `smtplib` and `nntplib`. The `email` package attempts to be as RFC-compliant as possible, supporting in addition to RFC 2822, such MIME-related RFCs as RFC 2045, RFC 2046, RFC 2047, and RFC 2231.

The primary distinguishing feature of the `email` package is that it splits the parsing and generating of email messages from the internal *object model* representation of email. Applications using the `email` package deal primarily with objects; you can add sub-objects to messages, remove sub-objects from messages, completely re-arrange the contents, etc. There is a separate parser and a separate generator which handles the transformation from flat text to the object model, and then back to flat text again. There are also handy subclasses for some common MIME object types, and a few miscellaneous utilities that help with such common tasks as extracting and parsing message field values, creating RFC-compliant dates, etc.

The following sections describe the functionality of the `email` package. The ordering follows a progression that should be common in applications: an email message is read as flat text from a file or other source, the text is parsed to produce the object structure of the email message, this structure is manipulated, and finally, the object tree is rendered back into flat text.

It is perfectly feasible to create the object structure out of whole cloth — i.e. completely from scratch. From there, a similar progression can be taken as above.

Also included are detailed specifications of all the classes and modules that the `email` package provides, the exception classes you might encounter while using the `email` package, some auxiliary utilities, and a few examples. For users of the older `mimelib` package, or previous versions of the `email` package, a section on differences and porting is provided.

See Also:

Module `smtplib` (section 18.13):

SMTP protocol client

Module `nntplib` (section 18.12):

NNTP protocol client

7.1.1 Representing an email message

The central class in the `email` package is the `Message` class, imported from the `email.message` module. It is the base class for the `email` object model. `Message` provides the core functionality for setting and querying header fields, and for accessing message bodies.

Conceptually, a `Message` object consists of *headers* and *payloads*. Headers are RFC 2822 style field names and values where the field name and value are separated by a colon. The colon is not part of either the field name or the field value.

Headers are stored and returned in case-preserving form but are matched case-insensitively. There may also be a single envelope header, also known as the *Unix-From* header or the `From_` header. The payload is either a string in the case of simple message objects or a list of `Message` objects for MIME container documents (e.g. `multipart/*` and `message/rfc822`).

`Message` objects provide a mapping style interface for accessing the message headers, and an explicit interface for accessing both the headers and the payload. It provides convenience methods for generating a flat text representation of the message object tree, for accessing commonly used header parameters, and for recursively walking over the object tree.

Here are the methods of the `Message` class:

class `Message` ()

The constructor takes no arguments.

as_string ([*unixfrom*])

Return the entire message flatten as a string. When optional *unixfrom* is `True`, the envelope header is included in the returned string. *unixfrom* defaults to `False`.

Note that this method is provided as a convenience and may not always format the message the way you want. For example, by default it mangles lines that begin with `From` . For more flexibility, instantiate a `Generator` instance and use its `flatten()` method directly. For example:

```
from cStringIO import StringIO
from email.generator import Generator
fp = StringIO()
g = Generator(fp, mangle_from_=False, maxheaderlen=60)
g.flatten(msg)
text = fp.getvalue()
```

__str__ ()

Equivalent to `as_string(unixfrom=True)`.

is_multipart ()

Return `True` if the message's payload is a list of sub-`Message` objects, otherwise return `False`. When `is_multipart()` returns `False`, the payload should be a string object.

set_unixfrom(*unixfrom*)

Set the message's envelope header to *unixfrom*, which should be a string.

get_unixfrom()

Return the message's envelope header. Defaults to `None` if the envelope header was never set.

attach(*payload*)

Add the given *payload* to the current payload, which must be `None` or a list of `Message` objects before the call. After the call, the payload will always be a list of `Message` objects. If you want to set the payload to a scalar object (e.g. a string), use `set_payload()` instead.

get_payload(*[i[, decode]]*)

Return a reference the current payload, which will be a list of `Message` objects when `is_multipart()` is `True`, or a string when `is_multipart()` is `False`. If the payload is a list and you mutate the list object, you modify the message's payload in place.

With optional argument *i*, `get_payload()` will return the *i*-th element of the payload, counting from zero, if `is_multipart()` is `True`. An `IndexError` will be raised if *i* is less than 0 or greater than or equal to the number of items in the payload. If the payload is a string (i.e. `is_multipart()` is `False`) and *i* is given, a `TypeError` is raised.

Optional *decode* is a flag indicating whether the payload should be decoded or not, according to the Content-Transfer-Encoding: header. When `True` and the message is not a multipart, the payload will be decoded if this header's value is 'quoted-printable' or 'base64'. If some other encoding is used, or Content-Transfer-Encoding: header is missing, or if the payload has bogus base64 data, the payload is returned as-is (undecoded). If the message is a multipart and the *decode* flag is `True`, then `None` is returned. The default for *decode* is `False`.

set_payload(*payload[, charset]*)

Set the entire message object's payload to *payload*. It is the client's responsibility to ensure the payload invariants. Optional *charset* sets the message's default character set; see `set_charset()` for details.

Changed in version 2.2.2: *charset* argument added.

set_charset(*charset*)

Set the character set of the payload to *charset*, which can either be a `Charset` instance (see [email.charset](#)), a string naming a character set, or `None`. If it is a string, it will be converted to a `Charset` instance. If *charset* is `None`, the *charset* parameter will be removed from the Content-Type: header. Anything else will generate a `TypeError`.

The message will be assumed to be of type `text/*` encoded with *charset.input_charset*. It will be converted to *charset.output_charset* and encoded properly, if needed, when generating the plain text representation of the message. MIME headers (MIME-Version:, Content-Type:, Content-Transfer-Encoding:) will be added as needed.

New in version 2.2.2.

get_charset()

Return the `Charset` instance associated with the message's payload. New in version 2.2.2.

The following methods implement a mapping-like interface for accessing the message's RFC 2822 headers. Note that there are some semantic differences between these methods and a normal mapping (i.e. dictionary) interface. For example, in a dictionary there are no duplicate keys, but here there may be duplicate message headers. Also, in dictionaries there is no guaranteed order to the keys returned by `keys()`, but in a `Message` object, headers are always returned in the order they appeared in the original message, or were added to the message later. Any header deleted and then re-added are always appended to the end of the header list.

These semantic differences are intentional and are biased toward maximal convenience.

Note that in all cases, any envelope header present in the message is not included in the mapping interface.

__len__()

Return the total number of headers, including duplicates.

__contains__(name)

Return true if the message object has a field named *name*. Matching is done case-insensitively and *name* should not include the trailing colon. Used for the `in` operator, e.g.:

```
if 'message-id' in myMessage:
    print 'Message-ID:', myMessage['message-id']
```

__getitem__(name)

Return the value of the named header field. *name* should not include the colon field separator. If the header is missing, `None` is returned; a `KeyError` is never raised.

Note that if the named field appears more than once in the message's headers, exactly which of those field values will be returned is undefined. Use the `get_all()` method to get the values of all the extant named headers.

__setitem__(name, val)

Add a header to the message with field name *name* and value *val*. The field is appended to the end of the message's existing fields.

Note that this does *not* overwrite or delete any existing header with the same name. If you want to ensure that the new header is the only one present in the message with field name *name*, delete the field first, e.g.:

```
del msg['subject']
msg['subject'] = 'Python roolz!'
```

__delitem__(name)

Delete all occurrences of the field with name *name* from the message's headers. No exception is raised if the named field isn't present in the headers.

has_key(name)

Return true if the message contains a header field named *name*, otherwise return false.

keys()

Return a list of all the message's header field names.

values()

Return a list of all the message's field values.

items()

Return a list of 2-tuples containing all the message's field headers and values.

get(name[, failobj])

Return the value of the named header field. This is identical to `__getitem__()` except that optional *failobj* is returned if the named header is missing (defaults to `None`).

Here are some additional useful methods:

get_all(name[, failobj])

Return a list of all the values for the field named *name*. If there are no such named headers in the message, *failobj* is returned (defaults to `None`).

add_header(_name, _value, **_params)

Extended header setting. This method is similar to `__setitem__()` except that additional header parameters can be provided as keyword arguments. *_name* is the header field to add and *_value* is the *primary* value for the header.

For each item in the keyword argument dictionary *_params*, the key is taken as the parameter name, with underscores converted to dashes (since dashes are illegal in Python identifiers). Normally, the parameter will be added as `key="value"` unless the value is `None`, in which case only the key will be added.

Here's an example:

```
msg.add_header('Content-Disposition', 'attachment', filename='bud.gif')
```

This will add a header that looks like

```
Content-Disposition: attachment; filename="bud.gif"
```

replace_header (*_name*, *_value*)

Replace a header. Replace the first header found in the message that matches *_name*, retaining header order and field name case. If no matching header was found, a `KeyError` is raised.

New in version 2.2.2.

get_content_type ()

Return the message's content type. The returned string is coerced to lower case of the form maintype/subtype. If there was no Content-Type: header in the message the default type as given by `get_default_type()` will be returned. Since according to RFC 2045, messages always have a default type, `get_content_type()` will always return a value.

RFC 2045 defines a message's default type to be text/plain unless it appears inside a multipart/digest container, in which case it would be message/rfc822. If the Content-Type: header has an invalid type specification, RFC 2045 mandates that the default type be text/plain.

New in version 2.2.2.

get_content_maintype ()

Return the message's main content type. This is the maintype part of the string returned by `get_content_type()`.

New in version 2.2.2.

get_content_subtype ()

Return the message's sub-content type. This is the subtype part of the string returned by `get_content_type()`.

New in version 2.2.2.

get_default_type ()

Return the default content type. Most messages have a default content type of text/plain, except for messages that are subparts of multipart/digest containers. Such subparts have a default content type of message/rfc822.

New in version 2.2.2.

set_default_type (*ctype*)

Set the default content type. *ctype* should either be text/plain or message/rfc822, although this is not enforced. The default content type is not stored in the Content-Type: header.

New in version 2.2.2.

get_params ([*failobj* [, *header* [, *unquote*]]])

Return the message's Content-Type: parameters, as a list. The elements of the returned list are 2-tuples of key/value pairs, as split on the '=' sign. The left hand side of the '=' is the key, while the right hand side is the value. If there is no '=' sign in the parameter the value is the empty string, otherwise the value is as described in `get_param()` and is unquoted if optional *unquote* is `True` (the default).

Optional *failobj* is the object to return if there is no Content-Type: header. Optional *header* is the header to search instead of Content-Type:.

Changed in version 2.2.2: *unquote* argument added.

get_param (*param* [, *failobj* [, *header* [, *unquote*]]])

Return the value of the Content-Type: header's parameter *param* as a string. If the message has no Content-Type: header or if there is no such parameter, then *failobj* is returned (defaults to `None`).

Optional *header* if given, specifies the message header to use instead of Content-Type:.

Parameter keys are always compared case insensitively. The return value can either be a string, or a 3-tuple if the parameter was RFC 2231 encoded. When it's a 3-tuple, the elements of the value are of the form (CHARSET, LANGUAGE, VALUE). Note that both CHARSET and LANGUAGE can be None, in which case you should consider VALUE to be encoded in the us-ascii charset. You can usually ignore LANGUAGE.

If your application doesn't care whether the parameter was encoded as in RFC 2231, you can collapse the parameter value by calling `email.Utils.collapse_rfc2231_value()`, passing in the return value from `get_param()`. This will return a suitably decoded Unicode string when the value is a tuple, or the original string unquoted if it isn't. For example:

```
rawparam = msg.get_param('foo')
param = email.Utils.collapse_rfc2231_value(rawparam)
```

In any case, the parameter value (either the returned string, or the VALUE item in the 3-tuple) is always unquoted, unless *unquote* is set to False.

Changed in version 2.2.2: *unquote* argument added, and 3-tuple return value possible.

set_param(*param*, *value*[, *header*[, *requote*[, *charset*[, *language*]]]])

Set a parameter in the Content-Type: header. If the parameter already exists in the header, its value will be replaced with *value*. If the Content-Type: header has not yet been defined for this message, it will be set to text/plain and the new parameter value will be appended as per RFC 2045.

Optional *header* specifies an alternative header to Content-Type:, and all parameters will be quoted as necessary unless optional *requote* is False (the default is True).

If optional *charset* is specified, the parameter will be encoded according to RFC 2231. Optional *language* specifies the RFC 2231 language, defaulting to the empty string. Both *charset* and *language* should be strings.

New in version 2.2.2.

del_param(*param*[, *header*[, *requote*]])

Remove the given parameter completely from the Content-Type: header. The header will be re-written in place without the parameter or its value. All values will be quoted as necessary unless *requote* is False (the default is True). Optional *header* specifies an alternative to Content-Type:.

New in version 2.2.2.

set_type(*type*[, *header*][, *requote*])

Set the main type and subtype for the Content-Type: header. *type* must be a string in the form maintype/subtype, otherwise a ValueError is raised.

This method replaces the Content-Type: header, keeping all the parameters in place. If *requote* is False, this leaves the existing header's quoting as is, otherwise the parameters will be quoted (the default).

An alternative header can be specified in the *header* argument. When the Content-Type: header is set a MIME-Version: header is also added.

New in version 2.2.2.

get_filename([*failobj*])

Return the value of the filename parameter of the Content-Disposition: header of the message. If the header does not have a filename parameter, this method falls back to looking for the name parameter. If neither is found, or the header is missing, then *failobj* is returned. The returned string will always be unquoted as per `Utils.unquote()`.

get_boundary([*failobj*])

Return the value of the boundary parameter of the Content-Type: header of the message, or *failobj* if either the header is missing, or has no boundary parameter. The returned string will always be unquoted as per `Utils.unquote()`.

set_boundary(*boundary*)

Set the boundary parameter of the Content-Type: header to *boundary*. `set_boundary()` will always quote *boundary* if necessary. A HeaderParseError is raised if the message object has no Content-Type: header.

Note that using this method is subtly different than deleting the old Content-Type: header and adding a new one with the new boundary via `add_header()`, because `set_boundary()` preserves the order of the Content-Type: header in the list of headers. However, it does *not* preserve any continuation lines which may have been present in the original Content-Type: header.

get_content_charset ([*failobj*])

Return the `charset` parameter of the Content-Type: header, coerced to lower case. If there is no Content-Type: header, or if that header has no `charset` parameter, *failobj* is returned.

Note that this method differs from `get_charset()` which returns the `Charset` instance for the default encoding of the message body.

New in version 2.2.2.

get_charsets ([*failobj*])

Return a list containing the character set names in the message. If the message is a multipart, then the list will contain one element for each subpart in the payload, otherwise, it will be a list of length 1.

Each item in the list will be a string which is the value of the `charset` parameter in the Content-Type: header for the represented subpart. However, if the subpart has no Content-Type: header, no `charset` parameter, or is not of the text main MIME type, then that item in the returned list will be *failobj*.

walk ()

The `walk()` method is an all-purpose generator which can be used to iterate over all the parts and subparts of a message object tree, in depth-first traversal order. You will typically use `walk()` as the iterator in a `for` loop; each iteration returns the next subpart.

Here's an example that prints the MIME type of every part of a multipart message structure:

```
>>> for part in msg.walk():
...     print part.get_content_type()
multipart/report
text/plain
message/delivery-status
text/plain
text/plain
message/rfc822
```

Changed in version 2.5: The previously deprecated methods `get_type()`, `get_main_type()`, and `get_subtype()` were removed.

Message objects can also optionally contain two instance attributes, which can be used when generating the plain text of a MIME message.

preamble

The format of a MIME document allows for some text between the blank line following the headers, and the first multipart boundary string. Normally, this text is never visible in a MIME-aware mail reader because it falls outside the standard MIME armor. However, when viewing the raw text of the message, or when viewing the message in a non-MIME aware reader, this text can become visible.

The *preamble* attribute contains this leading extra-armor text for MIME documents. When the `Parser` discovers some text after the headers but before the first boundary string, it assigns this text to the message's *preamble* attribute. When the `Generator` is writing out the plain text representation of a MIME message, and it finds the message has a *preamble* attribute, it will write this text in the area between the headers and the first boundary. See [email.parser](#) and [email.generator](#) for details.

Note that if the message object has no preamble, the *preamble* attribute will be `None`.

epilogue

The *epilogue* attribute acts the same way as the *preamble* attribute, except that it contains text that appears between the last boundary and the end of the message.

Changed in version 2.5: You do not need to set the epilogue to the empty string in order for the `Generator` to print a newline at the end of the file.

defects

The *defects* attribute contains a list of all the problems found when parsing this message. See [email.errors](#) for a detailed description of the possible parsing defects.

New in version 2.4.

7.1.2 Parsing email messages

Message object structures can be created in one of two ways: they can be created from whole cloth by instantiating `Message` objects and stringing them together via `attach()` and `set_payload()` calls, or they can be created by parsing a flat text representation of the email message.

The `email` package provides a standard parser that understands most email document structures, including MIME documents. You can pass the parser a string or a file object, and the parser will return to you the root `Message` instance of the object structure. For simple, non-MIME messages the payload of this root object will likely be a string containing the text of the message. For MIME messages, the root object will return `True` from its `is_multipart()` method, and the subparts can be accessed via the `get_payload()` and `walk()` methods.

There are actually two parser interfaces available for use, the classic `Parser` API and the incremental `FeedParser` API. The classic `Parser` API is fine if you have the entire text of the message in memory as a string, or if the entire message lives in a file on the file system. `FeedParser` is more appropriate for when you're reading the message from a stream which might block waiting for more input (e.g. reading an email message from a socket). The `FeedParser` can consume and parse the message incrementally, and only returns the root object when you close the parser¹.

Note that the parser can be extended in limited ways, and of course you can implement your own parser completely from scratch. There is no magical connection between the `email` package's bundled parser and the `Message` class, so your custom parser can create message object trees any way it finds necessary.

FeedParser API

New in version 2.4.

The `FeedParser`, imported from the `email.feedparser` module, provides an API that is conducive to incremental parsing of email messages, such as would be necessary when reading the text of an email message from a source that can block (e.g. a socket). The `FeedParser` can of course be used to parse an email message fully contained in a string or a file, but the classic `Parser` API may be more convenient for such use cases. The semantics and results of the two parser APIs are identical.

The `FeedParser`'s API is simple; you create an instance, feed it a bunch of text until there's no more to feed it, then close the parser to retrieve the root message object. The `FeedParser` is extremely accurate when parsing standards-compliant messages, and it does a very good job of parsing non-compliant messages, providing information about how a message was deemed broken. It will populate a message object's *defects* attribute with a list of any problems it found in a message. See the [email.errors](#) module for the list of defects that it can find.

Here is the API for the `FeedParser`:

class `FeedParser` (`[_factory]`)

Create a `FeedParser` instance. Optional *_factory* is a no-argument callable that will be called whenever a new message object is needed. It defaults to the `email.message.Message` class.

feed (*data*)

Feed the `FeedParser` some more data. *data* should be a string containing one or more lines. The lines can be partial and the `FeedParser` will stitch such partial lines together properly. The lines in the string can have

¹As of email package version 3.0, introduced in Python 2.4, the classic `Parser` was re-implemented in terms of the `FeedParser`, so the semantics and results are identical between the two parsers.

any of the common three line endings, carriage return, newline, or carriage return and newline (they can even be mixed).

close()

Closing a `FeedParser` completes the parsing of all previously fed data, and returns the root message object. It is undefined what happens if you feed more data to a closed `FeedParser`.

Parser class API

The `Parser` class, imported from the `email.parser` module, provides an API that can be used to parse a message when the complete contents of the message are available in a string or file. The `email.parser` module also provides a second class, called `HeaderParser` which can be used if you're only interested in the headers of the message. `HeaderParser` can be much faster in these situations, since it does not attempt to parse the message body, instead setting the payload to the raw body as a string. `HeaderParser` has the same API as the `Parser` class.

class Parser (`[_class]`)

The constructor for the `Parser` class takes an optional argument `_class`. This must be a callable factory (such as a function or a class), and it is used whenever a sub-message object needs to be created. It defaults to `Message` (see [email.message](#)). The factory will be called without arguments.

The optional *strict* flag is ignored. **Deprecated since release 2.4.** Because the `Parser` class is a backward compatible API wrapper around the new-in-Python 2.4 `FeedParser`, *all* parsing is effectively non-strict. You should simply stop passing a *strict* flag to the `Parser` constructor.

Changed in version 2.2.2: The *strict* flag was added. Changed in version 2.4: The *strict* flag was deprecated.

The other public `Parser` methods are:

parse (`fp`, `[headersonly]`)

Read all the data from the file-like object `fp`, parse the resulting text, and return the root message object. `fp` must support both the `readline()` and the `read()` methods on file-like objects.

The text contained in `fp` must be formatted as a block of RFC 2822 style headers and header continuation lines, optionally preceded by an envelope header. The header block is terminated either by the end of the data or by a blank line. Following the header block is the body of the message (which may contain MIME-encoded subparts).

Optional *headersonly* is as with the `parse()` method.

Changed in version 2.2.2: The *headersonly* flag was added.

parsestr (`text`, `[headersonly]`)

Similar to the `parse()` method, except it takes a string object instead of a file-like object. Calling this method on a string is exactly equivalent to wrapping `text` in a `StringIO` instance first and calling `parse()`.

Optional *headersonly* is a flag specifying whether to stop parsing after reading the headers or not. The default is `False`, meaning it parses the entire contents of the file.

Changed in version 2.2.2: The *headersonly* flag was added.

Since creating a message object structure from a string or a file object is such a common task, two functions are provided as a convenience. They are available in the top-level `email` package namespace.

message_from_string (`s`, `[_class]`, `[strict]`)

Return a message object structure from a string. This is exactly equivalent to `Parser().parsestr(s)`. Optional `_class` and `strict` are interpreted as with the `Parser` class constructor.

Changed in version 2.2.2: The *strict* flag was added.

message_from_file (`fp`, `[_class]`, `[strict]`)

Return a message object structure tree from an open file object. This is exactly equivalent to `Parser().parse(fp)`. Optional `_class` and `strict` are interpreted as with the `Parser` class constructor.

Changed in version 2.2.2: The *strict* flag was added.

Here's an example of how you might use this at an interactive Python prompt:

```
>>> import email
>>> msg = email.message_from_string(myString)
```

Additional notes

Here are some notes on the parsing semantics:

- Most non-multipart type messages are parsed as a single message object with a string payload. These objects will return `False` for `is_multipart()`. Their `get_payload()` method will return a string object.
- All multipart type messages will be parsed as a container message object with a list of sub-message objects for their payload. The outer container message will return `True` for `is_multipart()` and their `get_payload()` method will return the list of `Message` subparts.
- Most messages with a content type of `message/*` (e.g. `message/delivery-status` and `message/rfc822`) will also be parsed as container object containing a list payload of length 1. Their `is_multipart()` method will return `True`. The single element in the list payload will be a sub-message object.
- Some non-standards compliant messages may not be internally consistent about their multipart-ness. Such messages may have a `Content-Type:` header of type `multipart`, but their `is_multipart()` method may return `False`. If such messages were parsed with the `FeedParser`, they will have an instance of the `MultipartInvariantViolationDefect` class in their `defects` attribute list. See [email.errors](#) for details.

7.1.3 Generating MIME documents

One of the most common tasks is to generate the flat text of the email message represented by a message object structure. You will need to do this if you want to send your message via the [smtplib](#) module or the [nntplib](#) module, or print the message on the console. Taking a message object structure and producing a flat text document is the job of the `Generator` class.

Again, as with the [email.parser](#) module, you aren't limited to the functionality of the bundled generator; you could write one from scratch yourself. However the bundled generator knows how to generate most email in a standards-compliant way, should handle MIME and non-MIME email messages just fine, and is designed so that the transformation from flat text, to a message structure via the `Parser` class, and back to flat text, is idempotent (the input is identical to the output).

Here are the public methods of the `Generator` class, imported from the `email.generator` module:

```
class Generator (outfp [, mangle_from_ [, maxheaderlen ] ])
```

The constructor for the `Generator` class takes a file-like object called *outfp* for an argument. *outfp* must support the `write()` method and be usable as the output file in a Python extended print statement.

Optional *mangle_from_* is a flag that, when `True`, puts a `>` character in front of any line in the body that starts exactly as `'From '`, i.e. `From` followed by a space at the beginning of the line. This is the only guaranteed portable way to avoid having such lines be mistaken for a UNIX mailbox format envelope header separator (see [WHY THE CONTENT-LENGTH FORMAT IS BAD](#) for details). *mangle_from_* defaults to `True`, but you might want to set this to `False` if you are not writing UNIX mailbox format files.

Optional *maxheaderlen* specifies the longest length for a non-continued header. When a header line is longer than *maxheaderlen* (in characters, with tabs expanded to 8 spaces), the header will be split as defined in the `email.header.Header` class. Set to zero to disable header wrapping. The default is 78, as recommended (but not required) by RFC 2822.

The other public `Generator` methods are:

flatten (*msg*[, *unixfrom*])

Print the textual representation of the message object structure rooted at *msg* to the output file specified when the `Generator` instance was created. Subparts are visited depth-first and the resulting text will be properly MIME encoded.

Optional *unixfrom* is a flag that forces the printing of the envelope header delimiter before the first RFC 2822 header of the root message object. If the root object has no envelope header, a standard one is crafted. By default, this is set to `False` to inhibit the printing of the envelope delimiter.

Note that for subparts, no envelope header is ever printed.

New in version 2.2.2.

clone (*fp*)

Return an independent clone of this `Generator` instance with the exact same options.

New in version 2.2.2.

write (*s*)

Write the string *s* to the underlying file object, i.e. *outfp* passed to `Generator`'s constructor. This provides just enough file-like API for `Generator` instances to be used in extended print statements.

As a convenience, see the methods `Message.as_string()` and `str(aMessage)`, a.k.a. `Message.__str__()`, which simplify the generation of a formatted string representation of a message object. For more detail, see [email.message](#).

The `email.generator` module also provides a derived class, called `DecodedGenerator` which is like the `Generator` base class, except that non-text parts are substituted with a format string representing the part.

class DecodedGenerator (*outfp*[, *mangle_from_*[, *maxheaderlen*[, *fmt*]]])

This class, derived from `Generator` walks through all the subparts of a message. If the subpart is of main type `text`, then it prints the decoded payload of the subpart. Optional *mangle_from_* and *maxheaderlen* are as with the `Generator` base class.

If the subpart is not of main type `text`, optional *fmt* is a format string that is used instead of the message payload. *fmt* is expanded with the following keywords, '`%(keyword)s`' format:

- type* – Full MIME type of the non-text part
- maintype* – Main MIME type of the non-text part
- subtype* – Sub-MIME type of the non-text part
- filename* – Filename of the non-text part
- description* – Description associated with the non-text part
- encoding* – Content transfer encoding of the non-text part

The default value for *fmt* is `None`, meaning

```
[Non-text %(type)s) part of message omitted, filename %(filename)s]
```

New in version 2.2.2.

Changed in version 2.5: The previously deprecated method `__call__()` was removed.

7.1.4 Creating email and MIME objects from scratch

Ordinarily, you get a message object structure by passing a file or some text to a parser, which parses the text and returns the root message object. However you can also build a complete message structure from scratch, or even individual `Message` objects by hand. In fact, you can also take an existing structure and add new `Message` objects, move them around, etc. This makes a very convenient interface for slicing-and-dicing MIME messages.

You can create a new object structure by creating `Message` instances, adding attachments and all the appropriate headers manually. For MIME messages though, the `email` package provides some convenient subclasses to make things easier.

Here are the classes:

class `MIMEBase` (*_maintype*, *_subtype*, ****_params**)

Module: `email.mime.base`

This is the base class for all the MIME-specific subclasses of `Message`. Ordinarily you won't create instances specifically of `MIMEBase`, although you could. `MIMEBase` is provided primarily as a convenient base class for more specific MIME-aware subclasses.

_maintype is the Content-Type: major type (e.g. text or image), and *_subtype* is the Content-Type: minor type (e.g. plain or gif). *_params* is a parameter key/value dictionary and is passed directly to `Message.add_header()`.

The `MIMEBase` class always adds a Content-Type: header (based on *_maintype*, *_subtype*, and *_params*), and a MIME-Version: header (always set to 1.0).

class `MIMENonMultipart` ()

Module: `email.mime.nonmultipart`

A subclass of `MIMEBase`, this is an intermediate base class for MIME messages that are not multipart. The primary purpose of this class is to prevent the use of the `attach()` method, which only makes sense for multipart messages. If `attach()` is called, a `MultipartConversionError` exception is raised.

New in version 2.2.2.

class `MIMEMultipart` ([*subtype*, *boundary*, *_subparts*, *_params*]]])

Module: `email.mime.multipart`

A subclass of `MIMEBase`, this is an intermediate base class for MIME messages that are multipart. Optional *_subtype* defaults to `mixed`, but can be used to specify the subtype of the message. A Content-Type: header of `multipart/_subtype` will be added to the message object. A MIME-Version: header will also be added.

Optional *boundary* is the multipart boundary string. When `None` (the default), the boundary is calculated when needed.

_subparts is a sequence of initial subparts for the payload. It must be possible to convert this sequence to a list. You can always attach new subparts to the message by using the `Message.attach()` method.

Additional parameters for the Content-Type: header are taken from the keyword arguments, or passed into the *_params* argument, which is a keyword dictionary.

New in version 2.2.2.

class `MIMEApplication` (*_data*, *_subtype*, *_encoder*, ****_params**]])

Module: `email.mime.application`

A subclass of `MIMENonMultipart`, the `MIMEApplication` class is used to represent MIME message objects of major type `application`. *_data* is a string containing the raw byte data. Optional *_subtype* specifies the MIME subtype and defaults to `octet-stream`.

Optional *_encoder* is a callable (i.e. function) which will perform the actual encoding of the data for transport. This callable takes one argument, which is the `MIMEApplication` instance. It should use `get_payload()` and `set_payload()` to change the payload to encoded form. It should also add any Content-Transfer-Encoding: or other headers to the message object as necessary. The default encoding is `base64`. See the [email.encoders](#) module for a list of the built-in encoders.

_params are passed straight through to the base class constructor. New in version 2.5.

class `MIMEAudio` (*_audiodata*, *_subtype*, *_encoder*, ****_params**]])

Module: `email.mime.audio`

A subclass of `MIMENonMultipart`, the `MIMEAudio` class is used to create MIME message objects of major type `audio`. *_audiodata* is a string containing the raw audio data. If this data can be decoded by the standard

Python module `sndhdr`, then the subtype will be automatically included in the Content-Type: header. Otherwise you can explicitly specify the audio subtype via the `_subtype` parameter. If the minor type could not be guessed and `_subtype` was not given, then `TypeError` is raised.

Optional `_encoder` is a callable (i.e. function) which will perform the actual encoding of the audio data for transport. This callable takes one argument, which is the `MIMEAudio` instance. It should use `get_payload()` and `set_payload()` to change the payload to encoded form. It should also add any Content-Transfer-Encoding: or other headers to the message object as necessary. The default encoding is base64. See the `email.encoders` module for a list of the built-in encoders.

`_params` are passed straight through to the base class constructor.

```
class MIMEImage (_imagedata[, _subtype[, _encoder[, **_params ]]])  
Module: email.mime.image
```

A subclass of `MIMENonMultipart`, the `MIMEImage` class is used to create MIME message objects of major type image. `_imagedata` is a string containing the raw image data. If this data can be decoded by the standard Python module `imghdr`, then the subtype will be automatically included in the Content-Type: header. Otherwise you can explicitly specify the image subtype via the `_subtype` parameter. If the minor type could not be guessed and `_subtype` was not given, then `TypeError` is raised.

Optional `_encoder` is a callable (i.e. function) which will perform the actual encoding of the image data for transport. This callable takes one argument, which is the `MIMEImage` instance. It should use `get_payload()` and `set_payload()` to change the payload to encoded form. It should also add any Content-Transfer-Encoding: or other headers to the message object as necessary. The default encoding is base64. See the `email.encoders` module for a list of the built-in encoders.

`_params` are passed straight through to the `MIMEBase` constructor.

```
class MIMEMessage (_msg[, _subtype])  
Module: email.mime.message
```

A subclass of `MIMENonMultipart`, the `MIMEMessage` class is used to create MIME objects of main type message. `_msg` is used as the payload, and must be an instance of class `Message` (or a subclass thereof), otherwise a `TypeError` is raised.

Optional `_subtype` sets the subtype of the message; it defaults to `rfc822`.

```
class MIMEText (_text[, _subtype[, _charset ]])  
Module: email.mime.text
```

A subclass of `MIMENonMultipart`, the `MIMEText` class is used to create MIME objects of major type text. `_text` is the string for the payload. `_subtype` is the minor type and defaults to `plain`. `_charset` is the character set of the text and is passed as a parameter to the `MIMENonMultipart` constructor; it defaults to `us-ascii`. No guessing or encoding is performed on the text data.

Changed in version 2.4: The previously deprecated `_encoding` argument has been removed. Encoding happens implicitly based on the `_charset` argument.

7.1.5 Internationalized headers

RFC 2822 is the base standard that describes the format of email messages. It derives from the older RFC 822 standard which came into widespread use at a time when most email was composed of ASCII characters only. RFC 2822 is a specification written assuming email contains only 7-bit ASCII characters.

Of course, as email has been deployed worldwide, it has become internationalized, such that language specific character sets can now be used in email messages. The base standard still requires email messages to be transferred using only 7-bit ASCII characters, so a slew of RFCs have been written describing how to encode email containing non-ASCII characters into RFC 2822-compliant format. These RFCs include RFC 2045, RFC 2046, RFC 2047, and RFC 2231. The `email` package supports these standards in its `email.header` and `email.charset` modules.

If you want to include non-ASCII characters in your email headers, say in the Subject: or To: fields, you should use the `Header` class and assign the field in the `Message` object to an instance of `Header` instead of using a string for the header value. Import the `Header` class from the `email.header` module. For example:

```
>>> from email.message import Message
>>> from email.header import Header
>>> msg = Message()
>>> h = Header('p\xF6stal', 'iso-8859-1')
>>> msg['Subject'] = h
>>> print msg.as_string()
Subject: =?iso-8859-1?q?p=F6stal?=
```

Notice here how we wanted the Subject: field to contain a non-ASCII character? We did this by creating a `Header` instance and passing in the character set that the byte string was encoded in. When the subsequent `Message` instance was flattened, the Subject: field was properly RFC 2047 encoded. MIME-aware mail readers would show this header using the embedded ISO-8859-1 character.

New in version 2.2.2.

Here is the `Header` class description:

class Header (`s`[, `charset`[, `maxlinelen`[, `header_name`[, `continuation_ws`[, `errors`]]]]])

Create a MIME-compliant header that can contain strings in different character sets.

Optional `s` is the initial header value. If `None` (the default), the initial header value is not set. You can later append to the header with `append()` method calls. `s` may be a byte string or a Unicode string, but see the `append()` documentation for semantics.

Optional `charset` serves two purposes: it has the same meaning as the `charset` argument to the `append()` method. It also sets the default character set for all subsequent `append()` calls that omit the `charset` argument. If `charset` is not provided in the constructor (the default), the `us-ascii` character set is used both as `s`'s initial charset and as the default for subsequent `append()` calls.

The maximum line length can be specified explicit via `maxlinelen`. For splitting the first line to a shorter value (to account for the field header which isn't included in `s`, e.g. Subject:) pass in the name of the field in `header_name`. The default `maxlinelen` is 76, and the default value for `header_name` is `None`, meaning it is not taken into account for the first line of a long, split header.

Optional `continuation_ws` must be RFC 2822-compliant folding whitespace, and is usually either a space or a hard tab character. This character will be prepended to continuation lines.

Optional `errors` is passed straight through to the `append()` method.

append (`s`[, `charset`[, `errors`]])

Append the string `s` to the MIME header.

Optional `charset`, if given, should be a `Charset` instance (see [email.charset](#)) or the name of a character set, which will be converted to a `Charset` instance. A value of `None` (the default) means that the `charset` given in the constructor is used.

`s` may be a byte string or a Unicode string. If it is a byte string (i.e. `isinstance(s, str)` is true), then `charset` is the encoding of that byte string, and a `UnicodeError` will be raised if the string cannot be decoded with that character set.

If `s` is a Unicode string, then `charset` is a hint specifying the character set of the characters in the string. In this case, when producing an RFC 2822-compliant header using RFC 2047 rules, the Unicode string will be encoded using the following charsets in order: `us-ascii`, the `charset` hint, `utf-8`. The first character set to not provoke a `UnicodeError` is used.

Optional `errors` is passed through to any `unicode()` or `ustr.encode()` call, and defaults to "strict".

encode ([*splitchars*])

Encode a message header into an RFC-compliant format, possibly wrapping long lines and encapsulating non-ASCII parts in base64 or quoted-printable encodings. Optional *splitchars* is a string containing characters to split long ASCII lines on, in rough support of RFC 2822's *highest level syntactic breaks*. This doesn't affect RFC 2047 encoded lines.

The `Header` class also provides a number of methods to support standard operators and built-in functions.

__str__ ()

A synonym for `Header.encode()`. Useful for `str(aHeader)`.

__unicode__ ()

A helper for the built-in `unicode()` function. Returns the header as a Unicode string.

__eq__ (*other*)

This method allows you to compare two `Header` instances for equality.

__ne__ (*other*)

This method allows you to compare two `Header` instances for inequality.

The `email.header` module also provides the following convenient functions.

decode_header (*header*)

Decode a message header value without converting the character set. The header value is in *header*.

This function returns a list of (*decoded_string*, *charset*) pairs containing each of the decoded parts of the header. *charset* is `None` for non-encoded parts of the header, otherwise a lower case string containing the name of the character set specified in the encoded string.

Here's an example:

```
>>> from email.header import decode_header
>>> decode_header('=?iso-8859-1?q?F6stal?')
[('p\xxf6stal', 'iso-8859-1')]
```

make_header (*decoded_seq* [, *maxlinelen* [, *header_name* [, *continuation_ws*]]])

Create a `Header` instance from a sequence of pairs as returned by `decode_header()`.

`decode_header()` takes a header value string and returns a sequence of pairs of the format (*decoded_string*, *charset*) where *charset* is the name of the character set.

This function takes one of those sequence of pairs and returns a `Header` instance. Optional *maxlinelen*, *header_name*, and *continuation_ws* are as in the `Header` constructor.

7.1.6 Representing character sets

This module provides a class `Charset` for representing character sets and character set conversions in email messages, as well as a character set registry and several convenience methods for manipulating this registry. Instances of `Charset` are used in several other modules within the `email` package.

Import this class from the `email.charset` module.

New in version 2.2.2.

class Charset ([*input_charset*])

Map character sets to their email properties.

This class provides information about the requirements imposed on email for a specific character set. It also provides convenience routines for converting between character sets, given the availability of the applicable codecs. Given a character set, it will do its best to provide information on how to use that character set in an email message in an RFC-compliant way.

Certain character sets must be encoded with quoted-printable or base64 when used in email headers or bodies. Certain character sets must be converted outright, and are not allowed in email.

Optional *input_charset* is as described below; it is always coerced to lower case. After being alias normalized it is also used as a lookup into the registry of character sets to find out the header encoding, body encoding, and output conversion codec to be used for the character set. For example, if *input_charset* is `iso-8859-1`, then headers and bodies will be encoded using quoted-printable and no output conversion codec is necessary. If *input_charset* is `eur-jp`, then headers will be encoded with base64, bodies will not be encoded, but output text will be converted from the `eur-jp` character set to the `iso-2022-jp` character set.

Charset instances have the following data attributes:

input_charset

The initial character set specified. Common aliases are converted to their *official* email names (e.g. `latin_1` is converted to `iso-8859-1`). Defaults to 7-bit `us-ascii`.

header_encoding

If the character set must be encoded before it can be used in an email header, this attribute will be set to `Charset.QP` (for quoted-printable), `Charset.BASE64` (for base64 encoding), or `Charset.SHORTEST` for the shortest of QP or BASE64 encoding. Otherwise, it will be `None`.

body_encoding

Same as *header_encoding*, but describes the encoding for the mail message's body, which indeed may be different than the header encoding. `Charset.SHORTEST` is not allowed for *body_encoding*.

output_charset

Some character sets must be converted before they can be used in email headers or bodies. If the *input_charset* is one of them, this attribute will contain the name of the character set output will be converted to. Otherwise, it will be `None`.

input_codec

The name of the Python codec used to convert the *input_charset* to Unicode. If no conversion codec is necessary, this attribute will be `None`.

output_codec

The name of the Python codec used to convert Unicode to the *output_charset*. If no conversion codec is necessary, this attribute will have the same value as the *input_codec*.

Charset instances also have the following methods:

get_body_encoding()

Return the content transfer encoding used for body encoding.

This is either the string `'quoted-printable'` or `'base64'` depending on the encoding used, or it is a function, in which case you should call the function with a single argument, the Message object being encoded. The function should then set the Content-Transfer-Encoding: header itself to whatever is appropriate.

Returns the string `'quoted-printable'` if *body_encoding* is QP, returns the string `'base64'` if *body_encoding* is BASE64, and returns the string `'7bit'` otherwise.

convert(s)

Convert the string *s* from the *input_codec* to the *output_codec*.

to_splittable(s)

Convert a possibly multibyte string to a safely splittable format. *s* is the string to split.

Uses the *input_codec* to try and convert the string to Unicode, so it can be safely split on character boundaries (even for multibyte characters).

Returns the string as-is if it isn't known how to convert *s* to Unicode with the *input_charset*.

Characters that could not be converted to Unicode will be replaced with the Unicode replacement character `'U+FFFD'`.

from_splittable (*ustr*[, *to_output*])

Convert a splittable string back into an encoded string. *ustr* is a Unicode string to “unsplit”.

This method uses the proper codec to try and convert the string from Unicode back into an encoded format. Return the string as-is if it is not Unicode, or if it could not be converted from Unicode.

Characters that could not be converted from Unicode will be replaced with an appropriate character (usually ‘?’).

If *to_output* is `True` (the default), uses *output_codec* to convert to an encoded format. If *to_output* is `False`, it uses *input_codec*.

get_output_charset ()

Return the output character set.

This is the *output_charset* attribute if that is not `None`, otherwise it is *input_charset*.

encoded_header_len ()

Return the length of the encoded header string, properly calculating for quoted-printable or base64 encoding.

header_encode (*s*[, *convert*])

Header-encode the string *s*.

If *convert* is `True`, the string will be converted from the input charset to the output charset automatically. This is not useful for multibyte character sets, which have line length issues (multibyte characters must be split on a character, not a byte boundary); use the higher-level `Header` class to deal with these issues (see [email.header](#)). *convert* defaults to `False`.

The type of encoding (base64 or quoted-printable) will be based on the *header_encoding* attribute.

body_encode (*s*[, *convert*])

Body-encode the string *s*.

If *convert* is `True` (the default), the string will be converted from the input charset to output charset automatically. Unlike `header_encode()`, there are no issues with byte boundaries and multibyte charsets in email bodies, so this is usually pretty safe.

The type of encoding (base64 or quoted-printable) will be based on the *body_encoding* attribute.

The `Charset` class also provides a number of methods to support standard operations and built-in functions.

__str__ ()

Returns *input_charset* as a string coerced to lower case. `__repr__()` is an alias for `__str__()`.

__eq__ (*other*)

This method allows you to compare two `Charset` instances for equality.

__ne__ (*other*)

This method allows you to compare two `Charset` instances for inequality.

The `email.charset` module also provides the following functions for adding new entries to the global character set, alias, and codec registries:

add_charset (*charset*[, *header_enc*[, *body_enc*[, *output_charset*]]])

Add character properties to the global registry.

charset is the input character set, and must be the canonical name of a character set.

Optional *header_enc* and *body_enc* is either `Charset.QP` for quoted-printable, `Charset.BASE64` for base64 encoding, `Charset.SHORTEST` for the shortest of quoted-printable or base64 encoding, or `None` for no encoding. `SHORTEST` is only valid for *header_enc*. The default is `None` for no encoding.

Optional *output_charset* is the character set that the output should be in. Conversions will proceed from input charset, to Unicode, to the output charset when the method `Charset.convert()` is called. The default is to output in the same character set as the input.

Both *input_charset* and *output_charset* must have Unicode codec entries in the module's character set-to-codec mapping; use `add_codec()` to add codecs the module does not know about. See the `codecs` module's documentation for more information.

The global character set registry is kept in the module global dictionary `CHARSETS`.

add_alias (*alias*, *canonical*)

Add a character set alias. *alias* is the alias name, e.g. `latin-1`. *canonical* is the character set's canonical name, e.g. `iso-8859-1`.

The global charset alias registry is kept in the module global dictionary `ALIASES`.

add_codec (*charset*, *codecname*)

Add a codec that map characters in the given character set to and from Unicode.

charset is the canonical name of a character set. *codecname* is the name of a Python codec, as appropriate for the second argument to the `unicode()` built-in, or to the `encode()` method of a Unicode string.

7.1.7 Encoders

When creating `Message` objects from scratch, you often need to encode the payloads for transport through compliant mail servers. This is especially true for `image/*` and `text/*` type messages containing binary data.

The `email` package provides some convenient encodings in its `encoders` module. These encoders are actually used by the `MIMEAudio` and `MIMEImage` class constructors to provide default encodings. All encoder functions take exactly one argument, the message object to encode. They usually extract the payload, encode it, and reset the payload to this newly encoded value. They should also set the Content-Transfer-Encoding: header as appropriate.

Here are the encoding functions provided:

encode_quopri (*msg*)

Encodes the payload into quoted-printable form and sets the Content-Transfer-Encoding: header to `quoted-printable`². This is a good encoding to use when most of your payload is normal printable data, but contains a few unprintable characters.

encode_base64 (*msg*)

Encodes the payload into base64 form and sets the Content-Transfer-Encoding: header to `base64`. This is a good encoding to use when most of your payload is unprintable data since it is a more compact form than quoted-printable. The drawback of base64 encoding is that it renders the text non-human readable.

encode_7or8bit (*msg*)

This doesn't actually modify the message's payload, but it does set the Content-Transfer-Encoding: header to either `7bit` or `8bit` as appropriate, based on the payload data.

encode_noop (*msg*)

This does nothing; it doesn't even set the Content-Transfer-Encoding: header.

7.1.8 Exception and Defect classes

The following exception classes are defined in the `email.errors` module:

exception MessageError ()

This is the base class for all exceptions that the `email` package can raise. It is derived from the standard `Exception` class and defines no additional methods.

exception MessageParseError ()

This is the base class for exceptions thrown by the `Parser` class. It is derived from `MessageError`.

²Note that encoding with `encode_quopri()` also encodes all tabs and space characters in the data.

exception HeaderParseError()

Raised under some error conditions when parsing the RFC 2822 headers of a message, this class is derived from `MessageParseError`. It can be raised from the `Parser.parse()` or `Parser.parsestr()` methods.

Situations where it can be raised include finding an envelope header after the first RFC 2822 header of the message, finding a continuation line before the first RFC 2822 header is found, or finding a line in the headers which is neither a header or a continuation line.

exception BoundaryError()

Raised under some error conditions when parsing the RFC 2822 headers of a message, this class is derived from `MessageParseError`. It can be raised from the `Parser.parse()` or `Parser.parsestr()` methods.

Situations where it can be raised include not being able to find the starting or terminating boundary in a multipart/* message when strict parsing is used.

exception MultipartConversionError()

Raised when a payload is added to a `Message` object using `add_payload()`, but the payload is already a scalar and the message's Content-Type: main type is not either multipart or missing. `MultipartConversionError` multiply inherits from `MessageError` and the built-in `TypeError`.

Since `Message.add_payload()` is deprecated, this exception is rarely raised in practice. However the exception may also be raised if the `attach()` method is called on an instance of a class derived from `MIMENonMultipart` (e.g. `MIMEImage`).

Here's the list of the defects that the `FeedParser` can find while parsing messages. Note that the defects are added to the message where the problem was found, so for example, if a message nested inside a multipart/alternative had a malformed header, that nested message object would have a defect, but the containing messages would not.

All defect classes are subclassed from `email.errors.MessageDefect`, but this class is *not* an exception!

New in version 2.4: All the defect classes were added.

- `NoBoundaryInMultipartDefect` – A message claimed to be a multipart, but had no boundary parameter.
- `StartBoundaryNotFoundDefect` – The start boundary claimed in the Content-Type: header was never found.
- `FirstHeaderLineIsContinuationDefect` – The message had a continuation line as its first header line.
- `MisplacedEnvelopeHeaderDefect` – A “Unix From” header was found in the middle of a header block.
- `MalformedHeaderDefect` – A header was found that was missing a colon, or was otherwise malformed.
- `MultipartInvariantViolationDefect` – A message claimed to be a multipart, but no subparts were found. Note that when a message has this defect, its `is_multipart()` method may return false even though its content type claims to be multipart.

7.1.9 Miscellaneous utilities

There are several useful utilities provided in the `email.utils` module:

quote(str)

Return a new string with backslashes in *str* replaced by two backslashes, and double quotes replaced by backslash-double quote.

unquote(str)

Return a new string which is an *unquoted* version of *str*. If *str* ends and begins with double quotes, they are stripped off. Likewise if *str* ends and begins with angle brackets, they are stripped off.

parseaddr (*address*)

Parse address – which should be the value of some address-containing field such as To: or Cc: – into its constituent *realname* and *email address* parts. Returns a tuple of that information, unless the parse fails, in which case a 2-tuple of ('', '') is returned.

formataddr (*pair*)

The inverse of `parseaddr()`, this takes a 2-tuple of the form (*realname*, *email_address*) and returns the string value suitable for a To: or Cc: header. If the first element of *pair* is false, then the second element is returned unmodified.

getaddresses (*fieldvalues*)

This method returns a list of 2-tuples of the form returned by `parseaddr()`. *fieldvalues* is a sequence of header field values as might be returned by `Message.get_all()`. Here's a simple example that gets all the recipients of a message:

```
from email.utils import getaddresses

tos = msg.get_all('to', [])
ccs = msg.get_all('cc', [])
resent_tos = msg.get_all('resent-to', [])
resent_ccs = msg.get_all('resent-cc', [])
all_recipients = getaddresses(tos + ccs + resent_tos + resent_ccs)
```

parsedate (*date*)

Attempts to parse a date according to the rules in RFC 2822. However, some mailers don't follow that format as specified, so `parsedate()` tries to guess correctly in such cases. *date* is a string containing an RFC 2822 date, such as "Mon, 20 Nov 1995 19:12:08 -0500". If it succeeds in parsing the date, `parsedate()` returns a 9-tuple that can be passed directly to `time.mktime()`; otherwise `None` will be returned. Note that fields 6, 7, and 8 of the result tuple are not usable.

parsedate_tz (*date*)

Performs the same function as `parsedate()`, but returns either `None` or a 10-tuple; the first 9 elements make up a tuple that can be passed directly to `time.mktime()`, and the tenth is the offset of the date's timezone from UTC (which is the official term for Greenwich Mean Time)³. If the input string has no timezone, the last element of the tuple returned is `None`. Note that fields 6, 7, and 8 of the result tuple are not usable.

mktime_tz (*tuple*)

Turn a 10-tuple as returned by `parsedate_tz()` into a UTC timestamp. If the timezone item in the tuple is `None`, assume local time. Minor deficiency: `mktime_tz()` interprets the first 8 elements of *tuple* as a local time and then compensates for the timezone difference. This may yield a slight error around changes in daylight savings time, though not worth worrying about for common use.

formatdate ([*timeval* [, *localtime*] [, *usegmt*]])

Returns a date string as per RFC 2822, e.g.:

```
Fri, 09 Nov 2001 01:08:47 -0000
```

Optional *timeval* if given is a floating point time value as accepted by `time.gmtime()` and `time.localtime()`, otherwise the current time is used.

Optional *localtime* is a flag that when `True`, interprets *timeval*, and returns a date relative to the local timezone instead of UTC, properly taking daylight savings time into account. The default is `False` meaning UTC is used.

Optional *usegmt* is a flag that when `True`, outputs a date string with the timezone as an ascii string GMT, rather than a numeric -0000. This is needed for some protocols (such as HTTP). This only applies when *localtime* is `False`. New in version 2.4.

³Note that the sign of the timezone offset is the opposite of the sign of the `time.timezone` variable for the same timezone; the latter variable follows the POSIX standard while this module follows RFC 2822.

make_msgid ([*idstring*])

Returns a string suitable for an RFC 2822-compliant Message-ID: header. Optional *idstring* if given, is a string used to strengthen the uniqueness of the message id.

decode_rfc2231 (*s*)

Decode the string *s* according to RFC 2231.

encode_rfc2231 (*s* [, *charset* [, *language*]])

Encode the string *s* according to RFC 2231. Optional *charset* and *language*, if given is the character set name and language name to use. If neither is given, *s* is returned as-is. If *charset* is given but *language* is not, the string is encoded using the empty string for *language*.

collapse_rfc2231_value (*value* [, *errors* [, *fallback_charset*]])

When a header parameter is encoded in RFC 2231 format, `Message.get_param()` may return a 3-tuple containing the character set, language, and value. `collapse_rfc2231_value()` turns this into a unicode string. Optional *errors* is passed to the *errors* argument of the built-in `unicode()` function; it defaults to `replace`. Optional *fallback_charset* specifies the character set to use if the one in the RFC 2231 header is not known by Python; it defaults to `us-ascii`.

For convenience, if the *value* passed to `collapse_rfc2231_value()` is not a tuple, it should be a string and it is returned unquoted.

decode_params (*params*)

Decode parameters list according to RFC 2231. *params* is a sequence of 2-tuples containing elements of the form (content-type, string-value).

Changed in version 2.4: The `dump_address_pair()` function has been removed; use `formataddr()` instead.

Changed in version 2.4: The `decode()` function has been removed; use the `Header.decode_header()` method instead.

Changed in version 2.4: The `encode()` function has been removed; use the `Header.encode()` method instead.

7.1.10 Iterators

Iterating over a message object tree is fairly easy with the `Message.walk()` method. The `email.iterators` module provides some useful higher level iterations over message object trees.

body_line_iterator (*msg* [, *decode*])

This iterates over all the payloads in all the subparts of *msg*, returning the string payloads line-by-line. It skips over all the subpart headers, and it skips over any subpart with a payload that isn't a Python string. This is somewhat equivalent to reading the flat text representation of the message from a file using `readline()`, skipping over all the intervening headers.

Optional *decode* is passed through to `Message.get_payload()`.

typed_subpart_iterator (*msg* [, *maintype* [, *subtype*]])

This iterates over all the subparts of *msg*, returning only those subparts that match the MIME type specified by *maintype* and *subtype*.

Note that *subtype* is optional; if omitted, then subpart MIME type matching is done only with the main type. *maintype* is optional too; it defaults to `text`.

Thus, by default `typed_subpart_iterator()` returns each subpart that has a MIME type of `text/*`.

The following function has been added as a useful debugging tool. It should *not* be considered part of the supported public interface for the package.

_structure (*msg* [, *fp* [, *level*]])

Prints an indented representation of the content types of the message object structure. For example:

```

>>> msg = email.message_from_file(somefile)
>>> _structure(msg)
multipart/mixed
  text/plain
  text/plain
  multipart/digest
    message/rfc822
      text/plain
    message/rfc822
      text/plain
    message/rfc822
      text/plain
    message/rfc822
      text/plain
    message/rfc822
      text/plain
    message/rfc822
      text/plain
  text/plain

```

Optional *fp* is a file-like object to print the output to. It must be suitable for Python's extended print statement. *level* is used internally.

7.1.11 Package History

This table describes the release history of the email package, corresponding to the version of Python that the package was released with. For purposes of this document, when you see a note about change or added versions, these refer to the Python version the change was made in, *not* the email package version. This table also describes the Python compatibility of each version of the package.

email version	distributed with	compatible with
1.x	Python 2.2.0 to Python 2.2.1	<i>no longer supported</i>
2.5	Python 2.2.2+ and Python 2.3	Python 2.1 to 2.5
3.0	Python 2.4	Python 2.3 to 2.5
4.0	Python 2.5	Python 2.3 to 2.5

Here are the major differences between email version 4 and version 3:

- All modules have been renamed according to PEP 8 standards. For example, the version 3 module `email.Message` was renamed to `email.message` in version 4.
- A new subpackage `email.mime` was added and all the version 3 `email.MIME*` modules were renamed and situated into the `email.mime` subpackage. For example, the version 3 module `email.MIMEText` was renamed to `email.mime.text`.
Note that the version 3 names will continue to work until Python 2.6.
- The `email.mime.application` module was added, which contains the `MIMEApplication` class.
- Methods that were deprecated in version 3 have been removed. These include `Generator.__call__()`, `Message.get_type()`, `Message.get_main_type()`, `Message.get_subtype()`.
- Fixes have been added for RFC 2231 support which can change some of the return types for `Message.get_param()` and friends. Under some circumstances, values which used to return a 3-tuple now return simple strings (specifically, if all extended parameter segments were unencoded, there is no language and charset designation expected, so the return type is now a simple string). Also, %-decoding used to be done for both encoded and unencoded segments; this decoding is now done only for encoded segments.

Here are the major differences between email version 3 and version 2:

- The `FeedParser` class was introduced, and the `Parser` class was implemented in terms of the `FeedParser`. All parsing therefore is non-strict, and parsing will make a best effort never to raise an exception. Problems found while parsing messages are stored in the message's *defect* attribute.
- All aspects of the API which raised `DeprecationWarnings` in version 2 have been removed. These include the `_encoder` argument to the `MIMEText` constructor, the `Message.add_payload()` method, the `Utils.dump_address_pair()` function, and the functions `Utils.decode()` and `Utils.encode()`.
- New `DeprecationWarnings` have been added to: `Generator.__call__()`, `Message.get_type()`, `Message.get_main_type()`, `Message.get_subtype()`, and the *strict* argument to the `Parser` class. These are expected to be removed in future versions.
- Support for Pythons earlier than 2.3 has been removed.

Here are the differences between email version 2 and version 1:

- The `email.Header` and `email.Charset` modules have been added.
- The pickle format for `Message` instances has changed. Since this was never (and still isn't) formally defined, this isn't considered a backward incompatibility. However if your application pickles and unpickles `Message` instances, be aware that in email version 2, `Message` instances now have private variables `_charset` and `_default_type`.
- Several methods in the `Message` class have been deprecated, or their signatures changed. Also, many new methods have been added. See the documentation for the `Message` class for details. The changes should be completely backward compatible.
- The object structure has changed in the face of `message/rfc822` content types. In email version 1, such a type would be represented by a scalar payload, i.e. the container message's `is_multipart()` returned false, `get_payload()` was not a list object, but a single `Message` instance.
This structure was inconsistent with the rest of the package, so the object representation for `message/rfc822` content types was changed. In email version 2, the container *does* return True from `is_multipart()`, and `get_payload()` returns a list containing a single `Message` item.
Note that this is one place that backward compatibility could not be completely maintained. However, if you're already testing the return type of `get_payload()`, you should be fine. You just need to make sure your code doesn't do a `set_payload()` with a `Message` instance on a container with a content type of `message/rfc822`.
- The `Parser` constructor's *strict* argument was added, and its `parse()` and `parsestr()` methods grew a *headersonly* argument. The *strict* flag was also added to functions `email.message_from_file()` and `email.message_from_string()`.
- `Generator.__call__()` is deprecated; use `Generator.flatten()` instead. The `Generator` class has also grown the `clone()` method.
- The `DecodedGenerator` class in the `email.Generator` module was added.
- The intermediate base classes `MIMENonMultipart` and `MIMEMultipart` have been added, and interposed in the class hierarchy for most of the other MIME-related derived classes.
- The `_encoder` argument to the `MIMEText` constructor has been deprecated. Encoding now happens implicitly based on the `_charset` argument.
- The following functions in the `email.Utils` module have been deprecated: `dump_address_pairs()`, `decode()`, and `encode()`. The following functions have been added to the module: `make_msgid()`, `decode_rfc2231()`, `encode_rfc2231()`, and `decode_params()`.
- The non-public function `email.Iterators._structure()` was added.

7.1.12 Differences from `mimelib`

The `email` package was originally prototyped as a separate library called `mimelib`. Changes have been made so that method names are more consistent, and some methods or modules have either been added or removed. The semantics of some of the methods have also changed. For the most part, any functionality available in `mimelib` is still available in the `email` package, albeit often in a different way. Backward compatibility between the `mimelib` package and the `email` package was not a priority.

Here is a brief description of the differences between the `mimelib` and the `email` packages, along with hints on how to port your applications.

Of course, the most visible difference between the two packages is that the package name has been changed to `email`. In addition, the top-level package has the following differences:

- `messageFromString()` has been renamed to `message_from_string()`.
- `messageFromFile()` has been renamed to `message_from_file()`.

The `Message` class has the following differences:

- The method `asString()` was renamed to `as_string()`.
- The method `ismultipart()` was renamed to `is_multipart()`.
- The `get_payload()` method has grown a *decode* optional argument.
- The method `getall()` was renamed to `get_all()`.
- The method `addheader()` was renamed to `add_header()`.
- The method `gettype()` was renamed to `get_type()`.
- The method `getmaintype()` was renamed to `get_main_type()`.
- The method `getsubtype()` was renamed to `get_subtype()`.
- The method `getparams()` was renamed to `get_params()`. Also, whereas `getparams()` returned a list of strings, `get_params()` returns a list of 2-tuples, effectively the key/value pairs of the parameters, split on the '=' sign.
- The method `getparam()` was renamed to `get_param()`.
- The method `getcharsets()` was renamed to `get_charsets()`.
- The method `getfilename()` was renamed to `get_filename()`.
- The method `getboundary()` was renamed to `get_boundary()`.
- The method `setboundary()` was renamed to `set_boundary()`.
- The method `getdecodedpayload()` was removed. To get similar functionality, pass the value 1 to the *decode* flag of the `get_payload()` method.
- The method `getpayloadastext()` was removed. Similar functionality is supported by the `DecodedGenerator` class in the `email.generator` module.
- The method `getbodyastext()` was removed. You can get similar functionality by creating an iterator with `typed_subpart_iterator()` in the `email.iterators` module.

The `Parser` class has no differences in its public interface. It does have some additional smarts to recognize message/delivery-status type messages, which it represents as a `Message` instance containing separate `Message` subparts for each header block in the delivery status notification⁴.

The `Generator` class has no differences in its public interface. There is a new class in the `email.generator` module though, called `DecodedGenerator` which provides most of the functionality previously available in the `Message.getpayloadastext()` method.

The following modules and classes have been changed:

- The `MIMEBase` class constructor arguments `_major` and `_minor` have changed to `_maintype` and `_subtype` respectively.
- The `Image` class/module has been renamed to `MIMEImage`. The `_minor` argument has been renamed to `_subtype`.
- The `Text` class/module has been renamed to `MIMEText`. The `_minor` argument has been renamed to `_subtype`.
- The `MessageRFC822` class/module has been renamed to `MIMEMessage`. Note that an earlier version of `mimelib` called this class/module `RFC822`, but that clashed with the Python standard library module `rfc822` on some case-insensitive file systems.

Also, the `MIMEMessage` class now represents any kind of MIME message with main type `message`. It takes an optional argument `_subtype` which is used to set the MIME subtype. `_subtype` defaults to `rfc822`.

`mimelib` provided some utility functions in its `address` and `date` modules. All of these functions have been moved to the `email.utils` module.

The `MsgReader` class/module has been removed. Its functionality is most closely supported in the `body_line_iterator()` function in the `email.iterators` module.

7.1.13 Examples

Here are a few examples of how to use the `email` package to read, write, and send simple email messages, as well as more complex MIME messages.

First, let's see how to create and send a simple text message:

```
# Import smtplib for the actual sending function
import smtplib

# Import the email modules we'll need
from email.mime.text import MIMEText

# Open a plain text file for reading. For this example, assume that
# the text file contains only ASCII characters.
fp = open(textfile, 'rb')
# Create a text/plain message
msg = MIMEText(fp.read())
fp.close()

# me == the sender's email address
# you == the recipient's email address
msg['Subject'] = 'The contents of %s' % textfile
msg['From'] = me
msg['To'] = you
```

⁴Delivery Status Notifications (DSN) are defined in RFC 1894.

```

# Send the message via our own SMTP server, but don't include the
# envelope header.
s = smtplib.SMTP()
s.connect()
s.sendmail(me, [you], msg.as_string())
s.close()

```

Here's an example of how to send a MIME message containing a bunch of family pictures that may be residing in a directory:

```

# Import smtplib for the actual sending function
import smtplib

# Here are the email package modules we'll need
from email.mime.image import MIMEImage
from email.mime.multipart import MIMEMultipart

COMMASPACE = ', '

# Create the container (outer) email message.
msg = MIMEMultipart()
msg['Subject'] = 'Our family reunion'
# me == the sender's email address
# family = the list of all recipients' email addresses
msg['From'] = me
msg['To'] = COMMASPACE.join(family)
msg.preamble = 'Our family reunion'

# Assume we know that the image files are all in PNG format
for file in pngfiles:
    # Open the files in binary mode. Let the MIMEImage class automatically
    # guess the specific image type.
    fp = open(file, 'rb')
    img = MIMEImage(fp.read())
    fp.close()
    msg.attach(img)

# Send the email via our own SMTP server.
s = smtplib.SMTP()
s.connect()
s.sendmail(me, family, msg.as_string())
s.close()

```

Here's an example of how to send the entire contents of a directory as an email message:⁵

```

#!/usr/bin/env python

"""Send the contents of a directory as a MIME message."""

import os
import sys
import smtplib
# For guessing MIME type based on file name extension
import mimetypes

from optparse import OptionParser

```

⁵Thanks to Matthew Dixon Cowles for the original inspiration and examples.

```

from email import encoders
from email.message import Message
from email.mime.audio import MIMEAudio
from email.mime.base import MIMEBase
from email.mime.image import MIMEImage
from email.mime.multipart import MIMEMultipart
from email.mime.text import MIMEText

COMMASPACE = ', '

def main():
    parser = OptionParser(usage="""\
Send the contents of a directory as a MIME message.

Usage: %prog [options]

Unless the -o option is given, the email is sent by forwarding to your local
SMTP server, which then does the normal delivery process. Your local machine
must be running an SMTP server.
""")
    parser.add_option('-d', '--directory',
                      type='string', action='store',
                      help="""Mail the contents of the specified directory,
otherwise use the current directory. Only the regular
files in the directory are sent, and we don't recurse to
subdirectories.""")
    parser.add_option('-o', '--output',
                      type='string', action='store', metavar='FILE',
                      help="""Print the composed message to FILE instead of
sending the message to the SMTP server.""")
    parser.add_option('-s', '--sender',
                      type='string', action='store', metavar='SENDER',
                      help='The value of the From: header (required)')
    parser.add_option('-r', '--recipient',
                      type='string', action='append', metavar='RECIPIENT',
                      default=[], dest='recipients',
                      help='A To: header value (at least one required)')
    opts, args = parser.parse_args()
    if not opts.sender or not opts.recipients:
        parser.print_help()
        sys.exit(1)
    directory = opts.directory
    if not directory:
        directory = '.'
    # Create the enclosing (outer) message
    outer = MIMEMultipart()
    outer['Subject'] = 'Contents of directory %s' % os.path.abspath(directory)
    outer['To'] = COMMASPACE.join(opts.recipients)
    outer['From'] = opts.sender
    outer.preamble = 'You will not see this in a MIME-aware mail reader.\n'

    for filename in os.listdir(directory):
        path = os.path.join(directory, filename)
        if not os.path.isfile(path):
            continue
        # Guess the content type based on the file's extension. Encoding
        # will be ignored, although we should check for simple things like
        # gzip'd or compressed files.

```

```

ctype, encoding = mimetypes.guess_type(path)
if ctype is None or encoding is not None:
    # No guess could be made, or the file is encoded (compressed), so
    # use a generic bag-of-bits type.
    ctype = 'application/octet-stream'
maintype, subtype = ctype.split('/', 1)
if maintype == 'text':
    fp = open(path)
    # Note: we should handle calculating the charset
    msg = MIMEText(fp.read(), _subtype=subtype)
    fp.close()
elif maintype == 'image':
    fp = open(path, 'rb')
    msg = MIMEImage(fp.read(), _subtype=subtype)
    fp.close()
elif maintype == 'audio':
    fp = open(path, 'rb')
    msg = MIMEAudio(fp.read(), _subtype=subtype)
    fp.close()
else:
    fp = open(path, 'rb')
    msg = MIMEBase(maintype, subtype)
    msg.set_payload(fp.read())
    fp.close()
    # Encode the payload using Base64
    encoders.encode_base64(msg)
    # Set the filename parameter
    msg.add_header('Content-Disposition', 'attachment', filename=filename)
outer.attach(msg)
# Now send or store the message
composed = outer.as_string()
if opts.output:
    fp = open(opts.output, 'w')
    fp.write(composed)
    fp.close()
else:
    s = smtplib.SMTP()
    s.connect()
    s.sendmail(opts.sender, opts.recipients, composed)
    s.close()

if __name__ == '__main__':
    main()

```

And finally, here's an example of how to unpack a MIME message like the one above, into a directory of files:

```

#!/usr/bin/env python

"""Unpack a MIME message into a directory of files."""

import os
import sys
import email
import errno
import mimetypes

from optparse import OptionParser

```

```

def main():
    parser = OptionParser(usage="""\
Unpack a MIME message into a directory of files.

Usage: %prog [options] msgfile
""")
    parser.add_option('-d', '--directory',
                      type='string', action='store',
                      help="""Unpack the MIME message into the named
                      directory, which will be created if it doesn't already
                      exist.""")
    opts, args = parser.parse_args()
    if not opts.directory:
        parser.print_help()
        sys.exit(1)

    try:
        msgfile = args[0]
    except IndexError:
        parser.print_help()
        sys.exit(1)

    try:
        os.mkdir(opts.directory)
    except OSError, e:
        # Ignore directory exists error
        if e.errno <> errno.EEXIST:
            raise

    fp = open(msgfile)
    msg = email.message_from_file(fp)
    fp.close()

    counter = 1
    for part in msg.walk():
        # multipart/* are just containers
        if part.get_content_maintype() == 'multipart':
            continue
        # Applications should really sanitize the given filename so that an
        # email message can't be used to overwrite important files
        filename = part.get_filename()
        if not filename:
            ext = mimetypes.guess_extension(part.get_content_type())
            if not ext:
                # Use a generic bag-of-bits extension
                ext = '.bin'
            filename = 'part-%03d%s' % (counter, ext)
        counter += 1
        fp = open(os.path.join(opts.directory, filename), 'wb')
        fp.write(part.get_payload(decode=True))
        fp.close()

if __name__ == '__main__':
    main()

```

7.2 mailcap — Mailcap file handling.

Mailcap files are used to configure how MIME-aware applications such as mail readers and Web browsers react to files with different MIME types. (The name “mailcap” is derived from the phrase “mail capability”.) For example, a mailcap file might contain a line like `video/mpeg; xmpeg %s`. Then, if the user encounters an email message or Web document with the MIME type `video/mpeg`, `%s` will be replaced by a filename (usually one belonging to a temporary file) and the **xmpeg** program can be automatically started to view the file.

The mailcap format is documented in RFC 1524, “A User Agent Configuration Mechanism For Multimedia Mail Format Information,” but is not an Internet standard. However, mailcap files are supported on most UNIX systems.

findmatch (*caps*, *MIMEtype* [, *key* [, *filename* [, *plist*]]])

Return a 2-tuple; the first element is a string containing the command line to be executed (which can be passed to `os.system()`), and the second element is the mailcap entry for a given MIME type. If no matching MIME type can be found, `(None, None)` is returned.

key is the name of the field desired, which represents the type of activity to be performed; the default value is `'view'`, since in the most common case you simply want to view the body of the MIME-typed data. Other possible values might be `'compose'` and `'edit'`, if you wanted to create a new body of the given MIME type or alter the existing body data. See RFC 1524 for a complete list of these fields.

filename is the filename to be substituted for `%s` in the command line; the default value is `'/dev/null'` which is almost certainly not what you want, so usually you'll override it by specifying a filename.

plist can be a list containing named parameters; the default value is simply an empty list. Each entry in the list must be a string containing the parameter name, an equals sign (`'='`), and the parameter's value. Mailcap entries can contain named parameters like `%{foo}`, which will be replaced by the value of the parameter named `'foo'`. For example, if the command line `'showpartial %{id} %{number} %{total}'` was in a mailcap file, and *plist* was set to `['id=1', 'number=2', 'total=3']`, the resulting command line would be `'showpartial 1 2 3'`.

In a mailcap file, the “test” field can optionally be specified to test some external condition (such as the machine architecture, or the window system in use) to determine whether or not the mailcap line applies. `findmatch()` will automatically check such conditions and skip the entry if the check fails.

getcaps ()

Returns a dictionary mapping MIME types to a list of mailcap file entries. This dictionary must be passed to the `findmatch()` function. An entry is stored as a list of dictionaries, but it shouldn't be necessary to know the details of this representation.

The information is derived from all of the mailcap files found on the system. Settings in the user's mailcap file `‘$HOME/mailcap’` will override settings in the system mailcap files `‘/etc/mailcap’`, `‘/usr/etc/mailcap’`, and `‘/usr/local/etc/mailcap’`.

An example usage:

```
>>> import mailcap
>>> d=mailcap.getcaps()
>>> mailcap.findmatch(d, 'video/mpeg', filename='/tmp/tmp1223')
('xmpeg /tmp/tmp1223', {'view': 'xmpeg %s'})
```

7.3 mailbox — Manipulate mailboxes in various formats

This module defines two classes, `Mailbox` and `Message`, for accessing and manipulating on-disk mailboxes and the messages they contain. `Mailbox` offers a dictionary-like mapping from keys to messages. `Message` extends the

`email.Message` module's `Message` class with format-specific state and behavior. Supported mailbox formats are Maildir, mbox, MH, Babyl, and MMDF.

See Also:

[Module `email`](#) (section 7.1):

Represent and manipulate messages.

7.3.1 Mailbox objects

class `Mailbox`

A mailbox, which may be inspected and modified.

The `Mailbox` class defines an interface and is not intended to be instantiated. Instead, format-specific subclasses should inherit from `Mailbox` and your code should instantiate a particular subclass.

The `Mailbox` interface is dictionary-like, with small keys corresponding to messages. Keys are issued by the `Mailbox` instance with which they will be used and are only meaningful to that `Mailbox` instance. A key continues to identify a message even if the corresponding message is modified, such as by replacing it with another message.

Messages may be added to a `Mailbox` instance using the set-like method `add()` and removed using a `del` statement or the set-like methods `remove()` and `discard()`.

`Mailbox` interface semantics differ from dictionary semantics in some noteworthy ways. Each time a message is requested, a new representation (typically a `Message` instance) is generated based upon the current state of the mailbox. Similarly, when a message is added to a `Mailbox` instance, the provided message representation's contents are copied. In neither case is a reference to the message representation kept by the `Mailbox` instance.

The default `Mailbox` iterator iterates over message representations, not keys as the default dictionary iterator does. Moreover, modification of a mailbox during iteration is safe and well-defined. Messages added to the mailbox after an iterator is created will not be seen by the iterator. Messages removed from the mailbox before the iterator yields them will be silently skipped, though using a key from an iterator may result in a `KeyError` exception if the corresponding message is subsequently removed.

Warning: Be very cautious when modifying mailboxes that might be simultaneously changed by some other process. The safest mailbox format to use for such tasks is Maildir; try to avoid using single-file formats such as mbox for concurrent writing. If you're modifying a mailbox, you *must* lock it by calling the `lock()` and `unlock()` methods *before* reading any messages in the file or making any changes by adding or deleting a message. Failing to lock the mailbox runs the risk of losing messages or corrupting the entire mailbox.

`Mailbox` instances have the following methods:

`add(message)`

Add *message* to the mailbox and return the key that has been assigned to it.

Parameter *message* may be a `Message` instance, an `email.Message.Message` instance, a string, or a file-like object (which should be open in text mode). If *message* is an instance of the appropriate format-specific `Message` subclass (e.g., if it's an `mboxMessage` instance and this is an `mbox` instance), its format-specific information is used. Otherwise, reasonable defaults for format-specific information are used.

`remove(key)`

`__delitem__(key)`

`discard(key)`

Delete the message corresponding to *key* from the mailbox.

If no such message exists, a `KeyError` exception is raised if the method was called as `remove()` or `__delitem__()` but no exception is raised if the method was called as `discard()`. The behavior of `discard()` may be preferred if the underlying mailbox format supports concurrent modification by other

processes.

__setitem__ (*key*, *message*)

Replace the message corresponding to *key* with *message*. Raise a `KeyError` exception if no message already corresponds to *key*.

As with `add()`, parameter *message* may be a `Message` instance, an `email.Message.Message` instance, a string, or a file-like object (which should be open in text mode). If *message* is an instance of the appropriate format-specific `Message` subclass (e.g., if it's an `mboxMessage` instance and this is an `mbox` instance), its format-specific information is used. Otherwise, the format-specific information of the message that currently corresponds to *key* is left unchanged.

iterkeys ()

keys ()

Return an iterator over all keys if called as `iterkeys()` or return a list of keys if called as `keys()`.

itervalues ()

__iter__ ()

values ()

Return an iterator over representations of all messages if called as `itervalues()` or `__iter__()` or return a list of such representations if called as `values()`. The messages are represented as instances of the appropriate format-specific `Message` subclass unless a custom message factory was specified when the `Mailbox` instance was initialized. **Note:** The behavior of `__iter__()` is unlike that of dictionaries, which iterate over keys.

iteritems ()

items ()

Return an iterator over (*key*, *message*) pairs, where *key* is a key and *message* is a message representation, if called as `iteritems()` or return a list of such pairs if called as `items()`. The messages are represented as instances of the appropriate format-specific `Message` subclass unless a custom message factory was specified when the `Mailbox` instance was initialized.

get (*key* [, *default=None*])

__getitem__ (*key*)

Return a representation of the message corresponding to *key*. If no such message exists, *default* is returned if the method was called as `get()` and a `KeyError` exception is raised if the method was called as `__getitem__()`. The message is represented as an instance of the appropriate format-specific `Message` subclass unless a custom message factory was specified when the `Mailbox` instance was initialized.

get_message (*key*)

Return a representation of the message corresponding to *key* as an instance of the appropriate format-specific `Message` subclass, or raise a `KeyError` exception if no such message exists.

get_string (*key*)

Return a string representation of the message corresponding to *key*, or raise a `KeyError` exception if no such message exists.

get_file (*key*)

Return a file-like representation of the message corresponding to *key*, or raise a `KeyError` exception if no such message exists. The file-like object behaves as if open in binary mode. This file should be closed once it is no longer needed.

Note: Unlike other representations of messages, file-like representations are not necessarily independent of the `Mailbox` instance that created them or of the underlying mailbox. More specific documentation is provided by each subclass.

has_key (*key*)

__contains__ (*key*)

Return `True` if *key* corresponds to a message, `False` otherwise.

__len__ ()

Return a count of messages in the mailbox.

clear()

Delete all messages from the mailbox.

pop(*key* [, *default*])

Return a representation of the message corresponding to *key* and delete the message. If no such message exists, return *default* if it was supplied or else raise a `KeyError` exception. The message is represented as an instance of the appropriate format-specific `Message` subclass unless a custom message factory was specified when the `Mailbox` instance was initialized.

popitem()

Return an arbitrary (*key*, *message*) pair, where *key* is a key and *message* is a message representation, and delete the corresponding message. If the mailbox is empty, raise a `KeyError` exception. The message is represented as an instance of the appropriate format-specific `Message` subclass unless a custom message factory was specified when the `Mailbox` instance was initialized.

update(*arg*)

Parameter *arg* should be a *key-to-message* mapping or an iterable of (*key*, *message*) pairs. Updates the mailbox so that, for each given *key* and *message*, the message corresponding to *key* is set to *message* as if by using `__setitem__()`. As with `__setitem__()`, each *key* must already correspond to a message in the mailbox or else a `KeyError` exception will be raised, so in general it is incorrect for *arg* to be a `Mailbox` instance.

Note: Unlike with dictionaries, keyword arguments are not supported.

flush()

Write any pending changes to the filesystem. For some `Mailbox` subclasses, changes are always written immediately and `flush()` does nothing, but you should still make a habit of calling this method.

lock()

Acquire an exclusive advisory lock on the mailbox so that other processes know not to modify it. An `ExternalClashError` is raised if the lock is not available. The particular locking mechanisms used depend upon the mailbox format. You should *always* lock the mailbox before making any modifications to its contents.

unlock()

Release the lock on the mailbox, if any.

close()

Flush the mailbox, unlock it if necessary, and close any open files. For some `Mailbox` subclasses, this method does nothing.

`Maildir`

class Maildir(*dirname* [, *factory*=`rfc822.Message` [, *create*=`True`]])

A subclass of `Mailbox` for mailboxes in Maildir format. Parameter *factory* is a callable object that accepts a file-like message representation (which behaves as if opened in binary mode) and returns a custom representation. If *factory* is `None`, `MaildirMessage` is used as the default message representation. If *create* is `True`, the mailbox is created if it does not exist.

It is for historical reasons that *factory* defaults to `rfc822.Message` and that *dirname* is named as such rather than *path*. For a `Maildir` instance that behaves like instances of other `Mailbox` subclasses, set *factory* to `None`.

Maildir is a directory-based mailbox format invented for the qmail mail transfer agent and now widely supported by other programs. Messages in a Maildir mailbox are stored in separate files within a common directory structure. This design allows Maildir mailboxes to be accessed and modified by multiple unrelated programs without data corruption, so file locking is unnecessary.

Maildir mailboxes contain three subdirectories, namely: 'tmp', 'new', and 'cur'. Messages are created momentarily in the 'tmp' subdirectory and then moved to the 'new' subdirectory to finalize delivery. A mail user agent may subsequently move the message to the 'cur' subdirectory and store information about the state of the message in a special "info" section appended to its file name.

Folders of the style introduced by the Courier mail transfer agent are also supported. Any subdirectory of the main mailbox is considered a folder if '.' is the first character in its name. Folder names are represented by Maildir without the leading '.'. Each folder is itself a Maildir mailbox but should not contain other folders. Instead, a logical nesting is indicated using '.' to delimit levels, e.g., "Archived.2005.07".

Note: The Maildir specification requires the use of a colon (':') in certain message file names. However, some operating systems do not permit this character in file names. If you wish to use a Maildir-like format on such an operating system, you should specify another character to use instead. The exclamation point ('!') is a popular choice. For example:

```
import mailbox
mailbox.Maildir.colon = '!'
```

The `colon` attribute may also be set on a per-instance basis.

Maildir instances have all of the methods of Mailbox in addition to the following:

list_folders()

Return a list of the names of all folders.

get_folder(folder)

Return a Maildir instance representing the folder whose name is *folder*. A `NoSuchMailboxError` exception is raised if the folder does not exist.

add_folder(folder)

Create a folder whose name is *folder* and return a Maildir instance representing it.

remove_folder(folder)

Delete the folder whose name is *folder*. If the folder contains any messages, a `NotEmptyError` exception will be raised and the folder will not be deleted.

clean()

Delete temporary files from the mailbox that have not been accessed in the last 36 hours. The Maildir specification says that mail-reading programs should do this occasionally.

Some Mailbox methods implemented by Maildir deserve special remarks:

add(message)

__setitem__(key, message)

update(arg)

Warning: These methods generate unique file names based upon the current process ID. When using multiple threads, undetected name clashes may occur and cause corruption of the mailbox unless threads are coordinated to avoid using these methods to manipulate the same mailbox simultaneously.

flush()

All changes to Maildir mailboxes are immediately applied, so this method does nothing.

lock()

unlock()

Maildir mailboxes do not support (or require) locking, so these methods do nothing.

close()

Maildir instances do not keep any open files and the underlying mailboxes do not support locking, so this method does nothing.

get_file(key)

Depending upon the host platform, it may not be possible to modify or remove the underlying message while the returned file remains open.

See Also:

[maildir man page from qmail](#)

The original specification of the format.

[Using maildir format](#)

Notes on Maildir by its inventor. Includes an updated name-creation scheme and details on "info" semantics.

[maildir man page from Courier](#)

Another specification of the format. Describes a common extension for supporting folders.

mbox

class `mbox` (*path*[, *factory*=None[, *create*=True]])

A subclass of `Mailbox` for mailboxes in mbox format. Parameter *factory* is a callable object that accepts a file-like message representation (which behaves as if opened in binary mode) and returns a custom representation. If *factory* is None, `mboxMessage` is used as the default message representation. If *create* is True, the mailbox is created if it does not exist.

The mbox format is the classic format for storing mail on UNIX systems. All messages in an mbox mailbox are stored in a single file with the beginning of each message indicated by a line whose first five characters are "From ".

Several variations of the mbox format exist to address perceived shortcomings in the original. In the interest of compatibility, `mbox` implements the original format, which is sometimes referred to as *mboxo*. This means that the Content-Length: header, if present, is ignored and that any occurrences of "From " at the beginning of a line in a message body are transformed to "From " when storing the message, although occurrences of "From " are not transformed to "From " when reading the message.

Some `Mailbox` methods implemented by `mbox` deserve special remarks:

`get_file` (*key*)

Using the file after calling `flush()` or `close()` on the `mbox` instance may yield unpredictable results or raise an exception.

`lock` ()

`unlock` ()

Three locking mechanisms are used—dot locking and, if available, the `flock()` and `lockf()` system calls.

See Also:

[mbox man page from qmail](#)

A specification of the format and its variations.

[mbox man page from tin](#)

Another specification of the format, with details on locking.

[Configuring Netscape Mail on UNIX: Why The Content-Length Format is Bad](#)

An argument for using the original mbox format rather than a variation.

["mbox" is a family of several mutually incompatible mailbox formats](#)

A history of mbox variations.

MH

class `MH` (*path*[, *factory*=None[, *create*=True]])

A subclass of `Mailbox` for mailboxes in MH format. Parameter *factory* is a callable object that accepts a file-like message representation (which behaves as if opened in binary mode) and returns a custom representation.

If *factory* is `None`, `MHMessage` is used as the default message representation. If *create* is `True`, the mailbox is created if it does not exist.

MH is a directory-based mailbox format invented for the MH Message Handling System, a mail user agent. Each message in an MH mailbox resides in its own file. An MH mailbox may contain other MH mailboxes (called *folders*) in addition to messages. Folders may be nested indefinitely. MH mailboxes also support *sequences*, which are named lists used to logically group messages without moving them to sub-folders. Sequences are defined in a file called `‘.mh.sequences’` in each folder.

The `MH` class manipulates MH mailboxes, but it does not attempt to emulate all of **mh**’s behaviors. In particular, it does not modify and is not affected by the `‘context’` or `‘.mh.profile’` files that are used by **mh** to store its state and configuration.

MH instances have all of the methods of `Mailbox` in addition to the following:

list_folders ()

Return a list of the names of all folders.

get_folder (*folder*)

Return an MH instance representing the folder whose name is *folder*. A `NoSuchMailboxError` exception is raised if the folder does not exist.

add_folder (*folder*)

Create a folder whose name is *folder* and return an MH instance representing it.

remove_folder (*folder*)

Delete the folder whose name is *folder*. If the folder contains any messages, a `NotEmptyError` exception will be raised and the folder will not be deleted.

get_sequences ()

Return a dictionary of sequence names mapped to key lists. If there are no sequences, the empty dictionary is returned.

set_sequences (*sequences*)

Re-define the sequences that exist in the mailbox based upon *sequences*, a dictionary of names mapped to key lists, like returned by `get_sequences()`.

pack ()

Rename messages in the mailbox as necessary to eliminate gaps in numbering. Entries in the sequences list are updated correspondingly. **Note:** Already-issued keys are invalidated by this operation and should not be subsequently used.

Some `Mailbox` methods implemented by MH deserve special remarks:

remove (*key*)

__delitem__ (*key*)

discard (*key*)

These methods immediately delete the message. The MH convention of marking a message for deletion by prepending a comma to its name is not used.

lock ()

unlock ()

Three locking mechanisms are used—dot locking and, if available, the `flock()` and `lockf()` system calls. For MH mailboxes, locking the mailbox means locking the `‘.mh.sequences’` file and, only for the duration of any operations that affect them, locking individual message files.

get_file (*key*)

Depending upon the host platform, it may not be possible to remove the underlying message while the returned file remains open.

flush ()

All changes to MH mailboxes are immediately applied, so this method does nothing.

close()

MH instances do not keep any open files, so this method is equivalent to `unlock()`.

See Also:

[nmh - Message Handling System](#)

Home page of **nmh**, an updated version of the original **mh**.

[MH & nmh: Email for Users & Programmers](#)

A GPL-licensed book on **mh** and **nmh**, with some information on the mailbox format.

Babyl

class Babyl (*path*[, *factory*=None[, *create*=True]])

A subclass of `Mailbox` for mailboxes in Babyl format. Parameter *factory* is a callable object that accepts a file-like message representation (which behaves as if opened in binary mode) and returns a custom representation. If *factory* is None, `BabylMessage` is used as the default message representation. If *create* is `True`, the mailbox is created if it does not exist.

Babyl is a single-file mailbox format used by the Rmail mail user agent included with Emacs. The beginning of a message is indicated by a line containing the two characters Control-Underscore (`'\037'`) and Control-L (`'\014'`). The end of a message is indicated by the start of the next message or, in the case of the last message, a line containing a Control-Underscore (`'\037'`) character.

Messages in a Babyl mailbox have two sets of headers, original headers and so-called visible headers. Visible headers are typically a subset of the original headers that have been reformatted or abridged to be more attractive. Each message in a Babyl mailbox also has an accompanying list of *labels*, or short strings that record extra information about the message, and a list of all user-defined labels found in the mailbox is kept in the Babyl options section.

Babyl instances have all of the methods of `Mailbox` in addition to the following:

get_labels()

Return a list of the names of all user-defined labels used in the mailbox. **Note:** The actual messages are inspected to determine which labels exist in the mailbox rather than consulting the list of labels in the Babyl options section, but the Babyl section is updated whenever the mailbox is modified.

Some `Mailbox` methods implemented by Babyl deserve special remarks:

get_file(*key*)

In Babyl mailboxes, the headers of a message are not stored contiguously with the body of the message. To generate a file-like representation, the headers and body are copied together into a `StringIO` instance (from the `StringIO` module), which has an API identical to that of a file. As a result, the file-like object is truly independent of the underlying mailbox but does not save memory compared to a string representation.

lock()

unlock()

Three locking mechanisms are used—dot locking and, if available, the `flock()` and `lockf()` system calls.

See Also:

[Format of Version 5 Babyl Files](#)

A specification of the Babyl format.

[Reading Mail with Rmail](#)

The Rmail manual, with some information on Babyl semantics.

MMDF

class `MMDF` (*path* [, *factory*=None [, *create*=True]])

A subclass of `Mailbox` for mailboxes in MMDF format. Parameter *factory* is a callable object that accepts a file-like message representation (which behaves as if opened in binary mode) and returns a custom representation. If *factory* is None, `MMDFMessage` is used as the default message representation. If *create* is True, the mailbox is created if it does not exist.

MMDF is a single-file mailbox format invented for the Multichannel Memorandum Distribution Facility, a mail transfer agent. Each message is in the same form as an mbox message but is bracketed before and after by lines containing four Control-A (`'\001'`) characters. As with the mbox format, the beginning of each message is indicated by a line whose first five characters are "From ", but additional occurrences of "From " are not transformed to "¿From " when storing messages because the extra message separator lines prevent mistaking such occurrences for the starts of subsequent messages.

Some `Mailbox` methods implemented by `MMDF` deserve special remarks:

`get_file` (*key*)

Using the file after calling `flush()` or `close()` on the `MMDF` instance may yield unpredictable results or raise an exception.

`lock` ()

`unlock` ()

Three locking mechanisms are used—dot locking and, if available, the `flock()` and `lockf()` system calls.

See Also:

[mmdf man page from tin](#)

A specification of MMDF format from the documentation of tin, a newsreader.

[MMDF](#)

A Wikipedia article describing the Multichannel Memorandum Distribution Facility.

7.3.2 Message objects

class `Message` ([*message*])

A subclass of the `email.Message` module's `Message`. Subclasses of `mailbox.Message` add mailbox-format-specific state and behavior.

If *message* is omitted, the new instance is created in a default, empty state. If *message* is an `email.Message.Message` instance, its contents are copied; furthermore, any format-specific information is converted insofar as possible if *message* is a `Message` instance. If *message* is a string or a file, it should contain an RFC 2822-compliant message, which is read and parsed.

The format-specific state and behaviors offered by subclasses vary, but in general it is only the properties that are not specific to a particular mailbox that are supported (although presumably the properties are specific to a particular mailbox format). For example, file offsets for single-file mailbox formats and file names for directory-based mailbox formats are not retained, because they are only applicable to the original mailbox. But state such as whether a message has been read by the user or marked as important is retained, because it applies to the message itself.

There is no requirement that `Message` instances be used to represent messages retrieved using `Mailbox` instances. In some situations, the time and memory required to generate `Message` representations might not be acceptable. For such situations, `Mailbox` instances also offer string and file-like representations, and a custom message factory may be specified when a `Mailbox` instance is initialized.

`MaildirMessage`

class `MaildirMessage` ([*message*])

A message with Maildir-specific behaviors. Parameter *message* has the same meaning as with the `Message` constructor.

Typically, a mail user agent application moves all of the messages in the ‘new’ subdirectory to the ‘cur’ subdirectory after the first time the user opens and closes the mailbox, recording that the messages are old whether or not they’ve actually been read. Each message in ‘cur’ has an “info” section added to its file name to store information about its state. (Some mail readers may also add an “info” section to messages in ‘new’.) The “info” section may take one of two forms: it may contain “2,” followed by a list of standardized flags (e.g., “2,FR”) or it may contain “1,” followed by so-called experimental information. Standard flags for Maildir messages are as follows:

Flag	Meaning	Explanation
D	Draft	Under composition
F	Flagged	Marked as important
P	Passed	Forwarded, resent, or bounced
R	Replied	Replied to
S	Seen	Read
T	Trashed	Marked for subsequent deletion

MaildirMessage instances offer the following methods:

get_subdir()

Return either “new” (if the message should be stored in the ‘new’ subdirectory) or “cur” (if the message should be stored in the ‘cur’ subdirectory). **Note:** A message is typically moved from ‘new’ to ‘cur’ after its mailbox has been accessed, whether or not the message is has been read. A message `msg` has been read if “S” in `msg.get_flags()` is True.

set_subdir(subdir)

Set the subdirectory the message should be stored in. Parameter *subdir* must be either “new” or “cur”.

get_flags()

Return a string specifying the flags that are currently set. If the message complies with the standard Maildir format, the result is the concatenation in alphabetical order of zero or one occurrence of each of ‘D’, ‘F’, ‘P’, ‘R’, ‘S’, and ‘T’. The empty string is returned if no flags are set or if “info” contains experimental semantics.

set_flags(flags)

Set the flags specified by *flags* and unset all others.

add_flag(flag)

Set the flag(s) specified by *flag* without changing other flags. To add more than one flag at a time, *flag* may be a string of more than one character. The current “info” is overwritten whether or not it contains experimental information rather than flags.

remove_flag(flag)

Unset the flag(s) specified by *flag* without changing other flags. To remove more than one flag at a time, *flag* maybe a string of more than one character. If “info” contains experimental information rather than flags, the current “info” is not modified.

get_date()

Return the delivery date of the message as a floating-point number representing seconds since the epoch.

set_date(date)

Set the delivery date of the message to *date*, a floating-point number representing seconds since the epoch.

get_info()

Return a string containing the “info” for a message. This is useful for accessing and modifying “info” that is experimental (i.e., not a list of flags).

set_info(info)

Set “info” to *info*, which should be a string.

When a MaildirMessage instance is created based upon an mboxMessage or MMDFMessage instance, the Status: and X-Status: headers are omitted and the following conversions take place:

Resulting state	mboxMessage or MMDMessage state
"cur" subdirectory	O flag
F flag	F flag
R flag	A flag
S flag	R flag
T flag	D flag

When a MaildirMessage instance is created based upon an MHMessage instance, the following conversions take place:

Resulting state	MHMessage state
"cur" subdirectory	"unseen" sequence
"cur" subdirectory and S flag	no "unseen" sequence
F flag	"flagged" sequence
R flag	"replied" sequence

When a MaildirMessage instance is created based upon a Baby1Message instance, the following conversions take place:

Resulting state	Baby1Message state
"cur" subdirectory	"unseen" label
"cur" subdirectory and S flag	no "unseen" label
P flag	"forwarded" or "resent" label
R flag	"answered" label
T flag	"deleted" label

mboxMessage

class mboxMessage ([*message*])

A message with mbox-specific behaviors. Parameter *message* has the same meaning as with the Message constructor.

Messages in an mbox mailbox are stored together in a single file. The sender's envelope address and the time of delivery are typically stored in a line beginning with "From " that is used to indicate the start of a message, though there is considerable variation in the exact format of this data among mbox implementations. Flags that indicate the state of the message, such as whether it has been read or marked as important, are typically stored in Status: and X-Status: headers.

Conventional flags for mbox messages are as follows:

Flag	Meaning	Explanation
R	Read	Read
O	Old	Previously detected by MUA
D	Deleted	Marked for subsequent deletion
F	Flagged	Marked as important
A	Answered	Replied to

The "R" and "O" flags are stored in the Status: header, and the "D", "F", and "A" flags are stored in the X-Status: header. The flags and headers typically appear in the order mentioned.

mboxMessage instances offer the following methods:

get_from()

Return a string representing the "From " line that marks the start of the message in an mbox mailbox. The leading "From " and the trailing newline are excluded.

set_from (*from_* [, *time_* = None])

Set the "From " line to *from_*, which should be specified without a leading "From " or trailing newline. For convenience, *time_* may be specified and will be formatted appropriately and appended to *from_*. If *time_* is specified, it should be a `struct_time` instance, a tuple suitable for passing to `time.strftime()`, or `True` (to use `time.gmtime()`).

get_flags ()

Return a string specifying the flags that are currently set. If the message complies with the conventional format, the result is the concatenation in the following order of zero or one occurrence of each of 'R', 'O', 'D', 'F', and 'A'.

set_flags (*flags*)

Set the flags specified by *flags* and unset all others. Parameter *flags* should be the concatenation in any order of zero or more occurrences of each of 'R', 'O', 'D', 'F', and 'A'.

add_flag (*flag*)

Set the flag(s) specified by *flag* without changing other flags. To add more than one flag at a time, *flag* may be a string of more than one character.

remove_flag (*flag*)

Unset the flag(s) specified by *flag* without changing other flags. To remove more than one flag at a time, *flag* may be a string of more than one character.

When an `mboxMessage` instance is created based upon a `MaildirMessage` instance, a "From " line is generated based upon the `MaildirMessage` instance's delivery date, and the following conversions take place:

Resulting state	MaildirMessage state
R flag	S flag
O flag	"cur" subdirectory
D flag	T flag
F flag	F flag
A flag	R flag

When an `mboxMessage` instance is created based upon an `MHMessage` instance, the following conversions take place:

Resulting state	MHMessage state
R flag and O flag	no "unseen" sequence
O flag	"unseen" sequence
F flag	"flagged" sequence
A flag	"replied" sequence

When an `mboxMessage` instance is created based upon a `BabylMessage` instance, the following conversions take place:

Resulting state	BabylMessage state
R flag and O flag	no "unseen" label
O flag	"unseen" label
D flag	"deleted" label
A flag	"answered" label

When a `Message` instance is created based upon an `MMDFMessage` instance, the "From " line is copied and all flags directly correspond:

Resulting state	MMDFMessage state
R flag	R flag
O flag	O flag
D flag	D flag
F flag	F flag
A flag	A flag

MHMessage

class MHMessage (*[message]*)

A message with MH-specific behaviors. Parameter *message* has the same meaning as with the `Message` constructor.

MH messages do not support marks or flags in the traditional sense, but they do support sequences, which are logical groupings of arbitrary messages. Some mail reading programs (although not the standard **mh** and **nmh**) use sequences in much the same way flags are used with other formats, as follows:

Sequence	Explanation
unseen	Not read, but previously detected by MUA
replied	Replied to
flagged	Marked as important

MHMessage instances offer the following methods:

get_sequences ()

Return a list of the names of sequences that include this message.

set_sequences (*sequences*)

Set the list of sequences that include this message.

add_sequence (*sequence*)

Add *sequence* to the list of sequences that include this message.

remove_sequence (*sequence*)

Remove *sequence* from the list of sequences that include this message.

When an MHMessage instance is created based upon a MaildirMessage instance, the following conversions take place:

Resulting state	MaildirMessage state
"unseen" sequence	no S flag
"replied" sequence	R flag
"flagged" sequence	F flag

When an MHMessage instance is created based upon an mboxMessage or MMDFMessage instance, the Status: and X-Status: headers are omitted and the following conversions take place:

Resulting state	mboxMessage or MMDFMessage state
"unseen" sequence	no R flag
"replied" sequence	A flag
"flagged" sequence	F flag

When an MHMessage instance is created based upon a Baby1Message instance, the following conversions take place:

Resulting state	BabylMessage state
"unseen" sequence	"unseen" label
"replied" sequence	"answered" label

BabylMessage

class BabylMessage (*[message]*)

A message with Babyl-specific behaviors. Parameter *message* has the same meaning as with the `Message` constructor.

Certain message labels, called *attributes*, are defined by convention to have special meanings. The attributes are as follows:

Label	Explanation
unseen	Not read, but previously detected by MUA
deleted	Marked for subsequent deletion
filed	Copied to another file or mailbox
answered	Replied to
forwarded	Forwarded
edited	Modified by the user
resent	Resent

By default, Rmail displays only visible headers. The `BabylMessage` class, though, uses the original headers because they are more complete. Visible headers may be accessed explicitly if desired.

`BabylMessage` instances offer the following methods:

get_labels ()

Return a list of labels on the message.

set_labels (*labels*)

Set the list of labels on the message to *labels*.

add_label (*label*)

Add *label* to the list of labels on the message.

remove_label (*label*)

Remove *label* from the list of labels on the message.

get_visible ()

Return an `Message` instance whose headers are the message's visible headers and whose body is empty.

set_visible (*visible*)

Set the message's visible headers to be the same as the headers in *message*. Parameter *visible* should be a `Message` instance, an `email.Message.Message` instance, a string, or a file-like object (which should be open in text mode).

update_visible ()

When a `BabylMessage` instance's original headers are modified, the visible headers are not automatically modified to correspond. This method updates the visible headers as follows: each visible header with a corresponding original header is set to the value of the original header, each visible header without a corresponding original header is removed, and any of `Date:`, `From:`, `Reply-To:`, `To:`, `CC:`, and `Subject:` that are present in the original headers but not the visible headers are added to the visible headers.

When a `BabylMessage` instance is created based upon a `MaildirMessage` instance, the following conversions take place:

Resulting state	MaildirMessage state
"unseen" label	no S flag
"deleted" label	T flag
"answered" label	R flag
"forwarded" label	P flag

When a `BabylMessage` instance is created based upon an `mboxMessage` or `MMDFMessage` instance, the `Status:` and `X-Status:` headers are omitted and the following conversions take place:

Resulting state	mboxMessage or MMDFMessage state
"unseen" label	no R flag
"deleted" label	D flag
"answered" label	A flag

When a `BabylMessage` instance is created based upon an `MHMessage` instance, the following conversions take place:

Resulting state	MHMessage state
"unseen" label	"unseen" sequence
"answered" label	"replied" sequence

`MMDFMessage`

class `MMDFMessage` (`[message]`)

A message with MMDF-specific behaviors. Parameter *message* has the same meaning as with the `Message` constructor.

As with message in an mbox mailbox, MMDF messages are stored with the sender's address and the delivery date in an initial line beginning with "From ". Likewise, flags that indicate the state of the message are typically stored in `Status:` and `X-Status:` headers.

Conventional flags for MMDF messages are identical to those of mbox message and are as follows:

Flag	Meaning	Explanation
R	Read	Read
O	Old	Previously detected by MUA
D	Deleted	Marked for subsequent deletion
F	Flagged	Marked as important
A	Answered	Replied to

The "R" and "O" flags are stored in the `Status:` header, and the "D", "F", and "A" flags are stored in the `X-Status:` header. The flags and headers typically appear in the order mentioned.

`MMDFMessage` instances offer the following methods, which are identical to those offered by `mboxMessage`:

`get_from()`

Return a string representing the "From " line that marks the start of the message in an mbox mailbox. The leading "From " and the trailing newline are excluded.

`set_from(from_, time_=None)`

Set the "From " line to *from_*, which should be specified without a leading "From " or trailing newline. For convenience, *time_* may be specified and will be formatted appropriately and appended to *from_*. If *time_* is specified, it should be a `struct_time` instance, a tuple suitable for passing to `time.strftime()`, or `True` (to use `time.gmtime()`).

get_flags()

Return a string specifying the flags that are currently set. If the message complies with the conventional format, the result is the concatenation in the following order of zero or one occurrence of each of 'R', 'O', 'D', 'F', and 'A'.

set_flags(flags)

Set the flags specified by *flags* and unset all others. Parameter *flags* should be the concatenation in any order of zero or more occurrences of each of 'R', 'O', 'D', 'F', and 'A'.

add_flag(flag)

Set the flag(s) specified by *flag* without changing other flags. To add more than one flag at a time, *flag* may be a string of more than one character.

remove_flag(flag)

Unset the flag(s) specified by *flag* without changing other flags. To remove more than one flag at a time, *flag* may be a string of more than one character.

When an `MMDFMessage` instance is created based upon a `MaildirMessage` instance, a "From" line is generated based upon the `MaildirMessage` instance's delivery date, and the following conversions take place:

Resulting state	MaildirMessage state
R flag	S flag
O flag	"cur" subdirectory
D flag	T flag
F flag	F flag
A flag	R flag

When an `MMDFMessage` instance is created based upon an `MHMessage` instance, the following conversions take place:

Resulting state	MHMessage state
R flag and O flag	no "unseen" sequence
O flag	"unseen" sequence
F flag	"flagged" sequence
A flag	"replied" sequence

When an `MMDFMessage` instance is created based upon a `BabylMessage` instance, the following conversions take place:

Resulting state	BabylMessage state
R flag and O flag	no "unseen" label
O flag	"unseen" label
D flag	"deleted" label
A flag	"answered" label

When an `MMDFMessage` instance is created based upon an `mboxMessage` instance, the "From" line is copied and all flags directly correspond:

Resulting state	mboxMessage state
R flag	R flag
O flag	O flag
D flag	D flag
F flag	F flag
A flag	A flag

7.3.3 Exceptions

The following exception classes are defined in the `mailbox` module:

class `Error` ()

The based class for all other module-specific exceptions.

class `NoSuchMailboxError` ()

Raised when a mailbox is expected but is not found, such as when instantiating a `Mailbox` subclass with a path that does not exist (and with the `create` parameter set to `False`), or when opening a folder that does not exist.

class `NotEmptyError` ()

Raised when a mailbox is not empty but is expected to be, such as when deleting a folder that contains messages.

class `ExternalClashError` ()

Raised when some mailbox-related condition beyond the control of the program causes it to be unable to proceed, such as when failing to acquire a lock that another program already holds a lock, or when a uniquely-generated file name already exists.

class `FormatError` ()

Raised when the data in a file cannot be parsed, such as when an MH instance attempts to read a corrupted `‘mh_sequences’` file.

7.3.4 Deprecated classes and methods

Older versions of the `mailbox` module do not support modification of mailboxes, such as adding or removing message, and do not provide classes to represent format-specific message properties. For backward compatibility, the older mailbox classes are still available, but the newer classes should be used in preference to them.

Older mailbox objects support only iteration and provide a single public method:

`next` ()

Return the next message in the mailbox, created with the optional *factory* argument passed into the mailbox object’s constructor. By default this is an `rfc822.Message` object (see the `rfc822` module). Depending on the mailbox implementation the *fp* attribute of this object may be a true file object or a class instance simulating a file object, taking care of things like message boundaries if multiple mail messages are contained in a single file, etc. If no more messages are available, this method returns `None`.

Most of the older mailbox classes have names that differ from the current mailbox class names, except for `Maildir`. For this reason, the new `Maildir` class defines a `next ()` method and its constructor differs slightly from those of the other new mailbox classes.

The older mailbox classes whose names are not the same as their newer counterparts are as follows:

class `UnixMailbox` (*fp* [, *factory*])

Access to a classic UNIX-style mailbox, where all messages are contained in a single file and separated by `‘From ’` (a.k.a. `‘From_’`) lines. The file object *fp* points to the mailbox file. The optional *factory* parameter is a callable that should create new message objects. *factory* is called with one argument, *fp* by the `next ()` method of the mailbox object. The default is the `rfc822.Message` class (see the `rfc822` module – and the note below).

Note: For reasons of this module’s internal implementation, you will probably want to open the *fp* object in binary mode. This is especially important on Windows.

For maximum portability, messages in a UNIX-style mailbox are separated by any line that begins exactly with the string `‘From ’` (note the trailing space) if preceded by exactly two newlines. Because of the wide-range of variations in practice, nothing else on the `From_` line should be considered. However, the current implementation doesn’t check for the leading two newlines. This is usually fine for most applications.

The `UnixMailbox` class implements a more strict version of `From_` line checking, using a regular expression that usually correctly matched `From_` delimiters. It considers delimiter line to be separated by `‘From name`

time’ lines. For maximum portability, use the `PortableUnixMailbox` class instead. This class is identical to `UnixMailbox` except that individual messages are separated by only ‘From ’ lines.

For more information, see [Configuring Netscape Mail on UNIX: Why the Content-Length Format is Bad](#).

class `PortableUnixMailbox` (*fp*[, *factory*])

A less-strict version of `UnixMailbox`, which considers only the ‘From ’ at the beginning of the line separating messages. The “*name time*” portion of the From line is ignored, to protect against some variations that are observed in practice. This works since lines in the message which begin with ‘From ’ are quoted by mail handling software at delivery-time.

class `MmdfMailbox` (*fp*[, *factory*])

Access an MMDF-style mailbox, where all messages are contained in a single file and separated by lines consisting of 4 control-A characters. The file object *fp* points to the mailbox file. Optional *factory* is as with the `UnixMailbox` class.

class `MHMailbox` (*dirname*[, *factory*])

Access an MH mailbox, a directory with each message in a separate file with a numeric name. The name of the mailbox directory is passed in *dirname*. *factory* is as with the `UnixMailbox` class.

class `BabylMailbox` (*fp*[, *factory*])

Access a Babyl mailbox, which is similar to an MMDF mailbox. In Babyl format, each message has two sets of headers, the *original* headers and the *visible* headers. The original headers appear before a line containing only ‘*** EOOH ***’ (End-Of-Original-Headers) and the visible headers appear after the EOOH line. Babyl-compliant mail readers will show you only the visible headers, and `BabylMailbox` objects will return messages containing only the visible headers. You’ll have to do your own parsing of the mailbox file to get at the original headers. Mail messages start with the EOOH line and end with a line containing only ‘\037\014’. *factory* is as with the `UnixMailbox` class.

If you wish to use the older mailbox classes with the `email` module rather than the deprecated `rfc822` module, you can do so as follows:

```
import email
import email.Errors
import mailbox

def msgfactory(fp):
    try:
        return email.message_from_file(fp)
    except email.Errors.MessageParseError:
        # Don't return None since that will
        # stop the mailbox iterator
        return ''

mbox = mailbox.UnixMailbox(fp, msgfactory)
```

Alternatively, if you know your mailbox contains only well-formed MIME messages, you can simplify this to:

```
import email
import mailbox

mbox = mailbox.UnixMailbox(fp, email.message_from_file)
```

7.3.5 Examples

A simple example of printing the subjects of all messages in a mailbox that seem interesting:

```
import mailbox
for message in mailbox.mbox('~/.mbox'):
    subject = message['subject']      # Could possibly be None.
    if subject and 'python' in subject.lower():
        print subject
```

To copy all mail from a Babyl mailbox to an MH mailbox, converting all of the format-specific information that can be converted:

```
import mailbox
destination = mailbox.MH('~/.Mail')
destination.lock()
for message in mailbox.Babyl('~/.RMAIL'):
    destination.add(MHMessage(message))
destination.flush()
destination.unlock()
```

This example sorts mail from several mailing lists into different mailboxes, being careful to avoid mail corruption due to concurrent modification by other programs, mail loss due to interruption of the program, or premature termination due to malformed messages in the mailbox:


```

import mailbox
import email.Errors

list_names = ('python-list', 'python-dev', 'python-bugs')

boxes = dict((name, mailbox.mbox('~/.email/%s' % name)) for name in list_names)
inbox = mailbox.Maildir('~/.Maildir', factory=None)

for key in inbox.iterkeys():
    try:
        message = inbox[key]
    except email.Errors.MessageParseError:
        continue          # The message is malformed. Just leave it.

    for name in list_names:
        list_id = message['list-id']
        if list_id and name in list_id:
            # Get mailbox to use
            box = boxes[name]

            # Write copy to disk before removing original.
            # If there's a crash, you might duplicate a message, but
            # that's better than losing a message completely.
            box.lock()
            box.add(message)
            box.flush()
            box.unlock()

            # Remove original message
            inbox.lock()
            inbox.discard(key)
            inbox.flush()
            inbox.unlock()
            break          # Found destination, so stop looking.

for box in boxes.itervalues():
    box.close()

```

7.4 mhtmlib — Access to MH mailboxes

The `mhtmlib` module provides a Python interface to MH folders and their contents.

The module contains three basic classes, `MH`, which represents a particular collection of folders, `Folder`, which represents a single folder, and `Message`, which represents a single message.

class `MH` (*[path[, profile]]*)

`MH` represents a collection of MH folders.

class `Folder` (*mh, name*)

The `Folder` class represents a single folder and its messages.

class `Message` (*folder, number[, name]*)

`Message` objects represent individual messages in a folder. The `Message` class is derived from `mimetools.Message`.

7.4.1 MH Objects

MH instances have the following methods:

error (*format*[, ...])
Print an error message – can be overridden.

getprofile (*key*)
Return a profile entry (None if not set).

getpath ()
Return the mailbox pathname.

getcontext ()
Return the current folder name.

setcontext (*name*)
Set the current folder name.

listfolders ()
Return a list of top-level folders.

listallfolders ()
Return a list of all folders.

listsubfolders (*name*)
Return a list of direct subfolders of the given folder.

listallsubfolders (*name*)
Return a list of all subfolders of the given folder.

makefolder (*name*)
Create a new folder.

deletefolder (*name*)
Delete a folder – must have no subfolders.

openfolder (*name*)
Return a new open folder object.

7.4.2 Folder Objects

Folder instances represent open folders and have the following methods:

error (*format*[, ...])
Print an error message – can be overridden.

getfullname ()
Return the folder's full pathname.

getsequencesfilename ()
Return the full pathname of the folder's sequences file.

getmessagefilename (*n*)
Return the full pathname of message *n* of the folder.

listmessages ()
Return a list of messages in the folder (as numbers).

getcurrent ()
Return the current message number.

setcurrent (*n*)

Set the current message number to *n*.

parsesequence (*seq*)

Parse msgs syntax into list of messages.

getlast ()

Get last message, or 0 if no messages are in the folder.

setlast (*n*)

Set last message (internal use only).

getsequences ()

Return dictionary of sequences in folder. The sequence names are used as keys, and the values are the lists of message numbers in the sequences.

putsequences (*dict*)

Return dictionary of sequences in folder name: list.

removemessages (*list*)

Remove messages in list from folder.

refilemessages (*list, tofolder*)

Move messages in list to other folder.

movemessage (*n, tofolder, ton*)

Move one message to a given destination in another folder.

copymessage (*n, tofolder, ton*)

Copy one message to a given destination in another folder.

7.4.3 Message Objects

The `Message` class adds one method to those of `mimertools.Message`:

openmessage (*n*)

Return a new open message object (costs a file descriptor).

7.5 `mimertools` — Tools for parsing MIME messages

Deprecated since release 2.3. The `email` package should be used in preference to the `mimertools` module. This module is present only to maintain backward compatibility.

This module defines a subclass of the `rfc822` module's `Message` class and a number of utility functions that are useful for the manipulation for MIME multipart or encoded message.

It defines the following items:

class Message (*fp* [, *seekable*])

Return a new instance of the `Message` class. This is a subclass of the `rfc822.Message` class, with some additional methods (see below). The *seekable* argument has the same meaning as for `rfc822.Message`.

choose_boundary ()

Return a unique string that has a high likelihood of being usable as a part boundary. The string has the form `'hostipaddr.uid.pid.timestamp.random'`.

decode (*input, output, encoding*)

Read data encoded using the allowed MIME *encoding* from open file object *input* and write the decoded data to open file object *output*. Valid values for *encoding* include `'base64'`, `'quoted-printable'`, `'uuencode'`, `'x-uuencode'`, `'uue'`, `'x-uue'`, `'7bit'`, and `'8bit'`. Decoding messages encoded

in '7bit' or '8bit' has no effect. The input is simply copied to the output.

encode (*input*, *output*, *encoding*)

Read data from open file object *input* and write it encoded using the allowed MIME *encoding* to open file object *output*. Valid values for *encoding* are the same as for `decode()`.

copyliteral (*input*, *output*)

Read lines from open file *input* until EOF and write them to open file *output*.

copybinary (*input*, *output*)

Read blocks until EOF from open file *input* and write them to open file *output*. The block size is currently fixed at 8192.

See Also:

Module [email](#) (section 7.1):

Comprehensive email handling package; supersedes the `mimertools` module.

Module [rfc822](#) (section 7.10):

Provides the base class for `mimertools.Message`.

Module [multifile](#) (section 7.9):

Support for reading files which contain distinct parts, such as MIME data.

<http://www.cs.uu.nl/wais/html/na-dir/mail/mime-faq.html>

The MIME Frequently Asked Questions document. For an overview of MIME, see the answer to question 1.1 in Part 1 of this document.

7.5.1 Additional Methods of Message Objects

The `Message` class defines the following methods in addition to the `rfc822.Message` methods:

getplist ()

Return the parameter list of the Content-Type: header. This is a list of strings. For parameters of the form 'key=value', *key* is converted to lower case but *value* is not. For example, if the message contains the header 'Content-type: text/html; spam=1; Spam=2; Spam' then `getplist()` will return the Python list ['spam=1', 'spam=2', 'Spam'].

getparam (*name*)

Return the *value* of the first parameter (as returned by `getplist()`) of the form '*name=value*' for the given *name*. If *value* is surrounded by quotes of the form '<...>' or '"..."', these are removed.

getencoding ()

Return the encoding specified in the Content-Transfer-Encoding: message header. If no such header exists, return '7bit'. The encoding is converted to lower case.

gettype ()

Return the message type (of the form '*type/subtype*') as specified in the Content-Type: header. If no such header exists, return 'text/plain'. The type is converted to lower case.

getmaintype ()

Return the main type as specified in the Content-Type: header. If no such header exists, return 'text'. The main type is converted to lower case.

getsubtype ()

Return the subtype as specified in the Content-Type: header. If no such header exists, return 'plain'. The subtype is converted to lower case.

7.6 `mimetypes` — Map filenames to MIME types

The `mimetypes` module converts between a filename or URL and the MIME type associated with the filename extension. Conversions are provided from filename to MIME type and from MIME type to filename extension; encodings are not supported for the latter conversion.

The module provides one class and a number of convenience functions. The functions are the normal interface to this module, but some applications may be interested in the class as well.

The functions described below provide the primary interface for this module. If the module has not been initialized, they will call `init()` if they rely on the information `init()` sets up.

`guess_type(filename[, strict])`

Guess the type of a file based on its filename or URL, given by *filename*. The return value is a tuple (*type*, *encoding*) where *type* is `None` if the type can't be guessed (missing or unknown suffix) or a string of the form '*type/subtype*', usable for a MIME content-type: header.

encoding is `None` for no encoding or the name of the program used to encode (e.g. **`compress`** or **`gzip`**). The encoding is suitable for use as a Content-Encoding: header, *not* as a Content-Transfer-Encoding: header. The mappings are table driven. Encoding suffixes are case sensitive; type suffixes are first tried case sensitively, then case insensitively.

Optional *strict* is a flag specifying whether the list of known MIME types is limited to only the official types [registered with IANA](#) are recognized. When *strict* is true (the default), only the IANA types are supported; when *strict* is false, some additional non-standard but commonly used MIME types are also recognized.

`guess_all_extensions(type[, strict])`

Guess the extensions for a file based on its MIME type, given by *type*. The return value is a list of strings giving all possible filename extensions, including the leading dot ('.'). The extensions are not guaranteed to have been associated with any particular data stream, but would be mapped to the MIME type *type* by `guess_type()`.

Optional *strict* has the same meaning as with the `guess_type()` function.

`guess_extension(type[, strict])`

Guess the extension for a file based on its MIME type, given by *type*. The return value is a string giving a filename extension, including the leading dot ('.'). The extension is not guaranteed to have been associated with any particular data stream, but would be mapped to the MIME type *type* by `guess_type()`. If no extension can be guessed for *type*, `None` is returned.

Optional *strict* has the same meaning as with the `guess_type()` function.

Some additional functions and data items are available for controlling the behavior of the module.

`init([files])`

Initialize the internal data structures. If given, *files* must be a sequence of file names which should be used to augment the default type map. If omitted, the file names to use are taken from `knownfiles`. Each file named in *files* or `knownfiles` takes precedence over those named before it. Calling `init()` repeatedly is allowed.

`read_mime_types(filename)`

Load the type map given in the file *filename*, if it exists. The type map is returned as a dictionary mapping filename extensions, including the leading dot ('.'), to strings of the form '*type/subtype*'. If the file *filename* does not exist or cannot be read, `None` is returned.

`add_type(type, ext[, strict])`

Add a mapping from the mimetype *type* to the extension *ext*. When the extension is already known, the new type will replace the old one. When the type is already known the extension will be added to the list of known extensions.

When *strict* is the mapping will added to the official MIME types, otherwise to the non-standard ones.

`inited`

Flag indicating whether or not the global data structures have been initialized. This is set to true by `init()`.

knownfiles

List of type map file names commonly installed. These files are typically named ‘mime.types’ and are installed in different locations by different packages.

suffix_map

Dictionary mapping suffixes to suffixes. This is used to allow recognition of encoded files for which the encoding and the type are indicated by the same extension. For example, the ‘.tgz’ extension is mapped to ‘.tar.gz’ to allow the encoding and type to be recognized separately.

encodings_map

Dictionary mapping filename extensions to encoding types.

types_map

Dictionary mapping filename extensions to MIME types.

common_types

Dictionary mapping filename extensions to non-standard, but commonly found MIME types.

The `MimeTypes` class may be useful for applications which may want more than one MIME-type database:

class MimeTypes (*[filenames]*)

This class represents a MIME-types database. By default, it provides access to the same database as the rest of this module. The initial database is a copy of that provided by the module, and may be extended by loading additional ‘mime.types’-style files into the database using the `read()` or `readfp()` methods. The mapping dictionaries may also be cleared before loading additional data if the default data is not desired.

The optional *filenames* parameter can be used to cause additional files to be loaded “on top” of the default database.

New in version 2.2.

An example usage of the module:

```
>>> import mimetypes
>>> mimetypes.init()
>>> mimetypes.knownfiles
['/etc/mime.types', '/etc/httpd/mime.types', ... ]
>>> mimetypes.suffix_map['.tgz']
'.tar.gz'
>>> mimetypes.encodings_map['.gz']
'gzip'
>>> mimetypes.types_map['.tgz']
'application/x-tar-gz'
```

7.6.1 MimeTypes Objects

`MimeTypes` instances provide an interface which is very like that of the `mimetypes` module.

suffix_map

Dictionary mapping suffixes to suffixes. This is used to allow recognition of encoded files for which the encoding and the type are indicated by the same extension. For example, the ‘.tgz’ extension is mapped to ‘.tar.gz’ to allow the encoding and type to be recognized separately. This is initially a copy of the global `suffix_map` defined in the module.

encodings_map

Dictionary mapping filename extensions to encoding types. This is initially a copy of the global `encodings_map` defined in the module.

types_map

Dictionary mapping filename extensions to MIME types. This is initially a copy of the global `types_map` defined in the module.

common_types

Dictionary mapping filename extensions to non-standard, but commonly found MIME types. This is initially a copy of the global `common_types` defined in the module.

guess_extension (*type* [, *strict*])

Similar to the `guess_extension()` function, using the tables stored as part of the object.

guess_type (*url* [, *strict*])

Similar to the `guess_type()` function, using the tables stored as part of the object.

read (*path*)

Load MIME information from a file named *path*. This uses `readfp()` to parse the file.

readfp (*file*)

Load MIME type information from an open file. The file must have the format of the standard ‘mime.types’ files.

7.7 MimeWriter — Generic MIME file writer

Deprecated since release 2.3. The `email` package should be used in preference to the `MimeWriter` module. This module is present only to maintain backward compatibility.

This module defines the class `MimeWriter`. The `MimeWriter` class implements a basic formatter for creating MIME multi-part files. It doesn’t seek around the output file nor does it use large amounts of buffer space. You must write the parts out in the order that they should occur in the final file. `MimeWriter` does buffer the headers you add, allowing you to rearrange their order.

class MimeWriter (*fp*)

Return a new instance of the `MimeWriter` class. The only argument passed, *fp*, is a file object to be used for writing. Note that a `StringIO` object could also be used.

7.7.1 MimeWriter Objects

`MimeWriter` instances have the following methods:

addheader (*key*, *value* [, *prefix*])

Add a header line to the MIME message. The *key* is the name of the header, where the *value* obviously provides the value of the header. The optional argument *prefix* determines where the header is inserted; ‘0’ means append at the end, ‘1’ is insert at the start. The default is to append.

flushheaders ()

Causes all headers accumulated so far to be written out (and forgotten). This is useful if you don’t need a body part at all, e.g. for a subpart of type `message/rfc822` that’s (mis)used to store some header-like information.

startbody (*ctype* [, *plist* [, *prefix*]])

Returns a file-like object which can be used to write to the body of the message. The content-type is set to the provided *ctype*, and the optional parameter *plist* provides additional parameters for the content-type declaration. *prefix* functions as in `addheader()` except that the default is to insert at the start.

startmultipartbody (*subtype* [, *boundary* [, *plist* [, *prefix*]]])

Returns a file-like object which can be used to write to the body of the message. Additionally, this method initializes the multi-part code, where *subtype* provides the multipart subtype, *boundary* may provide a user-defined boundary specification, and *plist* provides optional parameters for the subtype. *prefix* functions as in `startbody()`. Subparts should be created using `nextpart()`.

nextpart ()

Returns a new instance of `MimeWriter` which represents an individual part in a multipart message. This may be used to write the part as well as used for creating recursively complex multipart messages. The message must first be initialized with `startmultipartbody ()` before using `nextpart ()`.

lastpart ()

This is used to designate the last part of a multipart message, and should *always* be used when writing multipart messages.

7.8 `mimify` — MIME processing of mail messages

Deprecated since release 2.3. The `email` package should be used in preference to the `mimify` module. This module is present only to maintain backward compatibility.

The `mimify` module defines two functions to convert mail messages to and from MIME format. The mail message can be either a simple message or a so-called multipart message. Each part is treated separately. Mimifying (a part of) a message entails encoding the message as quoted-printable if it contains any characters that cannot be represented using 7-bit ASCII. Unmimifying (a part of) a message entails undoing the quoted-printable encoding. Mimify and unmimify are especially useful when a message has to be edited before being sent. Typical use would be:

```
unmimify message
edit message
mimify message
send message
```

The module defines the following user-callable functions and user-settable variables:

mimify (infile, outfile)

Copy the message in *infile* to *outfile*, converting parts to quoted-printable and adding MIME mail headers when necessary. *infile* and *outfile* can be file objects (actually, any object that has a `readline ()` method (for *infile*) or a `write ()` method (for *outfile*)) or strings naming the files. If *infile* and *outfile* are both strings, they may have the same value.

unmimify (infile, outfile[, decode_base64])

Copy the message in *infile* to *outfile*, decoding all quoted-printable parts. *infile* and *outfile* can be file objects (actually, any object that has a `readline ()` method (for *infile*) or a `write ()` method (for *outfile*)) or strings naming the files. If *infile* and *outfile* are both strings, they may have the same value. If the *decode_base64* argument is provided and tests true, any parts that are coded in the base64 encoding are decoded as well.

mime_decode_header (line)

Return a decoded version of the encoded header line in *line*. This only supports the ISO 8859-1 charset (Latin-1).

mime_encode_header (line)

Return a MIME-encoded version of the header line in *line*.

MAXLEN

By default, a part will be encoded as quoted-printable when it contains any non-ASCII characters (characters with the 8th bit set), or if there are any lines longer than MAXLEN characters (default value 200).

CHARSET

When not specified in the mail headers, a character set must be filled in. The string used is stored in `CHARSET`, and the default value is ISO-8859-1 (also known as Latin1 (latin-one)).

This module can also be used from the command line. Usage is as follows:


```
mimify.py -e [-l length] [infile [outfile]]
mimify.py -d [-b] [infile [outfile]]
```

to encode (*mimify*) and decode (*unmimify*) respectively. *infile* defaults to standard input, *outfile* defaults to standard output. The same file can be specified for input and output.

If the **-l** option is given when encoding, if there are any lines longer than the specified *length*, the containing part will be encoded.

If the **-b** option is given when decoding, any base64 parts will be decoded as well.

See Also:

[Module `quopri`](#) (section 7.14):

Encode and decode MIME quoted-printable files.

7.9 `multifile` — Support for files containing distinct parts

Deprecated since release 2.5. The [email](#) package should be used in preference to the `multifile` module. This module is present only to maintain backward compatibility.

The `MultiFile` object enables you to treat sections of a text file as file-like input objects, with `' '` being returned by `readline()` when a given delimiter pattern is encountered. The defaults of this class are designed to make it useful for parsing MIME multipart messages, but by subclassing it and overriding methods it can be easily adapted for more general use.

class `MultiFile` (*fp*, [*seekable*])

Create a multi-file. You must instantiate this class with an input object argument for the `MultiFile` instance to get lines from, such as a file object returned by `open()`.

`MultiFile` only ever looks at the input object's `readline()`, `seek()` and `tell()` methods, and the latter two are only needed if you want random access to the individual MIME parts. To use `MultiFile` on a non-seekable stream object, set the optional *seekable* argument to false; this will prevent using the input object's `seek()` and `tell()` methods.

It will be useful to know that in `MultiFile`'s view of the world, text is composed of three kinds of lines: data, section-dividers, and end-markers. `MultiFile` is designed to support parsing of messages that may have multiple nested message parts, each with its own pattern for section-divider and end-marker lines.

See Also:

[Module `email`](#) (section 7.1):

Comprehensive email handling package; supersedes the `multifile` module.

7.9.1 `MultiFile` Objects

A `MultiFile` instance has the following methods:

`readline` (*str*)

Read a line. If the line is data (not a section-divider or end-marker or real EOF) return it. If the line matches the most-recently-stacked boundary, return `' '` and set `self.last` to 1 or 0 according as the match is or is not an end-marker. If the line matches any other stacked boundary, raise an error. On encountering end-of-file on the underlying stream object, the method raises `Error` unless all boundaries have been popped.

`readlines` (*str*)

Return all lines remaining in this part as a list of strings.

read()
Read all lines, up to the next section. Return them as a single (multiline) string. Note that this doesn't take a size argument!

seek(*pos* [, *whence*])
Seek. Seek indices are relative to the start of the current section. The *pos* and *whence* arguments are interpreted as for a file seek.

tell()
Return the file position relative to the start of the current section.

next()
Skip lines to the next section (that is, read lines until a section-divider or end-marker has been consumed). Return true if there is such a section, false if an end-marker is seen. Re-enable the most-recently-pushed boundary.

is_data(*str*)
Return true if *str* is data and false if it might be a section boundary. As written, it tests for a prefix other than ' -- ' at start of line (which all MIME boundaries have) but it is declared so it can be overridden in derived classes.

Note that this test is used intended as a fast guard for the real boundary tests; if it always returns false it will merely slow processing, not cause it to fail.

push(*str*)
Push a boundary string. When a decorated version of this boundary is found as an input line, it will be interpreted as a section-divider or end-marker (depending on the decoration, see RFC 2045). All subsequent reads will return the empty string to indicate end-of-file, until a call to `pop()` removes the boundary or `next()` call reenables it.

It is possible to push more than one boundary. Encountering the most-recently-pushed boundary will return EOF; encountering any other boundary will raise an error.

pop()
Pop a section boundary. This boundary will no longer be interpreted as EOF.

section_divider(*str*)
Turn a boundary into a section-divider line. By default, this method prepends ' -- ' (which MIME section boundaries have) but it is declared so it can be overridden in derived classes. This method need not append LF or CR-LF, as comparison with the result ignores trailing whitespace.

end_marker(*str*)
Turn a boundary string into an end-marker line. By default, this method prepends ' -- ' and appends ' -- ' (like a MIME-multipart end-of-message marker) but it is declared so it can be overridden in derived classes. This method need not append LF or CR-LF, as comparison with the result ignores trailing whitespace.

Finally, `MultiFile` instances have two public instance variables:

level
Nesting depth of the current part.

last
True if the last end-of-file was for an end-of-message marker.

7.9.2 MultiFile Example

```
import mimetools
import multifile
import StringIO

def extract_mime_part_matching(stream, mimetype):
    """Return the first element in a multipart MIME message on stream
    matching mimetype."""

    msg = mimetools.Message(stream)
    msgtype = msg.gettype()
    params = msg.getplist()

    data = StringIO.StringIO()
    if msgtype[:10] == "multipart/":

        file = multifile.MultiFile(stream)
        file.push(msg.getparam("boundary"))
        while file.next():
            submsg = mimetools.Message(file)
            try:
                data = StringIO.StringIO()
                mimetools.decode(file, data, submsg.getencoding())
            except ValueError:
                continue
            if submsg.gettype() == mimetype:
                break
        file.pop()
    return data.getvalue()
```

7.10 rfc822 — Parse RFC 2822 mail headers

Deprecated since release 2.3. The [email](#) package should be used in preference to the `rfc822` module. This module is present only to maintain backward compatibility.

This module defines a class, `Message`, which represents an “email message” as defined by the Internet standard RFC 2822.⁶ Such messages consist of a collection of message headers, and a message body. This module also defines a helper class `AddressList` for parsing RFC 2822 addresses. Please refer to the RFC for information on the specific syntax of RFC 2822 messages.

The [mailbox](#) module provides classes to read mailboxes produced by various end-user mail programs.

class `Message` (*file* [, *seekable*])

A `Message` instance is instantiated with an input object as parameter. `Message` relies only on the input object having a `readline()` method; in particular, ordinary file objects qualify. Instantiation reads headers from the input object up to a delimiter line (normally a blank line) and stores them in the instance. The message body, following the headers, is not consumed.

This class can work with any input object that supports a `readline()` method. If the input object has seek and tell capability, the `rewindbody()` method will work; also, illegal lines will be pushed back onto the input stream. If the input object lacks seek but has an `unread()` method that can push back a line of input,

⁶This module originally conformed to RFC 822, hence the name. Since then, RFC 2822 has been released as an update to RFC 822. This module should be considered RFC 2822-conformant, especially in cases where the syntax or semantics have changed since RFC 822.

Message will use that to push back illegal lines. Thus this class can be used to parse messages coming from a buffered stream.

The optional *seekable* argument is provided as a workaround for certain stdio libraries in which `tell()` discards buffered data before discovering that the `lseek()` system call doesn't work. For maximum portability, you should set the *seekable* argument to zero to prevent that initial `tell()` when passing in an unseekable object such as a file object created from a socket object.

Input lines as read from the file may either be terminated by CR-LF or by a single linefeed; a terminating CR-LF is replaced by a single linefeed before the line is stored.

All header matching is done independent of upper or lower case; e.g. `m['From']`, `m['from']` and `m['FROM']` all yield the same result.

class AddressList (*field*)

You may instantiate the `AddressList` helper class using a single string parameter, a comma-separated list of RFC 2822 addresses to be parsed. (The parameter `None` yields an empty list.)

quote (*str*)

Return a new string with backslashes in *str* replaced by two backslashes and double quotes replaced by backslash-double quote.

unquote (*str*)

Return a new string which is an *unquoted* version of *str*. If *str* ends and begins with double quotes, they are stripped off. Likewise if *str* ends and begins with angle brackets, they are stripped off.

parseaddr (*address*)

Parse *address*, which should be the value of some address-containing field such as `To:` or `Cc:`, into its constituent “realname” and “email address” parts. Returns a tuple of that information, unless the parse fails, in which case a 2-tuple `(None, None)` is returned.

dump_address_pair (*pair*)

The inverse of `parseaddr()`, this takes a 2-tuple of the form `(realname, email_address)` and returns the string value suitable for a `To:` or `Cc:` header. If the first element of *pair* is false, then the second element is returned unmodified.

parsedate (*date*)

Attempts to parse a date according to the rules in RFC 2822. however, some mailers don't follow that format as specified, so `parsedate()` tries to guess correctly in such cases. *date* is a string containing an RFC 2822 date, such as `'Mon, 20 Nov 1995 19:12:08 -0500'`. If it succeeds in parsing the date, `parsedate()` returns a 9-tuple that can be passed directly to `time.mktime()`; otherwise `None` will be returned. Note that fields 6, 7, and 8 of the result tuple are not usable.

parsedate_tz (*date*)

Performs the same function as `parsedate()`, but returns either `None` or a 10-tuple; the first 9 elements make up a tuple that can be passed directly to `time.mktime()`, and the tenth is the offset of the date's timezone from UTC (which is the official term for Greenwich Mean Time). (Note that the sign of the timezone offset is the opposite of the sign of the `time.timezone` variable for the same timezone; the latter variable follows the POSIX standard while this module follows RFC 2822.) If the input string has no timezone, the last element of the tuple returned is `None`. Note that fields 6, 7, and 8 of the result tuple are not usable.

mktime_tz (*tuple*)

Turn a 10-tuple as returned by `parsedate_tz()` into a UTC timestamp. If the timezone item in the tuple is `None`, assume local time. Minor deficiency: this first interprets the first 8 elements as a local time and then compensates for the timezone difference; this may yield a slight error around daylight savings time switch dates. Not enough to worry about for common use.

See Also:

[Module email](#) (section 7.1):

Comprehensive email handling package; supersedes the `rfc822` module.

Module `mailbox` (section 7.3):

Classes to read various mailbox formats produced by end-user mail programs.

Module `mimetools` (section 7.5):

Subclass of `rfc822.Message` that handles MIME encoded messages.

7.10.1 Message Objects

A `Message` instance has the following methods:

`rewindbody()`

Seek to the start of the message body. This only works if the file object is seekable.

`isheader(line)`

Returns a line's canonicalized fieldname (the dictionary key that will be used to index it) if the line is a legal RFC 2822 header; otherwise returns `None` (implying that parsing should stop here and the line be pushed back on the input stream). It is sometimes useful to override this method in a subclass.

`islast(line)`

Return `True` if the given line is a delimiter on which `Message` should stop. The delimiter line is consumed, and the file object's read location positioned immediately after it. By default this method just checks that the line is blank, but you can override it in a subclass.

`iscomment(line)`

Return `True` if the given line should be ignored entirely, just skipped. By default this is a stub that always returns `False`, but you can override it in a subclass.

`getallmatchingheaders(name)`

Return a list of lines consisting of all headers matching *name*, if any. Each physical line, whether it is a continuation line or not, is a separate list item. Return the empty list if no header matches *name*.

`getfirstmatchingheader(name)`

Return a list of lines comprising the first header matching *name*, and its continuation line(s), if any. Return `None` if there is no header matching *name*.

`getrawheader(name)`

Return a single string consisting of the text after the colon in the first header matching *name*. This includes leading whitespace, the trailing linefeed, and internal linefeeds and whitespace if there any continuation line(s) were present. Return `None` if there is no header matching *name*.

`getheader(name[, default])`

Like `getrawheader(name)`, but strip leading and trailing whitespace. Internal whitespace is not stripped. The optional *default* argument can be used to specify a different default to be returned when there is no header matching *name*.

`get(name[, default])`

An alias for `getheader()`, to make the interface more compatible with regular dictionaries.

`getaddr(name)`

Return a pair (*full name*, *email address*) parsed from the string returned by `getheader(name)`. If no header matching *name* exists, return (`None`, `None`); otherwise both the full name and the address are (possibly empty) strings.

Example: If *m*'s first `From:` header contains the string `'jack@cwil.nl (Jack Jansen)'`, then `m.getaddr('From')` will yield the pair `('Jack Jansen', 'jack@cwil.nl')`. If the header contained `'Jack Jansen <jack@cwil.nl>'` instead, it would yield the exact same result.

`getaddrlist(name)`

This is similar to `getaddr(list)`, but parses a header containing a list of email addresses (e.g. a `To:` header) and returns a list of (*full name*, *email address*) pairs (even if there was only one address in the header). If

there is no header matching *name*, return an empty list.

If multiple headers exist that match the named header (e.g. if there are several Cc: headers), all are parsed for addresses. Any continuation lines the named headers contain are also parsed.

getdate (*name*)

Retrieve a header using `getheader()` and parse it into a 9-tuple compatible with `time.mktime()`; note that fields 6, 7, and 8 are not usable. If there is no header matching *name*, or it is unparsable, return `None`.

Date parsing appears to be a black art, and not all mailers adhere to the standard. While it has been tested and found correct on a large collection of email from many sources, it is still possible that this function may occasionally yield an incorrect result.

getdate_tz (*name*)

Retrieve a header using `getheader()` and parse it into a 10-tuple; the first 9 elements will make a tuple compatible with `time.mktime()`, and the 10th is a number giving the offset of the date's timezone from UTC. Note that fields 6, 7, and 8 are not usable. Similarly to `getdate()`, if there is no header matching *name*, or it is unparsable, return `None`.

Message instances also support a limited mapping interface. In particular: `m[name]` is like `m.getheader(name)` but raises `KeyError` if there is no matching header; and `len(m)`, `m.get(name[, default])`, `m.has_key(name)`, `m.keys()`, `m.values()`, `m.items()`, and `m.setdefault(name[, default])` act as expected, with the one difference that `setdefault()` uses an empty string as the default value. Message instances also support the mapping writable interface `m[name] = value` and `del m[name]`. Message objects do not support the `clear()`, `copy()`, `popitem()`, or `update()` methods of the mapping interface. (Support for `get()` and `setdefault()` was only added in Python 2.2.)

Finally, Message instances have some public instance variables:

headers

A list containing the entire set of header lines, in the order in which they were read (except that `setitem` calls may disturb this order). Each line contains a trailing newline. The blank line terminating the headers is not contained in the list.

fp

The file or file-like object passed at instantiation time. This can be used to read the message content.

unixfrom

The UNIX 'From' line, if the message had one, or an empty string. This is needed to regenerate the message in some contexts, such as an mbox-style mailbox file.

7.10.2 AddressList Objects

An `AddressList` instance has the following methods:

__len__ ()

Return the number of addresses in the address list.

__str__ ()

Return a canonicalized string representation of the address list. Addresses are rendered in "name" ;host@domain form, comma-separated.

__add__ (alist)

Return a new `AddressList` instance that contains all addresses in both `AddressList` operands, with duplicates removed (set union).

__iadd__ (alist)

In-place version of `__add__()`; turns this `AddressList` instance into the union of itself and the right-hand instance, *alist*.

__sub__ (alist)

Return a new `AddressList` instance that contains every address in the left-hand `AddressList` operand that is not present in the right-hand address operand (set difference).

`__isub__` (*alist*)

In-place version of `__sub__()`, removing addresses in this list which are also in *alist*.

Finally, `AddressList` instances have one public instance variable:

`addresslist`

A list of tuple string pairs, one per address. In each member, the first is the canonicalized name part, the second is the actual route-address ('@'-separated username-host.domain pair).

7.11 `base64` — RFC 3548: Base16, Base32, Base64 Data Encodings

This module provides data encoding and decoding as specified in RFC 3548. This standard defines the Base16, Base32, and Base64 algorithms for encoding and decoding arbitrary binary strings into text strings that can be safely sent by email, used as parts of URLs, or included as part of an HTTP POST request. The encoding algorithm is not the same as the `uuencode` program.

There are two interfaces provided by this module. The modern interface supports encoding and decoding string objects using all three alphabets. The legacy interface provides for encoding and decoding to and from file-like objects as well as strings, but only using the Base64 standard alphabet.

The modern interface, which was introduced in Python 2.4, provides:

`b64encode` (*s* [, *altchars*])

Encode a string *s* using Base64.

s is the string to encode. Optional *altchars* must be a string of at least length 2 (additional characters are ignored) which specifies an alternative alphabet for the + and / characters. This allows an application to e.g. generate URL or filesystem safe Base64 strings. The default is `None`, for which the standard Base64 alphabet is used.

The encoded string is returned.

`b64decode` (*s* [, *altchars*])

Decode a Base64 encoded string.

s is the string to decode. Optional *altchars* must be a string of at least length 2 (additional characters are ignored) which specifies the alternative alphabet used instead of the + and / characters.

The decoded string is returned. A `TypeError` is raised if *s* were incorrectly padded or if there are non-alphabet characters present in the string.

`standard_b64encode` (*s*)

Encode string *s* using the standard Base64 alphabet.

`standard_b64decode` (*s*)

Decode string *s* using the standard Base64 alphabet.

`urlsafe_b64encode` (*s*)

Encode string *s* using a URL-safe alphabet, which substitutes - instead of + and _ instead of / in the standard Base64 alphabet.

`urlsafe_b64decode` (*s*)

Decode string *s* using a URL-safe alphabet, which substitutes - instead of + and _ instead of / in the standard Base64 alphabet.

`b32encode` (*s*)

Encode a string using Base32. *s* is the string to encode. The encoded string is returned.

`b32decode` (*s* [, *casefold* [, *map01*]])

Decode a Base32 encoded string.

s is the string to decode. Optional *casefold* is a flag specifying whether a lowercase alphabet is acceptable as input. For security purposes, the default is `False`.

RFC 3548 allows for optional mapping of the digit 0 (zero) to the letter O (oh), and for optional mapping of the digit 1 (one) to either the letter I (eye) or letter L (el). The optional argument *map01* when not `None`, specifies which letter the digit 1 should be mapped to (when *map01* is not `None`, the digit 0 is always mapped to the letter O). For security purposes the default is `None`, so that 0 and 1 are not allowed in the input.

The decoded string is returned. A `TypeError` is raised if *s* were incorrectly padded or if there are non-alphabet characters present in the string.

base64.encode(*s*)

Encode a string using Base16.

s is the string to encode. The encoded string is returned.

base64.decode(*s*[, *casefold*])

Decode a Base16 encoded string.

s is the string to decode. Optional *casefold* is a flag specifying whether a lowercase alphabet is acceptable as input. For security purposes, the default is `False`.

The decoded string is returned. A `TypeError` is raised if *s* were incorrectly padded or if there are non-alphabet characters present in the string.

The legacy interface:

decode(*input*, *output*)

Decode the contents of the *input* file and write the resulting binary data to the *output* file. *input* and *output* must either be file objects or objects that mimic the file object interface. *input* will be read until *input*.`read()` returns an empty string.

decodestring(*s*)

Decode the string *s*, which must contain one or more lines of base64 encoded data, and return a string containing the resulting binary data.

encode(*input*, *output*)

Encode the contents of the *input* file and write the resulting base64 encoded data to the *output* file. *input* and *output* must either be file objects or objects that mimic the file object interface. *input* will be read until *input*.`read()` returns an empty string. `encode()` returns the encoded data plus a trailing newline character (`'\n'`).

encodestring(*s*)

Encode the string *s*, which can contain arbitrary binary data, and return a string containing one or more lines of base64-encoded data. `encodestring()` returns a string containing one or more lines of base64-encoded data always including an extra trailing newline (`'\n'`).

An example usage of the module:

```
>>> import base64
>>> encoded = base64.b64encode('data to be encoded')
>>> encoded
'ZGF0YSB0byBiZSB1bmNvZGVk'
>>> data = base64.b64decode(encoded)
>>> data
'data to be encoded'
```

See Also:

[Module binascii](#) (section 7.13):

Support module containing ASCII-to-binary and binary-to-ASCII conversions.

RFC 1521, “*MIME (Multipurpose Internet Mail Extensions) Part One: Mechanisms for Specifying and Describing the Format of Internet Messages*”, Section 5.2, “Base64 Content-Transfer-Encoding,” provides the definition of the base64 encoding.

7.12 binhex — Encode and decode binhex4 files

This module encodes and decodes files in binhex4 format, a format allowing representation of Macintosh files in ASCII. On the Macintosh, both forks of a file and the finder information are encoded (or decoded), on other platforms only the data fork is handled.

The `binhex` module defines the following functions:

binhex (*input*, *output*)

Convert a binary file with filename *input* to binhex file *output*. The *output* parameter can either be a filename or a file-like object (any object supporting a `write()` and `close()` method).

hexbin (*input* [, *output*])

Decode a binhex file *input*. *input* may be a filename or a file-like object supporting `read()` and `close()` methods. The resulting file is written to a file named *output*, unless the argument is omitted in which case the output filename is read from the binhex file.

The following exception is also defined:

exception Error

Exception raised when something can’t be encoded using the binhex format (for example, a filename is too long to fit in the filename field), or when input is not properly encoded binhex data.

See Also:

[Module binascii](#) (section 7.13):

Support module containing ASCII-to-binary and binary-to-ASCII conversions.

7.12.1 Notes

There is an alternative, more powerful interface to the coder and decoder, see the source for details.

If you code or decode textfiles on non-Macintosh platforms they will still use the Macintosh newline convention (carriage-return as end of line).

As of this writing, `hexbin()` appears to not work in all cases.

7.13 binascii — Convert between binary and ASCII

The `binascii` module contains a number of methods to convert between binary and various ASCII-encoded binary representations. Normally, you will not use these functions directly but use wrapper modules like `uu`, `base64`, or `binhex` instead. The `binascii` module contains low-level functions written in C for greater speed that are used by the higher-level modules.

The `binascii` module defines the following functions:

a2b_uu (*string*)

Convert a single line of uuencoded data back to binary and return the binary data. Lines normally contain 45 (binary) bytes, except for the last line. Line data may be followed by whitespace.

b2a_uu (*data*)

Convert binary data to a line of ASCII characters, the return value is the converted line, including a newline char. The length of *data* should be at most 45.

a2b_base64 (*string*)

Convert a block of base64 data back to binary and return the binary data. More than one line may be passed at a time.

b2a_base64 (*data*)

Convert binary data to a line of ASCII characters in base64 coding. The return value is the converted line, including a newline char. The length of *data* should be at most 57 to adhere to the base64 standard.

a2b_qp (*string* [, *header*])

Convert a block of quoted-printable data back to binary and return the binary data. More than one line may be passed at a time. If the optional argument *header* is present and true, underscores will be decoded as spaces.

b2a_qp (*data* [, *quotetabs*, *istext*, *header*])

Convert binary data to a line(s) of ASCII characters in quoted-printable encoding. The return value is the converted line(s). If the optional argument *quotetabs* is present and true, all tabs and spaces will be encoded. If the optional argument *istext* is present and true, newlines are not encoded but trailing whitespace will be encoded. If the optional argument *header* is present and true, spaces will be encoded as underscores per RFC1522. If the optional argument *header* is present and false, newline characters will be encoded as well; otherwise linefeed conversion might corrupt the binary data stream.

a2b_hqx (*string*)

Convert binhex4 formatted ASCII data to binary, without doing RLE-decompression. The string should contain a complete number of binary bytes, or (in case of the last portion of the binhex4 data) have the remaining bits zero.

rledecode_hqx (*data*)

Perform RLE-decompression on the data, as per the binhex4 standard. The algorithm uses 0x90 after a byte as a repeat indicator, followed by a count. A count of 0 specifies a byte value of 0x90. The routine returns the decompressed data, unless data input data ends in an orphaned repeat indicator, in which case the `Incomplete` exception is raised.

rlecode_hqx (*data*)

Perform binhex4 style RLE-compression on *data* and return the result.

b2a_hqx (*data*)

Perform hexbin4 binary-to-ASCII translation and return the resulting string. The argument should already be RLE-coded, and have a length divisible by 3 (except possibly the last fragment).

crc_hqx (*data*, *crc*)

Compute the binhex4 crc value of *data*, starting with an initial *crc* and returning the result.

crc32 (*data* [, *crc*])

Compute CRC-32, the 32-bit checksum of data, starting with an initial *crc*. This is consistent with the ZIP file checksum. Since the algorithm is designed for use as a checksum algorithm, it is not suitable for use as a general hash algorithm. Use as follows:

```
print binascii.crc32("hello world")
# Or, in two pieces:
crc = binascii.crc32("hello")
crc = binascii.crc32(" world", crc)
print crc
```

b2a_hex (*data*)**hexlify** (*data*)

Return the hexadecimal representation of the binary *data*. Every byte of *data* is converted into the corresponding 2-digit hex representation. The resulting string is therefore twice as long as the length of *data*.

a2b_hex (*hexstr*)**unhexlify** (*hexstr*)

Return the binary data represented by the hexadecimal string *hexstr*. This function is the inverse of `b2a_hex()`. *hexstr* must contain an even number of hexadecimal digits (which can be upper or lower case), otherwise a `TypeError` is raised.

exception Error

Exception raised on errors. These are usually programming errors.

exception Incomplete

Exception raised on incomplete data. These are usually not programming errors, but may be handled by reading a little more data and trying again.

See Also:

[Module `base64`](#) (section 7.11):

Support for base64 encoding used in MIME email messages.

[Module `binhex`](#) (section 7.12):

Support for the binhex format used on the Macintosh.

[Module `uu`](#) (section 7.15):

Support for UU encoding used on UNIX.

[Module `quopri`](#) (section 7.14):

Support for quoted-printable encoding used in MIME email messages.

7.14 `quopri` — Encode and decode MIME quoted-printable data

This module performs quoted-printable transport encoding and decoding, as defined in RFC 1521: “MIME (Multipurpose Internet Mail Extensions) Part One: Mechanisms for Specifying and Describing the Format of Internet Message Bodies”. The quoted-printable encoding is designed for data where there are relatively few nonprintable characters; the base64 encoding scheme available via the [base64](#) module is more compact if there are many such characters, as when sending a graphics file.

`decode` (*input*, *output*[, *header*])

Decode the contents of the *input* file and write the resulting decoded binary data to the *output* file. *input* and *output* must either be file objects or objects that mimic the file object interface. *input* will be read until *input.readline()* returns an empty string. If the optional argument *header* is present and true, underscore will be decoded as space. This is used to decode “Q”-encoded headers as described in RFC 1522: “MIME (Multipurpose Internet Mail Extensions) Part Two: Message Header Extensions for Non-ASCII Text”.

`encode` (*input*, *output*, *quotetabs*)

Encode the contents of the *input* file and write the resulting quoted-printable data to the *output* file. *input* and *output* must either be file objects or objects that mimic the file object interface. *input* will be read until *input.readline()* returns an empty string. *quotetabs* is a flag which controls whether to encode embedded spaces and tabs; when true it encodes such embedded whitespace, and when false it leaves them unencoded. Note that spaces and tabs appearing at the end of lines are always encoded, as per RFC 1521.

`decodestring` (*s*[, *header*])

Like `decode()`, except that it accepts a source string and returns the corresponding decoded string.

`encodestring` (*s*[, *quotetabs*])

Like `encode()`, except that it accepts a source string and returns the corresponding encoded string. *quotetabs* is optional (defaulting to 0), and is passed straight through to `encode()`.

See Also:

[Module `mimify`](#) (section 7.8):

General utilities for processing of MIME messages.

[Module `base64`](#) (section 7.11):

7.15 uu — Encode and decode uuencode files

This module encodes and decodes files in uuencode format, allowing arbitrary binary data to be transferred over ASCII-only connections. Wherever a file argument is expected, the methods accept a file-like object. For backwards compatibility, a string containing a pathname is also accepted, and the corresponding file will be opened for reading and writing; the pathname `'-'` is understood to mean the standard input or output. However, this interface is deprecated; it's better for the caller to open the file itself, and be sure that, when required, the mode is `'rb'` or `'wb'` on Windows.

This code was contributed by Lance Ellinghouse, and modified by Jack Jansen.

The `uu` module defines the following functions:

encode (*in_file*, *out_file* [, *name* [, *mode*]])

Uuencode file *in_file* into file *out_file*. The uuencoded file will have the header specifying *name* and *mode* as the defaults for the results of decoding the file. The default defaults are taken from *in_file*, or `'-'` and `0666` respectively.

decode (*in_file* [, *out_file* [, *mode* [, *quiet*]]])

This call decodes uuencoded file *in_file* placing the result on file *out_file*. If *out_file* is a pathname, *mode* is used to set the permission bits if the file must be created. Defaults for *out_file* and *mode* are taken from the uuencode header. However, if the file specified in the header already exists, a `uu.Error` is raised.

`decode()` may print a warning to standard error if the input was produced by an incorrect uuencoder and Python could recover from that error. Setting *quiet* to a true value silences this warning.

exception Error ()

Subclass of `Exception`, this can be raised by `uu.decode()` under various situations, such as described above, but also including a badly formatted header, or truncated input file.

See Also:

[Module `binascii`](#) (section 7.13):

Support module containing ASCII-to-binary and binary-to-ASCII conversions.

Structured Markup Processing Tools

Python supports a variety of modules to work with various forms of structured data markup. This includes modules to work with the Standard Generalized Markup Language (SGML) and the Hypertext Markup Language (HTML), and several interfaces for working with the Extensible Markup Language (XML).

It is important to note that modules in the `xml` package require that there be at least one SAX-compliant XML parser available. Starting with Python 2.3, the Expat parser is included with Python, so the `xml.parsers.expat` module will always be available. You may still want to be aware of the [PyXML add-on package](#); that package provides an extended set of XML libraries for Python.

The documentation for the `xml.dom` and `xml.sax` packages are the definition of the Python bindings for the DOM and SAX interfaces.

<code>HTMLParser</code>	A simple parser that can handle HTML and XHTML.
<code>sgmllib</code>	Only as much of an SGML parser as needed to parse HTML.
<code>htmllib</code>	A parser for HTML documents.
<code>htmlentitydefs</code>	Definitions of HTML general entities.
<code>xml.parsers.expat</code>	An interface to the Expat non-validating XML parser.
<code>xml.dom</code>	Document Object Model API for Python.
<code>xml.dom.minidom</code>	Lightweight Document Object Model (DOM) implementation.
<code>xml.dom.pulldom</code>	Support for building partial DOM trees from SAX events.
<code>xml.sax</code>	Package containing SAX2 base classes and convenience functions.
<code>xml.sax.handler</code>	Base classes for SAX event handlers.
<code>xml.sax.saxutils</code>	Convenience functions and classes for use with SAX.
<code>xml.sax.xmlreader</code>	Interface which SAX-compliant XML parsers must implement.
<code>xml.etree.ElementTree</code>	Implementation of the ElementTree API.

See Also:

Python/XML Libraries

(<http://pyxml.sourceforge.net/>)

Home page for the PyXML package, containing an extension of `xml` package bundled with Python.

8.1 HTMLParser — Simple HTML and XHTML parser

New in version 2.2.

This module defines a class `HTMLParser` which serves as the basis for parsing text files formatted in HTML (Hypertext Mark-up Language) and XHTML. Unlike the parser in `htmllib`, this parser is not based on the SGML parser in `sgmlib`.

class HTMLParser()

The `HTMLParser` class is instantiated without arguments.

An `HTMLParser` instance is fed HTML data and calls handler functions when tags begin and end. The `HTMLParser` class is meant to be overridden by the user to provide a desired behavior.

Unlike the parser in [htmllib](#), this parser does not check that end tags match start tags or call the end-tag handler for elements which are closed implicitly by closing an outer element.

An exception is defined as well:

exception `HTMLParseError`

Exception raised by the `HTMLParser` class when it encounters an error while parsing. This exception provides three attributes: `msg` is a brief message explaining the error, `lineno` is the number of the line on which the broken construct was detected, and `offset` is the number of characters into the line at which the construct starts.

`HTMLParser` instances have the following methods:

`reset()`

Reset the instance. Loses all unprocessed data. This is called implicitly at instantiation time.

`feed(data)`

Feed some text to the parser. It is processed insofar as it consists of complete elements; incomplete data is buffered until more data is fed or `close()` is called.

`close()`

Force processing of all buffered data as if it were followed by an end-of-file mark. This method may be redefined by a derived class to define additional processing at the end of the input, but the redefined version should always call the `HTMLParser` base class method `close()`.

`getpos()`

Return current line number and offset.

`get_starttag_text()`

Return the text of the most recently opened start tag. This should not normally be needed for structured processing, but may be useful in dealing with HTML “as deployed” or for re-generating input with minimal changes (whitespace between attributes can be preserved, etc.).

`handle_starttag(tag, attrs)`

This method is called to handle the start of a tag. It is intended to be overridden by a derived class; the base class implementation does nothing.

The `tag` argument is the name of the tag converted to lower case. The `attrs` argument is a list of (`name`, `value`) pairs containing the attributes found inside the tag’s `<>` brackets. The `name` will be translated to lower case and double quotes and backslashes in the `value` have been interpreted. For instance, for the tag ``, this method would be called as `handle_starttag('a', [('href', 'http://www.cwi.nl/')])`.

`handle_startendtag(tag, attrs)`

Similar to `handle_starttag()`, but called when the parser encounters an XHTML-style empty tag (`<a.../>`). This method may be overridden by subclasses which require this particular lexical information; the default implementation simply calls `handle_starttag()` and `handle_endtag()`.

`handle_endtag(tag)`

This method is called to handle the end tag of an element. It is intended to be overridden by a derived class; the base class implementation does nothing. The `tag` argument is the name of the tag converted to lower case.

`handle_data(data)`

This method is called to process arbitrary data. It is intended to be overridden by a derived class; the base class implementation does nothing.

`handle_charref(name)`

This method is called to process a character reference of the form `&#ref;`. It is intended to be overridden by a derived class; the base class implementation does nothing.

handle_entityref (*name*)

This method is called to process a general entity reference of the form ‘&*name*;’ where *name* is an general entity reference. It is intended to be overridden by a derived class; the base class implementation does nothing.

handle_comment (*data*)

This method is called when a comment is encountered. The *comment* argument is a string containing the text between the ‘--’ and ‘--’ delimiters, but not the delimiters themselves. For example, the comment ‘<!--text-->’ will cause this method to be called with the argument ‘text’. It is intended to be overridden by a derived class; the base class implementation does nothing.

handle_decl (*decl*)

Method called when an SGML declaration is read by the parser. The *decl* parameter will be the entire contents of the declaration inside the <!--> markup. It is intended to be overridden by a derived class; the base class implementation does nothing.

handle_pi (*data*)

Method called when a processing instruction is encountered. The *data* parameter will contain the entire processing instruction. For example, for the processing instruction <?proc color='red'>, this method would be called as `handle_pi("proc color='red' ")`. It is intended to be overridden by a derived class; the base class implementation does nothing.

Note: The `HTMLParser` class uses the SGML syntactic rules for processing instructions. An XHTML processing instruction using the trailing ‘?’ will cause the ‘?’ to be included in *data*.

8.1.1 Example HTML Parser Application

As a basic example, below is a very basic HTML parser that uses the `HTMLParser` class to print out tags as they are encountered:

```
from HTMLParser import HTMLParser

class MyHTMLParser(HTMLParser):

    def handle_starttag(self, tag, attrs):
        print "Encountered the beginning of a %s tag" % tag

    def handle_endtag(self, tag):
        print "Encountered the end of a %s tag" % tag
```

8.2 sgmllib — Simple SGML parser

This module defines a class `SGMLParser` which serves as the basis for parsing text files formatted in SGML (Standard Generalized Mark-up Language). In fact, it does not provide a full SGML parser — it only parses SGML insofar as it is used by HTML, and the module only exists as a base for the `htmllib` module. Another HTML parser which supports XHTML and offers a somewhat different interface is available in the `HTMLParser` module.

class SGMLParser ()

The `SGMLParser` class is instantiated without arguments. The parser is hardcoded to recognize the following constructs:

- Opening and closing tags of the form ‘<tag attr="value" ...>’ and ‘</tag>’, respectively.
- Numeric character references of the form ‘&#*name*;’.

- Entity references of the form ‘&name;’.
- SGML comments of the form ‘<!--text-->’. Note that spaces, tabs, and newlines are allowed between the trailing ‘>’ and the immediately preceding ‘--’.

A single exception is defined as well:

exception SGMLParseError

Exception raised by the `SGMLParser` class when it encounters an error while parsing. New in version 2.1.

`SGMLParser` instances have the following methods:

reset ()

Reset the instance. Loses all unprocessed data. This is called implicitly at instantiation time.

setnomoretags ()

Stop processing tags. Treat all following input as literal input (CDATA). (This is only provided so the HTML tag `<PLAINTEXT>` can be implemented.)

setliteral ()

Enter literal mode (CDATA mode).

feed (data)

Feed some text to the parser. It is processed insofar as it consists of complete elements; incomplete data is buffered until more data is fed or `close ()` is called.

close ()

Force processing of all buffered data as if it were followed by an end-of-file mark. This method may be redefined by a derived class to define additional processing at the end of the input, but the redefined version should always call `close ()`.

get_starttag_text ()

Return the text of the most recently opened start tag. This should not normally be needed for structured processing, but may be useful in dealing with HTML “as deployed” or for re-generating input with minimal changes (whitespace between attributes can be preserved, etc.).

handle_starttag (tag, method, attributes)

This method is called to handle start tags for which either a `start_tag ()` or `do_tag ()` method has been defined. The *tag* argument is the name of the tag converted to lower case, and the *method* argument is the bound method which should be used to support semantic interpretation of the start tag. The *attributes* argument is a list of (*name*, *value*) pairs containing the attributes found inside the tag’s `<>` brackets.

The *name* has been translated to lower case. Double quotes and backslashes in the *value* have been interpreted, as well as known character references and known entity references terminated by a semicolon (normally, entity references can be terminated by any non-alphanumerical character, but this would break the very common case of `` when *eggs* is a valid entity name).

For instance, for the tag ``, this method would be called as `‘unknown_starttag(‘a’, [(‘href’, ‘http://www.cwi.nl/’)])’`. The base implementation simply calls *method* with *attributes* as the only argument. New in version 2.5: Handling of entity and character references within attribute values.

handle_endtag (tag, method)

This method is called to handle endtags for which an `end_tag ()` method has been defined. The *tag* argument is the name of the tag converted to lower case, and the *method* argument is the bound method which should be used to support semantic interpretation of the end tag. If no `end_tag ()` method is defined for the closing element, this handler is not called. The base implementation simply calls *method*.

handle_data (data)

This method is called to process arbitrary data. It is intended to be overridden by a derived class; the base class implementation does nothing.

handle_charref (*ref*)

This method is called to process a character reference of the form ‘&#ref;’. The base implementation uses `convert_charref()` to convert the reference to a string. If that method returns a string, it is passed to `handle_data()`, otherwise `unknown_charref(ref)` is called to handle the error. Changed in version 2.5: Use `convert_charref()` instead of hard-coding the conversion.

convert_charref (*ref*)

Convert a character reference to a string, or `None`. *ref* is the reference passed in as a string. In the base implementation, *ref* must be a decimal number in the range 0-255. It converts the code point found using the `convert_codepoint()` method. If *ref* is invalid or out of range, this method returns `None`. This method is called by the default `handle_charref()` implementation and by the attribute value parser. New in version 2.5.

convert_codepoint (*codepoint*)

Convert a codepoint to a `str` value. Encodings can be handled here if appropriate, though the rest of `sgmllib` is oblivious on this matter. New in version 2.5.

handle_entityref (*ref*)

This method is called to process a general entity reference of the form ‘&ref;’ where *ref* is a general entity reference. It converts *ref* by passing it to `convert_entityref()`. If a translation is returned, it calls the method `handle_data()` with the translation; otherwise, it calls the method `unknown_entityref(ref)`. The default `entitydefs` defines translations for `&`, `'`, `>`, `<`, and `"`. Changed in version 2.5: Use `convert_entityref()` instead of hard-coding the conversion.

convert_entityref (*ref*)

Convert a named entity reference to a `str` value, or `None`. The resulting value will not be parsed. *ref* will be only the name of the entity. The default implementation looks for *ref* in the instance (or class) variable `entitydefs` which should be a mapping from entity names to corresponding translations. If no translation is available for *ref*, this method returns `None`. This method is called by the default `handle_entityref()` implementation and by the attribute value parser. New in version 2.5.

handle_comment (*comment*)

This method is called when a comment is encountered. The *comment* argument is a string containing the text between the ‘<!--’ and ‘-->’ delimiters, but not the delimiters themselves. For example, the comment ‘<!--text-->’ will cause this method to be called with the argument ‘text’. The default method does nothing.

handle_decl (*data*)

Method called when an SGML declaration is read by the parser. In practice, the DOCTYPE declaration is the only thing observed in HTML, but the parser does not discriminate among different (or broken) declarations. Internal subsets in a DOCTYPE declaration are not supported. The *data* parameter will be the entire contents of the declaration inside the ‘<!...>’ markup. The default implementation does nothing.

report_unbalanced (*tag*)

This method is called when an end tag is found which does not correspond to any open element.

unknown_starttag (*tag*, *attributes*)

This method is called to process an unknown start tag. It is intended to be overridden by a derived class; the base class implementation does nothing.

unknown_endtag (*tag*)

This method is called to process an unknown end tag. It is intended to be overridden by a derived class; the base class implementation does nothing.

unknown_charref (*ref*)

This method is called to process unresolvable numeric character references. Refer to `handle_charref()` to determine what is handled by default. It is intended to be overridden by a derived class; the base class implementation does nothing.

unknown_entityref (*ref*)

This method is called to process an unknown entity reference. It is intended to be overridden by a derived class; the base class implementation does nothing.

Apart from overriding or extending the methods listed above, derived classes may also define methods of the following form to define processing of specific tags. Tag names in the input stream are case independent; the *tag* occurring in method names must be in lower case:

start_tag (*attributes*)

This method is called to process an opening tag *tag*. It has preference over `do_tag()`. The *attributes* argument has the same meaning as described for `handle_starttag()` above.

do_tag (*attributes*)

This method is called to process an opening tag *tag* for which no `start_tag` method is defined. The *attributes* argument has the same meaning as described for `handle_starttag()` above.

end_tag ()

This method is called to process a closing tag *tag*.

Note that the parser maintains a stack of open elements for which no end tag has been found yet. Only tags processed by `start_tag()` are pushed on this stack. Definition of an `end_tag()` method is optional for these tags. For tags processed by `do_tag()` or by `unknown_tag()`, no `end_tag()` method must be defined; if defined, it will not be used. If both `start_tag()` and `do_tag()` methods exist for a tag, the `start_tag()` method takes precedence.

8.3 `htmllib` — A parser for HTML documents

This module defines a class which can serve as a base for parsing text files formatted in the HyperText Mark-up Language (HTML). The class is not directly concerned with I/O — it must be provided with input in string form via a method, and makes calls to methods of a “formatter” object in order to produce output. The `HTMLParser` class is designed to be used as a base class for other classes in order to add functionality, and allows most of its methods to be extended or overridden. In turn, this class is derived from and extends the `SGMLParser` class defined in module `sgmlib`. The `HTMLParser` implementation supports the HTML 2.0 language as described in RFC 1866. Two implementations of formatter objects are provided in the `formatter` module; refer to the documentation for that module for information on the formatter interface.

The following is a summary of the interface defined by `sgmlib.SGMLParser`:

- The interface to feed data to an instance is through the `feed()` method, which takes a string argument. This can be called with as little or as much text at a time as desired; ‘`p.feed(a); p.feed(b)`’ has the same effect as ‘`p.feed(a+b)`’. When the data contains complete HTML markup constructs, these are processed immediately; incomplete constructs are saved in a buffer. To force processing of all unprocessed data, call the `close()` method.

For example, to parse the entire contents of a file, use:

```
parser.feed(open('myfile.html').read())
parser.close()
```

- The interface to define semantics for HTML tags is very simple: derive a class and define methods called `start_tag()`, `end_tag()`, or `do_tag()`. The parser will call these at appropriate moments: `start_tag` or `do_tag` is called when an opening tag of the form `<tag . . .>` is encountered; `end_tag` is called when a closing tag of the form `</tag>` is encountered. If an opening tag requires a corresponding closing tag, like `<H1> ... </H1>`, the class should define the `start_tag()` method; if a tag requires no closing tag, like `<P>`, the class should define the `do_tag()` method.

The module defines a parser class and an exception:

class `HTMLParser` (*formatter*)

This is the basic HTML parser class. It supports all entity names required by the XHTML 1.0 Recommendation (<http://www.w3.org/TR/xhtml1>). It also defines handlers for all HTML 2.0 and many HTML 3.0 and 3.2 elements.

exception `HTMLParseError`

Exception raised by the `HTMLParser` class when it encounters an error while parsing. New in version 2.4.

See Also:

[Module `formatter`](#) (section 33.1):

Interface definition for transforming an abstract flow of formatting events into specific output events on writer objects.

[Module `HTMLParser`](#) (section 8.1):

Alternate HTML parser that offers a slightly lower-level view of the input, but is designed to work with XHTML, and does not implement some of the SGML syntax not used in “HTML as deployed” and which isn’t legal for XHTML.

[Module `htmlentitydefs`](#) (section 8.4):

Definition of replacement text for XHTML 1.0 entities.

[Module `sgmllib`](#) (section 8.2):

Base class for `HTMLParser`.

8.3.1 HTMLParser Objects

In addition to tag methods, the `HTMLParser` class provides some additional methods and instance variables for use within tag methods.

`formatter`

This is the formatter instance associated with the parser.

`nofill`

Boolean flag which should be true when whitespace should not be collapsed, or false when it should be. In general, this should only be true when character data is to be treated as “preformatted” text, as within a `<PRE>` element. The default value is false. This affects the operation of `handle_data()` and `save_end()`.

`anchor_bgn` (*href*, *name*, *type*)

This method is called at the start of an anchor region. The arguments correspond to the attributes of the `<A>` tag with the same names. The default implementation maintains a list of hyperlinks (defined by the `HREF` attribute for `<A>` tags) within the document. The list of hyperlinks is available as the data attribute `anchorlist`.

`anchor_end` ()

This method is called at the end of an anchor region. The default implementation adds a textual footnote marker using an index into the list of hyperlinks created by `anchor_bgn()`.

`handle_image` (*source*, *alt* [, *ismap* [, *align* [, *width* [, *height*]]]])

This method is called to handle images. The default implementation simply passes the *alt* value to the `handle_data()` method.

`save_bgn` ()

Begins saving character data in a buffer instead of sending it to the formatter object. Retrieve the stored data via `save_end()`. Use of the `save_bgn()` / `save_end()` pair may not be nested.

`save_end` ()

Ends buffering character data and returns all data saved since the preceding call to `save_bgn()`. If the `nofill` flag is false, whitespace is collapsed to single spaces. A call to this method without a preceding call to `save_bgn()` will raise a `TypeError` exception.

8.4 `htmlentitydefs` — Definitions of HTML general entities

This module defines three dictionaries, `name2codepoint`, `codepoint2name`, and `entitydefs`. `entitydefs` is used by the `htmllib` module to provide the `entitydefs` member of the `HTMLParser` class. The definition provided here contains all the entities defined by XHTML 1.0 that can be handled using simple textual substitution in the Latin-1 character set (ISO-8859-1).

`entitydefs`

A dictionary mapping XHTML 1.0 entity definitions to their replacement text in ISO Latin-1.

`name2codepoint`

A dictionary that maps HTML entity names to the Unicode codepoints. New in version 2.3.

`codepoint2name`

A dictionary that maps Unicode codepoints to HTML entity names. New in version 2.3.

8.5 `xml.parsers.expat` — Fast XML parsing using Expat

New in version 2.0.

The `xml.parsers.expat` module is a Python interface to the Expat non-validating XML parser. The module provides a single extension type, `xmlparser`, that represents the current state of an XML parser. After an `xmlparser` object has been created, various attributes of the object can be set to handler functions. When an XML document is then fed to the parser, the handler functions are called for the character data and markup in the XML document.

This module uses the `pyexpat` module to provide access to the Expat parser. Direct use of the `pyexpat` module is deprecated.

This module provides one exception and one type object:

exception `ExpatError`

The exception raised when Expat reports an error. See section 8.5.2, “ExpatError Exceptions,” for more information on interpreting Expat errors.

exception `error`

Alias for `ExpatError`.

`XMLParserType`

The type of the return values from the `ParserCreate()` function.

The `xml.parsers.expat` module contains two functions:

`ErrorString(errno)`

Returns an explanatory string for a given error number *errno*.

`ParserCreate([encoding[, namespace_separator]])`

Creates and returns a new `xmlparser` object. *encoding*, if specified, must be a string naming the encoding used by the XML data. Expat doesn’t support as many encodings as Python does, and its repertoire of encodings can’t be extended; it supports UTF-8, UTF-16, ISO-8859-1 (Latin1), and ASCII. If *encoding* is given it will override the implicit or explicit encoding of the document.

Expat can optionally do XML namespace processing for you, enabled by providing a value for *namespace_separator*. The value must be a one-character string; a `ValueError` will be raised if the string has an illegal length (`None` is considered the same as omission). When namespace processing is enabled, element type names and attribute names that belong to a namespace will be expanded. The element name passed to the element handlers `StartElementHandler` and `EndElementHandler` will be the concatenation of the namespace URI, the namespace separator character, and the local part of the name. If the namespace separator is a zero byte (`chr(0)`) then the namespace URI and the local part will be concatenated without any separator.

For example, if *namespace_separator* is set to a space character (`' '`) and the following document is parsed:

```

<?xml version="1.0"?>
<root xmlns      = "http://default-namespace.org/"
      xmlns:py   = "http://www.python.org/ns/">
  <py:elem1 />
  <elem2 xmlns="" />
</root>

```

`StartElementHandler` will receive the following strings for each element:

```

http://default-namespace.org/ root
http://www.python.org/ns/ elem1
elem2

```

See Also:

The Expat XML Parser

(<http://www.libexpat.org/>)

Home page of the Expat project.

8.5.1 XMLParser Objects

`xmlparser` objects have the following methods:

Parse (*data* [, *isfinal*])

Parses the contents of the string *data*, calling the appropriate handler functions to process the parsed data. *isfinal* must be true on the final call to this method. *data* can be the empty string at any time.

ParseFile (*file*)

Parse XML data reading from the object *file*. *file* only needs to provide the `read(nbytes)` method, returning the empty string when there's no more data.

SetBase (*base*)

Sets the base to be used for resolving relative URIs in system identifiers in declarations. Resolving relative identifiers is left to the application: this value will be passed through as the *base* argument to the `ExternalEntityRefHandler`, `NotationDeclHandler`, and `UnparsedEntityDeclHandler` functions.

GetBase ()

Returns a string containing the base set by a previous call to `SetBase()`, or `None` if `SetBase()` hasn't been called.

GetInputContext ()

Returns the input data that generated the current event as a string. The data is in the encoding of the entity which contains the text. When called while an event handler is not active, the return value is `None`. New in version 2.1.

ExternalEntityParserCreate (*context* [, *encoding*])

Create a "child" parser which can be used to parse an external parsed entity referred to by content parsed by the parent parser. The *context* parameter should be the string passed to the `ExternalEntityRefHandler()` handler function, described below. The child parser is created with the `ordered_attributes`, `returns_unicode` and `specified_attributes` set to the values of this parser.

UseForeignDTD ([*flag*])

Calling this with a true value for *flag* (the default) will cause Expat to call the `ExternalEntityRefHandler` with `None` for all arguments to allow an alternate DTD to be loaded. If the document does not contain a document type declaration, the `ExternalEntityRefHandler` will still be called, but the `StartDoctypeDeclHandler` and `EndDoctypeDeclHandler` will not be called.

Passing a false value for *flag* will cancel a previous call that passed a true value, but otherwise has no effect.

This method can only be called before the `Parse()` or `ParseFile()` methods are called; calling it after either of those have been called causes `ExpatError` to be raised with the `code` attribute set to `errors.XML_ERROR_CANT_CHANGE_FEATURE_ONCE_PARSING`.

New in version 2.3.

`xmlparser` objects have the following attributes:

buffer_size

The size of the buffer used when `buffer_text` is true. This value cannot be changed at this time. New in version 2.3.

buffer_text

Setting this to true causes the `xmlparser` object to buffer textual content returned by Expat to avoid multiple calls to the `CharacterDataHandler()` callback whenever possible. This can improve performance substantially since Expat normally breaks character data into chunks at every line ending. This attribute is false by default, and may be changed at any time. New in version 2.3.

buffer_used

If `buffer_text` is enabled, the number of bytes stored in the buffer. These bytes represent UTF-8 encoded text. This attribute has no meaningful interpretation when `buffer_text` is false. New in version 2.3.

ordered_attributes

Setting this attribute to a non-zero integer causes the attributes to be reported as a list rather than a dictionary. The attributes are presented in the order found in the document text. For each attribute, two list entries are presented: the attribute name and the attribute value. (Older versions of this module also used this format.) By default, this attribute is false; it may be changed at any time. New in version 2.1.

returns_unicode

If this attribute is set to a non-zero integer, the handler functions will be passed Unicode strings. If `returns_unicode` is `False`, 8-bit strings containing UTF-8 encoded data will be passed to the handlers. This is `True` by default when Python is built with Unicode support. Changed in version 1.6: Can be changed at any time to affect the result type.

specified_attributes

If set to a non-zero integer, the parser will report only those attributes which were specified in the document instance and not those which were derived from attribute declarations. Applications which set this need to be especially careful to use what additional information is available from the declarations as needed to comply with the standards for the behavior of XML processors. By default, this attribute is false; it may be changed at any time. New in version 2.1.

The following attributes contain values relating to the most recent error encountered by an `xmlparser` object, and will only have correct values once a call to `Parse()` or `ParseFile()` has raised a `xml.parsers.expat.ExpatError` exception.

ErrorByteIndex

Byte index at which an error occurred.

ErrorCode

Numeric code specifying the problem. This value can be passed to the `ErrorString()` function, or compared to one of the constants defined in the `errors` object.

ErrorColumnNumber

Column number at which an error occurred.

ErrorLineNumber

Line number at which an error occurred.

The following attributes contain values relating to the current parse location in an `xmlparser` object. During a callback reporting a parse event they indicate the location of the first of the sequence of characters that generated the

event. When called outside of a callback, the position indicated will be just past the last parse event (regardless of whether there was an associated callback). New in version 2.4.

CurrentByteIndex

Current byte index in the parser input.

CurrentColumnNumber

Current column number in the parser input.

CurrentLineNumber

Current line number in the parser input.

Here is the list of handlers that can be set. To set a handler on an `xmlparser` object *o*, use `o.handlername = func`. *handlername* must be taken from the following list, and *func* must be a callable object accepting the correct number of arguments. The arguments are all strings, unless otherwise stated.

XmlDeclHandler (*version, encoding, standalone*)

Called when the XML declaration is parsed. The XML declaration is the (optional) declaration of the applicable version of the XML recommendation, the encoding of the document text, and an optional “standalone” declaration. *version* and *encoding* will be strings of the type dictated by the `returns_unicode` attribute, and *standalone* will be 1 if the document is declared standalone, 0 if it is declared not to be standalone, or -1 if the standalone clause was omitted. This is only available with Expat version 1.95.0 or newer. New in version 2.1.

StartDoctypeDeclHandler (*doctypeName, systemId, publicId, has_internal_subset*)

Called when Expat begins parsing the document type declaration (`<!DOCTYPE ...`). The *doctypeName* is provided exactly as presented. The *systemId* and *publicId* parameters give the system and public identifiers if specified, or `None` if omitted. *has_internal_subset* will be true if the document contains an internal document declaration subset. This requires Expat version 1.2 or newer.

EndDoctypeDeclHandler ()

Called when Expat is done parsing the document type declaration. This requires Expat version 1.2 or newer.

ElementDeclHandler (*name, model*)

Called once for each element type declaration. *name* is the name of the element type, and *model* is a representation of the content model.

AttlistDeclHandler (*elname, attname, type, default, required*)

Called for each declared attribute for an element type. If an attribute list declaration declares three attributes, this handler is called three times, once for each attribute. *elname* is the name of the element to which the declaration applies and *attname* is the name of the attribute declared. The attribute type is a string passed as *type*; the possible values are `'CDATA'`, `'ID'`, `'IDREF'`, ... *default* gives the default value for the attribute used when the attribute is not specified by the document instance, or `None` if there is no default value (`#IMPLIED` values). If the attribute is required to be given in the document instance, *required* will be true. This requires Expat version 1.95.0 or newer.

StartElementHandler (*name, attributes*)

Called for the start of every element. *name* is a string containing the element name, and *attributes* is a dictionary mapping attribute names to their values.

EndElementHandler (*name*)

Called for the end of every element.

ProcessingInstructionHandler (*target, data*)

Called for every processing instruction.

CharacterDataHandler (*data*)

Called for character data. This will be called for normal character data, CDATA marked content, and ignorable whitespace. Applications which must distinguish these cases can use the `StartCdataSectionHandler`, `EndCdataSectionHandler`, and `ElementDeclHandler` callbacks to collect the required information.

UnparsedEntityDeclHandler (*entityName, base, systemId, publicId, notationName*)

Called for unparsed (NDATA) entity declarations. This is only present for version 1.2 of the Expat library; for more recent versions, use `EntityDeclHandler` instead. (The underlying function in the Expat library has been declared obsolete.)

EntityDeclHandler (*entityName*, *is_parameter_entity*, *value*, *base*, *systemId*, *publicId*, *notationName*)

Called for all entity declarations. For parameter and internal entities, *value* will be a string giving the declared contents of the entity; this will be `None` for external entities. The *notationName* parameter will be `None` for parsed entities, and the name of the notation for unparsed entities. *is_parameter_entity* will be true if the entity is a parameter entity or false for general entities (most applications only need to be concerned with general entities). This is only available starting with version 1.95.0 of the Expat library. New in version 2.1.

NotationDeclHandler (*notationName*, *base*, *systemId*, *publicId*)

Called for notation declarations. *notationName*, *base*, and *systemId*, and *publicId* are strings if given. If the public identifier is omitted, *publicId* will be `None`.

StartNamespaceDeclHandler (*prefix*, *uri*)

Called when an element contains a namespace declaration. Namespace declarations are processed before the `StartElementHandler` is called for the element on which declarations are placed.

EndNamespaceDeclHandler (*prefix*)

Called when the closing tag is reached for an element that contained a namespace declaration. This is called once for each namespace declaration on the element in the reverse of the order for which the `StartNamespaceDeclHandler` was called to indicate the start of each namespace declaration's scope. Calls to this handler are made after the corresponding `EndElementHandler` for the end of the element.

CommentHandler (*data*)

Called for comments. *data* is the text of the comment, excluding the leading '`<!--`' and trailing '`-->`'.

StartCdataSectionHandler ()

Called at the start of a CDATA section. This and `EndCdataSectionHandler` are needed to be able to identify the syntactical start and end for CDATA sections.

EndCdataSectionHandler ()

Called at the end of a CDATA section.

DefaultHandler (*data*)

Called for any characters in the XML document for which no applicable handler has been specified. This means characters that are part of a construct which could be reported, but for which no handler has been supplied.

DefaultHandlerExpand (*data*)

This is the same as the `DefaultHandler`, but doesn't inhibit expansion of internal entities. The entity reference will not be passed to the default handler.

NotStandaloneHandler ()

Called if the XML document hasn't been declared as being a standalone document. This happens when there is an external subset or a reference to a parameter entity, but the XML declaration does not set `standalone` to `yes` in an XML declaration. If this handler returns 0, then the parser will throw an `XML_ERROR_NOT_STANDALONE` error. If this handler is not set, no exception is raised by the parser for this condition.

ExternalEntityRefHandler (*context*, *base*, *systemId*, *publicId*)

Called for references to external entities. *base* is the current base, as set by a previous call to `SetBase()`. The public and system identifiers, *systemId* and *publicId*, are strings if given; if the public identifier is not given, *publicId* will be `None`. The *context* value is opaque and should only be used as described below.

For external entities to be parsed, this handler must be implemented. It is responsible for creating the sub-parser using `ExternalEntityParserCreate(context)`, initializing it with the appropriate callbacks, and parsing the entity. This handler should return an integer; if it returns 0, the parser will throw an `XML_ERROR_EXTERNAL_ENTITY_HANDLING` error, otherwise parsing will continue.

If this handler is not provided, external entities are reported by the `DefaultHandler` callback, if provided.

8.5.2 ExpatError Exceptions

ExpatError exceptions have a number of interesting attributes:

code

Expat's internal error number for the specific error. This will match one of the constants defined in the `errors` object from this module. New in version 2.1.

lineno

Line number on which the error was detected. The first line is numbered 1. New in version 2.1.

offset

Character offset into the line where the error occurred. The first column is numbered 0. New in version 2.1.

8.5.3 Example

The following program defines three handlers that just print out their arguments.

```
import xml.parsers.expat

# 3 handler functions
def start_element(name, attrs):
    print 'Start element:', name, attrs
def end_element(name):
    print 'End element:', name
def char_data(data):
    print 'Character data:', repr(data)

p = xml.parsers.expat.ParserCreate()

p.StartElementHandler = start_element
p.EndElementHandler = end_element
p.CharacterDataHandler = char_data

p.Parse("<?xml version='1.0'?>
<parent id='top'><child1 name='paul'>Text goes here</child1>
<child2 name='fred'>More text</child2>
</parent>\"", 1)
```

The output from this program is:

```
Start element: parent {'id': 'top'}
Start element: child1 {'name': 'paul'}
Character data: 'Text goes here'
End element: child1
Character data: '\n'
Start element: child2 {'name': 'fred'}
Character data: 'More text'
End element: child2
Character data: '\n'
End element: parent
```

8.5.4 Content Model Descriptions

Content modules are described using nested tuples. Each tuple contains four values: the type, the quantifier, the name, and a tuple of children. Children are simply additional content module descriptions.

The values of the first two fields are constants defined in the `model` object of the `xml.parsers.expat` module. These constants can be collected in two groups: the model type group and the quantifier group.

The constants in the model type group are:

XML_CTYPE_ANY

The element named by the model name was declared to have a content model of ANY.

XML_CTYPE_CHOICE

The named element allows a choice from a number of options; this is used for content models such as `(A | B | C)`.

XML_CTYPE_EMPTY

Elements which are declared to be EMPTY have this model type.

XML_CTYPE_MIXED

XML_CTYPE_NAME

XML_CTYPE_SEQ

Models which represent a series of models which follow one after the other are indicated with this model type. This is used for models such as `(A, B, C)`.

The constants in the quantifier group are:

XML_CQUANT_NONE

No modifier is given, so it can appear exactly once, as for A.

XML_CQUANT_OPT

The model is optional: it can appear once or not at all, as for A?

XML_CQUANT_PLUS

The model must occur one or more times (like A+).

XML_CQUANT_REP

The model must occur zero or more times, as for A*.

8.5.5 Expat error constants

The following constants are provided in the `errors` object of the `xml.parsers.expat` module. These constants are useful in interpreting some of the attributes of the `ExpatError` exception objects raised when an error has occurred.

The `errors` object has the following attributes:

XML_ERROR_ASYNC_ENTITY

XML_ERROR_ATTRIBUTE_EXTERNAL_ENTITY_REF

An entity reference in an attribute value referred to an external entity instead of an internal entity.

XML_ERROR_BAD_CHAR_REF

A character reference referred to a character which is illegal in XML (for example, character 0, or `'�'`).

XML_ERROR_BINARY_ENTITY_REF

An entity reference referred to an entity which was declared with a notation, so cannot be parsed.

XML_ERROR_DUPLICATE_ATTRIBUTE

An attribute was used more than once in a start tag.

XML_ERROR_INCORRECT_ENCODING**XML_ERROR_INVALID_TOKEN**

Raised when an input byte could not properly be assigned to a character; for example, a NUL byte (value 0) in a UTF-8 input stream.

XML_ERROR_JUNK_AFTER_DOC_ELEMENT

Something other than whitespace occurred after the document element.

XML_ERROR_MISPLACED_XML_PI

An XML declaration was found somewhere other than the start of the input data.

XML_ERROR_NO_ELEMENTS

The document contains no elements (XML requires all documents to contain exactly one top-level element)..

XML_ERROR_NO_MEMORY

Expat was not able to allocate memory internally.

XML_ERROR_PARAM_ENTITY_REF

A parameter entity reference was found where it was not allowed.

XML_ERROR_PARTIAL_CHAR

An incomplete character was found in the input.

XML_ERROR_RECURSIVE_ENTITY_REF

An entity reference contained another reference to the same entity; possibly via a different name, and possibly indirectly.

XML_ERROR_SYNTAX

Some unspecified syntax error was encountered.

XML_ERROR_TAG_MISMATCH

An end tag did not match the innermost open start tag.

XML_ERROR_UNCLOSED_TOKEN

Some token (such as a start tag) was not closed before the end of the stream or the next token was encountered.

XML_ERROR_UNDEFINED_ENTITY

A reference was made to an entity which was not defined.

XML_ERROR_UNKNOWN_ENCODING

The document encoding is not supported by Expat.

XML_ERROR_UNCLOSED_CDATA_SECTION

A CDATA marked section was not closed.

XML_ERROR_EXTERNAL_ENTITY_HANDLING**XML_ERROR_NOT_STANDALONE**

The parser determined that the document was not “standalone” though it declared itself to be in the XML declaration, and the `NotStandaloneHandler` was set and returned 0.

XML_ERROR_UNEXPECTED_STATE**XML_ERROR_ENTITY_DECLARED_IN_PE****XML_ERROR_FEATURE_REQUIRES_XML_DTD**

An operation was requested that requires DTD support to be compiled in, but Expat was configured without DTD support. This should never be reported by a standard build of the `xml.parsers.expat` module.

XML_ERROR_CANT_CHANGE_FEATURE_ONCE_PARSING

A behavioral change was requested after parsing started that can only be changed before parsing has started. This is (currently) only raised by `UseForeignDTD()`.

XML_ERROR_UNBOUND_PREFIX

An undeclared prefix was found when namespace processing was enabled.

XML_ERROR_UNDECLARING_PREFIX

The document attempted to remove the namespace declaration associated with a prefix.

XML_ERROR_INCOMPLETE_PE

A parameter entity contained incomplete markup.

XML_ERROR_XML_DECL

The document contained no document element at all.

XML_ERROR_TEXT_DECL

There was an error parsing a text declaration in an external entity.

XML_ERROR_PUBLICID

Characters were found in the public id that are not allowed.

XML_ERROR_SUSPENDED

The requested operation was made on a suspended parser, but isn't allowed. This includes attempts to provide additional input or to stop the parser.

XML_ERROR_NOT_SUSPENDED

An attempt to resume the parser was made when the parser had not been suspended.

XML_ERROR_ABORTED

This should not be reported to Python applications.

XML_ERROR_FINISHED

The requested operation was made on a parser which was finished parsing input, but isn't allowed. This includes attempts to provide additional input or to stop the parser.

XML_ERROR_SUSPEND_PE

8.6 `xml.dom` — The Document Object Model API

New in version 2.0.

The Document Object Model, or “DOM,” is a cross-language API from the World Wide Web Consortium (W3C) for accessing and modifying XML documents. A DOM implementation presents an XML document as a tree structure, or allows client code to build such a structure from scratch. It then gives access to the structure through a set of objects which provided well-known interfaces.

The DOM is extremely useful for random-access applications. SAX only allows you a view of one bit of the document at a time. If you are looking at one SAX element, you have no access to another. If you are looking at a text node, you have no access to a containing element. When you write a SAX application, you need to keep track of your program's position in the document somewhere in your own code. SAX does not do it for you. Also, if you need to look ahead in the XML document, you are just out of luck.

Some applications are simply impossible in an event driven model with no access to a tree. Of course you could build some sort of tree yourself in SAX events, but the DOM allows you to avoid writing that code. The DOM is a standard tree representation for XML data.

The Document Object Model is being defined by the W3C in stages, or “levels” in their terminology. The Python mapping of the API is substantially based on the DOM Level 2 recommendation. The mapping of the Level 3 specification, currently only available in draft form, is being developed by the [Python XML Special Interest Group](#) as part of the [PyXML package](#). Refer to the documentation bundled with that package for information on the current state of DOM Level 3 support.

DOM applications typically start by parsing some XML into a DOM. How this is accomplished is not covered at all by DOM Level 1, and Level 2 provides only limited improvements: There is a `DOMImplementation` object class

which provides access to `Document` creation methods, but no way to access an XML reader/parser/Document builder in an implementation-independent way. There is also no well-defined way to access these methods without an existing `Document` object. In Python, each DOM implementation will provide a function `getDOMImplementation()`. DOM Level 3 adds a Load/Store specification, which defines an interface to the reader, but this is not yet available in the Python standard library.

Once you have a DOM document object, you can access the parts of your XML document through its properties and methods. These properties are defined in the DOM specification; this portion of the reference manual describes the interpretation of the specification in Python.

The specification provided by the W3C defines the DOM API for Java, ECMAScript, and OMG IDL. The Python mapping defined here is based in large part on the IDL version of the specification, but strict compliance is not required (though implementations are free to support the strict mapping from IDL). See section 8.6.3, “Conformance,” for a detailed discussion of mapping requirements.

See Also:

Document Object Model (DOM) Level 2 Specification

(<http://www.w3.org/TR/DOM-Level-2-Core/>)

The W3C recommendation upon which the Python DOM API is based.

Document Object Model (DOM) Level 1 Specification

(<http://www.w3.org/TR/REC-DOM-Level-1/>)

The W3C recommendation for the DOM supported by `xml.dom.minidom`.

PyXML

(<http://pyxml.sourceforge.net>)

Users that require a full-featured implementation of DOM should use the PyXML package.

Python Language Mapping Specification

(<http://www.omg.org/docs/formal/02-11-05.pdf>)

This specifies the mapping from OMG IDL to Python.

8.6.1 Module Contents

The `xml.dom` contains the following functions:

`registerDOMImplementation(name, factory)`

Register the *factory* function with the name *name*. The factory function should return an object which implements the `DOMImplementation` interface. The factory function can return the same object every time, or a new one for each call, as appropriate for the specific implementation (e.g. if that implementation supports some customization).

`getDOMImplementation([name[, features]])`

Return a suitable DOM implementation. The *name* is either well-known, the module name of a DOM implementation, or `None`. If it is not `None`, imports the corresponding module and returns a `DOMImplementation` object if the import succeeds. If no name is given, and if the environment variable `PYTHON_DOM` is set, this variable is used to find the implementation.

If name is not given, this examines the available implementations to find one with the required feature set. If no implementation can be found, raise an `ImportError`. The features list must be a sequence of (*feature*, *version*) pairs which are passed to the `hasFeature()` method on available `DOMImplementation` objects.

Some convenience constants are also provided:

`EMPTY_NAMESPACE`

The value used to indicate that no namespace is associated with a node in the DOM. This is typically found as the `namespaceURI` of a node, or used as the *namespaceURI* parameter to a namespaces-specific method. New in version 2.2.

XML_NAMESPACE

The namespace URI associated with the reserved prefix `xml`, as defined by [Namespaces in XML](#) (section 4). New in version 2.2.

XMLNS_NAMESPACE

The namespace URI for namespace declarations, as defined by [Document Object Model \(DOM\) Level 2 Core Specification](#) (section 1.1.8). New in version 2.2.

XHTML_NAMESPACE

The URI of the XHTML namespace as defined by [XHTML 1.0: The Extensible HyperText Markup Language](#) (section 3.1.1). New in version 2.2.

In addition, `xml.dom` contains a base `Node` class and the DOM exception classes. The `Node` class provided by this module does not implement any of the methods or attributes defined by the DOM specification; concrete DOM implementations must provide those. The `Node` class provided as part of this module does provide the constants used for the `nodeType` attribute on concrete `Node` objects; they are located within the class rather than at the module level to conform with the DOM specifications.

8.6.2 Objects in the DOM

The definitive documentation for the DOM is the DOM specification from the W3C.

Note that DOM attributes may also be manipulated as nodes instead of as simple strings. It is fairly rare that you must do this, however, so this usage is not yet documented.

Interface	Section	Purpose
<code>DOMImplementation</code>	8.6.2	Interface to the underlying implementation.
<code>Node</code>	8.6.2	Base interface for most objects in a document.
<code>NodeList</code>	8.6.2	Interface for a sequence of nodes.
<code>DocumentType</code>	8.6.2	Information about the declarations needed to process a document.
<code>Document</code>	8.6.2	Object which represents an entire document.
<code>Element</code>	8.6.2	Element nodes in the document hierarchy.
<code>Attr</code>	8.6.2	Attribute value nodes on element nodes.
<code>Comment</code>	8.6.2	Representation of comments in the source document.
<code>Text</code>	8.6.2	Nodes containing textual content from the document.
<code>ProcessingInstruction</code>	8.6.2	Processing instruction representation.

An additional section describes the exceptions defined for working with the DOM in Python.

DOMImplementation Objects

The `DOMImplementation` interface provides a way for applications to determine the availability of particular features in the DOM they are using. DOM Level 2 added the ability to create new `Document` and `DocumentType` objects using the `DOMImplementation` as well.

hasFeature (*feature*, *version*)

Return true if the feature identified by the pair of strings *feature* and *version* is implemented.

createDocument (*namespaceUri*, *qualifiedName*, *doctype*)

Return a new `Document` object (the root of the DOM), with a child `Element` object having the given *namespaceUri* and *qualifiedName*. The *doctype* must be a `DocumentType` object created by `createDocumentType()`, or `None`. In the Python DOM API, the first two arguments can also be `None` in order to indicate that no `Element` child is to be created.

createDocumentType (*qualifiedName*, *publicId*, *systemId*)

Return a new `DocumentType` object that encapsulates the given *qualifiedName*, *publicId*, and *systemId*

strings, representing the information contained in an XML document type declaration.

Node Objects

All of the components of an XML document are subclasses of `Node`.

nodeType

An integer representing the node type. Symbolic constants for the types are on the `Node` object: `ELEMENT_NODE`, `ATTRIBUTE_NODE`, `TEXT_NODE`, `CDATA_SECTION_NODE`, `ENTITY_NODE`, `PROCESSING_INSTRUCTION_NODE`, `COMMENT_NODE`, `DOCUMENT_NODE`, `DOCUMENT_TYPE_NODE`, `NOTATION_NODE`. This is a read-only attribute.

parentNode

The parent of the current node, or `None` for the document node. The value is always a `Node` object or `None`. For `Element` nodes, this will be the parent element, except for the root element, in which case it will be the `Document` object. For `Attr` nodes, this is always `None`. This is a read-only attribute.

attributes

A `NamedNodeMap` of attribute objects. Only elements have actual values for this; others provide `None` for this attribute. This is a read-only attribute.

previousSibling

The node that immediately precedes this one with the same parent. For instance the element with an end-tag that comes just before the *self* element's start-tag. Of course, XML documents are made up of more than just elements so the previous sibling could be text, a comment, or something else. If this node is the first child of the parent, this attribute will be `None`. This is a read-only attribute.

nextSibling

The node that immediately follows this one with the same parent. See also `previousSibling`. If this is the last child of the parent, this attribute will be `None`. This is a read-only attribute.

childNodes

A list of nodes contained within this node. This is a read-only attribute.

firstChild

The first child of the node, if there are any, or `None`. This is a read-only attribute.

lastChild

The last child of the node, if there are any, or `None`. This is a read-only attribute.

localName

The part of the `tagName` following the colon if there is one, else the entire `tagName`. The value is a string.

prefix

The part of the `tagName` preceding the colon if there is one, else the empty string. The value is a string, or `None`.

namespaceURI

The namespace associated with the element name. This will be a string or `None`. This is a read-only attribute.

nodeName

This has a different meaning for each node type; see the DOM specification for details. You can always get the information you would get here from another property such as the `tagName` property for elements or the `name` property for attributes. For all node types, the value of this attribute will be either a string or `None`. This is a read-only attribute.

nodeValue

This has a different meaning for each node type; see the DOM specification for details. The situation is similar to that with `nodeName`. The value is a string or `None`.

hasAttributes()

Returns true if the node has any attributes.

hasChildNodes ()

Returns true if the node has any child nodes.

isSameNode (*other*)

Returns true if *other* refers to the same node as this node. This is especially useful for DOM implementations which use any sort of proxy architecture (because more than one object can refer to the same node).

Note: This is based on a proposed DOM Level 3 API which is still in the “working draft” stage, but this particular interface appears uncontroversial. Changes from the W3C will not necessarily affect this method in the Python DOM interface (though any new W3C API for this would also be supported).

appendChild (*newChild*)

Add a new child node to this node at the end of the list of children, returning *newChild*.

insertBefore (*newChild*, *refChild*)

Insert a new child node before an existing child. It must be the case that *refChild* is a child of this node; if not, `ValueError` is raised. *newChild* is returned. If *refChild* is `None`, it inserts *newChild* at the end of the children’s list.

removeChild (*oldChild*)

Remove a child node. *oldChild* must be a child of this node; if not, `ValueError` is raised. *oldChild* is returned on success. If *oldChild* will not be used further, its `unlink()` method should be called.

replaceChild (*newChild*, *oldChild*)

Replace an existing node with a new node. It must be the case that *oldChild* is a child of this node; if not, `ValueError` is raised.

normalize ()

Join adjacent text nodes so that all stretches of text are stored as single `Text` instances. This simplifies processing text from a DOM tree for many applications. New in version 2.1.

cloneNode (*deep*)

Clone this node. Setting *deep* means to clone all child nodes as well. This returns the clone.

NodeList Objects

A `NodeList` represents a sequence of nodes. These objects are used in two ways in the DOM Core recommendation: the `Element` objects provides one as its list of child nodes, and the `getElementsByTagName()` and `getElementsByTagNameNS()` methods of `Node` return objects with this interface to represent query results.

The DOM Level 2 recommendation defines one method and one attribute for these objects:

item (*i*)

Return the *i*’th item from the sequence, if there is one, or `None`. The index *i* is not allowed to be less than zero or greater than or equal to the length of the sequence.

length

The number of nodes in the sequence.

In addition, the Python DOM interface requires that some additional support is provided to allow `NodeList` objects to be used as Python sequences. All `NodeList` implementations must include support for `__len__()` and `__getitem__()`; this allows iteration over the `NodeList` in `for` statements and proper support for the `len()` built-in function.

If a DOM implementation supports modification of the document, the `NodeList` implementation must also support the `__setitem__()` and `__delitem__()` methods.

DocumentType Objects

Information about the notations and entities declared by a document (including the external subset if the parser uses it and can provide the information) is available from a `DocumentType` object. The `DocumentType` for a document is available from the `Document` object's `doctype` attribute; if there is no DOCTYPE declaration for the document, the document's `doctype` attribute will be set to `None` instead of an instance of this interface.

`DocumentType` is a specialization of `Node`, and adds the following attributes:

publicId

The public identifier for the external subset of the document type definition. This will be a string or `None`.

systemId

The system identifier for the external subset of the document type definition. This will be a URI as a string, or `None`.

internalSubset

A string giving the complete internal subset from the document. This does not include the brackets which enclose the subset. If the document has no internal subset, this should be `None`.

name

The name of the root element as given in the DOCTYPE declaration, if present.

entities

This is a `NamedNodeMap` giving the definitions of external entities. For entity names defined more than once, only the first definition is provided (others are ignored as required by the XML recommendation). This may be `None` if the information is not provided by the parser, or if no entities are defined.

notations

This is a `NamedNodeMap` giving the definitions of notations. For notation names defined more than once, only the first definition is provided (others are ignored as required by the XML recommendation). This may be `None` if the information is not provided by the parser, or if no notations are defined.

Document Objects

A `Document` represents an entire XML document, including its constituent elements, attributes, processing instructions, comments etc. Remember that it inherits properties from `Node`.

documentElement

The one and only root element of the document.

createElement (*tagName*)

Create and return a new element node. The element is not inserted into the document when it is created. You need to explicitly insert it with one of the other methods such as `insertBefore()` or `appendChild()`.

createElementNS (*namespaceURI*, *tagName*)

Create and return a new element with a namespace. The *tagName* may have a prefix. The element is not inserted into the document when it is created. You need to explicitly insert it with one of the other methods such as `insertBefore()` or `appendChild()`.

createTextNode (*data*)

Create and return a text node containing the data passed as a parameter. As with the other creation methods, this one does not insert the node into the tree.

createComment (*data*)

Create and return a comment node containing the data passed as a parameter. As with the other creation methods, this one does not insert the node into the tree.

createProcessingInstruction (*target*, *data*)

Create and return a processing instruction node containing the *target* and *data* passed as parameters. As with

the other creation methods, this one does not insert the node into the tree.

createAttribute (*name*)

Create and return an attribute node. This method does not associate the attribute node with any particular element. You must use `setAttributeNode()` on the appropriate `Element` object to use the newly created attribute instance.

createAttributeNS (*namespaceURI*, *qualifiedName*)

Create and return an attribute node with a namespace. The *tagName* may have a prefix. This method does not associate the attribute node with any particular element. You must use `setAttributeNode()` on the appropriate `Element` object to use the newly created attribute instance.

getElementsByTagName (*tagName*)

Search for all descendants (direct children, children's children, etc.) with a particular element type name.

getElementsByTagNameNS (*namespaceURI*, *localName*)

Search for all descendants (direct children, children's children, etc.) with a particular namespace URI and localname. The localname is the part of the namespace after the prefix.

Element Objects

`Element` is a subclass of `Node`, so inherits all the attributes of that class.

tagName

The element type name. In a namespace-using document it may have colons in it. The value is a string.

getElementsByTagName (*tagName*)

Same as equivalent method in the `Document` class.

getElementsByTagNameNS (*tagName*)

Same as equivalent method in the `Document` class.

hasAttribute (*name*)

Returns true if the element has an attribute named by *name*.

hasAttributeNS (*namespaceURI*, *localName*)

Returns true if the element has an attribute named by *namespaceURI* and *localName*.

getAttribute (*name*)

Return the value of the attribute named by *name* as a string. If no such attribute exists, an empty string is returned, as if the attribute had no value.

getAttributeNode (*attrname*)

Return the `Attr` node for the attribute named by *attrname*.

getAttributeNS (*namespaceURI*, *localName*)

Return the value of the attribute named by *namespaceURI* and *localName* as a string. If no such attribute exists, an empty string is returned, as if the attribute had no value.

getAttributeNodeNS (*namespaceURI*, *localName*)

Return an attribute value as a node, given a *namespaceURI* and *localName*.

removeAttribute (*name*)

Remove an attribute by name. No exception is raised if there is no matching attribute.

removeAttributeNode (*oldAttr*)

Remove and return *oldAttr* from the attribute list, if present. If *oldAttr* is not present, `NotFoundErr` is raised.

removeAttributeNS (*namespaceURI*, *localName*)

Remove an attribute by name. Note that it uses a *localName*, not a *qname*. No exception is raised if there is no matching attribute.

setAttribute (*name*, *value*)

Set an attribute value from a string.

setAttributeNode (*newAttr*)

Add a new attribute node to the element, replacing an existing attribute if necessary if the *name* attribute matches. If a replacement occurs, the old attribute node will be returned. If *newAttr* is already in use, *InuseAttributeErr* will be raised.

setAttributeNodeNS (*newAttr*)

Add a new attribute node to the element, replacing an existing attribute if necessary if the *namespaceURI* and *localName* attributes match. If a replacement occurs, the old attribute node will be returned. If *newAttr* is already in use, *InuseAttributeErr* will be raised.

setAttributeNS (*namespaceURI*, *qname*, *value*)

Set an attribute value from a string, given a *namespaceURI* and a *qname*. Note that a *qname* is the whole attribute name. This is different than above.

Attr Objects

Attr inherits from *Node*, so inherits all its attributes.

name

The attribute name. In a namespace-using document it may have colons in it.

localName

The part of the name following the colon if there is one, else the entire name. This is a read-only attribute.

prefix

The part of the name preceding the colon if there is one, else the empty string.

NamedNodeMap Objects

NamedNodeMap does *not* inherit from *Node*.

length

The length of the attribute list.

item (*index*)

Return an attribute with a particular index. The order you get the attributes in is arbitrary but will be consistent for the life of a DOM. Each item is an attribute node. Get its value with the *value* attribute.

There are also experimental methods that give this class more mapping behavior. You can use them or you can use the standardized *getAttribute*()* family of methods on the *Element* objects.

Comment Objects

Comment represents a comment in the XML document. It is a subclass of *Node*, but cannot have child nodes.

data

The content of the comment as a string. The attribute contains all characters between the leading *<!--* and trailing *-->*, but does not include them.

Text and CDATASection Objects

The *Text* interface represents text in the XML document. If the parser and DOM implementation support the DOM's XML extension, portions of the text enclosed in CDATA marked sections are stored in *CDATASection* objects. These two interfaces are identical, but provide different values for the *nodeType* attribute.

These interfaces extend the `Node` interface. They cannot have child nodes.

data

The content of the text node as a string.

Note: The use of a `CDATASection` node does not indicate that the node represents a complete CDATA marked section, only that the content of the node was part of a CDATA section. A single CDATA section may be represented by more than one node in the document tree. There is no way to determine whether two adjacent `CDATASection` nodes represent different CDATA marked sections.

ProcessingInstruction Objects

Represents a processing instruction in the XML document; this inherits from the `Node` interface and cannot have child nodes.

target

The content of the processing instruction up to the first whitespace character. This is a read-only attribute.

data

The content of the processing instruction following the first whitespace character.

Exceptions

New in version 2.1.

The DOM Level 2 recommendation defines a single exception, `DOMException`, and a number of constants that allow applications to determine what sort of error occurred. `DOMException` instances carry a `code` attribute that provides the appropriate value for the specific exception.

The Python DOM interface provides the constants, but also expands the set of exceptions so that a specific exception exists for each of the exception codes defined by the DOM. The implementations must raise the appropriate specific exception, each of which carries the appropriate value for the `code` attribute.

exception `DOMException`

Base exception class used for all specific DOM exceptions. This exception class cannot be directly instantiated.

exception `DomstringSizeErr`

Raised when a specified range of text does not fit into a string. This is not known to be used in the Python DOM implementations, but may be received from DOM implementations not written in Python.

exception `HierarchyRequestErr`

Raised when an attempt is made to insert a node where the node type is not allowed.

exception `IndexSizeErr`

Raised when an index or size parameter to a method is negative or exceeds the allowed values.

exception `InuseAttributeErr`

Raised when an attempt is made to insert an `Attr` node that is already present elsewhere in the document.

exception `InvalidAccessErr`

Raised if a parameter or an operation is not supported on the underlying object.

exception `InvalidCharacterErr`

This exception is raised when a string parameter contains a character that is not permitted in the context it's being used in by the XML 1.0 recommendation. For example, attempting to create an `Element` node with a space in the element type name will cause this error to be raised.

exception `InvalidModificationErr`

Raised when an attempt is made to modify the type of a node.

exception `InvalidStateErr`

Raised when an attempt is made to use an object that is not defined or is no longer usable.

exception `NamespaceErr`

If an attempt is made to change any object in a way that is not permitted with regard to the [Namespaces in XML](#) recommendation, this exception is raised.

exception `NotFoundErr`

Exception when a node does not exist in the referenced context. For example, `NamedNodeMap.removeNamedItem()` will raise this if the node passed in does not exist in the map.

exception `NotSupportedErr`

Raised when the implementation does not support the requested type of object or operation.

exception `NoDataAllowedErr`

This is raised if data is specified for a node which does not support data.

exception `NoModificationAllowedErr`

Raised on attempts to modify an object where modifications are not allowed (such as for read-only nodes).

exception `SyntaxErr`

Raised when an invalid or illegal string is specified.

exception `WrongDocumentErr`

Raised when a node is inserted in a different document than it currently belongs to, and the implementation does not support migrating the node from one document to the other.

The exception codes defined in the DOM recommendation map to the exceptions described above according to this table:

Constant	Exception
<code>DOMSTRING_SIZE_ERR</code>	<code>DomstringSizeErr</code>
<code>HIERARCHY_REQUEST_ERR</code>	<code>HierarchyRequestErr</code>
<code>INDEX_SIZE_ERR</code>	<code>IndexSizeErr</code>
<code>INUSE_ATTRIBUTE_ERR</code>	<code>InuseAttributeErr</code>
<code>INVALID_ACCESS_ERR</code>	<code>InvalidAccessErr</code>
<code>INVALID_CHARACTER_ERR</code>	<code>InvalidCharacterErr</code>
<code>INVALID_MODIFICATION_ERR</code>	<code>InvalidModificationErr</code>
<code>INVALID_STATE_ERR</code>	<code>InvalidStateErr</code>
<code>NAMESPACE_ERR</code>	<code>NamespaceErr</code>
<code>NOT_FOUND_ERR</code>	<code>NotFoundErr</code>
<code>NOT_SUPPORTED_ERR</code>	<code>NotSupportedErr</code>
<code>NO_DATA_ALLOWED_ERR</code>	<code>NoDataAllowedErr</code>
<code>NO_MODIFICATION_ALLOWED_ERR</code>	<code>NoModificationAllowedErr</code>
<code>SYNTAX_ERR</code>	<code>SyntaxErr</code>
<code>WRONG_DOCUMENT_ERR</code>	<code>WrongDocumentErr</code>

8.6.3 Conformance

This section describes the conformance requirements and relationships between the Python DOM API, the W3C DOM recommendations, and the OMG IDL mapping for Python.

Type Mapping

The primitive IDL types used in the DOM specification are mapped to Python types according to the following table.

IDL Type	Python Type
boolean	IntegerType (with a value of 0 or 1)
int	IntegerType
long int	IntegerType
unsigned int	IntegerType

Additionally, the `DOMString` defined in the recommendation is mapped to a Python string or Unicode string. Applications should be able to handle Unicode whenever a string is returned from the DOM.

The IDL `null` value is mapped to `None`, which may be accepted or provided by the implementation whenever `null` is allowed by the API.

Accessor Methods

The mapping from OMG IDL to Python defines accessor functions for IDL attribute declarations in much the way the Java mapping does. Mapping the IDL declarations

```
readonly attribute string someValue;
    attribute string anotherValue;
```

yields three accessor functions: a “get” method for `someValue` (`_get_someValue()`), and “get” and “set” methods for `anotherValue` (`_get_anotherValue()` and `_set_anotherValue()`). The mapping, in particular, does not require that the IDL attributes are accessible as normal Python attributes: `object.someValue` is *not* required to work, and may raise an `AttributeError`.

The Python DOM API, however, *does* require that normal attribute access work. This means that the typical surrogates generated by Python IDL compilers are not likely to work, and wrapper objects may be needed on the client if the DOM objects are accessed via CORBA. While this does require some additional consideration for CORBA DOM clients, the implementers with experience using DOM over CORBA from Python do not consider this a problem. Attributes that are declared `readonly` may not restrict write access in all DOM implementations.

In the Python DOM API, accessor functions are not required. If provided, they should take the form defined by the Python IDL mapping, but these methods are considered unnecessary since the attributes are accessible directly from Python. “Set” accessors should never be provided for `readonly` attributes.

The IDL definitions do not fully embody the requirements of the W3C DOM API, such as the notion of certain objects, such as the return value of `getElementsByTagName()`, being “live”. The Python DOM API does not require implementations to enforce such requirements.

8.7 `xml.dom.minidom` — Lightweight DOM implementation

New in version 2.0.

`xml.dom.minidom` is a light-weight implementation of the Document Object Model interface. It is intended to be simpler than the full DOM and also significantly smaller.

DOM applications typically start by parsing some XML into a DOM. With `xml.dom.minidom`, this is done through the parse functions:

```

from xml.dom.minidom import parse, parseString

dom1 = parse('c:\\temp\\mydata.xml') # parse an XML file by name

datasource = open('c:\\temp\\mydata.xml')
dom2 = parse(datasource) # parse an open file

dom3 = parseString('<myxml>Some data<empty/> some more data</myxml>')

```

The `parse()` function can take either a filename or an open file object.

parse (*filename_or_file*, *parser*)

Return a `Document` from the given input. *filename_or_file* may be either a file name, or a file-like object. *parser*, if given, must be a SAX2 parser object. This function will change the document handler of the parser and activate namespace support; other parser configuration (like setting an entity resolver) must have been done in advance.

If you have XML in a string, you can use the `parseString()` function instead:

parseString (*string* [, *parser*])

Return a `Document` that represents the *string*. This method creates a `StringIO` object for the string and passes that on to `parse`.

Both functions return a `Document` object representing the content of the document.

What the `parse()` and `parseString()` functions do is connect an XML parser with a “DOM builder” that can accept parse events from any SAX parser and convert them into a DOM tree. The name of the functions are perhaps misleading, but are easy to grasp when learning the interfaces. The parsing of the document will be completed before these functions return; it’s simply that these functions do not provide a parser implementation themselves.

You can also create a `Document` by calling a method on a “DOM Implementation” object. You can get this object either by calling the `getDOMImplementation()` function in the `xml.dom` package or the `xml.dom.minidom` module. Using the implementation from the `xml.dom.minidom` module will always return a `Document` instance from the minidom implementation, while the version from `xml.dom` may provide an alternate implementation (this is likely if you have the [PyXML package](#) installed). Once you have a `Document`, you can add child nodes to it to populate the DOM:

```

from xml.dom.minidom import getDOMImplementation

impl = getDOMImplementation()

newdoc = impl.createDocument(None, "some_tag", None)
top_element = newdoc.documentElement
text = newdoc.createTextNode('Some textual content.')
top_element.appendChild(text)

```

Once you have a DOM document object, you can access the parts of your XML document through its properties and methods. These properties are defined in the DOM specification. The main property of the document object is the `documentElement` property. It gives you the main element in the XML document: the one that holds all others. Here is an example program:

```

dom3 = parseString("<myxml>Some data</myxml>")
assert dom3.documentElement.tagName == "myxml"

```

When you are finished with a DOM, you should clean it up. This is necessary because some versions of Python do not support garbage collection of objects that refer to each other in a cycle. Until this restriction is removed from all

versions of Python, it is safest to write your code as if cycles would not be cleaned up.

The way to clean up a DOM is to call its `unlink()` method:

```
dom1.unlink()
dom2.unlink()
dom3.unlink()
```

`unlink()` is a `xml.dom.minidom`-specific extension to the DOM API. After calling `unlink()` on a node, the node and its descendants are essentially useless.

See Also:

Document Object Model (DOM) Level 1 Specification

(<http://www.w3.org/TR/REC-DOM-Level-1/>)

The W3C recommendation for the DOM supported by `xml.dom.minidom`.

8.7.1 DOM Objects

The definition of the DOM API for Python is given as part of the `xml.dom` module documentation. This section lists the differences between the API and `xml.dom.minidom`.

`unlink()`

Break internal references within the DOM so that it will be garbage collected on versions of Python without cyclic GC. Even when cyclic GC is available, using this can make large amounts of memory available sooner, so calling this on DOM objects as soon as they are no longer needed is good practice. This only needs to be called on the `Document` object, but may be called on child nodes to discard children of that node.

`writexml(writer[, indent="", addindent="", newl=""])`

Write XML to the writer object. The writer should have a `write()` method which matches that of the file object interface. The *indent* parameter is the indentation of the current node. The *addindent* parameter is the incremental indentation to use for subnodes of the current one. The *newl* parameter specifies the string to use to terminate newlines.

Changed in version 2.1: The optional keyword parameters *indent*, *addindent*, and *newl* were added to support pretty output.

Changed in version 2.3: For the `Document` node, an additional keyword argument *encoding* can be used to specify the encoding field of the XML header.

`toxml([encoding])`

Return the XML that the DOM represents as a string.

With no argument, the XML header does not specify an encoding, and the result is Unicode string if the default encoding cannot represent all characters in the document. Encoding this string in an encoding other than UTF-8 is likely incorrect, since UTF-8 is the default encoding of XML.

With an explicit *encoding* argument, the result is a byte string in the specified encoding. It is recommended that this argument is always specified. To avoid `UnicodeError` exceptions in case of unrepresentable text data, the encoding argument should be specified as "utf-8".

Changed in version 2.3: the *encoding* argument was introduced.

`toprettyxml([indent, newl])`

Return a pretty-printed version of the document. *indent* specifies the indentation string and defaults to a tabulator; *newl* specifies the string emitted at the end of each line and defaults to `\n`.

New in version 2.1. Changed in version 2.3: the encoding argument; see `toxml()`.

The following standard DOM methods have special considerations with `xml.dom.minidom`:

`cloneNode` (*deep*)

Although this method was present in the version of `xml.dom.minidom` packaged with Python 2.0, it was seriously broken. This has been corrected for subsequent releases.

8.7.2 DOM Example

This example program is a fairly realistic example of a simple program. In this particular case, we do not take much advantage of the flexibility of the DOM.

```
import xml.dom.minidom

document = """\
<slideshow>
<title>Demo slideshow</title>
<slide><title>Slide title</title>
<point>This is a demo</point>
<point>Of a program for processing slides</point>
</slide>

<slide><title>Another demo slide</title>
<point>It is important</point>
<point>To have more than</point>
<point>one slide</point>
</slide>
</slideshow>
"""

dom = xml.dom.minidom.parseString(document)

def getText(nodelist):
    rc = ""
    for node in nodelist:
        if node.nodeType == node.TEXT_NODE:
            rc = rc + node.data
    return rc

def handleSlideshow(slideshow):
    print "<html>"
    handleSlideshowTitle(slideshow.getElementsByTagName("title")[0])
    slides = slideshow.getElementsByTagName("slide")
    handleToc(slides)
    handleSlides(slides)
    print "</html>"

def handleSlides(slides):
    for slide in slides:
        handleSlide(slide)

def handleSlide(slide):
    handleSlideTitle(slide.getElementsByTagName("title")[0])
    handlePoints(slide.getElementsByTagName("point"))

def handleSlideshowTitle(title):
    print "<title>%s</title>" % getText(title.childNodes)

def handleSlideTitle(title):
    print "<h2>%s</h2>" % getText(title.childNodes)
```

```

def handlePoints(points):
    print "<ul>"
    for point in points:
        handlePoint(point)
    print "</ul>"

def handlePoint(point):
    print "<li>%s</li>" % getText(point.childNodes)

def handleToc(slides):
    for slide in slides:
        title = slide.getElementsByTagName("title")[0]
        print "<p>%s</p>" % getText(title.childNodes)

handleSlideshow(dom)

```

8.7.3 minidom and the DOM standard

The `xml.dom.minidom` module is essentially a DOM 1.0-compatible DOM with some DOM 2 features (primarily namespace features).

Usage of the DOM interface in Python is straight-forward. The following mapping rules apply:

- Interfaces are accessed through instance objects. Applications should not instantiate the classes themselves; they should use the creator functions available on the `Document` object. Derived interfaces support all operations (and attributes) from the base interfaces, plus any new operations.
- Operations are used as methods. Since the DOM uses only `in` parameters, the arguments are passed in normal order (from left to right). There are no optional arguments. `void` operations return `None`.
- IDL attributes map to instance attributes. For compatibility with the OMG IDL language mapping for Python, an attribute `foo` can also be accessed through accessor methods `_get_foo()` and `_set_foo()`. `readonly` attributes must not be changed; this is not enforced at runtime.
- The types `short`, `int`, `unsigned int`, `unsigned long`, `long`, and `boolean` all map to Python integer objects.
- The type `DOMString` maps to Python strings. `xml.dom.minidom` supports either byte or Unicode strings, but will normally produce Unicode strings. Values of type `DOMString` may also be `None` where allowed to have the IDL null value by the DOM specification from the W3C.
- `const` declarations map to variables in their respective scope (e.g. `xml.dom.minidom.Node.PROCESSING_INSTRUCTION_NODE`); they must not be changed.
- `DOMException` is currently not supported in `xml.dom.minidom`. Instead, `xml.dom.minidom` uses standard Python exceptions such as `TypeError` and `AttributeError`.
- `NodeList` objects are implemented using Python's built-in list type. Starting with Python 2.2, these objects provide the interface defined in the DOM specification, but with earlier versions of Python they do not support the official API. They are, however, much more "Pythonic" than the interface defined in the W3C recommendations.

The following interfaces have no implementation in `xml.dom.minidom`:

- `DOMTimeStamp`

- `DocumentType` (added in Python 2.1)
- `DOMImplementation` (added in Python 2.1)
- `CharacterData`
- `CDATASection`
- `Notation`
- `Entity`
- `EntityReference`
- `DocumentFragment`

Most of these reflect information in the XML document that is not of general utility to most DOM users.

8.8 `xml.dom.pulldom` — Support for building partial DOM trees

New in version 2.0.

`xml.dom.pulldom` allows building only selected portions of a Document Object Model representation of a document from SAX events.

```
class PullDOM ([documentFactory])
    xml.sax.handler.ContentHandler implementation that ...
```

```
class DOMEventStream (stream, parser, bufsize)
    ...
```

```
class SAX2DOM ([documentFactory])
    xml.sax.handler.ContentHandler implementation that ...
```

```
parse (stream_or_string [, parser [, bufsize ]])
    ...
```

```
parseString (string [, parser ])
    ...
```

```
default_bufsize
    Default value for the bufsize parameter to parse(). Changed in version 2.1: The value of this variable can be
    changed before calling parse() and the new value will take effect.
```

8.8.1 `DOMEventStream` Objects

```
getEvent ()
    ...
```

```
expandNode (node)
    ...
```

```
reset ()
    ...
```

8.9 `xml.sax` — Support for SAX2 parsers

New in version 2.0.

The `xml.sax` package provides a number of modules which implement the Simple API for XML (SAX) interface for Python. The package itself provides the SAX exceptions and the convenience functions which will be most used by users of the SAX API.

The convenience functions are:

`make_parser` (`[parser_list]`)

Create and return a SAX `XMLReader` object. The first parser found will be used. If `parser_list` is provided, it must be a sequence of strings which name modules that have a function named `create_parser()`. Modules listed in `parser_list` will be used before modules in the default list of parsers.

`parse` (`filename_or_stream`, `handler` [, `error_handler`])

Create a SAX parser and use it to parse a document. The document, passed in as `filename_or_stream`, can be a filename or a file object. The `handler` parameter needs to be a SAX `ContentHandler` instance. If `error_handler` is given, it must be a SAX `ErrorHandler` instance; if omitted, `SAXParseException` will be raised on all errors. There is no return value; all work must be done by the `handler` passed in.

`parseString` (`string`, `handler` [, `error_handler`])

Similar to `parse()`, but parses from a buffer `string` received as a parameter.

A typical SAX application uses three kinds of objects: readers, handlers and input sources. “Reader” in this context is another term for parser, i.e. some piece of code that reads the bytes or characters from the input source, and produces a sequence of events. The events then get distributed to the handler objects, i.e. the reader invokes a method on the handler. A SAX application must therefore obtain a reader object, create or open the input sources, create the handlers, and connect these objects all together. As the final step of preparation, the reader is called to parse the input. During parsing, methods on the handler objects are called based on structural and syntactic events from the input data.

For these objects, only the interfaces are relevant; they are normally not instantiated by the application itself. Since Python does not have an explicit notion of interface, they are formally introduced as classes, but applications may use implementations which do not inherit from the provided classes. The `InputSource`, `Locator`, `Attributes`, `AttributesNS`, and `XMLReader` interfaces are defined in the module `xml.sax.xmlreader`. The handler interfaces are defined in `xml.sax.handler`. For convenience, `InputSource` (which is often instantiated directly) and the handler classes are also available from `xml.sax`. These interfaces are described below.

In addition to these classes, `xml.sax` provides the following exception classes.

`exception SAXException` (`msg` [, `exception`])

Encapsulate an XML error or warning. This class can contain basic error or warning information from either the XML parser or the application: it can be subclassed to provide additional functionality or to add localization. Note that although the handlers defined in the `ErrorHandler` interface receive instances of this exception, it is not required to actually raise the exception — it is also useful as a container for information.

When instantiated, `msg` should be a human-readable description of the error. The optional `exception` parameter, if given, should be `None` or an exception that was caught by the parsing code and is being passed along as information.

This is the base class for the other SAX exception classes.

`exception SAXParseException` (`msg`, `exception`, `locator`)

Subclass of `SAXException` raised on parse errors. Instances of this class are passed to the methods of the SAX `ErrorHandler` interface to provide information about the parse error. This class supports the SAX `Locator` interface as well as the `SAXException` interface.

`exception SAXNotRecognizedException` (`msg` [, `exception`])

Subclass of `SAXException` raised when a SAX `XMLReader` is confronted with an unrecognized feature or property. SAX applications and extensions may use this class for similar purposes.

exception SAXNotSupportedException (*msg* [, *exception*])

Subclass of `SAXException` raised when a `SAX XMLReader` is asked to enable a feature that is not supported, or to set a property to a value that the implementation does not support. SAX applications and extensions may use this class for similar purposes.

See Also:

SAX: The Simple API for XML

(<http://www.saxproject.org/>)

This site is the focal point for the definition of the SAX API. It provides a Java implementation and online documentation. Links to implementations and historical information are also available.

Module `xml.sax.handler` (section 8.10):

Definitions of the interfaces for application-provided objects.

Module `xml.sax.saxutils` (section 8.11):

Convenience functions for use in SAX applications.

Module `xml.sax.xmlreader` (section 8.12):

Definitions of the interfaces for parser-provided objects.

8.9.1 SAXException Objects

The `SAXException` exception class supports the following methods:

getMessage()

Return a human-readable message describing the error condition.

getException()

Return an encapsulated exception object, or `None`.

8.10 `xml.sax.handler` — Base classes for SAX handlers

New in version 2.0.

The SAX API defines four kinds of handlers: content handlers, DTD handlers, error handlers, and entity resolvers. Applications normally only need to implement those interfaces whose events they are interested in; they can implement the interfaces in a single object or in multiple objects. Handler implementations should inherit from the base classes provided in the module `xml.sax.handler`, so that all methods get default implementations.

class ContentHandler

This is the main callback interface in SAX, and the one most important to applications. The order of events in this interface mirrors the order of the information in the document.

class DTDHandler

Handle DTD events.

This interface specifies only those DTD events required for basic parsing (unparsed entities and attributes).

class EntityResolver

Basic interface for resolving entities. If you create an object implementing this interface, then register the object with your Parser, the parser will call the method in your object to resolve all external entities.

class ErrorHandler

Interface used by the parser to present error and warning messages to the application. The methods of this object control whether errors are immediately converted to exceptions or are handled in some other way.

In addition to these classes, `xml.sax.handler` provides symbolic constants for the feature and property names.

feature_namespaces

Value: "http://xml.org/sax/features/namespaces"

true: Perform Namespace processing.

false: Optionally do not perform Namespace processing (implies namespace-prefixes; default).

access: (parsing) read-only; (not parsing) read/write

feature_namespace_prefixes

Value: "http://xml.org/sax/features/namespace-prefixes"

true: Report the original prefixed names and attributes used for Namespace declarations.

false: Do not report attributes used for Namespace declarations, and optionally do not report original prefixed names (default).

access: (parsing) read-only; (not parsing) read/write

feature_string_interning

Value: "http://xml.org/sax/features/string-interning"

true: All element names, prefixes, attribute names, Namespace URIs, and local names are interned using the built-in intern function.

false: Names are not necessarily interned, although they may be (default).

access: (parsing) read-only; (not parsing) read/write

feature_validation

Value: "http://xml.org/sax/features/validation"

true: Report all validation errors (implies external-general-entities and external-parameter-entities).

false: Do not report validation errors.

access: (parsing) read-only; (not parsing) read/write

feature_external_ges

Value: "http://xml.org/sax/features/external-general-entities"

true: Include all external general (text) entities.

false: Do not include external general entities.

access: (parsing) read-only; (not parsing) read/write

feature_external_pes

Value: "http://xml.org/sax/features/external-parameter-entities"

true: Include all external parameter entities, including the external DTD subset.

false: Do not include any external parameter entities, even the external DTD subset.

access: (parsing) read-only; (not parsing) read/write

all_features

List of all features.

property_lexical_handler

Value: "http://xml.org/sax/properties/lexical-handler"

data type: xml.sax.sax2lib.LexicalHandler (not supported in Python 2)

description: An optional extension handler for lexical events like comments.

access: read/write

property_declaration_handler

Value: "http://xml.org/sax/properties/declaration-handler"

data type: xml.sax.sax2lib.DeclHandler (not supported in Python 2)

description: An optional extension handler for DTD-related events other than notations and unparsed entities.

access: read/write

property_dom_node

Value: "http://xml.org/sax/properties/dom-node"

data type: org.w3c.dom.Node (not supported in Python 2)

description: When parsing, the current DOM node being visited if this is a DOM iterator; when not parsing, the root DOM node for iteration.

access: (parsing) read-only; (not parsing) read/write

property_xml_string

Value: "http://xml.org/sax/properties/xml-string"

data type: String

description: The literal string of characters that was the source for the current event.

access: read-only

all_properties

List of all known property names.

8.10.1 ContentHandler Objects

Users are expected to subclass `ContentHandler` to support their application. The following methods are called by the parser on the appropriate events in the input document:

setDocumentLocator (*locator*)

Called by the parser to give the application a locator for locating the origin of document events.

SAX parsers are strongly encouraged (though not absolutely required) to supply a locator: if it does so, it must supply the locator to the application by invoking this method before invoking any of the other methods in the `DocumentHandler` interface.

The locator allows the application to determine the end position of any document-related event, even if the parser is not reporting an error. Typically, the application will use this information for reporting its own errors (such as character content that does not match an application's business rules). The information returned by the locator is probably not sufficient for use with a search engine.

Note that the locator will return correct information only during the invocation of the events in this interface. The application should not attempt to use it at any other time.

startDocument ()

Receive notification of the beginning of a document.

The SAX parser will invoke this method only once, before any other methods in this interface or in `DTDHandler` (except for `setDocumentLocator()`).

endDocument ()

Receive notification of the end of a document.

The SAX parser will invoke this method only once, and it will be the last method invoked during the parse. The parser shall not invoke this method until it has either abandoned parsing (because of an unrecoverable error) or reached the end of input.

startPrefixMapping (*prefix*, *uri*)

Begin the scope of a prefix-URI Namespace mapping.

The information from this event is not necessary for normal Namespace processing: the SAX XML reader will automatically replace prefixes for element and attribute names when the `feature_namespaces` feature is enabled (the default).

There are cases, however, when applications need to use prefixes in character data or in attribute values, where they cannot safely be expanded automatically; the `startPrefixMapping()` and `endPrefixMapping()` events supply the information to the application to expand prefixes in those contexts itself, if necessary.

Note that `startPrefixMapping()` and `endPrefixMapping()` events are not guaranteed to be properly nested relative to each-other: all `startPrefixMapping()` events will occur before the corresponding `startElement()` event, and all `endPrefixMapping()` events will occur after the corresponding `endElement()` event, but their order is not guaranteed.

endPrefixMapping (*prefix*)

End the scope of a prefix-URI mapping.

See `startPrefixMapping()` for details. This event will always occur after the corresponding `endElement()` event, but the order of `endPrefixMapping()` events is not otherwise guaranteed.

startElement (*name*, *attrs*)

Signals the start of an element in non-namespace mode.

The *name* parameter contains the raw XML 1.0 name of the element type as a string and the *attrs* parameter holds an object of the [Attributes interface](#) containing the attributes of the element. The object passed as *attrs* may be re-used by the parser; holding on to a reference to it is not a reliable way to keep a copy of the attributes. To keep a copy of the attributes, use the `copy()` method of the *attrs* object.

endElement (*name*)

Signals the end of an element in non-namespace mode.

The *name* parameter contains the name of the element type, just as with the `startElement()` event.

startElementNS (*name*, *qname*, *attrs*)

Signals the start of an element in namespace mode.

The *name* parameter contains the name of the element type as a (*uri*, *localname*) tuple, the *qname* parameter contains the raw XML 1.0 name used in the source document, and the *attrs* parameter holds an instance of the [AttributesNS interface](#) containing the attributes of the element. If no namespace is associated with the element, the *uri* component of *name* will be `None`. The object passed as *attrs* may be re-used by the parser; holding on to a reference to it is not a reliable way to keep a copy of the attributes. To keep a copy of the attributes, use the `copy()` method of the *attrs* object.

Parsers may set the *qname* parameter to `None`, unless the `feature_namespace_prefixes` feature is activated.

endElementNS (*name*, *qname*)

Signals the end of an element in namespace mode.

The *name* parameter contains the name of the element type, just as with the `startElementNS()` method, likewise the *qname* parameter.

characters (*content*)

Receive notification of character data.

The Parser will call this method to report each chunk of character data. SAX parsers may return all contiguous character data in a single chunk, or they may split it into several chunks; however, all of the characters in any single event must come from the same external entity so that the Locator provides useful information.

content may be a Unicode string or a byte string; the `expat` reader module produces always Unicode strings.

Note: The earlier SAX 1 interface provided by the Python XML Special Interest Group used a more Java-like interface for this method. Since most parsers used from Python did not take advantage of the older interface, the simpler signature was chosen to replace it. To convert old code to the new interface, use *content* instead of slicing *content* with the old *offset* and *length* parameters.

ignorableWhitespace (*whitespace*)

Receive notification of ignorable whitespace in element content.

Validating Parsers must use this method to report each chunk of ignorable whitespace (see the W3C XML 1.0 recommendation, section 2.10): non-validating parsers may also use this method if they are capable of parsing and using content models.

SAX parsers may return all contiguous whitespace in a single chunk, or they may split it into several chunks; however, all of the characters in any single event must come from the same external entity, so that the Locator provides useful information.

processingInstruction (*target*, *data*)

Receive notification of a processing instruction.

The Parser will invoke this method once for each processing instruction found: note that processing instructions may occur before or after the main document element.

A SAX parser should never report an XML declaration (XML 1.0, section 2.8) or a text declaration (XML 1.0, section 4.3.1) using this method.

skippedEntity (*name*)

Receive notification of a skipped entity.

The Parser will invoke this method once for each entity skipped. Non-validating processors may skip entities if they have not seen the declarations (because, for example, the entity was declared in an external DTD subset). All processors may skip external entities, depending on the values of the `feature_external_ges` and the `feature_external_pes` properties.

8.10.2 DTDHandler Objects

DTDHandler instances provide the following methods:

notationDecl (*name*, *publicId*, *systemId*)

Handle a notation declaration event.

unparsedEntityDecl (*name*, *publicId*, *systemId*, *ndata*)

Handle an unparsed entity declaration event.

8.10.3 EntityResolver Objects

resolveEntity (*publicId*, *systemId*)

Resolve the system identifier of an entity and return either the system identifier to read from as a string, or an `InputSource` to read from. The default implementation returns *systemId*.

8.10.4 ErrorHandler Objects

Objects with this interface are used to receive error and warning information from the `XMLReader`. If you create an object that implements this interface, then register the object with your `XMLReader`, the parser will call the methods in your object to report all warnings and errors. There are three levels of errors available: warnings, (possibly) recoverable errors, and unrecoverable errors. All methods take a `SAXParseException` as the only parameter. Errors and warnings may be converted to an exception by raising the passed-in exception object.

error (*exception*)

Called when the parser encounters a recoverable error. If this method does not raise an exception, parsing may continue, but further document information should not be expected by the application. Allowing the parser to continue may allow additional errors to be discovered in the input document.

fatalError (*exception*)

Called when the parser encounters an error it cannot recover from; parsing is expected to terminate when this method returns.

warning (*exception*)

Called when the parser presents minor warning information to the application. Parsing is expected to continue when this method returns, and document information will continue to be passed to the application. Raising an exception in this method will cause parsing to end.

8.11 xml.sax.saxutils — SAX Utilities

New in version 2.0.

The module `xml.sax.saxutils` contains a number of classes and functions that are commonly useful when creating SAX applications, either in direct use, or as base classes.

escape (*data*[, *entities*])

Escape '&', '<', and '>' in a string of data.

You can escape other strings of data by passing a dictionary as the optional *entities* parameter. The keys and values must all be strings; each key will be replaced with its corresponding value.

unescape (*data*[, *entities*])

Unescape '&', '<', and '>' in a string of data.

You can unescape other strings of data by passing a dictionary as the optional *entities* parameter. The keys and values must all be strings; each key will be replaced with its corresponding value.

New in version 2.3.

quoteattr (*data*[, *entities*])

Similar to `escape()`, but also prepares *data* to be used as an attribute value. The return value is a quoted version of *data* with any additional required replacements. `quoteattr()` will select a quote character based on the content of *data*, attempting to avoid encoding any quote characters in the string. If both single- and double-quote characters are already in *data*, the double-quote characters will be encoded and *data* will be wrapped in double-quotes. The resulting string can be used directly as an attribute value:

```
>>> print "<element attr=%s>" % quoteattr("ab ' cd \" ef")
<element attr="ab ' cd &quot; ef">
```

This function is useful when generating attribute values for HTML or any SGML using the reference concrete syntax. New in version 2.2.

class XMLGenerator ([*out*[, *encoding*]])

This class implements the `ContentHandler` interface by writing SAX events back into an XML document. In other words, using an `XMLGenerator` as the content handler will reproduce the original document being parsed. *out* should be a file-like object which will default to `sys.stdout`. *encoding* is the encoding of the output stream which defaults to `'iso-8859-1'`.

class XMLFilterBase (*base*)

This class is designed to sit between an `XMLReader` and the client application's event handlers. By default, it does nothing but pass requests up to the reader and events on to the handlers unmodified, but subclasses can override specific methods to modify the event stream or the configuration requests as they pass through.

prepare_input_source (*source*[, *base*])

This function takes an input source and an optional base URL and returns a fully resolved `InputSource` object ready for reading. The input source can be given as a string, a file-like object, or an `InputSource` object; parsers will use this function to implement the polymorphic *source* argument to their `parse()` method.

8.12 xml.sax.xmlreader — Interface for XML parsers

New in version 2.0.

SAX parsers implement the `XMLReader` interface. They are implemented in a Python module, which must provide a function `create_parser()`. This function is invoked by `xml.sax.make_parser()` with no arguments to create a new parser object.

class XMLReader ()

Base class which can be inherited by SAX parsers.

class IncrementalParser ()

In some cases, it is desirable not to parse an input source at once, but to feed chunks of the document as they get available. Note that the reader will normally not read the entire file, but read it in chunks as well; still `parse()` won't return until the entire document is processed. So these interfaces should be used if the blocking behaviour of `parse()` is not desirable.

When the parser is instantiated it is ready to begin accepting data from the feed method immediately. After parsing has been finished with a call to close the reset method must be called to make the parser ready to accept new data, either from feed or using the parse method.

Note that these methods must *not* be called during parsing, that is, after parse has been called and before it returns.

By default, the class also implements the parse method of the XMLReader interface using the feed, close and reset methods of the IncrementalParser interface as a convenience to SAX 2.0 driver writers.

class Locator ()

Interface for associating a SAX event with a document location. A locator object will return valid results only during calls to DocumentHandler methods; at any other time, the results are unpredictable. If information is not available, methods may return None.

class InputSource ([systemId])

Encapsulation of the information needed by the XMLReader to read entities.

This class may include information about the public identifier, system identifier, byte stream (possibly with character encoding information) and/or the character stream of an entity.

Applications will create objects of this class for use in the XMLReader.parse() method and for returning from EntityResolver.resolveEntity.

An InputSource belongs to the application, the XMLReader is not allowed to modify InputSource objects passed to it from the application, although it may make copies and modify those.

class AttributesImpl (attrs)

This is an implementation of the [Attributes interface](#) (see section 8.12.5). This is a dictionary-like object which represents the element attributes in a startElement() call. In addition to the most useful dictionary operations, it supports a number of other methods as described by the interface. Objects of this class should be instantiated by readers; attrs must be a dictionary-like object containing a mapping from attribute names to attribute values.

class AttributesNSImpl (attrs, qnames)

Namespace-aware variant of AttributesImpl, which will be passed to startElementNS(). It is derived from AttributesImpl, but understands attribute names as two-tuples of namespaceURI and localname. In addition, it provides a number of methods expecting qualified names as they appear in the original document. This class implements the [AttributesNS interface](#) (see section 8.12.6).

8.12.1 XMLReader Objects

The XMLReader interface supports the following methods:

parse (source)

Process an input source, producing SAX events. The source object can be a system identifier (a string identifying the input source – typically a file name or an URL), a file-like object, or an InputSource object. When parse() returns, the input is completely processed, and the parser object can be discarded or reset. As a limitation, the current implementation only accepts byte streams; processing of character streams is for further study.

getContentHandler ()

Return the current ContentHandler.

setContentHandler (handler)

Set the current ContentHandler. If no ContentHandler is set, content events will be discarded.

getDTDHandler ()

Return the current DTDHandler.

setDTDHandler (handler)

Set the current DTDHandler. If no DTDHandler is set, DTD events will be discarded.

getEntityResolver()

Return the current `EntityResolver`.

setEntityResolver(handler)

Set the current `EntityResolver`. If no `EntityResolver` is set, attempts to resolve an external entity will result in opening the system identifier for the entity, and fail if it is not available.

getErrorHandler()

Return the current `ErrorHandler`.

setErrorHandler(handler)

Set the current error handler. If no `ErrorHandler` is set, errors will be raised as exceptions, and warnings will be printed.

setLocale(locale)

Allow an application to set the locale for errors and warnings.

SAX parsers are not required to provide localization for errors and warnings; if they cannot support the requested locale, however, they must throw a SAX exception. Applications may request a locale change in the middle of a parse.

getFeature(featurename)

Return the current setting for feature *featurename*. If the feature is not recognized, `SAXNotRecognizedException` is raised. The well-known featurenames are listed in the module `xml.sax.handler`.

setFeature(featurename, value)

Set the *featurename* to *value*. If the feature is not recognized, `SAXNotRecognizedException` is raised. If the feature or its setting is not supported by the parser, `SAXNotSupportedException` is raised.

getProperty(propertyname)

Return the current setting for property *propertyname*. If the property is not recognized, a `SAXNotRecognizedException` is raised. The well-known propertynames are listed in the module `xml.sax.handler`.

setProperty(propertyname, value)

Set the *propertyname* to *value*. If the property is not recognized, `SAXNotRecognizedException` is raised. If the property or its setting is not supported by the parser, `SAXNotSupportedException` is raised.

8.12.2 IncrementalParser Objects

Instances of `IncrementalParser` offer the following additional methods:

feed(data)

Process a chunk of *data*.

close()

Assume the end of the document. That will check well-formedness conditions that can be checked only at the end, invoke handlers, and may clean up resources allocated during parsing.

reset()

This method is called after `close` has been called to reset the parser so that it is ready to parse new documents. The results of calling `parse` or `feed` after `close` without calling `reset` are undefined.

8.12.3 Locator Objects

Instances of `Locator` provide these methods:

getColumnNumber()

Return the column number where the current event ends.

getLineNumber()

Return the line number where the current event ends.

getPublicId()

Return the public identifier for the current event.

getSystemId()

Return the system identifier for the current event.

8.12.4 InputSource Objects

setPublicId(*id*)

Sets the public identifier of this `InputSource`.

getPublicId()

Returns the public identifier of this `InputSource`.

setSystemId(*id*)

Sets the system identifier of this `InputSource`.

getSystemId()

Returns the system identifier of this `InputSource`.

setEncoding(*encoding*)

Sets the character encoding of this `InputSource`.

The encoding must be a string acceptable for an XML encoding declaration (see section 4.3.3 of the XML recommendation).

The encoding attribute of the `InputSource` is ignored if the `InputSource` also contains a character stream.

getEncoding()

Get the character encoding of this `InputSource`.

setByteStream(*bytefile*)

Set the byte stream (a Python file-like object which does not perform byte-to-character conversion) for this input source.

The SAX parser will ignore this if there is also a character stream specified, but it will use a byte stream in preference to opening a URI connection itself.

If the application knows the character encoding of the byte stream, it should set it with the `setEncoding` method.

getByteStream()

Get the byte stream for this input source.

The `getEncoding` method will return the character encoding for this byte stream, or `None` if unknown.

setCharacterStream(*charfile*)

Set the character stream for this input source. (The stream must be a Python 1.6 Unicode-wrapped file-like that performs conversion to Unicode strings.)

If there is a character stream specified, the SAX parser will ignore any byte stream and will not attempt to open a URI connection to the system identifier.

getCharacterStream()

Get the character stream for this input source.

8.12.5 The `Attributes` Interface

`Attributes` objects implement a portion of the mapping protocol, including the methods `copy()`, `get()`, `has_key()`, `items()`, `keys()`, and `values()`. The following methods are also provided:

`getLength()`

Return the number of attributes.

`getNames()`

Return the names of the attributes.

`getType(name)`

Returns the type of the attribute *name*, which is normally `'CDATA'`.

`getValue(name)`

Return the value of attribute *name*.

8.12.6 The `AttributesNS` Interface

This interface is a subtype of the [Attributes interface](#) (see section 8.12.5). All methods supported by that interface are also available on `AttributesNS` objects.

The following methods are also available:

`getValueByQName(name)`

Return the value for a qualified name.

`getNameByQName(name)`

Return the *(namespace, localname)* pair for a qualified *name*.

`getQNameByName(name)`

Return the qualified name for a *(namespace, localname)* pair.

`getQNames()`

Return the qualified names of all attributes.

8.13 `xml.etree.ElementTree` — The `ElementTree` XML API

New in version 2.5.

The `Element` type is a flexible container object, designed to store hierarchical data structures in memory. The type can be described as a cross between a list and a dictionary.

Each element has a number of properties associated with it:

- a tag which is a string identifying what kind of data this element represents (the element type, in other words).
- a number of attributes, stored in a Python dictionary.
- a text string.
- an optional tail string.
- a number of child elements, stored in a Python sequence

To create an element instance, use the `Element` or `SubElement` factory functions.

The `ElementTree` class can be used to wrap an element structure, and convert it from and to XML.

A C implementation of this API is available as `xml.etree.cElementTree`.

8.13.1 Functions

Comment (*[text]*)

Comment element factory. This factory function creates a special element that will be serialized as an XML comment. The comment string can be either an 8-bit ASCII string or a Unicode string. *text* is a string containing the comment string.

Returns:

An element instance, representing a comment.

dump (*elem*)

Writes an element tree or element structure to sys.stdout. This function should be used for debugging only.

The exact output format is implementation dependent. In this version, it's written as an ordinary XML file.

elem is an element tree or an individual element.

Element (*tag*, *attrib* [, ***extra*])

Element factory. This function returns an object implementing the standard Element interface. The exact class or type of that object is implementation dependent, but it will always be compatible with the `_ElementInterface` class in this module.

The element name, attribute names, and attribute values can be either 8-bit ASCII strings or Unicode strings. *tag* is the element name. *attrib* is an optional dictionary, containing element attributes. *extra* contains additional attributes, given as keyword arguments.

Returns:

An element instance.

fromstring (*text*)

Parses an XML section from a string constant. Same as `XML`. *text* is a string containing XML data.

Returns:

An Element instance.

iselement (*element*)

Checks if an object appears to be a valid element object. *element* is an element instance.

Returns:

A true value if this is an element object.

iterparse (*source* [, *events*])

Parses an XML section into an element tree incrementally, and reports what's going on to the user. *source* is a filename or file object containing XML data. *events* is a list of events to report back. If omitted, only "end" events are reported.

Returns:

A (event, elem) iterator.

parse (*source* [, *parser*])

Parses an XML section into an element tree. *source* is a filename or file object containing XML data. *parser* is an optional parser instance. If not given, the standard `XMLTreeBuilder` parser is used.

Returns:

An `ElementTree` instance

ProcessingInstruction (*target* [, *text*])

PI element factory. This factory function creates a special element that will be serialized as an XML processing instruction. *target* is a string containing the PI target. *text* is a string containing the PI contents, if given.

Returns:

An element instance, representing a PI.

SubElement (*parent*, *tag* [, *attrib*] [, ***extra*])

Subelement factory. This function creates an element instance, and appends it to an existing element.

The element name, attribute names, and attribute values can be either 8-bit ASCII strings or Unicode strings. *parent* is the parent element. *tag* is the subelement name. *attrib* is an optional dictionary, containing element attributes. *extra* contains additional attributes, given as keyword arguments.

Returns:

An element instance.

tostring (*element* [, *encoding*])

Generates a string representation of an XML element, including all subelements. *element* is an Element instance. *encoding* is the output encoding (default is US-ASCII).

Returns:

An encoded string containing the XML data.

XML (*text*)

Parses an XML section from a string constant. This function can be used to embed “XML literals” in Python code. *text* is a string containing XML data.

Returns:

An Element instance.

XMLID (*text*)

Parses an XML section from a string constant, and also returns a dictionary which maps from element id:s to elements. *text* is a string containing XML data.

Returns:

A tuple containing an Element instance and a dictionary.

8.13.2 ElementTree Objects

class ElementTree ([*element*,] [*file*])

ElementTree wrapper class. This class represents an entire element hierarchy, and adds some extra support for serialization to and from standard XML.

element is the root element. The tree is initialized with the contents of the XML *file* if given.

__setroot (*element*)

Replaces the root element for this tree. This discards the current contents of the tree, and replaces it with the given element. Use with care. *element* is an element instance.

find (*path*)

Finds the first toplevel element with given tag. Same as `getroot().find(path)`. *path* is the element to look for.

Returns:

The first matching element, or None if no element was found.

findall (*path*)

Finds all toplevel elements with the given tag. Same as `getroot().findall(path)`. *path* is the element to look for.

Returns:

A list or iterator containing all matching elements, in section order.

findtext (*path* [, *default*])

Finds the element text for the first toplevel element with given tag. Same as `getroot().findtext(path)`. *path* is the toplevel element to look for. *default* is the value to return if the element was not found.

Returns:

The text content of the first matching element, or the default value no element was found. Note that if the element has is found, but has no text content, this method returns an empty string.

getiterator ([*tag*])

Creates a tree iterator for the root element. The iterator loops over all elements in this tree, in section order. *tag* is the tag to look for (default is to return all elements)

Returns:

An iterator.

getroot ()

Gets the root element for this tree.

Returns:

An element instance.

parse (source[, parser])

Loads an external XML section into this element tree. *source* is a file name or file object. *parser* is an optional parser instance. If not given, the standard XMLTreeBuilder parser is used.

Returns:

The section root element.

write (file[, encoding])

Writes the element tree to a file, as XML. *file* is a file name, or a file object opened for writing. *encoding* is the output encoding (default is US-ASCII).

8.13.3 QName Objects

class QName (text_or_uri[, tag])

QName wrapper. This can be used to wrap a QName attribute value, in order to get proper namespace handling on output. *text_or_uri* is a string containing the QName value, in the form {uri}local, or, if the tag argument is given, the URI part of a QName. If *tag* is given, the first argument is interpreted as an URI, and this argument is interpreted as a local name.

Returns:

An opaque object, representing the QName.

8.13.4 TreeBuilder Objects

class TreeBuilder ([element_factory])

Generic element structure builder. This builder converts a sequence of start, data, and end method calls to a well-formed element structure. You can use this class to build an element structure using a custom XML parser, or a parser for some other XML-like format. The *element_factory* is called to create new Element instances when given.

close ()

Flushes the parser buffers, and returns the toplevel document element.

Returns:

An Element instance.

data (data)

Adds text to the current element. *data* is a string. This should be either an 8-bit string containing ASCII text, or a Unicode string.

end (tag)

Closes the current element. *tag* is the element name.

Returns:

The closed element.

start (tag, attrs)

Opens a new element. *tag* is the element name. *attrs* is a dictionary containing element attributes.

Returns:

The opened element.

8.13.5 XMLTreeBuilder Objects

class XMLTreeBuilder (*[html,]* *[target]*)

Element structure builder for XML source data, based on the expat parser. *html* are predefined HTML entities. This flag is not supported by the current implementation. *target* is the target object. If omitted, the builder uses an instance of the standard TreeBuilder class.

close ()

Finishes feeding data to the parser.

Returns:

An element structure.

doctype (*name, pubid, system*)

Handles a doctype declaration. *name* is the doctype name. *pubid* is the public identifier. *system* is the system identifier.

feed (*data*)

Feeds data to the parser.

data is encoded data.

File Formats

The modules described in this chapter parse various miscellaneous file formats that aren't markup languages or are related to e-mail.

<code>csv</code>	Write and read tabular data to and from delimited files.
<code>ConfigParser</code>	Configuration file parser.
<code>robotparser</code>	Loads a 'robots.txt' file and answers questions about fetchability of other URLs.
<code>netrc</code>	Loading of '.netrc' files.
<code>xdrlib</code>	Encoders and decoders for the External Data Representation (XDR).

9.1 `CSV` — CSV File Reading and Writing

New in version 2.3.

The so-called CSV (Comma Separated Values) format is the most common import and export format for spreadsheets and databases. There is no “CSV standard”, so the format is operationally defined by the many applications which read and write it. The lack of a standard means that subtle differences often exist in the data produced and consumed by different applications. These differences can make it annoying to process CSV files from multiple sources. Still, while the delimiters and quoting characters vary, the overall format is similar enough that it is possible to write a single module which can efficiently manipulate such data, hiding the details of reading and writing the data from the programmer.

The `csv` module implements classes to read and write tabular data in CSV format. It allows programmers to say, “write this data in the format preferred by Excel,” or “read data from this file which was generated by Excel,” without knowing the precise details of the CSV format used by Excel. Programmers can also describe the CSV formats understood by other applications or define their own special-purpose CSV formats.

The `csv` module's `reader` and `writer` objects read and write sequences. Programmers can also read and write data in dictionary form using the `DictReader` and `DictWriter` classes.

Note: This version of the `csv` module doesn't support Unicode input. Also, there are currently some issues regarding ASCII NUL characters. Accordingly, all input should be UTF-8 or printable ASCII to be safe; see the examples in section 9.1.5. These restrictions will be removed in the future.

See Also:

PEP 305, “*CSV File API*”

The Python Enhancement Proposal which proposed this addition to Python.

9.1.1 Module Contents

The `csv` module defines the following functions:

reader (*csvfile* [, *dialect*='excel'] [, *fmtparam*])

Return a reader object which will iterate over lines in the given *csvfile*. *csvfile* can be any object which supports the iterator protocol and returns a string each time its `next` method is called — file objects and list objects are both suitable. If *csvfile* is a file object, it must be opened with the 'b' flag on platforms where that makes a difference. An optional *dialect* parameter can be given which is used to define a set of parameters specific to a particular CSV dialect. It may be an instance of a subclass of the `Dialect` class or one of the strings returned by the `list_dialects` function. The other optional *fmtparam* keyword arguments can be given to override individual formatting parameters in the current dialect. For full details about the dialect and formatting parameters, see section 9.1.2, “Dialects and Formatting Parameters”.

All data read are returned as strings. No automatic data type conversion is performed.

Changed in version 2.5: The parser is now stricter with respect to multi-line quoted fields. Previously, if a line ended within a quoted field without a terminating newline character, a newline would be inserted into the returned field. This behavior caused problems when reading files which contained carriage return characters within fields. The behavior was changed to return the field without inserting newlines. As a consequence, if newlines embedded within fields are important, the input should be split into lines in a manner which preserves the newline characters.

writer (*csvfile* [, *dialect*='excel'] [, *fmtparam*])

Return a writer object responsible for converting the user's data into delimited strings on the given file-like object. *csvfile* can be any object with a `write` method. If *csvfile* is a file object, it must be opened with the 'b' flag on platforms where that makes a difference. An optional *dialect* parameter can be given which is used to define a set of parameters specific to a particular CSV dialect. It may be an instance of a subclass of the `Dialect` class or one of the strings returned by the `list_dialects` function. The other optional *fmtparam* keyword arguments can be given to override individual formatting parameters in the current dialect. For full details about the dialect and formatting parameters, see section 9.1.2, “Dialects and Formatting Parameters”. To make it as easy as possible to interface with modules which implement the DB API, the value `None` is written as the empty string. While this isn't a reversible transformation, it makes it easier to dump SQL NULL data values to CSV files without preprocessing the data returned from a `cursor.fetch*()` call. All other non-string data are stringified with `str()` before being written.

register_dialect (*name* [, *dialect*] [, *fmtparam*])

Associate *dialect* with *name*. *name* must be a string or Unicode object. The dialect can be specified either by passing a sub-class of `Dialect`, or by *fmtparam* keyword arguments, or both, with keyword arguments overriding parameters of the dialect. For full details about the dialect and formatting parameters, see section 9.1.2, “Dialects and Formatting Parameters”.

unregister_dialect (*name*)

Delete the dialect associated with *name* from the dialect registry. An `Error` is raised if *name* is not a registered dialect name.

get_dialect (*name*)

Return the dialect associated with *name*. An `Error` is raised if *name* is not a registered dialect name.

Changed in version 2.5: This function now returns an immutable `Dialect`. Previously an instance of the requested dialect was returned. Users could modify the underlying class, changing the behavior of active readers and writers..

list_dialects ()

Return the names of all registered dialects.

field_size_limit ([*new_limit*])

Returns the current maximum field size allowed by the parser. If *new_limit* is given, this becomes the new limit. New in version 2.5.

The `csv` module defines the following classes:

```
class DictReader (csvfile [, fieldnames=None [, restkey=None [, restval=None [, dialect='excel' [, *args,
**kws ] ] ] ] ])
```

Create an object which operates like a regular reader but maps the information read into a dict whose keys are given by the optional *fieldnames* parameter. If the *fieldnames* parameter is omitted, the values in the first row of the *csvfile* will be used as the fieldnames. If the row read has fewer fields than the fieldnames sequence, the value of *restval* will be used as the default value. If the row read has more fields than the fieldnames sequence, the remaining data is added as a sequence keyed by the value of *restkey*. If the row read has fewer fields than the fieldnames sequence, the remaining keys take the value of the optional *restval* parameter. Any other optional or keyword arguments are passed to the underlying reader instance.

```
class DictWriter(csvfile, fieldnames[], restval="", extrasaction='raise', dialect='excel', *args,
                  **kws)
```

Create an object which operates like a regular writer but maps dictionaries onto output rows. The *fieldnames* parameter identifies the order in which values in the dictionary passed to the `writerow()` method are written to the *csvfile*. The optional *restval* parameter specifies the value to be written if the dictionary is missing a key in *fieldnames*. If the dictionary passed to the `writerow()` method contains a key not found in *fieldnames*, the optional *extrasaction* parameter indicates what action to take. If it is set to 'raise' a `ValueError` is raised. If it is set to 'ignore', extra values in the dictionary are ignored. Any other optional or keyword arguments are passed to the underlying writer instance.

Note that unlike the `DictReader` class, the *fieldnames* parameter of the `DictWriter` is not optional. Since Python's dict objects are not ordered, there is not enough information available to deduce the order in which the row should be written to the *csvfile*.

class Dialect

The `Dialect` class is a container class relied on primarily for its attributes, which are used to define the parameters for a specific reader or writer instance.

class excel()

The `excel` class defines the usual properties of an Excel-generated CSV file. It is registered with the dialect name 'excel'.

class excel_tab()

The `excel_tab` class defines the usual properties of an Excel-generated TAB-delimited file. It is registered with the dialect name 'excel-tab'.

class Sniffer()

The `Sniffer` class is used to deduce the format of a CSV file.

The `Sniffer` class provides two methods:

sniff(*sample*[, *delimiters*=None])

Analyze the given *sample* and return a `Dialect` subclass reflecting the parameters found. If the optional *delimiters* parameter is given, it is interpreted as a string containing possible valid delimiter characters.

has_header(*sample*)

Analyze the sample text (presumed to be in CSV format) and return `True` if the first row appears to be a series of column headers.

The `csv` module defines the following constants:

QUOTE_ALL

Instructs writer objects to quote all fields.

QUOTE_MINIMAL

Instructs writer objects to only quote those fields which contain special characters such as *delimiter*, *quotechar* or any of the characters in *lineterminator*.

QUOTE_NONNUMERIC

Instructs writer objects to quote all non-numeric fields.

Instructs the reader to convert all non-quoted fields to type *float*.

QUOTE_NONE

Instructs `writer` objects to never quote fields. When the current *delimiter* occurs in output data it is preceded by the current *escapechar* character. If *escapechar* is not set, the writer will raise `Error` if any characters that require escaping are encountered.

Instructs `reader` to perform no special processing of quote characters.

The `csv` module defines the following exception:

exception `Error`

Raised by any of the functions when an error is detected.

9.1.2 Dialects and Formatting Parameters

To make it easier to specify the format of input and output records, specific formatting parameters are grouped together into dialects. A dialect is a subclass of the `Dialect` class having a set of specific methods and a single `validate()` method. When creating `reader` or `writer` objects, the programmer can specify a string or a subclass of the `Dialect` class as the dialect parameter. In addition to, or instead of, the *dialect* parameter, the programmer can also specify individual formatting parameters, which have the same names as the attributes defined below for the `Dialect` class.

Dialects support the following attributes:

`delimiter`

A one-character string used to separate fields. It defaults to `' , '`.

`doublequote`

Controls how instances of *quotechar* appearing inside a field should be themselves be quoted. When `True`, the character is doubled. When `False`, the *escapechar* is used as a prefix to the *quotechar*. It defaults to `True`.

On output, if *doublequote* is `False` and no *escapechar* is set, `Error` is raised if a *quotechar* is found in a field.

`escapechar`

A one-character string used by the writer to escape the *delimiter* if *quoting* is set to `QUOTE_NONE` and the *quotechar* if *doublequote* is `False`. On reading, the *escapechar* removes any special meaning from the following character. It defaults to `None`, which disables escaping.

`lineterminator`

The string used to terminate lines produced by the `writer`. It defaults to `' \r\n '`.

Note: The `reader` is hard-coded to recognise either `' \r '` or `' \n '` as end-of-line, and ignores *lineterminator*. This behavior may change in the future.

`quotechar`

A one-character string used to quote fields containing special characters, such as the *delimiter* or *quotechar*, or which contain new-line characters. It defaults to `' \" '`.

`quoting`

Controls when quotes should be generated by the writer and recognised by the reader. It can take on any of the `QUOTE_*` constants (see section 9.1.1) and defaults to `QUOTE_MINIMAL`.

`skipinitialspace`

When `True`, whitespace immediately following the *delimiter* is ignored. The default is `False`.

9.1.3 Reader Objects

Reader objects (`DictReader` instances and objects returned by the `reader()` function) have the following public methods:

`next()`

Return the next row of the reader's iterable object as a list, parsed according to the current dialect.

Reader objects have the following public attributes:

dialect

A read-only description of the dialect in use by the parser.

line_num

The number of lines read from the source iterator. This is not the same as the number of records returned, as records can span multiple lines. New in version 2.5.

9.1.4 Writer Objects

Writer objects (`DictWriter` instances and objects returned by the `writer()` function) have the following public methods. A *row* must be a sequence of strings or numbers for `Writer` objects and a dictionary mapping fieldnames to strings or numbers (by passing them through `str()` first) for `DictWriter` objects. Note that complex numbers are written out surrounded by parens. This may cause some problems for other programs which read CSV files (assuming they support complex numbers at all).

writerow (*row*)

Write the *row* parameter to the writer's file object, formatted according to the current dialect.

writerows (*rows*)

Write all the *rows* parameters (a list of *row* objects as described above) to the writer's file object, formatted according to the current dialect.

Writer objects have the following public attribute:

dialect

A read-only description of the dialect in use by the writer.

9.1.5 Examples

The simplest example of reading a CSV file:

```
import csv
reader = csv.reader(open("some.csv", "rb"))
for row in reader:
    print row
```

Reading a file with an alternate format:

```
import csv
reader = csv.reader(open("passwd", "rb"), delimiter=':', quoting=csv.QUOTE_NONE)
for row in reader:
    print row
```

The corresponding simplest possible writing example is:

```
import csv
writer = csv.writer(open("some.csv", "wb"))
writer.writerows(someiterable)
```

Registering a new dialect:

```
import csv

csv.register_dialect('unixpwd', delimiter=':', quoting=csv.QUOTE_NONE)

reader = csv.reader(open("passwd", "rb"), 'unixpwd')
```

A slightly more advanced use of the reader — catching and reporting errors:

```
import csv, sys
filename = "some.csv"
reader = csv.reader(open(filename, "rb"))
try:
    for row in reader:
        print row
except csv.Error, e:
    sys.exit('file %s, line %d: %s' % (filename, reader.line_num, e))
```

And while the module doesn't directly support parsing strings, it can easily be done:

```
import csv
for row in csv.reader(['one,two,three']):
    print row
```

The `csv` module doesn't directly support reading and writing Unicode, but it is 8-bit-clean save for some problems with ASCII NUL characters. So you can write functions or classes that handle the encoding and decoding for you as long as you avoid encodings like UTF-16 that use NULs. UTF-8 is recommended.

`unicode_csv_reader` below is a generator that wraps `csv.reader` to handle Unicode CSV data (a list of Unicode strings). `utf_8_encoder` is a generator that encodes the Unicode strings as UTF-8, one string (or row) at a time. The encoded strings are parsed by the CSV reader, and `unicode_csv_reader` decodes the UTF-8-encoded cells back into Unicode:

```
import csv

def unicode_csv_reader(unicode_csv_data, dialect=csv.excel, **kwargs):
    # csv.py doesn't do Unicode; encode temporarily as UTF-8:
    csv_reader = csv.reader(utf_8_encoder(unicode_csv_data),
                            dialect=dialect, **kwargs)
    for row in csv_reader:
        # decode UTF-8 back to Unicode, cell by cell:
        yield [unicode(cell, 'utf-8') for cell in row]

def utf_8_encoder(unicode_csv_data):
    for line in unicode_csv_data:
        yield line.encode('utf-8')
```

For all other encodings the following `UnicodeReader` and `UnicodeWriter` classes can be used. They take an additional *encoding* parameter in their constructor and make sure that the data passes the real reader or writer encoded as UTF-8:


```

import csv, codecs, cStringIO

class UTF8Recoder:
    """
    Iterator that reads an encoded stream and reencodes the input to UTF-8
    """
    def __init__(self, f, encoding):
        self.reader = codecs.getreader(encoding)(f)

    def __iter__(self):
        return self

    def next(self):
        return self.reader.next().encode("utf-8")

class UnicodeReader:
    """
    A CSV reader which will iterate over lines in the CSV file "f",
    which is encoded in the given encoding.
    """

    def __init__(self, f, dialect=csv.excel, encoding="utf-8", **kwds):
        f = UTF8Recoder(f, encoding)
        self.reader = csv.reader(f, dialect=dialect, **kwds)

    def next(self):
        row = self.reader.next()
        return [unicode(s, "utf-8") for s in row]

    def __iter__(self):
        return self

class UnicodeWriter:
    """
    A CSV writer which will write rows to CSV file "f",
    which is encoded in the given encoding.
    """

    def __init__(self, f, dialect=csv.excel, encoding="utf-8", **kwds):
        # Redirect output to a queue
        self.queue = cStringIO.StringIO()
        self.writer = csv.writer(self.queue, dialect=dialect, **kwds)
        self.stream = f
        self.encoder = codecs.getincrementalencoder(encoding)()

    def writerow(self, row):
        self.writer.writerow([s.encode("utf-8") for s in row])
        # Fetch UTF-8 output from the queue ...
        data = self.queue.getvalue()
        data = data.decode("utf-8")
        # ... and reencode it into the target encoding
        data = self.encoder.encode(data)
        # write to the target stream
        self.stream.write(data)
        # empty queue
        self.queue.truncate(0)

    def writerows(self, rows):
        for row in rows:
            self.writerow(row)

```

9.2 ConfigParser — Configuration file parser

This module defines the class `ConfigParser`. The `ConfigParser` class implements a basic configuration file parser language which provides a structure similar to what you would find on Microsoft Windows INI files. You can use this to write Python programs which can be customized by end users easily.

Warning: This library does *not* interpret or write the value-type prefixes used in the Windows Registry extended version of INI syntax.

The configuration file consists of sections, led by a `[section]` header and followed by `'name: value'` entries, with continuations in the style of RFC 822; `'name=value'` is also accepted. Note that leading whitespace is removed from values. The optional values can contain format strings which refer to other values in the same section, or values in a special `DEFAULT` section. Additional defaults can be provided on initialization and retrieval. Lines beginning with `#` or `;` are ignored and may be used to provide comments.

For example:

```
[My Section]
foodir: %(dir)s/whatever
dir=frob
```

would resolve the `%(dir)s` to the value of `'dir'` (`'frob'` in this case). All reference expansions are done on demand.

Default values can be specified by passing them into the `ConfigParser` constructor as a dictionary. Additional defaults may be passed into the `get()` method which will override all others.

class RawConfigParser (`[defaults]`)

The basic configuration object. When *defaults* is given, it is initialized into the dictionary of intrinsic defaults. This class does not support the magical interpolation behavior. New in version 2.3.

class ConfigParser (`[defaults]`)

Derived class of `RawConfigParser` that implements the magical interpolation feature and adds optional arguments to the `get()` and `items()` methods. The values in *defaults* must be appropriate for the `'%()s'` string interpolation. Note that `__name__` is an intrinsic default; its value is the section name, and will override any value provided in *defaults*.

All option names used in interpolation will be passed through the `optionxform()` method just like any other option name reference. For example, using the default implementation of `optionxform()` (which converts option names to lower case), the values `'foo %(bar)s'` and `'foo %(BAR)s'` are equivalent.

class SafeConfigParser (`[defaults]`)

Derived class of `ConfigParser` that implements a more-sane variant of the magical interpolation feature. This implementation is more predictable as well. New applications should prefer this version if they don't need to be compatible with older versions of Python. New in version 2.3.

exception NoSectionError

Exception raised when a specified section is not found.

exception DuplicateSectionError

Exception raised if `add_section()` is called with the name of a section that is already present.

exception NoOptionError

Exception raised when a specified option is not found in the specified section.

exception InterpolationError

Base class for exceptions raised when problems occur performing string interpolation.

exception InterpolationDepthError

Exception raised when string interpolation cannot be completed because the number of iterations exceeds `MAX_INTERPOLATION_DEPTH`. Subclass of `InterpolationError`.

exception InterpolationMissingOptionError

Exception raised when an option referenced from a value does not exist. Subclass of `InterpolationError`. New in version 2.3.

exception InterpolationSyntaxError

Exception raised when the source text into which substitutions are made does not conform to the required syntax. Subclass of `InterpolationError`. New in version 2.3.

exception MissingSectionHeaderError

Exception raised when attempting to parse a file which has no section headers.

exception ParsingError

Exception raised when errors occur attempting to parse a file.

MAX_INTERPOLATION_DEPTH

The maximum depth for recursive interpolation for `get()` when the *raw* parameter is false. This is relevant only for the `ConfigParser` class.

See Also:

[Module `shlex`](#) (section 22.2):

Support for creating UNIX shell-like mini-languages which can be used as an alternate format for application configuration files.

9.2.1 RawConfigParser Objects

`RawConfigParser` instances have the following methods:

defaults()

Return a dictionary containing the instance-wide defaults.

sections()

Return a list of the sections available; `DEFAULT` is not included in the list.

add_section(section)

Add a section named *section* to the instance. If a section by the given name already exists, `DuplicateSectionError` is raised.

has_section(section)

Indicates whether the named section is present in the configuration. The `DEFAULT` section is not acknowledged.

options(section)

Returns a list of options available in the specified *section*.

has_option(section, option)

If the given section exists, and contains the given option, return `True`; otherwise return `False`. New in version 1.6.

read(filenames)

Attempt to read and parse a list of filenames, returning a list of filenames which were successfully parsed. If *filenames* is a string or Unicode string, it is treated as a single filename. If a file named in *filenames* cannot be opened, that file will be ignored. This is designed so that you can specify a list of potential configuration file locations (for example, the current directory, the user's home directory, and some system-wide directory), and all existing configuration files in the list will be read. If none of the named files exist, the `ConfigParser`

instance will contain an empty dataset. An application which requires initial values to be loaded from a file should load the required file or files using `readfp()` before calling `read()` for any optional files:

```
import ConfigParser, os

config = ConfigParser.ConfigParser()
config.readfp(open('defaults.cfg'))
config.read(['site.cfg', os.path.expanduser('~/.myapp.cfg')])
```

Changed in version 2.4: Returns list of successfully parsed filenames.

readfp (*fp* [, *filename*])

Read and parse configuration data from the file or file-like object in *fp* (only the `readline()` method is used). If *filename* is omitted and *fp* has a `name` attribute, that is used for *filename*; the default is '<???'>.

get (*section*, *option*)

Get an *option* value for the named *section*.

getint (*section*, *option*)

A convenience method which coerces the *option* in the specified *section* to an integer.

getfloat (*section*, *option*)

A convenience method which coerces the *option* in the specified *section* to a floating point number.

getboolean (*section*, *option*)

A convenience method which coerces the *option* in the specified *section* to a Boolean value. Note that the accepted values for the option are "1", "yes", "true", and "on", which cause this method to return `True`, and "0", "no", "false", and "off", which cause it to return `False`. These string values are checked in a case-insensitive manner. Any other value will cause it to raise `ValueError`.

items (*section*)

Return a list of (*name*, *value*) pairs for each option in the given *section*.

set (*section*, *option*, *value*)

If the given section exists, set the given option to the specified value; otherwise raise `NoSectionError`. While it is possible to use `RawConfigParser` (or `ConfigParser` with *raw* parameters set to `true`) for *internal* storage of non-string values, full functionality (including interpolation and output to files) can only be achieved using string values. New in version 1.6.

write (*fileobject*)

Write a representation of the configuration to the specified file object. This representation can be parsed by a future `read()` call. New in version 1.6.

remove_option (*section*, *option*)

Remove the specified *option* from the specified *section*. If the section does not exist, raise `NoSectionError`. If the option existed to be removed, return `True`; otherwise return `False`. New in version 1.6.

remove_section (*section*)

Remove the specified *section* from the configuration. If the section in fact existed, return `True`. Otherwise return `False`.

optionxform (*option*)

Transforms the option name *option* as found in an input file or as passed in by client code to the form that should be used in the internal structures. The default implementation returns a lower-case version of *option*; subclasses may override this or client code can set an attribute of this name on instances to affect this behavior. Setting this to `str()`, for example, would make option names case sensitive.

9.2.2 ConfigParser Objects

The `ConfigParser` class extends some methods of the `RawConfigParser` interface, adding some optional arguments.

get (*section*, *option* [, *raw* [, *vars*]])

Get an *option* value for the named *section*. All the ‘%’ interpolations are expanded in the return values, based on the defaults passed into the constructor, as well as the options *vars* provided, unless the *raw* argument is true.

items (*section* [, *raw* [, *vars*]])

Return a list of (*name*, *value*) pairs for each option in the given *section*. Optional arguments have the same meaning as for the `get()` method. New in version 2.3.

9.2.3 SafeConfigParser Objects

The `SafeConfigParser` class implements the same extended interface as `ConfigParser`, with the following addition:

set (*section*, *option*, *value*)

If the given section exists, set the given option to the specified value; otherwise raise `NoSectionError`. *value* must be a string (str or unicode); if not, `TypeError` is raised. New in version 2.4.

9.3 robotparser — Parser for robots.txt

This module provides a single class, `RobotFileParser`, which answers questions about whether or not a particular user agent can fetch a URL on the Web site that published the ‘robots.txt’ file. For more details on the structure of ‘robots.txt’ files, see <http://www.robotstxt.org/wc/norobots.html>.

class RobotFileParser()

This class provides a set of methods to read, parse and answer questions about a single ‘robots.txt’ file.

set_url (*url*)

Sets the URL referring to a ‘robots.txt’ file.

read ()

Reads the ‘robots.txt’ URL and feeds it to the parser.

parse (*lines*)

Parses the lines argument.

can_fetch (*useragent*, *url*)

Returns `True` if the *useragent* is allowed to fetch the *url* according to the rules contained in the parsed ‘robots.txt’ file.

mtime ()

Returns the time the `robots.txt` file was last fetched. This is useful for long-running web spiders that need to check for new `robots.txt` files periodically.

modified ()

Sets the time the `robots.txt` file was last fetched to the current time.

The following example demonstrates basic use of the `RobotFileParser` class.

```

>>> import robotparser
>>> rp = robotparser.RobotFileParser()
>>> rp.set_url("http://www.musi-cal.com/robots.txt")
>>> rp.read()
>>> rp.can_fetch("*", "http://www.musi-cal.com/cgi-bin/search?city=San+Francisco")
False
>>> rp.can_fetch("*", "http://www.musi-cal.com/")
True

```

9.4 netrc — netrc file processing

New in version 1.5.2.

The `netrc` class parses and encapsulates the netrc file format used by the UNIX **ftp** program and other FTP clients.

class netrc (*[file]*)

A `netrc` instance or subclass instance encapsulates data from a netrc file. The initialization argument, if present, specifies the file to parse. If no argument is given, the file ‘.netrc’ in the user’s home directory will be read. Parse errors will raise `NetrcParseError` with diagnostic information including the file name, line number, and terminating token.

exception NetrcParseError

Exception raised by the `netrc` class when syntactical errors are encountered in source text. Instances of this exception provide three interesting attributes: `msg` is a textual explanation of the error, `filename` is the name of the source file, and `lineno` gives the line number on which the error was found.

9.4.1 netrc Objects

A `netrc` instance has the following methods:

authenticators (*host*)

Return a 3-tuple (*login*, *account*, *password*) of authenticators for *host*. If the netrc file did not contain an entry for the given host, return the tuple associated with the ‘default’ entry. If neither matching host nor default entry is available, return `None`.

__repr__ ()

Dump the class data as a string in the format of a netrc file. (This discards comments and may reorder the entries.)

Instances of `netrc` have public instance variables:

hosts

Dictionary mapping host names to (*login*, *account*, *password*) tuples. The ‘default’ entry, if any, is represented as a pseudo-host by that name.

macros

Dictionary mapping macro names to string lists.

Note: Passwords are limited to a subset of the ASCII character set. Versions of this module prior to 2.3 were extremely limited. Starting with 2.3, all ASCII punctuation is allowed in passwords. However, note that whitespace and non-printable characters are not allowed in passwords. This is a limitation of the way the .netrc file is parsed and may be removed in the future.

9.5 xdrlib — Encode and decode XDR data

The `xdrlib` module supports the External Data Representation Standard as described in RFC 1014, written by Sun Microsystems, Inc. June 1987. It supports most of the data types described in the RFC.

The `xdrlib` module defines two classes, one for packing variables into XDR representation, and another for unpacking from XDR representation. There are also two exception classes.

class Packer ()

`Packer` is the class for packing data into XDR representation. The `Packer` class is instantiated with no arguments.

class Unpacker (data)

`Unpacker` is the complementary class which unpacks XDR data values from a string buffer. The input buffer is given as *data*.

See Also:

RFC 1014, “XDR: External Data Representation Standard”

This RFC defined the encoding of data which was XDR at the time this module was originally written. It has apparently been obsoleted by RFC 1832.

RFC 1832, “XDR: External Data Representation Standard”

Newer RFC that provides a revised definition of XDR.

9.5.1 Packer Objects

`Packer` instances have the following methods:

get_buffer ()

Returns the current pack buffer as a string.

reset ()

Resets the pack buffer to the empty string.

In general, you can pack any of the most common XDR data types by calling the appropriate `pack_type ()` method. Each method takes a single argument, the value to pack. The following simple data type packing methods are supported: `pack_uint ()`, `pack_int ()`, `pack_enum ()`, `pack_bool ()`, `pack_uhyper ()`, and `pack_hyper ()`.

pack_float (value)

Packs the single-precision floating point number *value*.

pack_double (value)

Packs the double-precision floating point number *value*.

The following methods support packing strings, bytes, and opaque data:

pack_fstring (n, s)

Packs a fixed length string, *s*. *n* is the length of the string but it is *not* packed into the data buffer. The string is padded with null bytes if necessary to guaranteed 4 byte alignment.

pack_fopaque (n, data)

Packs a fixed length opaque data stream, similarly to `pack_fstring ()`.

pack_string (s)

Packs a variable length string, *s*. The length of the string is first packed as an unsigned integer, then the string data is packed with `pack_fstring ()`.

pack_opaque (data)

Packs a variable length opaque data string, similarly to `pack_string ()`.

pack_bytes (*bytes*)

Packs a variable length byte stream, similarly to `pack_string()`.

The following methods support packing arrays and lists:

pack_list (*list*, *pack_item*)

Packs a *list* of homogeneous items. This method is useful for lists with an indeterminate size; i.e. the size is not available until the entire list has been walked. For each item in the list, an unsigned integer 1 is packed first, followed by the data value from the list. *pack_item* is the function that is called to pack the individual item. At the end of the list, an unsigned integer 0 is packed.

For example, to pack a list of integers, the code might appear like this:

```
import xdrlib
p = xdrlib.Packer()
p.pack_list([1, 2, 3], p.pack_int)
```

pack_farray (*n*, *array*, *pack_item*)

Packs a fixed length list (*array*) of homogeneous items. *n* is the length of the list; it is *not* packed into the buffer, but a `ValueError` exception is raised if `len(array)` is not equal to *n*. As above, *pack_item* is the function used to pack each element.

pack_array (*list*, *pack_item*)

Packs a variable length *list* of homogeneous items. First, the length of the list is packed as an unsigned integer, then each element is packed as in `pack_farray()` above.

9.5.2 Unpacker Objects

The `Unpacker` class offers the following methods:

reset (*data*)

Resets the string buffer with the given *data*.

get_position ()

Returns the current unpack position in the data buffer.

set_position (*position*)

Sets the data buffer unpack position to *position*. You should be careful about using `get_position()` and `set_position()`.

get_buffer ()

Returns the current unpack data buffer as a string.

done ()

Indicates unpack completion. Raises an `Error` exception if all of the data has not been unpacked.

In addition, every data type that can be packed with a `Packer`, can be unpacked with an `Unpacker`. Unpacking methods are of the form `unpack_type()`, and take no arguments. They return the unpacked object.

unpack_float ()

Unpacks a single-precision floating point number.

unpack_double ()

Unpacks a double-precision floating point number, similarly to `unpack_float()`.

In addition, the following methods unpack strings, bytes, and opaque data:

unpack_fstring (*n*)

Unpacks and returns a fixed length string. *n* is the number of characters expected. Padding with null bytes to guaranteed 4 byte alignment is assumed.

unpack_fopaque (*n*)

Unpacks and returns a fixed length opaque data stream, similarly to `unpack_fstring()`.

unpack_string ()

Unpacks and returns a variable length string. The length of the string is first unpacked as an unsigned integer, then the string data is unpacked with `unpack_fstring()`.

unpack_opaque ()

Unpacks and returns a variable length opaque data string, similarly to `unpack_string()`.

unpack_bytes ()

Unpacks and returns a variable length byte stream, similarly to `unpack_string()`.

The following methods support unpacking arrays and lists:

unpack_list (*unpack_item*)

Unpacks and returns a list of homogeneous items. The list is unpacked one element at a time by first unpacking an unsigned integer flag. If the flag is 1, then the item is unpacked and appended to the list. A flag of 0 indicates the end of the list. *unpack_item* is the function that is called to unpack the items.

unpack_farray (*n*, *unpack_item*)

Unpacks and returns (as a list) a fixed length array of homogeneous items. *n* is number of list elements to expect in the buffer. As above, *unpack_item* is the function used to unpack each element.

unpack_array (*unpack_item*)

Unpacks and returns a variable length *list* of homogeneous items. First, the length of the list is unpacked as an unsigned integer, then each element is unpacked as in `unpack_farray()` above.

9.5.3 Exceptions

Exceptions in this module are coded as class instances:

exception Error

The base exception class. `Error` has a single public data member `msg` containing the description of the error.

exception ConversionError

Class derived from `Error`. Contains no additional instance variables.

Here is an example of how you would catch one of these exceptions:

```
import xdrlib
p = xdrlib.Packer()
try:
    p.pack_double(8.01)
except xdrlib.ConversionError, instance:
    print 'packing the double failed:', instance.msg
```

Cryptographic Services

The modules described in this chapter implement various algorithms of a cryptographic nature. They are available at the discretion of the installation. Here's an overview:

<code>hashlib</code>	Secure hash and message digest algorithms.
<code>hmac</code>	Keyed-Hashing for Message Authentication (HMAC) implementation for Python.
<code>md5</code>	RSA's MD5 message digest algorithm.
<code>sha</code>	NIST's secure hash algorithm, SHA.

Hardcore cypherpunks will probably find the cryptographic modules written by A.M. Kuchling of further interest; the package contains modules for various encryption algorithms, most notably AES. These modules are not distributed with Python but available separately. See the URL <http://www.amk.ca/python/code/crypto.html> for more information.

10.1 `hashlib` — Secure hashes and message digests

New in version 2.5.

This module implements a common interface to many different secure hash and message digest algorithms. Included are the FIPS secure hash algorithms SHA1, SHA224, SHA256, SHA384, and SHA512 (defined in FIPS 180-2) as well as RSA's MD5 algorithm (defined in Internet RFC 1321). The terms secure hash and message digest are interchangeable. Older algorithms were called message digests. The modern term is secure hash.

Warning: Some algorithms have known hash collision weaknesses, see the FAQ at the end.

There is one constructor method named for each type of *hash*. All return a hash object with the same simple interface. For example: use `sha1()` to create a SHA1 hash object. You can now feed this object with arbitrary strings using the `update()` method. At any point you can ask it for the *digest* of the concatenation of the strings fed to it so far using the `digest()` or `hexdigest()` methods.

Constructors for hash algorithms that are always present in this module are `md5()`, `sha1()`, `sha224()`, `sha256()`, `sha384()`, and `sha512()`. Additional algorithms may also be available depending upon the OpenSSL library that Python uses on your platform.

For example, to obtain the digest of the string 'Nobody inspects the spammish repetition':

```
>>> import hashlib
>>> m = hashlib.md5()
>>> m.update("Nobody inspects")
>>> m.update(" the spammish repetition")
>>> m.digest()
'\xbbd\x9c\x83\xdd\x1e\xa5\xc9\xd9\xde\xc9\xa1\x8d\xf0\xff\xe9'
```

More condensed:

```
>>> hashlib.sha224("Nobody inspects the spammish repetition").hexdigest()
'a4337bc45a8fc544c03f52dc550cd6e1e87021bc896588bd79e901e2'
```

A generic `new()` constructor that takes the string name of the desired algorithm as its first parameter also exists to allow access to the above listed hashes as well as any other algorithms that your OpenSSL library may offer. The named constructors are much faster than `new()` and should be preferred.

Using `new()` with an algorithm provided by OpenSSL:

```
>>> h = hashlib.new('ripemd160')
>>> h.update("Nobody inspects the spammish repetition")
>>> h.hexdigest()
'cc4a5c1b3df48aec5d22d1f16b894a0b894eccc'
```

The following values are provided as constant attributes of the hash objects returned by the constructors:

digest_size

The size of the resulting hash in bytes.

block_size

The internal block size of the hash algorithm in bytes.

A hash object has the following methods:

update(*arg*)

Update the hash object with the string *arg*. Repeated calls are equivalent to a single call with the concatenation of all the arguments: `m.update(a); m.update(b)` is equivalent to `m.update(a+b)`.

digest()

Return the digest of the strings passed to the `update()` method so far. This is a string of `digest_size` bytes which may contain non-ASCII characters, including null bytes.

hexdigest()

Like `digest()` except the digest is returned as a string of double length, containing only hexadecimal digits. This may be used to exchange the value safely in email or other non-binary environments.

copy()

Return a copy ("clone") of the hash object. This can be used to efficiently compute the digests of strings that share a common initial substring.

See Also:

[Module hmac](#) (section 10.2):

A module to generate message authentication codes using hashes.

[Module base64](#) (section 7.11):

Another way to encode binary hashes for non-binary environments.

<http://csrc.nist.gov/publications/fips/fips180-2/fips180-2.pdf>

The FIPS 180-2 publication on Secure Hash Algorithms.

<http://www.cryptography.com/cnews/hash.html>

Hash Collision FAQ with information on which algorithms have known issues and what that means regarding their use.

10.2 hmac — Keyed-Hashing for Message Authentication

New in version 2.2.

This module implements the HMAC algorithm as described by RFC 2104.

new (*key* [, *msg* [, *digestmod*]])

Return a new hmac object. If *msg* is present, the method call `update (msg)` is made. *digestmod* is the digest constructor or module for the HMAC object to use. It defaults to the `hashlib.md5` constructor. **Note:** The md5 hash has known weaknesses but remains the default for backwards compatibility. Choose a better one for your application.

An HMAC object has the following methods:

update (*msg*)

Update the hmac object with the string *msg*. Repeated calls are equivalent to a single call with the concatenation of all the arguments: `m.update (a) ; m.update (b)` is equivalent to `m.update (a + b)`.

digest ()

Return the digest of the strings passed to the `update ()` method so far. This string will be the same length as the *digest_size* of the digest given to the constructor. It may contain non-ASCII characters, including NUL bytes.

hexdigest ()

Like `digest ()` except the digest is returned as a string twice the length containing only hexadecimal digits. This may be used to exchange the value safely in email or other non-binary environments.

copy ()

Return a copy (“clone”) of the hmac object. This can be used to efficiently compute the digests of strings that share a common initial substring.

See Also:

Module `hashlib` (section 10.1):

The python module providing secure hash functions.

10.3 md5 — MD5 message digest algorithm

Deprecated since release 2.5. Use the `hashlib` module instead.

This module implements the interface to RSA’s MD5 message digest algorithm (see also Internet RFC 1321). Its use is quite straightforward: use `new ()` to create an md5 object. You can now feed this object with arbitrary strings using the `update ()` method, and at any point you can ask it for the *digest* (a strong kind of 128-bit checksum, a.k.a. “fingerprint”) of the concatenation of the strings fed to it so far using the `digest ()` method.

For example, to obtain the digest of the string ‘Nobody inspects the spammish repetition’:

```
>>> import md5
>>> m = md5.new()
>>> m.update("Nobody inspects")
>>> m.update(" the spammish repetition")
>>> m.digest()
'\xbbd\x9c\x83\xdd\x1e\xa5\xc9\xd9\xde\xc9\xa1\x8d\xf0\xff\xe9'
```

More condensed:

```
>>> md5.new("Nobody inspects the spammish repetition").digest()
'\xbbd\x9c\x83\xdd\x1e\xa5\xc9\xd9\xde\xc9\xa1\x8d\xf0\xff\xe9'
```

The following values are provided as constants in the module and as attributes of the md5 objects returned by `new()`:

digest_size

The size of the resulting digest in bytes. This is always 16.

The md5 module provides the following functions:

new([arg])

Return a new md5 object. If *arg* is present, the method call `update(arg)` is made.

md5([arg])

For backward compatibility reasons, this is an alternative name for the `new()` function.

An md5 object has the following methods:

update(arg)

Update the md5 object with the string *arg*. Repeated calls are equivalent to a single call with the concatenation of all the arguments: `m.update(a); m.update(b)` is equivalent to `m.update(a+b)`.

digest()

Return the digest of the strings passed to the `update()` method so far. This is a 16-byte string which may contain non-ASCII characters, including null bytes.

hexdigest()

Like `digest()` except the digest is returned as a string of length 32, containing only hexadecimal digits. This may be used to exchange the value safely in email or other non-binary environments.

copy()

Return a copy (“clone”) of the md5 object. This can be used to efficiently compute the digests of strings that share a common initial substring.

See Also:

[Module sha](#) (section 10.4):

Similar module implementing the Secure Hash Algorithm (SHA). The SHA algorithm is considered a more secure hash.

10.4 sha — SHA-1 message digest algorithm

Deprecated since release 2.5. Use the [hashlib](#) module instead.

This module implements the interface to NIST’s secure hash algorithm, known as SHA-1. SHA-1 is an improved version of the original SHA hash algorithm. It is used in the same way as the [md5](#) module: use `new()` to create an sha object, then feed this object with arbitrary strings using the `update()` method, and at any point you can ask it for the *digest* of the concatenation of the strings fed to it so far. SHA-1 digests are 160 bits instead of MD5’s 128 bits.

new([string])

Return a new sha object. If *string* is present, the method call `update(string)` is made.

The following values are provided as constants in the module and as attributes of the sha objects returned by `new()`:

blocksize

Size of the blocks fed into the hash function; this is always 1. This size is used to allow an arbitrary string to be hashed.

digest_size

The size of the resulting digest in bytes. This is always 20.

An sha object has the same methods as md5 objects:

update (*arg*)

Update the sha object with the string *arg*. Repeated calls are equivalent to a single call with the concatenation of all the arguments: `m.update(a) ; m.update(b)` is equivalent to `m.update(a+b)`.

digest ()

Return the digest of the strings passed to the `update()` method so far. This is a 20-byte string which may contain non-ASCII characters, including null bytes.

hexdigest ()

Like `digest()` except the digest is returned as a string of length 40, containing only hexadecimal digits. This may be used to exchange the value safely in email or other non-binary environments.

copy ()

Return a copy (“clone”) of the sha object. This can be used to efficiently compute the digests of strings that share a common initial substring.

See Also:

Secure Hash Standard

(<http://csrc.nist.gov/publications/fips/fips180-2/fips180-2withchangenotice.pdf>)

The Secure Hash Algorithm is defined by NIST document FIPS PUB 180-2: *Secure Hash Standard*, published in August 2002.

Cryptographic Toolkit (Secure Hashing)

(<http://csrc.nist.gov/encryption/tkhash.html>)

Links from NIST to various information on secure hashing.

File and Directory Access

The modules described in this chapter deal with disk files and directories. For example, there are modules for reading the properties of files, manipulating paths in a portable way, and creating temporary files. The full list of modules in this chapter is:

os.path	Common pathname manipulations.
fileinput	Perl-like iteration over lines from multiple input streams, with “save in place” capability.
stat	Utilities for interpreting the results of <code>os.stat()</code> , <code>os.lstat()</code> and <code>os.fstat()</code> .
statvfs	Constants for interpreting the result of <code>os.statvfs()</code> .
filecmp	Compare files efficiently.
tempfile	Generate temporary files and directories.
glob	UNIX shell style pathname pattern expansion.
fnmatch	UNIX shell style filename pattern matching.
linecache	This module provides random access to individual lines from text files.
shutil	High-level file operations, including copying.
dircache	Return directory listing, with cache mechanism.

Also see section 3.9 for a description of Python’s built-in file objects.

See Also:

Module `os` (section 14.1):

Operating system interfaces, including functions to work with files at a lower level than the built-in file object.

11.1 `os.path` — Common pathname manipulations

This module implements some useful functions on pathnames.

Warning: On Windows, many of these functions do not properly support UNC pathnames. `splitunc()` and `ismount()` do handle them correctly.

abspath (*path*)

Return a normalized absolutized version of the pathname *path*. On most platforms, this is equivalent to `normpath(join(os.getcwd(), path))`. New in version 1.5.2.

basename (*path*)

Return the base name of pathname *path*. This is the second half of the pair returned by `split(path)`. Note that the result of this function is different from the UNIX **basename** program; where **basename** for `‘/foo/bar/’` returns `‘bar’`, the `basename()` function returns an empty string (`‘’`).

commonprefix (*list*)

Return the longest path prefix (taken character-by-character) that is a prefix of all paths in *list*. If *list* is empty, return the empty string (`‘’`). Note that this may return invalid paths because it works a character at a time.

dirname (*path*)

Return the directory name of pathname *path*. This is the first half of the pair returned by `split (path)`.

exists (*path*)

Return `True` if *path* refers to an existing path. Returns `False` for broken symbolic links. On some platforms, this function may return `False` if permission is not granted to execute `os.stat()` on the requested file, even if the *path* physically exists.

lexists (*path*)

Return `True` if *path* refers to an existing path. Returns `True` for broken symbolic links. Equivalent to `exists()` on platforms lacking `os.lstat()`. New in version 2.4.

expanduser (*path*)

On UNIX, return the argument with an initial component of `'~'` or `'~user'` replaced by that *user*'s home directory. An initial `'~'` is replaced by the environment variable `HOME` if it is set; otherwise the current user's home directory is looked up in the password directory through the built-in module `pwd`. An initial `'~user'` is looked up directly in the password directory.

On Windows, only `'~'` is supported; it is replaced by the environment variable `HOME` or by a combination of `HOMEDRIVE` and `HOMEPATH`.

If the expansion fails or if the path does not begin with a tilde, the path is returned unchanged.

expandvars (*path*)

Return the argument with environment variables expanded. Substrings of the form `'$name'` or `'${name}'` are replaced by the value of environment variable *name*. Malformed variable names and references to non-existing variables are left unchanged.

getatime (*path*)

Return the time of last access of *path*. The return value is a number giving the number of seconds since the epoch (see the `time` module). Raise `os.error` if the file does not exist or is inaccessible. New in version 1.5.2. Changed in version 2.3: If `os.stat_float_times()` returns `True`, the result is a floating point number.

getmtime (*path*)

Return the time of last modification of *path*. The return value is a number giving the number of seconds since the epoch (see the `time` module). Raise `os.error` if the file does not exist or is inaccessible. New in version 1.5.2. Changed in version 2.3: If `os.stat_float_times()` returns `True`, the result is a floating point number.

getctime (*path*)

Return the system's ctime which, on some systems (like UNIX) is the time of the last change, and, on others (like Windows), is the creation time for *path*. The return value is a number giving the number of seconds since the epoch (see the `time` module). Raise `os.error` if the file does not exist or is inaccessible. New in version 2.3.

getsize (*path*)

Return the size, in bytes, of *path*. Raise `os.error` if the file does not exist or is inaccessible. New in version 1.5.2.

isabs (*path*)

Return `True` if *path* is an absolute pathname (begins with a slash).

isfile (*path*)

Return `True` if *path* is an existing regular file. This follows symbolic links, so both `islink()` and `isfile()` can be true for the same path.

isdir (*path*)

Return `True` if *path* is an existing directory. This follows symbolic links, so both `islink()` and `isdir()` can be true for the same path.

islink (*path*)

Return `True` if *path* refers to a directory entry that is a symbolic link. Always `False` if symbolic links are not supported.

ismount (*path*)

Return `True` if pathname *path* is a *mount point*: a point in a file system where a different file system has been mounted. The function checks whether *path*'s parent, '*path*../', is on a different device than *path*, or whether '*path*../' and *path* point to the same i-node on the same device — this should detect mount points for all UNIX and POSIX variants.

join (*path1* [, *path2* [, ...]])

Join one or more path components intelligently. If any component is an absolute path, all previous components (on Windows, including the previous drive letter, if there was one) are thrown away, and joining continues. The return value is the concatenation of *path1*, and optionally *path2*, etc., with exactly one directory separator (`os.sep`) inserted between components, unless *path2* is empty. Note that on Windows, since there is a current directory for each drive, `os.path.join("c:", "foo")` represents a path relative to the current directory on drive 'C:' ('c:foo'), not 'c:\\foo'.

normcase (*path*)

Normalize the case of a pathname. On UNIX, this returns the path unchanged; on case-insensitive filesystems, it converts the path to lowercase. On Windows, it also converts forward slashes to backward slashes.

normpath (*path*)

Normalize a pathname. This collapses redundant separators and up-level references so that `A//B`, `A/./B` and `A/foo/./B` all become `A/B`. It does not normalize the case (use `normcase()` for that). On Windows, it converts forward slashes to backward slashes. It should be understood that this may change the meaning of the path if it contains symbolic links!

realpath (*path*)

Return the canonical path of the specified filename, eliminating any symbolic links encountered in the path (if they are supported by the operating system). New in version 2.2.

samefile (*path1*, *path2*)

Return `True` if both pathname arguments refer to the same file or directory (as indicated by device number and i-node number). Raise an exception if a `os.stat()` call on either pathname fails. Availability: Macintosh, UNIX.

sameopenfile (*fp1*, *fp2*)

Return `True` if the file descriptors *fp1* and *fp2* refer to the same file. Availability: Macintosh, UNIX.

samestat (*stat1*, *stat2*)

Return `True` if the stat tuples *stat1* and *stat2* refer to the same file. These structures may have been returned by `fstat()`, `lstat()`, or `stat()`. This function implements the underlying comparison used by `samefile()` and `sameopenfile()`. Availability: Macintosh, UNIX.

split (*path*)

Split the pathname *path* into a pair, (*head*, *tail*) where *tail* is the last pathname component and *head* is everything leading up to that. The *tail* part will never contain a slash; if *path* ends in a slash, *tail* will be empty. If there is no slash in *path*, *head* will be empty. If *path* is empty, both *head* and *tail* are empty. Trailing slashes are stripped from *head* unless it is the root (one or more slashes only). In nearly all cases, `join(head, tail)` equals *path* (the only exception being when there were multiple slashes separating *head* from *tail*).

splitdrive (*path*)

Split the pathname *path* into a pair (*drive*, *tail*) where *drive* is either a drive specification or the empty string. On systems which do not use drive specifications, *drive* will always be the empty string. In all cases, *drive* + *tail* will be the same as *path*. New in version 1.3.

splitext (*path*)

Split the pathname *path* into a pair (*root*, *ext*) such that *root* + *ext* == *path*, and *ext* is empty or begins with a period and contains at most one period.

splitunc (*path*)

Split the pathname *path* into a pair (*unc*, *rest*) so that *unc* is the UNC mount point (such as `r'\\host\mount'`), if present, and *rest* the rest of the path (such as `r'\path\file.ext'`). For paths containing drive letters, *unc* will always be the empty string. Availability: Windows.

walk (*path*, *visit*, *arg*)

Calls the function *visit* with arguments (*arg*, *dirname*, *names*) for each directory in the directory tree rooted at *path* (including *path* itself, if it is a directory). The argument *dirname* specifies the visited directory, the argument *names* lists the files in the directory (gotten from `os.listdir(dirname)`). The *visit* function may modify *names* to influence the set of directories visited below *dirname*, e.g. to avoid visiting certain parts of the tree. (The object referred to by *names* must be modified in place, using `del` or slice assignment.)

Note: Symbolic links to directories are not treated as subdirectories, and that `walk()` therefore will not visit them. To visit linked directories you must identify them with `os.path.islink(file)` and `os.path.isdir(file)`, and invoke `walk()` as necessary.

Note: The newer `os.walk()` generator supplies similar functionality and can be easier to use.

supports_unicode_filenames

True if arbitrary Unicode strings can be used as file names (within limitations imposed by the file system), and if `os.listdir()` returns Unicode strings for a Unicode argument. New in version 2.3.

11.2 fileinput — Iterate over lines from multiple input streams

This module implements a helper class and functions to quickly write a loop over standard input or a list of files.

The typical use is:

```
import fileinput
for line in fileinput.input():
    process(line)
```

This iterates over the lines of all files listed in `sys.argv[1:]`, defaulting to `sys.stdin` if the list is empty. If a filename is `'-'`, it is also replaced by `sys.stdin`. To specify an alternative list of filenames, pass it as the first argument to `input()`. A single file name is also allowed.

All files are opened in text mode by default, but you can override this by specifying the *mode* parameter in the call to `input()` or `FileInput()`. If an I/O error occurs during opening or reading a file, `IOError` is raised.

If `sys.stdin` is used more than once, the second and further use will return no lines, except perhaps for interactive use, or if it has been explicitly reset (e.g. using `sys.stdin.seek(0)`).

Empty files are opened and immediately closed; the only time their presence in the list of filenames is noticeable at all is when the last file opened is empty.

It is possible that the last line of a file does not end in a newline character; lines are returned including the trailing newline when it is present.

You can control how files are opened by providing an opening hook via the *openhook* parameter to `input()` or `FileInput()`. The hook must be a function that takes two arguments, *filename* and *mode*, and returns an accordingly opened file-like object. Two useful hooks are already provided by this module.

The following function is the primary interface of this module:

input (*[files[, inplace[, backup[, mode[, openhook]]]]*)

Create an instance of the `FileInput` class. The instance will be used as global state for the functions of this module, and is also returned to use during iteration. The parameters to this function will be passed along to the constructor of the `FileInput` class.

Changed in version 2.5: Added the *mode* and *openhook* parameters.

The following functions use the global state created by `input()`; if there is no active state, `RuntimeError` is raised.

filename()

Return the name of the file currently being read. Before the first line has been read, returns `None`.

fileno()

Return the integer “file descriptor” for the current file. When no file is opened (before the first line and between files), returns `-1`. New in version 2.5.

lineno()

Return the cumulative line number of the line that has just been read. Before the first line has been read, returns `0`. After the last line of the last file has been read, returns the line number of that line.

filelineno()

Return the line number in the current file. Before the first line has been read, returns `0`. After the last line of the last file has been read, returns the line number of that line within the file.

isfirstline()

Returns true if the line just read is the first line of its file, otherwise returns false.

isstdin()

Returns true if the last line was read from `sys.stdin`, otherwise returns false.

nextfile()

Close the current file so that the next iteration will read the first line from the next file (if any); lines not read from the file will not count towards the cumulative line count. The filename is not changed until after the first line of the next file has been read. Before the first line has been read, this function has no effect; it cannot be used to skip the first file. After the last line of the last file has been read, this function has no effect.

close()

Close the sequence.

The class which implements the sequence behavior provided by the module is available for subclassing as well:

class FileInput (`[files[, inplace[, backup[, mode[, openhook]]]]`)

Class `FileInput` is the implementation; its methods `filename()`, `fileno()`, `lineno()`, `fileline()`, `isfirstline()`, `isstdin()`, `nextfile()` and `close()` correspond to the functions of the same name in the module. In addition it has a `readline()` method which returns the next input line, and a `__getitem__()` method which implements the sequence behavior. The sequence must be accessed in strictly sequential order; random access and `readline()` cannot be mixed.

With *mode* you can specify which file mode will be passed to `open()`. It must be one of `'r'`, `'rU'`, `'U'` and `'rb'`.

The *openhook*, when given, must be a function that takes two arguments, *filename* and *mode*, and returns an accordingly opened file-like object. You cannot use *inplace* and *openhook* together.

Changed in version 2.5: Added the *mode* and *openhook* parameters.

Optional in-place filtering: if the keyword argument *inplace*=1 is passed to `input()` or to the `FileInput` constructor, the file is moved to a backup file and standard output is directed to the input file (if a file of the same name as the backup file already exists, it will be replaced silently). This makes it possible to write a filter that rewrites its input file in place. If the keyword argument *backup*=`'<some extension>'` is also given, it specifies the extension for the backup file, and the backup file remains around; by default, the extension is `'<some extension>.bak'` and it is deleted when the output file is closed. In-place filtering is disabled when standard input is read.

Caveat: The current implementation does not work for MS-DOS 8+3 filesystems.

The two following opening hooks are provided by this module:

hook_compressed (*filename*, *mode*)

Transparently opens files compressed with gzip and bzip2 (recognized by the extensions `' .gz '` and `' .bz2 '`) using the `gzip` and `bz2` modules. If the filename extension is not `' .gz '` or `' .bz2 '`, the file is opened normally (ie, using `open()` without any decompression).

Usage example: `'fi = fileinput.FileInput(openhook=fileinput.hook_compressed)'`

New in version 2.5.

hook_encoded(*encoding*)

Returns a hook which opens each file with `codecs.open()`, using the given *encoding* to read the file.

Usage example: `'fi = fileinput.FileInput(openhook=fileinput.hook_encoded("iso-8859-1"))'`

Note: With this hook, `FileInput` might return Unicode strings depending on the specified *encoding*. New in version 2.5.

11.3 stat — Interpreting `stat()` results

The `stat` module defines constants and functions for interpreting the results of `os.stat()`, `os.fstat()` and `os.lstat()` (if they exist). For complete details about the `stat()`, `fstat()` and `lstat()` calls, consult the documentation for your system.

The `stat` module defines the following functions to test for specific file types:

S_ISDIR(*mode*)

Return non-zero if the mode is from a directory.

S_ISCHR(*mode*)

Return non-zero if the mode is from a character special device file.

S_ISBLK(*mode*)

Return non-zero if the mode is from a block special device file.

S_ISREG(*mode*)

Return non-zero if the mode is from a regular file.

S_ISFIFO(*mode*)

Return non-zero if the mode is from a FIFO (named pipe).

S_ISLNK(*mode*)

Return non-zero if the mode is from a symbolic link.

S_ISSOCK(*mode*)

Return non-zero if the mode is from a socket.

Two additional functions are defined for more general manipulation of the file's mode:

S_IMODE(*mode*)

Return the portion of the file's mode that can be set by `os.chmod()`—that is, the file's permission bits, plus the sticky bit, set-group-id, and set-user-id bits (on systems that support them).

S_IFMT(*mode*)

Return the portion of the file's mode that describes the file type (used by the `S_IS*()` functions above).

Normally, you would use the `os.path.is*()` functions for testing the type of a file; the functions here are useful when you are doing multiple tests of the same file and wish to avoid the overhead of the `stat()` system call for each test. These are also useful when checking for information about a file that isn't handled by `os.path`, like the tests for block and character devices.

All the variables below are simply symbolic indexes into the 10-tuple returned by `os.stat()`, `os.fstat()` or `os.lstat()`.

ST_MODE

Inode protection mode.

ST_INO

Inode number.

ST_DEV

Device inode resides on.

ST_NLINK

Number of links to the inode.

ST_UID

User id of the owner.

ST_GID

Group id of the owner.

ST_SIZE

Size in bytes of a plain file; amount of data waiting on some special files.

ST_ATIME

Time of last access.

ST_MTIME

Time of last modification.

ST_CTIME

The “ctime” as reported by the operating system. On some systems (like UNIX) is the time of the last metadata change, and, on others (like Windows), is the creation time (see platform documentation for details).

The interpretation of “file size” changes according to the file type. For plain files this is the size of the file in bytes. For FIFOs and sockets under most flavors of UNIX (including Linux in particular), the “size” is the number of bytes waiting to be read at the time of the call to `os.stat()`, `os.fstat()`, or `os.lstat()`; this can sometimes be useful, especially for polling one of these special files after a non-blocking open. The meaning of the size field for other character and block devices varies more, depending on the implementation of the underlying system call.

Example:

```

import os, sys
from stat import *

def walktree(top, callback):
    '''recursively descend the directory tree rooted at top,
       calling the callback function for each regular file'''

    for f in os.listdir(top):
        pathname = os.path.join(top, f)
        mode = os.stat(pathname)[ST_MODE]
        if S_ISDIR(mode):
            # It's a directory, recurse into it
            walktree(pathname, callback)
        elif S_ISREG(mode):
            # It's a file, call the callback function
            callback(pathname)
        else:
            # Unknown file type, print a message
            print 'Skipping %s' % pathname

def visitfile(file):
    print 'visiting', file

if __name__ == '__main__':
    walktree(sys.argv[1], visitfile)

```

11.4 statvfs — Constants used with `os.statvfs()`

The `statvfs` module defines constants so interpreting the result if `os.statvfs()`, which returns a tuple, can be made without remembering “magic numbers.” Each of the constants defined in this module is the *index* of the entry in the tuple returned by `os.statvfs()` that contains the specified information.

F_BSIZE

Preferred file system block size.

F_FRSIZE

Fundamental file system block size.

F_BLOCKS

Total number of blocks in the filesystem.

F_BFREE

Total number of free blocks.

F_BAVAIL

Free blocks available to non-super user.

F_FILES

Total number of file nodes.

F_FFREE

Total number of free file nodes.

F_FAVAIL

Free nodes available to non-super user.

F_FLAG

Flags. System dependent: see `statvfs()` man page.

F_NAMEMAX

Maximum file name length.

11.5 filecmp — File and Directory Comparisons

The `filecmp` module defines functions to compare files and directories, with various optional time/correctness trade-offs.

The `filecmp` module defines the following functions:

cmp (*f1*, *f2* [, *shallow*])

Compare the files named *f1* and *f2*, returning `True` if they seem equal, `False` otherwise.

Unless *shallow* is given and is false, files with identical `os.stat()` signatures are taken to be equal.

Files that were compared using this function will not be compared again unless their `os.stat()` signature changes.

Note that no external programs are called from this function, giving it portability and efficiency.

cmpfiles (*dir1*, *dir2*, *common* [, *shallow*])

Returns three lists of file names: *match*, *mismatch*, *errors*. *match* contains the list of files match in both directories, *mismatch* includes the names of those that don't, and *errors* lists the names of files which could not be compared. Files may be listed in *errors* because the user may lack permission to read them or many other reasons, but always that the comparison could not be done for some reason.

The *common* parameter is a list of file names found in both directories. The *shallow* parameter has the same meaning and default value as for `filecmp.cmp()`.

Example:

```
>>> import filecmp
>>> filecmp.cmp('libundoc.tex', 'libundoc.tex')
True
>>> filecmp.cmp('libundoc.tex', 'lib.tex')
False
```

11.5.1 The `dircmp` class

`dircmp` instances are built using this constructor:

class dircmp (*a*, *b* [, *ignore* [, *hide*]])

Construct a new directory comparison object, to compare the directories *a* and *b*. *ignore* is a list of names to ignore, and defaults to `['RCS', 'CVS', 'tags']`. *hide* is a list of names to hide, and defaults to `[os.curdir, os.pardir]`.

The `dircmp` class provides the following methods:

report ()

Print (to `sys.stdout`) a comparison between *a* and *b*.

report_partial_closure ()

Print a comparison between *a* and *b* and common immediate subdirectories.

report_full_closure()

Print a comparison between *a* and *b* and common subdirectories (recursively).

The `dircmp` offers a number of interesting attributes that may be used to get various bits of information about the directory trees being compared.

Note that via `__getattr__()` hooks, all attributes are computed lazily, so there is no speed penalty if only those attributes which are lightweight to compute are used.

left_list

Files and subdirectories in *a*, filtered by *hide* and *ignore*.

right_list

Files and subdirectories in *b*, filtered by *hide* and *ignore*.

common

Files and subdirectories in both *a* and *b*.

left_only

Files and subdirectories only in *a*.

right_only

Files and subdirectories only in *b*.

common_dirs

Subdirectories in both *a* and *b*.

common_files

Files in both *a* and *b*

common_funny

Names in both *a* and *b*, such that the type differs between the directories, or names for which `os.stat()` reports an error.

same_files

Files which are identical in both *a* and *b*.

diff_files

Files which are in both *a* and *b*, whose contents differ.

funny_files

Files which are in both *a* and *b*, but could not be compared.

subdirs

A dictionary mapping names in `common_dirs` to `dircmp` objects.

11.6 `tempfile` — Generate temporary files and directories

This module generates temporary files and directories. It works on all supported platforms.

In version 2.3 of Python, this module was overhauled for enhanced security. It now provides three new functions, `NamedTemporaryFile()`, `mkstemp()`, and `mkdtemp()`, which should eliminate all remaining need to use the insecure `mktemp()` function. Temporary file names created by this module no longer contain the process ID; instead a string of six random characters is used.

Also, all the user-callable functions now take additional arguments which allow direct control over the location and name of temporary files. It is no longer necessary to use the global `tempdir` and `template` variables. To maintain backward compatibility, the argument order is somewhat odd; it is recommended to use keyword arguments for clarity.

The module defines the following user-callable functions:

TemporaryFile(`[mode='w+b'[, bufsize=-1[, suffix[, prefix[, dir]]]]])`

Return a file (or file-like) object that can be used as a temporary storage area. The file is created using `mkstemp`. It will be destroyed as soon as it is closed (including an implicit close when the object is garbage collected). Under UNIX, the directory entry for the file is removed immediately after the file is created. Other platforms do not support this; your code should not rely on a temporary file created using this function having or not having a visible name in the file system.

The *mode* parameter defaults to `'w+b'` so that the file created can be read and written without being closed. Binary mode is used so that it behaves consistently on all platforms without regard for the data that is stored. *bufsize* defaults to `-1`, meaning that the operating system default is used.

The *dir*, *prefix* and *suffix* parameters are passed to `mkstemp()`.

NamedTemporaryFile (`[mode='w+b', bufsize=-1, suffix[, prefix[, dir]]]`)

This function operates exactly as `TemporaryFile()` does, except that the file is guaranteed to have a visible name in the file system (on UNIX, the directory entry is not unlinked). That name can be retrieved from the *name* member of the file object. Whether the name can be used to open the file a second time, while the named temporary file is still open, varies across platforms (it can be so used on UNIX; it cannot on Windows NT or later). New in version 2.3.

mkstemp (`[suffix[, prefix[, dir[, text]]]`)

Creates a temporary file in the most secure manner possible. There are no race conditions in the file's creation, assuming that the platform properly implements the `O_EXCL` flag for `os.open()`. The file is readable and writable only by the creating user ID. If the platform uses permission bits to indicate whether a file is executable, the file is executable by no one. The file descriptor is not inherited by child processes.

Unlike `TemporaryFile()`, the user of `mkstemp()` is responsible for deleting the temporary file when done with it.

If *suffix* is specified, the file name will end with that suffix, otherwise there will be no suffix. `mkstemp()` does not put a dot between the file name and the suffix; if you need one, put it at the beginning of *suffix*.

If *prefix* is specified, the file name will begin with that prefix; otherwise, a default prefix is used.

If *dir* is specified, the file will be created in that directory; otherwise, a default directory is used. The default directory is chosen from a platform-dependent list, but the user of the application can control the directory location by setting the `TMPDIR`, `TEMP` or `TMP` environment variables. There is thus no guarantee that the generated filename will have any nice properties, such as not requiring quoting when passed to external commands via `os.popen()`.

If *text* is specified, it indicates whether to open the file in binary mode (the default) or text mode. On some platforms, this makes no difference.

`mkstemp()` returns a tuple containing an OS-level handle to an open file (as would be returned by `os.open()`) and the absolute pathname of that file, in that order. New in version 2.3.

mkdtemp (`[suffix[, prefix[, dir]]]`)

Creates a temporary directory in the most secure manner possible. There are no race conditions in the directory's creation. The directory is readable, writable, and searchable only by the creating user ID.

The user of `mkdtemp()` is responsible for deleting the temporary directory and its contents when done with it.

The *prefix*, *suffix*, and *dir* arguments are the same as for `mkstemp()`.

`mkdtemp()` returns the absolute pathname of the new directory. New in version 2.3.

mktemp (`[suffix[, prefix[, dir]]]`)

Deprecated since release 2.3. Use `mkstemp()` instead.

Return an absolute pathname of a file that did not exist at the time the call is made. The *prefix*, *suffix*, and *dir* arguments are the same as for `mkstemp()`.

Warning: Use of this function may introduce a security hole in your program. By the time you get around to doing anything with the file name it returns, someone else may have beaten you to the punch.

The module uses two global variables that tell it how to construct a temporary name. They are initialized at the first call to any of the functions above. The caller may change them, but this is discouraged; use the appropriate function arguments, instead.

tempdir

When set to a value other than `None`, this variable defines the default value for the *dir* argument to all the functions defined in this module.

If `tempdir` is unset or `None` at any call to any of the above functions, Python searches a standard list of directories and sets *tempdir* to the first one which the calling user can create files in. The list is:

- 1.The directory named by the `TMPDIR` environment variable.
- 2.The directory named by the `TEMP` environment variable.
- 3.The directory named by the `TMP` environment variable.
- 4.A platform-specific location:
 - On RiscOS, the directory named by the `Wimp$ScrapDir` environment variable.
 - On Windows, the directories `'C:\TEMP'`, `'C:\TMP'`, `'\TEMP'`, and `'\TMP'`, in that order.
 - On all other platforms, the directories `'/tmp'`, `'/var/tmp'`, and `'/usr/tmp'`, in that order.
- 5.As a last resort, the current working directory.

gettempdir()

Return the directory currently selected to create temporary files in. If `tempdir` is not `None`, this simply returns its contents; otherwise, the search described above is performed, and the result returned.

template

Deprecated since release 2.0. Use `gettempprefix()` instead.

When set to a value other than `None`, this variable defines the prefix of the final component of the filenames returned by `mktemp()`. A string of six random letters and digits is appended to the prefix to make the filename unique. On Windows, the default prefix is `'T'`; on all other systems it is `'tmp'`.

Older versions of this module used to require that `template` be set to `None` after a call to `os.fork()`; this has not been necessary since version 1.5.2.

gettempprefix()

Return the filename prefix used to create temporary files. This does not contain the directory component. Using this function is preferred over reading the *template* variable directly. New in version 1.5.2.

11.7 glob — UNIX style pathname pattern expansion

The `glob` module finds all the pathnames matching a specified pattern according to the rules used by the UNIX shell. No tilde expansion is done, but `*`, `?`, and character ranges expressed with `[]` will be correctly matched. This is done by using the `os.listdir()` and `fnmatch.fnmatch()` functions in concert, and not by actually invoking a subshell. (For tilde and shell variable expansion, use `os.path.expanduser()` and `os.path.expandvars()`.)

glob(pathname)

Return a possibly-empty list of path names that match *pathname*, which must be a string containing a path specification. *pathname* can be either absolute (like `'/usr/src/Python-1.5/Makefile'`) or relative (like `'../Tools/*/*.gif'`), and can contain shell-style wildcards. Broken symlinks are included in the results (as in the shell).

iglob(pathname)

Return an iterator which yields the same values as `glob()` without actually storing them all simultaneously. New in version 2.5.

For example, consider a directory containing only the following files: `'1.gif'`, `'2.txt'`, and `'card.gif'`. `glob()` will produce the following results. Notice how any leading components of the path are preserved.

```
>>> import glob
>>> glob.glob('./[0-9].*')
['./1.gif', './2.txt']
>>> glob.glob('*.gif')
['1.gif', 'card.gif']
>>> glob.glob('?.gif')
['1.gif']
```

See Also:

Module [fnmatch](#) (section 11.8):

Shell-style filename (not path) expansion

11.8 fnmatch — UNIX filename pattern matching

This module provides support for UNIX shell-style wildcards, which are *not* the same as regular expressions (which are documented in the [re](#) module). The special characters used in shell-style wildcards are:

Pattern	Meaning
*	matches everything
?	matches any single character
[<i>seq</i>]	matches any character in <i>seq</i>
[! <i>seq</i>]	matches any character not in <i>seq</i>

Note that the filename separator ('/' on UNIX) is *not* special to this module. See module [glob](#) for pathname expansion ([glob](#) uses `fnmatch()` to match pathname segments). Similarly, filenames starting with a period are not special for this module, and are matched by the * and ? patterns.

fnmatch (*filename*, *pattern*)

Test whether the *filename* string matches the *pattern* string, returning true or false. If the operating system is case-insensitive, then both parameters will be normalized to all lower- or upper-case before the comparison is performed. If you require a case-sensitive comparison regardless of whether that's standard for your operating system, use `fnmatchcase()` instead.

This example will print all file names in the current directory with the extension `.txt`:

```
import fnmatch
import os

for file in os.listdir('.'):
    if fnmatch.fnmatch(file, '*.txt'):
        print file
```

fnmatchcase (*filename*, *pattern*)

Test whether *filename* matches *pattern*, returning true or false; the comparison is case-sensitive.

filter (*names*, *pattern*)

Return the subset of the list of *names* that match *pattern*. It is the same as `[n for n in names if fnmatch(n, pattern)]`, but implemented more efficiently. New in version 2.2.

translate (*pattern*)

Return the shell-style *pattern* converted to a regular expression.

Example:

```
>>> import fnmatch, re
>>>
>>> regex = fnmatch.translate('*.txt')
>>> regex
'.*\\.txt$'
>>> reobj = re.compile(regex)
>>> print reobj.match('foobar.txt')
<_sre.SRE_Match object at 0x...>
```

See Also:

[Module glob](#) (section 11.7):

UNIX shell-style path expansion.

11.9 linecache — Random access to text lines

The `linecache` module allows one to get any line from any file, while attempting to optimize internally, using a cache, the common case where many lines are read from a single file. This is used by the [traceback](#) module to retrieve source lines for inclusion in the formatted traceback.

The `linecache` module defines the following functions:

getline (*filename*, *lineno* [, *module_globals*])

Get line *lineno* from file named *filename*. This function will never throw an exception — it will return '' on errors (the terminating newline character will be included for lines that are found).

If a file named *filename* is not found, the function will look for it in the module search path, `sys.path`, after first checking for a PEP 302 `__loader__` in *module_globals*, in case the module was imported from a zipfile or other non-filesystem import source.

New in version 2.5: The *module_globals* parameter was added.

clearcache ()

Clear the cache. Use this function if you no longer need lines from files previously read using `getline()`.

checkcache ([*filename*])

Check the cache for validity. Use this function if files in the cache may have changed on disk, and you require the updated version. If *filename* is omitted, it will check all the entries in the cache.

Example:

```
>>> import linecache
>>> linecache getline('/etc/passwd', 4)
'sys:x:3:3:sys:/dev:/bin/sh\n'
```

11.10 shutil — High-level file operations

The `shutil` module offers a number of high-level operations on files and collections of files. In particular, functions are provided which support file copying and removal.

Caveat: On MacOS, the resource fork and other metadata are not used. For file copies, this means that resources will be lost and file type and creator codes will not be correct.

copyfile (*src*, *dst*)

Copy the contents of the file named *src* to a file named *dst*. The destination location must be writable; otherwise, an `IOError` exception will be raised. If *dst* already exists, it will be replaced. Special files such as character or block devices and pipes cannot be copied with this function. *src* and *dst* are path names given as strings.

copyfileobj (*fsrc*, *fdst* [, *length*])

Copy the contents of the file-like object *fsrc* to the file-like object *fdst*. The integer *length*, if given, is the buffer size. In particular, a negative *length* value means to copy the data without looping over the source data in chunks; by default the data is read in chunks to avoid uncontrolled memory consumption. Note that if the current file position of the *fsrc* object is not 0, only the contents from the current file position to the end of the file will be copied.

copymode (*src*, *dst*)

Copy the permission bits from *src* to *dst*. The file contents, owner, and group are unaffected. *src* and *dst* are path names given as strings.

copystat (*src*, *dst*)

Copy the permission bits, last access time, and last modification time from *src* to *dst*. The file contents, owner, and group are unaffected. *src* and *dst* are path names given as strings.

copy (*src*, *dst*)

Copy the file *src* to the file or directory *dst*. If *dst* is a directory, a file with the same basename as *src* is created (or overwritten) in the directory specified. Permission bits are copied. *src* and *dst* are path names given as strings.

copy2 (*src*, *dst*)

Similar to `copy()`, but last access time and last modification time are copied as well. This is similar to the UNIX command `cp -p`.

copytree (*src*, *dst* [, *symlinks*])

Recursively copy an entire directory tree rooted at *src*. The destination directory, named by *dst*, must not already exist; it will be created as well as missing parent directories. Permissions and times of directories are copied with `copystat()`, individual files are copied using `copy2()`. If *symlinks* is true, symbolic links in the source tree are represented as symbolic links in the new tree; if false or omitted, the contents of the linked files are copied to the new tree. If exception(s) occur, an `Error` is raised with a list of reasons.

The source code for this should be considered an example rather than a tool.

Changed in version 2.3: `Error` is raised if any exceptions occur during copying, rather than printing a message.

Changed in version 2.5: Create intermediate directories needed to create *dst*, rather than raising an error. Copy permissions and times of directories using `copystat()`.

rmtree (*path* [, *ignore_errors* [, *onerror*]])

Delete an entire directory tree (*path* must point to a directory). If *ignore_errors* is true, errors resulting from failed removals will be ignored; if false or omitted, such errors are handled by calling a handler specified by *onerror* or, if that is omitted, they raise an exception.

If *onerror* is provided, it must be a callable that accepts three parameters: *function*, *path*, and *excinfo*. The first parameter, *function*, is the function which raised the exception; it will be `os.listdir()`, `os.remove()` or `os.rmdir()`. The second parameter, *path*, will be the path name passed to *function*. The third parameter, *excinfo*, will be the exception information return by `sys.exc_info()`. Exceptions raised by *onerror* will not be caught.

move (*src*, *dst*)

Recursively move a file or directory to another location.

If the destination is on our current filesystem, then simply use `rename`. Otherwise, copy *src* to the *dst* and then remove *src*.

New in version 2.3.

exception Error

This exception collects exceptions that raised during a mult-file operation. For `copytree`, the exception argument is a list of 3-tuples (*srcname*, *dstname*, *exception*).

New in version 2.3.

11.10.1 Example

This example is the implementation of the `copytree()` function, described above, with the docstring omitted. It demonstrates many of the other functions provided by this module.

```
def copytree(src, dst, symlinks=0):
    names = os.listdir(src)
    os.mkdir(dst)
    for name in names:
        srcname = os.path.join(src, name)
        dstname = os.path.join(dst, name)
        try:
            if symlinks and os.path.islink(srcname):
                linkto = os.readlink(srcname)
                os.symlink(linkto, dstname)
            elif os.path.isdir(srcname):
                copytree(srcname, dstname, symlinks)
            else:
                copy2(srcname, dstname)
        except (IOError, os.error), why:
            print "Can't copy %s to %s: %s" % ('srcname', 'dstname', str(why))
```

11.11 dircache — Cached directory listings

The `dircache` module defines a function for reading directory listing using a cache, and cache invalidation using the *mtime* of the directory. Additionally, it defines a function to annotate directories by appending a slash.

The `dircache` module defines the following functions:

reset()

Resets the directory cache.

listdir(path)

Return a directory listing of *path*, as gotten from `os.listdir()`. Note that unless *path* changes, further call to `listdir()` will not re-read the directory structure.

Note that the list returned should be regarded as read-only. (Perhaps a future version should change it to return a tuple?)

opendir(path)

Same as `listdir()`. Defined for backwards compatibility.

annotate(head, list)

Assume *list* is a list of paths relative to *head*, and append, in place, a `'/'` to each path which points to a directory.


```

>>> import dircache
>>> a = dircache.listdir('/')
>>> a = a[:] # Copy the return value so we can change 'a'
>>> a
['bin', 'boot', 'cdrom', 'dev', 'etc', 'floppy', 'home', 'initrd', 'lib', 'lost+
found', 'mnt', 'proc', 'root', 'sbin', 'tmp', 'usr', 'var', 'vmlinuz']
>>> dircache.annotate('/', a)
>>> a
['bin/', 'boot/', 'cdrom/', 'dev/', 'etc/', 'floppy/', 'home/', 'initrd/', 'lib/
', 'lost+found/', 'mnt/', 'proc/', 'root/', 'sbin/', 'tmp/', 'usr/', 'var/', 'vm
linuz']

```


Data Compression and Archiving

The modules described in this chapter support data compression with the `zlib`, `gzip`, and `bzip2` algorithms, and the creation of ZIP- and tar-format archives.

<code>zlib</code>	Low-level interface to compression and decompression routines compatible with gzip .
<code>gzip</code>	Interfaces for gzip compression and decompression using file objects.
<code>bz2</code>	Interface to compression and decompression routines compatible with bzip2 .
<code>zipfile</code>	Read and write ZIP-format archive files.
<code>tarfile</code>	Read and write tar-format archive files.

12.1 `zlib` — Compression compatible with **gzip**

For applications that require data compression, the functions in this module allow compression and decompression, using the `zlib` library. The `zlib` library has its own home page at <http://www.zlib.net>. There are known incompatibilities between the Python module and versions of the `zlib` library earlier than 1.1.3; 1.1.3 has a security vulnerability, so we recommend using 1.1.4 or later.

`zlib`'s functions have many options and often need to be used in a particular order. This documentation doesn't attempt to cover all of the permutations; consult the `zlib` manual at <http://www.zlib.net/manual.html> for authoritative information.

The available exception and functions in this module are:

exception error

Exception raised on compression and decompression errors.

adler32 (*string* [, *value*])

Computes a Adler-32 checksum of *string*. (An Adler-32 checksum is almost as reliable as a CRC32 but can be computed much more quickly.) If *value* is present, it is used as the starting value of the checksum; otherwise, a fixed default value is used. This allows computing a running checksum over the concatenation of several input strings. The algorithm is not cryptographically strong, and should not be used for authentication or digital signatures. Since the algorithm is designed for use as a checksum algorithm, it is not suitable for use as a general hash algorithm.

compress (*string* [, *level*])

Compresses the data in *string*, returning a string contained compressed data. *level* is an integer from 1 to 9 controlling the level of compression; 1 is fastest and produces the least compression, 9 is slowest and produces the most. The default value is 6. Raises the `error` exception if any error occurs.

compressobj ([*level*])

Returns a compression object, to be used for compressing data streams that won't fit into memory at once. *level* is an integer from 1 to 9 controlling the level of compression; 1 is fastest and produces the least compression, 9 is slowest and produces the most. The default value is 6.

crc32 (*string* [, *value*])

Computes a CRC (Cyclic Redundancy Check) checksum of *string*. If *value* is present, it is used as the starting value of the checksum; otherwise, a fixed default value is used. This allows computing a running checksum over the concatenation of several input strings. The algorithm is not cryptographically strong, and should not be used for authentication or digital signatures. Since the algorithm is designed for use as a checksum algorithm, it is not suitable for use as a general hash algorithm.

decompress (*string* [, *wbits* [, *bufsize*]])

Decompresses the data in *string*, returning a string containing the uncompressed data. The *wbits* parameter controls the size of the window buffer. If *bufsize* is given, it is used as the initial size of the output buffer. Raises the `error` exception if any error occurs.

The absolute value of *wbits* is the base two logarithm of the size of the history buffer (the “window size”) used when compressing data. Its absolute value should be between 8 and 15 for the most recent versions of the zlib library, larger values resulting in better compression at the expense of greater memory usage. The default value is 15. When *wbits* is negative, the standard **gzip** header is suppressed; this is an undocumented feature of the zlib library, used for compatibility with **unzip**’s compression file format.

bufsize is the initial size of the buffer used to hold decompressed data. If more space is required, the buffer size will be increased as needed, so you don’t have to get this value exactly right; tuning it will only save a few calls to `malloc()`. The default size is 16384.

decompressobj ([*wbits*])

Returns a decompression object, to be used for decompressing data streams that won’t fit into memory at once. The *wbits* parameter controls the size of the window buffer.

Compression objects support the following methods:

compress (*string*)

Compress *string*, returning a string containing compressed data for at least part of the data in *string*. This data should be concatenated to the output produced by any preceding calls to the `compress()` method. Some input may be kept in internal buffers for later processing.

flush ([*mode*])

All pending input is processed, and a string containing the remaining compressed output is returned. *mode* can be selected from the constants `Z_SYNC_FLUSH`, `Z_FULL_FLUSH`, or `Z_FINISH`, defaulting to `Z_FINISH`. `Z_SYNC_FLUSH` and `Z_FULL_FLUSH` allow compressing further strings of data, while `Z_FINISH` finishes the compressed stream and prevents compressing any more data. After calling `flush()` with *mode* set to `Z_FINISH`, the `compress()` method cannot be called again; the only realistic action is to delete the object.

copy ()

Returns a copy of the compression object. This can be used to efficiently compress a set of data that share a common initial prefix. New in version 2.5.

Decompression objects support the following methods, and two attributes:

unused_data

A string which contains any bytes past the end of the compressed data. That is, this remains "" until the last byte that contains compression data is available. If the whole string turned out to contain compressed data, this is "", the empty string.

The only way to determine where a string of compressed data ends is by actually decompressing it. This means that when compressed data is contained part of a larger file, you can only find the end of it by reading data and feeding it followed by some non-empty string into a decompression object’s `decompress` method until the `unused_data` attribute is no longer the empty string.

unconsumed_tail

A string that contains any data that was not consumed by the last `decompress` call because it exceeded the limit for the uncompressed data buffer. This data has not yet been seen by the zlib machinery, so you must feed it (possibly with further data concatenated to it) back to a subsequent `decompress` method call in order to get correct output.

decompress (*string* [, *max_length*])

Decompress *string*, returning a string containing the uncompressed data corresponding to at least part of the data in *string*. This data should be concatenated to the output produced by any preceding calls to the `decompress()` method. Some of the input data may be preserved in internal buffers for later processing.

If the optional parameter *max_length* is supplied then the return value will be no longer than *max_length*. This may mean that not all of the compressed input can be processed; and unconsumed data will be stored in the attribute `unconsumed_tail`. This string must be passed to a subsequent call to `decompress()` if decompression is to continue. If *max_length* is not supplied then the whole input is decompressed, and `unconsumed_tail` is an empty string.

flush ([*length*])

All pending input is processed, and a string containing the remaining uncompressed output is returned. After calling `flush()`, the `decompress()` method cannot be called again; the only realistic action is to delete the object.

The optional parameter *length* sets the initial size of the output buffer.

copy ()

Returns a copy of the decompression object. This can be used to save the state of the decompressor midway through the data stream in order to speed up random seeks into the stream at a future point. New in version 2.5.

See Also:

[Module `gzip`](#) (section 12.2):

Reading and writing **gzip**-format files.

<http://www.zlib.net>

The zlib library home page.

<http://www.zlib.net/manual.html>

The zlib manual explains the semantics and usage of the library's many functions.

12.2 `gzip` — Support for **gzip** files

The data compression provided by the `zlib` module is compatible with that used by the GNU compression program **gzip**. Accordingly, the `gzip` module provides the `GzipFile` class to read and write **gzip**-format files, automatically compressing or decompressing the data so it looks like an ordinary file object. Note that additional file formats which can be decompressed by the **gzip** and **gunzip** programs, such as those produced by **compress** and **pack**, are not supported by this module.

The module defines the following items:

class `GzipFile` ([*filename* [, *mode* [, *compresslevel* [, *fileobj*]]]])

Constructor for the `GzipFile` class, which simulates most of the methods of a file object, with the exception of the `readinto()` and `truncate()` methods. At least one of *fileobj* and *filename* must be given a non-trivial value.

The new class instance is based on *fileobj*, which can be a regular file, a `StringIO` object, or any other object which simulates a file. It defaults to `None`, in which case *filename* is opened to provide a file object.

When *fileobj* is not `None`, the *filename* argument is only used to be included in the **gzip** file header, which may include the original filename of the uncompressed file. It defaults to the filename of *fileobj*, if discernible; otherwise, it defaults to the empty string, and in this case the original filename is not included in the header.

The *mode* argument can be any of `'r'`, `'rb'`, `'a'`, `'ab'`, `'w'`, or `'wb'`, depending on whether the file will be read or written. The default is the mode of *fileobj* if discernible; otherwise, the default is `'rb'`. If not given, the `'b'` flag will be added to the mode to ensure the file is opened in binary mode for cross-platform portability.

The *compresslevel* argument is an integer from 1 to 9 controlling the level of compression; 1 is fastest and produces the least compression, and 9 is slowest and produces the most compression. The default is 9.

Calling a `GzipFile` object's `close()` method does not close *fileobj*, since you might wish to append more material after the compressed data. This also allows you to pass a `StringIO` object opened for writing as *fileobj*, and retrieve the resulting memory buffer using the `StringIO` object's `getvalue()` method.

open(*filename*[, *mode*[, *compresslevel*]])

This is a shorthand for `GzipFile(filename, mode, compresslevel)`. The *filename* argument is required; *mode* defaults to `'rb'` and *compresslevel* defaults to 9.

See Also:

[Module `zlib`](#) (section 12.1):

The basic data compression module needed to support the **gzip** file format.

12.3 bz2 — Compression compatible with bzip2

New in version 2.3.

This module provides a comprehensive interface for the bz2 compression library. It implements a complete file interface, one-shot (de)compression functions, and types for sequential (de)compression.

Here is a resume of the features offered by the bz2 module:

- `BZ2File` class implements a complete file interface, including `readline()`, `readlines()`, `writelines()`, `seek()`, etc;
- `BZ2File` class implements emulated `seek()` support;
- `BZ2File` class implements universal newline support;
- `BZ2File` class offers an optimized line iteration using the readahead algorithm borrowed from file objects;
- Sequential (de)compression supported by `BZ2Compressor` and `BZ2Decompressor` classes;
- One-shot (de)compression supported by `compress()` and `decompress()` functions;
- Thread safety uses individual locking mechanism;
- Complete inline documentation;

12.3.1 (De)compression of files

Handling of compressed files is offered by the `BZ2File` class.

class `BZ2File`(*filename*[, *mode*[, *buffering*[, *compresslevel*]]])

Open a bz2 file. Mode can be either `'r'` or `'w'`, for reading (default) or writing. When opened for writing, the file will be created if it doesn't exist, and truncated otherwise. If *buffering* is given, 0 means unbuffered, and larger numbers specify the buffer size; the default is 0. If *compresslevel* is given, it must be a number between 1 and 9; the default is 9. Add a `'U'` to mode to open the file for input with universal newline support. Any line ending in the input file will be seen as a `'\n'` in Python. Also, a file so opened gains the attribute `newlines`; the value for this attribute is one of `None` (no newline read yet), `'\r'`, `'\n'`, `'\r\n'` or a tuple containing all the newline types seen. Universal newlines are available only when reading. Instances support iteration in the same way as normal `file` instances.

close()

Close the file. Sets data attribute `closed` to true. A closed file cannot be used for further I/O operations. `close()` may be called more than once without error.

read (*[size]*)

Read at most *size* uncompressed bytes, returned as a string. If the *size* argument is negative or omitted, read until EOF is reached.

readline (*[size]*)

Return the next line from the file, as a string, retaining newline. A non-negative *size* argument limits the maximum number of bytes to return (an incomplete line may be returned then). Return an empty string at EOF.

readlines (*[size]*)

Return a list of lines read. The optional *size* argument, if given, is an approximate bound on the total number of bytes in the lines returned.

xreadlines ()

For backward compatibility. BZ2File objects now include the performance optimizations previously implemented in the `xreadlines` module. **Deprecated since release 2.3.** This exists only for compatibility with the method by this name on `file` objects, which is deprecated. Use `for line in file` instead.

seek (*offset* [*, whence*])

Move to new file position. Argument *offset* is a byte count. Optional argument *whence* defaults to `os.SEEK_SET` or 0 (offset from start of file; offset should be ≥ 0); other values are `os.SEEK_CUR` or 1 (move relative to current position; offset can be positive or negative), and `os.SEEK_END` or 2 (move relative to end of file; offset is usually negative, although many platforms allow seeking beyond the end of a file).

Note that seeking of bz2 files is emulated, and depending on the parameters the operation may be extremely slow.

tell ()

Return the current file position, an integer (may be a long integer).

write (*data*)

Write string *data* to file. Note that due to buffering, `close()` may be needed before the file on disk reflects the data written.

writelines (*sequence_of_strings*)

Write the sequence of strings to the file. Note that newlines are not added. The sequence can be any iterable object producing strings. This is equivalent to calling `write()` for each string.

12.3.2 Sequential (de)compression

Sequential compression and decompression is done using the classes `BZ2Compressor` and `BZ2Decompressor`.

class BZ2Compressor (*[compresslevel]*)

Create a new compressor object. This object may be used to compress data sequentially. If you want to compress data in one shot, use the `compress()` function instead. The *compresslevel* parameter, if given, must be a number between 1 and 9; the default is 9.

compress (*data*)

Provide more data to the compressor object. It will return chunks of compressed data whenever possible. When you've finished providing data to compress, call the `flush()` method to finish the compression process, and return what is left in internal buffers.

flush ()

Finish the compression process and return what is left in internal buffers. You must not use the compressor object after calling this method.

class BZ2Decompressor ()

Create a new decompressor object. This object may be used to decompress data sequentially. If you want to decompress data in one shot, use the `decompress()` function instead.

decompress (*data*)

Provide more data to the decompressor object. It will return chunks of decompressed data whenever possible. If you try to decompress data after the end of stream is found, `EOFError` will be raised. If any data was found after the end of stream, it'll be ignored and saved in `unused_data` attribute.

12.3.3 One-shot (de)compression

One-shot compression and decompression is provided through the `compress()` and `decompress()` functions.

compress (*data* [, *compresslevel*])

Compress *data* in one shot. If you want to compress data sequentially, use an instance of `BZ2Compressor` instead. The *compresslevel* parameter, if given, must be a number between 1 and 9; the default is 9.

decompress (*data*)

Decompress *data* in one shot. If you want to decompress data sequentially, use an instance of `BZ2Decompressor` instead.

12.4 zipfile — Work with ZIP archives

New in version 1.6.

The ZIP file format is a common archive and compression standard. This module provides tools to create, read, write, append, and list a ZIP file. Any advanced use of this module will require an understanding of the format, as defined in [PKZIP Application Note](#).

This module does not currently handle ZIP files which have appended comments, or multi-disk ZIP files. It can handle ZIP files that use the ZIP64 extensions (that is ZIP files that are more than 4 GByte in size).

The available attributes of this module are:

exception error

The error raised for bad ZIP files.

exception LargeZipFile

The error raised when a ZIP file would require ZIP64 functionality but that has not been enabled.

class ZipFile

The class for reading and writing ZIP files. See “*ZipFile Objects*” (section 12.4.1) for constructor details.

class PyZipFile

Class for creating ZIP archives containing Python libraries.

class ZipInfo ([*filename* [, *date_time*]])

Class used to represent information about a member of an archive. Instances of this class are returned by the `getinfo()` and `infolist()` methods of `ZipFile` objects. Most users of the `zipfile` module will not need to create these, but only use those created by this module. *filename* should be the full name of the archive member, and *date_time* should be a tuple containing six fields which describe the time of the last modification to the file; the fields are described in section 12.4.3, “*ZipInfo Objects*.”

is_zipfile (*filename*)

Returns `True` if *filename* is a valid ZIP file based on its magic number, otherwise returns `False`. This module does not currently handle ZIP files which have appended comments.

ZIP_STORED

The numeric constant for an uncompressed archive member.

ZIP_DEFLATED

The numeric constant for the usual ZIP compression method. This requires the `zlib` module. No other compres-

sion methods are currently supported.

See Also:

PKZIP Application Note

(http://www.pkware.com/business_and_developers/developer/appnote/)

Documentation on the ZIP file format by Phil Katz, the creator of the format and algorithms used.

Info-ZIP Home Page

(<http://www.info-zip.org/pub/infozip/>)

Information about the Info-ZIP project's ZIP archive programs and development libraries.

12.4.1 ZipFile Objects

class ZipFile (*file* [, *mode* [, *compression* [, *allowZip64*]]])

Open a ZIP file, where *file* can be either a path to a file (a string) or a file-like object. The *mode* parameter should be 'r' to read an existing file, 'w' to truncate and write a new file, or 'a' to append to an existing file. For *mode* is 'a' and *file* refers to an existing ZIP file, then additional files are added to it. If *file* does not refer to a ZIP file, then a new ZIP archive is appended to the file. This is meant for adding a ZIP archive to another file, such as 'python.exe'. Using

```
cat myzip.zip >> python.exe
```

also works, and at least **WinZip** can read such files. *compression* is the ZIP compression method to use when writing the archive, and should be ZIP_STORED or ZIP_DEFLATED; unrecognized values will cause `RuntimeError` to be raised. If ZIP_DEFLATED is specified but the `zlib` module is not available, `RuntimeError` is also raised. The default is ZIP_STORED. If *allowZip64* is `True` zipfile will create ZIP files that use the ZIP64 extensions when the zipfile is larger than 2 GB. If it is `false` (the default) zipfile will raise an exception when the ZIP file would require ZIP64 extensions. ZIP64 extensions are disabled by default because the default **zip** and **unzip** commands on UNIX (the InfoZIP utilities) don't support these extensions.

close ()

Close the archive file. You must call `close()` before exiting your program or essential records will not be written.

getinfo (*name*)

Return a `ZipInfo` object with information about the archive member *name*.

infolist ()

Return a list containing a `ZipInfo` object for each member of the archive. The objects are in the same order as their entries in the actual ZIP file on disk if an existing archive was opened.

namelist ()

Return a list of archive members by name.

printdir ()

Print a table of contents for the archive to `sys.stdout`.

read (*name*)

Return the bytes of the file in the archive. The archive must be open for read or append.

testzip ()

Read all the files in the archive and check their CRC's and file headers. Return the name of the first bad file, or else return `None`.

write (*filename* [, *arcname* [, *compress_type*]])

Write the file named *filename* to the archive, giving it the archive name *arcname* (by default, this will be the same as *filename*, but without a drive letter and with leading path separators removed). If given, *compress_type* overrides the value given for the *compression* parameter to the constructor for the new entry. The archive must

be open with mode `'w'` or `'a'`.

Note: There is no official file name encoding for ZIP files. If you have unicode file names, please convert them to byte strings in your desired encoding before passing them to `write()`. WinZip interprets all file names as encoded in CP437, also known as DOS Latin.

Note: Archive names should be relative to the archive root, that is, they should not start with a path separator.

writestr (*zinfo_or_arcname*, *bytes*)

Write the string *bytes* to the archive; *zinfo_or_arcname* is either the file name it will be given in the archive, or a `ZipInfo` instance. If it's an instance, at least the filename, date, and time must be given. If it's a name, the date and time is set to the current date and time. The archive must be opened with mode `'w'` or `'a'`.

The following data attribute is also available:

debug

The level of debug output to use. This may be set from 0 (the default, no output) to 3 (the most output). Debugging information is written to `sys.stdout`.

12.4.2 PyZipFile Objects

The `PyZipFile` constructor takes the same parameters as the `ZipFile` constructor. Instances have one method in addition to those of `ZipFile` objects.

writepy (*pathname*[, *basename*])

Search for files `'*.py'` and add the corresponding file to the archive. The corresponding file is a `'*.pyo'` file if available, else a `'*.pyc'` file, compiling if necessary. If the *pathname* is a file, the filename must end with `'.py'` , and just the (corresponding `'*.py[co]'`) file is added at the top level (no path information). If it is a directory, and the directory is not a package directory, then all the files `'*.py[co]'` are added at the top level. If the directory is a package directory, then all `'*.py[oc]'` are added under the package name as a file path, and if any subdirectories are package directories, all of these are added recursively. *basename* is intended for internal use only. The `writepy()` method makes archives with file names like this:

<code>string.pyc</code>	<code># Top level name</code>
<code>test/__init__.pyc</code>	<code># Package directory</code>
<code>test/testall.pyc</code>	<code># Module test.testall</code>
<code>test/bogus/__init__.pyc</code>	<code># Subpackage directory</code>
<code>test/bogus/myfile.pyc</code>	<code># Submodule test.bogus.myfile</code>

12.4.3 ZipInfo Objects

Instances of the `ZipInfo` class are returned by the `getinfo()` and `infolist()` methods of `ZipFile` objects. Each object stores information about a single member of the ZIP archive.

Instances have the following attributes:

filename

Name of the file in the archive.

date_time

The time and date of the last modification to the archive member. This is a tuple of six values:

Index	Value
0	Year
1	Month (one-based)
2	Day of month (one-based)
3	Hours (zero-based)
4	Minutes (zero-based)
5	Seconds (zero-based)

compress_type

Type of compression for the archive member.

comment

Comment for the individual archive member.

extra

Expansion field data. The *PKZIP Application Note* contains some comments on the internal structure of the data contained in this string.

create_system

System which created ZIP archive.

create_version

PKZIP version which created ZIP archive.

extract_version

PKZIP version needed to extract archive.

reserved

Must be zero.

flag_bits

ZIP flag bits.

volume

Volume number of file header.

internal_attr

Internal attributes.

external_attr

External file attributes.

header_offset

Byte offset to the file header.

CRC

CRC-32 of the uncompressed file.

compress_size

Size of the compressed data.

file_size

Size of the uncompressed file.

12.5 tarfile — Read and write tar archive files

New in version 2.3.

The `tarfile` module makes it possible to read and create tar archives. Some facts and figures:

- reads and writes `gzip` and `bzip2` compressed archives.

- creates POSIX 1003.1-1990 compliant or GNU tar compatible archives.
- reads GNU tar extensions *longname*, *longlink* and *sparse*.
- stores pathnames of unlimited length using GNU tar extensions.
- handles directories, regular files, hardlinks, symbolic links, fifos, character devices and block devices and is able to acquire and restore file information like timestamp, access permissions and owner.
- can handle tape devices.

open ([*name*[, *mode* [, *fileobj*[, *bufsize*]]]])

Return a `TarFile` object for the pathname *name*. For detailed information on `TarFile` objects, see *TarFile Objects* (section 12.5.1).

mode has to be a string of the form '`filemode[:compression]`', it defaults to '`r`'. Here is a full list of mode combinations:

mode	action
'r' or 'r:*	Open for reading with transparent compression (recommended).
'r:'	Open for reading exclusively without compression.
'r:gz'	Open for reading with gzip compression.
'r:bz2'	Open for reading with bzip2 compression.
'a' or 'a:'	Open for appending with no compression.
'w' or 'w:'	Open for uncompressed writing.
'w:gz'	Open for gzip compressed writing.
'w:bz2'	Open for bzip2 compressed writing.

Note that '`a:gz`' or '`a:bz2`' is not possible. If *mode* is not suitable to open a certain (compressed) file for reading, `ReadError` is raised. Use *mode* '`r`' to avoid this. If a compression method is not supported, `CompressionError` is raised.

If *fileobj* is specified, it is used as an alternative to a file object opened for *name*. It is supposed to be at position 0.

For special purposes, there is a second format for *mode*: '`filemode|[compression]`'. `open()` will return a `TarFile` object that processes its data as a stream of blocks. No random seeking will be done on the file. If given, *fileobj* may be any object that has a `read()` or `write()` method (depending on the *mode*). *bufsize* specifies the blocksize and defaults to `20 * 512` bytes. Use this variant in combination with e.g. `sys.stdin`, a socket file object or a tape device. However, such a `TarFile` object is limited in that it does not allow to be accessed randomly, see “Examples” (section 12.5.3). The currently possible modes:

Mode	Action
'r *'	Open a <i>stream</i> of tar blocks for reading with transparent compression.
'r '	Open a <i>stream</i> of uncompressed tar blocks for reading.
'r gz'	Open a gzip compressed <i>stream</i> for reading.
'r bz2'	Open a bzip2 compressed <i>stream</i> for reading.
'w '	Open an uncompressed <i>stream</i> for writing.
'w gz'	Open an gzip compressed <i>stream</i> for writing.
'w bz2'	Open an bzip2 compressed <i>stream</i> for writing.

class TarFile

Class for reading and writing tar archives. Do not use this class directly, better use `open()` instead. See “TarFile Objects” (section 12.5.1).

is_tarfile (*name*)

Return `True` if *name* is a tar archive file, that the `tarfile` module can read.

class TarFileCompat (*filename*[, *mode*[, *compression*]])

Class for limited access to tar archives with a `zipfile`-like interface. Please consult the documentation of the `zipfile` module for more details. *compression* must be one of the following constants:

TAR_PLAIN

Constant for an uncompressed tar archive.

TAR_GZIPPED

Constant for a [gzip](#) compressed tar archive.

exception TarError

Base class for all `tarfile` exceptions.

exception ReadError

Is raised when a tar archive is opened, that either cannot be handled by the `tarfile` module or is somehow invalid.

exception CompressionError

Is raised when a compression method is not supported or when the data cannot be decoded properly.

exception StreamError

Is raised for the limitations that are typical for stream-like `TarFile` objects.

exception ExtractError

Is raised for *non-fatal* errors when using `extract()`, but only if `TarFile.errorlevel == 2`.

See Also:

[Module zipfile](#) (section 12.4):

Documentation of the [zipfile](#) standard module.

GNU tar manual, Basic Tar Format

(http://www.gnu.org/software/tar/manual/html_node/tar_134.html#SEC134)

Documentation for tar archive files, including GNU tar extensions.

12.5.1 TarFile Objects

The `TarFile` object provides an interface to a tar archive. A tar archive is a sequence of blocks. An archive member (a stored file) is made up of a header block followed by data blocks. It is possible, to store a file in a tar archive several times. Each archive member is represented by a `TarInfo` object, see *TarInfo Objects* (section 12.5.2) for details.

class `TarFile` (`[name [, mode[, fileobj]]]`)

Open an (*uncompressed*) tar archive *name*. *mode* is either `'r'` to read from an existing archive, `'a'` to append data to an existing file or `'w'` to create a new file overwriting an existing one. *mode* defaults to `'r'`.

If *fileobj* is given, it is used for reading or writing data. If it can be determined, *mode* is overridden by *fileobj*'s mode. *fileobj* will be used from position 0.

Note: *fileobj* is not closed, when `TarFile` is closed.

open (...)

Alternative constructor. The `open()` function on module level is actually a shortcut to this classmethod. See section 12.5 for details.

getmember (*name*)

Return a `TarInfo` object for member *name*. If *name* can not be found in the archive, `KeyError` is raised.

Note: If a member occurs more than once in the archive, its last occurrence is assumed to be the most up-to-date version.

getmembers ()

Return the members of the archive as a list of `TarInfo` objects. The list has the same order as the members in the archive.

getnames ()

Return the members as a list of their names. It has the same order as the list returned by `getmembers()`.

list (*verbose=True*)

Print a table of contents to `sys.stdout`. If *verbose* is `False`, only the names of the members are printed. If it is `True`, output similar to that of `ls -l` is produced.

next ()

Return the next member of the archive as a `TarInfo` object, when `TarFile` is opened for reading. Return `None` if there is no more available.

extractall ([*path*, *members*])

Extract all members from the archive to the current working directory or directory *path*. If optional *members* is given, it must be a subset of the list returned by `getmembers()`. Directory informations like owner, modification time and permissions are set after all members have been extracted. This is done to work around two problems: A directory's modification time is reset each time a file is created in it. And, if a directory's permissions do not allow writing, extracting files to it will fail.

Warning: Never extract archives from untrusted sources without prior inspection. It is possible that files are created outside of *path*, e.g. members that have absolute filenames starting with `" / "` or filenames with two dots `" . . "`.

New in version 2.5.

extract (*member*, [*path*])

Extract a member from the archive to the current working directory, using its full name. Its file information is extracted as accurately as possible. *member* may be a filename or a `TarInfo` object. You can specify a different directory using *path*.

Note: Because the `extract()` method allows random access to a tar archive there are some issues you must take care of yourself. See the description for `extractall()` above.

Warning: See the warning for `extractall()`.

extractfile (*member*)

Extract a member from the archive as a file object. *member* may be a filename or a `TarInfo` object. If *member* is a regular file, a file-like object is returned. If *member* is a link, a file-like object is constructed from the link's target. If *member* is none of the above, `None` is returned.

Note: The file-like object is read-only and provides the following methods: `read()`, `readline()`, `readlines()`, `seek()`, `tell()`.

add (*name*, [*arcname*, *recursive*])

Add the file *name* to the archive. *name* may be any type of file (directory, fifo, symbolic link, etc.). If given, *arcname* specifies an alternative name for the file in the archive. Directories are added recursively by default. This can be avoided by setting *recursive* to `False`; the default is `True`.

addfile (*tarinfo*, [*fileobj*])

Add the `TarInfo` object *tarinfo* to the archive. If *fileobj* is given, *tarinfo.size* bytes are read from it and added to the archive. You can create `TarInfo` objects using `gettaringfo()`.

Note: On Windows platforms, *fileobj* should always be opened with mode `'rb'` to avoid irritation about the file size.

gettaringfo ([*name*, [*arcname*, *fileobj*]])

Create a `TarInfo` object for either the file *name* or the file object *fileobj* (using `os.fstat()` on its file descriptor). You can modify some of the `TarInfo`'s attributes before you add it using `addfile()`. If given, *arcname* specifies an alternative name for the file in the archive.

close ()

Close the `TarFile`. In write mode, two finishing zero blocks are appended to the archive.

posix

If true, create a POSIX 1003.1-1990 compliant archive. GNU extensions are not used, because they are not part

of the POSIX standard. This limits the length of filenames to at most 256, link names to 100 characters and the maximum file size to 8 gigabytes. A `ValueError` is raised if a file exceeds this limit. If false, create a GNU tar compatible archive. It will not be POSIX compliant, but can store files without any of the above restrictions. Changed in version 2.4: *posix* defaults to `False`.

dereference

If false, add symbolic and hard links to archive. If true, add the content of the target files to the archive. This has no effect on systems that do not support symbolic links.

ignore_zeros

If false, treat an empty block as the end of the archive. If true, skip empty (and invalid) blocks and try to get as many members as possible. This is only useful for concatenated or damaged archives.

debug=0

To be set from 0 (no debug messages; the default) up to 3 (all debug messages). The messages are written to `sys.stderr`.

errorlevel

If 0 (the default), all errors are ignored when using `extract()`. Nevertheless, they appear as error messages in the debug output, when debugging is enabled. If 1, all *fatal* errors are raised as `OSError` or `IOError` exceptions. If 2, all *non-fatal* errors are raised as `TarError` exceptions as well.

12.5.2 TarInfo Objects

A `TarInfo` object represents one member in a `TarFile`. Aside from storing all required attributes of a file (like file type, size, time, permissions, owner etc.), it provides some useful methods to determine its type. It does *not* contain the file's data itself.

`TarInfo` objects are returned by `TarFile`'s methods `getmember()`, `getmembers()` and `gettarinfo()`.

class TarInfo([name])

Create a `TarInfo` object.

frombuf()

Create and return a `TarInfo` object from a string buffer.

tobuf(posix)

Create a string buffer from a `TarInfo` object. See `TarFile`'s *posix* attribute for information on the *posix* argument. It defaults to `False`.

New in version 2.5: The *posix* parameter.

A `TarInfo` object has the following public data attributes:

name

Name of the archive member.

size

Size in bytes.

mtime

Time of last modification.

mode

Permission bits.

type

File type. *type* is usually one of these constants: `REGTYPE`, `AREGTYPE`, `LNKTYPE`, `SYMTYPE`, `DIRTYPE`, `FIFOTYPE`, `CONTTYPE`, `CHRTYPE`, `BLKTYPE`, `GNUTYPE_SPARSE`. To determine the type of a `TarInfo` object more conveniently, use the `is_*()` methods below.

linkname

Name of the target file name, which is only present in `TarInfo` objects of type `LNKTYPE` and `SYMTYPE`.

uid

User ID of the user who originally stored this member.

gid

Group ID of the user who originally stored this member.

uname

User name.

gname

Group name.

A `TarInfo` object also provides some convenient query methods:

isfile()

Return `True` if the `TarInfo` object is a regular file.

isreg()

Same as `isfile()`.

isdir()

Return `True` if it is a directory.

issym()

Return `True` if it is a symbolic link.

islnk()

Return `True` if it is a hard link.

ischr()

Return `True` if it is a character device.

isblk()

Return `True` if it is a block device.

isfifo()

Return `True` if it is a FIFO.

isdev()

Return `True` if it is one of character device, block device or FIFO.

12.5.3 Examples

How to extract an entire tar archive to the current working directory:

```
import tarfile
tar = tarfile.open("sample.tar.gz")
tar.extractall()
tar.close()
```

How to create an uncompressed tar archive from a list of filenames:


```

import tarfile
tar = tarfile.open("sample.tar", "w")
for name in ["foo", "bar", "quux"]:
    tar.add(name)
tar.close()

```

How to read a gzip compressed tar archive and display some member information:

```

import tarfile
tar = tarfile.open("sample.tar.gz", "r:gz")
for tarinfo in tar:
    print tarinfo.name, "is", tarinfo.size, "bytes in size and is",
    if tarinfo.isreg():
        print "a regular file."
    elif tarinfo.isdir():
        print "a directory."
    else:
        print "something else."
tar.close()

```

How to create a tar archive with faked information:

```

import tarfile
tar = tarfile.open("sample.tar.gz", "w:gz")
for name in namelist:
    tarinfo = tar.gettarinfo(name, "fakeproj-1.0/" + name)
    tarinfo.uid = 123
    tarinfo.gid = 456
    tarinfo.uname = "johndoe"
    tarinfo.gname = "fake"
    tar.addfile(tarinfo, file(name))
tar.close()

```

The *only* way to extract an uncompressed tar stream from `sys.stdin`:

```

import sys
import tarfile
tar = tarfile.open(mode="r|", fileobj=sys.stdin)
for tarinfo in tar:
    tar.extract(tarinfo)
tar.close()

```


Data Persistence

The modules described in this chapter support storing Python data in a persistent form on disk. The `pickle` and `marshal` modules can turn many Python data types into a stream of bytes and then recreate the objects from the bytes. The various DBM-related modules support a family of hash-based file formats that store a mapping of strings to other strings. The `bsddb` module also provides such disk-based string-to-string mappings based on hashing, and also supports B-Tree and record-based formats.

The list of modules described in this chapter is:

<code>pickle</code>	Convert Python objects to streams of bytes and back.
<code>cPickle</code>	Faster version of <code>pickle</code> , but not subclassable.
<code>copy_reg</code>	Register <code>pickle</code> support functions.
<code>shelve</code>	Python object persistence.
<code>marshal</code>	Convert Python objects to streams of bytes and back (with different constraints).
<code>anydbm</code>	Generic interface to DBM-style database modules.
<code>whichdb</code>	Guess which DBM-style module created a given database.
<code>dbm</code>	The standard “database” interface, based on <code>ndbm</code> .
<code>gdbm</code>	GNU’s reinterpretation of <code>dbm</code> .
<code>dbhash</code>	DBM-style interface to the BSD database library.
<code>bsddb</code>	Interface to Berkeley DB database library
<code>dumbdbm</code>	Portable implementation of the simple DBM interface.
<code>sqlite3</code>	A DB-API 2.0 implementation using SQLite 3.x.

13.1 `pickle` — Python object serialization

The `pickle` module implements a fundamental, but powerful algorithm for serializing and de-serializing a Python object structure. “Pickling” is the process whereby a Python object hierarchy is converted into a byte stream, and “unpickling” is the inverse operation, whereby a byte stream is converted back into an object hierarchy. Pickling (and unpickling) is alternatively known as “serialization”, “marshalling,”¹ or “flattening”, however, to avoid confusion, the terms used here are “pickling” and “unpickling”.

This documentation describes both the `pickle` module and the `cPickle` module.

13.1.1 Relationship to other Python modules

The `pickle` module has an optimized cousin called the `cPickle` module. As its name implies, `cPickle` is written in C, so it can be up to 1000 times faster than `pickle`. However it does not support subclassing of the `Pickler()` and `Unpickler()` classes, because in `cPickle` these are functions, not classes. Most applications have no need for this functionality, and can benefit from the improved performance of `cPickle`. Other than that, the interfaces of

¹Don’t confuse this with the `marshal` module

the two modules are nearly identical; the common interface is described in this manual and differences are pointed out where necessary. In the following discussions, we use the term “pickle” to collectively describe the `pickle` and `cPickle` modules.

The data streams the two modules produce are guaranteed to be interchangeable.

Python has a more primitive serialization module called `marshal`, but in general `pickle` should always be the preferred way to serialize Python objects. `marshal` exists primarily to support Python’s ‘.pyc’ files.

The `pickle` module differs from `marshal` several significant ways:

- The `pickle` module keeps track of the objects it has already serialized, so that later references to the same object won’t be serialized again. `marshal` doesn’t do this.

This has implications both for recursive objects and object sharing. Recursive objects are objects that contain references to themselves. These are not handled by `marshal`, and in fact, attempting to marshal recursive objects will crash your Python interpreter. Object sharing happens when there are multiple references to the same object in different places in the object hierarchy being serialized. `pickle` stores such objects only once, and ensures that all other references point to the master copy. Shared objects remain shared, which can be very important for mutable objects.

- `marshal` cannot be used to serialize user-defined classes and their instances. `pickle` can save and restore class instances transparently, however the class definition must be importable and live in the same module as when the object was stored.
- The `marshal` serialization format is not guaranteed to be portable across Python versions. Because its primary job in life is to support ‘.pyc’ files, the Python implementers reserve the right to change the serialization format in non-backwards compatible ways should the need arise. The `pickle` serialization format is guaranteed to be backwards compatible across Python releases.

Warning: The `pickle` module is not intended to be secure against erroneous or maliciously constructed data. Never unpickle data received from an untrusted or unauthenticated source.

Note that serialization is a more primitive notion than persistence; although `pickle` reads and writes file objects, it does not handle the issue of naming persistent objects, nor the (even more complicated) issue of concurrent access to persistent objects. The `pickle` module can transform a complex object into a byte stream and it can transform the byte stream into an object with the same internal structure. Perhaps the most obvious thing to do with these byte streams is to write them onto a file, but it is also conceivable to send them across a network or store them in a database. The module `shelve` provides a simple interface to pickle and unpickle objects on DBM-style database files.

13.1.2 Data stream format

The data format used by `pickle` is Python-specific. This has the advantage that there are no restrictions imposed by external standards such as XDR (which can’t represent pointer sharing); however it means that non-Python programs may not be able to reconstruct pickled Python objects.

By default, the `pickle` data format uses a printable ASCII representation. This is slightly more voluminous than a binary representation. The big advantage of using printable ASCII (and of some other characteristics of `pickle`’s representation) is that for debugging or recovery purposes it is possible for a human to read the pickled file with a standard text editor.

There are currently 3 different protocols which can be used for pickling.

- Protocol version 0 is the original ASCII protocol and is backwards compatible with earlier versions of Python.
- Protocol version 1 is the old binary format which is also compatible with earlier versions of Python.

- Protocol version 2 was introduced in Python 2.3. It provides much more efficient pickling of new-style classes.

Refer to PEP 307 for more information.

If a *protocol* is not specified, protocol 0 is used. If *protocol* is specified as a negative value or `HIGHEST_PROTOCOL`, the highest protocol version available will be used.

Changed in version 2.3: Introduced the *protocol* parameter.

A binary format, which is slightly more efficient, can be chosen by specifying a *protocol* version ≥ 1 .

13.1.3 Usage

To serialize an object hierarchy, you first create a pickler, then you call the pickler's `dump()` method. To de-serialize a data stream, you first create an unpickler, then you call the unpickler's `load()` method. The `pickle` module provides the following constant:

HIGHEST_PROTOCOL

The highest protocol version available. This value can be passed as a *protocol* value. New in version 2.3.

Note: Be sure to always open pickle files created with protocols ≥ 1 in binary mode. For the old ASCII-based pickle protocol 0 you can use either text mode or binary mode as long as you stay consistent.

A pickle file written with protocol 0 in binary mode will contain lone linefeeds as line terminators and therefore will look “funny” when viewed in Notepad or other editors which do not support this format.

The `pickle` module provides the following functions to make the pickling process more convenient:

dump(*obj*, *file*[, *protocol*])

Write a pickled representation of *obj* to the open file object *file*. This is equivalent to `Pickler(file, protocol) .dump(obj)`.

If the *protocol* parameter is omitted, protocol 0 is used. If *protocol* is specified as a negative value or `HIGHEST_PROTOCOL`, the highest protocol version will be used.

Changed in version 2.3: Introduced the *protocol* parameter.

file must have a `write()` method that accepts a single string argument. It can thus be a file object opened for writing, a `StringIO` object, or any other custom object that meets this interface.

load(*file*)

Read a string from the open file object *file* and interpret it as a pickle data stream, reconstructing and returning the original object hierarchy. This is equivalent to `Unpickler(file) .load()`.

file must have two methods, a `read()` method that takes an integer argument, and a `readline()` method that requires no arguments. Both methods should return a string. Thus *file* can be a file object opened for reading, a `StringIO` object, or any other custom object that meets this interface.

This function automatically determines whether the data stream was written in binary mode or not.

dumps(*obj*[, *protocol*])

Return the pickled representation of the object as a string, instead of writing it to a file.

If the *protocol* parameter is omitted, protocol 0 is used. If *protocol* is specified as a negative value or `HIGHEST_PROTOCOL`, the highest protocol version will be used.

Changed in version 2.3: The *protocol* parameter was added.

loads(*string*)

Read a pickled object hierarchy from a string. Characters in the string past the pickled object's representation are ignored.

The `pickle` module also defines three exceptions:

exception `PickleError`

A common base class for the other exceptions defined below. This inherits from `Exception`.

exception `PicklingError`

This exception is raised when an unpicklable object is passed to the `dump()` method.

exception `UnpicklingError`

This exception is raised when there is a problem unpickling an object. Note that other exceptions may also be raised during unpickling, including (but not necessarily limited to) `AttributeError`, `EOFError`, `ImportError`, and `IndexError`.

The `pickle` module also exports two callables², `Pickler` and `Unpickler`:

class `Pickler` (*file* [, *protocol*])

This takes a file-like object to which it will write a pickle data stream.

If the *protocol* parameter is omitted, protocol 0 is used. If *protocol* is specified as a negative value, the highest protocol version will be used.

Changed in version 2.3: Introduced the *protocol* parameter.

file must have a `write()` method that accepts a single string argument. It can thus be an open file object, a `StringIO` object, or any other custom object that meets this interface.

`Pickler` objects define one (or two) public methods:

`dump()` (*obj*)

Write a pickled representation of *obj* to the open file object given in the constructor. Either the binary or ASCII format will be used, depending on the value of the *protocol* argument passed to the constructor.

`clear_memo()`

Clears the pickler's "memo". The memo is the data structure that remembers which objects the pickler has already seen, so that shared or recursive objects pickled by reference and not by value. This method is useful when re-using picklers.

Note: Prior to Python 2.3, `clear_memo()` was only available on the picklers created by `cPickle`. In the `pickle` module, picklers have an instance variable called `memo` which is a Python dictionary. So to clear the memo for a `pickle` module pickler, you could do the following:

```
mypickler.memo.clear()
```

Code that does not need to support older versions of Python should simply use `clear_memo()`.

It is possible to make multiple calls to the `dump()` method of the same `Pickler` instance. These must then be matched to the same number of calls to the `load()` method of the corresponding `Unpickler` instance. If the same object is pickled by multiple `dump()` calls, the `load()` will all yield references to the same object.³

`Unpickler` objects are defined as:

class `Unpickler` (*file*)

This takes a file-like object from which it will read a pickle data stream. This class automatically determines whether the data stream was written in binary mode or not, so it does not need a flag as in the `Pickler` factory.

file must have two methods, a `read()` method that takes an integer argument, and a `readline()` method that requires no arguments. Both methods should return a string. Thus *file* can be a file object opened for reading, a `StringIO` object, or any other custom object that meets this interface.

²In the `pickle` module these callables are classes, which you could subclass to customize the behavior. However, in the `cPickle` module these callables are factory functions and so cannot be subclassed. One common reason to subclass is to control what objects can actually be unpickled. See section 13.1.6 for more details.

³**Warning:** this is intended for pickling multiple objects without intervening modifications to the objects or their parts. If you modify an object and then pickle it again using the same `Pickler` instance, the object is not pickled again — a reference to it is pickled and the `Unpickler` will return the old value, not the modified one. There are two problems here: (1) detecting changes, and (2) marshalling a minimal set of changes. Garbage Collection may also become a problem here.

Unpickler objects have one (or two) public methods:

load()

Read a pickled object representation from the open file object given in the constructor, and return the reconstituted object hierarchy specified therein.

noload()

This is just like `load()` except that it doesn't actually create any objects. This is useful primarily for finding what's called "persistent ids" that may be referenced in a pickle data stream. See section 13.1.5 below for more details.

Note: the `noload()` method is currently only available on Unpickler objects created with the `cPickle` module. `pickle` module Unpicklers do not have the `noload()` method.

13.1.4 What can be pickled and unpickled?

The following types can be pickled:

- `None`, `True`, and `False`
- integers, long integers, floating point numbers, complex numbers
- normal and Unicode strings
- tuples, lists, sets, and dictionaries containing only picklable objects
- functions defined at the top level of a module
- built-in functions defined at the top level of a module
- classes that are defined at the top level of a module
- instances of such classes whose `__dict__` or `__setstate__()` is picklable (see section 13.1.5 for details)

Attempts to pickle unpicklable objects will raise the `PicklingError` exception; when this happens, an unspecified number of bytes may have already been written to the underlying file. Trying to pickle a highly recursive data structure may exceed the maximum recursion depth, a `RuntimeError` will be raised in this case. You can carefully raise this limit with `sys.setrecursionlimit()`.

Note that functions (built-in and user-defined) are pickled by "fully qualified" name reference, not by value. This means that only the function name is pickled, along with the name of module the function is defined in. Neither the function's code, nor any of its function attributes are pickled. Thus the defining module must be importable in the unpickling environment, and the module must contain the named object, otherwise an exception will be raised.⁴

Similarly, classes are pickled by named reference, so the same restrictions in the unpickling environment apply. Note that none of the class's code or data is pickled, so in the following example the class attribute `attr` is not restored in the unpickling environment:

```
class Foo:
    attr = 'a class attr'

picklestring = pickle.dumps(Foo)
```

These restrictions are why picklable functions and classes must be defined in the top level of a module.

⁴The exception raised will likely be an `ImportError` or an `AttributeError` but it could be something else.

Similarly, when class instances are pickled, their class's code and data are not pickled along with them. Only the instance data are pickled. This is done on purpose, so you can fix bugs in a class or add methods to the class and still load objects that were created with an earlier version of the class. If you plan to have long-lived objects that will see many versions of a class, it may be worthwhile to put a version number in the objects so that suitable conversions can be made by the class's `__setstate__()` method.

13.1.5 The pickle protocol

This section describes the “pickling protocol” that defines the interface between the pickler/unpickler and the objects that are being serialized. This protocol provides a standard way for you to define, customize, and control how your objects are serialized and de-serialized. The description in this section doesn't cover specific customizations that you can employ to make the unpickling environment slightly safer from untrusted pickle data streams; see section 13.1.6 for more details.

Pickling and unpickling normal class instances

When a pickled class instance is unpickled, its `__init__()` method is normally *not* invoked. If it is desirable that the `__init__()` method be called on unpickling, an old-style class can define a method `__getinitargs__()`, which should return a *tuple* containing the arguments to be passed to the class constructor (`__init__()` for example). The `__getinitargs__()` method is called at pickle time; the tuple it returns is incorporated in the pickle for the instance.

New-style types can provide a `__getnewargs__()` method that is used for protocol 2. Implementing this method is needed if the type establishes some internal invariants when the instance is created, or if the memory allocation is affected by the values passed to the `__new__()` method for the type (as it is for tuples and strings). Instances of a new-style type `C` are created using

```
obj = C.__new__(C, *args)
```

where `args` is the result of calling `__getnewargs__()` on the original object; if there is no `__getnewargs__()`, an empty tuple is assumed.

Classes can further influence how their instances are pickled; if the class defines the method `__getstate__()`, it is called and the return state is pickled as the contents for the instance, instead of the contents of the instance's dictionary. If there is no `__getstate__()` method, the instance's `__dict__` is pickled.

Upon unpickling, if the class also defines the method `__setstate__()`, it is called with the unpickled state.⁵ If there is no `__setstate__()` method, the pickled state must be a dictionary and its items are assigned to the new instance's dictionary. If a class defines both `__getstate__()` and `__setstate__()`, the state object needn't be a dictionary and these methods can do what they want.⁶

Warning: For new-style classes, if `__getstate__()` returns a false value, the `__setstate__()` method will not be called.

Pickling and unpickling extension types

When the `Pickler` encounters an object of a type it knows nothing about — such as an extension type — it looks in two places for a hint of how to pickle it. One alternative is for the object to implement a `__reduce__()` method. If provided, at pickling time `__reduce__()` will be called with no arguments, and it must return either a string or a tuple.

⁵These methods can also be used to implement copying class instances.

⁶This protocol is also used by the shallow and deep copying operations defined in the `copy` module.

If a string is returned, it names a global variable whose contents are pickled as normal. The string returned by `__reduce__` should be the object's local name relative to its module; the pickle module searches the module namespace to determine the object's module.

When a tuple is returned, it must be between two and five elements long. Optional elements can either be omitted, or `None` can be provided as their value. The semantics of each element are:

- A callable object that will be called to create the initial version of the object. The next element of the tuple will provide arguments for this callable, and later elements provide additional state information that will subsequently be used to fully reconstruct the pickled data.

In the unpickling environment this object must be either a class, a callable registered as a “safe constructor” (see below), or it must have an attribute `__safe_for_unpickling__` with a true value. Otherwise, an `UnpicklingError` will be raised in the unpickling environment. Note that as usual, the callable itself is pickled by name.

- A tuple of arguments for the callable object. Changed in version 2.5: Formerly, this argument could also be `None`.
- Optionally, the object's state, which will be passed to the object's `__setstate__()` method as described in section 13.1.5. If the object has no `__setstate__()` method, then, as above, the value must be a dictionary and it will be added to the object's `__dict__`.
- Optionally, an iterator (and not a sequence) yielding successive list items. These list items will be pickled, and appended to the object using either `obj.append(item)` or `obj.extend(list_of_items)`. This is primarily used for list subclasses, but may be used by other classes as long as they have `append()` and `extend()` methods with the appropriate signature. (Whether `append()` or `extend()` is used depends on which pickle protocol version is used as well as the number of items to append, so both must be supported.)
- Optionally, an iterator (not a sequence) yielding successive dictionary items, which should be tuples of the form `(key, value)`. These items will be pickled and stored to the object using `obj[key] = value`. This is primarily used for dictionary subclasses, but may be used by other classes as long as they implement `__setitem__`.

It is sometimes useful to know the protocol version when implementing `__reduce__`. This can be done by implementing a method named `__reduce_ex__` instead of `__reduce__`. `__reduce_ex__`, when it exists, is called in preference over `__reduce__` (you may still provide `__reduce__` for backwards compatibility). The `__reduce_ex__` method will be called with a single integer argument, the protocol version.

The object class implements both `__reduce__` and `__reduce_ex__`; however, if a subclass overrides `__reduce__` but not `__reduce_ex__`, the `__reduce_ex__` implementation detects this and calls `__reduce__`.

An alternative to implementing a `__reduce__()` method on the object to be pickled, is to register the callable with the `copy_reg` module. This module provides a way for programs to register “reduction functions” and constructors for user-defined types. Reduction functions have the same semantics and interface as the `__reduce__()` method described above, except that they are called with a single argument, the object to be pickled.

The registered constructor is deemed a “safe constructor” for purposes of unpickling as described above.

Pickling and unpickling external objects

For the benefit of object persistence, the `pickle` module supports the notion of a reference to an object outside the pickled data stream. Such objects are referenced by a “persistent id”, which is just an arbitrary string of printable ASCII characters. The resolution of such names is not defined by the `pickle` module; it will delegate this resolution to user defined functions on the pickler and unpickler.⁷

⁷The actual mechanism for associating these user defined functions is slightly different for `pickle` and `cPickle`. The description given here works the same for both implementations. Users of the `pickle` module could also use subclassing to effect the same results, overriding the `persistent_id()` and `persistent_load()` methods in the derived classes.

To define external persistent id resolution, you need to set the `persistent_id` attribute of the pickler object and the `persistent_load` attribute of the unpickler object.

To pickle objects that have an external persistent id, the pickler must have a custom `persistent_id()` method that takes an object as an argument and returns either `None` or the persistent id for that object. When `None` is returned, the pickler simply pickles the object as normal. When a persistent id string is returned, the pickler will pickle that string, along with a marker so that the unpickler will recognize the string as a persistent id.

To unpickle external objects, the unpickler must have a custom `persistent_load()` function that takes a persistent id string and returns the referenced object.

Here's a silly example that *might* shed more light:

```

import pickle
from cStringIO import StringIO

src = StringIO()
p = pickle.Pickler(src)

def persistent_id(obj):
    if hasattr(obj, 'x'):
        return 'the value %d' % obj.x
    else:
        return None

p.persistent_id = persistent_id

class Integer:
    def __init__(self, x):
        self.x = x
    def __str__(self):
        return 'My name is integer %d' % self.x

i = Integer(7)
print i
p.dump(i)

datastream = src.getvalue()
print repr(datastream)
dst = StringIO(datastream)

up = pickle.Unpickler(dst)

class FancyInteger(Integer):
    def __str__(self):
        return 'I am the integer %d' % self.x

def persistent_load(persid):
    if persid.startswith('the value '):
        value = int(persid.split()[2])
        return FancyInteger(value)
    else:
        raise pickle.UnpicklingError, 'Invalid persistent id'

up.persistent_load = persistent_load

j = up.load()
print j

```

In the `cPickle` module, the unpickler's `persistent_load` attribute can also be set to a Python list, in which case, when the unpickler reaches a persistent id, the persistent id string will simply be appended to this list. This functionality exists so that a pickle data stream can be “sniffed” for object references without actually instantiating all the objects in a pickle.⁸ Setting `persistent_load` to a list is usually used in conjunction with the `noload()` method on the Unpickler.

⁸We'll leave you with the image of Guido and Jim sitting around sniffing pickles in their living rooms.

13.1.6 Subclassing Unpicklers

By default, unpickling will import any class that it finds in the pickle data. You can control exactly what gets unpickled and what gets called by customizing your unpickler. Unfortunately, exactly how you do this is different depending on whether you're using `pickle` or `cPickle`.⁹

In the `pickle` module, you need to derive a subclass from `Unpickler`, overriding the `load_global()` method. `load_global()` should read two lines from the pickle data stream where the first line will be the name of the module containing the class and the second line will be the name of the instance's class. It then looks up the class, possibly importing the module and digging out the attribute, then it appends what it finds to the unpickler's stack. Later on, this class will be assigned to the `__class__` attribute of an empty class, as a way of magically creating an instance without calling its class's `__init__()`. Your job (should you choose to accept it), would be to have `load_global()` push onto the unpickler's stack, a known safe version of any class you deem safe to unpickle. It is up to you to produce such a class. Or you could raise an error if you want to disallow all unpickling of instances. If this sounds like a hack, you're right. Refer to the source code to make this work.

Things are a little cleaner with `cPickle`, but not by much. To control what gets unpickled, you can set the unpickler's `find_global` attribute to a function or `None`. If it is `None` then any attempts to unpickle instances will raise an `UnpicklingError`. If it is a function, then it should accept a module name and a class name, and return the corresponding class object. It is responsible for looking up the class and performing any necessary imports, and it may raise an error to prevent instances of the class from being unpickled.

The moral of the story is that you should be really careful about the source of the strings your application unpickles.

13.1.7 Example

For the simplest code, use the `dump()` and `load()` functions. Note that a self-referencing list is pickled and restored correctly.

```
import pickle

data1 = {'a': [1, 2.0, 3, 4+6j],
        'b': ('string', u'Unicode string'),
        'c': None}

selfref_list = [1, 2, 3]
selfref_list.append(selfref_list)

output = open('data.pkl', 'wb')

# Pickle dictionary using protocol 0.
pickle.dump(data1, output)

# Pickle the list using the highest protocol available.
pickle.dump(selfref_list, output, -1)

output.close()
```

The following example reads the resulting pickled data. When reading a pickle-containing file, you should open the file in binary mode because you can't be sure if the ASCII or binary format was used.

⁹A word of caution: the mechanisms described here use internal attributes and methods, which are subject to change in future versions of Python. We intend to someday provide a common interface for controlling this behavior, which will work in either `pickle` or `cPickle`.

```

import pprint, pickle

pkl_file = open('data.pkl', 'rb')

data1 = pickle.load(pkl_file)
pprint.pprint(data1)

data2 = pickle.load(pkl_file)
pprint.pprint(data2)

pkl_file.close()

```

Here's a larger example that shows how to modify pickling behavior for a class. The `TextReader` class opens a text file, and returns the line number and line contents each time its `readline()` method is called. If a `TextReader` instance is pickled, all attributes *except* the file object member are saved. When the instance is unpickled, the file is reopened, and reading resumes from the last location. The `__setstate__()` and `__getstate__()` methods are used to implement this behavior.

```

class TextReader:
    """Print and number lines in a text file."""
    def __init__(self, file):
        self.file = file
        self.fh = open(file)
        self.lineno = 0

    def readline(self):
        self.lineno = self.lineno + 1
        line = self.fh.readline()
        if not line:
            return None
        if line.endswith("\n"):
            line = line[:-1]
        return "%d: %s" % (self.lineno, line)

    def __getstate__(self):
        odict = self.__dict__.copy() # copy the dict since we change it
        del odict['fh']              # remove filehandle entry
        return odict

    def __setstate__(self, dict):
        fh = open(dict['file'])      # reopen file
        count = dict['lineno']       # read from file...
        while count:                # until line count is restored
            fh.readline()
            count = count - 1
        self.__dict__.update(dict)  # update attributes
        self.fh = fh                # save the file object

```

A sample usage might be something like this:

```

>>> import TextReader
>>> obj = TextReader.TextReader("TextReader.py")
>>> obj.readline()
'1: #!/usr/local/bin/python'
>>> # (more invocations of obj.readline() here)
... obj.readline()
'7: class TextReader:'
>>> import pickle
>>> pickle.dump(obj, open('save.p', 'w'))

```

If you want to see that `pickle` works across Python processes, start another Python session, before continuing. What follows can happen from either the same process or a new process.

```

>>> import pickle
>>> reader = pickle.load(open('save.p'))
>>> reader.readline()
'8:      "Print and number lines in a text file."'

```

See Also:

[Module `copy_reg`](#) (section 13.3):

Pickle interface constructor registration for extension types.

[Module `shelve`](#) (section 13.4):

Indexed databases of objects; uses `pickle`.

[Module `copy`](#) (section 5.17):

Shallow and deep object copying.

[Module `marshal`](#) (section 13.5):

High-performance serialization of built-in types.

13.2 cPickle — A faster pickle

The `cPickle` module supports serialization and de-serialization of Python objects, providing an interface and functionality nearly identical to the `pickle` module. There are several differences, the most important being performance and subclassability.

First, `cPickle` can be up to 1000 times faster than `pickle` because the former is implemented in C. Second, in the `cPickle` module the callables `Pickler()` and `Unpickler()` are functions, not classes. This means that you cannot use them to derive custom pickling and unpickling subclasses. Most applications have no need for this functionality and should benefit from the greatly improved performance of the `cPickle` module.

The pickle data stream produced by `pickle` and `cPickle` are identical, so it is possible to use `pickle` and `cPickle` interchangeably with existing pickles.¹⁰

There are additional minor differences in API between `cPickle` and `pickle`, however for most applications, they are interchangeable. More documentation is provided in the `pickle` module documentation, which includes a list of the documented differences.

¹⁰Since the pickle data format is actually a tiny stack-oriented programming language, and some freedom is taken in the encodings of certain objects, it is possible that the two modules produce different data streams for the same input objects. However it is guaranteed that they will always be able to read each other's data streams.

13.3 copy_reg — Register pickle support functions

The `copy_reg` module provides support for the `pickle` and `cPickle` modules. The `copy` module is likely to use this in the future as well. It provides configuration information about object constructors which are not classes. Such constructors may be factory functions or class instances.

constructor (*object*)

Declares *object* to be a valid constructor. If *object* is not callable (and hence not valid as a constructor), raises `TypeError`.

pickle (*type*, *function* [, *constructor*])

Declares that *function* should be used as a “reduction” function for objects of type *type*; *type* must not be a “classic” class object. (Classic classes are handled differently; see the documentation for the `pickle` module for details.) *function* should return either a string or a tuple containing two or three elements.

The optional *constructor* parameter, if provided, is a callable object which can be used to reconstruct the object when called with the tuple of arguments returned by *function* at pickling time. `TypeError` will be raised if *object* is a class or *constructor* is not callable.

See the `pickle` module for more details on the interface expected of *function* and *constructor*.

13.4 shelve — Python object persistence

A “shelf” is a persistent, dictionary-like object. The difference with “dbm” databases is that the values (not the keys!) in a shelf can be essentially arbitrary Python objects — anything that the `pickle` module can handle. This includes most class instances, recursive data types, and objects containing lots of shared sub-objects. The keys are ordinary strings.

open (*filename* [, *flag*='c' [, *protocol*=None [, *writeback*=False]]])

Open a persistent dictionary. The filename specified is the base filename for the underlying database. As a side-effect, an extension may be added to the filename and more than one file may be created. By default, the underlying database file is opened for reading and writing. The optional *flag* parameter has the same interpretation as the *flag* parameter of `anydbm.open`.

By default, version 0 pickles are used to serialize values. The version of the pickle protocol can be specified with the *protocol* parameter. Changed in version 2.3: The *protocol* parameter was added.

By default, mutations to persistent-dictionary mutable entries are not automatically written back. If the optional *writeback* parameter is set to `True`, all entries accessed are cached in memory, and written back at close time; this can make it handier to mutate mutable entries in the persistent dictionary, but, if many entries are accessed, it can consume vast amounts of memory for the cache, and it can make the close operation very slow since all accessed entries are written back (there is no way to determine which accessed entries are mutable, nor which ones were actually mutated).

Shelve objects support all methods supported by dictionaries. This eases the transition from dictionary based scripts to those requiring persistent storage.

One additional method is supported:

sync ()

Write back all entries in the cache if the shelf was opened with *writeback* set to `True`. Also empty the cache and synchronize the persistent dictionary on disk, if feasible. This is called automatically when the shelf is closed with `close()`.

13.4.1 Restrictions

- The choice of which database package will be used (such as `dbm`, `gdbm` or `bsddb`) depends on which interface is available. Therefore it is not safe to open the database directly using `dbm`. The database is also (unfortunately)

subject to the limitations of `dbm`, if it is used — this means that (the pickled representation of) the objects stored in the database should be fairly small, and in rare cases key collisions may cause the database to refuse updates.

- Depending on the implementation, closing a persistent dictionary may or may not be necessary to flush changes to disk. The `__del__` method of the `Shelf` class calls the `close` method, so the programmer generally need not do this explicitly.
- The `shelve` module does not support *concurrent* read/write access to shelved objects. (Multiple simultaneous read accesses are safe.) When a program has a shelf open for writing, no other program should have it open for reading or writing. UNIX file locking can be used to solve this, but this differs across UNIX versions and requires knowledge about the database implementation used.

class `Shelf` (`dict`[, `protocol=None`[, `writeback=False`]])

A subclass of `UserDict.DictMixin` which stores pickled values in the `dict` object.

By default, version 0 pickles are used to serialize values. The version of the pickle protocol can be specified with the `protocol` parameter. See the `pickle` documentation for a discussion of the pickle protocols. Changed in version 2.3: The `protocol` parameter was added.

If the `writeback` parameter is `True`, the object will hold a cache of all entries accessed and write them back to the `dict` at sync and close times. This allows natural operations on mutable entries, but can consume much more memory and make sync and close take a long time.

class `BsddbShelf` (`dict`[, `protocol=None`[, `writeback=False`]])

A subclass of `Shelf` which exposes `first`, `next`, `previous`, `last` and `set_location` which are available in the `bsddb` module but not in other database modules. The `dict` object passed to the constructor must support those methods. This is generally accomplished by calling one of `bsddb.hashopen`, `bsddb.btopen` or `bsddb.rnopen`. The optional `protocol` and `writeback` parameters have the same interpretation as for the `Shelf` class.

class `DbfilenameShelf` (`filename`[, `flag='c'`[, `protocol=None`[, `writeback=False`]]])

A subclass of `Shelf` which accepts a `filename` instead of a dict-like object. The underlying file will be opened using `anydbm.open`. By default, the file will be created and opened for both read and write. The optional `flag` parameter has the same interpretation as for the `open` function. The optional `protocol` and `writeback` parameters have the same interpretation as for the `Shelf` class.

13.4.2 Example

To summarize the interface (key is a string, data is an arbitrary object):


```

import shelve

d = shelve.open(filename) # open -- file may get suffix added by low-level
                           # library

d[key] = data             # store data at key (overwrites old data if
                           # using an existing key)
data = d[key]             # retrieve a COPY of data at key (raise KeyError if no
                           # such key)
del d[key]               # delete data stored at key (raises KeyError
                           # if no such key)
flag = d.has_key(key)     # true if the key exists
klist = d.keys()          # a list of all existing keys (slow!)

# as d was opened WITHOUT writeback=True, beware:
d['xx'] = range(4)        # this works as expected, but...
d['xx'].append(5)         # *this doesn't!* -- d['xx'] is STILL range(4)!!!

# having opened d without writeback=True, you need to code carefully:
temp = d['xx']            # extracts the copy
temp.append(5)            # mutates the copy
d['xx'] = temp            # stores the copy right back, to persist it

# or, d=shelve.open(filename,writeback=True) would let you just code
# d['xx'].append(5) and have it work as expected, BUT it would also
# consume more memory and make the d.close() operation slower.

d.close()                # close it

```

See Also:

[Module anydbm](#) (section 13.6):

Generic interface to dbm-style databases.

[Module bsddb](#) (section 13.11):

BSD db database interface.

[Module dbhash](#) (section 13.10):

Thin layer around the bsddb which provides an open function like the other database modules.

[Module dbm](#) (section 13.8):

Standard UNIX database interface.

[Module dumbdbm](#) (section 13.12):

Portable implementation of the dbm interface.

[Module gdbm](#) (section 13.9):

GNU database interface, based on the dbm interface.

[Module pickle](#) (section 13.1):

Object serialization used by shelve.

[Module cPickle](#) (section 13.2):

High-performance version of [pickle](#).

13.5 marshal — Internal Python object serialization

This module contains functions that can read and write Python values in a binary format. The format is specific to Python, but independent of machine architecture issues (e.g., you can write a Python value to a file on a PC, transport the file to a Sun, and read it back there). Details of the format are undocumented on purpose; it may change between Python versions (although it rarely does).¹¹

This is not a general “persistence” module. For general persistence and transfer of Python objects through RPC calls, see the modules `pickle` and `shelve`. The `marshal` module exists mainly to support reading and writing the “pseudo-compiled” code for Python modules of ‘.pyc’ files. Therefore, the Python maintainers reserve the right to modify the marshal format in backward incompatible ways should the need arise. If you’re serializing and de-serializing Python objects, use the `pickle` module instead — the performance is comparable, version independence is guaranteed, and pickle supports a substantially wider range of objects than marshal.

Warning: The `marshal` module is not intended to be secure against erroneous or maliciously constructed data. Never unmarshal data received from an untrusted or unauthenticated source.

Not all Python object types are supported; in general, only objects whose value is independent from a particular invocation of Python can be written and read by this module. The following types are supported: `None`, integers, long integers, floating point numbers, strings, Unicode objects, tuples, lists, sets, dictionaries, and code objects, where it should be understood that tuples, lists and dictionaries are only supported as long as the values contained therein are themselves supported; and recursive lists and dictionaries should not be written (they will cause infinite loops).

Warning: Some unsupported types such as subclasses of builtins will appear to marshal and unmarshal correctly, but in fact, their type will change and the additional subclass functionality and instance attributes will be lost.

Caveat: On machines where C’s `long int` type has more than 32 bits (such as the DEC Alpha), it is possible to create plain Python integers that are longer than 32 bits. If such an integer is marshaled and read back in on a machine where C’s `long int` type has only 32 bits, a Python long integer object is returned instead. While of a different type, the numeric value is the same. (This behavior is new in Python 2.2. In earlier versions, all but the least-significant 32 bits of the value were lost, and a warning message was printed.)

There are functions that read/write files as well as functions operating on strings.

The module defines these functions:

dump (*value*, *file* [, *version*])

Write the value on the open file. The value must be a supported type. The file must be an open file object such as `sys.stdout` or returned by `open()` or `posix.popen()`. It must be opened in binary mode (`'wb'` or `'w+b'`).

If the value has (or contains an object that has) an unsupported type, a `ValueError` exception is raised — but garbage data will also be written to the file. The object will not be properly read back by `load()`.

New in version 2.4: The *version* argument indicates the data format that `dump` should use (see below).

load (*file*)

Read one value from the open file and return it. If no valid value is read, raise `EOFError`, `ValueError` or `TypeError`. The file must be an open file object opened in binary mode (`'rb'` or `'r+b'`).

Warning: If an object containing an unsupported type was marshalled with `dump()`, `load()` will substitute `None` for the unmarshallable type.

dumps (*value* [, *version*])

Return the string that would be written to a file by `dump(value, file)`. The value must be a supported type. Raise a `ValueError` exception if value has (or contains an object that has) an unsupported type.

New in version 2.4: The *version* argument indicates the data format that `dumps` should use (see below).

¹¹The name of this module stems from a bit of terminology used by the designers of Modula-3 (amongst others), who use the term “marshalling” for shipping of data around in a self-contained form. Strictly speaking, “to marshal” means to convert some data from internal to external form (in an RPC buffer for instance) and “unmarshalling” for the reverse process.

loads (*string*)

Convert the string to a value. If no valid value is found, raise `EOFError`, `ValueError` or `TypeError`. Extra characters in the string are ignored.

In addition, the following constants are defined:

version

Indicates the format that the module uses. Version 0 is the historical format, version 1 (added in Python 2.4) shares interned strings and version 2 (added in Python 2.5) uses a binary format for floating point numbers. The current version is 2.

New in version 2.4.

13.6 anydbm — Generic access to DBM-style databases

`anydbm` is a generic interface to variants of the DBM database — `dbhash` (requires `bsddb`), `gdbm`, or `dbm`. If none of these modules is installed, the slow-but-simple implementation in module `dumbdbm` will be used.

open (*filename*[, *flag*[, *mode*]])

Open the database file *filename* and return a corresponding object.

If the database file already exists, the `whichdb` module is used to determine its type and the appropriate module is used; if it does not exist, the first module listed above that can be imported is used.

The optional *flag* argument can be `'r'` to open an existing database for reading only, `'w'` to open an existing database for reading and writing, `'c'` to create the database if it doesn't exist, or `'n'`, which will always create a new empty database. If not specified, the default value is `'r'`.

The optional *mode* argument is the UNIX mode of the file, used only when the database has to be created. It defaults to octal `0666` (and will be modified by the prevailing `umask`).

exception error

A tuple containing the exceptions that can be raised by each of the supported modules, with a unique exception `anydbm.error` as the first item — the latter is used when `anydbm.error` is raised.

The object returned by `open()` supports most of the same functionality as dictionaries; keys and their corresponding values can be stored, retrieved, and deleted, and the `has_key()` and `keys()` methods are available. Keys and values must always be strings.

The following example records some hostnames and a corresponding title, and then prints out the contents of the database:

```

import anydbm

# Open database, creating it if necessary.
db = anydbm.open('cache', 'c')

# Record some values
db['www.python.org'] = 'Python Website'
db['www.cnn.com'] = 'Cable News Network'

# Loop through contents. Other dictionary methods
# such as .keys(), .values() also work.
for k, v in db.iteritems():
    print k, '\t', v

# Storing a non-string key or value will raise an exception (most
# likely a TypeError).
db['www.yahoo.com'] = 4

# Close when done.
db.close()

```

See Also:

[Module dbhash](#) (section 13.10):

BSD db database interface.

[Module dbm](#) (section 13.8):

Standard UNIX database interface.

[Module dumbdbm](#) (section 13.12):

Portable implementation of the dbm interface.

[Module gdbm](#) (section 13.9):

GNU database interface, based on the dbm interface.

[Module shelve](#) (section 13.4):

General object persistence built on top of the Python dbm interface.

[Module whichdb](#) (section 13.7):

Utility module used to determine the type of an existing database.

13.7 whichdb — Guess which DBM module created a database

The single function in this module attempts to guess which of the several simple database modules available—[dbm](#), [gdbm](#), or [dbhash](#)—should be used to open a given file.

whichdb (*filename*)

Returns one of the following values: `None` if the file can't be opened because it's unreadable or doesn't exist; the empty string (`''`) if the file's format can't be guessed; or a string containing the required module name, such as `'dbm'` or `'gdbm'`.

13.8 dbm — Simple “database” interface

The `dbm` module provides an interface to the UNIX (n)dbm library. Dbm objects behave like mappings (dictionaries), except that keys and values are always strings. Printing a dbm object doesn't print the keys and values, and the `items()` and `values()` methods are not supported.

This module can be used with the “classic” `ndbm` interface, the BSD DB compatibility interface, or the GNU GDBM compatibility interface. On UNIX, the **configure** script will attempt to locate the appropriate header file to simplify building this module.

The module defines the following:

exception error

Raised on dbm-specific errors, such as I/O errors. `KeyError` is raised for general mapping errors like specifying an incorrect key.

library

Name of the `ndbm` implementation library used.

open(filename[, flag[, mode]])

Open a dbm database and return a dbm object. The *filename* argument is the name of the database file (without the `.dir` or `.pag` extensions; note that the BSD DB implementation of the interface will append the extension `.db` and only create one file).

The optional *flag* argument must be one of these values:

Value	Meaning
'r'	Open existing database for reading only (default)
'w'	Open existing database for reading and writing
'c'	Open database for reading and writing, creating it if it doesn't exist
'n'	Always create a new, empty database, open for reading and writing

The optional *mode* argument is the UNIX mode of the file, used only when the database has to be created. It defaults to octal `0666`.

See Also:

Module [anydbm](#) (section 13.6):

Generic interface to dbm-style databases.

Module [gdbm](#) (section 13.9):

Similar interface to the GNU GDBM library.

Module [whichdb](#) (section 13.7):

Utility module used to determine the type of an existing database.

13.9 gdbm — GNU's reinterpretation of dbm

This module is quite similar to the [dbm](#) module, but uses `gdbm` instead to provide some additional functionality. Please note that the file formats created by `gdbm` and `dbm` are incompatible.

The `gdbm` module provides an interface to the GNU DBM library. `gdbm` objects behave like mappings (dictionaries), except that keys and values are always strings. Printing a `gdbm` object doesn't print the keys and values, and the `items()` and `values()` methods are not supported.

The module defines the following constant and functions:

exception error

Raised on `gdbm`-specific errors, such as I/O errors. `KeyError` is raised for general mapping errors like specifying an incorrect key.

open(filename, [flag, [mode]])

Open a `gdbm` database and return a `gdbm` object. The *filename* argument is the name of the database file.

The optional *flag* argument can be `'r'` (to open an existing database for reading only — default), `'w'` (to open an existing database for reading and writing), `'c'` (which creates the database if it doesn't exist), or `'n'` (which always creates a new empty database).

The following additional characters may be appended to the flag to control how the database is opened:

- `'f'` — Open the database in fast mode. Writes to the database will not be synchronized.
- `'s'` — Synchronized mode. This will cause changes to the database will be immediately written to the file.
- `'u'` — Do not lock database.

Not all flags are valid for all versions of `gdbm`. The module constant `open_flags` is a string of supported flag characters. The exception `error` is raised if an invalid flag is specified.

The optional *mode* argument is the UNIX mode of the file, used only when the database has to be created. It defaults to octal `0666`.

In addition to the dictionary-like methods, `gdbm` objects have the following methods:

firstkey()

It's possible to loop over every key in the database using this method and the `nextkey()` method. The traversal is ordered by `gdbm`'s internal hash values, and won't be sorted by the key values. This method returns the starting key.

nextkey(key)

Returns the key that follows *key* in the traversal. The following code prints every key in the database `db`, without having to create a list in memory that contains them all:

```
k = db.firstkey()
while k != None:
    print k
    k = db.nextkey(k)
```

reorganize()

If you have carried out a lot of deletions and would like to shrink the space used by the `gdbm` file, this routine will reorganize the database. `gdbm` will not shorten the length of a database file except by using this reorganization; otherwise, deleted file space will be kept and reused as new (key, value) pairs are added.

sync()

When the database has been opened in fast mode, this method forces any unwritten data to be written to the disk.

See Also:

Module [anydbm](#) (section 13.6):

Generic interface to dbm-style databases.

Module [whichdb](#) (section 13.7):

Utility module used to determine the type of an existing database.

13.10 `dbhash` — DBM-style interface to the BSD database library

The `dbhash` module provides a function to open databases using the BSD `db` library. This module mirrors the interface of the other Python database modules that provide access to DBM-style databases. The `bsddb` module is required to use `dbhash`.

This module provides an exception and a function:

exception error

Exception raised on database errors other than `KeyError`. It is a synonym for `bsddb.error`.

open (*path* [, *flag* [, *mode*]])

Open a db database and return the database object. The *path* argument is the name of the database file.

The *flag* argument can be `'r'` (the default), `'w'`, `'c'` (which creates the database if it doesn't exist), or `'n'` (which always creates a new empty database). For platforms on which the BSD db library supports locking, an `'l'` can be appended to indicate that locking should be used.

The optional *mode* parameter is used to indicate the UNIX permission bits that should be set if a new database must be created; this will be masked by the current umask value for the process.

See Also:

Module [anydbm](#) (section 13.6):

Generic interface to dbm-style databases.

Module [bsddb](#) (section 13.11):

Lower-level interface to the BSD db library.

Module [whichdb](#) (section 13.7):

Utility module used to determine the type of an existing database.

13.10.1 Database Objects

The database objects returned by `open()` provide the methods common to all the DBM-style databases and mapping objects. The following methods are available in addition to the standard methods.

first()

It's possible to loop over every key/value pair in the database using this method and the `next()` method. The traversal is ordered by the databases internal hash values, and won't be sorted by the key values. This method returns the starting key.

last()

Return the last key/value pair in a database traversal. This may be used to begin a reverse-order traversal; see `previous()`.

next()

Returns the key next key/value pair in a database traversal. The following code prints every key in the database `db`, without having to create a list in memory that contains them all:

```
print db.first()
for i in xrange(1, len(db)):
    print db.next()
```

previous()

Returns the previous key/value pair in a forward-traversal of the database. In conjunction with `last()`, this may be used to implement a reverse-order traversal.

sync()

This method forces any unwritten data to be written to the disk.

13.11 bsddb — Interface to Berkeley DB library

The `bsddb` module provides an interface to the Berkeley DB library. Users can create hash, btree or record based library files using the appropriate `open` call. `Bsddb` objects behave generally like dictionaries. Keys and values must be strings, however, so to use other objects as keys or to store other kinds of objects the user must serialize them somehow, typically using `marshal.dumps()` or `pickle.dumps()`.

The `bsddb` module requires a Berkeley DB library version from 3.3 thru 4.5.

See Also:

<http://pybsddb.sourceforge.net/>

The website with documentation for the `bsddb.db` Python Berkeley DB interface that closely mirrors the object oriented interface provided in Berkeley DB 3 and 4.

<http://www.oracle.com/database/berkeley-db/>

The Berkeley DB library.

A more modern DB, `DBEnv` and `DBSequence` object interface is available in the `bsddb.db` module which closely matches the Berkeley DB C API documented at the above URLs. Additional features provided by the `bsddb.db` API include fine tuning, transactions, logging, and multiprocess concurrent database access.

The following is a description of the legacy `bsddb` interface compatible with the old Python `bsddb` module. Starting in Python 2.5 this interface should be safe for multithreaded access. The `bsddb.db` API is recommended for threading users as it provides better control.

The `bsddb` module defines the following functions that create objects that access the appropriate type of Berkeley DB file. The first two arguments of each function are the same. For ease of portability, only the first two arguments should be used in most instances.

hashopen (*filename* [, *flag* [, *mode* [, *pgsize* [, *ffactor* [, *nelem* [, *cache*size [, *lorder* [, *hflags*]]]]]]]])

Open the hash format file named *filename*. Files never intended to be preserved on disk may be created by passing `None` as the *filename*. The optional *flag* identifies the mode used to open the file. It may be 'r' (read only), 'w' (read-write), 'c' (read-write - create if necessary; the default) or 'n' (read-write - truncate to zero length). The other arguments are rarely used and are just passed to the low-level `dbopen()` function. Consult the Berkeley DB documentation for their use and interpretation.

btopen (*filename* [, *flag* [, *mode* [, *btflags* [, *cache*size [, *maxkey*page [, *minkey*page [, *pgsize* [, *lorder*]]]]]]]])

Open the btree format file named *filename*. Files never intended to be preserved on disk may be created by passing `None` as the *filename*. The optional *flag* identifies the mode used to open the file. It may be 'r' (read only), 'w' (read-write), 'c' (read-write - create if necessary; the default) or 'n' (read-write - truncate to zero length). The other arguments are rarely used and are just passed to the low-level `dbopen` function. Consult the Berkeley DB documentation for their use and interpretation.

rnopen (*filename* [, *flag* [, *mode* [, *rnflags* [, *cache*size [, *pgsize* [, *lorder* [, *rlen* [, *delim* [, *source* [, *pad*]]]]]]]]]])

Open a DB record format file named *filename*. Files never intended to be preserved on disk may be created by passing `None` as the *filename*. The optional *flag* identifies the mode used to open the file. It may be 'r' (read only), 'w' (read-write), 'c' (read-write - create if necessary; the default) or 'n' (read-write - truncate to zero length). The other arguments are rarely used and are just passed to the low-level `dbopen` function. Consult the Berkeley DB documentation for their use and interpretation.

Note: Beginning in 2.3 some UNIX versions of Python may have a `bsddb185` module. This is present *only* to allow backwards compatibility with systems which ship with the old Berkeley DB 1.85 database library. The `bsddb185` module should never be used directly in new code.

See Also:

Module `dbhash` (section 13.10):

DBM-style interface to the `bsddb`

13.11.1 Hash, BTree and Record Objects

Once instantiated, hash, btree and record objects support the same methods as dictionaries. In addition, they support the methods listed below. Changed in version 2.3.1: Added dictionary methods.

close ()

Close the underlying file. The object can no longer be accessed. Since there is no `open` method for these objects, to open the file again a new `bsddb` module `open` function must be called.

keys()

Return the list of keys contained in the DB file. The order of the list is unspecified and should not be relied on. In particular, the order of the list returned is different for different file formats.

has_key(key)

Return 1 if the DB file contains the argument as a key.

set_location(key)

Set the cursor to the item indicated by *key* and return a tuple containing the key and its value. For binary tree databases (opened using `bopen()`), if *key* does not actually exist in the database, the cursor will point to the next item in sorted order and return that key and value. For other databases, `KeyError` will be raised if *key* is not found in the database.

first()

Set the cursor to the first item in the DB file and return it. The order of keys in the file is unspecified, except in the case of B-Tree databases. This method raises `bsddb.error` if the database is empty.

next()

Set the cursor to the next item in the DB file and return it. The order of keys in the file is unspecified, except in the case of B-Tree databases.

previous()

Set the cursor to the previous item in the DB file and return it. The order of keys in the file is unspecified, except in the case of B-Tree databases. This is not supported on hashtable databases (those opened with `hashopen()`).

last()

Set the cursor to the last item in the DB file and return it. The order of keys in the file is unspecified. This is not supported on hashtable databases (those opened with `hashopen()`). This method raises `bsddb.error` if the database is empty.

sync()

Synchronize the database on disk.

Example:

```

>>> import bsddb
>>> db = bsddb.btopen('/tmp/spam.db', 'c')
>>> for i in range(10): db['%d'%i] = '%d'% (i*i)
...
>>> db['3']
'9'
>>> db.keys()
['0', '1', '2', '3', '4', '5', '6', '7', '8', '9']
>>> db.first()
('0', '0')
>>> db.next()
('1', '1')
>>> db.last()
('9', '81')
>>> db.set_location('2')
('2', '4')
>>> db.previous()
('1', '1')
>>> for k, v in db.iteritems():
...     print k, v
0 0
1 1
2 4
3 9
4 16
5 25
6 36
7 49
8 64
9 81
>>> '8' in db
True
>>> db.sync()
0

```

13.12 dumbdbm — Portable DBM implementation

Note: The `dumbdbm` module is intended as a last resort fallback for the `anydbm` module when no more robust module is available. The `dumbdbm` module is not written for speed and is not nearly as heavily used as the other database modules.

The `dumbdbm` module provides a persistent dictionary-like interface which is written entirely in Python. Unlike other modules such as `gdbm` and `bsddb`, no external library is required. As with other persistent mappings, the keys and values must always be strings.

The module defines the following:

exception error

Raised on `dumbdbm`-specific errors, such as I/O errors. `KeyError` is raised for general mapping errors like specifying an incorrect key.

open (filename[, flag[, mode]])

Open a `dumbdbm` database and return a `dumbdbm` object. The *filename* argument is the basename of the database file (without any specific extensions). When a `dumbdbm` database is created, files with `.dat` and `.dir`

extensions are created.

The optional *flag* argument is currently ignored; the database is always opened for update, and will be created if it does not exist.

The optional *mode* argument is the UNIX mode of the file, used only when the database has to be created. It defaults to octal 0666 (and will be modified by the prevailing umask). Changed in version 2.2: The *mode* argument was ignored in earlier versions.

See Also:

[Module `anydbm`](#) (section 13.6):

Generic interface to dbm-style databases.

[Module `dbm`](#) (section 13.8):

Similar interface to the DBM/NDBM library.

[Module `gdbm`](#) (section 13.9):

Similar interface to the GNU GDBM library.

[Module `shelve`](#) (section 13.4):

Persistence module which stores non-string data.

[Module `whichdb`](#) (section 13.7):

Utility module used to determine the type of an existing database.

13.12.1 Dumbdbm Objects

In addition to the methods provided by the `UserDict.DictMixin` class, `dumbdbm` objects provide the following methods.

`sync()`

Synchronize the on-disk directory and data files. This method is called by the `sync` method of `Shelve` objects.

13.13 `sqlite3` — DB-API 2.0 interface for SQLite databases

New in version 2.5.

SQLite is a C library that provides a lightweight disk-based database that doesn't require a separate server process and allows accessing the database using a nonstandard variant of the SQL query language. Some applications can use SQLite for internal data storage. It's also possible to prototype an application using SQLite and then port the code to a larger database such as PostgreSQL or Oracle.

`pysqlite` was written by Gerhard Häring and provides a SQL interface compliant with the DB-API 2.0 specification described by PEP 249.

To use the module, you must first create a `Connection` object that represents the database. Here the data will be stored in the `'/tmp/example'` file:

```
conn = sqlite3.connect('/tmp/example')
```

You can also supply the special name `':memory:'` to create a database in RAM.

Once you have a `Connection`, you can create a `Cursor` object and call its `execute()` method to perform SQL commands:

```

c = conn.cursor()

# Create table
c.execute("""create table stocks
(date text, trans text, symbol text,
qty real, price real)""")

# Insert a row of data
c.execute("""insert into stocks
            values ('2006-01-05','BUY','RHAT',100,35.14) """)

# Save (commit) the changes
conn.commit()

# We can also close the cursor if we are done with it
c.close()

```

Usually your SQL operations will need to use values from Python variables. You shouldn't assemble your query using Python's string operations because doing so is insecure; it makes your program vulnerable to an SQL injection attack.

Instead, use the DB-API's parameter substitution. Put '?' as a placeholder wherever you want to use a value, and then provide a tuple of values as the second argument to the cursor's `execute()` method. (Other database modules may use a different placeholder, such as '%s' or ':1'.) For example:

```

# Never do this -- insecure!
symbol = 'IBM'
c.execute("... where symbol = '%s'" % symbol)

# Do this instead
t = (symbol,)
c.execute('select * from stocks where symbol=?', t)

# Larger example
for t in (('2006-03-28', 'BUY', 'IBM', 1000, 45.00),
          ('2006-04-05', 'BUY', 'MSOFT', 1000, 72.00),
          ('2006-04-06', 'SELL', 'IBM', 500, 53.00),
          ):
    c.execute('insert into stocks values (?,?,?,?,?)', t)

```

To retrieve data after executing a SELECT statement, you can either treat the cursor as an iterator, call the cursor's `fetchone()` method to retrieve a single matching row, or call `fetchall()` to get a list of the matching rows.

This example uses the iterator form:

```

>>> c = conn.cursor()
>>> c.execute('select * from stocks order by price')
>>> for row in c:
...     print row
...
(u'2006-01-05', u'BUY', u'RHAT', 100, 35.140000000000001)
(u'2006-03-28', u'BUY', u'IBM', 1000, 45.0)
(u'2006-04-06', u'SELL', u'IBM', 500, 53.0)
(u'2006-04-05', u'BUY', u'MSOFT', 1000, 72.0)
>>>

```

See Also:

<http://www.pysqlite.org>

The pysqlite web page.

<http://www.sqlite.org>

The SQLite web page; the documentation describes the syntax and the available data types for the supported SQL dialect.

PEP 249, “*Database API Specification 2.0*”

PEP written by Marc-André Lemburg.

13.13.1 Module functions and constants

PARSE_DECLTYPES

This constant is meant to be used with the *detect_types* parameter of the `connect` function.

Setting it makes the `sqlite3` module parse the declared type for each column it returns. It will parse out the first word of the declared type, i. e. for “integer primary key”, it will parse out “integer”. Then for that column, it will look into the converters dictionary and use the converter function registered for that type there. Converter names are case-sensitive!

PARSE_COLNAMES

This constant is meant to be used with the *detect_types* parameter of the `connect` function.

Setting this makes the SQLite interface parse the column name for each column it returns. It will look for a string formed [mytype] in there, and then decide that ‘mytype’ is the type of the column. It will try to find an entry of ‘mytype’ in the converters dictionary and then use the converter function found there to return the value. The column name found in `cursor.description` is only the first word of the column name, i. e. if you use something like ‘as “x [datetime]”’ in your SQL, then we will parse out everything until the first blank for the column name: the column name would simply be “x”.

connect (*database* [, *timeout*, *isolation_level*, *detect_types*, *factory*])

Opens a connection to the SQLite database file *database*. You can use “:memory:” to open a database connection to a database that resides in RAM instead of on disk.

When a database is accessed by multiple connections, and one of the processes modifies the database, the SQLite database is locked until that transaction is committed. The *timeout* parameter specifies how long the connection should wait for the lock to go away until raising an exception. The default for the timeout parameter is 5.0 (five seconds).

For the *isolation_level* parameter, please see the `isolation_level` property of `Connection` objects in section 13.13.2.

SQLite natively supports only the types TEXT, INTEGER, FLOAT, BLOB and NULL. If you want to use other types, like you have to add support for them yourself. The *detect_types* parameter and the using custom **converters** registered with the module-level `register_converter` function allow you to easily do that.

detect_types defaults to 0 (i. e. off, no type detection), you can set it to any combination of `PARSE_DECLTYPES` and `PARSE_COLNAMES` to turn type detection on.

By default, the `sqlite3` module uses its `Connection` class for the connect call. You can, however, subclass the `Connection` class and make `connect` use your class instead by providing your class for the *factory* parameter.

Consult the section 13.13.4 of this manual for details.

The `sqlite3` module internally uses a statement cache to avoid SQL parsing overhead. If you want to explicitly set the number of statements that are cached for the connection, you can set the *cached_statements* parameter. The currently implemented default is to cache 100 statements.

register_converter (*typename, callable*)

Registers a callable to convert a bytestring from the database into a custom Python type. The callable will be invoked for all database values that are of the type *typename*. Confer the parameter *detect_types* of the `connect` function for how the type detection works. Note that the case of *typename* and the name of the type in your query must match!

register_adapter (*type, callable*)

Registers a callable to convert the custom Python type *type* into one of SQLite's supported types. The callable *callable* accepts as single parameter the Python value, and must return a value of the following types: int, long, float, str (UTF-8 encoded), unicode or buffer.

complete_statement (*sql*)

Returns True if the string *sql* contains one or more complete SQL statements terminated by semicolons. It does not verify that the SQL is syntactically correct, only that there are no unclosed string literals and the statement is terminated by a semicolon.

This can be used to build a shell for SQLite, as in the following example:

```
_statement.py
```

enable_callback_tracebacks (*flag*)

By default you will not get any tracebacks in user-defined functions, aggregates, converters, authorizer callbacks etc. If you want to debug them, you can call this function with *flag* as True. Afterwards, you will get tracebacks from callbacks on `sys.stderr`. Use False to disable the feature again.

13.13.2 Connection Objects

A `Connection` instance has the following attributes and methods:

isolation_level

Get or set the current isolation level. None for autocommit mode or one of "DEFERRED", "IMMEDIATE" or "EXCLUSIVE". See "Controlling Transactions", section 13.13.5, for a more detailed explanation.

cursor ([*cursorClass*])

The cursor method accepts a single optional parameter *cursorClass*. If supplied, this must be a custom cursor class that extends `sqlite3.Cursor`.

execute (*sql*, [*parameters*])

This is a nonstandard shortcut that creates an intermediate cursor object by calling the cursor method, then calls the cursor's `execute` method with the parameters given.

executemany (*sql*, [*parameters*])

This is a nonstandard shortcut that creates an intermediate cursor object by calling the cursor method, then calls the cursor's `executemany` method with the parameters given.

executescript (*sql_script*)

This is a nonstandard shortcut that creates an intermediate cursor object by calling the cursor method, then calls the cursor's `executescript` method with the parameters given.

create_function (*name*, *num_params*, *func*)

Creates a user-defined function that you can later use from within SQL statements under the function name *name*. *num_params* is the number of parameters the function accepts, and *func* is a Python callable that is called as the SQL function.

The function can return any of the types supported by SQLite: unicode, str, int, long, float, buffer and None.

Example:

```
import sqlite3
import md5

def md5sum(t):
    return md5.md5(t).hexdigest()

con = sqlite3.connect(":memory:")
con.create_function("md5", 1, md5sum)
cur = con.cursor()
cur.execute("select md5(?)", ("foo",))
print cur.fetchone()[0]
```

create_aggregate (*name*, *num_params*, *aggregate_class*)

Creates a user-defined aggregate function.

The aggregate class must implement a `step` method, which accepts the number of parameters *num_params*, and a `finalize` method which will return the final result of the aggregate.

The `finalize` method can return any of the types supported by SQLite: unicode, str, int, long, float, buffer and None.

Example:

```
import sqlite3

class MySum:
    def __init__(self):
        self.count = 0

    def step(self, value):
        self.count += value

    def finalize(self):
        return self.count

con = sqlite3.connect(":memory:")
con.create_aggregate("mysum", 1, MySum)
cur = con.cursor()
cur.execute("create table test(i)")
cur.execute("insert into test(i) values (1)")
cur.execute("insert into test(i) values (2)")
cur.execute("select mysum(i) from test")
print cur.fetchone()[0]
```

create_collation (*name*, *callable*)

Creates a collation with the specified *name* and *callable*. The callable will be passed two string arguments. It should return -1 if the first is ordered lower than the second, 0 if they are ordered equal and 1 if the first is ordered higher than the second. Note that this controls sorting (ORDER BY in SQL) so your comparisons don't affect other SQL operations.

Note that the callable will get its parameters as Python bytestrings, which will normally be encoded in UTF-8.

The following example shows a custom collation that sorts "the wrong way":

`_reverse.py`

To remove a collation, call `create_collation` with `None` as callable:

```
con.create_collation("reverse", None)
```

interrupt()

You can call this method from a different thread to abort any queries that might be executing on the connection. The query will then abort and the caller will get an exception.

set_authorizer(authorizer_callback)

This routine registers a callback. The callback is invoked for each attempt to access a column of a table in the database. The callback should return `SQLITE_OK` if access is allowed, `SQLITE_DENY` if the entire SQL statement should be aborted with an error and `SQLITE_IGNORE` if the column should be treated as a NULL value. These constants are available in the `sqlite3` module.

The first argument to the callback signifies what kind of operation is to be authorized. The second and third argument will be arguments or `None` depending on the first argument. The 4th argument is the name of the database ("main", "temp", etc.) if applicable. The 5th argument is the name of the inner-most trigger or view that is responsible for the access attempt or `None` if this access attempt is directly from input SQL code.

Please consult the SQLite documentation about the possible values for the first argument and the meaning of the second and third argument depending on the first one. All necessary constants are available in the `sqlite3` module.

row_factory

You can change this attribute to a callable that accepts the cursor and the original row as a tuple and will return the real result row. This way, you can implement more advanced ways of returning results, such as returning an object that can also access columns by name.

Example:

`_factory.py`

If returning a tuple doesn't suffice and you want name-based access to columns, you should consider setting `row_factory` to the highly-optimized `sqlite3.Row` type. `Row` provides both index-based and case-insensitive name-based access to columns with almost no memory overhead. It will probably be better than your own custom dictionary-based approach or even a `db_row` based solution.

text_factory

Using this attribute you can control what objects are returned for the TEXT data type. By default, this attribute is set to `unicode` and the `sqlite3` module will return Unicode objects for TEXT. If you want to return bytestrings instead, you can set it to `str`.

For efficiency reasons, there's also a way to return Unicode objects only for non-ASCII data, and bytestrings otherwise. To activate it, set this attribute to `sqlite3.OptimizedUnicode`.

You can also set it to any other callable that accepts a single bytestring parameter and returns the resulting object.

See the following example code for illustration:

`_factory.py`

total_changes

Returns the total number of database rows that have been modified, inserted, or deleted since the database connection was opened.

13.13.3 Cursor Objects

A `Cursor` instance has the following attributes and methods:

execute (*sql*, [*parameters*])

Executes a SQL statement. The SQL statement may be parametrized (i. e. placeholders instead of SQL literals). The `sqlite3` module supports two kinds of placeholders: question marks (qmark style) and named placeholders (named style).

This example shows how to use parameters with qmark style:

```
.1.py
```

This example shows how to use the named style:

```
.2.py
```

`execute()` will only execute a single SQL statement. If you try to execute more than one statement with it, it will raise a `Warning`. Use `executescript()` if you want to execute multiple SQL statements with one call.

executemany (*sql*, *seq_of_parameters*)

Executes a SQL command against all parameter sequences or mappings found in the sequence *sql*. The `sqlite3` module also allows using an iterator yielding parameters instead of a sequence.

```
.1.py
```

Here's a shorter example using a generator:

```
.2.py
```

executescript (*sql_script*)

This is a nonstandard convenience method for executing multiple SQL statements at once. It issues a `COMMIT` statement first, then executes the SQL script it gets as a parameter.

sql_script can be a bytestring or a Unicode string.

Example:

```
import sqlite3

con = sqlite3.connect(":memory:")
cur = con.cursor()
cur.executescript("""
    create table person(
        firstname,
        lastname,
        age
    );

    create table book(
        title,
        author,
        published
    );

    insert into book(title, author, published)
    values (
        'Dirk Gently''s Holistic Detective Agency',
```

```

        'Douglas Adams',
        1987
    );
    """

```

rowcount

Although the `Cursor` class of the `sqlite3` module implements this attribute, the database engine's own support for the determination of "rows affected"/"rows selected" is quirky.

For `SELECT` statements, `rowcount` is always `None` because we cannot determine the number of rows a query produced until all rows were fetched.

For `DELETE` statements, SQLite reports `rowcount` as 0 if you make a `DELETE FROM table` without any condition.

For `executemany` statements, the number of modifications are summed up into `rowcount`.

As required by the Python DB API Spec, the `rowcount` attribute "is -1 in case no `executeXX()` has been performed on the cursor or the rowcount of the last operation is not determinable by the interface".

13.13.4 SQLite and Python types

Introduction

SQLite natively supports the following types: `NULL`, `INTEGER`, `REAL`, `TEXT`, `BLOB`.

The following Python types can thus be sent to SQLite without any problem:

Python type	SQLite type
<code>None</code>	<code>NULL</code>
<code>int</code>	<code>INTEGER</code>
<code>long</code>	<code>INTEGER</code>
<code>float</code>	<code>REAL</code>
<code>str</code> (UTF8-encoded)	<code>TEXT</code>
<code>unicode</code>	<code>TEXT</code>
<code>buffer</code>	<code>BLOB</code>

This is how SQLite types are converted to Python types by default:

SQLite type	Python type
<code>NULL</code>	<code>None</code>
<code>INTEGER</code>	<code>int</code> or <code>long</code> , depending on size
<code>REAL</code>	<code>float</code>
<code>TEXT</code>	depends on <code>text_factory</code> , <code>unicode</code> by default
<code>BLOB</code>	<code>buffer</code>

The type system of the `sqlite3` module is extensible in two ways: you can store additional Python types in a SQLite database via object adaptation, and you can let the `sqlite3` module convert SQLite types to different Python types via converters.

Using adapters to store additional Python types in SQLite databases

As described before, SQLite supports only a limited set of types natively. To use other Python types with SQLite, you must **adapt** them to one of the `sqlite3` module's supported types for SQLite: one of `NoneType`, `int`, `long`, `float`, `str`, `unicode`, `buffer`.

The `sqlite3` module uses Python object adaptation, as described in PEP 246 for this. The protocol to use is `PrepareProtocol`.

There are two ways to enable the `sqlite3` module to adapt a custom Python type to one of the supported ones.

Letting your object adapt itself This is a good approach if you write the class yourself. Let's suppose you have a class like this:

```
class Point(object):
    def __init__(self, x, y):
        self.x, self.y = x, y
```

Now you want to store the point in a single SQLite column. First you'll have to choose one of the supported types first to be used for representing the point. Let's just use `str` and separate the coordinates using a semicolon. Then you need to give your class a method `__conform__(self, protocol)` which must return the converted value. The parameter *protocol* will be `PrepareProtocol`.

`_point.1.py`

Registering an adapter callable The other possibility is to create a function that converts the type to the string representation and register the function with `register_adapter`.

Note: The type/class to adapt must be a new-style class, i. e. it must have `object` as one of its bases.

`_point.2.py`

The `sqlite3` module has two default adapters for Python's built-in `datetime.date` and `datetime.datetime` types. Now let's suppose we want to store `datetime.datetime` objects not in ISO representation, but as a UNIX timestamp.

`_datetime.py`

Converting SQLite values to custom Python types

Writing an adapter lets you send custom Python types to SQLite. But to make it really useful we need to make the Python to SQLite to Python roundtrip work.

Enter converters.

Let's go back to the `Point` class. We stored the `x` and `y` coordinates separated via semicolons as strings in SQLite.

First, we'll define a converter function that accepts the string as a parameter and constructs a `Point` object from it.

Note: Converter functions **always** get called with a string, no matter under which data type you sent the value to SQLite.

Note: Converter names are looked up in a case-sensitive manner.

```
def convert_point(s):
    x, y = map(float, s.split(";"))
    return Point(x, y)
```

Now you need to make the `sqlite3` module know that what you select from the database is actually a point. There are two ways of doing this:

- Implicitly via the declared type
- Explicitly via the column name

Both ways are described in “Module Constants”, section 13.13.1, in the entries for the constants `PARSE_DECLTYPES` and `PARSE_COLNAMES`.

The following example illustrates both approaches.

```
_point.py
```

Default adapters and converters

There are default adapters for the date and datetime types in the `datetime` module. They will be sent as ISO dates/ISO timestamps to SQLite.

The default converters are registered under the name “date” for `datetime.date` and under the name “timestamp” for `datetime.datetime`.

This way, you can use date/timestamps from Python without any additional fiddling in most cases. The format of the adapters is also compatible with the experimental SQLite date/time functions.

The following example demonstrates this.

```
_datetime.py
```

13.13.5 Controlling Transactions

By default, the `sqlite3` module opens transactions implicitly before a Data Modification Language (DML) statement (i.e. `INSERT/UPDATE/DELETE/REPLACE`), and commits transactions implicitly before a non-DML, non-query statement (i. e. anything other than `SELECT/INSERT/UPDATE/DELETE/REPLACE`).

So if you are within a transaction and issue a command like `CREATE TABLE ...`, `VACUUM`, `PRAGMA`, the `sqlite3` module will commit implicitly before executing that command. There are two reasons for doing that. The first is that some of these commands don’t work within transactions. The other reason is that `pysqlite` needs to keep track of the transaction state (if a transaction is active or not).

You can control which kind of “BEGIN” statements `pysqlite` implicitly executes (or none at all) via the *isolation_level* parameter to the `connect` call, or via the `isolation_level` property of connections.

If you want **autocommit mode**, then set `isolation_level` to `None`.

Otherwise leave it at its default, which will result in a plain “BEGIN” statement, or set it to one of SQLite’s supported isolation levels: `DEFERRED`, `IMMEDIATE` or `EXCLUSIVE`.

As the `sqlite3` module needs to keep track of the transaction state, you should not use `OR ROLLBACK` or `ON CONFLICT ROLLBACK` in your SQL. Instead, catch the `IntegrityError` and call the `rollback` method of the connection yourself.

13.13.6 Using pysqlite efficiently

Using shortcut methods

Using the nonstandard `execute`, `executemany` and `executescript` methods of the `Connection` object, your code can be written more concisely because you don’t have to create the (often superfluous) `Cursor` objects explicitly. Instead, the `Cursor` objects are created implicitly and these shortcut methods return the cursor objects. This

way, you can execute a `SELECT` statement and iterate over it directly using only a single call on the `Connection` object.

`_methods.py`

Accessing columns by name instead of by index

One useful feature of the `sqlite3` module is the builtin `sqlite3.Row` class designed to be used as a row factory.

Rows wrapped with this class can be accessed both by index (like tuples) and case-insensitively by name:

```
import sqlite3

con = sqlite3.connect("mydb")
con.row_factory = sqlite3.Row

cur = con.cursor()
cur.execute("select name_last, age from people")
for row in cur:
    assert row[0] == row["name_last"]
    assert row["name_last"] == row["nAmE_lAsT"]
    assert row[1] == row["age"]
    assert row[1] == row["AgE"]
```


Generic Operating System Services

The modules described in this chapter provide interfaces to operating system features that are available on (almost) all operating systems, such as files and a clock. The interfaces are generally modeled after the UNIX or C interfaces, but they are available on most other systems as well. Here's an overview:

<code>os</code>	Miscellaneous operating system interfaces.
<code>time</code>	Time access and conversions.
<code>optparse</code>	More convenient, flexible, and powerful command-line parsing library.
<code>getopt</code>	Portable parser for command line options; support both short and long option names.
<code>logging</code>	Logging module for Python based on PEP 282.
<code>getpass</code>	Portable reading of passwords and retrieval of the userid.
<code>curses</code>	An interface to the curses library, providing portable terminal handling.
<code>curses.textpad</code>	Emacs-like input editing in a curses window.
<code>curses.wrapper</code>	Terminal configuration wrapper for curses programs.
<code>curses.ascii</code>	Constants and set-membership functions for ASCII characters.
<code>curses.panel</code>	A panel stack extension that adds depth to curses windows.
<code>platform</code>	Retrieves as much platform identifying data as possible.
<code>errno</code>	Standard errno system symbols.
<code>ctypes</code>	A foreign function library for Python.

14.1 `os` — Miscellaneous operating system interfaces

This module provides a more portable way of using operating system dependent functionality than importing a operating system dependent built-in module like `posix` or `nt`.

This module searches for an operating system dependent built-in module like `mac` or `posix` and exports the same functions and data as found there. The design of all Python's built-in operating system dependent modules is such that as long as the same functionality is available, it uses the same interface; for example, the function `os.stat(path)` returns stat information about `path` in the same format (which happens to have originated with the POSIX interface).

Extensions peculiar to a particular operating system are also available through the `os` module, but using them is of course a threat to portability!

Note that after the first time `os` is imported, there is *no* performance penalty in using functions from `os` instead of directly from the operating system dependent built-in module, so there should be *no* reason not to use `os`!

exception error

This exception is raised when a function returns a system-related error (not for illegal argument types or other incidental errors). This is also known as the built-in exception `OSError`. The accompanying value is a pair containing the numeric error code from `errno` and the corresponding string, as would be printed by the C function `perror()`. See the module `errno`, which contains names for the error codes defined by the underlying operating system.

When exceptions are classes, this exception carries two attributes, `errno` and `strerror`. The first holds the value of the C `errno` variable, and the latter holds the corresponding error message from `strerror()`. For exceptions that involve a file system path (such as `chdir()` or `unlink()`), the exception instance will contain a third attribute, `filename`, which is the file name passed to the function.

name

The name of the operating system dependent module imported. The following names have currently been registered: `'posix'`, `'nt'`, `'mac'`, `'os2'`, `'ce'`, `'java'`, `'riscos'`.

path

The corresponding operating system dependent standard module for pathname operations, such as `posixpath` or `macpath`. Thus, given the proper imports, `os.path.split(file)` is equivalent to but more portable than `posixpath.split(file)`. Note that this is also an importable module: it may be imported directly as `os.path`.

14.1.1 Process Parameters

These functions and data items provide information and operate on the current process and user.

environ

A mapping object representing the string environment. For example, `environ['HOME']` is the pathname of your home directory (on some platforms), and is equivalent to `getenv("HOME")` in C.

This mapping is captured the first time the `os` module is imported, typically during Python startup as part of processing `'site.py'`. Changes to the environment made after this time are not reflected in `os.environ`, except for changes made by modifying `os.environ` directly.

If the platform supports the `putenv()` function, this mapping may be used to modify the environment as well as query the environment. `putenv()` will be called automatically when the mapping is modified. **Note:** Calling `putenv()` directly does not change `os.environ`, so it's better to modify `os.environ`. **Note:** On some platforms, including FreeBSD and Mac OS X, setting `environ` may cause memory leaks. Refer to the system documentation for `putenv()`.

If `putenv()` is not provided, a modified copy of this mapping may be passed to the appropriate process-creation functions to cause child processes to use a modified environment.

If the platform supports the `unsetenv()` function, you can delete items in this mapping to unset environment variables. `unsetenv()` will be called automatically when an item is deleted from `os.environ`.

chdir(path)

fchdir(fd)

getcwd()

These functions are described in “Files and Directories” (section 14.1.4).

ctermid()

Return the filename corresponding to the controlling terminal of the process. Availability: UNIX.

getegid()

Return the effective group id of the current process. This corresponds to the ‘set id’ bit on the file being executed in the current process. Availability: UNIX.

geteuid()

Return the current process’ effective user id. Availability: UNIX.

getgid()

Return the real group id of the current process. Availability: UNIX.

getgroups()

Return list of supplemental group ids associated with the current process. Availability: UNIX.

getlogin()

Return the name of the user logged in on the controlling terminal of the process. For most purposes, it is more useful to use the environment variable LOGNAME to find out who the user is, or `pwd.getpuid(os.getuid())[0]` to get the login name of the currently effective user ID. Availability: UNIX.

getpgid(*pid*)

Return the process group id of the process with process id *pid*. If *pid* is 0, the process group id of the current process is returned. Availability: UNIX. New in version 2.3.

getpgrp()

Return the id of the current process group. Availability: UNIX.

getpid()

Return the current process id. Availability: UNIX, Windows.

getppid()

Return the parent's process id. Availability: UNIX.

getuid()

Return the current process' user id. Availability: UNIX.

getenv(*varname*[, *value*])

Return the value of the environment variable *varname* if it exists, or *value* if it doesn't. *value* defaults to None. Availability: most flavors of UNIX, Windows.

putenv(*varname*, *value*)

Set the environment variable named *varname* to the string *value*. Such changes to the environment affect subprocesses started with `os.system()`, `popen()` or `fork()` and `execv()`. Availability: most flavors of UNIX, Windows.

Note: On some platforms, including FreeBSD and Mac OS X, setting `environ` may cause memory leaks. Refer to the system documentation for `putenv`.

When `putenv()` is supported, assignments to items in `os.environ` are automatically translated into corresponding calls to `putenv()`; however, calls to `putenv()` don't update `os.environ`, so it is actually preferable to assign to items of `os.environ`.

setegid(*egid*)

Set the current process's effective group id. Availability: UNIX.

seteuid(*euid*)

Set the current process's effective user id. Availability: UNIX.

setgid(*gid*)

Set the current process' group id. Availability: UNIX.

setgroups(*groups*)

Set the list of supplemental group ids associated with the current process to *groups*. *groups* must be a sequence, and each element must be an integer identifying a group. This operation is typically available only to the superuser. Availability: UNIX. New in version 2.2.

setpgrp()

Calls the system call `setpgrp()` or `setpgrp(0, 0)` depending on which version is implemented (if any). See the UNIX manual for the semantics. Availability: UNIX.

setpgid(*pid*, *pgrp*)

Calls the system call `setpgid()` to set the process group id of the process with id *pid* to the process group with id *pgrp*. See the UNIX manual for the semantics. Availability: UNIX.

setreuid(*ruid*, *euid*)

Set the current process's real and effective user ids. Availability: UNIX.

setregid(*rgid*, *egid*)

Set the current process's real and effective group ids. Availability: UNIX.

getsid (*pid*)

Calls the system call `getsid()`. See the UNIX manual for the semantics. Availability: UNIX. New in version 2.4.

setsid ()

Calls the system call `setsid()`. See the UNIX manual for the semantics. Availability: UNIX.

setuid (*uid*)

Set the current process' user id. Availability: UNIX.

strerror (*code*)

Return the error message corresponding to the error code in *code*. Availability: UNIX, Windows.

umask (*mask*)

Set the current numeric umask and returns the previous umask. Availability: UNIX, Windows.

uname ()

Return a 5-tuple containing information identifying the current operating system. The tuple contains 5 strings: (*sysname*, *nodename*, *release*, *version*, *machine*). Some systems truncate the *nodename* to 8 characters or to the leading component; a better way to get the hostname is `socket.gethostname()` or even `socket.gethostbyaddr(socket.gethostname())`. Availability: recent flavors of UNIX.

unsetenv (*varname*)

Unset (delete) the environment variable named *varname*. Such changes to the environment affect subprocesses started with `os.system()`, `popen()` or `fork()` and `execv()`. Availability: most flavors of UNIX, Windows.

When `unsetenv()` is supported, deletion of items in `os.environ` is automatically translated into a corresponding call to `unsetenv()`; however, calls to `unsetenv()` don't update `os.environ`, so it is actually preferable to delete items of `os.environ`.

14.1.2 File Object Creation

These functions create new file objects.

fdopen (*fd* [, *mode* [, *bufsize*]])

Return an open file object connected to the file descriptor *fd*. The *mode* and *bufsize* arguments have the same meaning as the corresponding arguments to the built-in `open()` function. Availability: Macintosh, UNIX, Windows.

Changed in version 2.3: When specified, the *mode* argument must now start with one of the letters 'r', 'w', or 'a', otherwise a `ValueError` is raised. Changed in version 2.5: On UNIX, when the *mode* argument starts with 'a', the `O_APPEND` flag is set on the file descriptor (which the `fdopen()` implementation already does on most platforms).

popen (*command* [, *mode* [, *bufsize*]])

Open a pipe to or from *command*. The return value is an open file object connected to the pipe, which can be read or written depending on whether *mode* is 'r' (default) or 'w'. The *bufsize* argument has the same meaning as the corresponding argument to the built-in `open()` function. The exit status of the command (encoded in the format specified for `wait()`) is available as the return value of the `close()` method of the file object, except that when the exit status is zero (termination without errors), `None` is returned. Availability: Macintosh, UNIX, Windows.

The `subprocess` module provides more powerful facilities for spawning new processes and retrieving their results; using that module is preferable to using this function.

Changed in version 2.0: This function worked unreliably under Windows in earlier versions of Python. This was due to the use of the `_popen()` function from the libraries provided with Windows. Newer versions of Python do not use the broken implementation from the Windows libraries.

tmpfile()

Return a new file object opened in update mode ('w+b'). The file has no directory entries associated with it and will be automatically deleted once there are no file descriptors for the file. Availability: Macintosh, UNIX, Windows.

There are a number of different `popen*`() functions that provide slightly different ways to create subprocesses. Note that the `subprocess` module is easier to use and more powerful; consider using that module before writing code using the lower-level `popen*`() functions.

For each of the `popen*`() variants, if *bufsize* is specified, it specifies the buffer size for the I/O pipes. *mode*, if provided, should be the string 'b' or 't'; on Windows this is needed to determine whether the file objects should be opened in binary or text mode. The default value for *mode* is 't'.

Also, for each of these variants, on UNIX, *cmd* may be a sequence, in which case arguments will be passed directly to the program without shell intervention (as with `os.spawnv()`). If *cmd* is a string it will be passed to the shell (as with `os.system()`).

These methods do not make it possible to retrieve the exit status from the child processes. The only way to control the input and output streams and also retrieve the return codes is to use the `Popen3` and `Popen4` classes from the [popen2](#) module; these are only available on UNIX.

For a discussion of possible deadlock conditions related to the use of these functions, see “[Flow Control Issues](#)” (section 17.4.2).

popen2(cmd[, mode[, bufsize]])

Executes *cmd* as a sub-process. Returns the file objects (*child_stdin*, *child_stdout*). Availability: Macintosh, UNIX, Windows. New in version 2.0.

popen3(cmd[, mode[, bufsize]])

Executes *cmd* as a sub-process. Returns the file objects (*child_stdin*, *child_stdout*, *child_stderr*). Availability: Macintosh, UNIX, Windows. New in version 2.0.

popen4(cmd[, mode[, bufsize]])

Executes *cmd* as a sub-process. Returns the file objects (*child_stdin*, *child_stdout_and_stderr*). Availability: Macintosh, UNIX, Windows. New in version 2.0.

(Note that *child_stdin*, *child_stdout*, and *child_stderr* are named from the point of view of the child process, so *child_stdin* is the child's standard input.)

This functionality is also available in the [popen2](#) module using functions of the same names, but the return values of those functions have a different order.

14.1.3 File Descriptor Operations

These functions operate on I/O streams referenced using file descriptors.

File descriptors are small integers corresponding to a file that has been opened by the current process. For example, standard input is usually file descriptor 0, standard output is 1, and standard error is 2. Further files opened by a process will then be assigned 3, 4, 5, and so forth. The name “file descriptor” is slightly deceptive; on UNIX platforms, sockets and pipes are also referenced by file descriptors.

close(fd)

Close file descriptor *fd*. Availability: Macintosh, UNIX, Windows.

Note: This function is intended for low-level I/O and must be applied to a file descriptor as returned by `open()` or `pipe()`. To close a “file object” returned by the built-in function `open()` or by `popen()` or `fdopen()`, use its `close()` method.

dup(fd)

Return a duplicate of file descriptor *fd*. Availability: Macintosh, UNIX, Windows.

dup2 (*fd*, *fd2*)

Duplicate file descriptor *fd* to *fd2*, closing the latter first if necessary. Availability: Macintosh, UNIX, Windows.

fdatasync (*fd*)

Force write of file with filedescriptor *fd* to disk. Does not force update of metadata. Availability: UNIX.

fpathconf (*fd*, *name*)

Return system configuration information relevant to an open file. *name* specifies the configuration value to retrieve; it may be a string which is the name of a defined system value; these names are specified in a number of standards (POSIX.1, UNIX 95, UNIX 98, and others). Some platforms define additional names as well. The names known to the host operating system are given in the `pathconf_names` dictionary. For configuration variables not included in that mapping, passing an integer for *name* is also accepted. Availability: Macintosh, UNIX.

If *name* is a string and is not known, `ValueError` is raised. If a specific value for *name* is not supported by the host system, even if it is included in `pathconf_names`, an `OSError` is raised with `errno.EINVAL` for the error number.

fstat (*fd*)

Return status for file descriptor *fd*, like `stat()`. Availability: Macintosh, UNIX, Windows.

fstatvfs (*fd*)

Return information about the filesystem containing the file associated with file descriptor *fd*, like `statvfs()`. Availability: UNIX.

fsync (*fd*)

Force write of file with filedescriptor *fd* to disk. On UNIX, this calls the native `fsync()` function; on Windows, the `MS_commit()` function.

If you're starting with a Python file object *f*, first do *f.flush()*, and then do `os.fsync(f.fileno())`, to ensure that all internal buffers associated with *f* are written to disk. Availability: Macintosh, UNIX, and Windows starting in 2.2.3.

ftruncate (*fd*, *length*)

Truncate the file corresponding to file descriptor *fd*, so that it is at most *length* bytes in size. Availability: Macintosh, UNIX.

isatty (*fd*)

Return `True` if the file descriptor *fd* is open and connected to a tty(-like) device, else `False`. Availability: Macintosh, UNIX.

lseek (*fd*, *pos*, *how*)

Set the current position of file descriptor *fd* to position *pos*, modified by *how*: 0 to set the position relative to the beginning of the file; 1 to set it relative to the current position; 2 to set it relative to the end of the file. Availability: Macintosh, UNIX, Windows.

open (*file*, *flags* [, *mode*])

Open the file *file* and set various flags according to *flags* and possibly its mode according to *mode*. The default *mode* is 0777 (octal), and the current umask value is first masked out. Return the file descriptor for the newly opened file. Availability: Macintosh, UNIX, Windows.

For a description of the flag and mode values, see the C run-time documentation; flag constants (like `O_RDONLY` and `O_WRONLY`) are defined in this module too (see below).

Note: This function is intended for low-level I/O. For normal usage, use the built-in function `open()`, which returns a “file object” with `read()` and `write()` methods (and many more). To wrap a file descriptor in a “file object”, use `fdopen()`.

openpty ()

Open a new pseudo-terminal pair. Return a pair of file descriptors (*master*, *slave*) for the pty and the tty, respectively. For a (slightly) more portable approach, use the `pty` module. Availability: Macintosh, Some flavors of UNIX.

pipe()

Create a pipe. Return a pair of file descriptors (*r*, *w*) usable for reading and writing, respectively. Availability: Macintosh, UNIX, Windows.

read(*fd*, *n*)

Read at most *n* bytes from file descriptor *fd*. Return a string containing the bytes read. If the end of the file referred to by *fd* has been reached, an empty string is returned. Availability: Macintosh, UNIX, Windows.

Note: This function is intended for low-level I/O and must be applied to a file descriptor as returned by `open()` or `pipe()`. To read a “file object” returned by the built-in function `open()` or by `popen()` or `fdopen()`, or `sys.stdin`, use its `read()` or `readline()` methods.

tcgetpgrp(*fd*)

Return the process group associated with the terminal given by *fd* (an open file descriptor as returned by `open()`). Availability: Macintosh, UNIX.

tcsetpgrp(*fd*, *pg*)

Set the process group associated with the terminal given by *fd* (an open file descriptor as returned by `open()`) to *pg*. Availability: Macintosh, UNIX.

ttyname(*fd*)

Return a string which specifies the terminal device associated with file-descriptor *fd*. If *fd* is not associated with a terminal device, an exception is raised. Availability: Macintosh, UNIX.

write(*fd*, *str*)

Write the string *str* to file descriptor *fd*. Return the number of bytes actually written. Availability: Macintosh, UNIX, Windows.

Note: This function is intended for low-level I/O and must be applied to a file descriptor as returned by `open()` or `pipe()`. To write a “file object” returned by the built-in function `open()` or by `popen()` or `fdopen()`, or `sys.stdout` or `sys.stderr`, use its `write()` method.

The following data items are available for use in constructing the *flags* parameter to the `open()` function. Some items will not be available on all platforms. For descriptions of their availability and use, consult `open(2)`.

O_RDONLY

O_WRONLY

O_RDWR

O_APPEND

O_CREAT

O_EXCL

O_TRUNC

Options for the *flag* argument to the `open()` function. These can be bit-wise OR'd together. Availability: Macintosh, UNIX, Windows.

O_DSYNC

O_RSYNC

O_SYNC

O_NDELAY

O_NONBLOCK

O_NOCTTY

O_SHLOCK

O_EXLOCK

More options for the *flag* argument to the `open()` function. Availability: Macintosh, UNIX.

O_BINARY

Option for the *flag* argument to the `open()` function. This can be bit-wise OR'd together with those listed above. Availability: Windows.

O_NOINHERIT

O_SHORT_LIVED

O_TEMPORARY
O_RANDOM
O_SEQUENTIAL
O_TEXT

Options for the *flag* argument to the `open()` function. These can be bit-wise OR'd together. Availability: Windows.

SEEK_SET
SEEK_CUR
SEEK_END

Parameters to the `lseek()` function. Their values are 0, 1, and 2, respectively. Availability: Windows, Macintosh, UNIX. New in version 2.5.

14.1.4 Files and Directories

access (*path, mode*)

Use the real uid/gid to test for access to *path*. Note that most operations will use the effective uid/gid, therefore this routine can be used in a `suid/sgid` environment to test if the invoking user has the specified access to *path*. *mode* should be `F_OK` to test the existence of *path*, or it can be the inclusive OR of one or more of `R_OK`, `W_OK`, and `X_OK` to test permissions. Return `True` if access is allowed, `False` if not. See the UNIX man page `access(2)` for more information. Availability: Macintosh, UNIX, Windows.

Note: Using `access()` to check if a user is authorized to e.g. open a file before actually doing so using `open()` creates a security hole, because the user might exploit the short time interval between checking and opening the file to manipulate it.

Note: I/O operations may fail even when `access()` indicates that they would succeed, particularly for operations on network filesystems which may have permissions semantics beyond the usual POSIX permission-bit model.

F_OK

Value to pass as the *mode* parameter of `access()` to test the existence of *path*.

R_OK

Value to include in the *mode* parameter of `access()` to test the readability of *path*.

W_OK

Value to include in the *mode* parameter of `access()` to test the writability of *path*.

X_OK

Value to include in the *mode* parameter of `access()` to determine if *path* can be executed.

chdir (*path*)

Change the current working directory to *path*. Availability: Macintosh, UNIX, Windows.

fchdir (*fd*)

Change the current working directory to the directory represented by the file descriptor *fd*. The descriptor must refer to an opened directory, not an open file. Availability: UNIX. New in version 2.3.

getcwd()

Return a string representing the current working directory. Availability: Macintosh, UNIX, Windows.

getcwdu()

Return a Unicode object representing the current working directory. Availability: Macintosh, UNIX, Windows. New in version 2.3.

chroot (*path*)

Change the root directory of the current process to *path*. Availability: Macintosh, UNIX. New in version 2.2.

chmod (*path, mode*)

Change the mode of *path* to the numeric *mode*. *mode* may take one of the following values (as defined in the `stat` module) or bitwise or-ed combinations of them:

- `S_ISUID`
- `S_ISGID`
- `S_ENFMT`
- `S_ISVTX`
- `S_IREAD`
- `S_IWRITE`
- `S_IEXEC`
- `S_IRWXU`
- `S_IRUSR`
- `S_IWUSR`
- `S_IXUSR`
- `S_IRWXG`
- `S_IRGRP`
- `S_IWGRP`
- `S_IXGRP`
- `S_IRWXO`
- `S_IROTH`
- `S_IWOTH`
- `S_IXOTH`

Availability: Macintosh, UNIX, Windows.

Note: Although Windows supports `chmod()`, you can only set the file's read-only flag with it (via the `S_IWRITE` and `S_IREAD` constants or a corresponding integer value). All other bits are ignored.

chown (*path*, *uid*, *gid*)

Change the owner and group id of *path* to the numeric *uid* and *gid*. To leave one of the ids unchanged, set it to -1. Availability: Macintosh, UNIX.

lchown (*path*, *uid*, *gid*)

Change the owner and group id of *path* to the numeric *uid* and *gid*. This function will not follow symbolic links. Availability: Macintosh, UNIX. New in version 2.3.

link (*src*, *dst*)

Create a hard link pointing to *src* named *dst*. Availability: Macintosh, UNIX.

listdir (*path*)

Return a list containing the names of the entries in the directory. The list is in arbitrary order. It does not include the special entries `'.'` and `'..'` even if they are present in the directory. Availability: Macintosh, UNIX, Windows.

Changed in version 2.3: On Windows NT/2k/XP and UNIX, if *path* is a Unicode object, the result will be a list of Unicode objects.

lstat (*path*)

Like `stat()`, but do not follow symbolic links. This is an alias for `stat()` on platforms that do not support symbolic links, such as Windows.

mkfifo (*path* [, *mode*])

Create a FIFO (a named pipe) named *path* with numeric mode *mode*. The default *mode* is 0666 (octal). The current umask value is first masked out from the mode. Availability: Macintosh, UNIX.

FIFOs are pipes that can be accessed like regular files. FIFOs exist until they are deleted (for example with `os.unlink()`). Generally, FIFOs are used as rendezvous between “client” and “server” type processes: the server opens the FIFO for reading, and the client opens it for writing. Note that `mkfifo()` doesn’t open the FIFO — it just creates the rendezvous point.

mknod (*filename* [, *mode*=0600, *device*])

Create a filesystem node (file, device special file or named pipe) named *filename*. *mode* specifies both the permissions to use and the type of node to be created, being combined (bitwise OR) with one of `S_IFREG`, `S_IFCHR`, `S_IFBLK`, and `S_IFIFO` (those constants are available in `stat`). For `S_IFCHR` and `S_IFBLK`, *device* defines the newly created device special file (probably using `os.makedev()`), otherwise it is ignored. New in version 2.3.

major (*device*)

Extracts the device major number from a raw device number (usually the `st_dev` or `st_rdev` field from `stat`). New in version 2.3.

minor (*device*)

Extracts the device minor number from a raw device number (usually the `st_dev` or `st_rdev` field from `stat`). New in version 2.3.

makedev (*major*, *minor*)

Composes a raw device number from the major and minor device numbers. New in version 2.3.

mkdir (*path* [, *mode*])

Create a directory named *path* with numeric mode *mode*. The default *mode* is 0777 (octal). On some systems, *mode* is ignored. Where it is used, the current umask value is first masked out. Availability: Macintosh, UNIX, Windows.

makedirs (*path* [, *mode*])

Recursive directory creation function. Like `mkdir()`, but makes all intermediate-level directories needed to contain the leaf directory. Throws an `error` exception if the leaf directory already exists or cannot be created. The default *mode* is 0777 (octal). On some systems, *mode* is ignored. Where it is used, the current umask value is first masked out. **Note:** `makedirs()` will become confused if the path elements to create include *os.pardir*. New in version 1.5.2. Changed in version 2.3: This function now handles UNC paths correctly.

pathconf (*path*, *name*)

Return system configuration information relevant to a named file. *name* specifies the configuration value to retrieve; it may be a string which is the name of a defined system value; these names are specified in a number of standards (POSIX.1, UNIX 95, UNIX 98, and others). Some platforms define additional names as well. The names known to the host operating system are given in the `pathconf_names` dictionary. For configuration variables not included in that mapping, passing an integer for *name* is also accepted. Availability: Macintosh, UNIX.

If *name* is a string and is not known, `ValueError` is raised. If a specific value for *name* is not supported by the host system, even if it is included in `pathconf_names`, an `OSError` is raised with `errno.EINVAL` for the error number.

pathconf_names

Dictionary mapping names accepted by `pathconf()` and `fpathconf()` to the integer values defined for those names by the host operating system. This can be used to determine the set of names known to the system. Availability: Macintosh, UNIX.

readlink (*path*)

Return a string representing the path to which the symbolic link points. The result may be either an absolute or relative pathname; if it is relative, it may be converted to an absolute pathname using `os.path.join(os.path.dirname(path), result)`. Availability: Macintosh, UNIX.

remove (*path*)

Remove the file *path*. If *path* is a directory, `OSError` is raised; see `rmdir()` below to remove a directory. This is identical to the `unlink()` function documented below. On Windows, attempting to remove a file that is in use causes an exception to be raised; on UNIX, the directory entry is removed but the storage allocated to the file is not made available until the original file is no longer in use. Availability: Macintosh, UNIX, Windows.

removedirs (*path*)

Removes directories recursively. Works like `rmdir()` except that, if the leaf directory is successfully removed, `removedirs()` tries to successively remove every parent directory mentioned in *path* until an error is raised (which is ignored, because it generally means that a parent directory is not empty). For example, `'os.removedirs('foo/bar/baz')'` will first remove the directory `'foo/bar/baz'`, and then remove `'foo/bar'` and `'foo'` if they are empty. Raises `OSError` if the leaf directory could not be successfully removed. New in version 1.5.2.

rename (*src*, *dst*)

Rename the file or directory *src* to *dst*. If *dst* is a directory, `OSError` will be raised. On UNIX, if *dst* exists and is a file, it will be removed silently if the user has permission. The operation may fail on some UNIX flavors if *src* and *dst* are on different filesystems. If successful, the renaming will be an atomic operation (this is a POSIX requirement). On Windows, if *dst* already exists, `OSError` will be raised even if it is a file; there may be no way to implement an atomic rename when *dst* names an existing file. Availability: Macintosh, UNIX, Windows.

renames (*old*, *new*)

Recursive directory or file renaming function. Works like `rename()`, except creation of any intermediate directories needed to make the new pathname good is attempted first. After the rename, directories corresponding to rightmost path segments of the old name will be pruned away using `removedirs()`. New in version 1.5.2.

Note: This function can fail with the new directory structure made if you lack permissions needed to remove the leaf directory or file.

rmdir (*path*)

Remove the directory *path*. Availability: Macintosh, UNIX, Windows.

stat (*path*)

Perform a `stat()` system call on the given path. The return value is an object whose attributes correspond to the members of the `stat` structure, namely: `st_mode` (protection bits), `st_ino` (inode number), `st_dev` (device), `st_nlink` (number of hard links), `st_uid` (user ID of owner), `st_gid` (group ID of owner), `st_size` (size of file, in bytes), `st_atime` (time of most recent access), `st_mtime` (time of most recent content modification), `st_ctime` (platform dependent; time of most recent metadata change on UNIX, or the time of creation on Windows):

```
>>> import os
>>> statinfo = os.stat('somefile.txt')
>>> statinfo
(33188, 422511L, 769L, 1, 1032, 100, 926L, 1105022698, 1105022732, 1105022732)
>>> statinfo.st_size
926L
>>>
```

Changed in version 2.3: If `stat_float_times` returns true, the time values are floats, measuring seconds. Fractions of a second may be reported if the system supports that. On Mac OS, the times are always floats. See `stat_float_times` for further discussion.

On some UNIX systems (such as Linux), the following attributes may also be available: `st_blocks` (number of blocks allocated for file), `st_blksize` (filesystem blocksize), `st_rdev` (type of device if an inode device), `st_flags` (user defined flags for file).

On other UNIX systems (such as FreeBSD), the following attributes may be available (but may be only filled out if root tries to use them): `st_gen` (file generation number), `st_birthtime` (time of file creation).

On Mac OS systems, the following attributes may also be available: `st_rsize`, `st_creator`, `st_type`.

On RISCOS systems, the following attributes are also available: `st_ftype` (file type), `st_attrs` (attributes), `st_obtype` (object type).

For backward compatibility, the return value of `stat()` is also accessible as a tuple of at least 10 integers giving the most important (and portable) members of the `stat` structure, in the order `st_mode`, `st_ino`, `st_dev`, `st_nlink`, `st_uid`, `st_gid`, `st_size`, `st_atime`, `st_mtime`, `st_ctime`. More items may be added at the end by some implementations. The standard module `stat` defines functions and constants that are useful for extracting information from a `stat` structure. (On Windows, some items are filled with dummy values.)

Note: The exact meaning and resolution of the `st_atime`, `st_mtime`, and `st_ctime` members depends on the operating system and the file system. For example, on Windows systems using the FAT or FAT32 file systems, `st_mtime` has 2-second resolution, and `st_atime` has only 1-day resolution. See your operating system documentation for details.

Availability: Macintosh, UNIX, Windows.

Changed in version 2.2: Added access to values as attributes of the returned object. Changed in version 2.5: Added `st_gen`, `st_birthtime`.

stat_float_times (*[newvalue]*)

Determine whether `stat_result` represents time stamps as float objects. If *newvalue* is `True`, future calls to `stat()` return floats, if it is `False`, future calls return ints. If *newvalue* is omitted, return the current setting.

For compatibility with older Python versions, accessing `stat_result` as a tuple always returns integers.

Changed in version 2.5: Python now returns float values by default. Applications which do not work correctly with floating point time stamps can use this function to restore the old behaviour.

The resolution of the timestamps (that is the smallest possible fraction) depends on the system. Some systems only support second resolution; on these systems, the fraction will always be zero.

It is recommended that this setting is only changed at program startup time in the `__main__` module; libraries should never change this setting. If an application uses a library that works incorrectly if floating point time stamps are processed, this application should turn the feature off until the library has been corrected.

statvfs (*path*)

Perform a `statvfs()` system call on the given path. The return value is an object whose attributes describe the filesystem on the given path, and correspond to the members of the `statvfs` structure, namely: `f_bsize`, `f_frsize`, `f_blocks`, `f_bfree`, `f_bavail`, `f_files`, `f_ffree`, `f_favail`, `f_flag`, `f_namemax`. Availability: UNIX.

For backward compatibility, the return value is also accessible as a tuple whose values correspond to the attributes, in the order given above. The standard module `statvfs` defines constants that are useful for extracting information from a `statvfs` structure when accessing it as a sequence; this remains useful when writing code that needs to work with versions of Python that don't support accessing the fields as attributes.

Changed in version 2.2: Added access to values as attributes of the returned object.

symlink (*src, dst*)

Create a symbolic link pointing to *src* named *dst*. Availability: UNIX.

tempnam (*[dir[, prefix]]*)

Return a unique path name that is reasonable for creating a temporary file. This will be an absolute path that names a potential directory entry in the directory *dir* or a common location for temporary files if *dir* is omitted or `None`. If given and not `None`, *prefix* is used to provide a short prefix to the filename. Applications are responsible for properly creating and managing files created using paths returned by `tempnam()`; no automatic cleanup is provided. On UNIX, the environment variable `TMPDIR` overrides *dir*, while on Windows the `TMP` is used. The specific behavior of this function depends on the C library implementation; some aspects are underspecified in system documentation. **Warning:** Use of `tempnam()` is vulnerable to symlink attacks; consider using `tempfile()` (section 14.1.2) instead. Availability: Macintosh, UNIX, Windows.

tmpnam()

Return a unique path name that is reasonable for creating a temporary file. This will be an absolute path that names a potential directory entry in a common location for temporary files. Applications are responsible for properly creating and managing files created using paths returned by `tmpnam()`; no automatic cleanup is provided. **Warning:** Use of `tmpnam()` is vulnerable to symlink attacks; consider using `tmpfile()` (section 14.1.2) instead. Availability: UNIX, Windows. This function probably shouldn't be used on Windows, though: Microsoft's implementation of `tmpnam()` always creates a name in the root directory of the current drive, and that's generally a poor location for a temp file (depending on privileges, you may not even be able to open a file using this name).

TMP_MAX

The maximum number of unique names that `tmpnam()` will generate before reusing names.

unlink(path)

Remove the file *path*. This is the same function as `remove()`; the `unlink()` name is its traditional UNIX name. Availability: Macintosh, UNIX, Windows.

utime(path, times)

Set the access and modified times of the file specified by *path*. If *times* is `None`, then the file's access and modified times are set to the current time. Otherwise, *times* must be a 2-tuple of numbers, of the form (*atime*, *mtime*) which is used to set the access and modified times, respectively. Whether a directory can be given for *path* depends on whether the operating system implements directories as files (for example, Windows does not). Note that the exact times you set here may not be returned by a subsequent `stat()` call, depending on the resolution with which your operating system records access and modification times; see `stat()`. Changed in version 2.0: Added support for `None` for *times*. Availability: Macintosh, UNIX, Windows.

walk(top[, topdown=True[, onerror=None]])

`walk()` generates the file names in a directory tree, by walking the tree either top down or bottom up. For each directory in the tree rooted at directory *top* (including *top* itself), it yields a 3-tuple (*dirpath*, *dirnames*, *filenames*).

dirpath is a string, the path to the directory. *dirnames* is a list of the names of the subdirectories in *dirpath* (excluding '.' and '..'). *filenames* is a list of the names of the non-directory files in *dirpath*. Note that the names in the lists contain no path components. To get a full path (which begins with *top*) to a file or directory in *dirpath*, do `os.path.join(dirpath, name)`.

If optional argument *topdown* is true or not specified, the triple for a directory is generated before the triples for any of its subdirectories (directories are generated top down). If *topdown* is false, the triple for a directory is generated after the triples for all of its subdirectories (directories are generated bottom up).

When *topdown* is true, the caller can modify the *dirnames* list in-place (perhaps using `del` or slice assignment), and `walk()` will only recurse into the subdirectories whose names remain in *dirnames*; this can be used to prune the search, impose a specific order of visiting, or even to inform `walk()` about directories the caller creates or renames before it resumes `walk()` again. Modifying *dirnames* when *topdown* is false is ineffective, because in bottom-up mode the directories in *dirnames* are generated before *dirpath* itself is generated.

By default errors from the `os.listdir()` call are ignored. If optional argument *onerror* is specified, it should be a function; it will be called with one argument, an `OSError` instance. It can report the error to continue with the walk, or raise the exception to abort the walk. Note that the filename is available as the *filename* attribute of the exception object.

Note: If you pass a relative pathname, don't change the current working directory between resumptions of `walk()`. `walk()` never changes the current directory, and assumes that its caller doesn't either.

Note: On systems that support symbolic links, links to subdirectories appear in *dirnames* lists, but `walk()` will not visit them (infinite loops are hard to avoid when following symbolic links). To visit linked directories, you can identify them with `os.path.islink(path)`, and invoke `walk(path)` on each directly.

This example displays the number of bytes taken by non-directory files in each directory under the starting directory, except that it doesn't look under any CVS subdirectory:

```

import os
from os.path import join, getsize
for root, dirs, files in os.walk('python/Lib/email'):
    print root, "consumes",
    print sum(getsize(join(root, name)) for name in files),
    print "bytes in", len(files), "non-directory files"
    if 'CVS' in dirs:
        dirs.remove('CVS') # don't visit CVS directories

```

In the next example, walking the tree bottom up is essential: `rmdir()` doesn't allow deleting a directory before the directory is empty:

```

# Delete everything reachable from the directory named in 'top',
# assuming there are no symbolic links.
# CAUTION: This is dangerous! For example, if top == '/', it
# could delete all your disk files.
import os
for root, dirs, files in os.walk(top, topdown=False):
    for name in files:
        os.remove(os.path.join(root, name))
    for name in dirs:
        os.rmdir(os.path.join(root, name))

```

New in version 2.3.

14.1.5 Process Management

These functions may be used to create and manage processes.

The various `exec*`() functions take a list of arguments for the new program loaded into the process. In each case, the first of these arguments is passed to the new program as its own name rather than as an argument a user may have typed on a command line. For the C programmer, this is the `argv[0]` passed to a program's `main()`. For example, `'os.execv('/bin/echo', ['foo', 'bar'])` will only print 'bar' on standard output; 'foo' will seem to be ignored.

abort()

Generate a SIGABRT signal to the current process. On UNIX, the default behavior is to produce a core dump; on Windows, the process immediately returns an exit code of 3. Be aware that programs which use `signal.signal()` to register a handler for SIGABRT will behave differently. Availability: Macintosh, UNIX, Windows.

```

execl (path, arg0, arg1, ...)
execle (path, arg0, arg1, ..., env)
execlp (file, arg0, arg1, ...)
execlep (file, arg0, arg1, ..., env)
execv (path, args)
execve (path, args, env)
execvp (file, args)
execvpe (file, args, env)

```

These functions all execute a new program, replacing the current process; they do not return. On UNIX, the new executable is loaded into the current process, and will have the same process ID as the caller. Errors will be reported as `OSError` exceptions.

The 'l' and 'v' variants of the `exec*`() functions differ in how command-line arguments are passed. The 'l' variants are perhaps the easiest to work with if the number of parameters is fixed when the code is written; the individual parameters simply become additional parameters to the `execl*()` functions. The 'v' variants are

good when the number of parameters is variable, with the arguments being passed in a list or tuple as the *args* parameter. In either case, the arguments to the child process should start with the name of the command being run, but this is not enforced.

The variants which include a ‘p’ near the end (`execlp()`, `execlpe()`, `execvp()`, and `execvpe()`) will use the `PATH` environment variable to locate the program *file*. When the environment is being replaced (using one of the `exec*e()` variants, discussed in the next paragraph), the new environment is used as the source of the `PATH` variable. The other variants, `execl()`, `execle()`, `execv()`, and `execve()`, will not use the `PATH` variable to locate the executable; *path* must contain an appropriate absolute or relative path.

For `execle()`, `execlpe()`, `execve()`, and `execvpe()` (note that these all end in ‘e’), the *env* parameter must be a mapping which is used to define the environment variables for the new process; the `execl()`, `execlp()`, `execv()`, and `execvp()` all cause the new process to inherit the environment of the current process. Availability: Macintosh, UNIX, Windows.

`_exit(n)`

Exit to the system with status *n*, without calling cleanup handlers, flushing stdio buffers, etc. Availability: Macintosh, UNIX, Windows.

Note: The standard way to exit is `sys.exit(n)`. `_exit()` should normally only be used in the child process after a `fork()`.

The following exit codes are defined, and can be used with `_exit()`, although they are not required. These are typically used for system programs written in Python, such as a mail server’s external command delivery program.

Note: Some of these may not be available on all UNIX platforms, since there is some variation. These constants are defined where they are defined by the underlying platform.

`EX_OK`

Exit code that means no error occurred. Availability: Macintosh, UNIX. New in version 2.3.

`EX_USAGE`

Exit code that means the command was used incorrectly, such as when the wrong number of arguments are given. Availability: Macintosh, UNIX. New in version 2.3.

`EX_DATAERR`

Exit code that means the input data was incorrect. Availability: Macintosh, UNIX. New in version 2.3.

`EX_NOINPUT`

Exit code that means an input file did not exist or was not readable. Availability: Macintosh, UNIX. New in version 2.3.

`EX_NOUSER`

Exit code that means a specified user did not exist. Availability: Macintosh, UNIX. New in version 2.3.

`EX_NOHOST`

Exit code that means a specified host did not exist. Availability: Macintosh, UNIX. New in version 2.3.

`EX_UNAVAILABLE`

Exit code that means that a required service is unavailable. Availability: Macintosh, UNIX. New in version 2.3.

`EX_SOFTWARE`

Exit code that means an internal software error was detected. Availability: Macintosh, UNIX. New in version 2.3.

`EX_OSERR`

Exit code that means an operating system error was detected, such as the inability to fork or create a pipe. Availability: Macintosh, UNIX. New in version 2.3.

`EX_OSFILE`

Exit code that means some system file did not exist, could not be opened, or had some other kind of error. Availability: Macintosh, UNIX. New in version 2.3.

`EX_CANTCREAT`

Exit code that means a user specified output file could not be created. Availability: Macintosh, UNIX. New in version 2.3.

EX_IOERR

Exit code that means that an error occurred while doing I/O on some file. Availability: Macintosh, UNIX. New in version 2.3.

EX_TEMPFAIL

Exit code that means a temporary failure occurred. This indicates something that may not really be an error, such as a network connection that couldn't be made during a retryable operation. Availability: Macintosh, UNIX. New in version 2.3.

EX_PROTOCOL

Exit code that means that a protocol exchange was illegal, invalid, or not understood. Availability: Macintosh, UNIX. New in version 2.3.

EX_NOPERM

Exit code that means that there were insufficient permissions to perform the operation (but not intended for file system problems). Availability: Macintosh, UNIX. New in version 2.3.

EX_CONFIG

Exit code that means that some kind of configuration error occurred. Availability: Macintosh, UNIX. New in version 2.3.

EX_NOTFOUND

Exit code that means something like “an entry was not found”. Availability: Macintosh, UNIX. New in version 2.3.

fork ()

Fork a child process. Return 0 in the child, the child's process id in the parent. Availability: Macintosh, UNIX.

forkpty ()

Fork a child process, using a new pseudo-terminal as the child's controlling terminal. Return a pair of (*pid*, *fd*), where *pid* is 0 in the child, the new child's process id in the parent, and *fd* is the file descriptor of the master end of the pseudo-terminal. For a more portable approach, use the [pty](#) module. Availability: Macintosh, Some flavors of UNIX.

kill (*pid*, *sig*)

Send signal *sig* to the process *pid*. Constants for the specific signals available on the host platform are defined in the [signal](#) module. Availability: Macintosh, UNIX.

killpg (*pgid*, *sig*)

Send the signal *sig* to the process group *pgid*. Availability: Macintosh, UNIX. New in version 2.3.

nice (*increment*)

Add *increment* to the process's “niceness”. Return the new niceness. Availability: Macintosh, UNIX.

plock (*op*)

Lock program segments into memory. The value of *op* (defined in `<sys/lock.h>`) determines which segments are locked. Availability: Macintosh, UNIX.

popen (...)

popen2 (...)

popen3 (...)

popen4 (...)

Run child processes, returning opened pipes for communications. These functions are described in section 14.1.2.

spawnl (*mode*, *path*, ...)

spawnle (*mode*, *path*, ..., *env*)

spawnlp (*mode*, *file*, ...)

spawnlpe (*mode, file, ..., env*)
spawnv (*mode, path, args*)
spawnve (*mode, path, args, env*)
spawnvp (*mode, file, args*)
spawnvpe (*mode, file, args, env*)

Execute the program *path* in a new process.

(Note that the `subprocess` module provides more powerful facilities for spawning new processes and retrieving their results; using that module is preferable to using these functions.)

If *mode* is `P_NOWAIT`, this function returns the process ID of the new process; if *mode* is `P_WAIT`, returns the process's exit code if it exits normally, or `-signal`, where *signal* is the signal that killed the process. On Windows, the process ID will actually be the process handle, so can be used with the `waitpid()` function.

The 'l' and 'v' variants of the `spawn*()` functions differ in how command-line arguments are passed. The 'l' variants are perhaps the easiest to work with if the number of parameters is fixed when the code is written; the individual parameters simply become additional parameters to the `spawnl*()` functions. The 'v' variants are good when the number of parameters is variable, with the arguments being passed in a list or tuple as the *args* parameter. In either case, the arguments to the child process must start with the name of the command being run.

The variants which include a second 'p' near the end (`spawnlp()`, `spawnlpe()`, `spawnvp()`, and `spawnvpe()`) will use the `PATH` environment variable to locate the program *file*. When the environment is being replaced (using one of the `spawn*e()` variants, discussed in the next paragraph), the new environment is used as the source of the `PATH` variable. The other variants, `spawnl()`, `spawnle()`, `spawnv()`, and `spawnve()`, will not use the `PATH` variable to locate the executable; *path* must contain an appropriate absolute or relative path.

For `spawnle()`, `spawnlpe()`, `spawnve()`, and `spawnvpe()` (note that these all end in 'e'), the *env* parameter must be a mapping which is used to define the environment variables for the new process; the `spawnl()`, `spawnlp()`, `spawnv()`, and `spawnvp()` all cause the new process to inherit the environment of the current process.

As an example, the following calls to `spawnlp()` and `spawnvpe()` are equivalent:

```
import os
os.spawnlp(os.P_WAIT, 'cp', 'cp', 'index.html', '/dev/null')

L = ['cp', 'index.html', '/dev/null']
os.spawnvpe(os.P_WAIT, 'cp', L, os.environ)
```

Availability: UNIX, Windows. `spawnlp()`, `spawnlpe()`, `spawnvp()` and `spawnvpe()` are not available on Windows. New in version 1.6.

P_NOWAIT

P_NOWAITO

Possible values for the *mode* parameter to the `spawn*()` family of functions. If either of these values is given, the `spawn*()` functions will return as soon as the new process has been created, with the process ID as the return value. Availability: Macintosh, UNIX, Windows. New in version 1.6.

P_WAIT

Possible value for the *mode* parameter to the `spawn*()` family of functions. If this is given as *mode*, the `spawn*()` functions will not return until the new process has run to completion and will return the exit code of the process the run is successful, or `-signal` if a signal kills the process. Availability: Macintosh, UNIX, Windows. New in version 1.6.

P_DETACH

P_OVERLAY

Possible values for the *mode* parameter to the `spawn*()` family of functions. These are less portable than those listed above. `P_DETACH` is similar to `P_NOWAIT`, but the new process is detached from the console of

the calling process. If `P_OVERLAY` is used, the current process will be replaced; the `spawn*()` function will not return. Availability: Windows. New in version 1.6.

startfile (*path* [, *operation*])

Start a file with its associated application.

When *operation* is not specified or `'open'`, this acts like double-clicking the file in Windows Explorer, or giving the file name as an argument to the **start** command from the interactive command shell: the file is opened with whatever application (if any) its extension is associated.

When another *operation* is given, it must be a “command verb” that specifies what should be done with the file. Common verbs documented by Microsoft are `'print'` and `'edit'` (to be used on files) as well as `'explore'` and `'find'` (to be used on directories).

`startfile()` returns as soon as the associated application is launched. There is no option to wait for the application to close, and no way to retrieve the application’s exit status. The *path* parameter is relative to the current directory. If you want to use an absolute path, make sure the first character is not a slash (`'/'`); the underlying Win32 `ShellExecute()` function doesn’t work if it is. Use the `os.path.normpath()` function to ensure that the path is properly encoded for Win32. Availability: Windows. New in version 2.0. New in version 2.5: The *operation* parameter.

system (*command*)

Execute the command (a string) in a subshell. This is implemented by calling the Standard C function `system()`, and has the same limitations. Changes to `posix.environ`, `sys.stdin`, etc. are not reflected in the environment of the executed command.

On UNIX, the return value is the exit status of the process encoded in the format specified for `wait()`. Note that POSIX does not specify the meaning of the return value of the C `system()` function, so the return value of the Python function is system-dependent.

On Windows, the return value is that returned by the system shell after running *command*, given by the Windows environment variable `COMSPEC`: on **command.com** systems (Windows 95, 98 and ME) this is always 0; on **cmd.exe** systems (Windows NT, 2000 and XP) this is the exit status of the command run; on systems using a non-native shell, consult your shell documentation.

Availability: Macintosh, UNIX, Windows.

The `subprocess` module provides more powerful facilities for spawning new processes and retrieving their results; using that module is preferable to using this function.

times ()

Return a 5-tuple of floating point numbers indicating accumulated (processor or other) times, in seconds. The items are: user time, system time, children’s user time, children’s system time, and elapsed real time since a fixed point in the past, in that order. See the UNIX manual page `times(2)` or the corresponding Windows Platform API documentation. Availability: Macintosh, UNIX, Windows.

wait ()

Wait for completion of a child process, and return a tuple containing its pid and exit status indication: a 16-bit number, whose low byte is the signal number that killed the process, and whose high byte is the exit status (if the signal number is zero); the high bit of the low byte is set if a core file was produced. Availability: Macintosh, UNIX.

waitpid (*pid*, *options*)

The details of this function differ on UNIX and Windows.

On UNIX: Wait for completion of a child process given by process id *pid*, and return a tuple containing its process id and exit status indication (encoded as for `wait()`). The semantics of the call are affected by the value of the integer *options*, which should be 0 for normal operation.

If *pid* is greater than 0, `waitpid()` requests status information for that specific process. If *pid* is 0, the request is for the status of any child in the process group of the current process. If *pid* is -1, the request pertains to any child of the current process. If *pid* is less than -1, status is requested for any process in the process group `-pid` (the absolute value of *pid*).

On Windows: Wait for completion of a process given by process handle *pid*, and return a tuple containing *pid*, and its exit status shifted left by 8 bits (shifting makes cross-platform use of the function easier). A *pid* less than or equal to 0 has no special meaning on Windows, and raises an exception. The value of integer *options* has no effect. *pid* can refer to any process whose id is known, not necessarily a child process. The `spawn()` functions called with `P_NOWAIT` return suitable process handles.

wait3([options])

Similar to `waitpid()`, except no process id argument is given and a 3-element tuple containing the child's process id, exit status indication, and resource usage information is returned. Refer to `resource.getrusage()` for details on resource usage information. The option argument is the same as that provided to `waitpid()` and `wait4()`. Availability: UNIX. New in version 2.5.

wait4(pid, options)

Similar to `waitpid()`, except a 3-element tuple, containing the child's process id, exit status indication, and resource usage information is returned. Refer to `resource.getrusage()` for details on resource usage information. The arguments to `wait4()` are the same as those provided to `waitpid()`. Availability: UNIX. New in version 2.5.

WNOHANG

The option for `waitpid()` to return immediately if no child process status is available immediately. The function returns (0, 0) in this case. Availability: Macintosh, UNIX.

WCONTINUED

This option causes child processes to be reported if they have been continued from a job control stop since their status was last reported. Availability: Some UNIX systems. New in version 2.3.

WUNTRACED

This option causes child processes to be reported if they have been stopped but their current state has not been reported since they were stopped. Availability: Macintosh, UNIX. New in version 2.3.

The following functions take a process status code as returned by `system()`, `wait()`, or `waitpid()` as a parameter. They may be used to determine the disposition of a process.

WCOREDUMP(status)

Returns `True` if a core dump was generated for the process, otherwise it returns `False`. Availability: Macintosh, UNIX. New in version 2.3.

WIFCONTINUED(status)

Returns `True` if the process has been continued from a job control stop, otherwise it returns `False`. Availability: UNIX. New in version 2.3.

WIFSTOPPED(status)

Returns `True` if the process has been stopped, otherwise it returns `False`. Availability: UNIX.

WIFSIGNALED(status)

Returns `True` if the process exited due to a signal, otherwise it returns `False`. Availability: Macintosh, UNIX.

WIFEXITED(status)

Returns `True` if the process exited using the `exit(2)` system call, otherwise it returns `False`. Availability: Macintosh, UNIX.

WEXITSTATUS(status)

If `WIFEXITED(status)` is true, return the integer parameter to the `exit(2)` system call. Otherwise, the return value is meaningless. Availability: Macintosh, UNIX.

WSTOPSIG(status)

Return the signal which caused the process to stop. Availability: Macintosh, UNIX.

WTERMSIG(status)

Return the signal which caused the process to exit. Availability: Macintosh, UNIX.

14.1.6 Miscellaneous System Information

confstr (*name*)

Return string-valued system configuration values. *name* specifies the configuration value to retrieve; it may be a string which is the name of a defined system value; these names are specified in a number of standards (POSIX, UNIX 95, UNIX 98, and others). Some platforms define additional names as well. The names known to the host operating system are given as the keys of the `confstr_names` dictionary. For configuration variables not included in that mapping, passing an integer for *name* is also accepted. Availability: Macintosh, UNIX.

If the configuration value specified by *name* isn't defined, `None` is returned.

If *name* is a string and is not known, `ValueError` is raised. If a specific value for *name* is not supported by the host system, even if it is included in `confstr_names`, an `OSError` is raised with `errno.EINVAL` for the error number.

confstr_names

Dictionary mapping names accepted by `confstr()` to the integer values defined for those names by the host operating system. This can be used to determine the set of names known to the system. Availability: Macintosh, UNIX.

getloadavg ()

Return the number of processes in the system run queue averaged over the last 1, 5, and 15 minutes or raises `OSError` if the load average was unobtainable.

New in version 2.3.

sysconf (*name*)

Return integer-valued system configuration values. If the configuration value specified by *name* isn't defined, `-1` is returned. The comments regarding the *name* parameter for `confstr()` apply here as well; the dictionary that provides information on the known names is given by `sysconf_names`. Availability: Macintosh, UNIX.

sysconf_names

Dictionary mapping names accepted by `sysconf()` to the integer values defined for those names by the host operating system. This can be used to determine the set of names known to the system. Availability: Macintosh, UNIX.

The follow data values are used to support path manipulation operations. These are defined for all platforms.

Higher-level operations on pathnames are defined in the `os.path` module.

curdir

The constant string used by the operating system to refer to the current directory. For example: `'.'` for POSIX or `'.'` for Mac OS 9. Also available via `os.path`.

pardir

The constant string used by the operating system to refer to the parent directory. For example: `'..'` for POSIX or `'..'` for Mac OS 9. Also available via `os.path`.

sep

The character used by the operating system to separate pathname components, for example, `'/'` for POSIX or `'.'` for Mac OS 9. Note that knowing this is not sufficient to be able to parse or concatenate pathnames — use `os.path.split()` and `os.path.join()` — but it is occasionally useful. Also available via `os.path`.

altsep

An alternative character used by the operating system to separate pathname components, or `None` if only one separator character exists. This is set to `'/'` on Windows systems where `sep` is a backslash. Also available via `os.path`.

extsep

The character which separates the base filename from the extension; for example, the `'.'` in `'os.py'`. Also available via `os.path`. New in version 2.2.

pathsep

The character conventionally used by the operating system to separate search path components (as in PATH), such as `:` for POSIX or `;` for Windows. Also available via `os.path`.

defpath

The default search path used by `exec*p*()` and `spawn*p*()` if the environment doesn't have a `'PATH'` key. Also available via `os.path`.

linesep

The string used to separate (or, rather, terminate) lines on the current platform. This may be a single character, such as `'\n'` for POSIX or `'\r'` for Mac OS, or multiple characters, for example, `'\r\n'` for Windows. Do not use `os.linesep` as a line terminator when writing files opened in text mode (the default); use a single `'\n'` instead, on all platforms.

devnull

The file path of the null device. For example: `'/dev/null'` for POSIX or `'Dev:Nul'` for Mac OS 9. Also available via `os.path`. New in version 2.4.

14.1.7 Miscellaneous Functions

urandom(*n*)

Return a string of *n* random bytes suitable for cryptographic use.

This function returns random bytes from an OS-specific randomness source. The returned data should be unpredictable enough for cryptographic applications, though its exact quality depends on the OS implementation. On a UNIX-like system this will query `/dev/urandom`, and on Windows it will use `CryptGenRandom`. If a randomness source is not found, `NotImplementedError` will be raised. New in version 2.4.

14.2 `time` — Time access and conversions

This module provides various time-related functions. It is always available, but not all functions are available on all platforms. Most of the functions defined in this module call platform C library functions with the same name. It may sometimes be helpful to consult the platform documentation, because the semantics of these functions varies among platforms.

An explanation of some terminology and conventions is in order.

- The *epoch* is the point where the time starts. On January 1st of that year, at 0 hours, the “time since the epoch” is zero. For UNIX, the epoch is 1970. To find out what the epoch is, look at `gmtime(0)`.
- The functions in this module do not handle dates and times before the epoch or far in the future. The cut-off point in the future is determined by the C library; for UNIX, it is typically in 2038.
- **Year 2000 (Y2K) issues:** Python depends on the platform's C library, which generally doesn't have year 2000 issues, since all dates and times are represented internally as seconds since the epoch. Functions accepting a `struct_time` (see below) generally require a 4-digit year. For backward compatibility, 2-digit years are supported if the module variable `accept2dyear` is a non-zero integer; this variable is initialized to 1 unless the environment variable `PYTHONY2K` is set to a non-empty string, in which case it is initialized to 0. Thus, you can set `PYTHONY2K` to a non-empty string in the environment to require 4-digit years for all year input. When 2-digit years are accepted, they are converted according to the POSIX or X/Open standard: values 69-99 are mapped to 1969-1999, and values 0-68 are mapped to 2000-2068. Values 100-1899 are always illegal. Note that this is new as of Python 1.5.2(a2); earlier versions, up to Python 1.5.1 and 1.5.2a1, would add 1900 to year values below 1900.
- UTC is Coordinated Universal Time (formerly known as Greenwich Mean Time, or GMT). The acronym UTC is not a mistake but a compromise between English and French.

- DST is Daylight Saving Time, an adjustment of the timezone by (usually) one hour during part of the year. DST rules are magic (determined by local law) and can change from year to year. The C library has a table containing the local rules (often it is read from a system file for flexibility) and is the only source of True Wisdom in this respect.
- The precision of the various real-time functions may be less than suggested by the units in which their value or argument is expressed. E.g. on most UNIX systems, the clock “ticks” only 50 or 100 times a second, and on the Mac, times are only accurate to whole seconds.
- On the other hand, the precision of `time()` and `sleep()` is better than their UNIX equivalents: times are expressed as floating point numbers, `time()` returns the most accurate time available (using UNIX `gettimeofday()` where available), and `sleep()` will accept a time with a nonzero fraction (UNIX `select()` is used to implement this, where available).
- The time value as returned by `gmtime()`, `localtime()`, and `strptime()`, and accepted by `asctime()`, `mktime()` and `strftime()`, is a sequence of 9 integers. The return values of `gmtime()`, `localtime()`, and `strptime()` also offer attribute names for individual fields.

Index	Attribute	Values
0	<code>tm_year</code>	(for example, 1993)
1	<code>tm_mon</code>	range [1,12]
2	<code>tm_mday</code>	range [1,31]
3	<code>tm_hour</code>	range [0,23]
4	<code>tm_min</code>	range [0,59]
5	<code>tm_sec</code>	range [0,61]; see (1) in <code>strftime()</code> description
6	<code>tm_wday</code>	range [0,6], Monday is 0
7	<code>tm_yday</code>	range [1,366]
8	<code>tm_isdst</code>	0, 1 or -1; see below

Note that unlike the C structure, the month value is a range of 1-12, not 0-11. A year value will be handled as described under “Year 2000 (Y2K) issues” above. A `-1` argument as the daylight savings flag, passed to `mktime()` will usually result in the correct daylight savings state to be filled in.

When a tuple with an incorrect length is passed to a function expecting a `struct_time`, or having elements of the wrong type, a `TypeError` is raised.

Changed in version 2.2: The time value sequence was changed from a tuple to a `struct_time`, with the addition of attribute names for the fields.

The module defines the following functions and data items:

`accept2dayear`

Boolean value indicating whether two-digit year values will be accepted. This is true by default, but will be set to false if the environment variable `PYTHONY2K` has been set to a non-empty string. It may also be modified at run time.

`altzone`

The offset of the local DST timezone, in seconds west of UTC, if one is defined. This is negative if the local DST timezone is east of UTC (as in Western Europe, including the UK). Only use this if `daylight` is nonzero.

`asctime([t])`

Convert a tuple or `struct_time` representing a time as returned by `gmtime()` or `localtime()` to a 24-character string of the following form: `'Sun Jun 20 23:21:05 1993'`. If `t` is not provided, the current time as returned by `localtime()` is used. Locale information is not used by `asctime()`. **Note:** Unlike the C function of the same name, there is no trailing newline. Changed in version 2.1: Allowed `t` to be omitted.

`clock()`

On UNIX, return the current processor time as a floating point number expressed in seconds. The precision, and

in fact the very definition of the meaning of “processor time”, depends on that of the C function of the same name, but in any case, this is the function to use for benchmarking Python or timing algorithms.

On Windows, this function returns wall-clock seconds elapsed since the first call to this function, as a floating point number, based on the Win32 function `QueryPerformanceCounter()`. The resolution is typically better than one microsecond.

ctime ([*secs*])

Convert a time expressed in seconds since the epoch to a string representing local time. If *secs* is not provided or `None`, the current time as returned by `time()` is used. `ctime(secs)` is equivalent to `asctime(localtime(secs))`. Locale information is not used by `ctime()`. Changed in version 2.1: Allowed *secs* to be omitted. Changed in version 2.4: If *secs* is `None`, the current time is used.

daylight

Nonzero if a DST timezone is defined.

gmtime ([*secs*])

Convert a time expressed in seconds since the epoch to a `struct_time` in UTC in which the `dst` flag is always zero. If *secs* is not provided or `None`, the current time as returned by `time()` is used. Fractions of a second are ignored. See above for a description of the `struct_time` object. See `calendar.timegm()` for the inverse of this function. Changed in version 2.1: Allowed *secs* to be omitted. Changed in version 2.4: If *secs* is `None`, the current time is used.

localtime ([*secs*])

Like `gmtime()` but converts to local time. If *secs* is not provided or `None`, the current time as returned by `time()` is used. The `dst` flag is set to 1 when DST applies to the given time. Changed in version 2.1: Allowed *secs* to be omitted. Changed in version 2.4: If *secs* is `None`, the current time is used.

mktime (*t*)

This is the inverse function of `localtime()`. Its argument is the `struct_time` or full 9-tuple (since the `dst` flag is needed; use `-1` as the `dst` flag if it is unknown) which expresses the time in *local* time, not UTC. It returns a floating point number, for compatibility with `time()`. If the input value cannot be represented as a valid time, either `OverflowError` or `ValueError` will be raised (which depends on whether the invalid value is caught by Python or the underlying C libraries). The earliest date for which it can generate a time is platform-dependent.

sleep (*secs*)

Suspend execution for the given number of seconds. The argument may be a floating point number to indicate a more precise sleep time. The actual suspension time may be less than that requested because any caught signal will terminate the `sleep()` following execution of that signal’s catching routine. Also, the suspension time may be longer than requested by an arbitrary amount because of the scheduling of other activity in the system.

strftime (*format*, [*t*])

Convert a tuple or `struct_time` representing a time as returned by `gmtime()` or `localtime()` to a string as specified by the *format* argument. If *t* is not provided, the current time as returned by `localtime()` is used. *format* must be a string. `ValueError` is raised if any field in *t* is outside of the allowed range. Changed in version 2.1: Allowed *t* to be omitted. Changed in version 2.4: `ValueError` raised if a field in *t* is out of range. Changed in version 2.5: 0 is now a legal argument for any position in the time tuple; if it is normally illegal the value is forced to a correct one..

The following directives can be embedded in the *format* string. They are shown without the optional field width and precision specification, and are replaced by the indicated characters in the `strftime()` result:

Directive	Meaning	Notes
%a	Locale's abbreviated weekday name.	
%A	Locale's full weekday name.	
%b	Locale's abbreviated month name.	
%B	Locale's full month name.	
%c	Locale's appropriate date and time representation.	
%d	Day of the month as a decimal number [01,31].	
%H	Hour (24-hour clock) as a decimal number [00,23].	
%I	Hour (12-hour clock) as a decimal number [01,12].	
%j	Day of the year as a decimal number [001,366].	
%m	Month as a decimal number [01,12].	
%M	Minute as a decimal number [00,59].	
%p	Locale's equivalent of either AM or PM.	(1)
%S	Second as a decimal number [00,61].	(2)
%U	Week number of the year (Sunday as the first day of the week) as a decimal number [00,53]. All days in a new year preceding the first Sunday are considered to be in week 0.	(3)
%w	Weekday as a decimal number [0(Sunday),6].	
%W	Week number of the year (Monday as the first day of the week) as a decimal number [00,53]. All days in a new year preceding the first Monday are considered to be in week 0.	(3)
%x	Locale's appropriate date representation.	
%X	Locale's appropriate time representation.	
%y	Year without century as a decimal number [00,99].	
%Y	Year with century as a decimal number.	
%Z	Time zone name (no characters if no time zone exists).	
%%	A literal '%' character.	

Notes:

(1)When used with the `strptime()` function, the `%p` directive only affects the output hour field if the `%I` directive is used to parse the hour.

(2)The range really is 0 to 61; this accounts for leap seconds and the (very rare) double leap seconds.

(3)When used with the `strptime()` function, `%U` and `%W` are only used in calculations when the day of the week and the year are specified.

Here is an example, a format for dates compatible with that specified in the RFC 2822 Internet email standard.¹

```
>>> from time import gmtime, strftime
>>> strftime("%a, %d %b %Y %H:%M:%S +0000", gmtime())
'Thu, 28 Jun 2001 14:17:15 +0000'
```

Additional directives may be supported on certain platforms, but only the ones listed here have a meaning standardized by ANSI C.

On some platforms, an optional field width and precision specification can immediately follow the initial '%' of a directive in the following order; this is also not portable. The field width is normally 2 except for `%j` where it is 3.

strptime (*string* [, *format*])

Parse a string representing a time according to a format. The return value is a `struct_time` as returned by `gmtime()` or `localtime()`.

¹The use of `%Z` is now deprecated, but the `%z` escape that expands to the preferred hour/minute offset is not supported by all ANSI C libraries. Also, a strict reading of the original 1982 RFC 822 standard calls for a two-digit year (`%y` rather than `%Y`), but practice moved to 4-digit years long before the year 2000. The 4-digit year has been mandated by RFC 2822, which obsoletes RFC 822.

The *format* parameter uses the same directives as those used by `strftime()`; it defaults to `"%a %b %d %H:%M:%S %Y"` which matches the formatting returned by `ctime()`. If *string* cannot be parsed according to *format*, or if it has excess data after parsing, `ValueError` is raised. The default values used to fill in any missing data when more accurate values cannot be inferred are `(1900, 1, 1, 0, 0, 0, 0, 1, -1)`.

For example:

```
>>> import time
>>> time.strptime("30 Nov 00", "%d %b %Y")
(2000, 11, 30, 0, 0, 0, 3, 335, -1)
```

Support for the `%Z` directive is based on the values contained in `tzname` and whether `daylight` is true. Because of this, it is platform-specific except for recognizing UTC and GMT which are always known (and are considered to be non-daylight savings timezones).

struct_time

The type of the time value sequence returned by `gmtime()`, `localtime()`, and `strptime()`. New in version 2.2.

time()

Return the time as a floating point number expressed in seconds since the epoch, in UTC. Note that even though the time is always returned as a floating point number, not all systems provide time with a better precision than 1 second. While this function normally returns non-decreasing values, it can return a lower value than a previous call if the system clock has been set back between the two calls.

timezone

The offset of the local (non-DST) timezone, in seconds west of UTC (negative in most of Western Europe, positive in the US, zero in the UK).

tzname

A tuple of two strings: the first is the name of the local non-DST timezone, the second is the name of the local DST timezone. If no DST timezone is defined, the second string should not be used.

tzset()

Resets the time conversion rules used by the library routines. The environment variable `TZ` specifies how this is done. New in version 2.3.

Availability: UNIX.

Note: Although in many cases, changing the `TZ` environment variable may affect the output of functions like `localtime` without calling `tzset`, this behavior should not be relied on.

The `TZ` environment variable should contain no whitespace.

The standard format of the `TZ` environment variable is: (whitespace added for clarity)

```
std offset [dst [offset[,start[/time], end[/time]]]]
```

Where:

`std` and `dst` Three or more alphanumerics giving the timezone abbreviations. These will be propagated into `time.tzname`

`offset` The offset has the form: $\pm hh[:mm[:ss]]$. This indicates the value added the local time to arrive at UTC. If preceded by a '-', the timezone is east of the Prime Meridian; otherwise, it is west. If no offset follows `dst`, summer time is assumed to be one hour ahead of standard time.

`start[/time,end[/time]]` Indicates when to change to and back from DST. The format of the start and end dates are one of the following:

Jn The Julian day *n* ($1 \leq n \leq 365$). Leap days are not counted, so in all years February 28 is day 59 and March 1 is day 60.

n The zero-based Julian day ($0 \leq n \leq 365$). Leap days are counted, and it is possible to refer to February 29.

*Mm.n.d*The *d*'th day ($0 \leq d \leq 6$) or week *n* of month *m* of the year ($1 \leq n \leq 5$, $1 \leq m \leq 12$, where week 5 means "the last *d* day in month *m*" which may occur in either the fourth or the fifth week). Week 1 is the first week in which the *d*'th day occurs. Day zero is Sunday.

time has the same format as offset except that no leading sign ('-' or '+') is allowed. The default, if time is not given, is 02:00:00.

```
>>> os.environ['TZ'] = 'EST+05EDT,M4.1.0,M10.5.0'
>>> time.tzset()
>>> time.strftime('%X %x %Z')
'02:07:36 05/08/03 EDT'
>>> os.environ['TZ'] = 'AEST-10AEDT-11,M10.5.0,M3.5.0'
>>> time.tzset()
>>> time.strftime('%X %x %Z')
'16:08:12 05/08/03 AEST'
```

On many UNIX systems (including *BSD, Linux, Solaris, and Darwin), it is more convenient to use the system's zoneinfo (*tzfile(5)*) database to specify the timezone rules. To do this, set the TZ environment variable to the path of the required timezone datafile, relative to the root of the systems 'zoneinfo' timezone database, usually located at '/usr/share/zoneinfo'. For example, 'US/Eastern', 'Australia/Melbourne', 'Egypt' or 'Europe/Amsterdam'.

```
>>> os.environ['TZ'] = 'US/Eastern'
>>> time.tzset()
>>> time.tzname
('EST', 'EDT')
>>> os.environ['TZ'] = 'Egypt'
>>> time.tzset()
>>> time.tzname
('EET', 'EEST')
```

See Also:

[Module datetime](#) (section 5.1):

More object-oriented interface to dates and times.

[Module locale](#) (section 21.2):

Internationalization services. The locale settings can affect the return values for some of the functions in the time module.

[Module calendar](#) (section 5.2):

General calendar-related functions. `timegm()` is the inverse of `gmtime()` from this module.

14.3 optparse — More powerful command line option parser

New in version 2.3.

`optparse` is a more convenient, flexible, and powerful library for parsing command-line options than `getopt`. `optparse` uses a more declarative style of command-line parsing: you create an instance of `OptionParser`, populate it with options, and parse the command line. `optparse` allows users to specify options in the conventional GNU/POSIX syntax, and additionally generates usage and help messages for you.

Here's an example of using `optparse` in a simple script:


```

from optparse import OptionParser
[...]
parser = OptionParser()
parser.add_option("-f", "--file", dest="filename",
                  help="write report to FILE", metavar="FILE")
parser.add_option("-q", "--quiet",
                  action="store_false", dest="verbose", default=True,
                  help="don't print status messages to stdout")

(options, args) = parser.parse_args()

```

With these few lines of code, users of your script can now do the “usual thing” on the command-line, for example:

```
<yourscript> --file=outfile -q
```

As it parses the command line, `optparse` sets attributes of the `options` object returned by `parse_args()` based on user-supplied command-line values. When `parse_args()` returns from parsing this command line, `options.filename` will be `"outfile"` and `options.verbose` will be `False`. `optparse` supports both long and short options, allows short options to be merged together, and allows options to be associated with their arguments in a variety of ways. Thus, the following command lines are all equivalent to the above example:

```

<yourscript> -f outfile --quiet
<yourscript> --quiet --file outfile
<yourscript> -q -foutfile
<yourscript> -qfoutfile

```

Additionally, users can run one of

```

<yourscript> -h
<yourscript> --help

```

and `optparse` will print out a brief summary of your script’s options:

```

usage: <yourscript> [options]

options:
  -h, --help            show this help message and exit
  -f FILE, --file=FILE  write report to FILE
  -q, --quiet           don't print status messages to stdout

```

where the value of *yourscript* is determined at runtime (normally from `sys.argv[0]`).

14.3.1 Background

`optparse` was explicitly designed to encourage the creation of programs with straightforward, conventional command-line interfaces. To that end, it supports only the most common command-line syntax and semantics conventionally used under UNIX. If you are unfamiliar with these conventions, read this section to acquaint yourself with them.

Terminology

argument a string entered on the command-line, and passed by the shell to `execl()` or `execv()`. In Python, arguments are elements of `sys.argv[1:]` (`sys.argv[0]` is the name of the program being executed). UNIX shells also use the term “word”.

It is occasionally desirable to substitute an argument list other than `sys.argv[1:]`, so you should read “argument” as “an element of `sys.argv[1:]`, or of some other list provided as a substitute for `sys.argv[1:]`”.

option an argument used to supply extra information to guide or customize the execution of a program. There are many different syntaxes for options; the traditional UNIX syntax is a hyphen (“-”) followed by a single letter, e.g. “-x” or “-F”. Also, traditional UNIX syntax allows multiple options to be merged into a single argument, e.g. “-x -F” is equivalent to “-xF”. The GNU project introduced a double hyphen followed by a series of hyphen-separated words, e.g. **--file** or **--dry-run**. These are the only two option syntaxes provided by `optparse`.

Some other option syntaxes that the world has seen include:

- a hyphen followed by a few letters, e.g. “-pf” (this is *not* the same as multiple options merged into a single argument)
- a hyphen followed by a whole word, e.g. “-file” (this is technically equivalent to the previous syntax, but they aren’t usually seen in the same program)
- a plus sign followed by a single letter, or a few letters, or a word, e.g. “+f”, “+rgb”
- a slash followed by a letter, or a few letters, or a word, e.g. “/f”, “/file”

These option syntaxes are not supported by `optparse`, and they never will be. This is deliberate: the first three are non-standard on any environment, and the last only makes sense if you’re exclusively targeting VMS, MS-DOS, and/or Windows.

option argument an argument that follows an option, is closely associated with that option, and is consumed from the argument list when that option is. With `optparse`, option arguments may either be in a separate argument from their option:

```
-f foo
--file foo
```

or included in the same argument:

```
-ffoo
--file=foo
```

Typically, a given option either takes an argument or it doesn’t. Lots of people want an “optional option arguments” feature, meaning that some options will take an argument if they see it, and won’t if they don’t. This is somewhat controversial, because it makes parsing ambiguous: if “-a” takes an optional argument and “-b” is another option entirely, how do we interpret “-ab”? Because of this ambiguity, `optparse` does not support this feature.

positional argument something leftover in the argument list after options have been parsed, i.e. after options and their arguments have been parsed and removed from the argument list.

required option an option that must be supplied on the command-line; note that the phrase “required option” is self-contradictory in English. `optparse` doesn’t prevent you from implementing required options, but doesn’t give you much help at it either. See `examples/required_1.py` and `examples/required_2.py` in the `optparse` source distribution for two ways to implement required options with `optparse`.

For example, consider this hypothetical command-line:

```
prog -v --report /tmp/report.txt foo bar
```

-v and **--report** are both options. Assuming that **--report** takes one argument, `"/tmp/report.txt"` is an option argument. `"foo"` and `"bar"` are positional arguments.

What are options for?

Options are used to provide extra information to tune or customize the execution of a program. In case it wasn't clear, options are usually *optional*. A program should be able to run just fine with no options whatsoever. (Pick a random program from the UNIX or GNU toolsets. Can it run without any options at all and still make sense? The main exceptions are `find`, `tar`, and `dd`—all of which are mutant oddballs that have been rightly criticized for their non-standard syntax and confusing interfaces.)

Lots of people want their programs to have “required options”. Think about it. If it's required, then it's *not optional*! If there is a piece of information that your program absolutely requires in order to run successfully, that's what positional arguments are for.

As an example of good command-line interface design, consider the humble `cp` utility, for copying files. It doesn't make much sense to try to copy files without supplying a destination and at least one source. Hence, `cp` fails if you run it with no arguments. However, it has a flexible, useful syntax that does not require any options at all:

```
cp SOURCE DEST
cp SOURCE ... DEST-DIR
```

You can get pretty far with just that. Most `cp` implementations provide a bunch of options to tweak exactly how the files are copied: you can preserve mode and modification time, avoid following symlinks, ask before clobbering existing files, etc. But none of this distracts from the core mission of `cp`, which is to copy either one file to another, or several files to another directory.

What are positional arguments for?

Positional arguments are for those pieces of information that your program absolutely, positively requires to run.

A good user interface should have as few absolute requirements as possible. If your program requires 17 distinct pieces of information in order to run successfully, it doesn't much matter *how* you get that information from the user—most people will give up and walk away before they successfully run the program. This applies whether the user interface is a command-line, a configuration file, or a GUI: if you make that many demands on your users, most of them will simply give up.

In short, try to minimize the amount of information that users are absolutely required to supply—use sensible defaults whenever possible. Of course, you also want to make your programs reasonably flexible. That's what options are for. Again, it doesn't matter if they are entries in a config file, widgets in the “Preferences” dialog of a GUI, or command-line options—the more options you implement, the more flexible your program is, and the more complicated its implementation becomes. Too much flexibility has drawbacks as well, of course; too many options can overwhelm users and make your code much harder to maintain.

14.3.2 Tutorial

While `optparse` is quite flexible and powerful, it's also straightforward to use in most cases. This section covers the code patterns that are common to any `optparse`-based program.

First, you need to import the `OptionParser` class; then, early in the main program, create an `OptionParser` instance:

```
from optparse import OptionParser
[...]  
parser = OptionParser()
```

Then you can start defining options. The basic syntax is:

```
parser.add_option(opt_str, ...,  
                  attr=value, ...)
```

Each option has one or more option strings, such as **-f** or **--file**, and several option attributes that tell `optparse` what to expect and what to do when it encounters that option on the command line.

Typically, each option will have one short option string and one long option string, e.g.:

```
parser.add_option("-f", "--file", ...)
```

You're free to define as many short option strings and as many long option strings as you like (including zero), as long as there is at least one option string overall.

The option strings passed to `add_option()` are effectively labels for the option defined by that call. For brevity, we will frequently refer to *encountering an option* on the command line; in reality, `optparse` encounters *option strings* and looks up options from them.

Once all of your options are defined, instruct `optparse` to parse your program's command line:

```
(options, args) = parser.parse_args()
```

(If you like, you can pass a custom argument list to `parse_args()`, but that's rarely necessary: by default it uses `sys.argv[1:]`.)

`parse_args()` returns two values:

- `options`, an object containing values for all of your options—e.g. if **--file** takes a single string argument, then `options.file` will be the filename supplied by the user, or `None` if the user did not supply that option
- `args`, the list of positional arguments leftover after parsing options

This tutorial section only covers the four most important option attributes: `action`, `type`, `dest` (destination), and `help`. Of these, `action` is the most fundamental.

Understanding option actions

Actions tell `optparse` what to do when it encounters an option on the command line. There is a fixed set of actions hard-coded into `optparse`; adding new actions is an advanced topic covered in section 14.3.5, Extending

`optparse`. Most actions tell `optparse` to store a value in some variable—for example, take a string from the command line and store it in an attribute of `options`.

If you don't specify an option action, `optparse` defaults to `store`.

The store action

The most common option action is `store`, which tells `optparse` to take the next argument (or the remainder of the current argument), ensure that it is of the correct type, and store it to your chosen destination.

For example:

```
parser.add_option("-f", "--file",
                  action="store", type="string", dest="filename")
```

Now let's make up a fake command line and ask `optparse` to parse it:

```
args = ["-f", "foo.txt"]
(options, args) = parser.parse_args(args)
```

When `optparse` sees the option string `"-f"`, it consumes the next argument, `"foo.txt"`, and stores it in `options.filename`. So, after this call to `parse_args()`, `options.filename` is `"foo.txt"`.

Some other option types supported by `optparse` are `int` and `float`. Here's an option that expects an integer argument:

```
parser.add_option("-n", type="int", dest="num")
```

Note that this option has no long option string, which is perfectly acceptable. Also, there's no explicit action, since the default is `store`.

Let's parse another fake command-line. This time, we'll jam the option argument right up against the option: since `"-n42"` (one argument) is equivalent to `"-n 42"` (two arguments), the code

```
(options, args) = parser.parse_args(["-n42"])
print options.num
```

will print `"42"`.

If you don't specify a type, `optparse` assumes `string`. Combined with the fact that the default action is `store`, that means our first example can be a lot shorter:

```
parser.add_option("-f", "--file", dest="filename")
```

If you don't supply a destination, `optparse` figures out a sensible default from the option strings: if the first long option string is `--foo-bar`, then the default destination is `foo_bar`. If there are no long option strings, `optparse` looks at the first short option string: the default destination for `"-f"` is `f`.

`optparse` also includes built-in `long` and `complex` types. Adding types is covered in section 14.3.5, *Extending `optparse`*.

Handling boolean (flag) options

Flag options—set a variable to true or false when a particular option is seen—are quite common. `optparse` supports them with two separate actions, `store_true` and `store_false`. For example, you might have a `verbose` flag that is turned on with `"-v"` and off with `"-q"`:

```
parser.add_option("-v", action="store_true", dest="verbose")
parser.add_option("-q", action="store_false", dest="verbose")
```

Here we have two different options with the same destination, which is perfectly OK. (It just means you have to be a bit careful when setting default values—see below.)

When `optparse` encounters `"-v"` on the command line, it sets `options.verbose` to `True`; when it encounters `"-q"`, `options.verbose` is set to `False`.

Other actions

Some other actions supported by `optparse` are:

store_const store a constant value

append append this option's argument to a list

count increment a counter by one

callback call a specified function

These are covered in section 14.3.3, Reference Guide and section 14.3.4, Option Callbacks.

Default values

All of the above examples involve setting some variable (the “destination”) when certain command-line options are seen. What happens if those options are never seen? Since we didn't supply any defaults, they are all set to `None`. This is usually fine, but sometimes you want more control. `optparse` lets you supply a default value for each destination, which is assigned before the command line is parsed.

First, consider the `verbose/quiet` example. If we want `optparse` to set `verbose` to `True` unless `"-q"` is seen, then we can do this:

```
parser.add_option("-v", action="store_true", dest="verbose", default=True)
parser.add_option("-q", action="store_false", dest="verbose")
```

Since default values apply to the *destination* rather than to any particular option, and these two options happen to have the same destination, this is exactly equivalent:

```
parser.add_option("-v", action="store_true", dest="verbose")
parser.add_option("-q", action="store_false", dest="verbose", default=True)
```

Consider this:

```
parser.add_option("-v", action="store_true", dest="verbose", default=False)
parser.add_option("-q", action="store_false", dest="verbose", default=True)
```

Again, the default value for `verbose` will be `True`: the last default value supplied for any particular destination is the one that counts.

A clearer way to specify default values is the `set_defaults()` method of `OptionParser`, which you can call at any time before calling `parse_args()`:

```
parser.set_defaults(verbose=True)
parser.add_option(...)
(options, args) = parser.parse_args()
```

As before, the last value specified for a given option destination is the one that counts. For clarity, try to use one method or the other of setting default values, not both.

Generating help

`optparse`'s ability to generate help and usage text automatically is useful for creating user-friendly command-line interfaces. All you have to do is supply a `help` value for each option, and optionally a short usage message for your whole program. Here's an `OptionParser` populated with user-friendly (documented) options:

```
usage = "usage: %prog [options] arg1 arg2"
parser = OptionParser(usage=usage)
parser.add_option("-v", "--verbose",
                  action="store_true", dest="verbose", default=True,
                  help="make lots of noise [default]")
parser.add_option("-q", "--quiet",
                  action="store_false", dest="verbose",
                  help="be vewwy quiet (I'm hunting wabbits)")
parser.add_option("-f", "--filename",
                  metavar="FILE", help="write output to FILE"),
parser.add_option("-m", "--mode",
                  default="intermediate",
                  help="interaction mode: novice, intermediate, "
                       "or expert [default: %default]")
```

If `optparse` encounters either **-h** or **--help** on the command-line, or if you just call `parser.print_help()`, it prints the following to standard output:

```
usage: <yourscript> [options] arg1 arg2

options:
  -h, --help            show this help message and exit
  -v, --verbose          make lots of noise [default]
  -q, --quiet           be vewwy quiet (I'm hunting wabbits)
  -f FILE, --filename=FILE
                        write output to FILE
  -m MODE, --mode=MODE  interaction mode: novice, intermediate, or
                        expert [default: intermediate]
```

(If the help output is triggered by a help option, `optparse` exits after printing the help text.)

There's a lot going on here to help `optparse` generate the best possible help message:

- the script defines its own usage message:

```
usage = "usage: %prog [options] arg1 arg2"
```

`optparse` expands `%prog` in the usage string to the name of the current program, i.e. `os.path.basename(sys.argv[0])`. The expanded string is then printed before the detailed option help.

If you don't supply a usage string, `optparse` uses a bland but sensible default: `"usage: %prog [options]"`, which is fine if your script doesn't take any positional arguments.

- every option defines a help string, and doesn't worry about line- wrapping—`optparse` takes care of wrapping lines and making the help output look good.
- options that take a value indicate this fact in their automatically-generated help message, e.g. for the "mode" option:

```
-m MODE, --mode=MODE
```

Here, "MODE" is called the meta-variable: it stands for the argument that the user is expected to supply to **-m/--mode**. By default, `optparse` converts the destination variable name to uppercase and uses that for the meta-variable. Sometimes, that's not what you want—for example, the **--filename** option explicitly sets `metavar="FILE"`, resulting in this automatically-generated option description:

```
-f FILE, --filename=FILE
```

This is important for more than just saving space, though: the manually written help text uses the meta-variable "FILE" to clue the user in that there's a connection between the semi-formal syntax `"-f FILE"` and the informal semantic description "write output to FILE". This is a simple but effective way to make your help text a lot clearer and more useful for end users.

- options that have a default value can include `%default` in the help string—`optparse` will replace it with `str()` of the option's default value. If an option has no default value (or the default value is `None`), `%default` expands to `none`.

When dealing with many options, it is convenient to group these options for better help output. An `OptionParser` can contain several option groups, each of which can contain several options.

Continuing with the parser defined above, adding an `OptionGroup` to a parser is easy:

```
group = OptionGroup(parser, ``Dangerous Options``,
                    ``Caution: use these options at your own risk. ``
                    ``It is believed that some of them bite.'`)
group.add_option(``-g``, action='store_true', help='Group option.')
parser.add_option_group(group)
```

This would result in the following help output:


```
usage:  [options] arg1 arg2

options:
  -h, --help            show this help message and exit
  -v, --verbose         make lots of noise [default]
  -q, --quiet           be vewwy quiet (I'm hunting wabbits)
  -fFILE, --file=FILE  write output to FILE
  -mMODE, --mode=MODE  interaction mode: one of 'novice', 'intermediate'
                      [default], 'expert'

Dangerous Options:
  Caution: use of these options is at your own risk.  It is believed that
  some of them bite.
  -g                    Group option.
```

Printing a version string

Similar to the brief usage string, `optparse` can also print a version string for your program. You have to supply the string as the `version` argument to `OptionParser`:

```
parser = OptionParser(usage="%prog [-f] [-q]", version="%prog 1.0")
```

`"%prog"` is expanded just like it is in usage. Apart from that, `version` can contain anything you like. When you supply it, `optparse` automatically adds a **--version** option to your parser. If it encounters this option on the command line, it expands your version string (by replacing `"%prog"`), prints it to stdout, and exits.

For example, if your script is called `/usr/bin/foo`:

```
$ /usr/bin/foo --version
foo 1.0
```

How `optparse` handles errors

There are two broad classes of errors that `optparse` has to worry about: programmer errors and user errors. Programmer errors are usually erroneous calls to `parser.add_option()`, e.g. invalid option strings, unknown option attributes, missing option attributes, etc. These are dealt with in the usual way: raise an exception (either `optparse.OptionError` or `TypeError`) and let the program crash.

Handling user errors is much more important, since they are guaranteed to happen no matter how stable your code is. `optparse` can automatically detect some user errors, such as bad option arguments (passing `"-n 4x"` where **-n** takes an integer argument), missing arguments (`"-n"` at the end of the command line, where **-n** takes an argument of any type). Also, you can call `parser.error()` to signal an application-defined error condition:

```
(options, args) = parser.parse_args()
[...]
if options.a and options.b:
    parser.error("options -a and -b are mutually exclusive")
```

In either case, `optparse` handles the error the same way: it prints the program's usage message and an error message to standard error and exits with error status 2.

Consider the first example above, where the user passes "4x" to an option that takes an integer:

```
$ /usr/bin/foo -n 4x
usage: foo [options]

foo: error: option -n: invalid integer value: '4x'
```

Or, where the user fails to pass a value at all:

```
$ /usr/bin/foo -n
usage: foo [options]

foo: error: -n option requires an argument
```

`optparse`-generated error messages take care always to mention the option involved in the error; be sure to do the same when calling `parser.error()` from your application code.

If `optparse`'s default error-handling behaviour does not suite your needs, you'll need to subclass `OptionParser` and override `exit()` and/or `error()`.

Putting it all together

Here's what `optparse`-based scripts usually look like:

```
from optparse import OptionParser
[...]
def main():
    usage = "usage: %prog [options] arg"
    parser = OptionParser(usage)
    parser.add_option("-f", "--file", dest="filename",
                      help="read data from FILENAME")
    parser.add_option("-v", "--verbose",
                      action="store_true", dest="verbose")
    parser.add_option("-q", "--quiet",
                      action="store_false", dest="verbose")
    [...]
    (options, args) = parser.parse_args()
    if len(args) != 1:
        parser.error("incorrect number of arguments")
    if options.verbose:
        print "reading %s..." % options.filename
    [...]

if __name__ == "__main__":
    main()
```

14.3.3 Reference Guide

Creating the parser

The first step in using `optparse` is to create an `OptionParser` instance:

```
parser = OptionParser(...)
```

The `OptionParser` constructor has no required arguments, but a number of optional keyword arguments. You should always pass them as keyword arguments, i.e. do not rely on the order in which the arguments are declared.

usage (default: "%prog [options]") The usage summary to print when your program is run incorrectly or with a help option. When `optparse` prints the usage string, it expands `%prog` to `os.path.basename(sys.argv[0])` (or to `prog` if you passed that keyword argument). To suppress a usage message, pass the special value `optparse.SUPPRESS_USAGE`.

option_list (default: []) A list of `Option` objects to populate the parser with. The options in `option_list` are added after any options in `standard_option_list` (a class attribute that may be set by `OptionParser` subclasses), but before any version or help options. Deprecated; use `add_option()` after creating the parser instead.

option_class (default: `optparse.Option`) Class to use when adding options to the parser in `add_option()`.

version (default: `None`) A version string to print when the user supplies a version option. If you supply a true value for `version`, `optparse` automatically adds a version option with the single option string `--version`. The substring `"%prog"` is expanded the same as for `usage`.

conflict_handler (default: "error") Specifies what to do when options with conflicting option strings are added to the parser; see section 14.3.3, Conflicts between options.

description (default: `None`) A paragraph of text giving a brief overview of your program. `optparse` reformats this paragraph to fit the current terminal width and prints it when the user requests help (after `usage`, but before the list of options).

formatter (default: a new `IndentedHelpFormatter`) An instance of `optparse.HelpFormatter` that will be used for printing help text. `optparse` provides two concrete classes for this purpose: `IndentedHelpFormatter` and `TitledHelpFormatter`.

add_help_option (default: `True`) If true, `optparse` will add a help option (with option strings `"-h"` and `--help`) to the parser.

prog The string to use when expanding `"%prog"` in `usage` and `version` instead of `os.path.basename(sys.argv[0])`.

Populating the parser

There are several ways to populate the parser with options. The preferred way is by using `OptionParser.add_option()`, as shown in section 14.3.2, the tutorial. `add_option()` can be called in one of two ways:

- pass it an `Option` instance (as returned by `make_option()`)
- pass it any combination of positional and keyword arguments that are acceptable to `make_option()` (i.e., to the `Option` constructor), and it will create the `Option` instance for you

The other alternative is to pass a list of pre-constructed `Option` instances to the `OptionParser` constructor, as in:

```

option_list = [
    make_option("-f", "--filename",
                action="store", type="string", dest="filename"),
    make_option("-q", "--quiet",
                action="store_false", dest="verbose"),
]
parser = OptionParser(option_list=option_list)

```

(`make_option()` is a factory function for creating `Option` instances; currently it is an alias for the `Option` constructor. A future version of `optparse` may split `Option` into several classes, and `make_option()` will pick the right class to instantiate. Do not instantiate `Option` directly.)

Defining options

Each `Option` instance represents a set of synonymous command-line option strings, e.g. **-f** and **--file**. You can specify any number of short or long option strings, but you must specify at least one overall option string.

The canonical way to create an `Option` instance is with the `add_option()` method of `OptionParser`:

```

parser.add_option(opt_str[, ...], attr=value, ...)

```

To define an option with only a short option string:

```

parser.add_option("-f", attr=value, ...)

```

And to define an option with only a long option string:

```

parser.add_option("--foo", attr=value, ...)

```

The keyword arguments define attributes of the new `Option` object. The most important option attribute is `action`, and it largely determines which other attributes are relevant or required. If you pass irrelevant option attributes, or fail to pass required ones, `optparse` raises an `OptionError` exception explaining your mistake.

An option's *action* determines what `optparse` does when it encounters this option on the command-line. The standard option actions hard-coded into `optparse` are:

store store this option's argument (default)

store_const store a constant value

store_true store a true value

store_false store a false value

append append this option's argument to a list

append_const append a constant value to a list

count increment a counter by one

callback call a specified function

help print a usage message including all options and the documentation for them

(If you don't supply an action, the default is `store`. For this action, you may also supply `type` and `dest` option attributes; see below.)

As you can see, most actions involve storing or updating a value somewhere. `optparse` always creates a special object for this, conventionally called `options` (it happens to be an instance of `optparse.Values`). Option arguments (and various other values) are stored as attributes of this object, according to the `dest` (destination) option attribute.

For example, when you call

```
parser.parse_args()
```

one of the first things `optparse` does is create the `options` object:

```
options = Values()
```

If one of the options in this parser is defined with

```
parser.add_option("-f", "--file", action="store", type="string", dest="filename")
```

and the command-line being parsed includes any of the following:

```
-ffoo
-f foo
--file=foo
--file foo
```

then `optparse`, on seeing this option, will do the equivalent of

```
options.filename = "foo"
```

The `type` and `dest` option attributes are almost as important as `action`, but `action` is the only one that makes sense for *all* options.

Standard option actions

The various option actions all have slightly different requirements and effects. Most actions have several relevant option attributes which you may specify to guide `optparse`'s behaviour; a few have required attributes, which you must specify for any option using that action.

- `store` [relevant: `type`, `dest`, `nargs`, `choices`]

The option must be followed by an argument, which is converted to a value according to `type` and stored in `dest`. If `nargs > 1`, multiple arguments will be consumed from the command line; all will be converted according to `type` and stored to `dest` as a tuple. See the "Option types" section below.

If `choices` is supplied (a list or tuple of strings), the type defaults to `choice`.

If `type` is not supplied, it defaults to `string`.

If `dest` is not supplied, `optparse` derives a destination from the first long option string (e.g., **--foo-bar** implies `foo_bar`). If there are no long option strings, `optparse` derives a destination from the first short option string (e.g., `-f` implies `f`).

Example:

```
parser.add_option("-f")
parser.add_option("-p", type="float", nargs=3, dest="point")
```

As it parses the command line

```
-f foo.txt -p 1 -3.5 4 -fbar.txt
```

`optparse` will set

```
options.f = "foo.txt"
options.point = (1.0, -3.5, 4.0)
options.f = "bar.txt"
```

- `store_const` [required: `const`; relevant: `dest`]

The value `const` is stored in `dest`.

Example:

```
parser.add_option("-q", "--quiet",
                  action="store_const", const=0, dest="verbose")
parser.add_option("-v", "--verbose",
                  action="store_const", const=1, dest="verbose")
parser.add_option("--noisy",
                  action="store_const", const=2, dest="verbose")
```

If **--noisy** is seen, `optparse` will set

```
options.verbose = 2
```

- `store_true` [relevant: `dest`]

A special case of `store_const` that stores a true value to `dest`.

- `store_false` [relevant: `dest`]

Like `store_true`, but stores a false value.

Example:

```
parser.add_option("--clobber", action="store_true", dest="clobber")
parser.add_option("--no-clobber", action="store_false", dest="clobber")
```

- `append` [relevant: `type`, `dest`, `nargs`, `choices`]

The option must be followed by an argument, which is appended to the list in `dest`. If no default value for `dest` is supplied, an empty list is automatically created when `optparse` first encounters this option on the command-line. If `nargs > 1`, multiple arguments are consumed, and a tuple of length `nargs` is appended to `dest`.

The defaults for `type` and `dest` are the same as for the `store` action.

Example:

```
parser.add_option("-t", "--tracks", action="append", type="int")
```

If `"-t3"` is seen on the command-line, `optparse` does the equivalent of:

```
options.tracks = []
options.tracks.append(int("3"))
```

If, a little later on, `--tracks=4` is seen, it does:

```
options.tracks.append(int("4"))
```

- `append_const` [required: `const`; relevant: `dest`]

Like `store_const`, but the value `const` is appended to `dest`; as with `append`, `dest` defaults to `None`, and an empty list is automatically created the first time the option is encountered.

- `count` [relevant: `dest`]

Increment the integer stored at `dest`. If no default value is supplied, `dest` is set to zero before being incremented the first time.

Example:

```
parser.add_option("-v", action="count", dest="verbosity")
```

The first time `"-v"` is seen on the command line, `optparse` does the equivalent of:

```
options.verbosity = 0
options.verbosity += 1
```

Every subsequent occurrence of `"-v"` results in

```
options.verbosity += 1
```

- `callback` [required: `callback`; relevant: `type`, `nargs`, `callback_args`, `callback_kwargs`]

Call the function specified by `callback`, which is called as

```
func(option, opt_str, value, parser, *args, **kwargs)
```

See section 14.3.4, Option Callbacks for more detail.

- `help`

Prints a complete help message for all the options in the current option parser. The help message is constructed from the `usage` string passed to `OptionParser`'s constructor and the `help` string passed to every option.

If no `help` string is supplied for an option, it will still be listed in the help message. To omit an option entirely, use the special value `optparse.SUPPRESS_HELP`.

optparse automatically adds a help option to all OptionParsers, so you do not normally need to create one.

Example:

```
from optparse import OptionParser, SUPPRESS_HELP

parser = OptionParser()
parser.add_option("-h", "--help", action="help"),
parser.add_option("-v", action="store_true", dest="verbose",
                  help="Be moderately verbose")
parser.add_option("--file", dest="filename",
                  help="Input file to read data from"),
parser.add_option("--secret", help=SUPPRESS_HELP)
```

If optparse sees either **h** or **--help** on the command line, it will print something like the following help message to stdout (assuming `sys.argv[0]` is `"foo.py"`):

```
usage: foo.py [options]

options:
  -h, --help            Show this help message and exit
  -v                    Be moderately verbose
  --file=FILENAME       Input file to read data from
```

After printing the help message, optparse terminates your process with `sys.exit(0)`.

- **version**

Prints the version number supplied to the OptionParser to stdout and exits. The version number is actually formatted and printed by the `print_version()` method of OptionParser. Generally only relevant if the `version` argument is supplied to the OptionParser constructor. As with help options, you will rarely create version options, since optparse automatically adds them when needed.

Option attributes

The following option attributes may be passed as keyword arguments to `parser.add_option()`. If you pass an option attribute that is not relevant to a particular option, or fail to pass a required option attribute, optparse raises `OptionError`.

- **action** (default: "store")

Determines optparse's behaviour when this option is seen on the command line; the available options are documented above.

- **type** (default: "string")

The argument type expected by this option (e.g., "string" or "int"); the available option types are documented below.

- **dest** (default: derived from option strings)

If the option's action implies writing or modifying a value somewhere, this tells optparse where to write it: `dest` names an attribute of the options object that optparse builds as it parses the command line.

- **default** (deprecated)

The value to use for this option's destination if the option is not seen on the command line. Deprecated; use `parser.set_defaults()` instead.

- `nargs` (default: 1)
How many arguments of type `type` should be consumed when this option is seen. If > 1 , `optparse` will store a tuple of values to `dest`.
- `const`
For actions that store a constant value, the constant value to store.
- `choices`
For options of type "choice", the list of strings the user may choose from.
- `callback`
For options with action "callback", the callable to call when this option is seen. See section 14.3.4, Option Callbacks for detail on the arguments passed to `callable`.
- `callback_args`, `callback_kwargs`
Additional positional and keyword arguments to pass to `callback` after the four standard callback arguments.
- `help`
Help text to print for this option when listing all available options after the user supplies a `help` option (such as `--help`). If no help text is supplied, the option will be listed without help text. To hide this option, use the special value `SUPPRESS_HELP`.
- `metavar` (default: derived from option strings)
Stand-in for the option argument(s) to use when printing help text. See section 14.3.2, the tutorial for an example.

Standard option types

`optparse` has six built-in option types: `string`, `int`, `long`, `choice`, `float` and `complex`. If you need to add new option types, see section 14.3.5, Extending `optparse`.

Arguments to string options are not checked or converted in any way: the text on the command line is stored in the destination (or passed to the callback) as-is.

Integer arguments (type `int` or `long`) are parsed as follows:

- if the number starts with `0x`, it is parsed as a hexadecimal number
- if the number starts with `0`, it is parsed as an octal number
- if the number starts with `0b`, it is parsed as a binary number
- otherwise, the number is parsed as a decimal number

The conversion is done by calling either `int()` or `long()` with the appropriate base (2, 8, 10, or 16). If this fails, so will `optparse`, although with a more useful error message.

`float` and `complex` option arguments are converted directly with `float()` and `complex()`, with similar error-handling.

`choice` options are a subtype of `string` options. The `choices` option attribute (a sequence of strings) defines the set of allowed option arguments. `optparse.check_choice()` compares user-supplied option arguments against this master list and raises `OptionValueError` if an invalid string is given.

Parsing arguments

The whole point of creating and populating an `OptionParser` is to call its `parse_args()` method:

```
(options, args) = parser.parse_args(args=None, values=None)
```

where the input parameters are

args the list of arguments to process (default: `sys.argv[1:]`)

values object to store option arguments in (default: a new instance of `optparse.Values`)

and the return values are

options the same object that was passed in as `options`, or the `optparse.Values` instance created by `optparse`

args the leftover positional arguments after all options have been processed

The most common usage is to supply neither keyword argument. If you supply `options`, it will be modified with repeated `setattr()` calls (roughly one for every option argument stored to an option destination) and returned by `parse_args()`.

If `parse_args()` encounters any errors in the argument list, it calls the `OptionParser`'s `error()` method with an appropriate end-user error message. This ultimately terminates your process with an exit status of 2 (the traditional UNIX exit status for command-line errors).

Querying and manipulating your option parser

Sometimes, it's useful to poke around your option parser and see what's there. `OptionParser` provides a couple of methods to help you out:

has_option(opt_str) Return true if the `OptionParser` has an option with option string `opt_str` (e.g., **-q** or **--verbose**).

get_option(opt_str) Returns the `Option` instance with the option string `opt_str`, or `None` if no options have that option string.

remove_option(opt_str) If the `OptionParser` has an option corresponding to `opt_str`, that option is removed. If that option provided any other option strings, all of those option strings become invalid. If `opt_str` does not occur in any option belonging to this `OptionParser`, raises `ValueError`.

Conflicts between options

If you're not careful, it's easy to define options with conflicting option strings:

```
parser.add_option("-n", "--dry-run", ...)
[...]
parser.add_option("-n", "--noisy", ...)
```

(This is particularly true if you've defined your own `OptionParser` subclass with some standard options.)

Every time you add an option, `optparse` checks for conflicts with existing options. If it finds any, it invokes the current conflict-handling mechanism. You can set the conflict-handling mechanism either in the constructor:

```
parser = OptionParser(..., conflict_handler=handler)
```

or with a separate call:

```
parser.set_conflict_handler(handler)
```

The available conflict handlers are:

- error (default)** assume option conflicts are a programming error and raise `OptionConflictError`
- resolve** resolve option conflicts intelligently (see below)

As an example, let's define an `OptionParser` that resolves conflicts intelligently and add conflicting options to it:

```
parser = OptionParser(conflict_handler="resolve")
parser.add_option("-n", "--dry-run", ..., help="do no harm")
parser.add_option("-n", "--noisy", ..., help="be noisy")
```

At this point, `optparse` detects that a previously-added option is already using the `"-n"` option string. Since `conflict_handler` is `"resolve"`, it resolves the situation by removing `"-n"` from the earlier option's list of option strings. Now **--dry-run** is the only way for the user to activate that option. If the user asks for help, the help message will reflect that:

```
options:
  --dry-run      do no harm
  [...]
  -n, --noisy    be noisy
```

It's possible to whittle away the option strings for a previously-added option until there are none left, and the user has no way of invoking that option from the command-line. In that case, `optparse` removes that option completely, so it doesn't show up in help text or anywhere else. Carrying on with our existing `OptionParser`:

```
parser.add_option("--dry-run", ..., help="new dry-run option")
```

At this point, the original **-n/--dry-run** option is no longer accessible, so `optparse` removes it, leaving this help text:

```
options:
  [...]
  -n, --noisy    be noisy
  --dry-run      new dry-run option
```

Cleanup

`OptionParser` instances have several cyclic references. This should not be a problem for Python's garbage collector, but you may wish to break the cyclic references explicitly by calling `destroy()` on your `OptionParser` once you

are done with it. This is particularly useful in long-running applications where large object graphs are reachable from your `OptionParser`.

Other methods

`OptionParser` supports several other public methods:

- `set_usage(usage)`
Set the usage string according to the rules described above for the `usage` constructor keyword argument. Passing `None` sets the default usage string; use `SUPPRESS_USAGE` to suppress a usage message.
- `enable_interspersed_args()`, `disable_interspersed_args()`
Enable/disable positional arguments interspersed with options, similar to GNU `getopt` (enabled by default). For example, if `"-a"` and `"-b"` are both simple options that take no arguments, `optparse` normally accepts this syntax:

```
prog -a arg1 -b arg2
```

and treats it as equivalent to

```
prog -a -b arg1 arg2
```

To disable this feature, call `disable_interspersed_args()`. This restores traditional UNIX syntax, where option parsing stops with the first non-option argument.

- `set_defaults(dest=value, ...)`
Set default values for several option destinations at once. Using `set_defaults()` is the preferred way to set default values for options, since multiple options can share the same destination. For example, if several “mode” options all set the same destination, any one of them can set the default, and the last one wins:

```
parser.add_option("--advanced", action="store_const",
                  dest="mode", const="advanced",
                  default="novice")    # overridden below
parser.add_option("--novice", action="store_const",
                  dest="mode", const="novice",
                  default="advanced")  # overrides above setting
```

To avoid this confusion, use `set_defaults()`:

```
parser.set_defaults(mode="advanced")
parser.add_option("--advanced", action="store_const",
                  dest="mode", const="advanced")
parser.add_option("--novice", action="store_const",
                  dest="mode", const="novice")
```

14.3.4 Option Callbacks

When `optparse`’s built-in actions and types aren’t quite enough for your needs, you have two choices: extend `optparse` or define a callback option. Extending `optparse` is more general, but overkill for a lot of simple cases. Quite often a simple callback is all you need.

There are two steps to defining a callback option:

- define the option itself using the `callback` action
- write the callback; this is a function (or method) that takes at least four arguments, as described below

Defining a callback option

As always, the easiest way to define a callback option is by using the `parser.add_option()` method. Apart from `action`, the only option attribute you must specify is `callback`, the function to call:

```
parser.add_option("-c", action="callback", callback=my_callback)
```

`callback` is a function (or other callable object), so you must have already defined `my_callback()` when you create this callback option. In this simple case, `optparse` doesn't even know if `-c` takes any arguments, which usually means that the option takes no arguments—the mere presence of `-c` on the command-line is all it needs to know. In some circumstances, though, you might want your callback to consume an arbitrary number of command-line arguments. This is where writing callbacks gets tricky; it's covered later in this section.

`optparse` always passes four particular arguments to your callback, and it will only pass additional arguments if you specify them via `callback_args` and `callback_kwargs`. Thus, the minimal callback function signature is:

```
def my_callback(option, opt, value, parser):
```

The four arguments to a callback are described below.

There are several other option attributes that you can supply when you define a callback option:

type has its usual meaning: as with the `store` or `append` actions, it instructs `optparse` to consume one argument and convert it to `type`. Rather than storing the converted value(s) anywhere, though, `optparse` passes it to your callback function.

nargs also has its usual meaning: if it is supplied and > 1 , `optparse` will consume `nargs` arguments, each of which must be convertible to `type`. It then passes a tuple of converted values to your callback.

callback_args a tuple of extra positional arguments to pass to the callback

callback_kwargs a dictionary of extra keyword arguments to pass to the callback

How callbacks are called

All callbacks are called as follows:

```
func(option, opt_str, value, parser, *args, **kwargs)
```

where

option is the `Option` instance that's calling the callback

opt_str is the option string seen on the command-line that's triggering the callback. (If an abbreviated long option was used, `opt_str` will be the full, canonical option string—e.g. if the user puts `--foo` on the command-line as an abbreviation for `--foobar`, then `opt_str` will be `--foobar`.)

value is the argument to this option seen on the command-line. `optparse` will only expect an argument if `type` is set; the type of `value` will be the type implied by the option's type. If `type` for this option is `None` (no argument expected), then `value` will be `None`. If `nargs > 1`, `value` will be a tuple of values of the appropriate type.

parser is the `OptionParser` instance driving the whole thing, mainly useful because you can access some other interesting data through its instance attributes:

parser.largs the current list of leftover arguments, ie. arguments that have been consumed but are neither options nor option arguments. Feel free to modify `parser.largs`, e.g. by adding more arguments to it. (This list will become `args`, the second return value of `parse_args()`.)

parser.rargs the current list of remaining arguments, ie. with `opt_str` and `value` (if applicable) removed, and only the arguments following them still there. Feel free to modify `parser.rargs`, e.g. by consuming more arguments.

parser.values the object where option values are by default stored (an instance of `optparse.OptionValues`). This lets callbacks use the same mechanism as the rest of `optparse` for storing option values; you don't need to mess around with globals or closures. You can also access or modify the value(s) of any options already encountered on the command-line.

args is a tuple of arbitrary positional arguments supplied via the `callback_args` option attribute.

kwargs is a dictionary of arbitrary keyword arguments supplied via `callback_kwargs`.

Raising errors in a callback

The callback function should raise `OptionValueError` if there are any problems with the option or its argument(s). `optparse` catches this and terminates the program, printing the error message you supply to `stderr`. Your message should be clear, concise, accurate, and mention the option at fault. Otherwise, the user will have a hard time figuring out what he did wrong.

Callback example 1: trivial callback

Here's an example of a callback option that takes no arguments, and simply records that the option was seen:

```
def record_foo_seen(option, opt_str, value, parser):
    parser.saw_foo = True

parser.add_option("--foo", action="callback", callback=record_foo_seen)
```

Of course, you could do that with the `store_true` action.

Callback example 2: check option order

Here's a slightly more interesting example: record the fact that `"-a"` is seen, but blow up if it comes after `"-b"` in the command-line.

```
def check_order(option, opt_str, value, parser):
    if parser.values.b:
        raise OptionValueError("can't use -a after -b")
    parser.values.a = 1
[...]
```

```
parser.add_option("-a", action="callback", callback=check_order)
parser.add_option("-b", action="store_true", dest="b")
```

Callback example 3: check option order (generalized)

If you want to re-use this callback for several similar options (set a flag, but blow up if "-b" has already been seen), it needs a bit of work: the error message and the flag that it sets must be generalized.

```
def check_order(option, opt_str, value, parser):
    if parser.values.b:
        raise OptionValueError("can't use %s after -b" % opt_str)
    setattr(parser.values, option.dest, 1)
[...]
```

```
parser.add_option("-a", action="callback", callback=check_order, dest='a')
parser.add_option("-b", action="store_true", dest="b")
parser.add_option("-c", action="callback", callback=check_order, dest='c')
```

Callback example 4: check arbitrary condition

Of course, you could put any condition in there—you're not limited to checking the values of already-defined options. For example, if you have options that should not be called when the moon is full, all you have to do is this:

```
def check_moon(option, opt_str, value, parser):
    if is_moon_full():
        raise OptionValueError("%s option invalid when moon is full"
                                % opt_str)
    setattr(parser.values, option.dest, 1)
[...]
```

```
parser.add_option("--foo",
                  action="callback", callback=check_moon, dest="foo")
```

(The definition of `is_moon_full()` is left as an exercise for the reader.)

Callback example 5: fixed arguments

Things get slightly more interesting when you define callback options that take a fixed number of arguments. Specifying that a callback option takes arguments is similar to defining a `store` or `append` option: if you define `type`, then the option takes one argument that must be convertible to that type; if you further define `nargs`, then the option takes `nargs` arguments.

Here's an example that just emulates the standard `store` action:

```
def store_value(option, opt_str, value, parser):
    setattr(parser.values, option.dest, value)
[...]
parser.add_option("--foo",
                  action="callback", callback=store_value,
                  type="int", nargs=3, dest="foo")
```

Note that `optparse` takes care of consuming 3 arguments and converting them to integers for you; all you have to do is store them. (Or whatever; obviously you don't need a callback for this example.)

Callback example 6: variable arguments

Things get hairy when you want an option to take a variable number of arguments. For this case, you must write a callback, as `optparse` doesn't provide any built-in capabilities for it. And you have to deal with certain intricacies of conventional UNIX command-line parsing that `optparse` normally handles for you. In particular, callbacks should implement the conventional rules for bare `--` and `-` arguments:

- either `--` or `-` can be option arguments
- bare `--` (if not the argument to some option): halt command-line processing and discard the `--`
- bare `-` (if not the argument to some option): halt command-line processing but keep the `-` (append it to `parser.largs`)

If you want an option that takes a variable number of arguments, there are several subtle, tricky issues to worry about. The exact implementation you choose will be based on which trade-offs you're willing to make for your application (which is why `optparse` doesn't support this sort of thing directly).

Nevertheless, here's a stab at a callback for an option with variable arguments:

```
def vararg_callback(option, opt_str, value, parser):
    assert value is None
    done = 0
    value = []
    rargs = parser.rargs
    while rargs:
        arg = rargs[0]

        # Stop if we hit an arg like "--foo", "-a", "-fx", "--file=f",
        # etc. Note that this also stops on "-3" or "-3.0", so if
        # your option takes numeric values, you will need to handle
        # this.
        if ((arg[:2] == "--" and len(arg) > 2) or
            (arg[:1] == "-" and len(arg) > 1 and arg[1] != "-")):
            break
        else:
            value.append(arg)
            del rargs[0]

    setattr(parser.values, option.dest, value)

[...]
parser.add_option("-c", "--callback",
                  action="callback", callback=varargs)
```


The main weakness with this particular implementation is that negative numbers in the arguments following `"-c"` will be interpreted as further options (probably causing an error), rather than as arguments to `"-c"`. Fixing this is left as an exercise for the reader.

14.3.5 Extending `optparse`

Since the two major controlling factors in how `optparse` interprets command-line options are the action and type of each option, the most likely direction of extension is to add new actions and new types.

Adding new types

To add new types, you need to define your own subclass of `optparse`'s `Option` class. This class has a couple of attributes that define `optparse`'s types: `TYPES` and `TYPE_CHECKER`.

`TYPES` is a tuple of type names; in your subclass, simply define a new tuple `TYPES` that builds on the standard one.

`TYPE_CHECKER` is a dictionary mapping type names to type-checking functions. A type-checking function has the following signature:

```
def check_mytype(option, opt, value)
```

where `option` is an `Option` instance, `opt` is an option string (e.g., `"-f"`), and `value` is the string from the command line that must be checked and converted to your desired type. `check_mytype()` should return an object of the hypothetical type `mytype`. The value returned by a type-checking function will wind up in the `OptionValues` instance returned by `OptionParser.parse_args()`, or be passed to a callback as the `value` parameter.

Your type-checking function should raise `OptionValueError` if it encounters any problems. `OptionValueError` takes a single string argument, which is passed as-is to `OptionParser's error()` method, which in turn prepends the program name and the string `"error: "` and prints everything to `stderr` before terminating the process.

Here's a silly example that demonstrates adding a complex option type to parse Python-style complex numbers on the command line. (This is even sillier than it used to be, because `optparse` 1.3 added built-in support for complex numbers, but never mind.)

First, the necessary imports:

```
from copy import copy
from optparse import Option, OptionValueError
```

You need to define your type-checker first, since it's referred to later (in the `TYPE_CHECKER` class attribute of your `Option` subclass):

```
def check_complex(option, opt, value):
    try:
        return complex(value)
    except ValueError:
        raise OptionValueError(
            "option %s: invalid complex value: %r" % (opt, value))
```

Finally, the `Option` subclass:

```
class MyOption (Option):
    TYPES = Option.TYPES + ("complex",)
    TYPE_CHECKER = copy (Option.TYPE_CHECKER)
    TYPE_CHECKER["complex"] = check_complex
```

(If we didn't make a `copy()` of `Option.TYPE_CHECKER`, we would end up modifying the `TYPE_CHECKER` attribute of `optparse`'s `Option` class. This being Python, nothing stops you from doing that except good manners and common sense.)

That's it! Now you can write a script that uses the new option type just like any other `optparse`-based script, except you have to instruct your `OptionParser` to use `MyOption` instead of `Option`:

```
parser = OptionParser(option_class=MyOption)
parser.add_option("-c", type="complex")
```

Alternately, you can build your own option list and pass it to `OptionParser`; if you don't use `add_option()` in the above way, you don't need to tell `OptionParser` which option class to use:

```
option_list = [MyOption("-c", action="store", type="complex", dest="c")]
parser = OptionParser(option_list=option_list)
```

Adding new actions

Adding new actions is a bit trickier, because you have to understand that `optparse` has a couple of classifications for actions:

“store” actions actions that result in `optparse` storing a value to an attribute of the current `OptionValues` instance; these options require a `dest` attribute to be supplied to the `Option` constructor

“typed” actions actions that take a value from the command line and expect it to be of a certain type; or rather, a string that can be converted to a certain type. These options require a `type` attribute to the `Option` constructor.

These are overlapping sets: some default “store” actions are `store`, `store_const`, `append`, and `count`, while the default “typed” actions are `store`, `append`, and `callback`.

When you add an action, you need to categorize it by listing it in at least one of the following class attributes of `Option` (all are lists of strings):

ACTIONS all actions must be listed in `ACTIONS`

STORE_ACTIONS “store” actions are additionally listed here

TYPED_ACTIONS “typed” actions are additionally listed here

ALWAYS_TYPED_ACTIONS actions that always take a type (i.e. whose options always take a value) are additionally listed here. The only effect of this is that `optparse` assigns the default type, `string`, to options with no explicit type whose action is listed in `ALWAYS_TYPED_ACTIONS`.

In order to actually implement your new action, you must override `Option`'s `take_action()` method and add a case that recognizes your action.

For example, let's add an `extend` action. This is similar to the standard `append` action, but instead of taking a single value from the command-line and appending it to an existing list, `extend` will take multiple values in a single comma-delimited string, and extend an existing list with them. That is, if `--names` is an `extend` option of type `string`, the command line

```
--names=foo,bar --names blah --names ding,dong
```

would result in a list

```
["foo", "bar", "blah", "ding", "dong"]
```

Again we define a subclass of `Option`:

```
class MyOption (Option):

    ACTIONS = Option.ACTIONS + ("extend",)
    STORE_ACTIONS = Option.STORE_ACTIONS + ("extend",)
    TYPED_ACTIONS = Option.TYPED_ACTIONS + ("extend",)
    ALWAYS_TYPED_ACTIONS = Option.ALWAYS_TYPED_ACTIONS + ("extend",)

    def take_action(self, action, dest, opt, value, values, parser):
        if action == "extend":
            lvalue = value.split(",")
            values.ensure_value(dest, []).extend(lvalue)
        else:
            Option.take_action(
                self, action, dest, opt, value, values, parser)
```

Features of note:

- `extend` both expects a value on the command-line and stores that value somewhere, so it goes in both `STORE_ACTIONS` and `TYPED_ACTIONS`
- to ensure that `optparse` assigns the default type of `string` to `extend` actions, we put the `extend` action in `ALWAYS_TYPED_ACTIONS` as well
- `MyOption.take_action()` implements just this one new action, and passes control back to `Option.take_action()` for the standard `optparse` actions
- `values` is an instance of the `optparse.parser.Values` class, which provides the very useful `ensure_value()` method. `ensure_value()` is essentially `getattr()` with a safety valve; it is called as

```
values.ensure_value(attr, value)
```

If the `attr` attribute of `values` doesn't exist or is `None`, then `ensure_value()` first sets it to `value`, and then returns `value`. This is very handy for actions like `extend`, `append`, and `count`, all of which accumulate data in a variable and expect that variable to be of a certain type (a list for the first two, an integer for the latter). Using `ensure_value()` means that scripts using your action don't have to worry about setting a default value for the option destinations in question; they can just leave the default as `None` and `ensure_value()` will take care of getting it right when it's needed.

14.4 getopt — Parser for command line options

This module helps scripts to parse the command line arguments in `sys.argv`. It supports the same conventions as the UNIX `getopt()` function (including the special meanings of arguments of the form `'-'` and `'--'`). Long options similar to those supported by GNU software may be used as well via an optional third argument. This module provides a single function and an exception:

getopt (*args*, *options* [, *long_options*])

Parses command line options and parameter list. *args* is the argument list to be parsed, without the leading reference to the running program. Typically, this means `'sys.argv[1:]'`. *options* is the string of option letters that the script wants to recognize, with options that require an argument followed by a colon (':'; i.e., the same format that UNIX `getopt()` uses).

Note: Unlike GNU `getopt()`, after a non-option argument, all further arguments are considered also non-options. This is similar to the way non-GNU UNIX systems work.

long_options, if specified, must be a list of strings with the names of the long options which should be supported. The leading `'--'` characters should not be included in the option name. Long options which require an argument should be followed by an equal sign ('='). To accept only long options, *options* should be an empty string. Long options on the command line can be recognized so long as they provide a prefix of the option name that matches exactly one of the accepted options. For example, if *long_options* is [`'foo'`, `'frob'`], the option `--fo` will match as `--foo`, but `--f` will not match uniquely, so `GetoptError` will be raised.

The return value consists of two elements: the first is a list of (*option*, *value*) pairs; the second is the list of program arguments left after the option list was stripped (this is a trailing slice of *args*). Each option-and-value pair returned has the option as its first element, prefixed with a hyphen for short options (e.g., `'-x'`) or two hyphens for long options (e.g., `'--long-option'`), and the option argument as its second element, or an empty string if the option has no argument. The options occur in the list in the same order in which they were found, thus allowing multiple occurrences. Long and short options may be mixed.

gnu_getopt (*args*, *options* [, *long_options*])

This function works like `getopt()`, except that GNU style scanning mode is used by default. This means that option and non-option arguments may be intermixed. The `getopt()` function stops processing options as soon as a non-option argument is encountered.

If the first character of the option string is `'+'`, or if the environment variable `POSIXLY_CORRECT` is set, then option processing stops as soon as a non-option argument is encountered.

New in version 2.3.

exception GetoptError

This is raised when an unrecognized option is found in the argument list or when an option requiring an argument is given none. The argument to the exception is a string indicating the cause of the error. For long options, an argument given to an option which does not require one will also cause this exception to be raised. The attributes `msg` and `opt` give the error message and related option; if there is no specific option to which the exception relates, `opt` is an empty string.

Changed in version 1.6: Introduced `GetoptError` as a synonym for `error`.

exception error

Alias for `GetoptError`; for backward compatibility.

An example using only UNIX style options:

```

>>> import getopt
>>> args = '-a -b -cfoo -d bar a1 a2'.split()
>>> args
['-a', '-b', '-cfoo', '-d', 'bar', 'a1', 'a2']
>>> optlist, args = getopt.getopt(args, 'abc:d:')
>>> optlist
[('-a', ''), ('-b', ''), ('-c', 'foo'), ('-d', 'bar')]
>>> args
['a1', 'a2']

```

Using long option names is equally easy:

```

>>> s = '--condition=foo --testing --output-file abc.def -x a1 a2'
>>> args = s.split()
>>> args
['--condition=foo', '--testing', '--output-file', 'abc.def', '-x', 'a1', 'a2']
>>> optlist, args = getopt.getopt(args, 'x', [
...     'condition=', 'output-file=', 'testing'])
>>> optlist
[('--condition', 'foo'), ('--testing', ''), ('--output-file', 'abc.def'), ('-x',
'')]
>>> args
['a1', 'a2']

```

In a script, typical usage is something like this:

```

import getopt, sys

def main():
    try:
        opts, args = getopt.getopt(sys.argv[1:], "ho:v", ["help", "output="])
    except getopt.GetoptError, err:
        # print help information and exit:
        print str(err) # will print something like "option -a not recognized"
        usage()
        sys.exit(2)
    output = None
    verbose = False
    for o, a in opts:
        if o == "-v":
            verbose = True
        elif o in ("-h", "--help"):
            usage()
            sys.exit()
        elif o in ("-o", "--output"):
            output = a
        else:
            assert False, "unhandled option"
    # ...

if __name__ == "__main__":
    main()

```

See Also:

[Module `optparse`](#) (section 14.3):

More object-oriented command line option parsing.

14.5 `logging` — Logging facility for Python

New in version 2.3. This module defines functions and classes which implement a flexible error logging system for applications.

Logging is performed by calling methods on instances of the `Logger` class (hereafter called *loggers*). Each instance has a name, and they are conceptually arranged in a name space hierarchy using dots (periods) as separators. For example, a logger named "scan" is the parent of loggers "scan.text", "scan.html" and "scan.pdf". Logger names can be anything you want, and indicate the area of an application in which a logged message originates.

Logged messages also have levels of importance associated with them. The default levels provided are `DEBUG`, `INFO`, `WARNING`, `ERROR` and `CRITICAL`. As a convenience, you indicate the importance of a logged message by calling an appropriate method of `Logger`. The methods are `debug()`, `info()`, `warning()`, `error()` and `critical()`, which mirror the default levels. You are not constrained to use these levels: you can specify your own and use a more general `Logger` method, `log()`, which takes an explicit level argument.

The numeric values of logging levels are given in the following table. These are primarily of interest if you want to define your own levels, and need them to have specific values relative to the predefined levels. If you define a level with the same numeric value, it overwrites the predefined value; the predefined name is lost.

Level	Numeric value
CRITICAL	50
ERROR	40
WARNING	30
INFO	20
DEBUG	10
NOTSET	0

Levels can also be associated with loggers, being set either by the developer or through loading a saved logging configuration. When a logging method is called on a logger, the logger compares its own level with the level associated with the method call. If the logger's level is higher than the method call's, no logging message is actually generated. This is the basic mechanism controlling the verbosity of logging output.

Logging messages are encoded as instances of the `LogRecord` class. When a logger decides to actually log an event, a `LogRecord` instance is created from the logging message.

Logging messages are subjected to a dispatch mechanism through the use of *handlers*, which are instances of subclasses of the `Handler` class. Handlers are responsible for ensuring that a logged message (in the form of a `LogRecord`) ends up in a particular location (or set of locations) which is useful for the target audience for that message (such as end users, support desk staff, system administrators, developers). Handlers are passed `LogRecord` instances intended for particular destinations. Each logger can have zero, one or more handlers associated with it (via the `addHandler()` method of `Logger`). In addition to any handlers directly associated with a logger, *all handlers associated with all ancestors of the logger* are called to dispatch the message.

Just as for loggers, handlers can have levels associated with them. A handler's level acts as a filter in the same way as a logger's level does. If a handler decides to actually dispatch an event, the `emit()` method is used to send the message to its destination. Most user-defined subclasses of `Handler` will need to override this `emit()`.

In addition to the base `Handler` class, many useful subclasses are provided:

1. `StreamHandler` instances send error messages to streams (file-like objects).

2. `FileHandler` instances send error messages to disk files.
3. `BaseRotatingHandler` is the base class for handlers that rotate log files at a certain point. It is not meant to be instantiated directly. Instead, use `RotatingFileHandler` or `TimedRotatingFileHandler`.
4. `RotatingFileHandler` instances send error messages to disk files, with support for maximum log file sizes and log file rotation.
5. `TimedRotatingFileHandler` instances send error messages to disk files rotating the log file at certain timed intervals.
6. `SocketHandler` instances send error messages to TCP/IP sockets.
7. `DatagramHandler` instances send error messages to UDP sockets.
8. `SMTPHandler` instances send error messages to a designated email address.
9. `SysLogHandler` instances send error messages to a UNIX syslog daemon, possibly on a remote machine.
10. `NTEventLogHandler` instances send error messages to a Windows NT/2000/XP event log.
11. `MemoryHandler` instances send error messages to a buffer in memory, which is flushed whenever specific criteria are met.
12. `HTTPHandler` instances send error messages to an HTTP server using either 'GET' or 'POST' semantics.

The `StreamHandler` and `FileHandler` classes are defined in the core logging package. The other handlers are defined in a sub- module, `logging.handlers`. (There is also another sub-module, `logging.config`, for configuration functionality.)

Logged messages are formatted for presentation through instances of the `Formatter` class. They are initialized with a format string suitable for use with the `%` operator and a dictionary.

For formatting multiple messages in a batch, instances of `BufferingFormatter` can be used. In addition to the format string (which is applied to each message in the batch), there is provision for header and trailer format strings.

When filtering based on logger level and/or handler level is not enough, instances of `Filter` can be added to both `Logger` and `Handler` instances (through their `addFilter()` method). Before deciding to process a message further, both loggers and handlers consult all their filters for permission. If any filter returns a false value, the message is not processed further.

The basic `Filter` functionality allows filtering by specific logger name. If this feature is used, messages sent to the named logger and its children are allowed through the filter, and all others dropped.

In addition to the classes described above, there are a number of module- level functions.

`getLogger([name])`

Return a logger with the specified name or, if no name is specified, return a logger which is the root logger of the hierarchy. If specified, the name is typically a dot-separated hierarchical name like `"a"`, `"a.b"` or `"a.b.c.d"`. Choice of these names is entirely up to the developer who is using logging.

All calls to this function with a given name return the same logger instance. This means that logger instances never need to be passed between different parts of an application.

`getLoggerClass()`

Return either the standard `Logger` class, or the last class passed to `setLoggerClass()`. This function may be called from within a new class definition, to ensure that installing a customised `Logger` class will not undo customisations already applied by other code. For example:

```
class MyLogger(logging.getLoggerClass()):
    # ... override behaviour here
```

debug (*msg* [, **args* [, ***kwargs*]])

Logs a message with level `DEBUG` on the root logger. The *msg* is the message format string, and the *args* are the arguments which are merged into *msg* using the string formatting operator. (Note that this means that you can use keywords in the format string, together with a single dictionary argument.)

There are two keyword arguments in *kwargs* which are inspected: *exc_info* which, if it does not evaluate as false, causes exception information to be added to the logging message. If an exception tuple (in the format returned by `sys.exc_info()`) is provided, it is used; otherwise, `sys.exc_info()` is called to get the exception information.

The other optional keyword argument is *extra* which can be used to pass a dictionary which is used to populate the `__dict__` of the `LogRecord` created for the logging event with user-defined attributes. These custom attributes can then be used as you like. For example, they could be incorporated into logged messages. For example:

```
FORMAT = "%(asctime)-15s %(clientip)s %(user)-8s %(message)s"
logging.basicConfig(format=FORMAT)
d = {'clientip': '192.168.0.1', 'user': 'fbloggs'}
logging.warning("Protocol problem: %s", "connection reset", extra=d)
```

would print something like

```
2006-02-08 22:20:02,165 192.168.0.1 fbloggs Protocol problem: connection reset
```

The keys in the dictionary passed in *extra* should not clash with the keys used by the logging system. (See the `Formatter` documentation for more information on which keys are used by the logging system.)

If you choose to use these attributes in logged messages, you need to exercise some care. In the above example, for instance, the `Formatter` has been set up with a format string which expects 'clientip' and 'user' in the attribute dictionary of the `LogRecord`. If these are missing, the message will not be logged because a string formatting exception will occur. So in this case, you always need to pass the *extra* dictionary with these keys.

While this might be annoying, this feature is intended for use in specialized circumstances, such as multi-threaded servers where the same code executes in many contexts, and interesting conditions which arise are dependent on this context (such as remote client IP address and authenticated user name, in the above example). In such circumstances, it is likely that specialized `Formatters` would be used with particular `Handlers`.

Changed in version 2.5: *extra* was added.

info (*msg* [, **args* [, ***kwargs*]])

Logs a message with level `INFO` on the root logger. The arguments are interpreted as for `debug()`.

warning (*msg* [, **args* [, ***kwargs*]])

Logs a message with level `WARNING` on the root logger. The arguments are interpreted as for `debug()`.

error (*msg* [, **args* [, ***kwargs*]])

Logs a message with level `ERROR` on the root logger. The arguments are interpreted as for `debug()`.

critical (*msg* [, **args* [, ***kwargs*]])

Logs a message with level `CRITICAL` on the root logger. The arguments are interpreted as for `debug()`.

exception (*msg* [, **args*])

Logs a message with level `ERROR` on the root logger. The arguments are interpreted as for `debug()`. Exception info is added to the logging message. This function should only be called from an exception handler.

log (*level*, *msg* [, **args* [, ***kwargs*]])

Logs a message with level *level* on the root logger. The other arguments are interpreted as for `debug()`.

disable (*lvl*)

Provides an overriding level *lvl* for all loggers which takes precedence over the logger's own level. When the need arises to temporarily throttle logging output down across the whole application, this function can be useful.

addLevelName (*lvl*, *levelName*)

Associates level *lvl* with text *levelName* in an internal dictionary, which is used to map numeric levels to a textual representation, for example when a `Formatter` formats a message. This function can also be used to define your own levels. The only constraints are that all levels used must be registered using this function, levels should be positive integers and they should increase in increasing order of severity.

getLevelName (*lvl*)

Returns the textual representation of logging level *lvl*. If the level is one of the predefined levels `CRITICAL`, `ERROR`, `WARNING`, `INFO` or `DEBUG` then you get the corresponding string. If you have associated levels with names using `addLevelName()` then the name you have associated with *lvl* is returned. If a numeric value corresponding to one of the defined levels is passed in, the corresponding string representation is returned. Otherwise, the string "Level %s" % *lvl* is returned.

makeLogRecord (*attrdict*)

Creates and returns a new `LogRecord` instance whose attributes are defined by *attrdict*. This function is useful for taking a pickled `LogRecord` attribute dictionary, sent over a socket, and reconstituting it as a `LogRecord` instance at the receiving end.

basicConfig ([***kwargs*])

Does basic configuration for the logging system by creating a `StreamHandler` with a default `Formatter` and adding it to the root logger. The functions `debug()`, `info()`, `warning()`, `error()` and `critical()` will call `basicConfig()` automatically if no handlers are defined for the root logger.

Changed in version 2.4: Formerly, `basicConfig` did not take any keyword arguments.

The following keyword arguments are supported.

Format	Description
<code>filename</code>	Specifies that a <code>FileHandler</code> be created, using the specified filename, rather than a <code>StreamHandler</code> .
<code>filemode</code>	Specifies the mode to open the file, if filename is specified (if filemode is unspecified, it defaults to 'a').
<code>format</code>	Use the specified format string for the handler.
<code>datefmt</code>	Use the specified date/time format.
<code>level</code>	Set the root logger level to the specified level.
<code>stream</code>	Use the specified stream to initialize the <code>StreamHandler</code> . Note that this argument is incompatible with 'filename'.

shutdown ()

Informs the logging system to perform an orderly shutdown by flushing and closing all handlers.

setLoggerClass (*klass*)

Tells the logging system to use the class *klass* when instantiating a logger. The class should define `__init__()` such that only a name argument is required, and the `__init__()` should call `Logger.__init__()`. This function is typically called before any loggers are instantiated by applications which need to use custom logger behavior.

See Also:

PEP 282, "A Logging System"

The proposal which described this feature for inclusion in the Python standard library.

[Original Python logging package](#)

This is the original source for the `logging` package. The version of the package available from this site is suitable for use with Python 1.5.2, 2.1.x and 2.2.x, which do not include the `logging` package in the standard library.

14.5.1 Logger Objects

Loggers have the following attributes and methods. Note that Loggers are never instantiated directly, but always through the module-level function `logging.getLogger(name)`.

propagate

If this evaluates to false, logging messages are not passed by this logger or by child loggers to higher level (ancestor) loggers. The constructor sets this attribute to 1.

setLevel (lvl)

Sets the threshold for this logger to *lvl*. Logging messages which are less severe than *lvl* will be ignored. When a logger is created, the level is set to NOTSET (which causes all messages to be processed when the logger is the root logger, or delegation to the parent when the logger is a non-root logger). Note that the root logger is created with level WARNING.

The term "delegation to the parent" means that if a logger has a level of NOTSET, its chain of ancestor loggers is traversed until either an ancestor with a level other than NOTSET is found, or the root is reached.

If an ancestor is found with a level other than NOTSET, then that ancestor's level is treated as the effective level of the logger where the ancestor search began, and is used to determine how a logging event is handled.

If the root is reached, and it has a level of NOTSET, then all messages will be processed. Otherwise, the root's level will be used as the effective level.

isEnabledFor (lvl)

Indicates if a message of severity *lvl* would be processed by this logger. This method checks first the module-level level set by `logging.disable(lvl)` and then the logger's effective level as determined by `getEffectiveLevel()`.

getEffectiveLevel ()

Indicates the effective level for this logger. If a value other than NOTSET has been set using `setLevel()`, it is returned. Otherwise, the hierarchy is traversed towards the root until a value other than NOTSET is found, and that value is returned.

debug (msg[, *args[, **kwargs]])

Logs a message with level DEBUG on this logger. The *msg* is the message format string, and the *args* are the arguments which are merged into *msg* using the string formatting operator. (Note that this means that you can use keywords in the format string, together with a single dictionary argument.)

There are two keyword arguments in *kwargs* which are inspected: *exc_info* which, if it does not evaluate as false, causes exception information to be added to the logging message. If an exception tuple (in the format returned by `sys.exc_info()`) is provided, it is used; otherwise, `sys.exc_info()` is called to get the exception information.

The other optional keyword argument is *extra* which can be used to pass a dictionary which is used to populate the `__dict__` of the LogRecord created for the logging event with user-defined attributes. These custom attributes can then be used as you like. For example, they could be incorporated into logged messages. For example:

```
FORMAT = "%(asctime)-15s %(clientip)s %(user)-8s %(message)s"
logging.basicConfig(format=FORMAT)
d = { 'clientip' : '192.168.0.1', 'user' : 'fbloggs' }
logger = logging.getLogger("tcpserver")
logger.warning("Protocol problem: %s", "connection reset", extra=d)
```

would print something like

```
2006-02-08 22:20:02,165 192.168.0.1 fbloggs Protocol problem: connection reset
```

The keys in the dictionary passed in *extra* should not clash with the keys used by the logging system. (See the `Formatter` documentation for more information on which keys are used by the logging system.)

If you choose to use these attributes in logged messages, you need to exercise some care. In the above example, for instance, the `Formatter` has been set up with a format string which expects 'clientip' and 'user' in the attribute dictionary of the LogRecord. If these are missing, the message will not be logged because a string formatting exception will occur. So in this case, you always need to pass the *extra* dictionary with these keys.

While this might be annoying, this feature is intended for use in specialized circumstances, such as multi-threaded servers where the same code executes in many contexts, and interesting conditions which arise are dependent on this context (such as remote client IP address and authenticated user name, in the above example). In such circumstances, it is likely that specialized `Formatters` would be used with particular `Handlers`.

Changed in version 2.5: *extra* was added.

info (*msg* [, **args* [, ***kwargs*]])

Logs a message with level `INFO` on this logger. The arguments are interpreted as for `debug()`.

warning (*msg* [, **args* [, ***kwargs*]])

Logs a message with level `WARNING` on this logger. The arguments are interpreted as for `debug()`.

error (*msg* [, **args* [, ***kwargs*]])

Logs a message with level `ERROR` on this logger. The arguments are interpreted as for `debug()`.

critical (*msg* [, **args* [, ***kwargs*]])

Logs a message with level `CRITICAL` on this logger. The arguments are interpreted as for `debug()`.

log (*lvl*, *msg* [, **args* [, ***kwargs*]])

Logs a message with integer level *lvl* on this logger. The other arguments are interpreted as for `debug()`.

exception (*msg* [, **args*])

Logs a message with level `ERROR` on this logger. The arguments are interpreted as for `debug()`. Exception info is added to the logging message. This method should only be called from an exception handler.

addFilter (*filt*)

Adds the specified filter *filt* to this logger.

removeFilter (*filt*)

Removes the specified filter *filt* from this logger.

filter (*record*)

Applies this logger's filters to the record and returns a true value if the record is to be processed.

addHandler (*hdlr*)

Adds the specified handler *hdlr* to this logger.

removeHandler (*hdlr*)

Removes the specified handler *hdlr* from this logger.

findCaller ()

Finds the caller's source filename and line number. Returns the filename, line number and function name as a 3-element tuple. Changed in version 2.4: The function name was added. In earlier versions, the filename and line number were returned as a 2-element tuple..

handle (*record*)

Handles a record by passing it to all handlers associated with this logger and its ancestors (until a false value of *propagate* is found). This method is used for unpickled records received from a socket, as well as those created locally. Logger-level filtering is applied using `filter()`.

makeRecord (*name*, *lvl*, *fn*, *lno*, *msg*, *args*, *exc_info* [, *func*, *extra*])

This is a factory method which can be overridden in subclasses to create specialized `LogRecord` instances. Changed in version 2.5: *func* and *extra* were added.

14.5.2 Basic example

Changed in version 2.4: formerly `basicConfig` did not take any keyword arguments.

The `logging` package provides a lot of flexibility, and its configuration can appear daunting. This section demonstrates that simple use of the logging package is possible.

The simplest example shows logging to the console:

```
import logging

logging.debug('A debug message')
logging.info('Some information')
logging.warning('A shot across the bows')
```

If you run the above script, you'll see this:

```
WARNING:root:A shot across the bows
```

Because no particular logger was specified, the system used the root logger. The debug and info messages didn't appear because by default, the root logger is configured to only handle messages with a severity of WARNING or above. The message format is also a configuration default, as is the output destination of the messages - `sys.stderr`. The severity level, the message format and destination can be easily changed, as shown in the example below:

```
import logging

logging.basicConfig(level=logging.DEBUG,
                    format='%(asctime)s %(levelname)s %(message)s',
                    filename='/tmp/myapp.log',
                    filemode='w')
logging.debug('A debug message')
logging.info('Some information')
logging.warning('A shot across the bows')
```

The `basicConfig()` method is used to change the configuration defaults, which results in output (written to `/tmp/myapp.log`) which should look something like the following:

```
2004-07-02 13:00:08,743 DEBUG A debug message
2004-07-02 13:00:08,743 INFO Some information
2004-07-02 13:00:08,743 WARNING A shot across the bows
```

This time, all messages with a severity of DEBUG or above were handled, and the format of the messages was also changed, and output went to the specified file rather than the console.

Formatting uses standard Python string formatting - see section 3.6.2. The format string takes the following common specifiers. For a complete list of specifiers, consult the `Formatter` documentation.

Format	Description
<code>%(name)s</code>	Name of the logger (logging channel).
<code>%(levelname)s</code>	Text logging level for the message ('DEBUG', 'INFO', 'WARNING', 'ERROR', 'CRITICAL').
<code>%(asctime)s</code>	Human-readable time when the <code>LogRecord</code> was created. By default this is of the form "2003-07-08 16:49:45,".
<code>%(message)s</code>	The logged message.

To change the date/time format, you can pass an additional keyword parameter, *datefmt*, as in the following:

```
import logging

logging.basicConfig(level=logging.DEBUG,
                    format='%(asctime)s %(levelname)-8s %(message)s',
                    datefmt='%a, %d %b %Y %H:%M:%S',
                    filename='/temp/myapp.log',
                    filemode='w')
logging.debug('A debug message')
logging.info('Some information')
logging.warning('A shot across the bows')
```

which would result in output like

```
Fri, 02 Jul 2004 13:06:18 DEBUG      A debug message
Fri, 02 Jul 2004 13:06:18 INFO      Some information
Fri, 02 Jul 2004 13:06:18 WARNING   A shot across the bows
```

The date format string follows the requirements of `strftime()` - see the documentation for the [time](#) module.

If, instead of sending logging output to the console or a file, you'd rather use a file-like object which you have created separately, you can pass it to `basicConfig()` using the *stream* keyword argument. Note that if both *stream* and *filename* keyword arguments are passed, the *stream* argument is ignored.

Of course, you can put variable information in your output. To do this, simply have the message be a format string and pass in additional arguments containing the variable information, as in the following example:

```
import logging

logging.basicConfig(level=logging.DEBUG,
                    format='%(asctime)s %(levelname)-8s %(message)s',
                    datefmt='%a, %d %b %Y %H:%M:%S',
                    filename='/temp/myapp.log',
                    filemode='w')
logging.error('Pack my box with %d dozen %s', 5, 'liquor jugs')
```

which would result in

```
Wed, 21 Jul 2004 15:35:16 ERROR      Pack my box with 5 dozen liquor jugs
```

14.5.3 Logging to multiple destinations

Let's say you want to log to console and file with different message formats and in differing circumstances. Say you want to log messages with levels of `DEBUG` and higher to file, and those messages at level `INFO` and higher to the console. Let's also assume that the file should contain timestamps, but the console messages should not. Here's how you can achieve this:

```

import logging

# set up logging to file - see previous section for more details
logging.basicConfig(level=logging.DEBUG,
                    format='%(asctime)s %(name)-12s %(levelname)-8s %(message)s',
                    datefmt='%m-%d %H:%M',
                    filename='/temp/myapp.log',
                    filemode='w')

# define a Handler which writes INFO messages or higher to the sys.stderr
console = logging.StreamHandler()
console.setLevel(logging.INFO)
# set a format which is simpler for console use
formatter = logging.Formatter('%(name)-12s: %(levelname)-8s %(message)s')
# tell the handler to use this format
console.setFormatter(formatter)
# add the handler to the root logger
logging.getLogger('').addHandler(console)

# Now, we can log to the root logger, or any other logger. First the root...
logging.info('Jackdaws love my big sphinx of quartz.')

# Now, define a couple of other loggers which might represent areas in your
# application:

logger1 = logging.getLogger('myapp.area1')
logger2 = logging.getLogger('myapp.area2')

logger1.debug('Quick zephyrs blow, vexing daft Jim.')
logger1.info('How quickly daft jumping zebras vex.')
logger2.warning('Jail zesty vixen who grabbed pay from quack.')
logger2.error('The five boxing wizards jump quickly.')

```

When you run this, on the console you will see

```

root          : INFO      Jackdaws love my big sphinx of quartz.
myapp.area1   : INFO      How quickly daft jumping zebras vex.
myapp.area2   : WARNING   Jail zesty vixen who grabbed pay from quack.
myapp.area2   : ERROR     The five boxing wizards jump quickly.

```

and in the file you will see something like

```

10-22 22:19 root          INFO      Jackdaws love my big sphinx of quartz.
10-22 22:19 myapp.area1   DEBUG     Quick zephyrs blow, vexing daft Jim.
10-22 22:19 myapp.area1   INFO      How quickly daft jumping zebras vex.
10-22 22:19 myapp.area2   WARNING   Jail zesty vixen who grabbed pay from quack.
10-22 22:19 myapp.area2   ERROR     The five boxing wizards jump quickly.

```

As you can see, the DEBUG message only shows up in the file. The other messages are sent to both destinations. This example uses console and file handlers, but you can use any number and combination of handlers you choose.

14.5.4 Sending and receiving logging events across a network

Let's say you want to send logging events across a network, and handle them at the receiving end. A simple way of doing this is attaching a `SocketHandler` instance to the root logger at the sending end:

```
import logging, logging.handlers

rootLogger = logging.getLogger('')
rootLogger.setLevel(logging.DEBUG)
socketHandler = logging.handlers.SocketHandler('localhost',
        logging.handlers.DEFAULT_TCP_LOGGING_PORT)
# don't bother with a formatter, since a socket handler sends the event as
# an unformatted pickle
rootLogger.addHandler(socketHandler)

# Now, we can log to the root logger, or any other logger. First the root...
logging.info('Jackdaws love my big sphinx of quartz.')

# Now, define a couple of other loggers which might represent areas in your
# application:

logger1 = logging.getLogger('myapp.area1')
logger2 = logging.getLogger('myapp.area2')

logger1.debug('Quick zephyrs blow, vexing daft Jim.')
logger1.info('How quickly daft jumping zebras vex.')
logger2.warning('Jail zesty vixen who grabbed pay from quack.')
logger2.error('The five boxing wizards jump quickly.')
```

At the receiving end, you can set up a receiver using the `SocketServer` module. Here is a basic working example:

```

import cPickle
import logging
import logging.handlers
import SocketServer
import struct

class LogRecordStreamHandler(SocketServer.StreamRequestHandler):
    """Handler for a streaming logging request.

    This basically logs the record using whatever logging policy is
    configured locally.
    """

    def handle(self):
        """
        Handle multiple requests - each expected to be a 4-byte length,
        followed by the LogRecord in pickle format. Logs the record
        according to whatever policy is configured locally.
        """
        while 1:
            chunk = self.connection.recv(4)
            if len(chunk) < 4:
                break
            slen = struct.unpack(">L", chunk)[0]
            chunk = self.connection.recv(slen)
            while len(chunk) < slen:
                chunk = chunk + self.connection.recv(slen - len(chunk))
            obj = self.unPickle(chunk)
            record = logging.makeLogRecord(obj)
            self.handleLogRecord(record)

    def unPickle(self, data):
        return cPickle.loads(data)

    def handleLogRecord(self, record):
        # if a name is specified, we use the named logger rather than the one
        # implied by the record.
        if self.server.logname is not None:
            name = self.server.logname
        else:
            name = record.name
        logger = logging.getLogger(name)
        # N.B. EVERY record gets logged. This is because Logger.handle
        # is normally called AFTER logger-level filtering. If you want
        # to do filtering, do it at the client end to save wasting
        # cycles and network bandwidth!
        logger.handle(record)

class LogRecordSocketReceiver(SocketServer.ThreadingTCPServer):
    """simple TCP socket-based logging receiver suitable for testing.
    """

    allow_reuse_address = 1

    def __init__(self, host='localhost',
                  port=logging.handlers.DEFAULT_TCP_LOGGING_PORT,
                  handler=LogRecordStreamHandler):
        SocketServer.ThreadingTCPServer.__init__(self, (host, port), handler)
        self.abort = 0
        self.timeout = 1
        self.logname = None

    def serve_until_stopped(self):
        import select

```


First run the server, and then the client. On the client side, nothing is printed on the console; on the server side, you should see something like:

```
About to start TCP server...
59 root INFO Jackdaws love my big sphinx of quartz.
59 myapp.area1 DEBUG Quick zephyrs blow, vexing daft Jim.
69 myapp.area1 INFO How quickly daft jumping zebras vex.
69 myapp.area2 WARNING Jail zesty vixen who grabbed pay from quack.
69 myapp.area2 ERROR The five boxing wizards jump quickly.
```

14.5.5 Handler Objects

Handlers have the following attributes and methods. Note that `Handler` is never instantiated directly; this class acts as a base for more useful subclasses. However, the `__init__()` method in subclasses needs to call `Handler.__init__()`.

`__init__(level=NOTSET)`

Initializes the `Handler` instance by setting its level, setting the list of filters to the empty list and creating a lock (using `createLock()`) for serializing access to an I/O mechanism.

`createLock()`

Initializes a thread lock which can be used to serialize access to underlying I/O functionality which may not be threadsafe.

`acquire()`

Acquires the thread lock created with `createLock()`.

`release()`

Releases the thread lock acquired with `acquire()`.

`setLevel(lvl)`

Sets the threshold for this handler to *lvl*. Logging messages which are less severe than *lvl* will be ignored. When a handler is created, the level is set to `NOTSET` (which causes all messages to be processed).

`setFormatter(form)`

Sets the `Formatter` for this handler to *form*.

`addFilter(filt)`

Adds the specified filter *filt* to this handler.

`removeFilter(filt)`

Removes the specified filter *filt* from this handler.

`filter(record)`

Applies this handler's filters to the record and returns a true value if the record is to be processed.

`flush()`

Ensure all logging output has been flushed. This version does nothing and is intended to be implemented by subclasses.

`close()`

Tidy up any resources used by the handler. This version does nothing and is intended to be implemented by subclasses.

`handle(record)`

Conditionally emits the specified logging record, depending on filters which may have been added to the handler. Wraps the actual emission of the record with acquisition/release of the I/O thread lock.

`handleError(record)`

This method should be called from handlers when an exception is encountered during an `emit()` call. By default it does nothing, which means that exceptions get silently ignored. This is what is mostly wanted for a logging system - most users will not care about errors in the logging system, they are more interested in application errors. You could, however, replace this with a custom handler if you wish. The specified record is the one which was being processed when the exception occurred.

format (*record*)

Do formatting for a record - if a formatter is set, use it. Otherwise, use the default formatter for the module.

emit (*record*)

Do whatever it takes to actually log the specified logging record. This version is intended to be implemented by subclasses and so raises a `NotImplementedError`.

StreamHandler

The `StreamHandler` class, located in the core logging package, sends logging output to streams such as `sys.stdout`, `sys.stderr` or any file-like object (or, more precisely, any object which supports `write()` and `flush()` methods).

class StreamHandler (*[strm]*)

Returns a new instance of the `StreamHandler` class. If *strm* is specified, the instance will use it for logging output; otherwise, `sys.stderr` will be used.

emit (*record*)

If a formatter is specified, it is used to format the record. The record is then written to the stream with a trailing newline. If exception information is present, it is formatted using `traceback.print_exception()` and appended to the stream.

flush ()

Flushes the stream by calling its `flush()` method. Note that the `close()` method is inherited from `Handler` and so does nothing, so an explicit `flush()` call may be needed at times.

FileHandler

The `FileHandler` class, located in the core logging package, sends logging output to a disk file. It inherits the output functionality from `StreamHandler`.

class FileHandler (*filename* [, *mode*])

Returns a new instance of the `FileHandler` class. The specified file is opened and used as the stream for logging. If *mode* is not specified, 'a' is used. By default, the file grows indefinitely.

close ()

Closes the file.

emit (*record*)

Outputs the record to the file.

RotatingFileHandler

The `RotatingFileHandler` class, located in the `logging.handlers` module, supports rotation of disk log files.

class RotatingFileHandler (*filename* [, *mode* [, *maxBytes* [, *backupCount*]]])

Returns a new instance of the `RotatingFileHandler` class. The specified file is opened and used as the stream for logging. If *mode* is not specified, 'a' is used. By default, the file grows indefinitely.

You can use the *maxBytes* and *backupCount* values to allow the file to *rollover* at a predetermined size. When

the size is about to be exceeded, the file is closed and a new file is silently opened for output. Rollover occurs whenever the current log file is nearly *maxBytes* in length; if *maxBytes* is zero, rollover never occurs. If *backupCount* is non-zero, the system will save old log files by appending the extensions ".1", ".2" etc., to the filename. For example, with a *backupCount* of 5 and a base file name of 'app.log', you would get 'app.log', 'app.log.1', 'app.log.2', up to 'app.log.5'. The file being written to is always 'app.log'. When this file is filled, it is closed and renamed to 'app.log.1', and if files 'app.log.1', 'app.log.2', etc. exist, then they are renamed to 'app.log.2', 'app.log.3' etc. respectively.

doRollover ()

Does a rollover, as described above.

emit (*record*)

Outputs the record to the file, catering for rollover as described previously.

TimedRotatingFileHandler

The `TimedRotatingFileHandler` class, located in the `logging.handlers` module, supports rotation of disk log files at certain timed intervals.

class TimedRotatingFileHandler (*filename* [,*when* [,*interval* [,*backupCount*]]])

Returns a new instance of the `TimedRotatingFileHandler` class. The specified file is opened and used as the stream for logging. On rotating it also sets the filename suffix. Rotating happens based on the product of *when* and *interval*.

You can use the *when* to specify the type of *interval*. The list of possible values is, note that they are not case sensitive:

Value	Type of interval
S	Seconds
M	Minutes
H	Hours
D	Days
W	Week day (0=Monday)
midnight	Roll over at midnight

If *backupCount* is non-zero, the system will save old log files by appending extensions to the filename. The extensions are date-and-time based, using the strftime format `%Y-%m-%d_%H-%M-%S` or a leading portion thereof, depending on the rollover interval. At most *backupCount* files will be kept, and if more would be created when rollover occurs, the oldest one is deleted.

doRollover ()

Does a rollover, as described above.

emit (*record*)

Outputs the record to the file, catering for rollover as described above.

SocketHandler

The `SocketHandler` class, located in the `logging.handlers` module, sends logging output to a network socket. The base class uses a TCP socket.

class SocketHandler (*host*, *port*)

Returns a new instance of the `SocketHandler` class intended to communicate with a remote machine whose address is given by *host* and *port*.

close ()

Closes the socket.

handleError ()

emit ()

Pickles the record's attribute dictionary and writes it to the socket in binary format. If there is an error with the socket, silently drops the packet. If the connection was previously lost, re-establishes the connection. To unpickle the record at the receiving end into a `LogRecord`, use the `makeLogRecord ()` function.

handleError ()

Handles an error which has occurred during `emit ()`. The most likely cause is a lost connection. Closes the socket so that we can retry on the next event.

makeSocket ()

This is a factory method which allows subclasses to define the precise type of socket they want. The default implementation creates a TCP socket (`socket . SOCK_STREAM`).

makePickle (record)

Pickles the record's attribute dictionary in binary format with a length prefix, and returns it ready for transmission across the socket.

send (packet)

Send a pickled string *packet* to the socket. This function allows for partial sends which can happen when the network is busy.

DatagramHandler

The `DatagramHandler` class, located in the `logging.handlers` module, inherits from `SocketHandler` to support sending logging messages over UDP sockets.

class DatagramHandler (host, port)

Returns a new instance of the `DatagramHandler` class intended to communicate with a remote machine whose address is given by *host* and *port*.

emit ()

Pickles the record's attribute dictionary and writes it to the socket in binary format. If there is an error with the socket, silently drops the packet. To unpickle the record at the receiving end into a `LogRecord`, use the `makeLogRecord ()` function.

makeSocket ()

The factory method of `SocketHandler` is here overridden to create a UDP socket (`socket . SOCK_DGRAM`).

send (s)

Send a pickled string to a socket.

SysLogHandler

The `SysLogHandler` class, located in the `logging.handlers` module, supports sending logging messages to a remote or local UNIX syslog.

class SysLogHandler ([address[, facility]])

Returns a new instance of the `SysLogHandler` class intended to communicate with a remote UNIX machine whose address is given by *address* in the form of a (*host*, *port*) tuple. If *address* is not specified, ('localhost', 514) is used. The address is used to open a UDP socket. An alternative to providing a (*host*, *port*) tuple is providing an address as a string, for example "/dev/log". In this case, a Unix domain socket is used to send the message to the syslog. If *facility* is not specified, `LOG_USER` is used.

close ()

Closes the socket to the remote host.

emit (record)

The record is formatted, and then sent to the syslog server. If exception information is present, it is *not* sent to

the server.

encodePriority (*facility, priority*)

Encodes the facility and priority into an integer. You can pass in strings or integers - if strings are passed, internal mapping dictionaries are used to convert them to integers.

NTEventLogHandler

The `NTEventLogHandler` class, located in the `logging.handlers` module, supports sending logging messages to a local Windows NT, Windows 2000 or Windows XP event log. Before you can use it, you need Mark Hammond's Win32 extensions for Python installed.

class NTEventLogHandler (*appname* [, *dllname* [, *logtype*]])

Returns a new instance of the `NTEventLogHandler` class. The *appname* is used to define the application name as it appears in the event log. An appropriate registry entry is created using this name. The *dllname* should give the fully qualified pathname of a .dll or .exe which contains message definitions to hold in the log (if not specified, 'win32service.pyd' is used - this is installed with the Win32 extensions and contains some basic placeholder message definitions. Note that use of these placeholders will make your event logs big, as the entire message source is held in the log. If you want slimmer logs, you have to pass in the name of your own .dll or .exe which contains the message definitions you want to use in the event log). The *logtype* is one of 'Application', 'System' or 'Security', and defaults to 'Application'.

close ()

At this point, you can remove the application name from the registry as a source of event log entries. However, if you do this, you will not be able to see the events as you intended in the Event Log Viewer - it needs to be able to access the registry to get the .dll name. The current version does not do this (in fact it doesn't do anything).

emit (*record*)

Determines the message ID, event category and event type, and then logs the message in the NT event log.

getEventCategory (*record*)

Returns the event category for the record. Override this if you want to specify your own categories. This version returns 0.

getEventType (*record*)

Returns the event type for the record. Override this if you want to specify your own types. This version does a mapping using the handler's `typemap` attribute, which is set up in `__init__()` to a dictionary which contains mappings for `DEBUG`, `INFO`, `WARNING`, `ERROR` and `CRITICAL`. If you are using your own levels, you will either need to override this method or place a suitable dictionary in the handler's `typemap` attribute.

getMessageID (*record*)

Returns the message ID for the record. If you are using your own messages, you could do this by having the *msg* passed to the logger being an ID rather than a format string. Then, in here, you could use a dictionary lookup to get the message ID. This version returns 1, which is the base message ID in 'win32service.pyd'.

SMTPHandler

The `SMTPHandler` class, located in the `logging.handlers` module, supports sending logging messages to an email address via SMTP.

class SMTPHandler (*mailhost, fromaddr, toaddrs, subject*)

Returns a new instance of the `SMTPHandler` class. The instance is initialized with the from and to addresses and subject line of the email. The *toaddrs* should be a list of strings. To specify a non-standard SMTP port, use the (host, port) tuple format for the *mailhost* argument. If you use a string, the standard SMTP port is used.

emit (*record*)

Formats the record and sends it to the specified addressees.

getSubject (*record*)

If you want to specify a subject line which is record-dependent, override this method.

MemoryHandler

The `MemoryHandler` class, located in the `logging.handlers` module, supports buffering of logging records in memory, periodically flushing them to a *target* handler. Flushing occurs whenever the buffer is full, or when an event of a certain severity or greater is seen.

`MemoryHandler` is a subclass of the more general `BufferingHandler`, which is an abstract class. This buffers logging records in memory. Whenever each record is added to the buffer, a check is made by calling `shouldFlush()` to see if the buffer should be flushed. If it should, then `flush()` is expected to do the needful.

class BufferingHandler (*capacity*)

Initializes the handler with a buffer of the specified capacity.

emit (*record*)

Appends the record to the buffer. If `shouldFlush()` returns true, calls `flush()` to process the buffer.

flush ()

You can override this to implement custom flushing behavior. This version just zaps the buffer to empty.

shouldFlush (*record*)

Returns true if the buffer is up to capacity. This method can be overridden to implement custom flushing strategies.

class MemoryHandler (*capacity* [, *flushLevel* [, *target*]])

Returns a new instance of the `MemoryHandler` class. The instance is initialized with a buffer size of *capacity*. If *flushLevel* is not specified, `ERROR` is used. If no *target* is specified, the target will need to be set using `setTarget()` before this handler does anything useful.

close ()

Calls `flush()`, sets the target to `None` and clears the buffer.

flush ()

For a `MemoryHandler`, flushing means just sending the buffered records to the target, if there is one. Override if you want different behavior.

setTarget (*target*)

Sets the target handler for this handler.

shouldFlush (*record*)

Checks for buffer full or a record at the *flushLevel* or higher.

HTTPHandler

The `HTTPHandler` class, located in the `logging.handlers` module, supports sending logging messages to a Web server, using either 'GET' or 'POST' semantics.

class HTTPHandler (*host*, *url* [, *method*])

Returns a new instance of the `HTTPHandler` class. The instance is initialized with a host address, url and HTTP method. The *host* can be of the form `host:port`, should you need to use a specific port number. If no *method* is specified, 'GET' is used.

emit (*record*)

Sends the record to the Web server as an URL-encoded dictionary.

14.5.6 Formatter Objects

Formatters have the following attributes and methods. They are responsible for converting a `LogRecord` to (usually) a string which can be interpreted by either a human or an external system. The base `Formatter` allows a formatting string to be specified. If none is supplied, the default value of `'%(message)s'` is used.

A `Formatter` can be initialized with a format string which makes use of knowledge of the `LogRecord` attributes - such as the default value mentioned above making use of the fact that the user's message and arguments are pre-formatted into a `LogRecord`'s `message` attribute. This format string contains standard python %-style mapping keys. See section 3.6.2, "String Formatting Operations," for more information on string formatting.

Currently, the useful mapping keys in a `LogRecord` are:

Format	Description
<code>%(name)s</code>	Name of the logger (logging channel).
<code>%(levelname)s</code>	Numeric logging level for the message (DEBUG, INFO, WARNING, ERROR, CRITICAL).
<code>%(levelname)s</code>	Text logging level for the message ('DEBUG', 'INFO', 'WARNING', 'ERROR', 'CRITICAL').
<code>%(pathname)s</code>	Full pathname of the source file where the logging call was issued (if available).
<code>%(filename)s</code>	Filename portion of pathname.
<code>%(module)s</code>	Module (name portion of filename).
<code>%(funcName)s</code>	Name of function containing the logging call.
<code>%(lineno)d</code>	Source line number where the logging call was issued (if available).
<code>%(created)f</code>	Time when the <code>LogRecord</code> was created (as returned by <code>time.time()</code>).
<code>%(relativeCreated)d</code>	Time in milliseconds when the <code>LogRecord</code> was created, relative to the time the logging module was loaded.
<code>%(asctime)s</code>	Human-readable time when the <code>LogRecord</code> was created. By default this is of the form "2003-07-08 12:00:00".
<code>%(msecs)d</code>	Millisecond portion of the time when the <code>LogRecord</code> was created.
<code>%(thread)d</code>	Thread ID (if available).
<code>%(threadName)s</code>	Thread name (if available).
<code>%(process)d</code>	Process ID (if available).
<code>%(message)s</code>	The logged message, computed as <code>msg %args</code> .

Changed in version 2.5: `funcName` was added.

class `Formatter` (`[fmt[, datefmt]]`)

Returns a new instance of the `Formatter` class. The instance is initialized with a format string for the message as a whole, as well as a format string for the date/time portion of a message. If no `fmt` is specified, `'%(message)s'` is used. If no `datefmt` is specified, the ISO8601 date format is used.

format (`record`)

The record's attribute dictionary is used as the operand to a string formatting operation. Returns the resulting string. Before formatting the dictionary, a couple of preparatory steps are carried out. The `message` attribute of the record is computed using `msg %args`. If the formatting string contains `'(asctime)'`, `formatTime()` is called to format the event time. If there is exception information, it is formatted using `formatException()` and appended to the message.

formatTime (`record[, datefmt]`)

This method should be called from `format()` by a formatter which wants to make use of a formatted time. This method can be overridden in formatters to provide for any specific requirement, but the basic behavior is as follows: if `datefmt` (a string) is specified, it is used with `time.strftime()` to format the creation time of the record. Otherwise, the ISO8601 format is used. The resulting string is returned.

formatException (`exc_info`)

Formats the specified exception information (a standard exception tuple as returned by `sys.exc_info()`) as a string. This default implementation just uses `traceback.print_exception()`. The resulting string is returned.

14.5.7 Filter Objects

Filters can be used by Handlers and Loggers for more sophisticated filtering than is provided by levels. The base filter class only allows events which are below a certain point in the logger hierarchy. For example, a filter initialized with "A.B" will allow events logged by loggers "A.B", "A.B.C", "A.B.C.D", "A.B.D" etc. but not "A.BB", "B.A.B" etc. If initialized with the empty string, all events are passed.

class Filter (*[name]*)

Returns an instance of the `Filter` class. If *name* is specified, it names a logger which, together with its children, will have its events allowed through the filter. If no name is specified, allows every event.

filter (*record*)

Is the specified record to be logged? Returns zero for no, nonzero for yes. If deemed appropriate, the record may be modified in-place by this method.

14.5.8 LogRecord Objects

`LogRecord` instances are created every time something is logged. They contain all the information pertinent to the event being logged. The main information passed in is in *msg* and *args*, which are combined using *msg % args* to create the message field of the record. The record also includes information such as when the record was created, the source line where the logging call was made, and any exception information to be logged.

class LogRecord (*name, lvl, pathname, lineno, msg, args, exc_info [, func]*)

Returns an instance of `LogRecord` initialized with interesting information. The *name* is the logger name; *lvl* is the numeric level; *pathname* is the absolute pathname of the source file in which the logging call was made; *lineno* is the line number in that file where the logging call is found; *msg* is the user-supplied message (a format string); *args* is the tuple which, together with *msg*, makes up the user message; and *exc_info* is the exception tuple obtained by calling `sys.exc_info()` (or `None`, if no exception information is available). The *func* is the name of the function from which the logging call was made. If not specified, it defaults to `None`. Changed in version 2.5: *func* was added.

getMessage ()

Returns the message for this `LogRecord` instance after merging any user-supplied arguments with the message.

14.5.9 Thread Safety

The logging module is intended to be thread-safe without any special work needing to be done by its clients. It achieves this though using threading locks; there is one lock to serialize access to the module's shared data, and each handler also creates a lock to serialize access to its underlying I/O.

14.5.10 Configuration

Configuration functions

The following functions configure the logging module. They are located in the `logging.config` module. Their use is optional — you can configure the logging module using these functions or by making calls to the main API (defined in `logging` itself) and defining handlers which are declared either in `logging` or `logging.handlers`.

fileConfig (*fname[, defaults]*)

Reads the logging configuration from a `ConfigParser`-format file named *fname*. This function can be called several times from an application, allowing an end user the ability to select from various pre-canned configurations (if the developer provides a mechanism to present the choices and load the chosen configuration). Defaults to be passed to `ConfigParser` can be specified in the *defaults* argument.

listen(*[port]*)

Starts up a socket server on the specified port, and listens for new configurations. If no port is specified, the module's default `DEFAULT_LOGGING_CONFIG_PORT` is used. Logging configurations will be sent as a file suitable for processing by `fileConfig()`. Returns a `Thread` instance on which you can call `start()` to start the server, and which you can `join()` when appropriate. To stop the server, call `stopListening()`. To send a configuration to the socket, read in the configuration file and send it to the socket as a string of bytes preceded by a four-byte length packed in binary using `struct.pack('>L', n)`.

stopListening()

Stops the listening server which was created with a call to `listen()`. This is typically called before calling `join()` on the return value from `listen()`.

Configuration file format

The configuration file format understood by `fileConfig()` is based on `ConfigParser` functionality. The file must contain sections called `[loggers]`, `[handlers]` and `[formatters]` which identify by name the entities of each type which are defined in the file. For each such entity, there is a separate section which identified how that entity is configured. Thus, for a logger named `log01` in the `[loggers]` section, the relevant configuration details are held in a section `[logger_log01]`. Similarly, a handler called `hand01` in the `[handlers]` section will have its configuration held in a section called `[handler_hand01]`, while a formatter called `form01` in the `[formatters]` section will have its configuration specified in a section called `[formatter_form01]`. The root logger configuration must be specified in a section called `[logger_root]`.

Examples of these sections in the file are given below.

```
[loggers]
keys=root,log02,log03,log04,log05,log06,log07

[handlers]
keys=hand01,hand02,hand03,hand04,hand05,hand06,hand07,hand08,hand09

[formatters]
keys=form01,form02,form03,form04,form05,form06,form07,form08,form09
```

The root logger must specify a level and a list of handlers. An example of a root logger section is given below.

```
[logger_root]
level=NOTSET
handlers=hand01
```

The `level` entry can be one of `DEBUG`, `INFO`, `WARNING`, `ERROR`, `CRITICAL` or `NOTSET`. For the root logger only, `NOTSET` means that all messages will be logged. Level values are evaluated in the context of the logging package's namespace.

The `handlers` entry is a comma-separated list of handler names, which must appear in the `[handlers]` section. These names must appear in the `[handlers]` section and have corresponding sections in the configuration file.

For loggers other than the root logger, some additional information is required. This is illustrated by the following example.

```
[logger_parser]
level=DEBUG
handlers=hand01
propagate=1
qualname=compiler.parser
```

The `level` and `handlers` entries are interpreted as for the root logger, except that if a non-root logger's level is specified as `NOTSET`, the system consults loggers higher up the hierarchy to determine the effective level of the logger. The `propagate` entry is set to 1 to indicate that messages must propagate to handlers higher up the logger hierarchy from this logger, or 0 to indicate that messages are **not** propagated to handlers up the hierarchy. The `qualname` entry is the hierarchical channel name of the logger, that is to say the name used by the application to get the logger.

Sections which specify handler configuration are exemplified by the following.

```
[handler_hand01]
class=StreamHandler
level=NOTSET
formatter=form01
args=(sys.stdout,)
```

The `class` entry indicates the handler's class (as determined by `eval()` in the logging package's namespace). The `level` is interpreted as for loggers, and `NOTSET` is taken to mean "log everything".

The `formatter` entry indicates the key name of the formatter for this handler. If blank, a default formatter (`logging._defaultFormatter`) is used. If a name is specified, it must appear in the `[formatters]` section and have a corresponding section in the configuration file.

The `args` entry, when `eval()` uated in the context of the logging package's namespace, is the list of arguments to the constructor for the handler class. Refer to the constructors for the relevant handlers, or to the examples below, to see how typical entries are constructed.

```

[handler_hand02]
class=FileHandler
level=DEBUG
formatter=form02
args=('python.log', 'w')

[handler_hand03]
class=handlers.SocketHandler
level=INFO
formatter=form03
args=('localhost', handlers.DEFAULT_TCP_LOGGING_PORT)

[handler_hand04]
class=handlers.DatagramHandler
level=WARN
formatter=form04
args=('localhost', handlers.DEFAULT_UDP_LOGGING_PORT)

[handler_hand05]
class=handlers.SysLogHandler
level=ERROR
formatter=form05
args= (('localhost', handlers.SYSLOG_UDP_PORT), handlers.SysLogHandler.LOG_USER)

[handler_hand06]
class=handlers.NTEventLogHandler
level=CRITICAL
formatter=form06
args=('Python Application', '', 'Application')

[handler_hand07]
class=handlers.SMTPHandler
level=WARN
formatter=form07
args=('localhost', 'from@abc', ['user1@abc', 'user2@xyz'], 'Logger Subject')

[handler_hand08]
class=handlers.MemoryHandler
level=NOTSET
formatter=form08
target=
args=(10, ERROR)

[handler_hand09]
class=handlers.HTTPHandler
level=NOTSET
formatter=form09
args=('localhost:9022', '/log', 'GET')

```

Sections which specify formatter configuration are typified by the following.

```

[formatter_form01]
format=F1 %(asctime)s %(levelname)s %(message)s
datefmt=
class=logging.Formatter

```

The `format` entry is the overall format string, and the `datefmt` entry is the `strftime()`-compatible date/time format string. If empty, the package substitutes ISO8601 format date/times, which is almost equivalent to specifying the date format string "The ISO8601 format also specifies milliseconds, which are appended to the result of using the above format string, with a comma separator. An example time in ISO8601 format is 2003-01-23 00:29:50,411.

The `class` entry is optional. It indicates the name of the formatter's class (as a dotted module and class name.) This option is useful for instantiating a `Formatter` subclass. Subclasses of `Formatter` can present exception tracebacks in an expanded or condensed format.

14.6 `getpass` — Portable password input

The `getpass` module provides two functions:

`getpass([prompt[, stream]])`

Prompt the user for a password without echoing. The user is prompted using the string *prompt*, which defaults to 'Password: '. On UNIX, the prompt is written to the file-like object *stream*, which defaults to `sys.stdout` (this argument is ignored on Windows).

Availability: Macintosh, UNIX, Windows. Changed in version 2.5: The *stream* parameter was added.

`getuser()`

Return the "login name" of the user. Availability: UNIX, Windows.

This function checks the environment variables LOGNAME, USER, LNAME and USERNAME, in order, and returns the value of the first one which is set to a non-empty string. If none are set, the login name from the password database is returned on systems which support the `pwd` module, otherwise, an exception is raised.

14.7 `curses` — Terminal handling for character-cell displays

Changed in version 1.6: Added support for the `ncurses` library and converted to a package.

The `curses` module provides an interface to the `curses` library, the de-facto standard for portable advanced terminal handling.

While `curses` is most widely used in the UNIX environment, versions are available for DOS, OS/2, and possibly other systems as well. This extension module is designed to match the API of `ncurses`, an open-source `curses` library hosted on Linux and the BSD variants of UNIX.

See Also:

[Module `curses.ascii`](#) (section 14.10):

Utilities for working with ASCII characters, regardless of your locale settings.

[Module `curses.panel`](#) (section 14.11):

A panel stack extension that adds depth to `curses` windows.

[Module `curses.textpad`](#) (section 14.8):

Editable text widget for `curses` supporting **Emacs**-like bindings.

[Module `curses.wrapper`](#) (section 14.9):

Convenience function to ensure proper terminal setup and resetting on application entry and exit.

Curses Programming with Python

(<http://www.python.org/doc/howto/curses/curses.html>)

Tutorial material on using `curses` with Python, by Andrew Kuchling and Eric Raymond, is available on the Python Web site.

The ‘Demo/curses/’ directory in the Python source distribution contains some example programs using the curses bindings provided by this module.

14.7.1 Functions

The module `curses` defines the following exception:

exception error

Exception raised when a curses library function returns an error.

Note: Whenever *x* or *y* arguments to a function or a method are optional, they default to the current cursor location. Whenever *attr* is optional, it defaults to `A_NORMAL`.

The module `curses` defines the following functions:

baudrate()

Returns the output speed of the terminal in bits per second. On software terminal emulators it will have a fixed high value. Included for historical reasons; in former times, it was used to write output loops for time delays and occasionally to change interfaces depending on the line speed.

beep()

Emit a short attention sound.

can_change_color()

Returns true or false, depending on whether the programmer can change the colors displayed by the terminal.

cbreak()

Enter cbreak mode. In cbreak mode (sometimes called “rare” mode) normal tty line buffering is turned off and characters are available to be read one by one. However, unlike raw mode, special characters (interrupt, quit, suspend, and flow control) retain their effects on the tty driver and calling program. Calling first `raw()` then `cbreak()` leaves the terminal in cbreak mode.

color_content(*color_number*)

Returns the intensity of the red, green, and blue (RGB) components in the color *color_number*, which must be between 0 and `COLORS`. A 3-tuple is returned, containing the R,G,B values for the given color, which will be between 0 (no component) and 1000 (maximum amount of component).

color_pair(*color_number*)

Returns the attribute value for displaying text in the specified color. This attribute value can be combined with `A_STANDOUT`, `A_REVERSE`, and the other `A_*` attributes. `pair_number()` is the counterpart to this function.

curs_set(*visibility*)

Sets the cursor state. *visibility* can be set to 0, 1, or 2, for invisible, normal, or very visible. If the terminal supports the visibility requested, the previous cursor state is returned; otherwise, an exception is raised. On many terminals, the “visible” mode is an underline cursor and the “very visible” mode is a block cursor.

def_prog_mode()

Saves the current terminal mode as the “program” mode, the mode when the running program is using curses. (Its counterpart is the “shell” mode, for when the program is not in curses.) Subsequent calls to `reset_prog_mode()` will restore this mode.

def_shell_mode()

Saves the current terminal mode as the “shell” mode, the mode when the running program is not using curses. (Its counterpart is the “program” mode, when the program is using curses capabilities.) Subsequent calls to `reset_shell_mode()` will restore this mode.

delay_output(*ms*)

Inserts an *ms* millisecond pause in output.

doupdate()

Update the physical screen. The curses library keeps two data structures, one representing the current physical screen contents and a virtual screen representing the desired next state. The `doupdate()` ground updates the physical screen to match the virtual screen.

The virtual screen may be updated by a `noutrefresh()` call after write operations such as `addstr()` have been performed on a window. The normal `refresh()` call is simply `noutrefresh()` followed by `doupdate()`; if you have to update multiple windows, you can speed performance and perhaps reduce screen flicker by issuing `noutrefresh()` calls on all windows, followed by a single `doupdate()`.

echo()

Enter echo mode. In echo mode, each character input is echoed to the screen as it is entered.

endwin()

De-initialize the library, and return terminal to normal status.

erasechar()

Returns the user's current erase character. Under UNIX operating systems this is a property of the controlling tty of the curses program, and is not set by the curses library itself.

filter()

The `filter()` routine, if used, must be called before `initscr()` is called. The effect is that, during those calls, `LINES` is set to 1; the capabilities `clear`, `cup`, `cud`, `cudl`, `cuu`, `vpa` are disabled; and the home string is set to the value of `cr`. The effect is that the cursor is confined to the current line, and so are screen updates. This may be used for enabling character-at-a-time line editing without touching the rest of the screen.

flash()

Flash the screen. That is, change it to reverse-video and then change it back in a short interval. Some people prefer such as 'visible bell' to the audible attention signal produced by `beep()`.

flushinp()

Flush all input buffers. This throws away any typeahead that has been typed by the user and has not yet been processed by the program.

getmouse()

After `getch()` returns `KEY_MOUSE` to signal a mouse event, this method should be call to retrieve the queued mouse event, represented as a 5-tuple $(id, x, y, z, bstate)$. id is an ID value used to distinguish multiple devices, and x, y, z are the event's coordinates. (z is currently unused.). $bstate$ is an integer value whose bits will be set to indicate the type of event, and will be the bitwise OR of one or more of the following constants, where n is the button number from 1 to 4: `BUTTONn_PRESSED`, `BUTTONn_RELEASED`, `BUTTONn_CLICKED`, `BUTTONn_DOUBLE_CLICKED`, `BUTTONn_TRIPLE_CLICKED`, `BUTTON_SHIFT`, `BUTTON_CTRL`, `BUTTON_ALT`.

getsyx()

Returns the current coordinates of the virtual screen cursor in y and x . If `leaveok` is currently true, then $-1, -1$ is returned.

getwin(file)

Reads window related data stored in the file by an earlier `putwin()` call. The routine then creates and initializes a new window using that data, returning the new window object.

has_colors()

Returns true if the terminal can display colors; otherwise, it returns false.

has_ic()

Returns true if the terminal has insert- and delete- character capabilities. This function is included for historical reasons only, as all modern software terminal emulators have such capabilities.

has_il()

Returns true if the terminal has insert- and delete-line capabilities, or can simulate them using scrolling regions. This function is included for historical reasons only, as all modern software terminal emulators have such

capabilities.

has_key (*ch*)

Takes a key value *ch*, and returns true if the current terminal type recognizes a key with that value.

halfdelay (*tenths*)

Used for half-delay mode, which is similar to cbreak mode in that characters typed by the user are immediately available to the program. However, after blocking for *tenths* tenths of seconds, an exception is raised if nothing has been typed. The value of *tenths* must be a number between 1 and 255. Use `nocbreak()` to leave half-delay mode.

init_color (*color_number*, *r*, *g*, *b*)

Changes the definition of a color, taking the number of the color to be changed followed by three RGB values (for the amounts of red, green, and blue components). The value of *color_number* must be between 0 and `COLORS`. Each of *r*, *g*, *b*, must be a value between 0 and 1000. When `init_color()` is used, all occurrences of that color on the screen immediately change to the new definition. This function is a no-op on most terminals; it is active only if `can_change_color()` returns 1.

init_pair (*pair_number*, *fg*, *bg*)

Changes the definition of a color-pair. It takes three arguments: the number of the color-pair to be changed, the foreground color number, and the background color number. The value of *pair_number* must be between 1 and `COLOR_PAIRS - 1` (the 0 color pair is wired to white on black and cannot be changed). The value of *fg* and *bg* arguments must be between 0 and `COLORS`. If the color-pair was previously initialized, the screen is refreshed and all occurrences of that color-pair are changed to the new definition.

initscr ()

Initialize the library. Returns a `WindowObject` which represents the whole screen. **Note:** If there is an error opening the terminal, the underlying curses library may cause the interpreter to exit.

isendwin ()

Returns true if `endwin()` has been called (that is, the curses library has been deinitialized).

keyname (*k*)

Return the name of the key numbered *k*. The name of a key generating printable ASCII character is the key's character. The name of a control-key combination is a two-character string consisting of a caret followed by the corresponding printable ASCII character. The name of an alt-key combination (128-255) is a string consisting of the prefix 'M-' followed by the name of the corresponding ASCII character.

killchar ()

Returns the user's current line kill character. Under UNIX operating systems this is a property of the controlling tty of the curses program, and is not set by the curses library itself.

longname ()

Returns a string containing the terminfo long name field describing the current terminal. The maximum length of a verbose description is 128 characters. It is defined only after the call to `initscr()`.

meta (*yes*)

If *yes* is 1, allow 8-bit characters to be input. If *yes* is 0, allow only 7-bit chars.

mouseinterval (*interval*)

Sets the maximum time in milliseconds that can elapse between press and release events in order for them to be recognized as a click, and returns the previous interval value. The default value is 200 msec, or one fifth of a second.

mousemask (*mousemask*)

Sets the mouse events to be reported, and returns a tuple (*availmask*, *oldmask*). *availmask* indicates which of the specified mouse events can be reported; on complete failure it returns 0. *oldmask* is the previous value of the given window's mouse event mask. If this function is never called, no mouse events are ever reported.

napms (*ms*)

Sleep for *ms* milliseconds.

newpad (*nlines*, *ncols*)

Creates and returns a pointer to a new pad data structure with the given number of lines and columns. A pad is returned as a window object.

A pad is like a window, except that it is not restricted by the screen size, and is not necessarily associated with a particular part of the screen. Pads can be used when a large window is needed, and only a part of the window will be on the screen at one time. Automatic refreshes of pads (such as from scrolling or echoing of input) do not occur. The `refresh()` and `noutrefresh()` methods of a pad require 6 arguments to specify the part of the pad to be displayed and the location on the screen to be used for the display. The arguments are *pminrow*, *pmincol*, *sminrow*, *smincol*, *smaxrow*, *smaxcol*; the *p* arguments refer to the upper left corner of the pad region to be displayed and the *s* arguments define a clipping box on the screen within which the pad region is to be displayed.

newwin ([*nlines*, *ncols*,] *begin_y*, *begin_x*)

Return a new window, whose left-upper corner is at (*begin_y*, *begin_x*), and whose height/width is *nlines/ncols*.

By default, the window will extend from the specified position to the lower right corner of the screen.

nl ()

Enter newline mode. This mode translates the return key into newline on input, and translates newline into return and line-feed on output. Newline mode is initially on.

nocbreak ()

Leave cbreak mode. Return to normal “cooked” mode with line buffering.

noecho ()

Leave echo mode. Echoing of input characters is turned off.

nonl ()

Leave newline mode. Disable translation of return into newline on input, and disable low-level translation of newline into newline/return on output (but this does not change the behavior of `addch(' \n')`, which always does the equivalent of return and line feed on the virtual screen). With translation off, curses can sometimes speed up vertical motion a little; also, it will be able to detect the return key on input.

noqiflush ()

When the `noqiflush` routine is used, normal flush of input and output queues associated with the INTR, QUIT and SUSP characters will not be done. You may want to call `noqiflush()` in a signal handler if you want output to continue as though the interrupt had not occurred, after the handler exits.

noraw ()

Leave raw mode. Return to normal “cooked” mode with line buffering.

pair_content (*pair_number*)

Returns a tuple (*fg*, *bg*) containing the colors for the requested color pair. The value of *pair_number* must be between 1 and `COLOR_PAIRS - 1`.

pair_number (*attr*)

Returns the number of the color-pair set by the attribute value *attr*. `color_pair()` is the counterpart to this function.

putp (*string*)

Equivalent to `tputs(str, 1, putchar)`; emits the value of a specified terminfo capability for the current terminal. Note that the output of `putp` always goes to standard output.

qiflush ([*flag*])

If *flag* is false, the effect is the same as calling `noqiflush()`. If *flag* is true, or no argument is provided, the queues will be flushed when these control characters are read.

raw ()

Enter raw mode. In raw mode, normal line buffering and processing of interrupt, quit, suspend, and flow control keys are turned off; characters are presented to curses input functions one by one.

reset_prog_mode()

Restores the terminal to “program” mode, as previously saved by `def_prog_mode()`.

reset_shell_mode()

Restores the terminal to “shell” mode, as previously saved by `def_shell_mode()`.

setsyx(y, x)

Sets the virtual screen cursor to *y*, *x*. If *y* and *x* are both -1, then `leaveok` is set.

setupterm([termstr, fd])

Initializes the terminal. *termstr* is a string giving the terminal name; if omitted, the value of the `TERM` environment variable will be used. *fd* is the file descriptor to which any initialization sequences will be sent; if not supplied, the file descriptor for `sys.stdout` will be used.

start_color()

Must be called if the programmer wants to use colors, and before any other color manipulation routine is called. It is good practice to call this routine right after `initscr()`.

`start_color()` initializes eight basic colors (black, red, green, yellow, blue, magenta, cyan, and white), and two global variables in the `curses` module, `COLORS` and `COLOR_PAIRS`, containing the maximum number of colors and color-pairs the terminal can support. It also restores the colors on the terminal to the values they had when the terminal was just turned on.

termattrs()

Returns a logical OR of all video attributes supported by the terminal. This information is useful when a `curses` program needs complete control over the appearance of the screen.

termname()

Returns the value of the environment variable `TERM`, truncated to 14 characters.

tigetflag(capname)

Returns the value of the Boolean capability corresponding to the terminfo capability name *capname*. The value -1 is returned if *capname* is not a Boolean capability, or 0 if it is canceled or absent from the terminal description.

tigetnum(capname)

Returns the value of the numeric capability corresponding to the terminfo capability name *capname*. The value -2 is returned if *capname* is not a numeric capability, or -1 if it is canceled or absent from the terminal description.

tigetstr(capname)

Returns the value of the string capability corresponding to the terminfo capability name *capname*. `None` is returned if *capname* is not a string capability, or is canceled or absent from the terminal description.

tparm(str[,...])

Instantiates the string *str* with the supplied parameters, where *str* should be a parameterized string obtained from the terminfo database. E.g. `tparm(tigetstr("cup"), 5, 3)` could result in `'\033[6;4H'`, the exact result depending on terminal type.

typeahead(fd)

Specifies that the file descriptor *fd* be used for typeahead checking. If *fd* is -1, then no typeahead checking is done.

The `curses` library does “line-breakout optimization” by looking for typeahead periodically while updating the screen. If input is found, and it is coming from a tty, the current update is postponed until `refresh` or `doupdate` is called again, allowing faster response to commands typed in advance. This function allows specifying a different file descriptor for typeahead checking.

unctrl(ch)

Returns a string which is a printable representation of the character *ch*. Control characters are displayed as a caret followed by the character, for example as `^C`. Printing characters are left as they are.

ungetch (*ch*)

Push *ch* so the next `getch()` will return it. **Note:** Only one *ch* can be pushed before `getch()` is called.

ungetmouse (*id*, *x*, *y*, *z*, *bstate*)

Push a `KEY_MOUSE` event onto the input queue, associating the given state data with it.

use_env (*flag*)

If used, this function should be called before `initscr()` or `newterm` are called. When *flag* is false, the values of lines and columns specified in the terminfo database will be used, even if environment variables `LINES` and `COLUMNS` (used by default) are set, or if `curses` is running in a window (in which case default behavior would be to use the window size if `LINES` and `COLUMNS` are not set).

use_default_colors ()

Allow use of default values for colors on terminals supporting this feature. Use this to support transparency in your application. The default color is assigned to the color number -1. After calling this function, `init_pair(x, curses.COLOR_RED, -1)` initializes, for instance, color pair *x* to a red foreground color on the default background.

14.7.2 Window Objects

Window objects, as returned by `initscr()` and `newwin()` above, have the following methods:

addch ([*y*, *x*,] *ch*[, *attr*])

Note: A *character* means a C character (an ASCII code), rather than a Python character (a string of length 1). (This note is true whenever the documentation mentions a character.) The builtin `ord()` is handy for conveying strings to codes.

Paint character *ch* at (*y*, *x*) with attributes *attr*, overwriting any character previously painter at that location. By default, the character position and attributes are the current settings for the window object.

addnstr ([*y*, *x*,] *str*, *n*[, *attr*])

Paint at most *n* characters of the string *str* at (*y*, *x*) with attributes *attr*, overwriting anything previously on the display.

addstr ([*y*, *x*,] *str*[, *attr*])

Paint the string *str* at (*y*, *x*) with attributes *attr*, overwriting anything previously on the display.

attroff (*attr*)

Remove attribute *attr* from the “background” set applied to all writes to the current window.

attron (*attr*)

Add attribute *attr* from the “background” set applied to all writes to the current window.

attrset (*attr*)

Set the “background” set of attributes to *attr*. This set is initially 0 (no attributes).

bkgd (*ch*[, *attr*])

Sets the background property of the window to the character *ch*, with attributes *attr*. The change is then applied to every character position in that window:

- The attribute of every character in the window is changed to the new background attribute.
- Wherever the former background character appears, it is changed to the new background character.

bkgdset (*ch*[, *attr*])

Sets the window’s background. A window’s background consists of a character and any combination of attributes. The attribute part of the background is combined (OR’ed) with all non-blank characters that are written into the window. Both the character and attribute parts of the background are combined with the blank characters. The background becomes a property of the character and moves with the character through any scrolling and insert/delete line/character operations.

border (*ls* [, *rs* [, *ts* [, *bs* [, *tl* [, *tr* [, *bl* [, *br*]]]]]]]])

Draw a border around the edges of the window. Each parameter specifies the character to use for a specific part of the border; see the table below for more details. The characters can be specified as integers or as one-character strings.

Note: A 0 value for any parameter will cause the default character to be used for that parameter. Keyword parameters can *not* be used. The defaults are listed in this table:

Parameter	Description	Default value
<i>ls</i>	Left side	ACS_VLINE
<i>rs</i>	Right side	ACS_VLINE
<i>ts</i>	Top	ACS_HLINE
<i>bs</i>	Bottom	ACS_HLINE
<i>tl</i>	Upper-left corner	ACS_ULCORNER
<i>tr</i>	Upper-right corner	ACS_URCORNER
<i>bl</i>	Bottom-left corner	ACS_LLCORNER
<i>br</i>	Bottom-right corner	ACS_LRCORNER

box (*vertch*, *horch*)

Similar to `border()`, but both *ls* and *rs* are *vertch* and both *ts* and *bs* are *horch*. The default corner characters are always used by this function.

clear ()

Like `erase()`, but also causes the whole window to be repainted upon next call to `refresh()`.

clearok (*yes*)

If *yes* is 1, the next call to `refresh()` will clear the window completely.

clrtoebot ()

Erase from cursor to the end of the window: all lines below the cursor are deleted, and then the equivalent of `clrtoeol()` is performed.

clrtoeol ()

Erase from cursor to the end of the line.

cursyncup ()

Updates the current cursor position of all the ancestors of the window to reflect the current cursor position of the window.

delch (*y*, *x*)

Delete any character at (*y*, *x*).

deleteln ()

Delete the line under the cursor. All following lines are moved up by 1 line.

derwin (*nlines*, *ncols*, *begin_y*, *begin_x*)

An abbreviation for “derive window”, `derwin()` is the same as calling `subwin()`, except that *begin_y* and *begin_x* are relative to the origin of the window, rather than relative to the entire screen. Returns a window object for the derived window.

echochar (*ch*, *attr*)

Add character *ch* with attribute *attr*, and immediately call `refresh()` on the window.

enclose (*y*, *x*)

Tests whether the given pair of screen-relative character-cell coordinates are enclosed by the given window, returning true or false. It is useful for determining what subset of the screen windows enclose the location of a mouse event.

erase ()

Clear the window.

getbegyx ()

Return a tuple (y, x) of co-ordinates of upper-left corner.

getch ($[y, x]$)

Get a character. Note that the integer returned does *not* have to be in ASCII range: function keys, keypad keys and so on return numbers higher than 256. In no-delay mode, -1 is returned if there is no input.

getkey ($[y, x]$)

Get a character, returning a string instead of an integer, as `getch()` does. Function keys, keypad keys and so on return a multibyte string containing the key name. In no-delay mode, an exception is raised if there is no input.

getmaxyx ()

Return a tuple (y, x) of the height and width of the window.

getparyx ()

Returns the beginning coordinates of this window relative to its parent window into two integer variables y and x . Returns $-1, -1$ if this window has no parent.

getstr ($[y, x]$)

Read a string from the user, with primitive line editing capacity.

getyx ()

Return a tuple (y, x) of current cursor position relative to the window's upper-left corner.

hline ($[y, x,] ch, n$)

Display a horizontal line starting at (y, x) with length n consisting of the character ch .

idcok ($flag$)

If $flag$ is false, `curses` no longer considers using the hardware insert/delete character feature of the terminal; if $flag$ is true, use of character insertion and deletion is enabled. When `curses` is first initialized, use of character insert/delete is enabled by default.

idlok (yes)

If called with yes equal to 1, `curses` will try and use hardware line editing facilities. Otherwise, line insertion/deletion are disabled.

immedok ($flag$)

If $flag$ is true, any change in the window image automatically causes the window to be refreshed; you no longer have to call `refresh()` yourself. However, it may degrade performance considerably, due to repeated calls to `wrefresh`. This option is disabled by default.

inch ($[y, x]$)

Return the character at the given position in the window. The bottom 8 bits are the character proper, and upper bits are the attributes.

insch ($[y, x,] ch[, attr]$)

Paint character ch at (y, x) with attributes $attr$, moving the line from position x right by one character.

insdelln ($nlines$)

Inserts $nlines$ lines into the specified window above the current line. The $nlines$ bottom lines are lost. For negative $nlines$, delete $nlines$ lines starting with the one under the cursor, and move the remaining lines up. The bottom $nlines$ lines are cleared. The current cursor position remains the same.

insertln ()

Insert a blank line under the cursor. All following lines are moved down by 1 line.

insnstr ($[y, x,] str, n [, attr]$)

Insert a character string (as many characters as will fit on the line) before the character under the cursor, up to n characters. If n is zero or negative, the entire string is inserted. All characters to the right of the cursor are shifted right, with the rightmost characters on the line being lost. The cursor position does not change (after moving to y, x , if specified).

insstr (*[y, x]* *str* *[, attr]*)

Insert a character string (as many characters as will fit on the line) before the character under the cursor. All characters to the right of the cursor are shifted right, with the rightmost characters on the line being lost. The cursor position does not change (after moving to *y, x*, if specified).

instr (*[y, x]* *[, n]*)

Returns a string of characters, extracted from the window starting at the current cursor position, or at *y, x* if specified. Attributes are stripped from the characters. If *n* is specified, **instr**() returns return a string at most *n* characters long (exclusive of the trailing NUL).

is_linetouched (*line*)

Returns true if the specified line was modified since the last call to **refresh**(); otherwise returns false. Raises a **curses.error** exception if *line* is not valid for the given window.

is_wintouched ()

Returns true if the specified window was modified since the last call to **refresh**(); otherwise returns false.

keypad (*yes*)

If *yes* is 1, escape sequences generated by some keys (keypad, function keys) will be interpreted by **curses**. If *yes* is 0, escape sequences will be left as is in the input stream.

leaveok (*yes*)

If *yes* is 1, cursor is left where it is on update, instead of being at “cursor position.” This reduces cursor movement where possible. If possible the cursor will be made invisible.

If *yes* is 0, cursor will always be at “cursor position” after an update.

move (*new_y, new_x*)

Move cursor to (*new_y*, *new_x*).

mvderwin (*y, x*)

Moves the window inside its parent window. The screen-relative parameters of the window are not changed. This routine is used to display different parts of the parent window at the same physical position on the screen.

mvwin (*new_y, new_x*)

Move the window so its upper-left corner is at (*new_y*, *new_x*).

nodelay (*yes*)

If *yes* is 1, **getch**() will be non-blocking.

notimeout (*yes*)

If *yes* is 1, escape sequences will not be timed out.

If *yes* is 0, after a few milliseconds, an escape sequence will not be interpreted, and will be left in the input stream as is.

noutrefresh ()

Mark for refresh but wait. This function updates the data structure representing the desired state of the window, but does not force an update of the physical screen. To accomplish that, call **doupdate**() .

overlay (*destwin* *[, sminrow, smincol, dminrow, dmincol, dmaxrow, dmaxcol]*)

Overlay the window on top of *destwin*. The windows need not be the same size, only the overlapping region is copied. This copy is non-destructive, which means that the current background character does not overwrite the old contents of *destwin*.

To get fine-grained control over the copied region, the second form of **overlay**() can be used. *sminrow* and *smincol* are the upper-left coordinates of the source window, and the other variables mark a rectangle in the destination window.

overwrite (*destwin* *[, sminrow, smincol, dminrow, dmincol, dmaxrow, dmaxcol]*)

Overwrite the window on top of *destwin*. The windows need not be the same size, in which case only the overlapping region is copied. This copy is destructive, which means that the current background character overwrites the old contents of *destwin*.

To get fine-grained control over the copied region, the second form of `overwrite()` can be used. *sminrow* and *smincol* are the upper-left coordinates of the source window, the other variables mark a rectangle in the destination window.

putwin (*file*)

Writes all data associated with the window into the provided file object. This information can be later retrieved using the `getwin()` function.

redrawln (*beg*, *num*)

Indicates that the *num* screen lines, starting at line *beg*, are corrupted and should be completely redrawn on the next `refresh()` call.

redrawwin ()

Touches the entire window, causing it to be completely redrawn on the next `refresh()` call.

refresh ([*pminrow*, *pmincol*, *sminrow*, *smincol*, *smaxrow*, *smaxcol*])

Update the display immediately (sync actual screen with previous drawing/deleting methods).

The 6 optional arguments can only be specified when the window is a pad created with `newpad()`. The additional parameters are needed to indicate what part of the pad and screen are involved. *pminrow* and *pmincol* specify the upper left-hand corner of the rectangle to be displayed in the pad. *sminrow*, *smincol*, *smaxrow*, and *smaxcol* specify the edges of the rectangle to be displayed on the screen. The lower right-hand corner of the rectangle to be displayed in the pad is calculated from the screen coordinates, since the rectangles must be the same size. Both rectangles must be entirely contained within their respective structures. Negative values of *pminrow*, *pmincol*, *sminrow*, or *smincol* are treated as if they were zero.

scroll ([*lines* = 1])

Scroll the screen or scrolling region upward by *lines* lines.

scrollok (*flag*)

Controls what happens when the cursor of a window is moved off the edge of the window or scrolling region, either as a result of a newline action on the bottom line, or typing the last character of the last line. If *flag* is false, the cursor is left on the bottom line. If *flag* is true, the window is scrolled up one line. Note that in order to get the physical scrolling effect on the terminal, it is also necessary to call `idlok()`.

setscrreg (*top*, *bottom*)

Set the scrolling region from line *top* to line *bottom*. All scrolling actions will take place in this region.

standend ()

Turn off the standout attribute. On some terminals this has the side effect of turning off all attributes.

standout ()

Turn on attribute *A_STANDOUT*.

subpad ([*nlines*, *ncols*,] *begin_y*, *begin_x*)

Return a sub-window, whose upper-left corner is at (*begin_y*, *begin_x*), and whose width/height is *ncols/nlines*.

subwin ([*nlines*, *ncols*,] *begin_y*, *begin_x*)

Return a sub-window, whose upper-left corner is at (*begin_y*, *begin_x*), and whose width/height is *ncols/nlines*.

By default, the sub-window will extend from the specified position to the lower right corner of the window.

syncdown ()

Touches each location in the window that has been touched in any of its ancestor windows. This routine is called by `refresh()`, so it should almost never be necessary to call it manually.

syncok (*flag*)

If called with *flag* set to true, then `syncup()` is called automatically whenever there is a change in the window.

syncup ()

Touches all locations in ancestors of the window that have been changed in the window.

timeout (*delay*)

Sets blocking or non-blocking read behavior for the window. If *delay* is negative, blocking read is used (which will wait indefinitely for input). If *delay* is zero, then non-blocking read is used, and -1 will be returned by `getch()` if no input is waiting. If *delay* is positive, then `getch()` will block for *delay* milliseconds, and return -1 if there is still no input at the end of that time.

touchline (*start*, *count* [, *changed*])

Pretend *count* lines have been changed, starting with line *start*. If *changed* is supplied, it specifies whether the affected lines are marked as having been changed (*changed*=1) or unchanged (*changed*=0).

touchwin ()

Pretend the whole window has been changed, for purposes of drawing optimizations.

untouchwin ()

Marks all lines in the window as unchanged since the last call to `refresh()`.

vline ([*y*, *x*,] *ch*, *n*)

Display a vertical line starting at (*y*, *x*) with length *n* consisting of the character *ch*.

14.7.3 Constants

The `curses` module defines the following data members:

ERR

Some curses routines that return an integer, such as `getch()`, return ERR upon failure.

OK

Some curses routines that return an integer, such as `napms()`, return OK upon success.

version

A string representing the current version of the module. Also available as `__version__`.

Several constants are available to specify character cell attributes:

Attribute	Meaning
A_ALTCHARSET	Alternate character set mode.
A_BLINK	Blink mode.
A_BOLD	Bold mode.
A_DIM	Dim mode.
A_NORMAL	Normal attribute.
A_STANDOUT	Standout mode.
A_UNDERLINE	Underline mode.

Keys are referred to by integer constants with names starting with 'KEY_'. The exact keycaps available are system dependent.

Key constant	Key
KEY_MIN	Minimum key value
KEY_BREAK	Break key (unreliable)
KEY_DOWN	Down-arrow
KEY_UP	Up-arrow
KEY_LEFT	Left-arrow
KEY_RIGHT	Right-arrow
KEY_HOME	Home key (upward+left arrow)
KEY_BACKSPACE	Backspace (unreliable)
KEY_F0	Function keys. Up to 64 function keys are supported.

Key constant	Key
KEY_Fn	Value of function key <i>n</i>
KEY_DL	Delete line
KEY_IL	Insert line
KEY_DC	Delete character
KEY_IC	Insert char or enter insert mode
KEY_EIC	Exit insert char mode
KEY_CLEAR	Clear screen
KEY_EOS	Clear to end of screen
KEY_EOL	Clear to end of line
KEY_SF	Scroll 1 line forward
KEY_SR	Scroll 1 line backward (reverse)
KEY_NPAGE	Next page
KEY_PPAGE	Previous page
KEY_STAB	Set tab
KEY_CTAB	Clear tab
KEY_CATAB	Clear all tabs
KEY_ENTER	Enter or send (unreliable)
KEY_SRESET	Soft (partial) reset (unreliable)
KEY_RESET	Reset or hard reset (unreliable)
KEY_PRINT	Print
KEY_LL	Home down or bottom (lower left)
KEY_A1	Upper left of keypad
KEY_A3	Upper right of keypad
KEY_B2	Center of keypad
KEY_C1	Lower left of keypad
KEY_C3	Lower right of keypad
KEY_BTAB	Back tab
KEY_BEG	Beg (beginning)
KEY_CANCEL	Cancel
KEY_CLOSE	Close
KEY_COMMAND	Cmd (command)
KEY_COPY	Copy
KEY_CREATE	Create
KEY_END	End
KEY_EXIT	Exit
KEY_FIND	Find
KEY_HELP	Help
KEY_MARK	Mark
KEY_MESSAGE	Message
KEY_MOVE	Move
KEY_NEXT	Next
KEY_OPEN	Open
KEY_OPTIONS	Options
KEY_PREVIOUS	Prev (previous)
KEY_REDO	Redo
KEY_REFERENCE	Ref (reference)
KEY_REFRESH	Refresh
KEY_REPLACE	Replace
KEY_RESTART	Restart
KEY_RESUME	Resume
KEY_SAVE	Save
KEY_SBEG	Shifted Beg (beginning)
KEY_SCANCEL	Shifted Cancel

Key constant	Key
KEY_SCOMMAND	Shifted Command
KEY_SCOPY	Shifted Copy
KEY_SCREATE	Shifted Create
KEY_SDC	Shifted Delete char
KEY_SDL	Shifted Delete line
KEY_SELECT	Select
KEY_SEND	Shifted End
KEY_SEOL	Shifted Clear line
KEY_SEXIT	Shifted Dxit
KEY_SFIND	Shifted Find
KEY_SHELP	Shifted Help
KEY_SHOME	Shifted Home
KEY_SIC	Shifted Input
KEY_SLEFT	Shifted Left arrow
KEY_SMESSAGE	Shifted Message
KEY_SMOVE	Shifted Move
KEY_SNEXT	Shifted Next
KEY_SOPTIONS	Shifted Options
KEY_SPREVIOUS	Shifted Prev
KEY_SPRINT	Shifted Print
KEY_SREDO	Shifted Redo
KEY_SREPLACE	Shifted Replace
KEY_SRIGHT	Shifted Right arrow
KEY_SRSUME	Shifted Resume
KEY_SSAVE	Shifted Save
KEY_SSUSPEND	Shifted Suspend
KEY_SUNDO	Shifted Undo
KEY_SUSPEND	Suspend
KEY_UNDO	Undo
KEY_MOUSE	Mouse event has occurred
KEY_RESIZE	Terminal resize event
KEY_MAX	Maximum key value

On VT100s and their software emulations, such as X terminal emulators, there are normally at least four function keys (KEY_F1, KEY_F2, KEY_F3, KEY_F4) available, and the arrow keys mapped to KEY_UP, KEY_DOWN, KEY_LEFT and KEY_RIGHT in the obvious way. If your machine has a PC keyboard, it is safe to expect arrow keys and twelve function keys (older PC keyboards may have only ten function keys); also, the following keypad mappings are standard:

Keycap	Constant
Insert	KEY_IC
Delete	KEY_DC
Home	KEY_HOME
End	KEY_END
Page Up	KEY_NPAGE
Page Down	KEY_PPAGE

The following table lists characters from the alternate character set. These are inherited from the VT100 terminal, and will generally be available on software emulations such as X terminals. When there is no graphic available, curses falls back on a crude printable ASCII approximation. **Note:** These are available only after `initscr()` has been called.

ACS code	Meaning
ACS_BBSS	alternate name for upper right corner
ACS_BLOCK	solid square block
ACS_BOARD	board of squares
ACS_BSBS	alternate name for horizontal line
ACS_BSSB	alternate name for upper left corner
ACS_BSSS	alternate name for top tee
ACS_BTEE	bottom tee
ACS_BULLET	bullet
ACS_CKBOARD	checker board (stipple)
ACS_DARROW	arrow pointing down
ACS_DEGREE	degree symbol
ACS_DIAMOND	diamond
ACS_GEQUAL	greater-than-or-equal-to
ACS_HLINE	horizontal line
ACS_LANTERN	lantern symbol
ACS_LARROW	left arrow
ACS_LEQUAL	less-than-or-equal-to
ACS_LLCORNER	lower left-hand corner
ACS_LRCORNER	lower right-hand corner
ACS_LTEE	left tee
ACS_NEQUAL	not-equal sign
ACS_PI	letter pi
ACS_PLMINUS	plus-or-minus sign
ACS_PLUS	big plus sign
ACS_RARROW	right arrow
ACS_RTEE	right tee
ACS_S1	scan line 1
ACS_S3	scan line 3
ACS_S7	scan line 7
ACS_S9	scan line 9
ACS_SBBS	alternate name for lower right corner
ACS_SBSB	alternate name for vertical line
ACS_SBSS	alternate name for right tee
ACS_SSBB	alternate name for lower left corner
ACS_SSBS	alternate name for bottom tee
ACS_SSSB	alternate name for left tee
ACS_SSSS	alternate name for crossover or big plus
ACS_STERLING	pound sterling
ACS_TTEE	top tee
ACS_UARROW	up arrow
ACS_ULCORNER	upper left corner
ACS_URCORNER	upper right corner
ACS_VLINE	vertical line

The following table lists the predefined colors:

Constant	Color
COLOR_BLACK	Black
COLOR_BLUE	Blue
COLOR_CYAN	Cyan (light greenish blue)
COLOR_GREEN	Green
COLOR_MAGENTA	Magenta (purplish red)
COLOR_RED	Red
COLOR_WHITE	White
COLOR_YELLOW	Yellow

14.8 `curses.textpad` — Text input widget for curses programs

New in version 1.6.

The `curses.textpad` module provides a `Textbox` class that handles elementary text editing in a curses window, supporting a set of keybindings resembling those of Emacs (thus, also of Netscape Navigator, BBedit 6.x, FrameMaker, and many other programs). The module also provides a rectangle-drawing function useful for framing text boxes or for other purposes.

The module `curses.textpad` defines the following function:

rectangle (*win, uly, ulx, lry, lrx*)

Draw a rectangle. The first argument must be a window object; the remaining arguments are coordinates relative to that window. The second and third arguments are the y and x coordinates of the upper left hand corner of the rectangle to be drawn; the fourth and fifth arguments are the y and x coordinates of the lower right hand corner. The rectangle will be drawn using VT100/IBM PC forms characters on terminals that make this possible (including xterm and most other software terminal emulators). Otherwise it will be drawn with ASCII dashes, vertical bars, and plus signs.

14.8.1 Textbox objects

You can instantiate a `Textbox` object as follows:

class Textbox (*win*)

Return a textbox widget object. The *win* argument should be a curses `WindowObject` in which the textbox is to be contained. The edit cursor of the textbox is initially located at the upper left hand corner of the containing window, with coordinates (0, 0). The instance's `stripspaces` flag is initially on.

Textbox objects have the following methods:

edit ([*validator*])

This is the entry point you will normally use. It accepts editing keystrokes until one of the termination keystrokes is entered. If *validator* is supplied, it must be a function. It will be called for each keystroke entered with the keystroke as a parameter; command dispatch is done on the result. This method returns the window contents as a string; whether blanks in the window are included is affected by the `stripspaces` member.

do_command (*ch*)

Process a single command keystroke. Here are the supported special keystrokes:

Keystroke	Action
Control-A	Go to left edge of window.
Control-B	Cursor left, wrapping to previous line if appropriate.
Control-D	Delete character under cursor.
Control-E	Go to right edge (stripspaces off) or end of line (stripspaces on).
Control-F	Cursor right, wrapping to next line when appropriate.
Control-G	Terminate, returning the window contents.
Control-H	Delete character backward.
Control-J	Terminate if the window is 1 line, otherwise insert newline.
Control-K	If line is blank, delete it, otherwise clear to end of line.
Control-L	Refresh screen.
Control-N	Cursor down; move down one line.
Control-O	Insert a blank line at cursor location.
Control-P	Cursor up; move up one line.

Move operations do nothing if the cursor is at an edge where the movement is not possible. The following synonyms are supported where possible:

Constant	Keystroke
KEY_LEFT	Control-B
KEY_RIGHT	Control-F
KEY_UP	Control-P
KEY_DOWN	Control-N
KEY_BACKSPACE	Control-h

All other keystrokes are treated as a command to insert the given character and move right (with line wrapping).

gather()

This method returns the window contents as a string; whether blanks in the window are included is affected by the `stripspaces` member.

stripspaces

This data member is a flag which controls the interpretation of blanks in the window. When it is on, trailing blanks on each line are ignored; any cursor motion that would land the cursor on a trailing blank goes to the end of that line instead, and trailing blanks are stripped when the window contents are gathered.

14.9 `curses.wrapper` — Terminal handler for curses programs

New in version 1.6.

This module supplies one function, `wrapper()`, which runs another function which should be the rest of your curses-using application. If the application raises an exception, `wrapper()` will restore the terminal to a sane state before re-raising the exception and generating a traceback.

wrapper(func, ...)

Wrapper function that initializes curses and calls another function, *func*, restoring normal keyboard/screen behavior on error. The callable object *func* is then passed the main window 'stdscr' as its first argument, followed by any other arguments passed to `wrapper()`.

Before calling the hook function, `wrapper()` turns on cbreak mode, turns off echo, enables the terminal keypad, and initializes colors if the terminal has color support. On exit (whether normally or by exception) it restores cooked mode, turns on echo, and disables the terminal keypad.

14.10 `curses.ascii` — Utilities for ASCII characters

New in version 1.6.

The `curses.ascii` module supplies name constants for ASCII characters and functions to test membership in various ASCII character classes. The constants supplied are names for control characters as follows:

Name	Meaning
NUL	
SOH	Start of heading, console interrupt
STX	Start of text
ETX	End of text
EOT	End of transmission
ENQ	Enquiry, goes with ACK flow control
ACK	Acknowledgement
BEL	Bell
BS	Backspace
TAB	Tab
HT	Alias for TAB: “Horizontal tab”
LF	Line feed
NL	Alias for LF: “New line”
VT	Vertical tab
FF	Form feed
CR	Carriage return
SO	Shift-out, begin alternate character set
SI	Shift-in, resume default character set
DLE	Data-link escape
DC1	XON, for flow control
DC2	Device control 2, block-mode flow control
DC3	XOFF, for flow control
DC4	Device control 4
NAK	Negative acknowledgement
SYN	Synchronous idle
ETB	End transmission block
CAN	Cancel
EM	End of medium
SUB	Substitute
ESC	Escape
FS	File separator
GS	Group separator
RS	Record separator, block-mode terminator
US	Unit separator
SP	Space
DEL	Delete

Note that many of these have little practical significance in modern usage. The mnemonics derive from teleprinter conventions that predate digital computers.

The module supplies the following functions, patterned on those in the standard C library:

isalnum(c)

Checks for an ASCII alphanumeric character; it is equivalent to `'isalpha(c) or isdigit(c)'`.

isalpha(c)

Checks for an ASCII alphabetic character; it is equivalent to `'isupper(c) or islower(c)'`.

isascii(c)

Checks for a character value that fits in the 7-bit ASCII set.

isblank(c)

Checks for an ASCII whitespace character.

isctrl (*c*)

Checks for an ASCII control character (in the range 0x00 to 0x1f).

isdigit (*c*)

Checks for an ASCII decimal digit, '0' through '9'. This is equivalent to '*c* in string.digits'.

isgraph (*c*)

Checks for ASCII any printable character except space.

islower (*c*)

Checks for an ASCII lower-case character.

isprint (*c*)

Checks for any ASCII printable character including space.

ispunct (*c*)

Checks for any printable ASCII character which is not a space or an alphanumeric character.

isspace (*c*)

Checks for ASCII white-space characters; space, line feed, carriage return, form feed, horizontal tab, vertical tab.

isupper (*c*)

Checks for an ASCII uppercase letter.

isxdigit (*c*)

Checks for an ASCII hexadecimal digit. This is equivalent to '*c* in string.hexdigits'.

isctrl (*c*)

Checks for an ASCII control character (ordinal values 0 to 31).

ismeta (*c*)

Checks for a non-ASCII character (ordinal values 0x80 and above).

These functions accept either integers or strings; when the argument is a string, it is first converted using the built-in function `ord()`.

Note that all these functions check ordinal bit values derived from the first character of the string you pass in; they do not actually know anything about the host machine's character encoding. For functions that know about the character encoding (and handle internationalization properly) see the [string](#) module.

The following two functions take either a single-character string or integer byte value; they return a value of the same type.

ascii (*c*)

Return the ASCII value corresponding to the low 7 bits of *c*.

ctrl (*c*)

Return the control character corresponding to the given character (the character bit value is bitwise-anded with 0x1f).

alt (*c*)

Return the 8-bit character corresponding to the given ASCII character (the character bit value is bitwise-ored with 0x80).

The following function takes either a single-character string or integer value; it returns a string.

unctrl (*c*)

Return a string representation of the ASCII character *c*. If *c* is printable, this string is the character itself. If the character is a control character (0x00-0x1f) the string consists of a caret (^) followed by the corresponding uppercase letter. If the character is an ASCII delete (0x7f) the string is '^?'. If the character has its meta bit (0x80) set, the meta bit is stripped, the preceding rules applied, and '^!' prepended to the result.

controlnames

A 33-element string array that contains the ASCII mnemonics for the thirty-two ASCII control characters from 0 (NUL) to 0x1f (US), in order, plus the mnemonic 'SP' for the space character.

14.11 `curses.panel` — A panel stack extension for curses.

Panels are windows with the added feature of depth, so they can be stacked on top of each other, and only the visible portions of each window will be displayed. Panels can be added, moved up or down in the stack, and removed.

14.11.1 Functions

The module `curses.panel` defines the following functions:

`bottom_panel()`

Returns the bottom panel in the panel stack.

`new_panel(win)`

Returns a panel object, associating it with the given window *win*. Be aware that you need to keep the returned panel object referenced explicitly. If you don't, the panel object is garbage collected and removed from the panel stack.

`top_panel()`

Returns the top panel in the panel stack.

`update_panels()`

Updates the virtual screen after changes in the panel stack. This does not call `curses.doupdate()`, so you'll have to do this yourself.

14.11.2 Panel Objects

Panel objects, as returned by `new_panel()` above, are windows with a stacking order. There's always a window associated with a panel which determines the content, while the panel methods are responsible for the window's depth in the panel stack.

Panel objects have the following methods:

`above()`

Returns the panel above the current panel.

`below()`

Returns the panel below the current panel.

`bottom()`

Push the panel to the bottom of the stack.

`hidden()`

Returns true if the panel is hidden (not visible), false otherwise.

`hide()`

Hide the panel. This does not delete the object, it just makes the window on screen invisible.

`move(y, x)`

Move the panel to the screen coordinates *(y, x)*.

`replace(win)`

Change the window associated with the panel to the window *win*.

`set_userptr(obj)`

Set the panel's user pointer to *obj*. This is used to associate an arbitrary piece of data with the panel, and can be any Python object.

show()

Display the panel (which might have been hidden).

top()

Push panel to the top of the stack.

userptr()

Returns the user pointer for the panel. This might be any Python object.

window()

Returns the window object associated with the panel.

14.12 platform — Access to underlying platform's identifying data.

New in version 2.3.

Note: Specific platforms listed alphabetically, with Linux included in the UNIX section.

14.12.1 Cross Platform

architecture (*executable=sys.executable, bits="", linkage=""*)

Queries the given executable (defaults to the Python interpreter binary) for various architecture information.

Returns a tuple (*bits*, *linkage*) which contain information about the bit architecture and the linkage format used for the executable. Both values are returned as strings.

Values that cannot be determined are returned as given by the parameter presets. If *bits* is given as *''*, the `sizeof(pointer)` (or `sizeof(long)` on Python version $\geq 1.5.2$) is used as indicator for the supported pointer size.

The function relies on the system's 'file' command to do the actual work. This is available on most if not all UNIX platforms and some non-UNIX platforms and then only if the executable points to the Python interpreter. Reasonable defaults are used when the above needs are not met.

machine()

Returns the machine type, e.g. *'i386'*. An empty string is returned if the value cannot be determined.

node()

Returns the computer's network name (may not be fully qualified!). An empty string is returned if the value cannot be determined.

platform (*aliased=0, terse=0*)

Returns a single string identifying the underlying platform with as much useful information as possible.

The output is intended to be *human readable* rather than machine parseable. It may look different on different platforms and this is intended.

If *aliased* is true, the function will use aliases for various platforms that report system names which differ from their common names, for example SunOS will be reported as Solaris. The `system_alias()` function is used to implement this.

Setting *terse* to true causes the function to return only the absolute minimum information needed to identify the platform.

processor()

Returns the (real) processor name, e.g. *'amd64'*.

An empty string is returned if the value cannot be determined. Note that many platforms do not provide this information or simply return the same value as for `machine()`. NetBSD does this.

python_build()

Returns a tuple (*buildno*, *builddate*) stating the Python build number and date as strings.

python_compiler()

Returns a string identifying the compiler used for compiling Python.

python_version()

Returns the Python version as string '*major.minor.patchlevel*'

Note that unlike the Python `sys.version`, the returned value will always include the patchlevel (it defaults to 0).

python_version_tuple()

Returns the Python version as tuple (*major*, *minor*, *patchlevel*) of strings.

Note that unlike the Python `sys.version`, the returned value will always include the patchlevel (it defaults to '0').

release()

Returns the system's release, e.g. '*2.2.0*' or '*NT*'. An empty string is returned if the value cannot be determined.

system()

Returns the system/OS name, e.g. '*Linux*', '*Windows*', or '*Java*'. An empty string is returned if the value cannot be determined.

system_alias(*system*, *release*, *version*)

Returns (*system*, *release*, *version*) aliased to common marketing names used for some systems. It also does some reordering of the information in some cases where it would otherwise cause confusion.

version()

Returns the system's release version, e.g. '*#3 on degas*'. An empty string is returned if the value cannot be determined.

uname()

Fairly portable uname interface. Returns a tuple of strings (*system*, *node*, *release*, *version*, *machine*, *processor*) identifying the underlying platform.

Note that unlike the `os.uname()` function this also returns possible processor information as additional tuple entry.

Entries which cannot be determined are set to ''.

14.12.2 Java Platform

java_ver(*release*="", *vendor*="", *vminfo*=("", ""), *osinfo*=("", ""))

Version interface for JPython.

Returns a tuple (*release*, *vendor*, *vminfo*, *osinfo*) with *vminfo* being a tuple (*vm_name*, *vm_release*, *vm_vendor*) and *osinfo* being a tuple (*os_name*, *os_version*, *os_arch*). Values which cannot be determined are set to the defaults given as parameters (which all default to '').

14.12.3 Windows Platform

win32_ver(*release*="", *version*="", *csd*="", *ptype*="")

Get additional version information from the Windows Registry and return a tuple (*version*, *csd*, *ptype*) referring to version number, CSD level and OS type (multi/single processor).

As a hint: *ptype* is '*Uniprocessor Free*' on single processor NT machines and '*Multiprocessor Free*' on multi processor machines. The '*Free*' refers to the OS version being free of debugging code. It could

also state *'Checked'* which means the OS version uses debugging code, i.e. code that checks arguments, ranges, etc.

Note: This function only works if Mark Hammond's `win32all` package is installed and (obviously) only runs on Win32 compatible platforms.

Win95/98 specific

popen (*cmd*, *mode*='r', *bufsize*=None)

Portable `popen()` interface. Find a working `popen` implementation preferring `win32pipe.popen()`. On Windows NT, `win32pipe.popen()` should work; on Windows 9x it hangs due to bugs in the MS C library.

14.12.4 Mac OS Platform

mac_ver (*release*="", *versioninfo*=","), *machine*="")

Get Mac OS version information and return it as tuple (*release*, *versioninfo*, *machine*) with *versioninfo* being a tuple (*version*, *dev_stage*, *non_release_version*).

Entries which cannot be determined are set to ''. All tuple entries are strings.

Documentation for the underlying `gestalt()` API is available online at <http://www.rgaros.nl/gestalt/>.

14.12.5 UNIX Platforms

dist (*distname*="", *version*="", *id*="", *supported_dists*=('SuSE','debian','redhat','mandrake'))

Tries to determine the name of the OS distribution name Returns a tuple (*distname*, *version*, *id*) which defaults to the args given as parameters.

libc_ver (*executable*=`sys.executable`, *lib*="", *version*="", *chunksize*=2048)

Tries to determine the libc version against which the file *executable* (defaults to the Python interpreter) is linked. Returns a tuple of strings (*lib*, *version*) which default to the given parameters in case the lookup fails.

Note that this function has intimate knowledge of how different libc versions add symbols to the executable is probably only useable for executables compiled using **gcc**.

The file is read and scanned in chunks of *chunksize* bytes.

14.13 `errno` — Standard `errno` system symbols

This module makes available standard `errno` system symbols. The value of each symbol is the corresponding integer value. The names and descriptions are borrowed from `'linux/include/errno.h'`, which should be pretty all-inclusive.

errorcode

Dictionary providing a mapping from the `errno` value to the string name in the underlying system. For instance, `errno.errorcode[errno.EPERM]` maps to `'EPERM'`.

To translate a numeric error code to an error message, use `os.strerror()`.

Of the following list, symbols that are not used on the current platform are not defined by the module. The specific list of defined symbols is available as `errno.errorcode.keys()`. Symbols available can include:

EPERM

Operation not permitted

ENOENT

No such file or directory

ESRCH
No such process

EINTR
Interrupted system call

EIO
I/O error

ENXIO
No such device or address

E2BIG
Arg list too long

ENOEXEC
Exec format error

EBADF
Bad file number

ECHILD
No child processes

EAGAIN
Try again

ENOMEM
Out of memory

EACCES
Permission denied

EFAULT
Bad address

ENOTBLK
Block device required

EBUSY
Device or resource busy

EEXIST
File exists

EXDEV
Cross-device link

ENODEV
No such device

ENOTDIR
Not a directory

EISDIR
Is a directory

EINVAL
Invalid argument

ENFILE
File table overflow

EMFILE
Too many open files

ENOTTY
Not a typewriter

ETXTBSY
Text file busy

EFBIG
File too large

ENOSPC
No space left on device

ESPIPE
Illegal seek

EROFS
Read-only file system

EMLINK
Too many links

EPIPE
Broken pipe

EDOM
Math argument out of domain of func

ERANGE
Math result not representable

EDEADLK
Resource deadlock would occur

ENAMETOOLONG
File name too long

ENOLCK
No record locks available

ENOSYS
Function not implemented

ENOTEMPTY
Directory not empty

ELOOP
Too many symbolic links encountered

EWouldBlock
Operation would block

ENOMSG
No message of desired type

EIDRM
Identifier removed

ECHRNG
Channel number out of range

EL2NSYNC
Level 2 not synchronized

EL3HLT
Level 3 halted

EL3RST
Level 3 reset

ELNRNG
Link number out of range

EUNATCH
Protocol driver not attached

ENOC SI
No CSI structure available

EL2HLT
Level 2 halted

EBADE
Invalid exchange

EBADR
Invalid request descriptor

EXFULL
Exchange full

ENOANO
No anode

EBADRQC
Invalid request code

EBADSLT
Invalid slot

EDEADLOCK
File locking deadlock error

EBFONT
Bad font file format

ENOSTR
Device not a stream

ENODATA
No data available

ETIME
Timer expired

ENOSR
Out of streams resources

ENONET
Machine is not on the network

ENOPKG
Package not installed

EREMOTE
Object is remote

ENOLINK
Link has been severed

EADV
Advertise error

ESRMNT
Srmount error

ECOMM
Communication error on send

EPROTO
Protocol error

EMULTIHOP
Multihop attempted

EDOTDOT
RFS specific error

EBADMSG
Not a data message

EOVERFLOW
Value too large for defined data type

ENOTUNIQ
Name not unique on network

EBADFD
File descriptor in bad state

EREMCHG
Remote address changed

ELIBACC
Can not access a needed shared library

ELIBBAD
Accessing a corrupted shared library

ELIBSCN
.lib section in a.out corrupted

ELIBMAX
Attempting to link in too many shared libraries

ELIBEXEC
Cannot exec a shared library directly

EILSEQ
Illegal byte sequence

ERESTART
Interrupted system call should be restarted

ESTRPIPE
Streams pipe error

EUSERS
Too many users

ENOTSOCK
Socket operation on non-socket

EDESTADDRREQ
Destination address required

EMSGSIZE
Message too long

EPROTOTYPE
Protocol wrong type for socket

ENOPROTOOPT
Protocol not available

EPROTONOSUPPORT
Protocol not supported

ESOCKTNOSUPPORT
Socket type not supported

EOPNOTSUPP
Operation not supported on transport endpoint

EPFNOSUPPORT
Protocol family not supported

EAFNOSUPPORT
Address family not supported by protocol

EADDRINUSE
Address already in use

EADDRNOTAVAIL
Cannot assign requested address

ENETDOWN
Network is down

ENETUNREACH
Network is unreachable

ENETRESET
Network dropped connection because of reset

ECONNABORTED
Software caused connection abort

ECONNRESET
Connection reset by peer

ENOBUFS
No buffer space available

EISCONN
Transport endpoint is already connected

ENOTCONN
Transport endpoint is not connected

ESHUTDOWN
Cannot send after transport endpoint shutdown

ETOOMANYREFS
Too many references: cannot splice

ETIMEDOUT
Connection timed out

ECONNREFUSED
Connection refused

EHOSTDOWN
Host is down

EHOSTUNREACH

No route to host

EALREADY

Operation already in progress

EINPROGRESS

Operation now in progress

ESTALE

Stale NFS file handle

EUCLEAN

Structure needs cleaning

ENOTNAM

Not a XENIX named type file

ENAVAIL

No XENIX semaphores available

EISNAM

Is a named type file

EREMOTEIO

Remote I/O error

EDQUOT

Quota exceeded

14.14 `ctypes` — A foreign function library for Python.

New in version 2.5.

`ctypes` is a foreign function library for Python. It provides C compatible data types, and allows to call functions in dlls/shared libraries. It can be used to wrap these libraries in pure Python.

14.14.1 `ctypes` tutorial

Note: The code samples in this tutorial uses `doctest` to make sure that they actually work. Since some code samples behave differently under Linux, Windows, or Mac OS X, they contain `doctest` directives in comments.

Note: Quite some code samples references the `ctypes c_int` type. This type is an alias to the `c_long` type on 32-bit systems. So, you should not be confused if `c_long` is printed if you would expect `c_int` - they are actually the same type.

Loading dynamic link libraries

`ctypes` exports the `cdll`, and on Windows also `windll` and `oledll` objects to load dynamic link libraries.

You load libraries by accessing them as attributes of these objects. `cdll` loads libraries which export functions using the standard `cdecl` calling convention, while `windll` libraries call functions using the `stdcall` calling convention. `oledll` also uses the `stdcall` calling convention, and assumes the functions return a Windows `HRESULT` error code. The error code is used to automatically raise `WindowsError` Python exceptions when the function call fails.

Here are some examples for Windows, note that `msvcrt` is the MS standard C library containing most standard C functions, and uses the `cdecl` calling convention:


```
>>> from ctypes import *
>>> print windll.kernel32 # doctest: +WINDOWS
<WinDLL 'kernel32', handle ... at ...>
>>> print cdll.msvcrt # doctest: +WINDOWS
<CDLL 'msvcrt', handle ... at ...>
>>> libc = cdll.msvcrt # doctest: +WINDOWS
>>>
```

Windows appends the usual '.dll' file suffix automatically.

On Linux, it is required to specify the filename *including* the extension to load a library, so attribute access does not work. Either the `LoadLibrary` method of the dll loaders should be used, or you should load the library by creating an instance of `CDLL` by calling the constructor:

```
>>> cdll.LoadLibrary("libc.so.6") # doctest: +LINUX
<CDLL 'libc.so.6', handle ... at ...>
>>> libc = CDLL("libc.so.6") # doctest: +LINUX
>>> libc # doctest: +LINUX
<CDLL 'libc.so.6', handle ... at ...>
>>>
```

Accessing functions from loaded dlls

Functions are accessed as attributes of dll objects:

```
>>> from ctypes import *
>>> libc.printf
<_FuncPtr object at 0x...>
>>> print windll.kernel32.GetModuleHandleA # doctest: +WINDOWS
<_FuncPtr object at 0x...>
>>> print windll.kernel32.MyOwnFunction # doctest: +WINDOWS
Traceback (most recent call last):
  File "<stdin>", line 1, in ?
  File "ctypes.py", line 239, in __getattr__
    func = _StdcallFuncPtr(name, self)
AttributeError: function 'MyOwnFunction' not found
>>>
```

Note that win32 system dlls like `kernel32` and `user32` often export ANSI as well as UNICODE versions of a function. The UNICODE version is exported with an `W` appended to the name, while the ANSI version is exported with an `A` appended to the name. The win32 `GetModuleHandle` function, which returns a *module handle* for a given module name, has the following C prototype, and a macro is used to expose one of them as `GetModuleHandle` depending on whether `UNICODE` is defined or not:

```
/* ANSI version */
HMODULE GetModuleHandleA(LPCSTR lpModuleName);
/* UNICODE version */
HMODULE GetModuleHandleW(LPCWSTR lpModuleName);
```

`windll` does not try to select one of them by magic, you must access the version you need by specifying

`GetModuleHandleA` or `GetModuleHandleW` explicitly, and then call it with normal strings or unicode strings respectively.

Sometimes, dlls export functions with names which aren't valid Python identifiers, like "??2@YAPAXI@Z". In this case you have to use `getattr` to retrieve the function:

```
>>> getattr(cdll.msvcrt, "??2@YAPAXI@Z") # doctest: +WINDOWS
<_FuncPtr object at 0x...>
>>>
```

On Windows, some dlls export functions not by name but by ordinal. These functions can be accessed by indexing the dll object with the ordinal number:

```
>>> cdll.kernel32[1] # doctest: +WINDOWS
<_FuncPtr object at 0x...>
>>> cdll.kernel32[0] # doctest: +WINDOWS
Traceback (most recent call last):
  File "<stdin>", line 1, in ?
  File "ctypes.py", line 310, in __getitem__
    func = _StdcallFuncPtr(name, self)
AttributeError: function ordinal 0 not found
>>>
```

Calling functions

You can call these functions like any other Python callable. This example uses the `time()` function, which returns system time in seconds since the UNIX epoch, and the `GetModuleHandleA()` function, which returns a win32 module handle.

This example calls both functions with a NULL pointer (`None` should be used as the NULL pointer):

```
>>> print libc.time(None) # doctest: +SKIP
1150640792
>>> print hex(windll.kernel32.GetModuleHandleA(None)) # doctest: +WINDOWS
0x1d000000
>>>
```

`ctypes` tries to protect you from calling functions with the wrong number of arguments or the wrong calling convention. Unfortunately this only works on Windows. It does this by examining the stack after the function returns, so although an error is raised the function *has* been called:

```
>>> windll.kernel32.GetModuleHandleA() # doctest: +WINDOWS
Traceback (most recent call last):
  File "<stdin>", line 1, in ?
ValueError: Procedure probably called with not enough arguments (4 bytes missing)
>>> windll.kernel32.GetModuleHandleA(0, 0) # doctest: +WINDOWS
Traceback (most recent call last):
  File "<stdin>", line 1, in ?
ValueError: Procedure probably called with too many arguments (4 bytes in excess)
>>>
```

The same exception is raised when you call an `stdcall` function with the `cdecl` calling convention, or vice versa:

```
>>> cdll.kernel32.GetModuleHandleA(None) # doctest: +WINDOWS
Traceback (most recent call last):
  File "<stdin>", line 1, in ?
ValueError: Procedure probably called with not enough arguments (4 bytes missing)
>>>

>>> windll.msvcrt.printf("spam") # doctest: +WINDOWS
Traceback (most recent call last):
  File "<stdin>", line 1, in ?
ValueError: Procedure probably called with too many arguments (4 bytes in excess)
>>>
```

To find out the correct calling convention you have to look into the C header file or the documentation for the function you want to call.

On Windows, `ctypes` uses win32 structured exception handling to prevent crashes from general protection faults when functions are called with invalid argument values:

```
>>> windll.kernel32.GetModuleHandleA(32) # doctest: +WINDOWS
Traceback (most recent call last):
  File "<stdin>", line 1, in ?
WindowsError: exception: access violation reading 0x00000020
>>>
```

There are, however, enough ways to crash Python with `ctypes`, so you should be careful anyway.

None, integers, longs, byte strings and unicode strings are the only native Python objects that can directly be used as parameters in these function calls. None is passed as a C `NULL` pointer, byte strings and unicode strings are passed as pointer to the memory block that contains their data (`char *` or `wchar_t *`). Python integers and Python longs are passed as the platforms default C `int` type, their value is masked to fit into the C type.

Before we move on calling functions with other parameter types, we have to learn more about `ctypes` data types.

Fundamental data types

`ctypes` defines a number of primitive C compatible data types :

ctypes type	C type	Python type
c_char	char	1-character string
c_wchar	wchar_t	1-character unicode string
c_byte	char	int/long
c_ubyte	unsigned char	int/long
c_short	short	int/long
c_ushort	unsigned short	int/long
c_int	int	int/long
c_uint	unsigned int	int/long
c_long	long	int/long
c_ulong	unsigned long	int/long
c_longlong	__int64 or long long	int/long
c_ulonglong	unsigned __int64 or unsigned long long	int/long
c_float	float	float
c_double	double	float
c_char_p	char * (NUL terminated)	string or None
c_wchar_p	wchar_t * (NUL terminated)	unicode or None
c_void_p	void *	int/long or None

All these types can be created by calling them with an optional initializer of the correct type and value:

```
>>> c_int()
c_long(0)
>>> c_char_p("Hello, World")
c_char_p('Hello, World')
>>> c_ushort(-3)
c_ushort(65533)
>>>
```

Since these types are mutable, their value can also be changed afterwards:

```
>>> i = c_int(42)
>>> print i
c_long(42)
>>> print i.value
42
>>> i.value = -99
>>> print i.value
-99
>>>
```

Assigning a new value to instances of the pointer types `c_char_p`, `c_wchar_p`, and `c_void_p` changes the *memory location* they point to, *not the contents* of the memory block (of course not, because Python strings are immutable):

```

>>> s = "Hello, World"
>>> c_s = c_char_p(s)
>>> print c_s
c_char_p('Hello, World')
>>> c_s.value = "Hi, there"
>>> print c_s
c_char_p('Hi, there')
>>> print s                                # first string is unchanged
Hello, World
>>>

```

You should be careful, however, not to pass them to functions expecting pointers to mutable memory. If you need mutable memory blocks, `ctypes` has a `create_string_buffer` function which creates these in various ways. The current memory block contents can be accessed (or changed) with the `raw` property; if you want to access it as NUL terminated string, use the `value` property:

```

>>> from ctypes import *
>>> p = create_string_buffer(3)          # create a 3 byte buffer, initialized to NUL bytes
>>> print sizeof(p), repr(p.raw)
3 '\x00\x00\x00'
>>> p = create_string_buffer("Hello")    # create a buffer containing a NUL terminated string
>>> print sizeof(p), repr(p.raw)
6 'Hello\x00'
>>> print repr(p.value)
'Hello'
>>> p = create_string_buffer("Hello", 10) # create a 10 byte buffer
>>> print sizeof(p), repr(p.raw)
10 'Hello\x00\x00\x00\x00\x00'
>>> p.value = "Hi"
>>> print sizeof(p), repr(p.raw)
10 'Hi\x00l0\x00\x00\x00\x00\x00'
>>>

```

The `create_string_buffer` function replaces the `c_buffer` function (which is still available as an alias), as well as the `c_string` function from earlier `ctypes` releases. To create a mutable memory block containing unicode characters of the C type `wchar_t` use the `create_unicode_buffer` function.

Calling functions, continued

Note that `printf` prints to the real standard output channel, *not* to `sys.stdout`, so these examples will only work at the console prompt, not from within *IDLE* or *PythonWin*:

```

>>> printf = libc.printf
>>> printf("Hello, %s\n", "World!")
Hello, World!
14
>>> printf("Hello, %S", u"World!")
Hello, World!
13
>>> printf("%d bottles of beer\n", 42)
42 bottles of beer
19
>>> printf("%f bottles of beer\n", 42.5)
Traceback (most recent call last):
  File "<stdin>", line 1, in ?
ArgumentError: argument 2: exceptions.TypeError: Don't know how to convert parameter 2
>>>

```

As has been mentioned before, all Python types except integers, strings, and unicode strings have to be wrapped in their corresponding `ctypes` type, so that they can be converted to the required C data type:

```

>>> printf("An int %d, a double %f\n", 1234, c_double(3.14))
Integer 1234, double 3.1400001049
31
>>>

```

Calling functions with your own custom data types

You can also customize `ctypes` argument conversion to allow instances of your own classes be used as function arguments. `ctypes` looks for an `_as_parameter_` attribute and uses this as the function argument. Of course, it must be one of integer, string, or unicode:

```

>>> class Bottles(object):
...     def __init__(self, number):
...         self._as_parameter_ = number
...
>>> bottles = Bottles(42)
>>> printf("%d bottles of beer\n", bottles)
42 bottles of beer
19
>>>

```

If you don't want to store the instance's data in the `_as_parameter_` instance variable, you could define a property which makes the data available.

Specifying the required argument types (function prototypes)

It is possible to specify the required argument types of functions exported from DLLs by setting the `argtypes` attribute.

`argtypes` must be a sequence of C data types (the `printf` function is probably not a good example here, because it takes a variable number and different types of parameters depending on the format string, on the other hand this is quite handy to experiment with this feature):

```
>>> printf.argtypes = [c_char_p, c_char_p, c_int, c_double]
>>> printf("String '%s', Int %d, Double %f\n", "Hi", 10, 2.2)
String 'Hi', Int 10, Double 2.200000
37
>>>
```

Specifying a format protects against incompatible argument types (just as a prototype for a C function), and tries to convert the arguments to valid types:

```
>>> printf("%d %d %d", 1, 2, 3)
Traceback (most recent call last):
  File "<stdin>", line 1, in ?
ArgumentError: argument 2: exceptions.TypeError: wrong type
>>> printf("%s %d %f", "X", 2, 3)
X 2 3.00000012
12
>>>
```

If you have defined your own classes which you pass to function calls, you have to implement a `from_param` class method for them to be able to use them in the `argtypes` sequence. The `from_param` class method receives the Python object passed to the function call, it should do a typecheck or whatever is needed to make sure this object is acceptable, and then return the object itself, its `_as_parameter_` attribute, or whatever you want to pass as the C function argument in this case. Again, the result should be an integer, string, unicode, a `ctypes` instance, or something having the `_as_parameter_` attribute.

Return types

By default functions are assumed to return the C `int` type. Other return types can be specified by setting the `restype` attribute of the function object.

Here is a more advanced example, it uses the `strchr` function, which expects a string pointer and a char, and returns a pointer to a string:

```
>>> strchr = libc.strchr
>>> strchr("abcdef", ord("d")) # doctest: +SKIP
8059983
>>> strchr.restype = c_char_p # c_char_p is a pointer to a string
>>> strchr("abcdef", ord("d"))
'def'
>>> print strchr("abcdef", ord("x"))
None
>>>
```

If you want to avoid the `ord("x")` calls above, you can set the `argtypes` attribute, and the second argument will be converted from a single character Python string into a C char:

```

>>> strchr.restype = c_char_p
>>> strchr.argtypes = [c_char_p, c_char]
>>> strchr("abcdef", "d")
'def'
>>> strchr("abcdef", "def")
Traceback (most recent call last):
  File "<stdin>", line 1, in ?
ArgumentError: argument 2: exceptions.TypeError: one character string expected
>>> print strchr("abcdef", "x")
None
>>> strchr("abcdef", "d")
'def'
>>>

```

You can also use a callable Python object (a function or a class for example) as the `restype` attribute, if the foreign function returns an integer. The callable will be called with the integer the C function returns, and the result of this call will be used as the result of your function call. This is useful to check for error return values and automatically raise an exception:

```

>>> GetModuleHandle = windll.kernel32.GetModuleHandleA # doctest: +WINDOWS
>>> def ValidHandle(value):
...     if value == 0:
...         raise WinError()
...     return value
...
>>>
>>> GetModuleHandle.restype = ValidHandle # doctest: +WINDOWS
>>> GetModuleHandle(None) # doctest: +WINDOWS
486539264
>>> GetModuleHandle("something silly") # doctest: +WINDOWS
Traceback (most recent call last):
  File "<stdin>", line 1, in ?
  File "<stdin>", line 3, in ValidHandle
WindowsError: [Errno 126] The specified module could not be found.
>>>

```

`WinError` is a function which will call `Windows.FormatMessage()` api to get the string representation of an error code, and *returns* an exception. `WinError` takes an optional error code parameter, if no one is used, it calls `GetLastError()` to retrieve it.

Please note that a much more powerful error checking mechanism is available through the `errcheck` attribute; see the reference manual for details.

Passing pointers (or: passing parameters by reference)

Sometimes a C api function expects a *pointer* to a data type as parameter, probably to write into the corresponding location, or if the data is too large to be passed by value. This is also known as *passing parameters by reference*.

`ctypes` exports the `byref` function which is used to pass parameters by reference. The same effect can be achieved with the `pointer` function, although `pointer` does a lot more work since it constructs a real pointer object, so it is faster to use `byref` if you don't need the pointer object in Python itself:


```

>>> i = c_int()
>>> f = c_float()
>>> s = create_string_buffer('\000' * 32)
>>> print i.value, f.value, repr(s.value)
0 0.0 ''
>>> libc sscanf("1 3.14 Hello", "%d %f %s",
...             byref(i), byref(f), s)
3
>>> print i.value, f.value, repr(s.value)
1 3.1400001049 'Hello'
>>>

```

Structures and unions

Structures and unions must derive from the `Structure` and `Union` base classes which are defined in the `ctypes` module. Each subclass must define a `_fields_` attribute. `_fields_` must be a list of 2-tuples, containing a *field name* and a *field type*.

The field type must be a `ctypes` type like `c_int`, or any other derived `ctypes` type: `structure`, `union`, `array`, `pointer`.

Here is a simple example of a `POINT` structure, which contains two integers named `x` and `y`, and also shows how to initialize a structure in the constructor:

```

>>> from ctypes import *
>>> class POINT(Structure):
...     _fields_ = [("x", c_int),
...                 ("y", c_int)]
...
>>> point = POINT(10, 20)
>>> print point.x, point.y
10 20
>>> point = POINT(y=5)
>>> print point.x, point.y
0 5
>>> POINT(1, 2, 3)
Traceback (most recent call last):
  File "<stdin>", line 1, in ?
ValueError: too many initializers
>>>

```

You can, however, build much more complicated structures. Structures can itself contain other structures by using a structure as a field type.

Here is a `RECT` structure which contains two `POINT`s named `upperleft` and `lowerright`

```

>>> class RECT(Structure):
...     _fields_ = [("upperleft", POINT),
...                 ("lowerright", POINT)]
...
>>> rc = RECT(point)
>>> print rc.upperleft.x, rc.upperleft.y
0 5
>>> print rc.lowerright.x, rc.lowerright.y
0 0
>>>

```

Nested structures can also be initialized in the constructor in several ways:

```

>>> r = RECT(POINT(1, 2), POINT(3, 4))
>>> r = RECT((1, 2), (3, 4))

```

Fields descriptors can be retrieved from the *class*, they are useful for debugging because they can provide useful information:

```

>>> print POINT.x
<Field type=c_long, ofs=0, size=4>
>>> print POINT.y
<Field type=c_long, ofs=4, size=4>
>>>

```

Structure/union alignment and byte order

By default, Structure and Union fields are aligned in the same way the C compiler does it. It is possible to override this behaviour by specifying a `_pack_` class attribute in the subclass definition. This must be set to a positive integer and specifies the maximum alignment for the fields. This is what `#pragma pack(n)` also does in MSVC.

`ctypes` uses the native byte order for Structures and Unions. To build structures with non-native byte order, you can use one of the `BigEndianStructure`, `LittleEndianStructure`, `BigEndianUnion`, and `LittleEndianUnion` base classes. These classes cannot contain pointer fields.

Bit fields in structures and unions

It is possible to create structures and unions containing bit fields. Bit fields are only possible for integer fields, the bit width is specified as the third item in the `_fields_` tuples:

```

>>> class Int(Structure):
...     _fields_ = [("first_16", c_int, 16),
...                 ("second_16", c_int, 16)]
...
>>> print Int.first_16
<Field type=c_long, ofs=0:0, bits=16>
>>> print Int.second_16
<Field type=c_long, ofs=0:16, bits=16>
>>>

```

Arrays

Arrays are sequences, containing a fixed number of instances of the same type.

The recommended way to create array types is by multiplying a data type with a positive integer:

```
TenPointsArrayType = POINT * 10
```

Here is an example of an somewhat artificial data type, a structure containing 4 POINTs among other stuff:

```

>>> from ctypes import *
>>> class POINT(Structure):
...     _fields_ = ("x", c_int), ("y", c_int)
...
>>> class MyStruct(Structure):
...     _fields_ = [("a", c_int),
...                 ("b", c_float),
...                 ("point_array", POINT * 4)]
>>>
>>> print len(MyStruct().point_array)
4
>>>

```

Instances are created in the usual way, by calling the class:

```

arr = TenPointsArrayType()
for pt in arr:
    print pt.x, pt.y

```

The above code print a series of 0 0 lines, because the array contents is initialized to zeros.

Initializers of the correct type can also be specified:

```

>>> from ctypes import *
>>> TenIntegers = c_int * 10
>>> ii = TenIntegers(1, 2, 3, 4, 5, 6, 7, 8, 9, 10)
>>> print ii
<c_long_Array_10 object at 0x...>
>>> for i in ii: print i,
...
1 2 3 4 5 6 7 8 9 10
>>>

```

Pointers

Pointer instances are created by calling the `pointer` function on a `ctypes` type:

```

>>> from ctypes import *
>>> i = c_int(42)
>>> pi = pointer(i)
>>>

```

Pointer instances have a `contents` attribute which returns the object to which the pointer points, the `i` object above:

```

>>> pi.contents
c_long(42)
>>>

```

Note that `ctypes` does not have OOR (original object return), it constructs a new, equivalent object each time you retrieve an attribute:

```

>>> pi.contents is i
False
>>> pi.contents is pi.contents
False
>>>

```

Assigning another `c_int` instance to the pointer's `contents` attribute would cause the pointer to point to the memory location where this is stored:

```

>>> i = c_int(99)
>>> pi.contents = i
>>> pi.contents
c_long(99)
>>>

```

Pointer instances can also be indexed with integers:

```
>>> pi[0]
99
>>>
```

Assigning to an integer index changes the pointed to value:

```
>>> print i
c_long(99)
>>> pi[0] = 22
>>> print i
c_long(22)
>>>
```

It is also possible to use indexes different from 0, but you must know what you're doing, just as in C: You can access or change arbitrary memory locations. Generally you only use this feature if you receive a pointer from a C function, and you *know* that the pointer actually points to an array instead of a single item.

Behind the scenes, the `pointer` function does more than simply create pointer instances, it has to create pointer *types* first. This is done with the `POINTER` function, which accepts any `ctypes` type, and returns a new type:

```
>>> PI = POINTER(c_int)
>>> PI
<class 'ctypes.LP_c_long'>
>>> PI(42)
Traceback (most recent call last):
  File "<stdin>", line 1, in ?
TypeError: expected c_long instead of int
>>> PI(c_int(42))
<ctypes.LP_c_long object at 0x...>
>>>
```

Calling the pointer type without an argument creates a `NULL` pointer. `NULL` pointers have a `False` boolean value:

```
>>> null_ptr = POINTER(c_int)()
>>> print bool(null_ptr)
False
>>>
```

`ctypes` checks for `NULL` when dereferencing pointers (but dereferencing non-`NULL` pointers would crash Python):

```

>>> null_ptr[0]
Traceback (most recent call last):
....
ValueError: NULL pointer access
>>>

>>> null_ptr[0] = 1234
Traceback (most recent call last):
....
ValueError: NULL pointer access
>>>

```

Type conversions

Usually, ctypes does strict type checking. This means, if you have `POINTER(c_int)` in the `argtypes` list of a function or as the type of a member field in a structure definition, only instances of exactly the same type are accepted. There are some exceptions to this rule, where ctypes accepts other objects. For example, you can pass compatible array instances instead of pointer types. So, for `POINTER(c_int)`, ctypes accepts an array of `c_int`:

```

>>> class Bar(Structure):
...     _fields_ = [("count", c_int), ("values", POINTER(c_int))]
...
>>> bar = Bar()
>>> bar.values = (c_int * 3)(1, 2, 3)
>>> bar.count = 3
>>> for i in range(bar.count):
...     print bar.values[i]
...
1
2
3
>>>

```

To set a `POINTER` type field to `NULL`, you can assign `None`:

```

>>> bar.values = None
>>>

```

XXX list other conversions...

Sometimes you have instances of incompatible types. In C, you can cast one type into another type. ctypes provides a `cast` function which can be used in the same way. The `Bar` structure defined above accepts `POINTER(c_int)` pointers or `c_int` arrays for its `values` field, but not instances of other types:

```

>>> bar.values = (c_byte * 4)()
Traceback (most recent call last):
  File "<stdin>", line 1, in ?
TypeError: incompatible types, c_byte_Array_4 instance instead of LP_c_long instance
>>>

```

For these cases, the `cast` function is handy.

The `cast` function can be used to cast a ctypes instance into a pointer to a different ctypes data type. `cast` takes two parameters, a ctypes object that is or can be converted to a pointer of some kind, and a ctypes pointer type. It returns an instance of the second argument, which references the same memory block as the first argument:

```
>>> a = (c_byte * 4)()
>>> cast(a, POINTER(c_int))
<ctypes.LP_c_long object at ...>
>>>
```

So, `cast` can be used to assign to the `values` field of `Bar` the structure:

```
>>> bar = Bar()
>>> bar.values = cast((c_byte * 4)(), POINTER(c_int))
>>> print bar.values[0]
0
>>>
```

Incomplete Types

Incomplete Types are structures, unions or arrays whose members are not yet specified. In C, they are specified by forward declarations, which are defined later:

```
struct cell; /* forward declaration */

struct {
    char *name;
    struct cell *next;
} cell;
```

The straightforward translation into ctypes code would be this, but it does not work:

```
>>> class cell(Structure):
...     _fields_ = [("name", c_char_p),
...                 ("next", POINTER(cell))]
...
Traceback (most recent call last):
  File "<stdin>", line 1, in ?
  File "<stdin>", line 2, in cell
NameError: name 'cell' is not defined
>>>
```

because the new class `cell` is not available in the class statement itself. In ctypes, we can define the `cell` class and set the `_fields_` attribute later, after the class statement:

```

>>> from ctypes import *
>>> class cell(Structure):
...     pass
...
>>> cell._fields_ = [("name", c_char_p),
...                  ("next", POINTER(cell))]
>>>

```

Lets try it. We create two instances of `cell`, and let them point to each other, and finally follow the pointer chain a few times:

```

>>> c1 = cell()
>>> c1.name = "foo"
>>> c2 = cell()
>>> c2.name = "bar"
>>> c1.next = pointer(c2)
>>> c2.next = pointer(c1)
>>> p = c1
>>> for i in range(8):
...     print p.name,
...     p = p.next[0]
...
foo bar foo bar foo bar foo bar
>>>

```

Callback functions

`ctypes` allows to create C callable function pointers from Python callables. These are sometimes called *callback functions*.

First, you must create a class for the callback function, the class knows the calling convention, the return type, and the number and types of arguments this function will receive.

The `CFUNCTYPE` factory function creates types for callback functions using the normal `cdecl` calling convention, and, on Windows, the `WINFUNCTYPE` factory function creates types for callback functions using the `stdcall` calling convention.

Both of these factory functions are called with the result type as first argument, and the callback functions expected argument types as the remaining arguments.

I will present an example here which uses the standard C library's `qsort` function, this is used to sort items with the help of a callback function. `qsort` will be used to sort an array of integers:

```

>>> IntArray5 = c_int * 5
>>> ia = IntArray5(5, 1, 7, 33, 99)
>>> qsort = libc.qsort
>>> qsort.restype = None
>>>

```

`qsort` must be called with a pointer to the data to sort, the number of items in the data array, the size of one item, and a pointer to the comparison function, the callback. The callback will then be called with two pointers to items, and it must return a negative integer if the first item is smaller than the second, a zero if they are equal, and a positive integer else.

So our callback function receives pointers to integers, and must return an integer. First we create the `type` for the callback function:

```
>>> CMPFUNC = CFUNCTYPE(c_int, POINTER(c_int), POINTER(c_int))
>>>
```

For the first implementation of the callback function, we simply print the arguments we get, and return 0 (incremental development ;-):

```
>>> def py_cmp_func(a, b):
...     print "py_cmp_func", a, b
...     return 0
...
>>>
```

Create the C callable callback:

```
>>> cmp_func = CMPFUNC(py_cmp_func)
>>>
```

And we're ready to go:

```
>>> qsort(ia, len(ia), sizeof(c_int), cmp_func) # doctest: +WINDOWS
py_cmp_func <ctypes.LP_c_long object at 0x00...> <ctypes.LP_c_long object at 0x00...>
py_cmp_func <ctypes.LP_c_long object at 0x00...> <ctypes.LP_c_long object at 0x00...>
py_cmp_func <ctypes.LP_c_long object at 0x00...> <ctypes.LP_c_long object at 0x00...>
py_cmp_func <ctypes.LP_c_long object at 0x00...> <ctypes.LP_c_long object at 0x00...>
py_cmp_func <ctypes.LP_c_long object at 0x00...> <ctypes.LP_c_long object at 0x00...>
py_cmp_func <ctypes.LP_c_long object at 0x00...> <ctypes.LP_c_long object at 0x00...>
py_cmp_func <ctypes.LP_c_long object at 0x00...> <ctypes.LP_c_long object at 0x00...>
py_cmp_func <ctypes.LP_c_long object at 0x00...> <ctypes.LP_c_long object at 0x00...>
py_cmp_func <ctypes.LP_c_long object at 0x00...> <ctypes.LP_c_long object at 0x00...>
py_cmp_func <ctypes.LP_c_long object at 0x00...> <ctypes.LP_c_long object at 0x00...>
>>>
```

We know how to access the contents of a pointer, so let's redefine our callback:

```
>>> def py_cmp_func(a, b):
...     print "py_cmp_func", a[0], b[0]
...     return 0
...
>>> cmp_func = CMPFUNC(py_cmp_func)
>>>
```

Here is what we get on Windows:

```
>>> qsort(ia, len(ia), sizeof(c_int), cmp_func) # doctest: +WINDOWS
py_cmp_func 7 1
py_cmp_func 33 1
py_cmp_func 99 1
py_cmp_func 5 1
py_cmp_func 7 5
py_cmp_func 33 5
py_cmp_func 99 5
py_cmp_func 7 99
py_cmp_func 33 99
py_cmp_func 7 33
>>>
```

It is funny to see that on linux the sort function seems to work much more efficient, it is doing less comparisons:

```
>>> qsort(ia, len(ia), sizeof(c_int), cmp_func) # doctest: +LINUX
py_cmp_func 5 1
py_cmp_func 33 99
py_cmp_func 7 33
py_cmp_func 5 7
py_cmp_func 1 7
>>>
```

Ah, we're nearly done! The last step is to actually compare the two items and return a useful result:

```
>>> def py_cmp_func(a, b):
...     print "py_cmp_func", a[0], b[0]
...     return a[0] - b[0]
...
>>>
```

Final run on Windows:

```
>>> qsort(ia, len(ia), sizeof(c_int), CMPFUNC(py_cmp_func)) # doctest: +WINDOWS
py_cmp_func 33 7
py_cmp_func 99 33
py_cmp_func 5 99
py_cmp_func 1 99
py_cmp_func 33 7
py_cmp_func 1 33
py_cmp_func 5 33
py_cmp_func 5 7
py_cmp_func 1 7
py_cmp_func 5 1
>>>
```

and on Linux:

```
>>> qsort(ia, len(ia), sizeof(c_int), CMPFUNC(py_cmp_func)) # doctest: +LINUX
py_cmp_func 5 1
py_cmp_func 33 99
py_cmp_func 7 33
py_cmp_func 1 7
py_cmp_func 5 7
>>>
```

It is quite interesting to see that the Windows `qsort` function needs more comparisons than the linux version!

As we can easily check, our array is sorted now:

```
>>> for i in ia: print i,
...
1 5 7 33 99
>>>
```

Important note for callback functions:

Make sure you keep references to `CFUNCTYPE` objects as long as they are used from C code. `ctypes` doesn't, and if you don't, they may be garbage collected, crashing your program when a callback is made.

Accessing values exported from dlls

Sometimes, a dll not only exports functions, it also exports variables. An example in the Python library itself is the `Py_OptimizeFlag`, an integer set to 0, 1, or 2, depending on the `-O` or `-OO` flag given on startup.

`ctypes` can access values like this with the `in_dll` class methods of the type. `pythonapi` is a predefined symbol giving access to the Python C api:

```
>>> opt_flag = c_int.in_dll(pythonapi, "Py_OptimizeFlag")
>>> print opt_flag
c_long(0)
>>>
```

If the interpreter would have been started with `-O`, the sample would have printed `c_long(1)`, or `c_long(2)` if `-OO` would have been specified.

An extended example which also demonstrates the use of pointers accesses the `PyImport_FrozenModules` pointer exported by Python.

Quoting the Python docs: *This pointer is initialized to point to an array of “struct frozen” records, terminated by one whose members are all NULL or zero. When a frozen module is imported, it is searched in this table. Third-party code could play tricks with this to provide a dynamically created collection of frozen modules.*

So manipulating this pointer could even prove useful. To restrict the example size, we show only how this table can be read with `ctypes`:

```

>>> from ctypes import *
>>>
>>> class struct_frozen(Structure):
...     _fields_ = [("name", c_char_p),
...                  ("code", POINTER(c_ubyte)),
...                  ("size", c_int)]
...
>>>

```

We have defined the struct `_frozen` data type, so we can get the pointer to the table:

```

>>> FrozenTable = POINTER(struct_frozen)
>>> table = FrozenTable.in_dll(pythonapi, "PyImport_FrozenModules")
>>>

```

Since `table` is a pointer to the array of `struct_frozen` records, we can iterate over it, but we just have to make sure that our loop terminates, because pointers have no size. Sooner or later it would probably crash with an access violation or whatever, so it's better to break out of the loop when we hit the NULL entry:

```

>>> for item in table:
...     print item.name, item.size
...     if item.name is None:
...         break
...
__hello__ 104
__phello__ -104
__phello__.spam 104
None 0
>>>

```

The fact that standard Python has a frozen module and a frozen package (indicated by the negative size member) is not wellknown, it is only used for testing. Try it out with `import __hello__` for example.

Surprises

There are some edges in `ctypes` where you may expect something else than what actually happens.

Consider the following example:

```

>>> from ctypes import *
>>> class POINT(Structure):
...     _fields_ = ("x", c_int), ("y", c_int)
...
>>> class RECT(Structure):
...     _fields_ = ("a", POINT), ("b", POINT)
...
>>> p1 = POINT(1, 2)
>>> p2 = POINT(3, 4)
>>> rc = RECT(p1, p2)
>>> print rc.a.x, rc.a.y, rc.b.x, rc.b.y
1 2 3 4
>>> # now swap the two points
>>> rc.a, rc.b = rc.b, rc.a
>>> print rc.a.x, rc.a.y, rc.b.x, rc.b.y
3 4 3 4
>>>

```

Hm. We certainly expected the last statement to print 3 4 1 2. What happened? Here are the steps of the `rc.a, rc.b = rc.b, rc.a` line above:

```

>>> temp0, temp1 = rc.b, rc.a
>>> rc.a = temp0
>>> rc.b = temp1
>>>

```

Note that `temp0` and `temp1` are objects still using the internal buffer of the `rc` object above. So executing `rc.a = temp0` copies the buffer contents of `temp0` into `rc`'s buffer. This, in turn, changes the contents of `temp1`. So, the last assignment `rc.b = temp1`, doesn't have the expected effect.

Keep in mind that retrieving subobjects from Structure, Unions, and Arrays doesn't *copy* the subobject, instead it retrieves a wrapper object accessing the root-object's underlying buffer.

Another example that may behave different from what one would expect is this:

```

>>> s = c_char_p()
>>> s.value = "abc def ghi"
>>> s.value
'abc def ghi'
>>> s.value is s.value
False
>>>

```

Why is it printing `False`? `ctypes` instances are objects containing a memory block plus some descriptors accessing the contents of the memory. Storing a Python object in the memory block does not store the object itself, instead the contents of the object is stored. Accessing the contents again constructs a new Python each time!

Variable-sized data types

`ctypes` provides some support for variable-sized arrays and structures (this was added in version 0.9.9.7).

The `resize` function can be used to resize the memory buffer of an existing `ctypes` object. The function takes the object as first argument, and the requested size in bytes as the second argument. The memory block cannot be made

smaller than the natural memory block specified by the objects type, a `ValueError` is raised if this is tried:

```
>>> short_array = (c_short * 4) ()
>>> print sizeof(short_array)
8
>>> resize(short_array, 4)
Traceback (most recent call last):
...
ValueError: minimum size is 8
>>> resize(short_array, 32)
>>> sizeof(short_array)
32
>>> sizeof(type(short_array))
8
>>>
```

This is nice and fine, but how would one access the additional elements contained in this array? Since the type still only knows about 4 elements, we get errors accessing other elements:

```
>>> short_array[:]
[0, 0, 0, 0]
>>> short_array[7]
Traceback (most recent call last):
...
IndexError: invalid index
>>>
```

Another way to use variable-sized data types with `ctypes` is to use the dynamic nature of Python, and (re-)define the data type after the required size is already known, on a case by case basis.

Bugs, ToDo and non-implemented things

Enumeration types are not implemented. You can do it easily yourself, using `c_int` as the base class.

`long double` is not implemented.

14.14.2 ctypes reference

Finding shared libraries

When programming in a compiled language, shared libraries are accessed when compiling/linking a program, and when the program is run.

The purpose of the `find_library` function is to locate a library in a way similar to what the compiler does (on platforms with several versions of a shared library the most recent should be loaded), while the `ctypes` library loaders act like when a program is run, and call the runtime loader directly.

The `ctypes.util` module provides a function which can help to determine the library to load.

find_library(name)

Try to find a library and return a pathname. *name* is the library name without any prefix like *lib*, suffix like *.so*, *.dylib* or version number (this is the form used for the posix linker option **-l**). If no library can be found, returns `None`.

The exact functionality is system dependend.

On Linux, `find_library` tries to run external programs (`/sbin/ldconfig`, `gcc`, and `objdump`) to find the library file. It returns the filename of the library file. Here are some examples:

```
>>> from ctypes.util import find_library
>>> find_library("m")
'libm.so.6'
>>> find_library("c")
'libc.so.6'
>>> find_library("bz2")
'libbz2.so.1.0'
>>>
```

On OS X, `find_library` tries several predefined naming schemes and paths to locate the library, and returns a full pathname if successful:

```
>>> from ctypes.util import find_library
>>> find_library("c")
'/usr/lib/libc.dylib'
>>> find_library("m")
'/usr/lib/libm.dylib'
>>> find_library("bz2")
'/usr/lib/libbz2.dylib'
>>> find_library("AGL")
'/System/Library/Frameworks/AGL.framework/AGL'
>>>
```

On Windows, `find_library` searches along the system search path, and returns the full pathname, but since there is no predefined naming scheme a call like `find_library("c")` will fail and return `None`.

If wrapping a shared library with `ctypes`, it *may* be better to determine the shared library name at development type, and hardcode that into the wrapper module instead of using `find_library` to locate the library at runtime.

Loading shared libraries

There are several ways to loaded shared libraries into the Python process. One way is to instantiate one of the following classes:

class `CDLL` (*name*, *mode=DEFAULT_MODE*, *handle=None*)

Instances of this class represent loaded shared libraries. Functions in these libraries use the standard C calling convention, and are assumed to return `int`.

class `OleDLL` (*name*, *mode=DEFAULT_MODE*, *handle=None*)

Windows only: Instances of this class represent loaded shared libraries, functions in these libraries use the `stdcall` calling convention, and are assumed to return the windows specific `HRESULT` code. `HRESULT` values contain information specifying whether the function call failed or succeeded, together with additional error code. If the return value signals a failure, an `WindowsError` is automatically raised.

class `WinDLL` (*name*, *mode=DEFAULT_MODE*, *handle=None*)

Windows only: Instances of this class represent loaded shared libraries, functions in these libraries use the `stdcall` calling convention, and are assumed to return `int` by default.

On Windows CE only the standard calling convention is used, for convenience the `WinDLL` and `OleDLL` use the standard calling convention on this platform.

The Python GIL is released before calling any function exported by these libraries, and required afterwards.

class PyDLL (*name, mode=DEFAULT_MODE, handle=None*)

Instances of this class behave like CDLL instances, except that the Python GIL is *not* released during the function call, and after the function execution the Python error flag is checked. If the error flag is set, a Python exception is raised.

Thus, this is only useful to call Python C api functions directly.

All these classes can be instantiated by calling them with at least one argument, the pathname of the shared library. If you have an existing handle to an already loaded shared library, it can be passed as the *handle* named parameter, otherwise the underlying platforms *dlopen* or *LoadLibrary* function is used to load the library into the process, and to get a handle to it.

The *mode* parameter can be used to specify how the library is loaded. For details, consult the *dlopen(3)* manpage, on Windows, *mode* is ignored.

RTLD_GLOBAL

Flag to use as *mode* parameter. On platforms where this flag is not available, it is defined as the integer zero.

RTLD_LOCAL

Flag to use as *mode* parameter. On platforms where this is not available, it is the same as *RTLD_GLOBAL*.

DEFAULT_MODE

The default mode which is used to load shared libraries. On OSX 10.3, this is *RTLD_GLOBAL*, otherwise it is the same as *RTLD_LOCAL*.

Instances of these classes have no public methods, however `__getattr__` and `__getitem__` have special behaviour: functions exported by the shared library can be accessed as attributes of by index. Please note that both `__getattr__` and `__getitem__` cache their result, so calling them repeatedly returns the same object each time.

The following public attributes are available, their name starts with an underscore to not clash with exported function names:

`__handle`

The system handle used to access the library.

`__name`

The name of the library passed in the constructor.

Shared libraries can also be loaded by using one of the prefabricated objects, which are instances of the *LibraryLoader* class, either by calling the *LoadLibrary* method, or by retrieving the library as attribute of the loader instance.

class LibraryLoader (*dlltype*)

Class which loads shared libraries. *dlltype* should be one of the CDLL, PyDLL, WinDLL, or OleDLL types.

`__getattr__` has special behaviour: It allows to load a shared library by accessing it as attribute of a library loader instance. The result is cached, so repeated attribute accesses return the same library each time.

LoadLibrary (*name*)

Load a shared library into the process and return it. This method always returns a new instance of the library.

These prefabricated library loaders are available:

cdll

Creates CDLL instances.

windll

Windows only: Creates WinDLL instances.

oledll

Windows only: Creates OleDLL instances.

pydll

Creates PyDLL instances.

For accessing the C Python api directly, a ready-to-use Python shared library object is available:

pythonapi

An instance of PyDLL that exposes Python C api functions as attributes. Note that all these functions are assumed to return C `int`, which is of course not always the truth, so you have to assign the correct `restype` attribute to use these functions.

Foreign functions

As explained in the previous section, foreign functions can be accessed as attributes of loaded shared libraries. The function objects created in this way by default accept any number of arguments, accept any ctypes data instances as arguments, and return the default result type specified by the library loader. They are instances of a private class:

class _FuncPtr

Base class for C callable foreign functions.

Instances of foreign functions are also C compatible data types; they represent C function pointers.

This behaviour can be customized by assigning to special attributes of the foreign function object.

restype

Assign a ctypes type to specify the result type of the foreign function. Use `None` for void a function not returning anything.

It is possible to assign a callable Python object that is not a ctypes type, in this case the function is assumed to return a C `int`, and the callable will be called with this integer, allowing to do further processing or error checking. Using this is deprecated, for more flexible postprocessing or error checking use a ctypes data type as `restype` and assign a callable to the `errcheck` attribute.

argtypes

Assign a tuple of ctypes types to specify the argument types that the function accepts. Functions using the `stdcall` calling convention can only be called with the same number of arguments as the length of this tuple; functions using the C calling convention accept additional, unspecified arguments as well.

When a foreign function is called, each actual argument is passed to the `from_param` class method of the items in the `argtypes` tuple, this method allows to adapt the actual argument to an object that the foreign function accepts. For example, a `c_char_p` item in the `argtypes` tuple will convert a unicode string passed as argument into an byte string using ctypes conversion rules.

New: It is now possible to put items in `argtypes` which are not ctypes types, but each item must have a `from_param` method which returns a value usable as argument (integer, string, ctypes instance). This allows to define adapters that can adapt custom objects as function parameters.

errcheck

Assign a Python function or another callable to this attribute. The callable will be called with three or more arguments:

callable (*result, func, arguments*)

result is what the foreign function returns, as specified by the `restype` attribute.

func is the foreign function object itself, this allows to reuse the same callable object to check or postprocess the results of several functions.

arguments is a tuple containing the parameters originally passed to the function call, this allows to specialize the behaviour on the arguments used.

The object that this function returns will be returned from the foreign function call, but it can also check the result value and raise an exception if the foreign function call failed.

exception ArgumentError()

This exception is raised when a foreign function call cannot convert one of the passed arguments.

Function prototypes

Foreign functions can also be created by instantiating function prototypes. Function prototypes are similar to function prototypes in C; they describe a function (return type, argument types, calling convention) without defining an implementation. The factory functions must be called with the desired result type and the argument types of the function.

CFUNCTYPE (*restype*, **argtypes*)

The returned function prototype creates functions that use the standard C calling convention. The function will release the GIL during the call.

WINFUNCTYPE (*restype*, **argtypes*)

Windows only: The returned function prototype creates functions that use the `stdcall` calling convention, except on Windows CE where `WINFUNCTYPE` is the same as `CFUNCTYPE`. The function will release the GIL during the call.

PYFUNCTYPE (*restype*, **argtypes*)

The returned function prototype creates functions that use the Python calling convention. The function will *not* release the GIL during the call.

Function prototypes created by the factory functions can be instantiated in different ways, depending on the type and number of the parameters in the call.

prototype (*address*)

Returns a foreign function at the specified address.

prototype (*callable*)

Create a C callable function (a callback function) from a Python `callable`.

prototype (*func_spec*[, *paramflags*])

Returns a foreign function exported by a shared library. `func_spec` must be a 2-tuple (`name_or_ordinal`, `library`). The first item is the name of the exported function as string, or the ordinal of the exported function as small integer. The second item is the shared library instance.

prototype (*vtbl_index*, *name*[, *paramflags*[, *iid*]])

Returns a foreign function that will call a COM method. `vtbl_index` is the index into the virtual function table, a small nonnegative integer. `name` is name of the COM method. `iid` is an optional pointer to the interface identifier which is used in extended error reporting.

COM methods use a special calling convention: They require a pointer to the COM interface as first argument, in addition to those parameters that are specified in the `argtypes` tuple.

The optional `paramflags` parameter creates foreign function wrappers with much more functionality than the features described above.

`paramflags` must be a tuple of the same length as `argtypes`.

Each item in this tuple contains further information about a parameter, it must be a tuple containing 1, 2, or 3 items.

The first item is an integer containing flags for the parameter:

- 1**
Specifies an input parameter to the function.
- 2**
Output parameter. The foreign function fills in a value.
- 4**
Input parameter which defaults to the integer zero.

The optional second item is the parameter name as string. If this is specified, the foreign function can be called with named parameters.

The optional third item is the default value for this parameter.

This example demonstrates how to wrap the Windows `MessageBoxA` function so that it supports default parameters and named arguments. The C declaration from the windows header file is this:

```
WINUSERAPI int WINAPI
MessageBox(
    HWND hWnd ,
    LPCSTR lpText,
    LPCSTR lpCaption,
    UINT uType);
```

Here is the wrapping with `ctypes`:

```
>>> from ctypes import c_int, WINFUNCTYPE, windll
>>> from ctypes.wintypes import HWND, LPCSTR, UINT
>>> prototype = WINFUNCTYPE(c_int, HWND, LPCSTR, LPCSTR, UINT)
>>> paramflags = (1, "hwnd", 0), (1, "text", "Hi"), (1, "caption", None), (1, "flags", 0)
>>> MessageBox = prototype(("MessageBoxA", windll.user32), paramflags)
>>>
```

The `MessageBox` foreign function can now be called in these ways:

```
>>> MessageBox()
>>> MessageBox(text="Spam", spam, spam)
>>> MessageBox(flags=2, text="foo bar")
>>>
```

A second example demonstrates output parameters. The win32 `GetWindowRect` function retrieves the dimensions of a specified window by copying them into `RECT` structure that the caller has to supply. Here is the C declaration:

```
WINUSERAPI BOOL WINAPI
GetWindowRect(
    HWND hWnd,
    LPRECT lpRect);
```

Here is the wrapping with `ctypes`:

```
>>> from ctypes import POINTER, WINFUNCTYPE, windll, WinError
>>> from ctypes.wintypes import BOOL, HWND, RECT
>>> prototype = WINFUNCTYPE(BOOL, HWND, POINTER(RECT))
>>> paramflags = (1, "hwnd"), (2, "lprect")
>>> GetWindowRect = prototype(("GetWindowRect", windll.user32), paramflags)
>>>
```

Functions with output parameters will automatically return the output parameter value if there is a single one, or a tuple containing the output parameter values when there are more than one, so the `GetWindowRect` function now returns a `RECT` instance, when called.

Output parameters can be combined with the `errcheck` protocol to do further output processing and error checking. The win32 `GetWindowRect` api function returns a `BOOL` to signal success or failure, so this function could do the error checking, and raises an exception when the api call failed:

```
>>> def errcheck(result, func, args):
...     if not result:
...         raise WinError()
...     return args
>>> GetWindowRect.errcheck = errcheck
>>>
```

If the `errcheck` function returns the argument tuple it receives unchanged, `ctypes` continues the normal processing it does on the output parameters. If you want to return a tuple of window coordinates instead of a `RECT` instance, you can retrieve the fields in the function and return them instead, the normal processing will no longer take place:

```
>>> def errcheck(result, func, args):
...     if not result:
...         raise WinError()
...     rc = args[1]
...     return rc.left, rc.top, rc.bottom, rc.right
>>>
>>> GetWindowRect.errcheck = errcheck
>>>
```

Utility functions

addressof (*obj*)

Returns the address of the memory buffer as integer. *obj* must be an instance of a `ctypes` type.

alignment (*obj_or_type*)

Returns the alignment requirements of a `ctypes` type. *obj_or_type* must be a `ctypes` type or instance.

byref (*obj*)

Returns a light-weight pointer to *obj*, which must be an instance of a `ctypes` type. The returned object can only be used as a foreign function call parameter. It behaves similar to `pointer(obj)`, but the construction is a lot faster.

cast (*obj, type*)

This function is similar to the cast operator in C. It returns a new instance of *type* which points to the same memory block as *obj*. *type* must be a pointer type, and *obj* must be an object that can be interpreted as a pointer.

create_string_buffer (*init_or_size* [, *size*])

This function creates a mutable character buffer. The returned object is a `ctypes` array of `c_char`.

init_or_size must be an integer which specifies the size of the array, or a string which will be used to initialize the array items.

If a string is specified as first argument, the buffer is made one item larger than the length of the string so that the last element in the array is a NUL termination character. An integer can be passed as second argument which allows to specify the size of the array if the length of the string should not be used.

If the first parameter is a unicode string, it is converted into an 8-bit string according to `ctypes` conversion rules.

create_unicode_buffer (*init_or_size* [, *size*])

This function creates a mutable unicode character buffer. The returned object is a `ctypes` array of `c_wchar`.

init_or_size must be an integer which specifies the size of the array, or a unicode string which will be used to initialize the array items.

If a unicode string is specified as first argument, the buffer is made one item larger than the length of the string so that the last element in the array is a NUL termination character. An integer can be passed as second argument which allows to specify the size of the array if the length of the string should not be used.

If the first parameter is a 8-bit string, it is converted into an unicode string according to ctypes conversion rules.

DllCanUnloadNow()

Windows only: This function is a hook which allows to implement inprocess COM servers with ctypes. It is called from the DllCanUnloadNow function that the _ctypes extension dll exports.

DllGetClassObject()

Windows only: This function is a hook which allows to implement inprocess COM servers with ctypes. It is called from the DllGetClassObject function that the _ctypes extension dll exports.

FormatError([code])

Windows only: Returns a textual description of the error code. If no error code is specified, the last error code is used by calling the Windows api function GetLastError.

GetLastError()

Windows only: Returns the last error code set by Windows in the calling thread.

memmove(dst, src, count)

Same as the standard C memmove library function: copies *count* bytes from *src* to *dst*. *dst* and *src* must be integers or ctypes instances that can be converted to pointers.

memset(dst, c, count)

Same as the standard C memset library function: fills the memory block at address *dst* with *count* bytes of value *c*. *dst* must be an integer specifying an address, or a ctypes instance.

POINTER(type)

This factory function creates and returns a new ctypes pointer type. Pointer types are cached and reused internally, so calling this function repeatedly is cheap. *type* must be a ctypes type.

pointer(obj)

This function creates a new pointer instance, pointing to *obj*. The returned object is of the type `POINTER(type(obj))`.

Note: If you just want to pass a pointer to an object to a foreign function call, you should use `byref(obj)` which is much faster.

resize(obj, size)

This function resizes the internal memory buffer of *obj*, which must be an instance of a ctypes type. It is not possible to make the buffer smaller than the native size of the objects type, as given by `sizeof(type(obj))`, but it is possible to enlarge the buffer.

set_conversion_mode(encoding, errors)

This function sets the rules that ctypes objects use when converting between 8-bit strings and unicode strings. *encoding* must be a string specifying an encoding, like 'utf-8' or 'mbcs', *errors* must be a string specifying the error handling on encoding/decoding errors. Examples of possible values are "strict", "replace", or "ignore".

`set_conversion_mode` returns a 2-tuple containing the previous conversion rules. On windows, the initial conversion rules are ('mbcs', 'ignore'), on other systems ('ascii', 'strict').

sizeof(obj_or_type)

Returns the size in bytes of a ctypes type or instance memory buffer. Does the same as the C `sizeof()` function.

string_at(address[, size])

This function returns the string starting at memory address *address*. If *size* is specified, it is used as size, otherwise the string is assumed to be zero-terminated.

WinError(code=None, descr=None)

Windows only: this function is probably the worst-named thing in ctypes. It creates an instance of `WindowsError`. If *code* is not specified, `GetLastError` is called to determine the error code. If *descr* is not specified, `FormatError` is called to get a textual description of the error.

wstring_at (*address*)

This function returns the wide character string starting at memory address *address* as unicode string. If *size* is specified, it is used as the number of characters of the string, otherwise the string is assumed to be zero-terminated.

Data types

class _CData

This non-public class is the common base class of all ctypes data types. Among other things, all ctypes type instances contain a memory block that hold C compatible data; the address of the memory block is returned by the `addressof()` helper function. Another instance variable is exposed as `_objects`; this contains other Python objects that need to be kept alive in case the memory block contains pointers.

Common methods of ctypes data types, these are all class methods (to be exact, they are methods of the metaclass):

from_address (*address*)

This method returns a ctypes type instance using the memory specified by *address* which must be an integer.

from_param (*obj*)

This method adapts *obj* to a ctypes type. It is called with the actual object used in a foreign function call, when the type is present in the foreign functions `argtypes` tuple; it must return an object that can be used as function call parameter.

All ctypes data types have a default implementation of this classmethod, normally it returns *obj* if that is an instance of the type. Some types accept other objects as well.

in_dll (*library*, *name*)

This method returns a ctypes type instance exported by a shared library. *name* is the name of the symbol that exports the data, *library* is the loaded shared library.

Common instance variables of ctypes data types:

_b_base_

Sometimes ctypes data instances do not own the memory block they contain, instead they share part of the memory block of a base object. The `_b_base_` readonly member is the root ctypes object that owns the memory block.

_b_needsfree_

This readonly variable is true when the ctypes data instance has allocated the memory block itself, false otherwise.

_objects

This member is either `None` or a dictionary containing Python objects that need to be kept alive so that the memory block contents is kept valid. This object is only exposed for debugging; never modify the contents of this dictionary.

Fundamental data types

class _SimpleCData

This non-public class is the base class of all fundamental ctypes data types. It is mentioned here because it contains the common attributes of the fundamental ctypes data types. `_SimpleCData` is a subclass of `_CData`, so it inherits their methods and attributes.

Instances have a single attribute:

value

This attribute contains the actual value of the instance. For integer and pointer types, it is an integer, for character types, it is a single character string, for character pointer types it is a Python string or unicode string.

When the `value` attribute is retrieved from a `ctypes` instance, usually a new object is returned each time. `ctypes` does *not* implement original object return, always a new object is constructed. The same is true for all other `ctypes` object instances.

Fundamental data types, when returned as foreign function call results, or, for example, by retrieving structure field members or array items, are transparently converted to native Python types. In other words, if a foreign function has a `restype` of `c_char_p`, you will always receive a Python string, *not* a `c_char_p` instance.

Subclasses of fundamental data types do *not* inherit this behaviour. So, if a foreign functions `restype` is a subclass of `c_void_p`, you will receive an instance of this subclass from the function call. Of course, you can get the value of the pointer by accessing the `value` attribute.

These are the fundamental `ctypes` data types:

class `c_byte`

Represents the C signed char datatype, and interprets the value as small integer. The constructor accepts an optional integer initializer; no overflow checking is done.

class `c_char`

Represents the C char datatype, and interprets the value as a single character. The constructor accepts an optional string initializer, the length of the string must be exactly one character.

class `c_char_p`

Represents the C char * datatype, which must be a pointer to a zero-terminated string. The constructor accepts an integer address, or a string.

class `c_double`

Represents the C double datatype. The constructor accepts an optional float initializer.

class `c_float`

Represents the C float datatype. The constructor accepts an optional float initializer.

class `c_int`

Represents the C signed int datatype. The constructor accepts an optional integer initializer; no overflow checking is done. On platforms where `sizeof(int) == sizeof(long)` it is an alias to `c_long`.

class `c_int8`

Represents the C 8-bit signed int datatype. Usually an alias for `c_byte`.

class `c_int16`

Represents the C 16-bit signed int datatype. Usually an alias for `c_short`.

class `c_int32`

Represents the C 32-bit signed int datatype. Usually an alias for `c_int`.

class `c_int64`

Represents the C 64-bit signed int datatype. Usually an alias for `c_longlong`.

class `c_long`

Represents the C signed long datatype. The constructor accepts an optional integer initializer; no overflow checking is done.

class `c_longlong`

Represents the C signed long long datatype. The constructor accepts an optional integer initializer; no overflow checking is done.

class `c_short`

Represents the C signed short datatype. The constructor accepts an optional integer initializer; no overflow checking is done.

class `c_size_t`
Represents the C `size_t` datatype.

class `c_ubyte`
Represents the C `unsigned char` datatype, it interprets the value as small integer. The constructor accepts an optional integer initializer; no overflow checking is done.

class `c_uint`
Represents the C `unsigned int` datatype. The constructor accepts an optional integer initializer; no overflow checking is done. On platforms where `sizeof(int) == sizeof(long)` it is an alias for `c_ulong`.

class `c_uint8`
Represents the C 8-bit unsigned int datatype. Usually an alias for `c_ubyte`.

class `c_uint16`
Represents the C 16-bit unsigned int datatype. Usually an alias for `c_ushort`.

class `c_uint32`
Represents the C 32-bit unsigned int datatype. Usually an alias for `c_uint`.

class `c_uint64`
Represents the C 64-bit unsigned int datatype. Usually an alias for `c_ulonglong`.

class `c_ulong`
Represents the C `unsigned long` datatype. The constructor accepts an optional integer initializer; no overflow checking is done.

class `c_ulonglong`
Represents the C `unsigned long long` datatype. The constructor accepts an optional integer initializer; no overflow checking is done.

class `c_ushort`
Represents the C `unsigned short` datatype. The constructor accepts an optional integer initializer; no overflow checking is done.

class `c_void_p`
Represents the C `void *` type. The value is represented as integer. The constructor accepts an optional integer initializer.

class `c_wchar`
Represents the C `wchar_t` datatype, and interprets the value as a single character unicode string. The constructor accepts an optional string initializer, the length of the string must be exactly one character.

class `c_wchar_p`
Represents the C `wchar_t *` datatype, which must be a pointer to a zero-terminated wide character string. The constructor accepts an integer address, or a string.

class `HRESULT`
Windows only: Represents a `HRESULT` value, which contains success or error information for a function or method call.

class `py_object`
Represents the C `PyObject *` datatype. Calling this without an argument creates a `NULL PyObject *` pointer.

The `ctypes.wintypes` module provides quite some other Windows specific data types, for example `HWND`, `WPARAM`, or `DWORD`. Some useful structures like `MSG` or `RECT` are also defined.

Structured data types

class Union (*args, **kw)

Abstract base class for unions in native byte order.

class BigEndianStructure (*args, **kw)

Abstract base class for structures in *big endian* byte order.

class LittleEndianStructure (*args, **kw)

Abstract base class for structures in *little endian* byte order.

Structures with non-native byte order cannot contain pointer type fields, or any other data types containing pointer type fields.

class Structure (*args, **kw)

Abstract base class for structures in *native* byte order.

Concrete structure and union types must be created by subclassing one of these types, and at least define a `__fields__` class variable. `ctypes` will create descriptors which allow reading and writing the fields by direct attribute accesses. These are the

`__fields__`

A sequence defining the structure fields. The items must be 2-tuples or 3-tuples. The first item is the name of the field, the second item specifies the type of the field; it can be any `ctypes` data type.

For integer type fields like `c_int`, a third optional item can be given. It must be a small positive integer defining the bit width of the field.

Field names must be unique within one structure or union. This is not checked, only one field can be accessed when names are repeated.

It is possible to define the `__fields__` class variable *after* the class statement that defines the Structure subclass, this allows to create data types that directly or indirectly reference themselves:

```
class List(Structure):
    pass
List.__fields__ = [("pNext", POINTER(List)),
                  ...
                  ]
```

The `__fields__` class variable must, however, be defined before the type is first used (an instance is created, `sizeof()` is called on it, and so on). Later assignments to the `__fields__` class variable will raise an `AttributeError`.

Structure and union subclass constructors accept both positional and named arguments. Positional arguments are used to initialize the fields in the same order as they appear in the `__fields__` definition, named arguments are used to initialize the fields with the corresponding name.

It is possible to defined sub-subclasses of structure types, they inherit the fields of the base class plus the `__fields__` defined in the sub-subclass, if any.

`__pack__`

An optional small integer that allows to override the alignment of structure fields in the instance. `__pack__` must already be defined when `__fields__` is assigned, otherwise it will have no effect.

`__anonymous__`

An optional sequence that lists the names of unnamed (anonymous) fields. `__anonymous__` must be already defined when `__fields__` is assigned, otherwise it will have no effect.

The fields listed in this variable must be structure or union type fields. `ctypes` will create descriptors in the structure type that allows to access the nested fields directly, without the need to create the structure or union field.

Here is an example type (Windows):

```
class _U(Union):
    _fields_ = [("lptdesc", POINTER(TYPEDESC)),
                ("lpadesc", POINTER(ARRAYDESC)),
                ("hreftype", HREFTYPE)]

class TYPEDESC(Structure):
    _fields_ = [("u", _U),
                ("vt", VARTYPE)]

    _anonymous_ = ("u",)
```

The TYPEDESC structure describes a COM data type, the vt field specifies which one of the union fields is valid. Since the u field is defined as anonymous field, it is now possible to access the members directly off the TYPEDESC instance. td.lptdesc and td.u.lptdesc are equivalent, but the former is faster since it does not need to create a temporary union instance:

```
td = TYPEDESC()
td.vt = VT_PTR
td.lptdesc = POINTER(some_type)
td.u.lptdesc = POINTER(some_type)
```

It is possible to defined sub-subclasses of structures, they inherit the fields of the base class. If the subclass definition has a separate _fields_ variable, the fields specified in this are appended to the fields of the base class.

Structure and union constructors accept both positional and keyword arguments. Positional arguments are used to initialize member fields in the same order as they appear in _fields_. Keyword arguments in the constructor are interpreted as attribute assignments, so they will initialize _fields_ with the same name, or create new attributes for names not present in _fields_.

Arrays and pointers

Not yet written - please see section 14.14.1, pointers and section 14.14.1, arrays in the tutorial.

Optional Operating System Services

The modules described in this chapter provide interfaces to operating system features that are available on selected operating systems only. The interfaces are generally modeled after the UNIX or C interfaces but they are available on some other systems as well (e.g. Windows or NT). Here's an overview:

<code>select</code>	Wait for I/O completion on multiple streams.
<code>thread</code>	Create multiple threads of control within one interpreter.
<code>threading</code>	Higher-level threading interface.
<code>dummy_thread</code>	Drop-in replacement for the <code>thread</code> module.
<code>dummy_threading</code>	Drop-in replacement for the <code>threading</code> module.
<code>mmap</code>	Interface to memory-mapped files for UNIX and Windows.
<code>readline</code>	GNU readline support for Python.
<code>rlcompleter</code>	Python identifier completion, suitable for the GNU readline library.

15.1 `select` — Waiting for I/O completion

This module provides access to the `select()` and `poll()` functions available in most operating systems. Note that on Windows, it only works for sockets; on other operating systems, it also works for other file types (in particular, on UNIX, it works on pipes). It cannot be used on regular files to determine whether a file has grown since it was last read.

The module defines the following:

exception error

The exception raised when an error occurs. The accompanying value is a pair containing the numeric error code from `errno` and the corresponding string, as would be printed by the C function `perror()`.

`poll()`

(Not supported by all operating systems.) Returns a polling object, which supports registering and unregistering file descriptors, and then polling them for I/O events; see section 15.1.1 below for the methods supported by polling objects.

`select(iwtd, owtd, ewtd[, timeout])`

This is a straightforward interface to the UNIX `select()` system call. The first three arguments are sequences of 'waitable objects': either integers representing file descriptors or objects with a parameterless method named `fileno()` returning such an integer. The three sequences of waitable objects are for input, output and 'exceptional conditions', respectively. Empty sequences are allowed, but acceptance of three empty sequences is platform-dependent. (It is known to work on UNIX but not on Windows.) The optional `timeout` argument specifies a time-out as a floating point number in seconds. When the `timeout` argument is omitted the function blocks until at least one file descriptor is ready. A time-out value of zero specifies a poll and never blocks.

The return value is a triple of lists of objects that are ready: subsets of the first three arguments. When the time-out is reached without a file descriptor becoming ready, three empty lists are returned.

Among the acceptable object types in the sequences are Python file objects (e.g. `sys.stdin`, or objects returned by `open()` or `os.popen()`), socket objects returned by `socket.socket()`. You may also define a *wrapper* class yourself, as long as it has an appropriate `fileno()` method (that really returns a file descriptor, not just a random integer). **Note:** File objects on Windows are not acceptable, but sockets are. On Windows, the underlying `select()` function is provided by the WinSock library, and does not handle file descriptors that don't originate from WinSock.

15.1.1 Polling Objects

The `poll()` system call, supported on most UNIX systems, provides better scalability for network servers that service many, many clients at the same time. `poll()` scales better because the system call only requires listing the file descriptors of interest, while `select()` builds a bitmap, turns on bits for the fds of interest, and then afterward the whole bitmap has to be linearly scanned again. `select()` is $O(\text{highest file descriptor})$, while `poll()` is $O(\text{number of file descriptors})$.

register (*fd* [, *eventmask*])

Register a file descriptor with the polling object. Future calls to the `poll()` method will then check whether the file descriptor has any pending I/O events. *fd* can be either an integer, or an object with a `fileno()` method that returns an integer. File objects implement `fileno()`, so they can also be used as the argument.

eventmask is an optional bitmask describing the type of events you want to check for, and can be a combination of the constants `POLLIN`, `POLLPRI`, and `POLLOUT`, described in the table below. If not specified, the default value used will check for all 3 types of events.

Constant	Meaning
<code>POLLIN</code>	There is data to read
<code>POLLPRI</code>	There is urgent data to read
<code>POLLOUT</code>	Ready for output: writing will not block
<code>POLLERR</code>	Error condition of some sort
<code>POLLHUP</code>	Hung up
<code>POLLNVAL</code>	Invalid request: descriptor not open

Registering a file descriptor that's already registered is not an error, and has the same effect as registering the descriptor exactly once.

unregister (*fd*)

Remove a file descriptor being tracked by a polling object. Just like the `register()` method, *fd* can be an integer or an object with a `fileno()` method that returns an integer.

Attempting to remove a file descriptor that was never registered causes a `KeyError` exception to be raised.

poll ([*timeout*])

Polls the set of registered file descriptors, and returns a possibly-empty list containing (*fd*, *event*) 2-tuples for the descriptors that have events or errors to report. *fd* is the file descriptor, and *event* is a bitmask with bits set for the reported events for that descriptor — `POLLIN` for waiting input, `POLLOUT` to indicate that the descriptor can be written to, and so forth. An empty list indicates that the call timed out and no file descriptors had any events to report. If *timeout* is given, it specifies the length of time in milliseconds which the system will wait for events before returning. If *timeout* is omitted, negative, or `None`, the call will block until there is an event for this poll object.

15.2 thread — Multiple threads of control

This module provides low-level primitives for working with multiple threads (a.k.a. *light-weight processes* or *tasks*) — multiple threads of control sharing their global data space. For synchronization, simple locks (a.k.a. *mutexes* or *binary semaphores*) are provided.

The module is optional. It is supported on Windows, Linux, SGI IRIX, Solaris 2.x, as well as on systems that have a POSIX thread (a.k.a. “pthread”) implementation. For systems lacking the `thread` module, the `dummy_thread` module is available. It duplicates this module’s interface and can be used as a drop-in replacement.

It defines the following constant and functions:

exception error

Raised on thread-specific errors.

LockType

This is the type of lock objects.

start_new_thread (*function*, *args* [, *kwargs*])

Start a new thread and return its identifier. The thread executes the function *function* with the argument list *args* (which must be a tuple). The optional *kwargs* argument specifies a dictionary of keyword arguments. When the function returns, the thread silently exits. When the function terminates with an unhandled exception, a stack trace is printed and then the thread exits (but other threads continue to run).

interrupt_main ()

Raise a `KeyboardInterrupt` exception in the main thread. A subthread can use this function to interrupt the main thread. New in version 2.3.

exit ()

Raise the `SystemExit` exception. When not caught, this will cause the thread to exit silently.

allocate_lock ()

Return a new lock object. Methods of locks are described below. The lock is initially unlocked.

get_ident ()

Return the ‘thread identifier’ of the current thread. This is a nonzero integer. Its value has no direct meaning; it is intended as a magic cookie to be used e.g. to index a dictionary of thread-specific data. Thread identifiers may be recycled when a thread exits and another thread is created.

stack_size ([*size*])

Return the thread stack size used when creating new threads. The optional *size* argument specifies the stack size to be used for subsequently created threads, and must be 0 (use platform or configured default) or a positive integer value of at least 32,768 (32kB). If changing the thread stack size is unsupported, a `ThreadError` is raised. If the specified stack size is invalid, a `ValueError` is raised and the stack size is unmodified. 32kB is currently the minimum supported stack size value to guarantee sufficient stack space for the interpreter itself. Note that some platforms may have particular restrictions on values for the stack size, such as requiring a minimum stack size \geq 32kB or requiring allocation in multiples of the system memory page size - platform documentation should be referred to for more information (4kB pages are common; using multiples of 4096 for the stack size is the suggested approach in the absence of more specific information). Availability: Windows, systems with POSIX threads. New in version 2.5.

Lock objects have the following methods:

acquire ([*waitflag*])

Without the optional argument, this method acquires the lock unconditionally, if necessary waiting until it is released by another thread (only one thread at a time can acquire a lock — that’s their reason for existence). If the integer *waitflag* argument is present, the action depends on its value: if it is zero, the lock is only acquired if it can be acquired immediately without waiting, while if it is nonzero, the lock is acquired unconditionally as before. The return value is `True` if the lock is acquired successfully, `False` if not.

release ()

Releases the lock. The lock must have been acquired earlier, but not necessarily by the same thread.

locked ()

Return the status of the lock: `True` if it has been acquired by some thread, `False` if not.

In addition to these methods, lock objects can also be used via the `with` statement, e.g.:

```

from __future__ import with_statement
import thread

a_lock = thread.allocate_lock()

with a_lock:
    print "a_lock is locked while this executes"

```

Caveats:

- Threads interact strangely with interrupts: the `KeyboardInterrupt` exception will be received by an arbitrary thread. (When the `signal` module is available, interrupts always go to the main thread.)
- Calling `sys.exit()` or raising the `SystemExit` exception is equivalent to calling `exit()`.
- Not all built-in functions that may block waiting for I/O allow other threads to run. (The most popular ones (`time.sleep()`, `file.read()`, `select.select()`) work as expected.)
- It is not possible to interrupt the `acquire()` method on a lock — the `KeyboardInterrupt` exception will happen after the lock has been acquired.
- When the main thread exits, it is system defined whether the other threads survive. On SGI IRIX using the native thread implementation, they survive. On most other systems, they are killed without executing `try ... finally` clauses or executing object destructors.
- When the main thread exits, it does not do any of its usual cleanup (except that `try ... finally` clauses are honored), and the standard I/O files are not flushed.

15.3 threading — Higher-level threading interface

This module constructs higher-level threading interfaces on top of the lower level `thread` module.

The `dummy_threading` module is provided for situations where `threading` cannot be used because `thread` is missing.

This module defines the following functions and objects:

activeCount()

Return the number of `Thread` objects currently alive. The returned count is equal to the length of the list returned by `enumerate()`.

Condition()

A factory function that returns a new condition variable object. A condition variable allows one or more threads to wait until they are notified by another thread.

currentThread()

Return the current `Thread` object, corresponding to the caller's thread of control. If the caller's thread of control was not created through the `threading` module, a dummy thread object with limited functionality is returned.

enumerate()

Return a list of all `Thread` objects currently alive. The list includes daemon threads, dummy thread objects created by `currentThread()`, and the main thread. It excludes terminated threads and threads that have not yet been started.

Event ()

A factory function that returns a new event object. An event manages a flag that can be set to true with the `set ()` method and reset to false with the `clear ()` method. The `wait ()` method blocks until the flag is true.

class local

A class that represents thread-local data. Thread-local data are data whose values are thread specific. To manage thread-local data, just create an instance of `local` (or a subclass) and store attributes on it:

```
mydata = threading.local()
mydata.x = 1
```

The instance's values will be different for separate threads.

For more details and extensive examples, see the documentation string of the `_threading_local` module.

New in version 2.4.

Lock ()

A factory function that returns a new primitive lock object. Once a thread has acquired it, subsequent attempts to acquire it block, until it is released; any thread may release it.

RLock ()

A factory function that returns a new reentrant lock object. A reentrant lock must be released by the thread that acquired it. Once a thread has acquired a reentrant lock, the same thread may acquire it again without blocking; the thread must release it once for each time it has acquired it.

Semaphore ([value])

A factory function that returns a new semaphore object. A semaphore manages a counter representing the number of `release ()` calls minus the number of `acquire ()` calls, plus an initial value. The `acquire ()` method blocks if necessary until it can return without making the counter negative. If not given, *value* defaults to 1.

BoundedSemaphore ([value])

A factory function that returns a new bounded semaphore object. A bounded semaphore checks to make sure its current value doesn't exceed its initial value. If it does, `ValueError` is raised. In most situations semaphores are used to guard resources with limited capacity. If the semaphore is released too many times it's a sign of a bug. If not given, *value* defaults to 1.

class Thread

A class that represents a thread of control. This class can be safely subclassed in a limited fashion.

class Timer

A thread that executes a function after a specified interval has passed.

settrace (func)

Set a trace function for all threads started from the `threading` module. The *func* will be passed to `sys.settrace ()` for each thread, before its `run ()` method is called. New in version 2.3.

setprofile (func)

Set a profile function for all threads started from the `threading` module. The *func* will be passed to `sys.setprofile ()` for each thread, before its `run ()` method is called. New in version 2.3.

stack_size ([size])

Return the thread stack size used when creating new threads. The optional *size* argument specifies the stack size to be used for subsequently created threads, and must be 0 (use platform or configured default) or a positive integer value of at least 32,768 (32kB). If changing the thread stack size is unsupported, a `ThreadError` is raised. If the specified stack size is invalid, a `ValueError` is raised and the stack size is unmodified. 32kB is currently the minimum supported stack size value to guarantee sufficient stack space for the interpreter itself. Note that some platforms may have particular restrictions on values for the stack size, such as requiring a minimum stack size \geq 32kB or requiring allocation in multiples of the system memory page size - platform documentation should be referred to for more information (4kB pages are common; using multiples of 4096 for

the stack size is the suggested approach in the absence of more specific information). Availability: Windows, systems with POSIX threads. New in version 2.5.

Detailed interfaces for the objects are documented below.

The design of this module is loosely based on Java's threading model. However, where Java makes locks and condition variables basic behavior of every object, they are separate objects in Python. Python's `Thread` class supports a subset of the behavior of Java's `Thread` class; currently, there are no priorities, no thread groups, and threads cannot be destroyed, stopped, suspended, resumed, or interrupted. The static methods of Java's `Thread` class, when implemented, are mapped to module-level functions.

All of the methods described below are executed atomically.

15.3.1 Lock Objects

A primitive lock is a synchronization primitive that is not owned by a particular thread when locked. In Python, it is currently the lowest level synchronization primitive available, implemented directly by the `thread` extension module.

A primitive lock is in one of two states, "locked" or "unlocked". It is created in the unlocked state. It has two basic methods, `acquire()` and `release()`. When the state is unlocked, `acquire()` changes the state to locked and returns immediately. When the state is locked, `acquire()` blocks until a call to `release()` in another thread changes it to unlocked, then the `acquire()` call resets it to locked and returns. The `release()` method should only be called in the locked state; it changes the state to unlocked and returns immediately. When more than one thread is blocked in `acquire()` waiting for the state to turn to unlocked, only one thread proceeds when a `release()` call resets the state to unlocked; which one of the waiting threads proceeds is not defined, and may vary across implementations.

All methods are executed atomically.

`acquire([blocking = 1])`

Acquire a lock, blocking or non-blocking.

When invoked without arguments, block until the lock is unlocked, then set it to locked, and return true.

When invoked with the *blocking* argument set to true, do the same thing as when called without arguments, and return true.

When invoked with the *blocking* argument set to false, do not block. If a call without an argument would block, return false immediately; otherwise, do the same thing as when called without arguments, and return true.

`release()`

Release a lock.

When the lock is locked, reset it to unlocked, and return. If any other threads are blocked waiting for the lock to become unlocked, allow exactly one of them to proceed.

Do not call this method when the lock is unlocked.

There is no return value.

15.3.2 RLock Objects

A reentrant lock is a synchronization primitive that may be acquired multiple times by the same thread. Internally, it uses the concepts of "owning thread" and "recursion level" in addition to the locked/unlocked state used by primitive locks. In the locked state, some thread owns the lock; in the unlocked state, no thread owns it.

To lock the lock, a thread calls its `acquire()` method; this returns once the thread owns the lock. To unlock the lock, a thread calls its `release()` method. `acquire()/release()` call pairs may be nested; only the final `release()` (the `release()` of the outermost pair) resets the lock to unlocked and allows another thread blocked in `acquire()` to proceed.

acquire ([*blocking* = 1])

Acquire a lock, blocking or non-blocking.

When invoked without arguments: if this thread already owns the lock, increment the recursion level by one, and return immediately. Otherwise, if another thread owns the lock, block until the lock is unlocked. Once the lock is unlocked (not owned by any thread), then grab ownership, set the recursion level to one, and return. If more than one thread is blocked waiting until the lock is unlocked, only one at a time will be able to grab ownership of the lock. There is no return value in this case.

When invoked with the *blocking* argument set to true, do the same thing as when called without arguments, and return true.

When invoked with the *blocking* argument set to false, do not block. If a call without an argument would block, return false immediately; otherwise, do the same thing as when called without arguments, and return true.

release ()

Release a lock, decrementing the recursion level. If after the decrement it is zero, reset the lock to unlocked (not owned by any thread), and if any other threads are blocked waiting for the lock to become unlocked, allow exactly one of them to proceed. If after the decrement the recursion level is still nonzero, the lock remains locked and owned by the calling thread.

Only call this method when the calling thread owns the lock. Do not call this method when the lock is unlocked.

There is no return value.

15.3.3 Condition Objects

A condition variable is always associated with some kind of lock; this can be passed in or one will be created by default. (Passing one in is useful when several condition variables must share the same lock.)

A condition variable has `acquire()` and `release()` methods that call the corresponding methods of the associated lock. It also has a `wait()` method, and `notify()` and `notifyAll()` methods. These three must only be called when the calling thread has acquired the lock.

The `wait()` method releases the lock, and then blocks until it is awakened by a `notify()` or `notifyAll()` call for the same condition variable in another thread. Once awakened, it re-acquires the lock and returns. It is also possible to specify a timeout.

The `notify()` method wakes up one of the threads waiting for the condition variable, if any are waiting. The `notifyAll()` method wakes up all threads waiting for the condition variable.

Note: the `notify()` and `notifyAll()` methods don't release the lock; this means that the thread or threads awakened will not return from their `wait()` call immediately, but only when the thread that called `notify()` or `notifyAll()` finally relinquishes ownership of the lock.

Tip: the typical programming style using condition variables uses the lock to synchronize access to some shared state; threads that are interested in a particular change of state call `wait()` repeatedly until they see the desired state, while threads that modify the state call `notify()` or `notifyAll()` when they change the state in such a way that it could possibly be a desired state for one of the waiters. For example, the following code is a generic producer-consumer situation with unlimited buffer capacity:

```

# Consume one item
cv.acquire()
while not an_item_is_available():
    cv.wait()
get_an_available_item()
cv.release()

# Produce one item
cv.acquire()
make_an_item_available()
cv.notify()
cv.release()

```

To choose between `notify()` and `notifyAll()`, consider whether one state change can be interesting for only one or several waiting threads. E.g. in a typical producer-consumer situation, adding one item to the buffer only needs to wake up one consumer thread.

class Condition ([*lock*])

If the *lock* argument is given and not `None`, it must be a `Lock` or `RLock` object, and it is used as the underlying lock. Otherwise, a new `RLock` object is created and used as the underlying lock.

acquire (**args*)

Acquire the underlying lock. This method calls the corresponding method on the underlying lock; the return value is whatever that method returns.

release ()

Release the underlying lock. This method calls the corresponding method on the underlying lock; there is no return value.

wait ([*timeout*])

Wait until notified or until a timeout occurs. This must only be called when the calling thread has acquired the lock.

This method releases the underlying lock, and then blocks until it is awakened by a `notify()` or `notifyAll()` call for the same condition variable in another thread, or until the optional timeout occurs. Once awakened or timed out, it re-acquires the lock and returns.

When the *timeout* argument is present and not `None`, it should be a floating point number specifying a timeout for the operation in seconds (or fractions thereof).

When the underlying lock is an `RLock`, it is not released using its `release()` method, since this may not actually unlock the lock when it was acquired multiple times recursively. Instead, an internal interface of the `RLock` class is used, which really unlocks it even when it has been recursively acquired several times. Another internal interface is then used to restore the recursion level when the lock is reacquired.

notify ()

Wake up a thread waiting on this condition, if any. This must only be called when the calling thread has acquired the lock.

This method wakes up one of the threads waiting for the condition variable, if any are waiting; it is a no-op if no threads are waiting.

The current implementation wakes up exactly one thread, if any are waiting. However, it's not safe to rely on this behavior. A future, optimized implementation may occasionally wake up more than one thread.

Note: the awakened thread does not actually return from its `wait()` call until it can reacquire the lock. Since `notify()` does not release the lock, its caller should.

notifyAll ()

Wake up all threads waiting on this condition. This method acts like `notify()`, but wakes up all waiting threads instead of one.

15.3.4 Semaphore Objects

This is one of the oldest synchronization primitives in the history of computer science, invented by the early Dutch computer scientist Edsger W. Dijkstra (he used `P()` and `V()` instead of `acquire()` and `release()`).

A semaphore manages an internal counter which is decremented by each `acquire()` call and incremented by each `release()` call. The counter can never go below zero; when `acquire()` finds that it is zero, it blocks, waiting until some other thread calls `release()`.

class Semaphore (*[value]*)

The optional argument gives the initial value for the internal counter; it defaults to 1.

acquire (*[blocking]*)

Acquire a semaphore.

When invoked without arguments: if the internal counter is larger than zero on entry, decrement it by one and return immediately. If it is zero on entry, block, waiting until some other thread has called `release()` to make it larger than zero. This is done with proper interlocking so that if multiple `acquire()` calls are blocked, `release()` will wake exactly one of them up. The implementation may pick one at random, so the order in which blocked threads are awakened should not be relied on. There is no return value in this case.

When invoked with *blocking* set to true, do the same thing as when called without arguments, and return true.

When invoked with *blocking* set to false, do not block. If a call without an argument would block, return false immediately; otherwise, do the same thing as when called without arguments, and return true.

release ()

Release a semaphore, incrementing the internal counter by one. When it was zero on entry and another thread is waiting for it to become larger than zero again, wake up that thread.

Semaphore Example

Semaphores are often used to guard resources with limited capacity, for example, a database server. In any situation where the size of the resource size is fixed, you should use a bounded semaphore. Before spawning any worker threads, your main thread would initialize the semaphore:

```
maxconnections = 5
...
pool_sema = BoundedSemaphore(value=maxconnections)
```

Once spawned, worker threads call the semaphore's `acquire` and `release` methods when they need to connect to the server:

```
pool_sema.acquire()
conn = connectdb()
... use connection ...
conn.close()
pool_sema.release()
```

The use of a bounded semaphore reduces the chance that a programming error which causes the semaphore to be released more than it's acquired will go undetected.

15.3.5 Event Objects

This is one of the simplest mechanisms for communication between threads: one thread signals an event and other threads wait for it.

An event object manages an internal flag that can be set to true with the `set()` method and reset to false with the `clear()` method. The `wait()` method blocks until the flag is true.

class Event()

The internal flag is initially false.

isSet()

Return true if and only if the internal flag is true.

set()

Set the internal flag to true. All threads waiting for it to become true are awakened. Threads that call `wait()` once the flag is true will not block at all.

clear()

Reset the internal flag to false. Subsequently, threads calling `wait()` will block until `set()` is called to set the internal flag to true again.

wait([timeout])

Block until the internal flag is true. If the internal flag is true on entry, return immediately. Otherwise, block until another thread calls `set()` to set the flag to true, or until the optional timeout occurs.

When the timeout argument is present and not `None`, it should be a floating point number specifying a timeout for the operation in seconds (or fractions thereof).

15.3.6 Thread Objects

This class represents an activity that is run in a separate thread of control. There are two ways to specify the activity: by passing a callable object to the constructor, or by overriding the `run()` method in a subclass. No other methods (except for the constructor) should be overridden in a subclass. In other words, *only* override the `__init__()` and `run()` methods of this class.

Once a thread object is created, its activity must be started by calling the thread's `start()` method. This invokes the `run()` method in a separate thread of control.

Once the thread's activity is started, the thread is considered 'alive'. It stops being alive when its `run()` method terminates – either normally, or by raising an unhandled exception. The `isAlive()` method tests whether the thread is alive.

Other threads can call a thread's `join()` method. This blocks the calling thread until the thread whose `join()` method is called is terminated.

A thread has a name. The name can be passed to the constructor, set with the `setName()` method, and retrieved with the `getName()` method.

A thread can be flagged as a “daemon thread”. The significance of this flag is that the entire Python program exits when only daemon threads are left. The initial value is inherited from the creating thread. The flag can be set with the `setDaemon()` method and retrieved with the `isDaemon()` method.

There is a “main thread” object; this corresponds to the initial thread of control in the Python program. It is not a daemon thread.

There is the possibility that “dummy thread objects” are created. These are thread objects corresponding to “alien threads”, which are threads of control started outside the threading module, such as directly from C code. Dummy thread objects have limited functionality; they are always considered alive and daemonic, and cannot be `join()`ed. They are never deleted, since it is impossible to detect the termination of alien threads.

class Thread(*group=None, target=None, name=None, args=(), kwargs={}*)

This constructor should always be called with keyword arguments. Arguments are:

group should be `None`; reserved for future extension when a `ThreadGroup` class is implemented.

target is the callable object to be invoked by the `run()` method. Defaults to `None`, meaning nothing is called.

name is the thread name. By default, a unique name is constructed of the form “Thread-*N*” where *N* is a small decimal number.

args is the argument tuple for the target invocation. Defaults to `()`.

kwargs is a dictionary of keyword arguments for the target invocation. Defaults to `{}`.

If the subclass overrides the constructor, it must make sure to invoke the base class constructor (`Thread.__init__()`) before doing anything else to the thread.

start()

Start the thread’s activity.

This must be called at most once per thread object. It arranges for the object’s `run()` method to be invoked in a separate thread of control.

run()

Method representing the thread’s activity.

You may override this method in a subclass. The standard `run()` method invokes the callable object passed to the object’s constructor as the *target* argument, if any, with sequential and keyword arguments taken from the *args* and *kwargs* arguments, respectively.

join([*timeout*])

Wait until the thread terminates. This blocks the calling thread until the thread whose `join()` method is called terminates – either normally or through an unhandled exception – or until the optional timeout occurs.

When the *timeout* argument is present and not `None`, it should be a floating point number specifying a timeout for the operation in seconds (or fractions thereof). As `join()` always returns `None`, you must call `isAlive()` to decide whether a timeout happened.

When the *timeout* argument is not present or `None`, the operation will block until the thread terminates.

A thread can be `join()`ed many times.

A thread cannot join itself because this would cause a deadlock.

It is an error to attempt to `join()` a thread before it has been started.

getName()

Return the thread’s name.

setName(*name*)

Set the thread’s name.

The name is a string used for identification purposes only. It has no semantics. Multiple threads may be given the same name. The initial name is set by the constructor.

isAlive()

Return whether the thread is alive.

Roughly, a thread is alive from the moment the `start()` method returns until its `run()` method terminates. The module function `enumerate()` returns a list of all alive threads.

isDaemon()

Return the thread’s daemon flag.

setDaemon(*daemonic*)

Set the thread’s daemon flag to the Boolean value *daemonic*. This must be called before `start()` is called.

The initial value is inherited from the creating thread.

The entire Python program exits when no alive non-daemon threads are left.

15.3.7 Timer Objects

This class represents an action that should be run only after a certain amount of time has passed — a timer. `Timer` is a subclass of `Thread` and as such also functions as an example of creating custom threads.

Timers are started, as with threads, by calling their `start()` method. The timer can be stopped (before its action has begun) by calling the `cancel()` method. The interval the timer will wait before executing its action may not be exactly the same as the interval specified by the user.

For example:

```
def hello():
    print "hello, world"

t = Timer(30.0, hello)
t.start() # after 30 seconds, "hello, world" will be printed
```

class `Timer` (*interval*, *function*, *args*=[], *kwargs*={})

Create a timer that will run *function* with arguments *args* and keyword arguments *kwargs*, after *interval* seconds have passed.

`cancel()`

Stop the timer, and cancel the execution of the timer's action. This will only work if the timer is still in its waiting stage.

15.3.8 Using locks, conditions, and semaphores in the `with` statement

All of the objects provided by this module that have `acquire()` and `release()` methods can be used as context managers for a `with` statement. The `acquire()` method will be called when the block is entered, and `release()` will be called when the block is exited.

Currently, `Lock`, `RLock`, `Condition`, `Semaphore`, and `BoundedSemaphore` objects may be used as `with` statement context managers. For example:

```
from __future__ import with_statement
import threading

some_rlock = threading.RLock()

with some_rlock:
    print "some_rlock is locked while this executes"
```

15.4 `dummy_thread` — Drop-in replacement for the `thread` module

This module provides a duplicate interface to the `thread` module. It is meant to be imported when the `thread` module is not provided on a platform.

Suggested usage is:

```
try:
    import thread as _thread
except ImportError:
    import dummy_thread as _thread
```

Be careful to not use this module where deadlock might occur from a thread being created that blocks waiting for

another thread to be created. This often occurs with blocking I/O.

15.5 dummy_threading — Drop-in replacement for the threading module

This module provides a duplicate interface to the `threading` module. It is meant to be imported when the `thread` module is not provided on a platform.

Suggested usage is:

```
try:
    import threading as _threading
except ImportError:
    import dummy_threading as _threading
```

Be careful to not use this module where deadlock might occur from a thread being created that blocks waiting for another thread to be created. This often occurs with blocking I/O.

15.6 mmap — Memory-mapped file support

Memory-mapped file objects behave like both strings and like file objects. Unlike normal string objects, however, these are mutable. You can use `mmap` objects in most places where strings are expected; for example, you can use the `re` module to search through a memory-mapped file. Since they're mutable, you can change a single character by doing `obj[index] = 'a'`, or change a substring by assigning to a slice: `obj[i1:i2] = '...'`. You can also read and write data starting at the current file position, and `seek()` through the file to different positions.

A memory-mapped file is created by the `mmap()` function, which is different on UNIX and on Windows. In either case you must provide a file descriptor for a file opened for update. If you wish to map an existing Python file object, use its `fileno()` method to obtain the correct value for the `fileno` parameter. Otherwise, you can open the file using the `os.open()` function, which returns a file descriptor directly (the file still needs to be closed when done).

For both the UNIX and Windows versions of the function, `access` may be specified as an optional keyword parameter. `access` accepts one of three values: `ACCESS_READ`, `ACCESS_WRITE`, or `ACCESS_COPY` to specify readonly, write-through or copy-on-write memory respectively. `access` can be used on both UNIX and Windows. If `access` is not specified, Windows `mmap` returns a write-through mapping. The initial memory values for all three access types are taken from the specified file. Assignment to an `ACCESS_READ` memory map raises a `TypeError` exception. Assignment to an `ACCESS_WRITE` memory map affects both memory and the underlying file. Assignment to an `ACCESS_COPY` memory map affects memory but does not update the underlying file. Changed in version 2.5: To map anonymous memory, -1 should be passed as the `fileno` along with the `length`.

mmap (*fileno*, *length*[, *tagname*[, *access*]])

(Windows version) Maps *length* bytes from the file specified by the file handle *fileno*, and returns a `mmap` object. If *length* is larger than the current size of the file, the file is extended to contain *length* bytes. If *length* is 0, the maximum length of the map is the current size of the file, except that if the file is empty Windows raises an exception (you cannot create an empty mapping on Windows).

tagname, if specified and not `None`, is a string giving a tag name for the mapping. Windows allows you to have many different mappings against the same file. If you specify the name of an existing tag, that tag is opened, otherwise a new tag of this name is created. If this parameter is omitted or `None`, the mapping is created without a name. Avoiding the use of the tag parameter will assist in keeping your code portable between UNIX and Windows.

mmap (*fileno*, *length*[, *flags*[, *prot*[, *access*]]])

(UNIX **version**) Maps *length* bytes from the file specified by the file descriptor *fileno*, and returns a mmap object. If *length* is 0, the maximum length of the map will be the current size of the file when `mmap()` is called.

flags specifies the nature of the mapping. `MAP_PRIVATE` creates a private copy-on-write mapping, so changes to the contents of the mmap object will be private to this process, and `MAP_SHARED` creates a mapping that's shared with all other processes mapping the same areas of the file. The default value is `MAP_SHARED`.

prot, if specified, gives the desired memory protection; the two most useful values are `PROT_READ` and `PROT_WRITE`, to specify that the pages may be read or written. *prot* defaults to `PROT_READ | PROT_WRITE`.

access may be specified in lieu of *flags* and *prot* as an optional keyword parameter. It is an error to specify both *flags*, *prot* and *access*. See the description of *access* above for information on how to use this parameter.

Memory-mapped file objects support the following methods:

close()

Close the file. Subsequent calls to other methods of the object will result in an exception being raised.

find(*string*[, *start*])

Returns the lowest index in the object where the substring *string* is found. Returns `-1` on failure. *start* is the index at which the search begins, and defaults to zero.

flush([*offset*, *size*])

Flushes changes made to the in-memory copy of a file back to disk. Without use of this call there is no guarantee that changes are written back before the object is destroyed. If *offset* and *size* are specified, only changes to the given range of bytes will be flushed to disk; otherwise, the whole extent of the mapping is flushed.

move(*dest*, *src*, *count*)

Copy the *count* bytes starting at offset *src* to the destination index *dest*. If the mmap was created with `ACCESS_READ`, then calls to move will throw a `TypeError` exception.

read(*num*)

Return a string containing up to *num* bytes starting from the current file position; the file position is updated to point after the bytes that were returned.

read_byte()

Returns a string of length 1 containing the character at the current file position, and advances the file position by 1.

readline()

Returns a single line, starting at the current file position and up to the next newline.

resize(*newsize*)

Resizes the map and the underlying file, if any. If the mmap was created with `ACCESS_READ` or `ACCESS_COPY`, resizing the map will throw a `TypeError` exception.

seek(*pos*[, *whence*])

Set the file's current position. *whence* argument is optional and defaults to `os.SEEK_SET` or 0 (absolute file positioning); other values are `os.SEEK_CUR` or 1 (seek relative to the current position) and `os.SEEK_END` or 2 (seek relative to the file's end).

size()

Return the length of the file, which can be larger than the size of the memory-mapped area.

tell()

Returns the current position of the file pointer.

write(*string*)

Write the bytes in *string* into memory at the current position of the file pointer; the file position is updated to point after the bytes that were written. If the mmap was created with `ACCESS_READ`, then writing to it will throw a `TypeError` exception.

write_byte (*byte*)

Write the single-character string *byte* into memory at the current position of the file pointer; the file position is advanced by 1. If the mmap was created with `ACCESS_READ`, then writing to it will throw a `TypeError` exception.

15.7 readline — GNU readline interface

The `readline` module defines a number of functions to facilitate completion and reading/writing of history files from the Python interpreter. This module can be used directly or via the `rlcompleter` module. Settings made using this module affect the behaviour of both the interpreter's interactive prompt and the prompts offered by the `raw_input()` and `input()` built-in functions.

The `readline` module defines the following functions:

parse_and_bind (*string*)

Parse and execute single line of a readline init file.

get_line_buffer ()

Return the current contents of the line buffer.

insert_text (*string*)

Insert text into the command line.

read_init_file ([*filename*])

Parse a readline initialization file. The default filename is the last filename used.

read_history_file ([*filename*])

Load a readline history file. The default filename is `~/.history`.

write_history_file ([*filename*])

Save a readline history file. The default filename is `~/.history`.

clear_history ()

Clear the current history. (Note: this function is not available if the installed version of GNU readline doesn't support it.) New in version 2.4.

get_history_length ()

Return the desired length of the history file. Negative values imply unlimited history file size.

set_history_length (*length*)

Set the number of lines to save in the history file. `write_history_file()` uses this value to truncate the history file when saving. Negative values imply unlimited history file size.

get_current_history_length ()

Return the number of lines currently in the history. (This is different from `get_history_length()`, which returns the maximum number of lines that will be written to a history file.) New in version 2.3.

get_history_item (*index*)

Return the current contents of history item at *index*. New in version 2.3.

remove_history_item (*pos*)

Remove history item specified by its position from the history. New in version 2.4.

replace_history_item (*pos*, *line*)

Replace history item specified by its position with the given line. New in version 2.4.

redisplay ()

Change what's displayed on the screen to reflect the current contents of the line buffer. New in version 2.3.

set_startup_hook ([*function*])

Set or remove the startup_hook function. If *function* is specified, it will be used as the new startup_hook function;

if omitted or `None`, any hook function already installed is removed. The `startup_hook` function is called with no arguments just before `readline` prints the first prompt.

set_pre_input_hook (*[function]*)

Set or remove the `pre_input_hook` function. If *function* is specified, it will be used as the new `pre_input_hook` function; if omitted or `None`, any hook function already installed is removed. The `pre_input_hook` function is called with no arguments after the first prompt has been printed and just before `readline` starts reading input characters.

set_completer (*[function]*)

Set or remove the completer function. If *function* is specified, it will be used as the new completer function; if omitted or `None`, any completer function already installed is removed. The completer function is called as *function(text, state)*, for *state* in 0, 1, 2, ..., until it returns a non-string value. It should return the next possible completion starting with *text*.

get_completer ()

Get the completer function, or `None` if no completer function has been set. New in version 2.3.

get_begidx ()

Get the beginning index of the `readline` tab-completion scope.

get_endidx ()

Get the ending index of the `readline` tab-completion scope.

set_completer_delims (*string*)

Set the `readline` word delimiters for tab-completion.

get_completer_delims ()

Get the `readline` word delimiters for tab-completion.

add_history (*line*)

Append a line to the history buffer, as if it was the last line typed.

See Also:

[Module `rlcompleter`](#) (section 15.8):

Completion of Python identifiers at the interactive prompt.

15.7.1 Example

The following example demonstrates how to use the `readline` module's history reading and writing functions to automatically load and save a history file named `'pyhist'` from the user's home directory. The code below would normally be executed automatically during interactive sessions from the user's `PYTHONSTARTUP` file.

```
import os
histfile = os.path.join(os.environ["HOME"], ".pyhist")
try:
    readline.read_history_file(histfile)
except IOError:
    pass
import atexit
atexit.register(readline.write_history_file, histfile)
del os, histfile
```

The following example extends the `code.InteractiveConsole` class to support history save/restore.

```

import code
import readline
import atexit
import os

class HistoryConsole(code.InteractiveConsole):
    def __init__(self, locals=None, filename="<console>",
                 histfile=os.path.expanduser("~/console-history")):
        code.InteractiveConsole.__init__(self)
        self.init_history(histfile)

    def init_history(self, histfile):
        readline.parse_and_bind("tab: complete")
        if hasattr(readline, "read_history_file"):
            try:
                readline.read_history_file(histfile)
            except IOError:
                pass
            atexit.register(self.save_history, histfile)

    def save_history(self, histfile):
        readline.write_history_file(histfile)

```

15.8 rlcompleter — Completion function for GNU readline

The `rlcompleter` module defines a completion function suitable for the `readline` module by completing valid Python identifiers and keywords.

When this module is imported on a UNIX platform with the `readline` module available, an instance of the `Completer` class is automatically created and its `complete` method is set as the `readline` completer.

Example:

```

>>> import rlcompleter
>>> import readline
>>> readline.parse_and_bind("tab: complete")
>>> readline. <TAB PRESSED>
readline.__doc__      readline.get_line_buffer  readline.read_init_file
readline.__file__     readline.insert_text      readline.set_completer
readline.__name__     readline.parse_and_bind
>>> readline.

```

The `rlcompleter` module is designed for use with Python's interactive mode. A user can add the following lines to his or her initialization file (identified by the `PYTHONSTARTUP` environment variable) to get automatic Tab completion:

```

try:
    import readline
except ImportError:
    print "Module readline not available."
else:
    import rlcompleter
    readline.parse_and_bind("tab: complete")

```

On platforms without `readline`, the `Completer` class defined by this module can still be used for custom purposes.

15.8.1 Completer Objects

Completer objects have the following method:

complete (*text*, *state*)

Return the *state* completion for *text*.

If called for *text* that doesn't include a period character (`'.'`), it will complete from names currently defined in `__main__`, `__builtin__` and keywords (as defined by the `keyword` module).

If called for a dotted name, it will try to evaluate anything without obvious side-effects (functions will not be evaluated, but it can generate calls to `__getattr__()` up to the last part, and find matches for the rest via the `dir()` function).

Unix Specific Services

The modules described in this chapter provide interfaces to features that are unique to the UNIX operating system, or in some cases to some or many variants of it. Here's an overview:

<code>posix</code>	The most common POSIX system calls (normally used via module <code>os</code>).
<code>pwd</code>	The password database (<code>getpwnam()</code> and friends).
<code>spwd</code>	The shadow password database (<code>getspnam()</code> and friends).
<code>grp</code>	The group database (<code>getgrnam()</code> and friends).
<code>crypt</code>	The <code>crypt()</code> function used to check UNIX passwords.
<code>dl</code>	Call C functions in shared objects.
<code>termios</code>	POSIX style tty control.
<code>tty</code>	Utility functions that perform common terminal control operations.
<code>pty</code>	Pseudo-Terminal Handling for SGI and Linux.
<code>fcntl</code>	The <code>fcntl()</code> and <code>ioctl()</code> system calls.
<code>pipes</code>	A Python interface to UNIX shell pipelines.
<code>posixfile</code>	A file-like object with support for locking.
<code>resource</code>	An interface to provide resource usage information on the current process.
<code>nis</code>	Interface to Sun's NIS (Yellow Pages) library.
<code>syslog</code>	An interface to the UNIX syslog library routines.
<code>commands</code>	Utility functions for running external commands.

16.1 `posix` — The most common POSIX system calls

This module provides access to operating system functionality that is standardized by the C Standard and the POSIX standard (a thinly disguised UNIX interface).

Do not import this module directly. Instead, import the module `os`, which provides a *portable* version of this interface. On UNIX, the `os` module provides a superset of the `posix` interface. On non-UNIX operating systems the `posix` module is not available, but a subset is always available through the `os` interface. Once `os` is imported, there is *no* performance penalty in using it instead of `posix`. In addition, `os` provides some additional functionality, such as automatically calling `putenv()` when an entry in `os.environ` is changed.

The descriptions below are very terse; refer to the corresponding UNIX manual (or POSIX documentation) entry for more information. Arguments called *path* refer to a pathname given as a string.

Errors are reported as exceptions; the usual exceptions are given for type errors, while errors reported by the system calls raise `error` (a synonym for the standard exception `OSError`), described below.

16.1.1 Large File Support

Several operating systems (including AIX, HPUX, Irix and Solaris) provide support for files that are larger than 2 Gb from a C programming model where `int` and `long` are 32-bit values. This is typically accomplished by defining the relevant size and offset types as 64-bit values. Such files are sometimes referred to as *large files*.

Large file support is enabled in Python when the size of an `off_t` is larger than a `long` and the `long long` type is available and is at least as large as an `off_t`. Python longs are then used to represent file sizes, offsets and other values that can exceed the range of a Python `int`. It may be necessary to configure and compile Python with certain compiler flags to enable this mode. For example, it is enabled by default with recent versions of Irix, but with Solaris 2.6 and 2.7 you need to do something like:

```
CFLAGS="'getconf LFS_CFLAGS'" OPT="-g -O2 $CFLAGS" \
./configure
```

On large-file-capable Linux systems, this might work:

```
CFLAGS='-D_LARGEFILE64_SOURCE -D_FILE_OFFSET_BITS=64' OPT="-g -O2 $CFLAGS" \
./configure
```

16.1.2 Module Contents

Module `posix` defines the following data item:

environ

A dictionary representing the string environment at the time the interpreter was started. For example, `environ['HOME']` is the pathname of your home directory, equivalent to `getenv("HOME")` in C.

Modifying this dictionary does not affect the string environment passed on by `execv()`, `popen()` or `system()`; if you need to change the environment, pass `environ` to `execve()` or add variable assignments and export statements to the command string for `system()` or `popen()`.

Note: The `os` module provides an alternate implementation of `environ` which updates the environment on modification. Note also that updating `os.environ` will render this dictionary obsolete. Use of the `os` module version of this is recommended over direct access to the `posix` module.

Additional contents of this module should only be accessed via the `os` module; refer to the documentation for that module for further information.

16.2 pwd — The password database

This module provides access to the UNIX user account and password database. It is available on all UNIX versions.

Password database entries are reported as a tuple-like object, whose attributes correspond to the members of the `passwd` structure (Attribute field below, see `<pwd.h>`):

Index	Attribute	Meaning
0	<code>pw_name</code>	Login name
1	<code>pw_passwd</code>	Optional encrypted password
2	<code>pw_uid</code>	Numerical user ID
3	<code>pw_gid</code>	Numerical group ID
4	<code>pw_gecos</code>	User name or comment field
5	<code>pw_dir</code>	User home directory
6	<code>pw_shell</code>	User command interpreter

The uid and gid items are integers, all others are strings. `KeyError` is raised if the entry asked for cannot be found.

Note: In traditional UNIX the field `pw_passwd` usually contains a password encrypted with a DES derived algorithm (see module [crypt](#)). However most modern unices use a so-called *shadow password* system. On those unices the `pw_passwd` field only contains an asterisk (`'*'`) or the letter `'x'` where the encrypted password is stored in a file `'etc/shadow'` which is not world readable. Whether the `pw_passwd` field contains anything useful is system-dependent. If available, the `spwd` module should be used where access to the encrypted password is required.

It defines the following items:

getpwuid (*uid*)

Return the password database entry for the given numeric user ID.

getpwnam (*name*)

Return the password database entry for the given user name.

getpwall ()

Return a list of all available password database entries, in arbitrary order.

See Also:

Module [grp](#) (section 16.4):

An interface to the group database, similar to this.

Module [spwd](#) (section 16.3):

An interface to the shadow password database, similar to this.

16.3 spwd — The shadow password database

New in version 2.5.

This module provides access to the UNIX shadow password database. It is available on various UNIX versions.

You must have enough privileges to access the shadow password database (this usually means you have to be root).

Shadow password database entries are reported as a tuple-like object, whose attributes correspond to the members of the `spwd` structure (Attribute field below, see `<shadow.h>`):

Index	Attribute	Meaning
0	<code>sp_nam</code>	Login name
1	<code>sp_pwd</code>	Encrypted password
2	<code>sp_lstchg</code>	Date of last change
3	<code>sp_min</code>	Minimal number of days between changes
4	<code>sp_max</code>	Maximum number of days between changes
5	<code>sp_warn</code>	Number of days before password expires to warn user about it
6	<code>sp_inact</code>	Number of days after password expires until account is blocked
7	<code>sp_expire</code>	Number of days since 1970-01-01 until account is disabled
8	<code>sp_flag</code>	Reserved

The `sp_nam` and `sp_pwd` items are strings, all others are integers. `KeyError` is raised if the entry asked for cannot be found.

It defines the following items:

getspnam (*name*)

Return the shadow password database entry for the given user name.

getspall ()

Return a list of all available shadow password database entries, in arbitrary order.

See Also:

[Module grp](#) (section 16.4):

An interface to the group database, similar to this.

[Module pwd](#) (section 16.2):

An interface to the normal password database, similar to this.

16.4 grp — The group database

This module provides access to the UNIX group database. It is available on all UNIX versions.

Group database entries are reported as a tuple-like object, whose attributes correspond to the members of the `group` structure (Attribute field below, see `<pwd.h>`):

Index	Attribute	Meaning
0	<code>gr_name</code>	the name of the group
1	<code>gr_passwd</code>	the (encrypted) group password; often empty
2	<code>gr_gid</code>	the numerical group ID
3	<code>gr_mem</code>	all the group member's user names

The `gid` is an integer, name and password are strings, and the member list is a list of strings. (Note that most users are not explicitly listed as members of the group they are in according to the password database. Check both databases to get complete membership information.)

It defines the following items:

getgrgid (*gid*)

Return the group database entry for the given numeric group ID. `KeyError` is raised if the entry asked for cannot be found.

getgrnam (*name*)

Return the group database entry for the given group name. `KeyError` is raised if the entry asked for cannot be found.

getgrall ()

Return a list of all available group entries, in arbitrary order.

See Also:

[Module pwd](#) (section 16.2):

An interface to the user database, similar to this.

[Module spwd](#) (section 16.3):

An interface to the shadow password database, similar to this.

16.5 crypt — Function to check UNIX passwords

This module implements an interface to the `crypt(3)` routine, which is a one-way hash function based upon a modified DES algorithm; see the UNIX man page for further details. Possible uses include allowing Python scripts to accept typed passwords from the user, or attempting to crack UNIX passwords with a dictionary.

Notice that the behavior of this module depends on the actual implementation of the `crypt(3)` routine in the running system. Therefore, any extensions available on the current implementation will also be available on this module.

crypt (*word*, *salt*)

word will usually be a user's password as typed at a prompt or in a graphical interface. *salt* is usually a random

two-character string which will be used to perturb the DES algorithm in one of 4096 ways. The characters in *salt* must be in the set `[./a-zA-Z0-9]`. Returns the hashed password as a string, which will be composed of characters from the same alphabet as the salt (the first two characters represent the salt itself).

Since a few *crypt(3)* extensions allow different values, with different sizes in the *salt*, it is recommended to use the full crypted password as salt when checking for a password.

A simple example illustrating typical use:

```
import crypt, getpass, pwd

def login():
    username = raw_input('Python login:')
    cryptedpasswd = pwd.getpwnam(username)[1]
    if cryptedpasswd:
        if cryptedpasswd == 'x' or cryptedpasswd == '*':
            raise "Sorry, currently no support for shadow passwords"
        cleartext = getpass.getpass()
        return crypt.crypt(cleartext, cryptedpasswd) == cryptedpasswd
    else:
        return 1
```

16.6 dl — Call C functions in shared objects

The `dl` module defines an interface to the `dlopen()` function, which is the most common interface on UNIX platforms for handling dynamically linked libraries. It allows the program to call arbitrary functions in such a library.

Warning: The `dl` module bypasses the Python type system and error handling. If used incorrectly it may cause segmentation faults, crashes or other incorrect behaviour.

Note: This module will not work unless `sizeof(int) == sizeof(long) == sizeof(char *)`. If this is not the case, `SystemError` will be raised on import.

The `dl` module defines the following function:

open (*name* [, *mode* = `RTLD_LAZY`])

Open a shared object file, and return a handle. Mode signifies late binding (`RTLD_LAZY`) or immediate binding (`RTLD_NOW`). Default is `RTLD_LAZY`. Note that some systems do not support `RTLD_NOW`.

Return value is a `dlobj`ect.

The `dl` module defines the following constants:

RTLD_LAZY

Useful as an argument to `open()`.

RTLD_NOW

Useful as an argument to `open()`. Note that on systems which do not support immediate binding, this constant will not appear in the module. For maximum portability, use `hasattr()` to determine if the system supports immediate binding.

The `dl` module defines the following exception:

exception error

Exception raised when an error has occurred inside the dynamic loading and linking routines.

Example:

```
>>> import dl, time
>>> a=dl.open('/lib/libc.so.6')
>>> a.call('time'), time.time()
(929723914, 929723914.498)
```

This example was tried on a Debian GNU/Linux system, and is a good example of the fact that using this module is usually a bad alternative.

16.6.1 DL Objects

DL objects, as returned by `open()` above, have the following methods:

close()

Free all resources, except the memory.

sym(name)

Return the pointer for the function named *name*, as a number, if it exists in the referenced shared object, otherwise None. This is useful in code like:

```
>>> if a.sym('time'):
...     a.call('time')
... else:
...     time.time()
```

(Note that this function will return a non-zero number, as zero is the NULL pointer)

call(name[, arg1[, arg2...]])

Call the function named *name* in the referenced shared object. The arguments must be either Python integers, which will be passed as is, Python strings, to which a pointer will be passed, or None, which will be passed as NULL. Note that strings should only be passed to functions as `const char*`, as Python will not like its string mutated.

There must be at most 10 arguments, and arguments not given will be treated as None. The function's return value must be a C long, which is a Python integer.

16.7 `termios` — POSIX style tty control

This module provides an interface to the POSIX calls for tty I/O control. For a complete description of these calls, see the POSIX or UNIX manual pages. It is only available for those UNIX versions that support POSIX *termios* style tty I/O control (and then only if configured at installation time).

All functions in this module take a file descriptor *fd* as their first argument. This can be an integer file descriptor, such as returned by `sys.stdin.fileno()`, or a file object, such as `sys.stdin` itself.

This module also defines all the constants needed to work with the functions provided here; these have the same name as their counterparts in C. Please refer to your system documentation for more information on using these terminal control interfaces.

The module defines the following functions:

tcgetattr(fd)

Return a list containing the tty attributes for file descriptor *fd*, as follows: [*iflag*, *oflag*, *cflag*, *lflag*, *ispeed*, *ospeed*, *cc*] where *cc* is a list of the tty special characters (each a string of length 1, except the items with indices VMIN and VTIME, which are integers when these fields are defined). The interpretation of the flags and the speeds as well as the indexing in the *cc* array must be done using the symbolic constants defined in the `termios` module.

tcsetattr (*fd*, *when*, *attributes*)

Set the tty attributes for file descriptor *fd* from the *attributes*, which is a list like the one returned by `tcgetattr()`. The *when* argument determines when the attributes are changed: `TCSANOW` to change immediately, `TCSADRAIN` to change after transmitting all queued output, or `TCSAFLUSH` to change after transmitting all queued output and discarding all queued input.

tcsendbreak (*fd*, *duration*)

Send a break on file descriptor *fd*. A zero *duration* sends a break for 0.25–0.5 seconds; a nonzero *duration* has a system dependent meaning.

tcdrain (*fd*)

Wait until all output written to file descriptor *fd* has been transmitted.

tcflush (*fd*, *queue*)

Discard queued data on file descriptor *fd*. The *queue* selector specifies which queue: `TCIFLUSH` for the input queue, `TCOFLUSH` for the output queue, or `TCIOFLUSH` for both queues.

tcflow (*fd*, *action*)

Suspend or resume input or output on file descriptor *fd*. The *action* argument can be `TCOOFF` to suspend output, `TCOON` to restart output, `TCIOFF` to suspend input, or `TCION` to restart input.

See Also:

[Module `tty`](#) (section 16.8):

Convenience functions for common terminal control operations.

16.7.1 Example

Here's a function that prompts for a password with echoing turned off. Note the technique using a separate `tcgetattr()` call and a `try ... finally` statement to ensure that the old tty attributes are restored exactly no matter what happens:

```
def getpass(prompt = "Password: "):
    import termios, sys
    fd = sys.stdin.fileno()
    old = termios.tcgetattr(fd)
    new = termios.tcgetattr(fd)
    new[3] = new[3] & ~termios.ECHO          # lflags
    try:
        termios.tcsetattr(fd, termios.TCSADRAIN, new)
        passwd = raw_input(prompt)
    finally:
        termios.tcsetattr(fd, termios.TCSADRAIN, old)
    return passwd
```

16.8 `tty` — Terminal control functions

The `tty` module defines functions for putting the tty into cbreak and raw modes.

Because it requires the [termios](#) module, it will work only on UNIX.

The `tty` module defines the following functions:

setraw (*fd*[, *when*])

Change the mode of the file descriptor *fd* to raw. If *when* is omitted, it defaults to `termios.TCSAFLUSH`, and

is passed to `termios.tcsetattr()`.

setcbreak (*fd* [, *when*])

Change the mode of file descriptor *fd* to cbreak. If *when* is omitted, it defaults to `termios.TCSAFLUSH`, and is passed to `termios.tcsetattr()`.

See Also:

Module `termios` (section 16.7):

Low-level terminal control interface.

16.9 pty — Pseudo-terminal utilities

The `pty` module defines operations for handling the pseudo-terminal concept: starting another process and being able to write to and read from its controlling terminal programmatically.

Because pseudo-terminal handling is highly platform dependant, there is code to do it only for SGI and Linux. (The Linux code is supposed to work on other platforms, but hasn't been tested yet.)

The `pty` module defines the following functions:

fork ()

Fork. Connect the child's controlling terminal to a pseudo-terminal. Return value is (*pid*, *fd*). Note that the child gets *pid* 0, and the *fd* is *invalid*. The parent's return value is the *pid* of the child, and *fd* is a file descriptor connected to the child's controlling terminal (and also to the child's standard input and output).

openpty ()

Open a new pseudo-terminal pair, using `os.openpty()` if possible, or emulation code for SGI and generic UNIX systems. Return a pair of file descriptors (*master*, *slave*), for the master and the slave end, respectively.

spawn (*argv* [, *master_read* [, *stdin_read*]])

Spawn a process, and connect its controlling terminal with the current process's standard io. This is often used to baffle programs which insist on reading from the controlling terminal.

The functions *master_read* and *stdin_read* should be functions which read from a file-descriptor. The defaults try to read 1024 bytes each time they are called.

16.10 fcntl — The fcntl() and ioctl() system calls

This module performs file control and I/O control on file descriptors. It is an interface to the `fcntl()` and `ioctl()` UNIX routines.

All functions in this module take a file descriptor *fd* as their first argument. This can be an integer file descriptor, such as returned by `sys.stdin.fileno()`, or a file object, such as `sys.stdin` itself, which provides a `fileno()` which returns a genuine file descriptor.

The module defines the following functions:

fcntl (*fd*, *op* [, *arg*])

Perform the requested operation on file descriptor *fd* (file objects providing a `fileno()` method are accepted as well). The operation is defined by *op* and is operating system dependent. These codes are also found in the `fcntl` module. The argument *arg* is optional, and defaults to the integer value 0. When present, it can either be an integer value, or a string. With the argument missing or an integer value, the return value of this function is the integer return value of the C `fcntl()` call. When the argument is a string it represents a binary structure, e.g. created by `struct.pack()`. The binary data is copied to a buffer whose address is passed to the C `fcntl()` call. The return value after a successful call is the contents of the buffer, converted to a string object. The length of the returned string will be the same as the length of the *arg* argument. This is limited to

1024 bytes. If the information returned in the buffer by the operating system is larger than 1024 bytes, this is most likely to result in a segmentation violation or a more subtle data corruption.

If the `fcntl()` fails, an `IOError` is raised.

`ioctl`(*fd*, *op*[, *arg*[, *mutate_flag*]])

This function is identical to the `fcntl()` function, except that the operations are typically defined in the library module `termios` and the argument handling is even more complicated.

The parameter *arg* can be one of an integer, absent (treated identically to the integer 0), an object supporting the read-only buffer interface (most likely a plain Python string) or an object supporting the read-write buffer interface.

In all but the last case, behaviour is as for the `fcntl()` function.

If a mutable buffer is passed, then the behaviour is determined by the value of the *mutate_flag* parameter.

If it is false, the buffer's mutability is ignored and behaviour is as for a read-only buffer, except that the 1024 byte limit mentioned above is avoided – so long as the buffer you pass is at least as long as what the operating system wants to put there, things should work.

If *mutate_flag* is true, then the buffer is (in effect) passed to the underlying `ioctl()` system call, the latter's return code is passed back to the calling Python, and the buffer's new contents reflect the action of the `ioctl()`. This is a slight simplification, because if the supplied buffer is less than 1024 bytes long it is first copied into a static buffer 1024 bytes long which is then passed to `ioctl()` and copied back into the supplied buffer.

If *mutate_flag* is not supplied, then from Python 2.5 it defaults to true, which is a change from versions 2.3 and 2.4. Supply the argument explicitly if version portability is a priority.

An example:

```
>>> import array, fcntl, struct, termios, os
>>> os.getpgrp()
13341
>>> struct.unpack('h', fcntl.ioctl(0, termios.TIOCGPGRP, " "))[0]
13341
>>> buf = array.array('h', [0])
>>> fcntl.ioctl(0, termios.TIOCGPGRP, buf, 1)
0
>>> buf
array('h', [13341])
```

`flock`(*fd*, *op*)

Perform the lock operation *op* on file descriptor *fd* (file objects providing a `fileno()` method are accepted as well). See the UNIX manual `flock(3)` for details. (On some systems, this function is emulated using `fcntl()`.)

`lockf`(*fd*, *operation*, [*length*, [*start*, [*whence*]]])

This is essentially a wrapper around the `fcntl()` locking calls. *fd* is the file descriptor of the file to lock or unlock, and *operation* is one of the following values:

- `LOCK_UN` – unlock
- `LOCK_SH` – acquire a shared lock
- `LOCK_EX` – acquire an exclusive lock

When *operation* is `LOCK_SH` or `LOCK_EX`, it can also be bit-wise OR'd with `LOCK_NB` to avoid blocking on lock acquisition. If `LOCK_NB` is used and the lock cannot be acquired, an `IOError` will be raised and the exception will have an *errno* attribute set to `EACCES` or `EAGAIN` (depending on the operating system; for portability, check for both values). On at least some systems, `LOCK_EX` can only be used if the file descriptor refers to a file opened for writing.

length is the number of bytes to lock, *start* is the byte offset at which the lock starts, relative to *whence*, and *whence* is as with `fileobj.seek()`, specifically:

- 0 – relative to the start of the file (SEEK_SET)
- 1 – relative to the current buffer position (SEEK_CUR)
- 2 – relative to the end of the file (SEEK_END)

The default for *start* is 0, which means to start at the beginning of the file. The default for *length* is 0 which means to lock to the end of the file. The default for *whence* is also 0.

Examples (all on a SVR4 compliant system):

```
import struct, fcntl, os

f = open(...)
rv = fcntl.fcntl(f, fcntl.F_SETFL, os.O_NDELAY)

lockdata = struct.pack('hhllhh', fcntl.F_WRLCK, 0, 0, 0, 0, 0)
rv = fcntl.fcntl(f, fcntl.F_SETLKW, lockdata)
```

Note that in the first example the return value variable *rv* will hold an integer value; in the second example it will hold a string value. The structure lay-out for the *lockdata* variable is system dependent — therefore using the `flock()` call may be better.

See Also:

[Module os](#) (section 14.1):

If the locking flags `O_SHLOCK` and `O_EXLOCK` are present in the `os` module, the `os.open()` function provides a more platform-independent alternative to the `lockf()` and `flock()` functions.

16.11 pipes — Interface to shell pipelines

The `pipes` module defines a class to abstract the concept of a *pipeline* — a sequence of converters from one file to another.

Because the module uses `/bin/sh` command lines, a POSIX or compatible shell for `os.system()` and `os.popen()` is required.

The `pipes` module defines the following class:

```
class Template()
    An abstraction of a pipeline.
```

Example:

```
>>> import pipes
>>> t=pipes.Template()
>>> t.append('tr a-z A-Z', '--')
>>> f=t.open('/tmp/1', 'w')
>>> f.write('hello world')
>>> f.close()
>>> open('/tmp/1').read()
'HELLO WORLD'
```

16.11.1 Template Objects

Template objects following methods:

reset ()

Restore a pipeline template to its initial state.

clone ()

Return a new, equivalent, pipeline template.

debug (*flag*)

If *flag* is true, turn debugging on. Otherwise, turn debugging off. When debugging is on, commands to be executed are printed, and the shell is given `set -x` command to be more verbose.

append (*cmd*, *kind*)

Append a new action at the end. The *cmd* variable must be a valid bourne shell command. The *kind* variable consists of two letters.

The first letter can be either of `'-'` (which means the command reads its standard input), `'f'` (which means the command reads a given file on the command line) or `'.'` (which means the command reads no input, and hence must be first.)

Similarly, the second letter can be either of `'-'` (which means the command writes to standard output), `'f'` (which means the command writes a file on the command line) or `'.'` (which means the command does not write anything, and hence must be last.)

prepend (*cmd*, *kind*)

Add a new action at the beginning. See `append()` for explanations of the arguments.

open (*file*, *mode*)

Return a file-like object, open to *file*, but read from or written to by the pipeline. Note that only one of `'r'`, `'w'` may be given.

copy (*infile*, *outfile*)

Copy *infile* to *outfile* through the pipe.

16.12 `posixfile` — File-like objects with locking support

Deprecated since release 1.5. The locking operation that this module provides is done better and more portably by the `fcntl.lockf()` call.

This module implements some additional functionality over the built-in file objects. In particular, it implements file locking, control over the file flags, and an easy interface to duplicate the file object. The module defines a new file object, the `posixfile` object. It has all the standard file object methods and adds the methods described below. This module only works for certain flavors of UNIX, since it uses `fcntl.fcntl()` for file locking.

To instantiate a `posixfile` object, use the `open()` function in the `posixfile` module. The resulting object looks and feels roughly the same as a standard file object.

The `posixfile` module defines the following constants:

SEEK_SET

Offset is calculated from the start of the file.

SEEK_CUR

Offset is calculated from the current position in the file.

SEEK_END

Offset is calculated from the end of the file.

The `posixfile` module defines the following functions:

open (*filename* [, *mode* [, *bufsize*]])

Create a new posixfile object with the given filename and mode. The *filename*, *mode* and *bufsize* arguments are interpreted the same way as by the built-in `open()` function.

fileopen (*fileobject*)

Create a new posixfile object with the given standard file object. The resulting object has the same filename and mode as the original file object.

The posixfile object defines the following additional methods:

lock (*fmt*, [*len* [, *start* [, *whence*]]])

Lock the specified section of the file that the file object is referring to. The format is explained below in a table. The *len* argument specifies the length of the section that should be locked. The default is 0. *start* specifies the starting offset of the section, where the default is 0. The *whence* argument specifies where the offset is relative to. It accepts one of the constants `SEEK_SET`, `SEEK_CUR` or `SEEK_END`. The default is `SEEK_SET`. For more information about the arguments refer to the *fcntl(2)* manual page on your system.

flags ([*flags*])

Set the specified flags for the file that the file object is referring to. The new flags are ORed with the old flags, unless specified otherwise. The format is explained below in a table. Without the *flags* argument a string indicating the current flags is returned (this is the same as the '?' modifier). For more information about the flags refer to the *fcntl(2)* manual page on your system.

dup ()

Duplicate the file object and the underlying file pointer and file descriptor. The resulting object behaves as if it were newly opened.

dup2 (*fd*)

Duplicate the file object and the underlying file pointer and file descriptor. The new object will have the given file descriptor. Otherwise the resulting object behaves as if it were newly opened.

file ()

Return the standard file object that the posixfile object is based on. This is sometimes necessary for functions that insist on a standard file object.

All methods raise `IOError` when the request fails.

Format characters for the `lock()` method have the following meaning:

Format	Meaning
'u'	unlock the specified region
'r'	request a read lock for the specified section
'w'	request a write lock for the specified section

In addition the following modifiers can be added to the format:

Modifier	Meaning	Notes
' '	wait until the lock has been granted	
'?'	return the first lock conflicting with the requested lock, or <code>None</code> if there is no conflict.	(1)

Note:

(1) The lock returned is in the format (*mode*, *len*, *start*, *whence*, *pid*) where *mode* is a character representing the type of lock ('r' or 'w'). This modifier prevents a request from being granted; it is for query purposes only.

Format characters for the `flags()` method have the following meanings:

Format	Meaning
'a'	append only flag
'c'	close on exec flag
'n'	no delay flag (also called non-blocking flag)
's'	synchronization flag

In addition the following modifiers can be added to the format:

Modifier	Meaning	Notes
'!'	turn the specified flags 'off', instead of the default 'on'	(1)
'='	replace the flags, instead of the default 'OR' operation	(1)
'?'	return a string in which the characters represent the flags that are set.	(2)

Notes:

- (1) The '!' and '=' modifiers are mutually exclusive.
- (2) This string represents the flags after they may have been altered by the same call.

Examples:

```
import posixfile

file = posixfile.open('/tmp/test', 'w')
file.lock('w|')
...
file.lock('u')
file.close()
```

16.13 resource — Resource usage information

This module provides basic mechanisms for measuring and controlling system resources utilized by a program.

Symbolic constants are used to specify particular system resources and to request usage information about either the current process or its children.

A single exception is defined for errors:

exception error

The functions described below may raise this error if the underlying system call failures unexpectedly.

16.13.1 Resource Limits

Resources usage can be limited using the `setrlimit()` function described below. Each resource is controlled by a pair of limits: a soft limit and a hard limit. The soft limit is the current limit, and may be lowered or raised by a process over time. The soft limit can never exceed the hard limit. The hard limit can be lowered to any value greater than the soft limit, but not raised. (Only processes with the effective UID of the super-user can raise a hard limit.)

The specific resources that can be limited are system dependent. They are described in the `getrlimit(2)` man page. The resources listed below are supported when the underlying operating system supports them; resources which cannot be checked or controlled by the operating system are not defined in this module for those platforms.

getrlimit (*resource*)

Returns a tuple (*soft*, *hard*) with the current soft and hard limits of *resource*. Raises `ValueError` if an invalid resource is specified, or `error` if the underlying system call fails unexpectedly.

setrlimit (*resource*, *limits*)

Sets new limits of consumption of *resource*. The *limits* argument must be a tuple (*soft*, *hard*) of two integers describing the new limits. A value of `-1` can be used to specify the maximum possible upper limit.

Raises `ValueError` if an invalid resource is specified, if the new soft limit exceeds the hard limit, or if a process tries to raise its hard limit (unless the process has an effective UID of super-user). Can also raise `error` if the underlying system call fails.

These symbols define resources whose consumption can be controlled using the `setrlimit()` and `getrlimit()` functions described below. The values of these symbols are exactly the constants used by C programs.

The UNIX man page for `getrlimit(2)` lists the available resources. Note that not all systems use the same symbol or same value to denote the same resource. This module does not attempt to mask platform differences — symbols not defined for a platform will not be available from this module on that platform.

RLIMIT_CORE

The maximum size (in bytes) of a core file that the current process can create. This may result in the creation of a partial core file if a larger core would be required to contain the entire process image.

RLIMIT_CPU

The maximum amount of processor time (in seconds) that a process can use. If this limit is exceeded, a `SIGXCPU` signal is sent to the process. (See the [signal](#) module documentation for information about how to catch this signal and do something useful, e.g. flush open files to disk.)

RLIMIT_FSIZE

The maximum size of a file which the process may create. This only affects the stack of the main thread in a multi-threaded process.

RLIMIT_DATA

The maximum size (in bytes) of the process's heap.

RLIMIT_STACK

The maximum size (in bytes) of the call stack for the current process.

RLIMIT_RSS

The maximum resident set size that should be made available to the process.

RLIMIT_NPROC

The maximum number of processes the current process may create.

RLIMIT_NOFILE

The maximum number of open file descriptors for the current process.

RLIMIT_OFILE

The BSD name for `RLIMIT_NOFILE`.

RLIMIT_MEMLOCK

The maximum address space which may be locked in memory.

RLIMIT_VMEM

The largest area of mapped memory which the process may occupy.

RLIMIT_AS

The maximum area (in bytes) of address space which may be taken by the process.

16.13.2 Resource Usage

These functions are used to retrieve resource usage information:

getrusage (*who*)

This function returns an object that describes the resources consumed by either the current process or its children, as specified by the *who* parameter. The *who* parameter should be specified using one of the `RUSAGE_*` constants described below.

The fields of the return value each describe how a particular system resource has been used, e.g. amount of time spent running in user mode or number of times the process was swapped out of main memory. Some values are dependent on the clock tick interval, e.g. the amount of memory the process is using.

For backward compatibility, the return value is also accessible as a tuple of 16 elements.

The fields `ru_utime` and `ru_stime` of the return value are floating point values representing the amount of time spent executing in user mode and the amount of time spent executing in system mode, respectively. The remaining values are integers. Consult the *getrusage*(2) man page for detailed information about these values. A brief summary is presented here:

Index	Field	Resource
0	<code>ru_utime</code>	time in user mode (float)
1	<code>ru_stime</code>	time in system mode (float)
2	<code>ru_maxrss</code>	maximum resident set size
3	<code>ru_ixrss</code>	shared memory size
4	<code>ru_idrss</code>	unshared memory size
5	<code>ru_isrss</code>	unshared stack size
6	<code>ru_minflt</code>	page faults not requiring I/O
7	<code>ru_majflt</code>	page faults requiring I/O
8	<code>ru_nswap</code>	number of swap outs
9	<code>ru_inblock</code>	block input operations
10	<code>ru_oublock</code>	block output operations
11	<code>ru_msgsnd</code>	messages sent
12	<code>ru_msgrcv</code>	messages received
13	<code>ru_nsignals</code>	signals received
14	<code>ru_nvcsw</code>	voluntary context switches
15	<code>ru_nivcsw</code>	involuntary context switches

This function will raise a `ValueError` if an invalid *who* parameter is specified. It may also raise error exception in unusual circumstances.

Changed in version 2.3: Added access to values as attributes of the returned object.

getpagesize ()

Returns the number of bytes in a system page. (This need not be the same as the hardware page size.) This function is useful for determining the number of bytes of memory a process is using. The third element of the tuple returned by `getrusage ()` describes memory usage in pages; multiplying by page size produces number of bytes.

The following `RUSAGE_*` symbols are passed to the `getrusage ()` function to specify which processes information should be provided for.

RUSAGE_SELF

`RUSAGE_SELF` should be used to request information pertaining only to the process itself.

RUSAGE_CHILDREN

Pass to `getrusage ()` to request resource information for child processes of the calling process.

RUSAGE_BOTH

Pass to `getrusage ()` to request resources consumed by both the current process and child processes. May not be available on all systems.

16.14 `nis` — Interface to Sun's NIS (Yellow Pages)

The `nis` module gives a thin wrapper around the NIS library, useful for central administration of several hosts.

Because NIS exists only on UNIX systems, this module is only available for UNIX.

The `nis` module defines the following functions:

match (*key*, *mapname*[, *domain*=*default_domain*])

Return the match for *key* in map *mapname*, or raise an error (`nis.error`) if there is none. Both should be strings, *key* is 8-bit clean. Return value is an arbitrary array of bytes (may contain NULL and other joys).

Note that *mapname* is first checked if it is an alias to another name.

Changed in version 2.5: The *domain* argument allows to override the NIS domain used for the lookup. If unspecified, lookup is in the default NIS domain.

cat (*mapname*[, *domain*=*default_domain*])

Return a dictionary mapping *key* to *value* such that `match(key, mapname) == value`. Note that both keys and values of the dictionary are arbitrary arrays of bytes.

Note that *mapname* is first checked if it is an alias to another name.

Changed in version 2.5: The *domain* argument allows to override the NIS domain used for the lookup. If unspecified, lookup is in the default NIS domain.

maps ([*domain*=*default_domain*])

Return a list of all valid maps.

Changed in version 2.5: The *domain* argument allows to override the NIS domain used for the lookup. If unspecified, lookup is in the default NIS domain.

get_default_domain ()

Return the system default NIS domain. New in version 2.5.

The `nis` module defines the following exception:

exception error

An error raised when a NIS function returns an error code.

16.15 syslog — UNIX syslog library routines

This module provides an interface to the UNIX `syslog` library routines. Refer to the UNIX manual pages for a detailed description of the `syslog` facility.

The module defines the following functions:

syslog ([*priority*,] *message*)

Send the string *message* to the system logger. A trailing newline is added if necessary. Each message is tagged with a priority composed of a *facility* and a *level*. The optional *priority* argument, which defaults to `LOG_INFO`, determines the message priority. If the facility is not encoded in *priority* using logical-or (`LOG_INFO | LOG_USER`), the value given in the `openlog()` call is used.

openlog (*ident*[, *logopt*[, *facility*]])

Logging options other than the defaults can be set by explicitly opening the log file with `openlog()` prior to calling `syslog()`. The defaults are (usually) *ident* = `'syslog'`, *logopt* = 0, *facility* = `LOG_USER`. The *ident* argument is a string which is prepended to every message. The optional *logopt* argument is a bit field - see below for possible values to combine. The optional *facility* argument sets the default facility for messages which do not have a facility explicitly encoded.

closelog ()

Close the log file.

setlogmask (*maskpri*)

Set the priority mask to *maskpri* and return the previous mask value. Calls to `syslog()` with a priority level

not set in *maskpri* are ignored. The default is to log all priorities. The function `LOG_MASK(pri)` calculates the mask for the individual priority *pri*. The function `LOG_UPTO(pri)` calculates the mask for all priorities up to and including *pri*.

The module defines the following constants:

Priority levels (high to low): `LOG_EMERG`, `LOG_ALERT`, `LOG_CRIT`, `LOG_ERR`, `LOG_WARNING`, `LOG_NOTICE`, `LOG_INFO`, `LOG_DEBUG`.

Facilities: `LOG_KERN`, `LOG_USER`, `LOG_MAIL`, `LOG_DAEMON`, `LOG_AUTH`, `LOG_LPR`, `LOG_NEWS`, `LOG_UUCP`, `LOG_CRON` and `LOG_LOCAL0` to `LOG_LOCAL7`.

Log options: `LOG_PID`, `LOG_CONS`, `LOG_NDELAY`, `LOG_NOWAIT` and `LOG_PERROR` if defined in `<syslog.h>`.

16.16 commands — Utilities for running commands

The `commands` module contains wrapper functions for `os.popen()` which take a system command as a string and return any output generated by the command and, optionally, the exit status.

The `subprocess` module provides more powerful facilities for spawning new processes and retrieving their results. Using the `subprocess` module is preferable to using the `commands` module.

The `commands` module defines the following functions:

getstatusoutput (*cmd*)

Execute the string *cmd* in a shell with `os.popen()` and return a 2-tuple (*status*, *output*). *cmd* is actually run as `{cmd ; }2>&1`, so that the returned output will contain output or error messages. A trailing newline is stripped from the output. The exit status for the command can be interpreted according to the rules for the C function `wait()`.

getoutput (*cmd*)

Like `getstatusoutput()`, except the exit status is ignored and the return value is a string containing the command's output.

getstatus (*file*)

Return the output of `'ls -ld file'` as a string. This function uses the `getoutput()` function, and properly escapes backslashes and dollar signs in the argument.

Example:

```
>>> import commands
>>> commands.getstatusoutput('ls /bin/ls')
(0, '/bin/ls')
>>> commands.getstatusoutput('cat /bin/junk')
(256, 'cat: /bin/junk: No such file or directory')
>>> commands.getstatusoutput('/bin/junk')
(256, 'sh: /bin/junk: not found')
>>> commands.getoutput('ls /bin/ls')
'/bin/ls'
>>> commands.getstatus('/bin/ls')
'-rwxr-xr-x  1 root          13352 Oct 14  1994 /bin/ls'
```

See Also:

[Module subprocess](#) (section 17.1):

Module for spawning and managing subprocesses.

Interprocess Communication and Networking

The modules described in this chapter provide mechanisms for different processes to communicate.

Some modules only work for two processes that are on the same machine, e.g. `signal` and `subprocess`. Other modules support networking protocols that two or more processes can use to communicate across machines.

The list of modules described in this chapter is:

<code>subprocess</code>	Subprocess management.
<code>socket</code>	Low-level networking interface.
<code>signal</code>	Set handlers for asynchronous events.
<code>popen2</code>	Subprocesses with accessible standard I/O streams.
<code>asyncore</code>	A base class for developing asynchronous socket handling services.
<code>asynchat</code>	Support for asynchronous command/response protocols.

17.1 `subprocess` — Subprocess management

New in version 2.4.

The `subprocess` module allows you to spawn new processes, connect to their input/output/error pipes, and obtain their return codes. This module intends to replace several other, older modules and functions, such as:

```
os.system
os.spawn*
os.popen*
popen2.*
commands.*
```

Information about how the `subprocess` module can be used to replace these modules and functions can be found in the following sections.

17.1.1 Using the `subprocess` Module

This module defines one class called `Popen`:

```
class Popen (args, bufsize=0, executable=None, stdin=None, stdout=None, stderr=None, preexec_fn=None, close_  
fds=False, shell=False, cwd=None, env=None, universal_newlines=False, startupinfo=None, creation_  
flags=0)
```

Arguments are:

args should be a string, or a sequence of program arguments. The program to execute is normally the first item in the *args* sequence or string, but can be explicitly set by using the executable argument.

On UNIX, with *shell=False* (default): In this case, the `Popen` class uses `os.execvp()` to execute the child program. *args* should normally be a sequence. A string will be treated as a sequence with the string as the only item (the program to execute).

On UNIX, with *shell=True*: If *args* is a string, it specifies the command string to execute through the shell. If *args* is a sequence, the first item specifies the command string, and any additional items will be treated as additional shell arguments.

On Windows: the `Popen` class uses `CreateProcess()` to execute the child program, which operates on strings. If *args* is a sequence, it will be converted to a string using the `list2cmdline` method. Please note that not all MS Windows applications interpret the command line the same way: `list2cmdline` is designed for applications using the same rules as the MS C runtime.

bufsize, if given, has the same meaning as the corresponding argument to the built-in `open()` function: 0 means unbuffered, 1 means line buffered, any other positive value means use a buffer of (approximately) that size. A negative *bufsize* means to use the system default, which usually means fully buffered. The default value for *bufsize* is 0 (unbuffered).

The *executable* argument specifies the program to execute. It is very seldom needed: Usually, the program to execute is defined by the *args* argument. If *shell=True*, the *executable* argument specifies which shell to use. On UNIX, the default shell is `'/bin/sh'`. On Windows, the default shell is specified by the COMSPEC environment variable.

stdin, *stdout* and *stderr* specify the executed programs' standard input, standard output and standard error file handles, respectively. Valid values are `PIPE`, an existing file descriptor (a positive integer), an existing file object, and `None`. `PIPE` indicates that a new pipe to the child should be created. With `None`, no redirection will occur; the child's file handles will be inherited from the parent. Additionally, *stderr* can be `STDOUT`, which indicates that the *stderr* data from the applications should be captured into the same file handle as for *stdout*.

If *preexec_fn* is set to a callable object, this object will be called in the child process just before the child is executed. (UNIX only)

If *close_fds* is true, all file descriptors except 0, 1 and 2 will be closed before the child process is executed. (UNIX only)

If *shell* is `True`, the specified command will be executed through the shell.

If *cwd* is not `None`, the child's current directory will be changed to *cwd* before it is executed. Note that this directory is not considered when searching the executable, so you can't specify the program's path relative to *cwd*.

If *env* is not `None`, it defines the environment variables for the new process.

If *universal_newlines* is `True`, the file objects *stdout* and *stderr* are opened as text files, but lines may be terminated by any of `'\n'`, the UNIX end-of-line convention, `'\r'`, the Macintosh convention or `'\r\n'`, the Windows convention. All of these external representations are seen as `'\n'` by the Python program. **Note:** This feature is only available if Python is built with universal newline support (the default). Also, the *newlines* attribute of the file objects *stdout*, *stdin* and *stderr* are not updated by the `communicate()` method.

The *startupinfo* and *creationflags*, if given, will be passed to the underlying `CreateProcess()` function. They can specify things such as appearance of the main window and priority for the new process. (Windows only)

Convenience Functions

This module also defines two shortcut functions:

call (**popenargs*, ***kwargs*)

Run command with arguments. Wait for command to complete, then return the `returncode` attribute.

The arguments are the same as for the Popen constructor. Example:

```
retcode = call(["ls", "-l"])
```

check_call (*popenargs, **kwargs)

Run command with arguments. Wait for command to complete. If the exit code was zero then return, otherwise raise `CalledProcessError`. The `CalledProcessError` object will have the return code in the `returncode` attribute.

The arguments are the same as for the Popen constructor. Example:

```
check_call(["ls", "-l"])
```

New in version 2.5.

Exceptions

Exceptions raised in the child process, before the new program has started to execute, will be re-raised in the parent. Additionally, the exception object will have one extra attribute called `child_traceback`, which is a string containing traceback information from the child's point of view.

The most common exception raised is `OSError`. This occurs, for example, when trying to execute a non-existent file. Applications should prepare for `OSError` exceptions.

A `ValueError` will be raised if `Popen` is called with invalid arguments.

`check_call()` will raise `CalledProcessError`, if the called process returns a non-zero return code.

Security

Unlike some other popen functions, this implementation will never call `/bin/sh` implicitly. This means that all characters, including shell metacharacters, can safely be passed to child processes.

17.1.2 Popen Objects

Instances of the `Popen` class have the following methods:

poll ()

Check if child process has terminated. Returns `returncode` attribute.

wait ()

Wait for child process to terminate. Returns `returncode` attribute.

communicate (input=None)

Interact with process: Send data to stdin. Read data from stdout and stderr, until end-of-file is reached. Wait for process to terminate. The optional *input* argument should be a string to be sent to the child process, or `None`, if no data should be sent to the child.

`communicate()` returns a tuple (stdout, stderr).

Note: The data read is buffered in memory, so do not use this method if the data size is large or unlimited.

The following attributes are also available:

stdin

If the *stdin* argument is `PIPE`, this attribute is a file object that provides input to the child process. Otherwise, it is `None`.

stdout

If the *stdout* argument is `PIPE`, this attribute is a file object that provides output from the child process. Otherwise, it is `None`.

stderr

If the *stderr* argument is `PIPE`, this attribute is file object that provides error output from the child process. Otherwise, it is `None`.

pid

The process ID of the child process.

returncode

The child return code. A `None` value indicates that the process hasn't terminated yet. A negative value `-N` indicates that the child was terminated by signal `N` (UNIX only).

17.1.3 Replacing Older Functions with the subprocess Module

In this section, "`a ==> b`" means that `b` can be used as a replacement for `a`.

Note: All functions in this section fail (more or less) silently if the executed program cannot be found; this module raises an `OSError` exception.

In the following examples, we assume that the `subprocess` module is imported with "`from subprocess import *`".

Replacing `/bin/sh` shell backquote

```
output='mycmd myarg'
==>
output = Popen(["mycmd", "myarg"], stdout=PIPE).communicate()[0]
```

Replacing shell pipe line

```
output='dmesg | grep hda'
==>
p1 = Popen(["dmesg"], stdout=PIPE)
p2 = Popen(["grep", "hda"], stdin=p1.stdout, stdout=PIPE)
output = p2.communicate()[0]
```

Replacing `os.system()`

```
sts = os.system("mycmd" + " myarg")
==>
p = Popen("mycmd" + " myarg", shell=True)
sts = os.waitpid(p.pid, 0)
```

Notes:

- Calling the program through the shell is usually not required.

- It's easier to look at the `returncode` attribute than the exit status.

A more realistic example would look like this:

```
try:
    retcode = call("mycmd" + " myarg", shell=True)
    if retcode < 0:
        print >>sys.stderr, "Child was terminated by signal", -retcode
    else:
        print >>sys.stderr, "Child returned", retcode
except OSError, e:
    print >>sys.stderr, "Execution failed:", e
```

Replacing `os.spawn*`

`P_NOWAIT` example:

```
pid = os.spawnlp(os.P_NOWAIT, "/bin/mycmd", "mycmd", "myarg")
==>
pid = Popen(["/bin/mycmd", "myarg"]).pid
```

`P_WAIT` example:

```
retcode = os.spawnlp(os.P_WAIT, "/bin/mycmd", "mycmd", "myarg")
==>
retcode = call(["/bin/mycmd", "myarg"])
```

Vector example:

```
os.spawnvp(os.P_NOWAIT, path, args)
==>
Popen([path] + args[1:])
```

Environment example:

```
os.spawnlpe(os.P_NOWAIT, "/bin/mycmd", "mycmd", "myarg", env)
==>
Popen(["/bin/mycmd", "myarg"], env={"PATH": "/usr/bin"})
```

Replacing `os.popen*`

```
pipe = os.popen(cmd, mode='r', bufsize)
==>
pipe = Popen(cmd, shell=True, bufsize=bufsize, stdout=PIPE).stdout
```

```

pipe = os.popen(cmd, mode='w', bufsize)
==>
pipe = Popen(cmd, shell=True, bufsize=bufsize, stdin=PIPE).stdin

(child_stdin, child_stdout) = os.popen2(cmd, mode, bufsize)
==>
p = Popen(cmd, shell=True, bufsize=bufsize,
          stdin=PIPE, stdout=PIPE, close_fds=True)
(child_stdin, child_stdout) = (p.stdin, p.stdout)

(child_stdin,
 child_stdout,
 child_stderr) = os.popen3(cmd, mode, bufsize)
==>
p = Popen(cmd, shell=True, bufsize=bufsize,
          stdin=PIPE, stdout=PIPE, stderr=PIPE, close_fds=True)
(child_stdin,
 child_stdout,
 child_stderr) = (p.stdin, p.stdout, p.stderr)

(child_stdin, child_stdout_and_stderr) = os.popen4(cmd, mode, bufsize)
==>
p = Popen(cmd, shell=True, bufsize=bufsize,
          stdin=PIPE, stdout=PIPE, stderr=STDOUT, close_fds=True)
(child_stdin, child_stdout_and_stderr) = (p.stdin, p.stdout)

```

Replacing popen2.*

Note: If the `cmd` argument to `popen2` functions is a string, the command is executed through `/bin/sh`. If it is a list, the command is directly executed.

```

(child_stdout, child_stdin) = popen2.popen2("somestring", bufsize, mode)
==>
p = Popen(["somestring"], shell=True, bufsize=bufsize,
          stdin=PIPE, stdout=PIPE, close_fds=True)
(child_stdout, child_stdin) = (p.stdout, p.stdin)

(child_stdout, child_stdin) = popen2.popen2(["mycmd", "myarg"], bufsize, mode)
==>
p = Popen(["mycmd", "myarg"], bufsize=bufsize,
          stdin=PIPE, stdout=PIPE, close_fds=True)
(child_stdout, child_stdin) = (p.stdout, p.stdin)

```

The `popen2.Popen3` and `popen2.Popen4` basically works as `subprocess.Popen`, except that:

- `subprocess.Popen` raises an exception if the execution fails

- the `capturestderr` argument is replaced with the `stderr` argument.
- `stdin=PIPE` and `stdout=PIPE` must be specified.
- `popen2` closes all file descriptors by default, but you have to specify `close_fds=True` with `subprocess.Popen`.

17.2 `socket` — Low-level networking interface

This module provides access to the BSD *socket* interface. It is available on all modern UNIX systems, Windows, MacOS, BeOS, OS/2, and probably additional platforms. **Note:** Some behavior may be platform dependent, since calls are made to the operating system socket APIs.

For an introduction to socket programming (in C), see the following papers: *An Introductory 4.3BSD Interprocess Communication Tutorial*, by Stuart Sechrest and *An Advanced 4.3BSD Interprocess Communication Tutorial*, by Samuel J. Leffler et al, both in the *UNIX Programmer's Manual, Supplementary Documents 1* (sections PS1:7 and PS1:8). The platform-specific reference material for the various socket-related system calls are also a valuable source of information on the details of socket semantics. For UNIX, refer to the manual pages; for Windows, see the WinSock (or Winsock 2) specification. For IPv6-ready APIs, readers may want to refer to RFC 2553 titled *Basic Socket Interface Extensions for IPv6*.

The Python interface is a straightforward transliteration of the UNIX system call and library interface for sockets to Python's object-oriented style: the `socket()` function returns a *socket object* whose methods implement the various socket system calls. Parameter types are somewhat higher-level than in the C interface: as with `read()` and `write()` operations on Python files, buffer allocation on receive operations is automatic, and buffer length is implicit on send operations.

Socket addresses are represented as follows: A single string is used for the `AF_UNIX` address family. A pair (*host*, *port*) is used for the `AF_INET` address family, where *host* is a string representing either a hostname in Internet domain notation like `'daring.cwi.nl'` or an IPv4 address like `'100.50.200.5'`, and *port* is an integral port number. For `AF_INET6` address family, a four-tuple (*host*, *port*, *flowinfo*, *scopeid*) is used, where *flowinfo* and *scopeid* represents `sin6_flowinfo` and `sin6_scope_id` member in `struct sockaddr_in6` in C. For `socket` module methods, *flowinfo* and *scopeid* can be omitted just for backward compatibility. Note, however, omission of *scopeid* can cause problems in manipulating scoped IPv6 addresses. Other address families are currently not supported. The address format required by a particular socket object is automatically selected based on the address family specified when the socket object was created.

For IPv4 addresses, two special forms are accepted instead of a host address: the empty string represents `INADDR_ANY`, and the string `'<broadcast>'` represents `INADDR_BROADCAST`. The behavior is not available for IPv6 for backward compatibility, therefore, you may want to avoid these if you intend to support IPv6 with your Python programs.

If you use a hostname in the *host* portion of IPv4/v6 socket address, the program may show a nondeterministic behavior, as Python uses the first address returned from the DNS resolution. The socket address will be resolved differently into an actual IPv4/v6 address, depending on the results from DNS resolution and/or the host configuration. For deterministic behavior use a numeric address in *host* portion.

New in version 2.5: `AF_NETLINK` sockets are represented as pairs *pid*, *groups*.

All errors raise exceptions. The normal exceptions for invalid argument types and out-of-memory conditions can be raised; errors related to socket or address semantics raise the error `socket.error`.

Non-blocking mode is supported through `setblocking()`. A generalization of this based on timeouts is supported through `settimeout()`.

The module `socket` exports the following constants and functions:

exception `error`

This exception is raised for socket-related errors. The accompanying value is either a string telling what went

wrong or a pair (*errno*, *string*) representing an error returned by a system call, similar to the value accompanying `os.error`. See the module `errno`, which contains names for the error codes defined by the underlying operating system.

exception `herror`

This exception is raised for address-related errors, i.e. for functions that use *h_errno* in the C API, including `gethostbyname_ex()` and `gethostbyaddr()`.

The accompanying value is a pair (*h_errno*, *string*) representing an error returned by a library call. *string* represents the description of *h_errno*, as returned by the `hstrerror()` C function.

exception `gaierror`

This exception is raised for address-related errors, for `getaddrinfo()` and `getnameinfo()`. The accompanying value is a pair (*error*, *string*) representing an error returned by a library call. *string* represents the description of *error*, as returned by the `gai_strerror()` C function. The *error* value will match one of the `EAI_*` constants defined in this module.

exception `timeout`

This exception is raised when a timeout occurs on a socket which has had timeouts enabled via a prior call to `settimeout()`. The accompanying value is a string whose value is currently always “timed out”. New in version 2.3.

`AF_UNIX`

`AF_INET`

`AF_INET6`

These constants represent the address (and protocol) families, used for the first argument to `socket()`. If the `AF_UNIX` constant is not defined then this protocol is unsupported.

`SOCK_STREAM`

`SOCK_DGRAM`

`SOCK_RAW`

`SOCK_RDM`

`SOCK_SEQPACKET`

These constants represent the socket types, used for the second argument to `socket()`. (Only `SOCK_STREAM` and `SOCK_DGRAM` appear to be generally useful.)

`SO_*`

`SOMAXCONN`

`MSG_*`

`SOL_*`

`IPPROTO_*`

`IPPORT_*`

`INADDR_*`

`IP_*`

`IPV6_*`

`EAI_*`

`AI_*`

`NI_*`

`TCP_*`

Many constants of these forms, documented in the UNIX documentation on sockets and/or the IP protocol, are also defined in the `socket` module. They are generally used in arguments to the `setsockopt()` and `getsockopt()` methods of socket objects. In most cases, only those symbols that are defined in the UNIX header files are defined; for a few symbols, default values are provided.

`has_ipv6`

This constant contains a boolean value which indicates if IPv6 is supported on this platform. New in version 2.3.

`getaddrinfo` (*host*, *port*[, *family*[, *socktype*[, *proto*[, *flags*]]]])

Resolves the *host/port* argument, into a sequence of 5-tuples that contain all the necessary argument for the sockets manipulation. *host* is a domain name, a string representation of IPv4/v6 address or `None`. *port* is a string service name (like `'http'`), a numeric port number or `None`.

The rest of the arguments are optional and must be numeric if specified. For *host* and *port*, by passing either an empty string or `None`, you can pass `NULL` to the C API. The `getaddrinfo()` function returns a list of 5-tuples with the following structure:

(family, socktype, proto, canonname, sockaddr)

family, *socktype*, *proto* are all integer and are meant to be passed to the `socket()` function. *canonname* is a string representing the canonical name of the *host*. It can be a numeric IPv4/v6 address when `AI_CANONNAME` is specified for a numeric *host*. *sockaddr* is a tuple describing a socket address, as described above. See the source for the [httplib](#) and other library modules for a typical usage of the function. New in version 2.2.

getfqdn(*[name]*)

Return a fully qualified domain name for *name*. If *name* is omitted or empty, it is interpreted as the local host. To find the fully qualified name, the hostname returned by `gethostbyaddr()` is checked, then aliases for the host, if available. The first name which includes a period is selected. In case no fully qualified domain name is available, the hostname as returned by `gethostname()` is returned. New in version 2.0.

gethostbyname(*hostname*)

Translate a host name to IPv4 address format. The IPv4 address is returned as a string, such as `'100.50.200.5'`. If the host name is an IPv4 address itself it is returned unchanged. See `gethostbyname_ex()` for a more complete interface. `gethostbyname()` does not support IPv6 name resolution, and `getaddrinfo()` should be used instead for IPv4/v6 dual stack support.

gethostbyname_ex(*hostname*)

Translate a host name to IPv4 address format, extended interface. Return a triple (*hostname*, *aliaslist*, *ipaddrlist*) where *hostname* is the primary host name responding to the given *ip_address*, *aliaslist* is a (possibly empty) list of alternative host names for the same address, and *ipaddrlist* is a list of IPv4 addresses for the same interface on the same host (often but not always a single address). `gethostbyname_ex()` does not support IPv6 name resolution, and `getaddrinfo()` should be used instead for IPv4/v6 dual stack support.

gethostname()

Return a string containing the hostname of the machine where the Python interpreter is currently executing. If you want to know the current machine's IP address, you may want to use `gethostbyname(gethostname())`. This operation assumes that there is a valid address-to-host mapping for the host, and the assumption does not always hold. Note: `gethostname()` doesn't always return the fully qualified domain name; use `getfqdn()` (see above).

gethostbyaddr(*ip_address*)

Return a triple (*hostname*, *aliaslist*, *ipaddrlist*) where *hostname* is the primary host name responding to the given *ip_address*, *aliaslist* is a (possibly empty) list of alternative host names for the same address, and *ipaddrlist* is a list of IPv4/v6 addresses for the same interface on the same host (most likely containing only a single address). To find the fully qualified domain name, use the function `getfqdn()`. `gethostbyaddr` supports both IPv4 and IPv6.

getnameinfo(*sockaddr, flags*)

Translate a socket address *sockaddr* into a 2-tuple (*host*, *port*). Depending on the settings of *flags*, the result can contain a fully-qualified domain name or numeric address representation in *host*. Similarly, *port* can contain a string port name or a numeric port number. New in version 2.2.

getprotobyname(*protocolname*)

Translate an Internet protocol name (for example, `'icmp'`) to a constant suitable for passing as the (optional) third argument to the `socket()` function. This is usually only needed for sockets opened in "raw" mode (`SOCK_RAW`); for the normal socket modes, the correct protocol is chosen automatically if the protocol is omitted or zero.

getservbyname(*servicename[, protocolname]*)

Translate an Internet service name and protocol name to a port number for that service. The optional protocol name, if given, should be 'tcp' or 'udp', otherwise any protocol will match.

getservbyport (*port* [, *protocolname*])

Translate an Internet port number and protocol name to a service name for that service. The optional protocol name, if given, should be 'tcp' or 'udp', otherwise any protocol will match.

socket ([*family* [, *type* [, *proto*]]])

Create a new socket using the given address family, socket type and protocol number. The address family should be AF_INET (the default), AF_INET6 or AF_UNIX. The socket type should be SOCK_STREAM (the default), SOCK_DGRAM or perhaps one of the other 'SOCK_' constants. The protocol number is usually zero and may be omitted in that case.

ssl (*sock* [, *keyfile*, *certfile*])

Initiate a SSL connection over the socket *sock*. *keyfile* is the name of a PEM formatted file that contains your private key. *certfile* is a PEM formatted certificate chain file. On success, a new `SSLObject` is returned.

Warning: This does not do any certificate verification!

socketpair ([*family* [, *type* [, *proto*]]])

Build a pair of connected socket objects using the given address family, socket type, and protocol number. Address family, socket type, and protocol number are as for the `socket()` function above. The default family is AF_UNIX if defined on the platform; otherwise, the default is AF_INET. Availability: UNIX. New in version 2.4.

fromfd (*fd*, *family*, *type* [, *proto*])

Duplicate the file descriptor *fd* (an integer as returned by a file object's `fileno()` method) and build a socket object from the result. Address family, socket type and protocol number are as for the `socket()` function above. The file descriptor should refer to a socket, but this is not checked — subsequent operations on the object may fail if the file descriptor is invalid. This function is rarely needed, but can be used to get or set socket options on a socket passed to a program as standard input or output (such as a server started by the UNIX `inetd` daemon). The socket is assumed to be in blocking mode. Availability: UNIX.

ntohl (*x*)

Convert 32-bit integers from network to host byte order. On machines where the host byte order is the same as network byte order, this is a no-op; otherwise, it performs a 4-byte swap operation.

ntohs (*x*)

Convert 16-bit integers from network to host byte order. On machines where the host byte order is the same as network byte order, this is a no-op; otherwise, it performs a 2-byte swap operation.

htonl (*x*)

Convert 32-bit integers from host to network byte order. On machines where the host byte order is the same as network byte order, this is a no-op; otherwise, it performs a 4-byte swap operation.

htons (*x*)

Convert 16-bit integers from host to network byte order. On machines where the host byte order is the same as network byte order, this is a no-op; otherwise, it performs a 2-byte swap operation.

inet_aton (*ip_string*)

Convert an IPv4 address from dotted-quad string format (for example, '123.45.67.89') to 32-bit packed binary format, as a string four characters in length. This is useful when conversing with a program that uses the standard C library and needs objects of type `struct in_addr`, which is the C type for the 32-bit packed binary this function returns.

If the IPv4 address string passed to this function is invalid, `socket.error` will be raised. Note that exactly what is valid depends on the underlying C implementation of `inet_aton()`.

`inet_aton()` does not support IPv6, and `getnameinfo()` should be used instead for IPv4/v6 dual stack support.

inet_ntoa (*packed_ip*)

Convert a 32-bit packed IPv4 address (a string four characters in length) to its standard dotted-quad string representation (for example, '123.45.67.89'). This is useful when conversing with a program that uses the standard C library and needs objects of type `struct in_addr`, which is the C type for the 32-bit packed binary data this function takes as an argument.

If the string passed to this function is not exactly 4 bytes in length, `socket.error` will be raised. `inet_ntoa()` does not support IPv6, and `getnameinfo()` should be used instead for IPv4/v6 dual stack support.

inet_pton (*address_family*, *ip_string*)

Convert an IP address from its family-specific string format to a packed, binary format. `inet_pton()` is useful when a library or network protocol calls for an object of type `struct in_addr` (similar to `inet_aton()`) or `struct in6_addr`.

Supported values for *address_family* are currently `AF_INET` and `AF_INET6`. If the IP address string *ip_string* is invalid, `socket.error` will be raised. Note that exactly what is valid depends on both the value of *address_family* and the underlying implementation of `inet_pton()`.

Availability: UNIX (maybe not all platforms). New in version 2.3.

inet_ntop (*address_family*, *packed_ip*)

Convert a packed IP address (a string of some number of characters) to its standard, family-specific string representation (for example, '7.10.0.5' or '5aef:2b::8') `inet_ntop()` is useful when a library or network protocol returns an object of type `struct in_addr` (similar to `inet_ntoa()`) or `struct in6_addr`.

Supported values for *address_family* are currently `AF_INET` and `AF_INET6`. If the string *packed_ip* is not the correct length for the specified address family, `ValueError` will be raised. A `socket.error` is raised for errors from the call to `inet_ntop()`.

Availability: UNIX (maybe not all platforms). New in version 2.3.

getdefaulttimeout ()

Return the default timeout in floating seconds for new socket objects. A value of `None` indicates that new socket objects have no timeout. When the socket module is first imported, the default is `None`. New in version 2.3.

setdefaulttimeout (*timeout*)

Set the default timeout in floating seconds for new socket objects. A value of `None` indicates that new socket objects have no timeout. When the socket module is first imported, the default is `None`. New in version 2.3.

SocketType

This is a Python type object that represents the socket object type. It is the same as `type(socket(...))`.

See Also:

[Module SocketServer](#) (section 18.18):

Classes that simplify writing network servers.

17.2.1 Socket Objects

Socket objects have the following methods. Except for `makefile()` these correspond to UNIX system calls applicable to sockets.

accept ()

Accept a connection. The socket must be bound to an address and listening for connections. The return value is a pair (*conn*, *address*) where *conn* is a new socket object usable to send and receive data on the connection, and *address* is the address bound to the socket on the other end of the connection.

bind (*address*)

Bind the socket to *address*. The socket must not already be bound. (The format of *address* depends on the address family — see above.) **Note:** This method has historically accepted a pair of parameters for `AF_INET` addresses instead of only a tuple. This was never intentional and is no longer available in Python 2.0 and later.

close()

Close the socket. All future operations on the socket object will fail. The remote end will receive no more data (after queued data is flushed). Sockets are automatically closed when they are garbage-collected.

connect(address)

Connect to a remote socket at *address*. (The format of *address* depends on the address family — see above.)

Note: This method has historically accepted a pair of parameters for `AF_INET` addresses instead of only a tuple. This was never intentional and is no longer available in Python 2.0 and later.

connect_ex(address)

Like `connect(address)`, but return an error indicator instead of raising an exception for errors returned by the C-level `connect()` call (other problems, such as “host not found,” can still raise exceptions). The error indicator is 0 if the operation succeeded, otherwise the value of the `errno` variable. This is useful to support, for example, asynchronous connects. **Note:** This method has historically accepted a pair of parameters for `AF_INET` addresses instead of only a tuple. This was never intentional and is no longer available in Python 2.0 and later.

fileno()

Return the socket’s file descriptor (a small integer). This is useful with `select.select()`.

Under Windows the small integer returned by this method cannot be used where a file descriptor can be used (such as `os.fdopen()`). UNIX does not have this limitation.

getpeername()

Return the remote address to which the socket is connected. This is useful to find out the port number of a remote IPv4/v6 socket, for instance. (The format of the address returned depends on the address family — see above.) On some systems this function is not supported.

getsockname()

Return the socket’s own address. This is useful to find out the port number of an IPv4/v6 socket, for instance. (The format of the address returned depends on the address family — see above.)

getsockopt(level, optname[, buflen])

Return the value of the given socket option (see the UNIX man page `getsockopt(2)`). The needed symbolic constants (`SO_*` etc.) are defined in this module. If *buflen* is absent, an integer option is assumed and its integer value is returned by the function. If *buflen* is present, it specifies the maximum length of the buffer used to receive the option in, and this buffer is returned as a string. It is up to the caller to decode the contents of the buffer (see the optional built-in module `struct` for a way to decode C structures encoded as strings).

listen(backlog)

Listen for connections made to the socket. The *backlog* argument specifies the maximum number of queued connections and should be at least 1; the maximum value is system-dependent (usually 5).

makefile([mode[, bufsize]])

Return a *file object* associated with the socket. (File objects are described in 3.9, “File Objects.”) The file object references a `dup()` ped version of the socket file descriptor, so the file object and socket object may be closed or garbage-collected independently. The socket must be in blocking mode. The optional *mode* and *bufsize* arguments are interpreted the same way as by the built-in `file()` function; see “Built-in Functions” (section 2.1) for more information.

recv(bufsize[, flags])

Receive data from the socket. The return value is a string representing the data received. The maximum amount of data to be received at once is specified by *bufsize*. See the UNIX manual page `recv(2)` for the meaning of the optional argument *flags*; it defaults to zero. **Note:** For best match with hardware and network realities, the value of *bufsize* should be a relatively small power of 2, for example, 4096.

recvfrom(bufsize[, flags])

Receive data from the socket. The return value is a pair (*string*, *address*) where *string* is a string representing the data received and *address* is the address of the socket sending the data. The optional *flags* argument has the same meaning as for `recv()` above. (The format of *address* depends on the address family — see above.)

recvfrom_into (*buffer* [, *nbytes* [, *flags*]])

Receive data from the socket, writing it into *buffer* instead of creating a new string. The return value is a pair (*nbytes*, *address*) where *nbytes* is the number of bytes received and *address* is the address of the socket sending the data. See the UNIX manual page *recv(2)* for the meaning of the optional argument *flags*; it defaults to zero. (The format of *address* depends on the address family — see above.) New in version 2.5.

recv_into (*buffer* [, *nbytes* [, *flags*]])

Receive up to *nbytes* bytes from the socket, storing the data into a buffer rather than creating a new string. If *nbytes* is not specified (or 0), receive up to the size available in the given buffer. See the UNIX manual page *recv(2)* for the meaning of the optional argument *flags*; it defaults to zero. New in version 2.5.

send (*string* [, *flags*])

Send data to the socket. The socket must be connected to a remote socket. The optional *flags* argument has the same meaning as for *recv()* above. Returns the number of bytes sent. Applications are responsible for checking that all data has been sent; if only some of the data was transmitted, the application needs to attempt delivery of the remaining data.

sendall (*string* [, *flags*])

Send data to the socket. The socket must be connected to a remote socket. The optional *flags* argument has the same meaning as for *recv()* above. Unlike *send()*, this method continues to send data from *string* until either all data has been sent or an error occurs. None is returned on success. On error, an exception is raised, and there is no way to determine how much data, if any, was successfully sent.

sendto (*string* [, *flags*], *address*)

Send data to the socket. The socket should not be connected to a remote socket, since the destination socket is specified by *address*. The optional *flags* argument has the same meaning as for *recv()* above. Return the number of bytes sent. (The format of *address* depends on the address family — see above.)

setblocking (*flag*)

Set blocking or non-blocking mode of the socket: if *flag* is 0, the socket is set to non-blocking, else to blocking mode. Initially all sockets are in blocking mode. In non-blocking mode, if a *recv()* call doesn't find any data, or if a *send()* call can't immediately dispose of the data, a *error* exception is raised; in blocking mode, the calls block until they can proceed. *s.setblocking(0)* is equivalent to *s.settimeout(0)*; *s.setblocking(1)* is equivalent to *s.settimeout(None)*.

settimeout (*value*)

Set a timeout on blocking socket operations. The *value* argument can be a nonnegative float expressing seconds, or None. If a float is given, subsequent socket operations will raise an *timeout* exception if the timeout period *value* has elapsed before the operation has completed. Setting a timeout of None disables timeouts on socket operations. *s.settimeout(0.0)* is equivalent to *s.setblocking(0)*; *s.settimeout(None)* is equivalent to *s.setblocking(1)*. New in version 2.3.

gettimeout ()

Return the timeout in floating seconds associated with socket operations, or None if no timeout is set. This reflects the last call to *setblocking()* or *settimeout()*. New in version 2.3.

Some notes on socket blocking and timeouts: A socket object can be in one of three modes: blocking, non-blocking, or timeout. Sockets are always created in blocking mode. In blocking mode, operations block until complete. In non-blocking mode, operations fail (with an error that is unfortunately system-dependent) if they cannot be completed immediately. In timeout mode, operations fail if they cannot be completed within the timeout specified for the socket. The *setblocking()* method is simply a shorthand for certain *settimeout()* calls.

Timeout mode internally sets the socket in non-blocking mode. The blocking and timeout modes are shared between file descriptors and socket objects that refer to the same network endpoint. A consequence of this is that file objects returned by the *makefile()* method must only be used when the socket is in blocking mode; in timeout or non-blocking mode file operations that cannot be completed immediately will fail.

Note that the *connect()* operation is subject to the timeout setting, and in general it is recommended to call *settimeout()* before calling *connect()*.

setsockopt (*level, optname, value*)

Set the value of the given socket option (see the UNIX manual page *setsockopt(2)*). The needed symbolic constants are defined in the `socket` module (`SO_*` etc.). The value can be an integer or a string representing a buffer. In the latter case it is up to the caller to ensure that the string contains the proper bits (see the optional built-in module `struct` for a way to encode C structures as strings).

shutdown (*how*)

Shut down one or both halves of the connection. If *how* is `SHUT_RD`, further receives are disallowed. If *how* is `SHUT_WR`, further sends are disallowed. If *how* is `SHUT_RDWR`, further sends and receives are disallowed.

Note that there are no methods `read()` or `write()`; use `recv()` and `send()` without *flags* argument instead.

Socket objects also have these (read-only) attributes that correspond to the values given to the `socket` constructor.

family

The socket family. New in version 2.5.

type

The socket type. New in version 2.5.

proto

The socket protocol. New in version 2.5.

17.2.2 SSL Objects

SSL objects have the following methods.

write (*s*)

Writes the string *s* to the on the object's SSL connection. The return value is the number of bytes written.

read (*[n]*)

If *n* is provided, read *n* bytes from the SSL connection, otherwise read until EOF. The return value is a string of the bytes read.

server ()

Returns a string describing the server's certificate. Useful for debugging purposes; do not parse the content of this string because its format can't be parsed unambiguously.

issuer ()

Returns a string describing the issuer of the server's certificate. Useful for debugging purposes; do not parse the content of this string because its format can't be parsed unambiguously.

17.2.3 Example

Here are four minimal example programs using the TCP/IP protocol: a server that echoes all data that it receives back (servicing only one client), and a client using it. Note that a server must perform the sequence `socket()`, `bind()`, `listen()`, `accept()` (possibly repeating the `accept()` to service more than one client), while a client only needs the sequence `socket()`, `connect()`. Also note that the server does not `send()/recv()` on the socket it is listening on but on the new socket returned by `accept()`.

The first two examples support IPv4 only.

```

# Echo server program
import socket

HOST = ''          # Symbolic name meaning the local host
PORT = 50007       # Arbitrary non-privileged port
s = socket.socket(socket.AF_INET, socket.SOCK_STREAM)
s.bind((HOST, PORT))
s.listen(1)
conn, addr = s.accept()
print 'Connected by', addr
while 1:
    data = conn.recv(1024)
    if not data: break
    conn.send(data)
conn.close()

# Echo client program
import socket

HOST = 'daring.cwi.nl' # The remote host
PORT = 50007           # The same port as used by the server
s = socket.socket(socket.AF_INET, socket.SOCK_STREAM)
s.connect((HOST, PORT))
s.send('Hello, world')
data = s.recv(1024)
s.close()
print 'Received', repr(data)

```

The next two examples are identical to the above two, but support both IPv4 and IPv6. The server side will listen to the first address family available (it should listen to both instead). On most of IPv6-ready systems, IPv6 will take precedence and the server may not accept IPv4 traffic. The client side will try to connect to the all addresses returned as a result of the name resolution, and sends traffic to the first one connected successfully.

```

# Echo server program
import socket
import sys

HOST = ''          # Symbolic name meaning the local host
PORT = 50007       # Arbitrary non-privileged port
s = None
for res in socket.getaddrinfo(HOST, PORT, socket.AF_UNSPEC, socket.SOCK_STREAM, 0, socket.AI_PASSIVE):
    af, socktype, proto, canonname, sa = res
    try:
        s = socket.socket(af, socktype, proto)
    except socket.error, msg:
        s = None
        continue
    try:
        s.bind(sa)
    except socket.error, msg:
        s.close()
        s = None
        continue
    break
if s is None:
    print 'could not open socket'
    sys.exit(1)
conn, addr = s.accept()
print 'Connected by', addr
while 1:
    data = conn.recv(1024)
    if not data: break
    conn.send(data)
conn.close()

```

```

# Echo client program
import socket
import sys

HOST = 'daring.cwi.nl'      # The remote host
PORT = 50007                # The same port as used by the server
s = None
for res in socket.getaddrinfo(HOST, PORT, socket.AF_UNSPEC, socket.SOCK_STREAM):
    af, socktype, proto, canonname, sa = res
    try:
        s = socket.socket(af, socktype, proto)
        except socket.error, msg:
        s = None
        continue
        try:
            s.connect(sa)
            except socket.error, msg:
            s.close()
            s = None
            continue
            break
if s is None:
    print 'could not open socket'
    sys.exit(1)
s.send('Hello, world')
data = s.recv(1024)
s.close()
print 'Received', repr(data)

```

This example connects to an SSL server, prints the server and issuer's distinguished names, sends some bytes, and reads part of the response:

```

import socket

s = socket.socket(socket.AF_INET, socket.SOCK_STREAM)
s.connect(('www.verisign.com', 443))

ssl_sock = socket.ssl(s)

print repr(ssl_sock.server())
print repr(ssl_sock.issuer())

# Set a simple HTTP request -- use httplib in actual code.
ssl_sock.write("""GET / HTTP/1.0\r
Host: www.verisign.com\r\n\r\n""")

# Read a chunk of data. Will not necessarily
# read all the data returned by the server.
data = ssl_sock.read()

# Note that you need to close the underlying socket, not the SSL object.
del ssl_sock
s.close()

```

At this writing, this SSL example prints the following output (line breaks inserted for readability):

```
'/C=US/ST=California/L=Mountain View/
O=VeriSign, Inc./OU=Production Services/
OU=Terms of use at www.verisign.com/rpa (c)00/
CN=www.verisign.com'
'/O=VeriSign Trust Network/OU=VeriSign, Inc./
OU=VeriSign International Server CA - Class 3/
OU=www.verisign.com/CPS Incorp.by Ref. LIABILITY LTD.(c)97 VeriSign'
```

17.3 signal — Set handlers for asynchronous events

This module provides mechanisms to use signal handlers in Python. Some general rules for working with signals and their handlers:

- A handler for a particular signal, once set, remains installed until it is explicitly reset (Python emulates the BSD style interface regardless of the underlying implementation), with the exception of the handler for `SIGCHLD`, which follows the underlying implementation.
- There is no way to “block” signals temporarily from critical sections (since this is not supported by all UNIX flavors).
- Although Python signal handlers are called asynchronously as far as the Python user is concerned, they can only occur between the “atomic” instructions of the Python interpreter. This means that signals arriving during long calculations implemented purely in C (such as regular expression matches on large bodies of text) may be delayed for an arbitrary amount of time.
- When a signal arrives during an I/O operation, it is possible that the I/O operation raises an exception after the signal handler returns. This is dependent on the underlying UNIX system’s semantics regarding interrupted system calls.
- Because the C signal handler always returns, it makes little sense to catch synchronous errors like `SIGFPE` or `SIGSEGV`.
- Python installs a small number of signal handlers by default: `SIGPIPE` is ignored (so write errors on pipes and sockets can be reported as ordinary Python exceptions) and `SIGINT` is translated into a `KeyboardInterrupt` exception. All of these can be overridden.
- Some care must be taken if both signals and threads are used in the same program. The fundamental thing to remember in using signals and threads simultaneously is: always perform `signal()` operations in the main thread of execution. Any thread can perform an `alarm()`, `getsignal()`, or `pause()`; only the main thread can set a new signal handler, and the main thread will be the only one to receive signals (this is enforced by the Python `signal` module, even if the underlying thread implementation supports sending signals to individual threads). This means that signals can’t be used as a means of inter-thread communication. Use locks instead.

The variables defined in the `signal` module are:

SIG_DFL

This is one of two standard signal handling options; it will simply perform the default function for the signal. For example, on most systems the default action for `SIGQUIT` is to dump core and exit, while the default action for `SIGCLD` is to simply ignore it.

SIG_IGN

This is another standard signal handler, which will simply ignore the given signal.

SIG*

All the signal numbers are defined symbolically. For example, the hangup signal is defined as `signal.SIGHUP`; the variable names are identical to the names used in C programs, as found in `<signal.h>`. The UNIX man page for `'signal()'` lists the existing signals (on some systems this is *signal(2)*, on others the list is in *signal(7)*). Note that not all systems define the same set of signal names; only those names defined by the system are defined by this module.

NSIG

One more than the number of the highest signal number.

The `signal` module defines the following functions:

alarm(*time*)

If *time* is non-zero, this function requests that a `SIGALRM` signal be sent to the process in *time* seconds. Any previously scheduled alarm is canceled (only one alarm can be scheduled at any time). The returned value is then the number of seconds before any previously set alarm was to have been delivered. If *time* is zero, no alarm is scheduled, and any scheduled alarm is canceled. If the return value is zero, no alarm is currently scheduled. (See the UNIX man page *alarm(2)*.) Availability: UNIX.

getsignal(*signalnum*)

Return the current signal handler for the signal *signalnum*. The returned value may be a callable Python object, or one of the special values `signal.SIG_IGN`, `signal.SIG_DFL` or `None`. Here, `signal.SIG_IGN` means that the signal was previously ignored, `signal.SIG_DFL` means that the default way of handling the signal was previously in use, and `None` means that the previous signal handler was not installed from Python.

pause()

Cause the process to sleep until a signal is received; the appropriate handler will then be called. Returns nothing. Not on Windows. (See the UNIX man page *signal(2)*.)

signal(*signalnum*, *handler*)

Set the handler for signal *signalnum* to the function *handler*. *handler* can be a callable Python object taking two arguments (see below), or one of the special values `signal.SIG_IGN` or `signal.SIG_DFL`. The previous signal handler will be returned (see the description of `getsignal()` above). (See the UNIX man page *signal(2)*.)

When threads are enabled, this function can only be called from the main thread; attempting to call it from other threads will cause a `ValueError` exception to be raised.

The *handler* is called with two arguments: the signal number and the current stack frame (`None` or a frame object; for a description of frame objects, see the reference manual section on the standard type hierarchy or see the attribute descriptions in the `inspect` module).

17.3.1 Example

Here is a minimal example program. It uses the `alarm()` function to limit the time spent waiting to open a file; this is useful if the file is for a serial device that may not be turned on, which would normally cause the `os.open()` to hang indefinitely. The solution is to set a 5-second alarm before opening the file; if the operation takes too long, the alarm signal will be sent, and the handler raises an exception.

```

import signal, os

def handler(signum, frame):
    print 'Signal handler called with signal', signum
    raise IOError, "Couldn't open device!"

# Set the signal handler and a 5-second alarm
signal.signal(signal.SIGALRM, handler)
signal.alarm(5)

# This open() may hang indefinitely
fd = os.open('/dev/ttyS0', os.O_RDWR)

signal.alarm(0)          # Disable the alarm

```

17.4 popen2 — Subprocesses with accessible I/O streams

This module allows you to spawn processes and connect to their input/output/error pipes and obtain their return codes under UNIX and Windows.

The subprocess module provides more powerful facilities for spawning new processes and retrieving their results. Using the subprocess module is preferable to using the popen2 module.

The primary interface offered by this module is a trio of factory functions. For each of these, if *bufsize* is specified, it specifies the buffer size for the I/O pipes. *mode*, if provided, should be the string *'b'* or *'t'*; on Windows this is needed to determine whether the file objects should be opened in binary or text mode. The default value for *mode* is *'t'*.

On UNIX, *cmd* may be a sequence, in which case arguments will be passed directly to the program without shell intervention (as with `os.spawnv()`). If *cmd* is a string it will be passed to the shell (as with `os.system()`).

The only way to retrieve the return codes for the child processes is by using the `poll()` or `wait()` methods on the `Popen3` and `Popen4` classes; these are only available on UNIX. This information is not available when using the `popen2()`, `popen3()`, and `popen4()` functions, or the equivalent functions in the `os` module. (Note that the tuples returned by the `os` module's functions are in a different order from the ones returned by the `popen2` module.)

popen2 (*cmd* [, *bufsize* [, *mode*]])

Executes *cmd* as a sub-process. Returns the file objects (*child_stdout*, *child_stdin*).

popen3 (*cmd* [, *bufsize* [, *mode*]])

Executes *cmd* as a sub-process. Returns the file objects (*child_stdout*, *child_stdin*, *child_stderr*).

popen4 (*cmd* [, *bufsize* [, *mode*]])

Executes *cmd* as a sub-process. Returns the file objects (*child_stdout_and_stderr*, *child_stdin*). New in version 2.0.

On UNIX, a class defining the objects returned by the factory functions is also available. These are not used for the Windows implementation, and are not available on that platform.

class Popen3 (*cmd* [, *capturestderr* [, *bufsize*]])

This class represents a child process. Normally, `Popen3` instances are created using the `popen2()` and `popen3()` factory functions described above.

If not using one of the helper functions to create `Popen3` objects, the parameter *cmd* is the shell command to execute in a sub-process. The *capturestderr* flag, if true, specifies that the object should capture standard error output of the child process. The default is false. If the *bufsize* parameter is specified, it specifies the size of the

I/O buffers to/from the child process.

class Popen4 (*cmd*[, *bufsize*])

Similar to `Popen3`, but always captures standard error into the same file object as standard output. These are typically created using `popen4()`. New in version 2.0.

17.4.1 Popen3 and Popen4 Objects

Instances of the `Popen3` and `Popen4` classes have the following methods:

poll()

Returns `-1` if child process hasn't completed yet, or its status code (see `wait()`) otherwise.

wait()

Waits for and returns the status code of the child process. The status code encodes both the return code of the process and information about whether it exited using the `exit()` system call or died due to a signal. Functions to help interpret the status code are defined in the `os` module; see section 14.1.5 for the `W*`() family of functions.

The following attributes are also available:

fromchild

A file object that provides output from the child process. For `Popen4` instances, this will provide both the standard output and standard error streams.

tochild

A file object that provides input to the child process.

childerr

A file object that provides error output from the child process, if *capturestderr* was true for the constructor, otherwise `None`. This will always be `None` for `Popen4` instances.

pid

The process ID of the child process.

17.4.2 Flow Control Issues

Any time you are working with any form of inter-process communication, control flow needs to be carefully thought out. This remains the case with the file objects provided by this module (or the `os` module equivalents).

When reading output from a child process that writes a lot of data to standard error while the parent is reading from the child's standard output, a deadlock can occur. A similar situation can occur with other combinations of reads and writes. The essential factors are that more than `_PC_PIPE_BUF` bytes are being written by one process in a blocking fashion, while the other process is reading from the other process, also in a blocking fashion.

There are several ways to deal with this situation.

The simplest application change, in many cases, will be to follow this model in the parent process:

```
import popen2

r, w, e = popen2.popen3('python slave.py')
e.readlines()
r.readlines()
r.close()
e.close()
w.close()
```

with code like this in the child:

```
import os
import sys

# note that each of these print statements
# writes a single long string

print >>sys.stderr, 400 * 'this is a test\n'
os.close(sys.stderr.fileno())
print >>sys.stdout, 400 * 'this is another test\n'
```

In particular, note that `sys.stderr` must be closed after writing all data, or `readlines()` won't return. Also note that `os.close()` must be used, as `sys.stderr.close()` won't close `stderr` (otherwise assigning to `sys.stderr` will silently close it, so no further errors can be printed).

Applications which need to support a more general approach should integrate I/O over pipes with their `select()` loops, or use separate threads to read each of the individual files provided by whichever `popen*()` function or `Popen*` class was used.

See Also:

[Module subprocess](#) (section 17.1):

Module for spawning and managing subprocesses.

17.5 `asyncore` — Asynchronous socket handler

This module provides the basic infrastructure for writing asynchronous socket service clients and servers.

There are only two ways to have a program on a single processor do “more than one thing at a time.” Multi-threaded programming is the simplest and most popular way to do it, but there is another very different technique, that lets you have nearly all the advantages of multi-threading, without actually using multiple threads. It's really only practical if your program is largely I/O bound. If your program is processor bound, then pre-emptive scheduled threads are probably what you really need. Network servers are rarely processor bound, however.

If your operating system supports the `select()` system call in its I/O library (and nearly all do), then you can use it to juggle multiple communication channels at once; doing other work while your I/O is taking place in the “background.” Although this strategy can seem strange and complex, especially at first, it is in many ways easier to understand and control than multi-threaded programming. The `asyncore` module solves many of the difficult problems for you, making the task of building sophisticated high-performance network servers and clients a snap. For “conversational” applications and protocols the companion [asynchat](#) module is invaluable.

The basic idea behind both modules is to create one or more network *channels*, instances of class `asyncore.dispatcher` and `asynchat.async_chat`. Creating the channels adds them to a global map, used by the `loop()` function if you do not provide it with your own *map*.

Once the initial channel(s) is(are) created, calling the `loop()` function activates channel service, which continues until the last channel (including any that have been added to the map during asynchronous service) is closed.

loop([*timeout* [, *use_poll* [, *map* [, *count*]]]])

Enter a polling loop that terminates after *count* passes or all open channels have been closed. All arguments are optional. The (*count*) parameter defaults to `None`, resulting in the loop terminating only when all channels have been closed. The *timeout* argument sets the timeout parameter for the appropriate `select()` or `poll()` call, measured in seconds; the default is 30 seconds. The *use_poll* parameter, if true, indicates that `poll()` should be used in preference to `select()` (the default is `False`).

The *map* parameter is a dictionary whose items are the channels to watch. As channels are closed they are deleted

from their map. If *map* is omitted, a global map is used. Channels (instances of `asyncore.dispatcher`, `asyncchat.async_chat` and subclasses thereof) can freely be mixed in the map.

class dispatcher ()

The `dispatcher` class is a thin wrapper around a low-level socket object. To make it more useful, it has a few methods for event-handling which are called from the asynchronous loop. Otherwise, it can be treated as a normal non-blocking socket object.

The firing of low-level events at certain times or in certain connection states tells the asynchronous loop that certain higher-level events have taken place. For example, if we have asked for a socket to connect to another host, we know that the connection has been made when the socket becomes writable for the first time (at this point you know that you may write to it with the expectation of success). The implied higher-level events are:

Event	Description
<code>handle_connect ()</code>	Implied by the first write event
<code>handle_close ()</code>	Implied by a read event with no data available
<code>handle_accept ()</code>	Implied by a read event on a listening socket

During asynchronous processing, each mapped channel's `readable ()` and `writable ()` methods are used to determine whether the channel's socket should be added to the list of channels `select ()`ed or `poll ()`ed for read and write events.

Thus, the set of channel events is larger than the basic socket events. The full set of methods that can be overridden in your subclass follows:

handle_read ()

Called when the asynchronous loop detects that a `read ()` call on the channel's socket will succeed.

handle_write ()

Called when the asynchronous loop detects that a writable socket can be written. Often this method will implement the necessary buffering for performance. For example:

```
def handle_write(self):
    sent = self.send(self.buffer)
    self.buffer = self.buffer[sent:]
```

handle_expt ()

Called when there is out of band (OOB) data for a socket connection. This will almost never happen, as OOB is tenuously supported and rarely used.

handle_connect ()

Called when the active opener's socket actually makes a connection. Might send a "welcome" banner, or initiate a protocol negotiation with the remote endpoint, for example.

handle_close ()

Called when the socket is closed.

handle_error ()

Called when an exception is raised and not otherwise handled. The default version prints a condensed traceback.

handle_accept ()

Called on listening channels (passive openers) when a connection can be established with a new remote endpoint that has issued a `connect ()` call for the local endpoint.

readable ()

Called each time around the asynchronous loop to determine whether a channel's socket should be added to the list on which read events can occur. The default method simply returns `True`, indicating that by default, all channels will be interested in read events.

writable ()

Called each time around the asynchronous loop to determine whether a channel's socket should be added to the

list on which write events can occur. The default method simply returns `True`, indicating that by default, all channels will be interested in write events.

In addition, each channel delegates or extends many of the socket methods. Most of these are nearly identical to their socket partners.

create_socket (*family, type*)

This is identical to the creation of a normal socket, and will use the same options for creation. Refer to the [socket](#) documentation for information on creating sockets.

connect (*address*)

As with the normal socket object, *address* is a tuple with the first element the host to connect to, and the second the port number.

send (*data*)

Send *data* to the remote end-point of the socket.

recv (*buffer_size*)

Read at most *buffer_size* bytes from the socket's remote end-point. An empty string implies that the channel has been closed from the other end.

listen (*backlog*)

Listen for connections made to the socket. The *backlog* argument specifies the maximum number of queued connections and should be at least 1; the maximum value is system-dependent (usually 5).

bind (*address*)

Bind the socket to *address*. The socket must not already be bound. (The format of *address* depends on the address family — see above.) To mark the socket as re-usable (setting the `SO_REUSEADDR` option), call the dispatcher object's `set_reuse_addr()` method.

accept ()

Accept a connection. The socket must be bound to an address and listening for connections. The return value is a pair (*conn*, *address*) where *conn* is a *new* socket object usable to send and receive data on the connection, and *address* is the address bound to the socket on the other end of the connection.

close ()

Close the socket. All future operations on the socket object will fail. The remote end-point will receive no more data (after queued data is flushed). Sockets are automatically closed when they are garbage-collected.

17.5.1 `asyncore` Example basic HTTP client

Here is a very basic HTTP client that uses the `dispatcher` class to implement its socket handling:

```

import asyncore, socket

class http_client(asyncore.dispatcher):

    def __init__(self, host, path):
        asyncore.dispatcher.__init__(self)
        self.create_socket(socket.AF_INET, socket.SOCK_STREAM)
        self.connect( (host, 80) )
        self.buffer = 'GET %s HTTP/1.0\r\n\r\n' % path

    def handle_connect(self):
        pass

    def handle_close(self):
        self.close()

    def handle_read(self):
        print self.recv(8192)

    def writable(self):
        return (len(self.buffer) > 0)

    def handle_write(self):
        sent = self.send(self.buffer)
        self.buffer = self.buffer[sent:]

c = http_client('www.python.org', '/')

asyncore.loop()

```

17.6 `asyncchat` — Asynchronous socket command/response handler

This module builds on the `asyncore` infrastructure, simplifying asynchronous clients and servers and making it easier to handle protocols whose elements are terminated by arbitrary strings, or are of variable length. `asyncchat` defines the abstract class `async_chat` that you subclass, providing implementations of the `collect_incoming_data()` and `found_terminator()` methods. It uses the same asynchronous loop as `asyncore`, and the two types of channel, `asyncore.dispatcher` and `asyncchat.async_chat`, can freely be mixed in the channel map. Typically an `asyncore.dispatcher` server channel generates new `asyncchat.async_chat` channel objects as it receives incoming connection requests.

class `async_chat` ()

This class is an abstract subclass of `asyncore.dispatcher`. To make practical use of the code you must subclass `async_chat`, providing meaningful `collect_incoming_data()` and `found_terminator()` methods. The `asyncore.dispatcher` methods can be used, although not all make sense in a message/response context.

Like `asyncore.dispatcher`, `async_chat` defines a set of events that are generated by an analysis of socket conditions after a `select()` call. Once the polling loop has been started the `async_chat` object's methods are called by the event-processing framework with no action on the part of the programmer.

Two class attributes can be modified, to improve performance, or possibly even to conserve memory.

`ac_in_buffer_size`

The asynchronous input buffer size (default 4096).

ac_out_buffer_size

The asynchronous output buffer size (default 4096).

Unlike `asyncore.dispatcher`, `async_chat` allows you to define a first-in-first-out queue (fifo) of *producers*. A producer need have only one method, `more()`, which should return data to be transmitted on the channel. The producer indicates exhaustion (*i.e.* that it contains no more data) by having its `more()` method return the empty string. At this point the `async_chat` object removes the producer from the fifo and starts using the next producer, if any. When the producer fifo is empty the `handle_write()` method does nothing. You use the channel object's `set_terminator()` method to describe how to recognize the end of, or an important breakpoint in, an incoming transmission from the remote endpoint.

To build a functioning `async_chat` subclass your input methods `collect_incoming_data()` and `found_terminator()` must handle the data that the channel receives asynchronously. The methods are described below.

close_when_done()

Pushes a `None` on to the producer fifo. When this producer is popped off the fifo it causes the channel to be closed.

collect_incoming_data(data)

Called with *data* holding an arbitrary amount of received data. The default method, which must be overridden, raises a `NotImplementedError` exception.

discard_buffers()

In emergencies this method will discard any data held in the input and/or output buffers and the producer fifo.

found_terminator()

Called when the incoming data stream matches the termination condition set by `set_terminator`. The default method, which must be overridden, raises a `NotImplementedError` exception. The buffered input data should be available via an instance attribute.

get_terminator()

Returns the current terminator for the channel.

handle_close()

Called when the channel is closed. The default method silently closes the channel's socket.

handle_read()

Called when a read event fires on the channel's socket in the asynchronous loop. The default method checks for the termination condition established by `set_terminator()`, which can be either the appearance of a particular string in the input stream or the receipt of a particular number of characters. When the terminator is found, `handle_read` calls the `found_terminator()` method after calling `collect_incoming_data()` with any data preceding the terminating condition.

handle_write()

Called when the application may write data to the channel. The default method calls the `initiate_send()` method, which in turn will call `refill_buffer()` to collect data from the producer fifo associated with the channel.

push(data)

Creates a `simple_producer` object (*see below*) containing the data and pushes it on to the channel's `producer_fifo` to ensure its transmission. This is all you need to do to have the channel write the data out to the network, although it is possible to use your own producers in more complex schemes to implement encryption and chunking, for example.

push_with_producer(producer)

Takes a producer object and adds it to the producer fifo associated with the channel. When all currently-pushed producers have been exhausted the channel will consume this producer's data by calling its `more()` method and send the data to the remote endpoint.

readable()

Should return `True` for the channel to be included in the set of channels tested by the `select()` loop for readability.

refill_buffer()

Refills the output buffer by calling the `more()` method of the producer at the head of the fifo. If it is exhausted then the producer is popped off the fifo and the next producer is activated. If the current producer is, or becomes, `None` then the channel is closed.

set_terminator(term)

Sets the terminating condition to be recognised on the channel. `term` may be any of three types of value, corresponding to three different ways to handle incoming protocol data.

term	Description
<i>string</i>	Will call <code>found_terminator()</code> when the string is found in the input stream
<i>integer</i>	Will call <code>found_terminator()</code> when the indicated number of characters have been received
<i>None</i>	The channel continues to collect data forever

Note that any data following the terminator will be available for reading by the channel after `found_terminator()` is called.

writable()

Should return `True` as long as items remain on the producer fifo, or the channel is connected and the channel's output buffer is non-empty.

17.6.1 asynchat - Auxiliary Classes and Functions

class simple_producer(data[, buffer_size=512])

A `simple_producer` takes a chunk of data and an optional buffer size. Repeated calls to its `more()` method yield successive chunks of the data no larger than `buffer_size`.

more()

Produces the next chunk of information from the producer, or returns the empty string.

class fifo([list=None])

Each channel maintains a `fifo` holding data which has been pushed by the application but not yet popped for writing to the channel. A `fifo` is a list used to hold data and/or producers until they are required. If the `list` argument is provided then it should contain producers or data items to be written to the channel.

is_empty()

Returns `True` iff the fifo is empty.

first()

Returns the least-recently `push()`ed item from the fifo.

push(data)

Adds the given data (which may be a string or a producer object) to the producer fifo.

pop()

If the fifo is not empty, returns `True`, `first()`, deleting the popped item. Returns `False`, `None` for an empty fifo.

The `asynchat` module also defines one utility function, which may be of use in network and textual analysis operations.

find_prefix_at_end(haystack, needle)

Returns `True` if string `haystack` ends with any non-empty prefix of string `needle`.

17.6.2 asynchat Example

The following partial example shows how HTTP requests can be read with `asynchat`. A web server might create an `http_request_handler` object for each incoming client connection. Notice that initially the channel terminator is set to match the blank line at the end of the HTTP headers, and a flag indicates that the headers are being read.

Once the headers have been read, if the request is of type POST (indicating that further data are present in the input stream) then the `Content-Length:` header is used to set a numeric terminator to read the right amount of data from the channel.

The `handle_request()` method is called once all relevant input has been marshalled, after setting the channel terminator to `None` to ensure that any extraneous data sent by the web client are ignored.

```
class http_request_handler(asynchat.async_chat):

    def __init__(self, conn, addr, sessions, log):
        asynchat.async_chat.__init__(self, conn=conn)
        self.addr = addr
        self.sessions = sessions
        self.ibuffer = []
        self.obuffer = ""
        self.set_terminator("\r\n\r\n")
        self.reading_headers = True
        self.handling = False
        self.cgi_data = None
        self.log = log

    def collect_incoming_data(self, data):
        """Buffer the data"""
        self.ibuffer.append(data)

    def found_terminator(self):
        if self.reading_headers:
            self.reading_headers = False
            self.parse_headers("".join(self.ibuffer))
            self.ibuffer = []
            if self.op.upper() == "POST":
                clen = self.headers.getheader("content-length")
                self.set_terminator(int(clen))
            else:
                self.handling = True
                self.set_terminator(None)
                self.handle_request()
        elif not self.handling:
            self.set_terminator(None) # browsers sometimes over-send
            self.cgi_data = parse(self.headers, "".join(self.ibuffer))
            self.handling = True
            self.ibuffer = []
            self.handle_request()
```

Internet Protocols and Support

The modules described in this chapter implement Internet protocols and support for related technology. They are all implemented in Python. Most of these modules require the presence of the system-dependent module `socket`, which is currently supported on most popular platforms. Here is an overview:

<code>webbrowser</code>	Easy-to-use controller for Web browsers.
<code>cgi</code>	Common Gateway Interface support, used to interpret forms in server-side scripts.
<code>cgitb</code>	Configurable traceback handler for CGI scripts.
<code>wsgiref.handlers</code>	WSGI Utilities and Reference Implementation
<code>urllib</code>	Open an arbitrary network resource by URL (requires sockets).
<code>urllib2</code>	An extensible library for opening URLs using a variety of protocols
<code>httplib</code>	HTTP and HTTPS protocol client (requires sockets).
<code>ftplib</code>	FTP protocol client (requires sockets).
<code>gopherlib</code>	Gopher protocol client (requires sockets).
<code>poplib</code>	POP3 protocol client (requires sockets).
<code>imaplib</code>	IMAP4 protocol client (requires sockets).
<code>nntplib</code>	NNTP protocol client (requires sockets).
<code>smtplib</code>	SMTP protocol client (requires sockets).
<code>smtpd</code>	Implement a flexible SMTP server
<code>telnetlib</code>	Telnet client class.
<code>uuid</code>	UUID objects (universally unique identifiers) according to RFC 4122
<code>urlparse</code>	Parse URLs into components.
<code>SocketServer</code>	A framework for network servers.
<code>BaseHTTPServer</code>	Basic HTTP server (base class for <code>SimpleHTTPServer</code> and <code>CGIHTTPServer</code>).
<code>SimpleHTTPServer</code>	This module provides a basic request handler for HTTP servers.
<code>CGIHTTPServer</code>	This module provides a request handler for HTTP servers which can run CGI scripts.
<code>cookielib</code>	Cookie handling for HTTP clients
<code>Cookie</code>	Support for HTTP state management (cookies).
<code>xmlrpclib</code>	XML-RPC client access.
<code>SimpleXMLRPCServer</code>	Basic XML-RPC server implementation.
<code>DocXMLRPCServer</code>	Self-documenting XML-RPC server implementation.

18.1 `webbrowser` — Convenient Web-browser controller

The `webbrowser` module provides a high-level interface to allow displaying Web-based documents to users. Under most circumstances, simply calling the `open()` function from this module will do the right thing.

Under UNIX, graphical browsers are preferred under X11, but text-mode browsers will be used if graphical browsers are not available or an X11 display isn't available. If text-mode browsers are used, the calling process will block until the user exits the browser.

If the environment variable `BROWSER` exists, it is interpreted to override the platform default list of browsers, as a `os.pathsep`-separated list of browsers to try in order. When the value of a list part contains the string `%s`, then it is interpreted as a literal browser command line to be used with the argument `URL` substituted for `%s`; if the part does not contain `%s`, it is simply interpreted as the name of the browser to launch.

For non-UNIX platforms, or when a remote browser is available on UNIX, the controlling process will not wait for the user to finish with the browser, but allow the remote browser to maintain its own windows on the display. If remote browsers are not available on UNIX, the controlling process will launch a new browser and wait.

The script **webbrowser** can be used as a command-line interface for the module. It accepts an URL as the argument. It accepts the following optional parameters: **-n** opens the URL in a new browser window, if possible; **-t** opens the URL in a new browser page ("tab"). The options are, naturally, mutually exclusive.

The following exception is defined:

exception Error

Exception raised when a browser control error occurs.

The following functions are defined:

open (*url* [, *new*=0 [, *autoraise*=1]])

Display *url* using the default browser. If *new* is 0, the *url* is opened in the same browser window if possible. If *new* is 1, a new browser window is opened if possible. If *new* is 2, a new browser page ("tab") is opened if possible. If *autoraise* is true, the window is raised if possible (note that under many window managers this will occur regardless of the setting of this variable). Changed in version 2.5: *new* can now be 2.

open_new (*url*)

Open *url* in a new window of the default browser, if possible, otherwise, open *url* in the only browser window.

open_new_tab (*url*)

Open *url* in a new page ("tab") of the default browser, if possible, otherwise equivalent to `open_new`. New in version 2.5.

get ([*name*])

Return a controller object for the browser type *name*. If *name* is empty, return a controller for a default browser appropriate to the caller's environment.

register (*name*, *constructor* [, *instance*])

Register the browser type *name*. Once a browser type is registered, the `get ()` function can return a controller for that browser type. If *instance* is not provided, or is `None`, *constructor* will be called without parameters to create an instance when needed. If *instance* is provided, *constructor* will never be called, and may be `None`.

This entry point is only useful if you plan to either set the `BROWSER` variable or call `get` with a nonempty argument matching the name of a handler you declare.

A number of browser types are predefined. This table gives the type names that may be passed to the `get ()` function and the corresponding instantiations for the controller classes, all defined in this module.

Type Name	Class Name	Notes
'mozilla'	Mozilla('mozilla')	
'firefox'	Mozilla('mozilla')	
'netscape'	Mozilla('netscape')	
'galeon'	Galeon('galeon')	
'epiphany'	Galeon('epiphany')	
'skipstone'	BackgroundBrowser('skipstone')	
'kfmclient'	Konqueror()	(1)
'konqueror'	Konqueror()	(1)
'kfm'	Konqueror()	(1)
'mosaic'	BackgroundBrowser('mosaic')	
'opera'	Opera()	
'grail'	Grail()	
'links'	GenericBrowser('links')	
'elinks'	Elinks('elinks')	
'lynx'	GenericBrowser('lynx')	
'w3m'	GenericBrowser('w3m')	
'windows-default'	WindowsDefault	(2)
'internet-config'	InternetConfig	(3)
'macosx'	MacOSX('default')	(4)

Notes:

- (1) “Konqueror” is the file manager for the KDE desktop environment for UNIX, and only makes sense to use if KDE is running. Some way of reliably detecting KDE would be nice; the KDEDIR variable is not sufficient. Note also that the name “kfm” is used even when using the **konqueror** command with KDE 2 — the implementation selects the best strategy for running Konqueror.
- (2) Only on Windows platforms.
- (3) Only on MacOS platforms; requires the standard MacPython `ic` module, described in the [Macintosh Library Modules](#) manual.
- (4) Only on MacOS X platform.

Here are some simple examples:

```
url = 'http://www.python.org'

# Open URL in a new tab, if a browser window is already open.
webbrowser.open_new_tab(url + '/doc')

# Open URL in new window, raising the window if possible.
webbrowser.open_new(url)
```

18.1.1 Browser Controller Objects

Browser controllers provide two methods which parallel two of the module-level convenience functions:

open (*url* [, *new* [, *autoraise*=1]])

Display *url* using the browser handled by this controller. If *new* is 1, a new browser window is opened if possible. If *new* is 2, a new browser page (“tab”) is opened if possible.

open_new (*url*)

Open *url* in a new window of the browser handled by this controller, if possible, otherwise, open *url* in the only browser window. Alias `open_new`.

open_new_tab (*url*)

Open *url* in a new page ("tab") of the browser handled by this controller, if possible, otherwise equivalent to `open_new`. New in version 2.5.

18.2 cgi — Common Gateway Interface support.

Support module for Common Gateway Interface (CGI) scripts.

This module defines a number of utilities for use by CGI scripts written in Python.

18.2.1 Introduction

A CGI script is invoked by an HTTP server, usually to process user input submitted through an HTML `<FORM>` or `<ISINDEX>` element.

Most often, CGI scripts live in the server's special 'cgi-bin' directory. The HTTP server places all sorts of information about the request (such as the client's hostname, the requested URL, the query string, and lots of other goodies) in the script's shell environment, executes the script, and sends the script's output back to the client.

The script's input is connected to the client too, and sometimes the form data is read this way; at other times the form data is passed via the "query string" part of the URL. This module is intended to take care of the different cases and provide a simpler interface to the Python script. It also provides a number of utilities that help in debugging scripts, and the latest addition is support for file uploads from a form (if your browser supports it).

The output of a CGI script should consist of two sections, separated by a blank line. The first section contains a number of headers, telling the client what kind of data is following. Python code to generate a minimal header section looks like this:

```
print "Content-Type: text/html"      # HTML is following
print                               # blank line, end of headers
```

The second section is usually HTML, which allows the client software to display nicely formatted text with header, in-line images, etc. Here's Python code that prints a simple piece of HTML:

```
print "<TITLE>CGI script output</TITLE>"
print "<H1>This is my first CGI script</H1>"
print "Hello, world!"
```

18.2.2 Using the cgi module

Begin by writing `'import cgi'`. Do not use `'from cgi import *'` — the module defines all sorts of names for its own use or for backward compatibility that you don't want in your namespace.

When you write a new script, consider adding the line:

```
import cgitb; cgitb.enable()
```

This activates a special exception handler that will display detailed reports in the Web browser if any errors occur. If you'd rather not show the guts of your program to users of your script, you can have the reports saved to files instead, with a line like this:

```
import cgitb; cgitb.enable(display=0, logdir="/tmp")
```

It's very helpful to use this feature during script development. The reports produced by `cgitb` provide information that can save you a lot of time in tracking down bugs. You can always remove the `cgitb` line later when you have tested your script and are confident that it works correctly.

To get at submitted form data, it's best to use the `FieldStorage` class. The other classes defined in this module are provided mostly for backward compatibility. Instantiate it exactly once, without arguments. This reads the form contents from standard input or the environment (depending on the value of various environment variables set according to the CGI standard). Since it may consume standard input, it should be instantiated only once.

The `FieldStorage` instance can be indexed like a Python dictionary, and also supports the standard dictionary methods `has_key()` and `keys()`. The built-in `len()` is also supported. Form fields containing empty strings are ignored and do not appear in the dictionary; to keep such values, provide a true value for the optional *keep_blank_values* keyword parameter when creating the `FieldStorage` instance.

For instance, the following code (which assumes that the Content-Type: header and blank line have already been printed) checks that the fields `name` and `addr` are both set to a non-empty string:

```
form = cgi.FieldStorage()
if not (form.has_key("name") and form.has_key("addr")):
    print "<H1>Error</H1>"
    print "Please fill in the name and addr fields."
    return
print "<p>name:", form["name"].value
print "<p>addr:", form["addr"].value
...further form processing here...
```

Here the fields, accessed through `'form[key]'`, are themselves instances of `FieldStorage` (or `MiniFieldStorage`, depending on the form encoding). The `value` attribute of the instance yields the string value of the field. The `getvalue()` method returns this string value directly; it also accepts an optional second argument as a default to return if the requested key is not present.

If the submitted form data contains more than one field with the same name, the object retrieved by `'form[key]'` is not a `FieldStorage` or `MiniFieldStorage` instance but a list of such instances. Similarly, in this situation, `'form.getvalue(key)'` would return a list of strings. If you expect this possibility (when your HTML form contains multiple fields with the same name), use the `getlist()` function, which always returns a list of values (so that you do not need to special-case the single item case). For example, this code concatenates any number of username fields, separated by commas:

```
value = form.getlist("username")
usernames = ",".join(value)
```

If a field represents an uploaded file, accessing the value via the `value` attribute or the `getvalue()` method reads the entire file in memory as a string. This may not be what you want. You can test for an uploaded file by testing either

the `filename` attribute or the `file` attribute. You can then read the data at leisure from the `file` attribute:

```
fileitem = form["userfile"]
if fileitem.file:
    # It's an uploaded file; count lines
    linecount = 0
    while 1:
        line = fileitem.file.readline()
        if not line: break
        linecount = linecount + 1
```

If an error is encountered when obtaining the contents of an uploaded file (for example, when the user interrupts the form submission by clicking on a Back or Cancel button) the `done` attribute of the object for the field will be set to the value `-1`.

The file upload draft standard entertains the possibility of uploading multiple files from one field (using a recursive multipart/* encoding). When this occurs, the item will be a dictionary-like `FieldStorage` item. This can be determined by testing its `type` attribute, which should be `multipart/form-data` (or perhaps another MIME type matching multipart/*). In this case, it can be iterated over recursively just like the top-level form object.

When a form is submitted in the “old” format (as the query string or as a single data part of type `application/x-www-form-urlencoded`), the items will actually be instances of the class `MiniFieldStorage`. In this case, the `list`, `file`, and `filename` attributes are always `None`.

18.2.3 Higher Level Interface

New in version 2.2.

The previous section explains how to read CGI form data using the `FieldStorage` class. This section describes a higher level interface which was added to this class to allow one to do it in a more readable and intuitive way. The interface doesn't make the techniques described in previous sections obsolete — they are still useful to process file uploads efficiently, for example.

The interface consists of two simple methods. Using the methods you can process form data in a generic way, without the need to worry whether only one or more values were posted under one name.

In the previous section, you learned to write following code anytime you expected a user to post more than one value under one name:

```
item = form.getvalue("item")
if isinstance(item, list):
    # The user is requesting more than one item.
else:
    # The user is requesting only one item.
```

This situation is common for example when a form contains a group of multiple checkboxes with the same name:

```
<input type="checkbox" name="item" value="1" />
<input type="checkbox" name="item" value="2" />
```

In most situations, however, there's only one form control with a particular name in a form and then you expect and need only one value associated with this name. So you write a script containing for example this code:


```
user = form.getvalue("user").upper()
```

The problem with the code is that you should never expect that a client will provide valid input to your scripts. For example, if a curious user appends another `'user=foo'` pair to the query string, then the script would crash, because in this situation the `getvalue("user")` method call returns a list instead of a string. Calling the `toupper()` method on a list is not valid (since lists do not have a method of this name) and results in an `AttributeError` exception.

Therefore, the appropriate way to read form data values was to always use the code which checks whether the obtained value is a single value or a list of values. That's annoying and leads to less readable scripts.

A more convenient approach is to use the methods `getfirst()` and `getlist()` provided by this higher level interface.

getfirst (*name* [, *default*])

This method always returns only one value associated with form field *name*. The method returns only the first value in case that more values were posted under such name. Please note that the order in which the values are received may vary from browser to browser and should not be counted on.¹ If no such form field or value exists then the method returns the value specified by the optional parameter *default*. This parameter defaults to `None` if not specified.

getlist (*name*)

This method always returns a list of values associated with form field *name*. The method returns an empty list if no such form field or value exists for *name*. It returns a list consisting of one item if only one such value exists.

Using these methods you can write nice compact code:

```
import cgi
form = cgi.FieldStorage()
user = form.getfirst("user", "").upper()      # This way it's safe.
for item in form.getlist("item"):
    do_something(item)
```

18.2.4 Old classes

These classes, present in earlier versions of the `cgi` module, are still supported for backward compatibility. New applications should use the `FieldStorage` class.

`SvFormContentDict` stores single value form content as dictionary; it assumes each field name occurs in the form only once.

`FormContentDict` stores multiple value form content as a dictionary (the form items are lists of values). Useful if your form contains multiple fields with the same name.

Other classes (`FormContent`, `InterpFormContentDict`) are present for backwards compatibility with really old applications only. If you still use these and would be inconvenienced when they disappeared from a next version of this module, drop me a note.

18.2.5 Functions

¹Note that some recent versions of the HTML specification do state what order the field values should be supplied in, but knowing whether a request was received from a conforming browser, or even from a browser at all, is tedious and error-prone.

These are useful if you want more control, or if you want to employ some of the algorithms implemented in this module in other circumstances.

parse (*fp*, [*keep_blank_values*, *strict_parsing*])

Parse a query in the environment or from a file (the file defaults to `sys.stdin`). The *keep_blank_values* and *strict_parsing* parameters are passed to `parse_qs()` unchanged.

parse_qs (*qs*, [*keep_blank_values*, *strict_parsing*])

Parse a query string given as a string argument (data of type `application/x-www-form-urlencoded`). Data are returned as a dictionary. The dictionary keys are the unique query variable names and the values are lists of values for each name.

The optional argument *keep_blank_values* is a flag indicating whether blank values in URL encoded queries should be treated as blank strings. A true value indicates that blanks should be retained as blank strings. The default false value indicates that blank values are to be ignored and treated as if they were not included.

The optional argument *strict_parsing* is a flag indicating what to do with parsing errors. If false (the default), errors are silently ignored. If true, errors raise a `ValueError` exception.

Use the `urllib.urlencode()` function to convert such dictionaries into query strings.

parse_qs1 (*qs*, [*keep_blank_values*, *strict_parsing*])

Parse a query string given as a string argument (data of type `application/x-www-form-urlencoded`). Data are returned as a list of name, value pairs.

The optional argument *keep_blank_values* is a flag indicating whether blank values in URL encoded queries should be treated as blank strings. A true value indicates that blanks should be retained as blank strings. The default false value indicates that blank values are to be ignored and treated as if they were not included.

The optional argument *strict_parsing* is a flag indicating what to do with parsing errors. If false (the default), errors are silently ignored. If true, errors raise a `ValueError` exception.

Use the `urllib.urlencode()` function to convert such lists of pairs into query strings.

parse_multipart (*fp*, *pdict*)

Parse input of type multipart/form-data (for file uploads). Arguments are *fp* for the input file and *pdict* for a dictionary containing other parameters in the Content-Type: header.

Returns a dictionary just like `parse_qs()` keys are the field names, each value is a list of values for that field. This is easy to use but not much good if you are expecting megabytes to be uploaded — in that case, use the `FieldStorage` class instead which is much more flexible.

Note that this does not parse nested multipart parts — use `FieldStorage` for that.

parse_header (*string*)

Parse a MIME header (such as Content-Type:) into a main value and a dictionary of parameters.

test ()

Robust test CGI script, usable as main program. Writes minimal HTTP headers and formats all information provided to the script in HTML form.

print_environ ()

Format the shell environment in HTML.

print_form (*form*)

Format a form in HTML.

print_directory ()

Format the current directory in HTML.

print_environ_usage ()

Print a list of useful (used by CGI) environment variables in HTML.

escape (*s*, [*quote*])

Convert the characters '&', '<' and '>' in string *s* to HTML-safe sequences. Use this if you need to display

text that might contain such characters in HTML. If the optional flag *quote* is true, the quotation mark character (‘”’) is also translated; this helps for inclusion in an HTML attribute value, as in ``. If the value to be quoted might include single- or double-quote characters, or both, consider using the `quoteattr()` function in the `xml.sax.saxutils` module instead.

18.2.6 Caring about security

There’s one important rule: if you invoke an external program (via the `os.system()` or `os.popen()` functions, or others with similar functionality), make very sure you don’t pass arbitrary strings received from the client to the shell. This is a well-known security hole whereby clever hackers anywhere on the Web can exploit a gullible CGI script to invoke arbitrary shell commands. Even parts of the URL or field names cannot be trusted, since the request doesn’t have to come from your form!

To be on the safe side, if you must pass a string gotten from a form to a shell command, you should make sure the string contains only alphanumeric characters, dashes, underscores, and periods.

18.2.7 Installing your CGI script on a UNIX system

Read the documentation for your HTTP server and check with your local system administrator to find the directory where CGI scripts should be installed; usually this is in a directory ‘cgi-bin’ in the server tree.

Make sure that your script is readable and executable by “others”; the UNIX file mode should be 0755 octal (use ‘`chmod 0755 filename`’). Make sure that the first line of the script contains `#!` starting in column 1 followed by the pathname of the Python interpreter, for instance:

```
#!/usr/local/bin/python
```

Make sure the Python interpreter exists and is executable by “others”.

Make sure that any files your script needs to read or write are readable or writable, respectively, by “others” — their mode should be 0644 for readable and 0666 for writable. This is because, for security reasons, the HTTP server executes your script as user “nobody”, without any special privileges. It can only read (write, execute) files that everybody can read (write, execute). The current directory at execution time is also different (it is usually the server’s cgi-bin directory) and the set of environment variables is also different from what you get when you log in. In particular, don’t count on the shell’s search path for executables (PATH) or the Python module search path (PYTHONPATH) to be set to anything interesting.

If you need to load modules from a directory which is not on Python’s default module search path, you can change the path in your script, before importing other modules. For example:

```
import sys
sys.path.insert(0, "/usr/home/joe/lib/python")
sys.path.insert(0, "/usr/local/lib/python")
```

(This way, the directory inserted last will be searched first!)

Instructions for non-UNIX systems will vary; check your HTTP server’s documentation (it will usually have a section on CGI scripts).

18.2.8 Testing your CGI script

Unfortunately, a CGI script will generally not run when you try it from the command line, and a script that works perfectly from the command line may fail mysteriously when run from the server. There's one reason why you should still test your script from the command line: if it contains a syntax error, the Python interpreter won't execute it at all, and the HTTP server will most likely send a cryptic error to the client.

Assuming your script has no syntax errors, yet it does not work, you have no choice but to read the next section.

18.2.9 Debugging CGI scripts

First of all, check for trivial installation errors — reading the section above on installing your CGI script carefully can save you a lot of time. If you wonder whether you have understood the installation procedure correctly, try installing a copy of this module file (`'cgi.py'`) as a CGI script. When invoked as a script, the file will dump its environment and the contents of the form in HTML form. Give it the right mode etc, and send it a request. If it's installed in the standard `'cgi-bin'` directory, it should be possible to send it a request by entering a URL into your browser of the form:

```
http://yourhostname/cgi-bin/cgi.py?name=Joe+Blow&addr=At+Home
```

If this gives an error of type 404, the server cannot find the script — perhaps you need to install it in a different directory. If it gives another error, there's an installation problem that you should fix before trying to go any further. If you get a nicely formatted listing of the environment and form content (in this example, the fields should be listed as `"addr"` with value `"At Home"` and `"name"` with value `"Joe Blow"`), the `'cgi.py'` script has been installed correctly. If you follow the same procedure for your own script, you should now be able to debug it.

The next step could be to call the `cgi` module's `test()` function from your script: replace its main code with the single statement

```
cgi.test()
```

This should produce the same results as those gotten from installing the `'cgi.py'` file itself.

When an ordinary Python script raises an unhandled exception (for whatever reason: of a typo in a module name, a file that can't be opened, etc.), the Python interpreter prints a nice traceback and exits. While the Python interpreter will still do this when your CGI script raises an exception, most likely the traceback will end up in one of the HTTP server's log files, or be discarded altogether.

Fortunately, once you have managed to get your script to execute *some* code, you can easily send tracebacks to the Web browser using the `cgibtb` module. If you haven't done so already, just add the line:

```
import cgitb; cgitb.enable()
```

to the top of your script. Then try running it again; when a problem occurs, you should see a detailed report that will likely make apparent the cause of the crash.

If you suspect that there may be a problem in importing the `cgibtb` module, you can use an even more robust approach (which only uses built-in modules):

```
import sys
sys.stderr = sys.stdout
print "Content-Type: text/plain"
print
...your code here...
```

This relies on the Python interpreter to print the traceback. The content type of the output is set to plain text, which disables all HTML processing. If your script works, the raw HTML will be displayed by your client. If it raises an exception, most likely after the first two lines have been printed, a traceback will be displayed. Because no HTML interpretation is going on, the traceback will be readable.

18.2.10 Common problems and solutions

- Most HTTP servers buffer the output from CGI scripts until the script is completed. This means that it is not possible to display a progress report on the client's display while the script is running.
- Check the installation instructions above.
- Check the HTTP server's log files. ('tail -f logfile' in a separate window may be useful!)
- Always check a script for syntax errors first, by doing something like 'python script.py'.
- If your script does not have any syntax errors, try adding 'import cgitb; cgitb.enable()' to the top of the script.
- When invoking external programs, make sure they can be found. Usually, this means using absolute path names — PATH is usually not set to a very useful value in a CGI script.
- When reading or writing external files, make sure they can be read or written by the userid under which your CGI script will be running: this is typically the userid under which the web server is running, or some explicitly specified userid for a web server's 'suexec' feature.
- Don't try to give a CGI script a set-uid mode. This doesn't work on most systems, and is a security liability as well.

18.3 cgitb — Traceback manager for CGI scripts

New in version 2.2.

The `cgitb` module provides a special exception handler for Python scripts. (Its name is a bit misleading. It was originally designed to display extensive traceback information in HTML for CGI scripts. It was later generalized to also display this information in plain text.) After this module is activated, if an uncaught exception occurs, a detailed, formatted report will be displayed. The report includes a traceback showing excerpts of the source code for each level, as well as the values of the arguments and local variables to currently running functions, to help you debug the problem. Optionally, you can save this information to a file instead of sending it to the browser.

To enable this feature, simply add one line to the top of your CGI script:

```
import cgitb; cgitb.enable()
```

The options to the `enable()` function control whether the report is displayed in the browser and whether the report is logged to a file for later analysis.

enable ([*display* [, *logdir* [, *context* [, *format*]]]])

This function causes the `cgitb` module to take over the interpreter’s default handling for exceptions by setting the value of `sys.excepthook`.

The optional argument *display* defaults to 1 and can be set to 0 to suppress sending the traceback to the browser. If the argument *logdir* is present, the traceback reports are written to files. The value of *logdir* should be a directory where these files will be placed. The optional argument *context* is the number of lines of context to display around the current line of source code in the traceback; this defaults to 5. If the optional argument *format* is "html", the output is formatted as HTML. Any other value forces plain text output. The default value is "html".

handler ([*info*])

This function handles an exception using the default settings (that is, show a report in the browser, but don’t log to a file). This can be used when you’ve caught an exception and want to report it using `cgitb`. The optional *info* argument should be a 3-tuple containing an exception type, exception value, and traceback object, exactly like the tuple returned by `sys.exc_info()`. If the *info* argument is not supplied, the current exception is obtained from `sys.exc_info()`.

18.4 wsgiref — WSGI Utilities and Reference Implementation

New in version 2.5.

The Web Server Gateway Interface (WSGI) is a standard interface between web server software and web applications written in Python. Having a standard interface makes it easy to use an application that supports WSGI with a number of different web servers.

Only authors of web servers and programming frameworks need to know every detail and corner case of the WSGI design. You don’t need to understand every detail of WSGI just to install a WSGI application or to write a web application using an existing framework.

`wsgiref` is a reference implementation of the WSGI specification that can be used to add WSGI support to a web server or framework. It provides utilities for manipulating WSGI environment variables and response headers, base classes for implementing WSGI servers, a demo HTTP server that serves WSGI applications, and a validation tool that checks WSGI servers and applications for conformance to the WSGI specification (PEP 333).

See <http://www.wsgi.org> for more information about WSGI, and links to tutorials and other resources.

18.4.1 wsgiref.util – WSGI environment utilities

This module provides a variety of utility functions for working with WSGI environments. A WSGI environment is a dictionary containing HTTP request variables as described in PEP 333. All of the functions taking an *environ* parameter expect a WSGI-compliant dictionary to be supplied; please see PEP 333 for a detailed specification.

guess_scheme (*environ*)

Return a guess for whether `wsgi.url_scheme` should be “http” or “https”, by checking for a HTTPS environment variable in the *environ* dictionary. The return value is a string.

This function is useful when creating a gateway that wraps CGI or a CGI-like protocol such as FastCGI. Typically, servers providing such protocols will include a `HTTPS` variable with a value of “1” “yes”, or “on” when a request is received via SSL. So, this function returns “https” if such a value is found, and “http” otherwise.

request_uri (*environ* [, *include_query=1*])

Return the full request URI, optionally including the query string, using the algorithm found in the “URL Reconstruction” section of PEP 333. If *include_query* is false, the query string is not included in the resulting URI.

application_uri (*environ*)

Similar to `request_uri`, except that the `PATH_INFO` and `QUERY_STRING` variables are ignored. The result is the base URI of the application object addressed by the request.

shift_path_info (*environ*)

Shift a single name from `PATH_INFO` to `SCRIPT_NAME` and return the name. The *environ* dictionary is *modified* in-place; use a copy if you need to keep the original `PATH_INFO` or `SCRIPT_NAME` intact.

If there are no remaining path segments in `PATH_INFO`, `None` is returned.

Typically, this routine is used to process each portion of a request URI path, for example to treat the path as a series of dictionary keys. This routine modifies the passed-in environment to make it suitable for invoking another WSGI application that is located at the target URI. For example, if there is a WSGI application at `/foo`, and the request URI path is `/foo/bar/baz`, and the WSGI application at `/foo` calls `shift_path_info`, it will receive the string “bar”, and the environment will be updated to be suitable for passing to a WSGI application at `/foo/bar`. That is, `SCRIPT_NAME` will change from `/foo` to `/foo/bar`, and `PATH_INFO` will change from `/bar/baz` to `/baz`.

When `PATH_INFO` is just a “/”, this routine returns an empty string and appends a trailing slash to `SCRIPT_NAME`, even though empty path segments are normally ignored, and `SCRIPT_NAME` doesn’t normally end in a slash. This is intentional behavior, to ensure that an application can tell the difference between URIs ending in `/x` from ones ending in `/x/` when using this routine to do object traversal.

setup_testing_defaults (*environ*)

Update *environ* with trivial defaults for testing purposes.

This routine adds various parameters required for WSGI, including `HTTP_HOST`, `SERVER_NAME`, `SERVER_PORT`, `REQUEST_METHOD`, `SCRIPT_NAME`, `PATH_INFO`, and all of the PEP 333-defined `wsgi.*` variables. It only supplies default values, and does not replace any existing settings for these variables.

This routine is intended to make it easier for unit tests of WSGI servers and applications to set up dummy environments. It should NOT be used by actual WSGI servers or applications, since the data is fake!

In addition to the environment functions above, the `wsgiref.util` module also provides these miscellaneous utilities:

is_hop_by_hop (*header_name*)

Return true if ‘*header_name*’ is an HTTP/1.1 “Hop-by-Hop” header, as defined by RFC 2616.

class FileWrapper (*filelike* [, *blksize=8192*])

A wrapper to convert a file-like object to an iterator. The resulting objects support both `__getitem__` and `__iter__` iteration styles, for compatibility with Python 2.1 and Jython. As the object is iterated over, the optional *blksize* parameter will be repeatedly passed to the *filelike* object’s `read()` method to obtain strings to yield. When `read()` returns an empty string, iteration is ended and is not resumable.

If *filelike* has a `close()` method, the returned object will also have a `close()` method, and it will invoke the *filelike* object’s `close()` method when called.

18.4.2 `wsgiref.headers` – WSGI response header tools

This module provides a single class, `Headers`, for convenient manipulation of WSGI response headers using a mapping-like interface.

class Headers (*headers*)

Create a mapping-like object wrapping *headers*, which must be a list of header name/value tuples as described in PEP 333. Any changes made to the new `Headers` object will directly update the *headers* list it was created with.

`Headers` objects support typical mapping operations including `__getitem__`, `get`, `__setitem__`, `setdefault`, `__delitem__`, `__contains__` and `has_key`. For each of these methods, the key is the header name (treated case-insensitively), and the value is the first value associated with that header name. Setting a header deletes any existing values for that header, then adds a new value at the end of the wrapped

header list. Headers' existing order is generally maintained, with new headers added to the end of the wrapped list.

Unlike a dictionary, `Headers` objects do not raise an error when you try to get or delete a key that isn't in the wrapped header list. Getting a nonexistent header just returns `None`, and deleting a nonexistent header does nothing.

`Headers` objects also support `keys()`, `values()`, and `items()` methods. The lists returned by `keys()` and `items()` can include the same key more than once if there is a multi-valued header. The `len()` of a `Headers` object is the same as the length of its `items()`, which is the same as the length of the wrapped header list. In fact, the `items()` method just returns a copy of the wrapped header list.

Calling `str()` on a `Headers` object returns a formatted string suitable for transmission as HTTP response headers. Each header is placed on a line with its value, separated by a colon and a space. Each line is terminated by a carriage return and line feed, and the string is terminated with a blank line.

In addition to their mapping interface and formatting features, `Headers` objects also have the following methods for querying and adding multi-valued headers, and for adding headers with MIME parameters:

get_all (*name*)

Return a list of all the values for the named header.

The returned list will be sorted in the order they appeared in the original header list or were added to this instance, and may contain duplicates. Any fields deleted and re-inserted are always appended to the header list. If no fields exist with the given name, returns an empty list.

add_header (*name*, *value*, ***_params*)

Add a (possibly multi-valued) header, with optional MIME parameters specified via keyword arguments.

name is the header field to add. Keyword arguments can be used to set MIME parameters for the header field. Each parameter must be a string or `None`. Underscores in parameter names are converted to dashes, since dashes are illegal in Python identifiers, but many MIME parameter names include dashes. If the parameter value is a string, it is added to the header value parameters in the form `name="value"`. If it is `None`, only the parameter name is added. (This is used for MIME parameters without a value.) Example usage:

```
h.add_header('content-disposition', 'attachment', filename='bud.gif')
```

The above will add a header that looks like this:

```
Content-Disposition: attachment; filename="bud.gif"
```

18.4.3 `wsgiref.simple_server` – a simple WSGI HTTP server

This module implements a simple HTTP server (based on `BaseHTTPServer`) that serves WSGI applications. Each server instance serves a single WSGI application on a given host and port. If you want to serve multiple applications on a single host and port, you should create a WSGI application that parses `PATH_INFO` to select which application to invoke for each request. (E.g., using the `shift_path_info()` function from `wsgiref.util`.)

make_server (*host*, *port*, *app* [, *server_class*=`WSGIServer` [, *handler_class*=`WSGIRequestHandler`]])

Create a new WSGI server listening on *host* and *port*, accepting connections for *app*. The return value is an instance of the supplied *server_class*, and will process requests using the specified *handler_class*. *app* must be a WSGI application object, as defined by PEP 333.

Example usage:


```

from wsgiref.simple_server import make_server, demo_app

httpd = make_server('', 8000, demo_app)
print "Serving HTTP on port 8000..."

# Respond to requests until process is killed
httpd.serve_forever()

# Alternative: serve one request, then exit
##httpd.handle_request()

```

demo_app (*environ*, *start_response*)

This function is a small but complete WSGI application that returns a text page containing the message “Hello world!” and a list of the key/value pairs provided in the *environ* parameter. It’s useful for verifying that a WSGI server (such as `wsgiref.simple_server`) is able to run a simple WSGI application correctly.

class WSGIServer (*server_address*, *RequestHandlerClass*)

Create a `WSGIServer` instance. *server_address* should be a (*host*, *port*) tuple, and *RequestHandlerClass* should be the subclass of `BaseHTTPServer.BaseHTTPRequestHandler` that will be used to process requests.

You do not normally need to call this constructor, as the `make_server()` function can handle all the details for you.

`WSGIServer` is a subclass of `BaseHTTPServer.HTTPServer`, so all of its methods (such as `serve_forever()` and `handle_request()`) are available. `WSGIServer` also provides these WSGI-specific methods:

set_app (*application*)

Sets the callable *application* as the WSGI application that will receive requests.

get_app ()

Returns the currently-set application callable.

Normally, however, you do not need to use these additional methods, as `set_app()` is normally called by `make_server()`, and the `get_app()` exists mainly for the benefit of request handler instances.

class WSGIRequestHandler (*request*, *client_address*, *server*)

Create an HTTP handler for the given *request* (i.e. a socket), *client_address* (a (*host*, *port*) tuple), and *server* (`WSGIServer` instance).

You do not need to create instances of this class directly; they are automatically created as needed by `WSGIServer` objects. You can, however, subclass this class and supply it as a *handler_class* to the `make_server()` function. Some possibly relevant methods for overriding in subclasses:

get_environ ()

Returns a dictionary containing the WSGI environment for a request. The default implementation copies the contents of the `WSGIServer` object’s `base_environ` dictionary attribute and then adds various headers derived from the HTTP request. Each call to this method should return a new dictionary containing all of the relevant CGI environment variables as specified in PEP 333.

get_stderr ()

Return the object that should be used as the `wsgi.errors` stream. The default implementation just returns `sys.stderr`.

handle ()

Process the HTTP request. The default implementation creates a handler instance using a `wsgiref.handlers` class to implement the actual WSGI application interface.

18.4.4 `wsgiref.validate` – WSGI conformance checker

When creating new WSGI application objects, frameworks, servers, or middleware, it can be useful to validate the new code's conformance using `wsgiref.validate`. This module provides a function that creates WSGI application objects that validate communications between a WSGI server or gateway and a WSGI application object, to check both sides for protocol conformance.

Note that this utility does not guarantee complete PEP 333 compliance; an absence of errors from this module does not necessarily mean that errors do not exist. However, if this module does produce an error, then it is virtually certain that either the server or application is not 100% compliant.

This module is based on the `paste.lint` module from Ian Bicking's "Python Paste" library.

validator (*application*)

Wrap *application* and return a new WSGI application object. The returned application will forward all requests to the original *application*, and will check that both the *application* and the server invoking it are conforming to the WSGI specification and to RFC 2616.

Any detected nonconformance results in an `AssertionError` being raised; note, however, that how these errors are handled is server-dependent. For example, `wsgiref.simple_server` and other servers based on `wsgiref.handlers` (that don't override the error handling methods to do something else) will simply output a message that an error has occurred, and dump the traceback to `sys.stderr` or some other error stream.

This wrapper may also generate output using the `warnings` module to indicate behaviors that are questionable but which may not actually be prohibited by PEP 333. Unless they are suppressed using Python command-line options or the `warnings` API, any such warnings will be written to `sys.stderr` (*not* `wsgi.errors`, unless they happen to be the same object).

18.4.5 `wsgiref.handlers` – server/gateway base classes

This module provides base handler classes for implementing WSGI servers and gateways. These base classes handle most of the work of communicating with a WSGI application, as long as they are given a CGI-like environment, along with input, output, and error streams.

class CGIHandler ()

CGI-based invocation via `sys.stdin`, `sys.stdout`, `sys.stderr` and `os.environ`. This is useful when you have a WSGI application and want to run it as a CGI script. Simply invoke `CGIHandler().run(app)`, where `app` is the WSGI application object you wish to invoke.

This class is a subclass of `BaseCGIHandler` that sets `wsgi.run_once` to `true`, `wsgi.multithread` to `false`, and `wsgi.multiprocess` to `true`, and always uses `sys` and `os` to obtain the necessary CGI streams and environment.

class BaseCGIHandler (*stdin, stdout, stderr, environ* [, *multithread=True* [, *multiprocess=False*]])

Similar to `CGIHandler`, but instead of using the `sys` and `os` modules, the CGI environment and I/O streams are specified explicitly. The *multithread* and *multiprocess* values are used to set the `wsgi.multithread` and `wsgi.multiprocess` flags for any applications run by the handler instance.

This class is a subclass of `SimpleHandler` intended for use with software other than HTTP "origin servers". If you are writing a gateway protocol implementation (such as CGI, FastCGI, SCGI, etc.) that uses a `Status:` header to send an HTTP status, you probably want to subclass this instead of `SimpleHandler`.

class SimpleHandler (*stdin, stdout, stderr, environ* [, *multithread=True* [, *multiprocess=False*]])

Similar to `BaseCGIHandler`, but designed for use with HTTP origin servers. If you are writing an HTTP server implementation, you will probably want to subclass this instead of `BaseCGIHandler`.

This class is a subclass of `BaseHandler`. It overrides the `__init__()`, `get_stdin()`, `get_stderr()`, `add_cgi_vars()`, `_write()`, and `_flush()` methods to support explicitly setting the environment and streams via the constructor. The supplied environment and streams are stored in the `stdin`, `stdout`, `stderr`, and `environ` attributes.

class BaseHandler ()

This is an abstract base class for running WSGI applications. Each instance will handle a single HTTP request, although in principle you could create a subclass that was reusable for multiple requests.

`BaseHandler` instances have only one method intended for external use:

`run (app)`

Run the specified WSGI application, *app*.

All of the other `BaseHandler` methods are invoked by this method in the process of running the application, and thus exist primarily to allow customizing the process.

The following methods **MUST** be overridden in a subclass:

`_write (data)`

Buffer the string *data* for transmission to the client. It's okay if this method actually transmits the data; `BaseHandler` just separates write and flush operations for greater efficiency when the underlying system actually has such a distinction.

`_flush ()`

Force buffered data to be transmitted to the client. It's okay if this method is a no-op (i.e., if `_write ()` actually sends the data).

`get_stdin ()`

Return an input stream object suitable for use as the `wsgi.input` of the request currently being processed.

`get_stderr ()`

Return an output stream object suitable for use as the `wsgi.errors` of the request currently being processed.

`add_cgi_vars ()`

Insert CGI variables for the current request into the `environ` attribute.

Here are some other methods and attributes you may wish to override. This list is only a summary, however, and does not include every method that can be overridden. You should consult the docstrings and source code for additional information before attempting to create a customized `BaseHandler` subclass.

Attributes and methods for customizing the WSGI environment:

`wsgi_multithread`

The value to be used for the `wsgi.multithread` environment variable. It defaults to `true` in `BaseHandler`, but may have a different default (or be set by the constructor) in the other subclasses.

`wsgi_multiprocess`

The value to be used for the `wsgi.multiprocess` environment variable. It defaults to `true` in `BaseHandler`, but may have a different default (or be set by the constructor) in the other subclasses.

`wsgi_run_once`

The value to be used for the `wsgi.run_once` environment variable. It defaults to `false` in `BaseHandler`, but `CGIHandler` sets it to `true` by default.

`os_environ`

The default environment variables to be included in every request's WSGI environment. By default, this is a copy of `os.environ` at the time that `wsgiref.handlers` was imported, but subclasses can either create their own at the class or instance level. Note that the dictionary should be considered read-only, since the default value is shared between multiple classes and instances.

`server_software`

If the `origin_server` attribute is set, this attribute's value is used to set the default `SERVER_SOFTWARE` WSGI environment variable, and also to set a default `Server:` header in HTTP responses. It is ignored for handlers (such as `BaseCGIHandler` and `CGIHandler`) that are not HTTP origin servers.

`get_scheme ()`

Return the URL scheme being used for the current request. The default implementation uses the `guess_scheme ()` function from `wsgiref.util` to guess whether the scheme should be "http" or "https", based on the current request's `environ` variables.

setup_environ()

Set the `environ` attribute to a fully-populated WSGI environment. The default implementation uses all of the above methods and attributes, plus the `get_stdin()`, `get_stderr()`, and `add_cgi_vars()` methods and the `wsgi_file_wrapper` attribute. It also inserts a `SERVER_SOFTWARE` key if not present, as long as the `origin_server` attribute is a true value and the `server_software` attribute is set.

Methods and attributes for customizing exception handling:

log_exception(exc_info)

Log the `exc_info` tuple in the server log. `exc_info` is a `(type, value, traceback)` tuple. The default implementation simply writes the traceback to the request's `wsgi.errors` stream and flushes it. Subclasses can override this method to change the format or retarget the output, mail the traceback to an administrator, or whatever other action may be deemed suitable.

traceback_limit

The maximum number of frames to include in tracebacks output by the default `log_exception()` method. If `None`, all frames are included.

error_output(envIRON, start_response)

This method is a WSGI application to generate an error page for the user. It is only invoked if an error occurs before headers are sent to the client.

This method can access the current error information using `sys.exc_info()`, and should pass that information to `start_response` when calling it (as described in the “Error Handling” section of PEP 333).

The default implementation just uses the `error_status`, `error_headers`, and `error_body` attributes to generate an output page. Subclasses can override this to produce more dynamic error output.

Note, however, that it's not recommended from a security perspective to spit out diagnostics to any old user; ideally, you should have to do something special to enable diagnostic output, which is why the default implementation doesn't include any.

error_status

The HTTP status used for error responses. This should be a status string as defined in PEP 333; it defaults to a 500 code and message.

error_headers

The HTTP headers used for error responses. This should be a list of WSGI response headers `((name, value))` tuples), as described in PEP 333. The default list just sets the content type to `text/plain`.

error_body

The error response body. This should be an HTTP response body string. It defaults to the plain text, “A server error occurred. Please contact the administrator.”

Methods and attributes for PEP 333's “Optional Platform-Specific File Handling” feature:

wsgi_file_wrapper

A `wsgi.file_wrapper` factory, or `None`. The default value of this attribute is the `FileWrapper` class from `wsgiref.util`.

sendfile()

Override to implement platform-specific file transmission. This method is called only if the application's return value is an instance of the class specified by the `wsgi_file_wrapper` attribute. It should return a true value if it was able to successfully transmit the file, so that the default transmission code will not be executed. The default implementation of this method just returns a false value.

Miscellaneous methods and attributes:

origin_server

This attribute should be set to a true value if the handler's `_write()` and `_flush()` are being used to communicate directly to the client, rather than via a CGI-like gateway protocol that wants the HTTP status in a special `Status:` header.

This attribute's default value is true in `BaseHandler`, but false in `BaseCGIHandler` and `CGIHandler`.

http_version

If `origin_server` is true, this string attribute is used to set the HTTP version of the response set to the client. It defaults to "1.0".

18.5 urllib — Open arbitrary resources by URL

This module provides a high-level interface for fetching data across the World Wide Web. In particular, the `urlopen()` function is similar to the built-in function `open()`, but accepts Universal Resource Locators (URLs) instead of filenames. Some restrictions apply — it can only open URLs for reading, and no seek operations are available.

It defines the following public functions:

urlopen(*url*[, *data*[, *proxies*]])

Open a network object denoted by a URL for reading. If the URL does not have a scheme identifier, or if it has 'file:' as its scheme identifier, this opens a local file (without universal newlines); otherwise it opens a socket to a server somewhere on the network. If the connection cannot be made the `IOError` exception is raised. If all went well, a file-like object is returned. This supports the following methods: `read()`, `readline()`, `readlines()`, `fileno()`, `close()`, `info()` and `geturl()`. It also has proper support for the iterator protocol. One caveat: the `read()` method, if the size argument is omitted or negative, may not read until the end of the data stream; there is no good way to determine that the entire stream from a socket has been read in the general case.

Except for the `info()` and `geturl()` methods, these methods have the same interface as for file objects — see section 3.9 in this manual. (It is not a built-in file object, however, so it can't be used at those few places where a true built-in file object is required.)

The `info()` method returns an instance of the class `mimertools.Message` containing meta-information associated with the URL. When the method is HTTP, these headers are those returned by the server at the head of the retrieved HTML page (including Content-Length and Content-Type). When the method is FTP, a Content-Length header will be present if (as is now usual) the server passed back a file length in response to the FTP retrieval request. A Content-Type header will be present if the MIME type can be guessed. When the method is local-file, returned headers will include a Date representing the file's last-modified time, a Content-Length giving file size, and a Content-Type containing a guess at the file's type. See also the description of the `mimertools` module.

The `geturl()` method returns the real URL of the page. In some cases, the HTTP server redirects a client to another URL. The `urlopen()` function handles this transparently, but in some cases the caller needs to know which URL the client was redirected to. The `geturl()` method can be used to get at this redirected URL.

If the *url* uses the 'http:' scheme identifier, the optional *data* argument may be given to specify a POST request (normally the request type is GET). The *data* argument must be in standard application/x-www-form-urlencoded format; see the `urlencode()` function below.

The `urlopen()` function works transparently with proxies which do not require authentication. In a UNIX or Windows environment, set the `http_proxy`, `ftp_proxy` or `gopher_proxy` environment variables to a URL that identifies the proxy server before starting the Python interpreter. For example (the '%' is the command prompt):

```
% http_proxy="http://www.someproxy.com:3128"
% export http_proxy
% python
...
```

In a Windows environment, if no proxy environment variables are set, proxy settings are obtained from the registry's Internet Settings section.

In a Macintosh environment, `urlopen()` will retrieve proxy information from Internet Config.

Alternatively, the optional *proxies* argument may be used to explicitly specify proxies. It must be a dictionary mapping scheme names to proxy URLs, where an empty dictionary causes no proxies to be used, and *None* (the default value) causes environmental proxy settings to be used as discussed above. For example:

```
# Use http://www.someproxy.com:3128 for http proxying
proxies = {'http': 'http://www.someproxy.com:3128'}
filehandle = urllib.urlopen(some_url, proxies=proxies)
# Don't use any proxies
filehandle = urllib.urlopen(some_url, proxies={})
# Use proxies from environment - both versions are equivalent
filehandle = urllib.urlopen(some_url, proxies=None)
filehandle = urllib.urlopen(some_url)
```

The `urlopen()` function does not support explicit proxy specification. If you need to override environmental proxy settings, use `URLopener`, or a subclass such as `FancyURLopener`.

Proxies which require authentication for use are not currently supported; this is considered an implementation limitation.

Changed in version 2.3: Added the *proxies* support.

urlretrieve(*url*[, *filename*[, *reporthook*[, *data*]]])

Copy a network object denoted by a URL to a local file, if necessary. If the URL points to a local file, or a valid cached copy of the object exists, the object is not copied. Return a tuple (*filename*, *headers*) where *filename* is the local file name under which the object can be found, and *headers* is whatever the `info()` method of the object returned by `urlopen()` returned (for a remote object, possibly cached). Exceptions are the same as for `urlopen()`.

The second argument, if present, specifies the file location to copy to (if absent, the location will be a tempfile with a generated name). The third argument, if present, is a hook function that will be called once on establishment of the network connection and once after each block read thereafter. The hook will be passed three arguments; a count of blocks transferred so far, a block size in bytes, and the total size of the file. The third argument may be `-1` on older FTP servers which do not return a file size in response to a retrieval request.

If the *url* uses the 'http:' scheme identifier, the optional *data* argument may be given to specify a POST request (normally the request type is GET). The *data* argument must in standard application/x-www-form-urlencoded format; see the `urlencode()` function below.

Changed in version 2.5: `urlretrieve()` will raise `ContentTooShortError` when it detects that the amount of data available was less than the expected amount (which is the size reported by a *Content-Length* header). This can occur, for example, when the download is interrupted.

The *Content-Length* is treated as a lower bound: if there's more data to read, `urlretrieve` reads more data, but if less data is available, it raises the exception.

You can still retrieve the downloaded data in this case, it is stored in the `content` attribute of the exception instance.

If no *Content-Length* header was supplied, `urlretrieve` can not check the size of the data it has downloaded, and just returns it. In this case you just have to assume that the download was successful.

_url opener

The public functions `urlopen()` and `urlretrieve()` create an instance of the `FancyURLopener` class and use it to perform their requested actions. To override this functionality, programmers can create a subclass of `URLopener` or `FancyURLopener`, then assign an instance of that class to the `urllib._url opener` variable before calling the desired function. For example, applications may want to specify a different User-Agent: header than `URLopener` defines. This can be accomplished with the following code:

```
import urllib

class AppURLopener(urllib.FancyURLopener):
    version = "App/1.7"

urllib._urlopener = AppURLopener()
```

urllib.cleanup()

Clear the cache that may have been built up by previous calls to `urlretrieve()`.

quote(string[, safe])

Replace special characters in *string* using the ‘%xx’ escape. Letters, digits, and the characters ‘_’ and ‘-’ are never quoted. The optional *safe* parameter specifies additional characters that should not be quoted — its default value is ‘/’.

Example: `quote('/~connolly/')` yields `/%7econnolly/`.

quote_plus(string[, safe])

Like `quote()`, but also replaces spaces by plus signs, as required for quoting HTML form values. Plus signs in the original string are escaped unless they are included in *safe*. It also does not have *safe* default to ‘/’.

unquote(string)

Replace ‘%xx’ escapes by their single-character equivalent.

Example: `unquote('/%7Econnolly/')` yields `'/~connolly/'`.

unquote_plus(string)

Like `unquote()`, but also replaces plus signs by spaces, as required for unquoting HTML form values.

urlencode(query[, doseq])

Convert a mapping object or a sequence of two-element tuples to a “url-encoded” string, suitable to pass to `urlopen()` above as the optional *data* argument. This is useful to pass a dictionary of form fields to a POST request. The resulting string is a series of *key=value* pairs separated by ‘&’ characters, where both *key* and *value* are quoted using `quote_plus()` above. If the optional parameter *doseq* is present and evaluates to true, individual *key=value* pairs are generated for each element of the sequence. When a sequence of two-element tuples is used as the *query* argument, the first element of each tuple is a key and the second is a value. The order of parameters in the encoded string will match the order of parameter tuples in the sequence. The `cgi` module provides the functions `parse_qs()` and `parse_qsl()` which are used to parse query strings into Python data structures.

pathname2url(path)

Convert the pathname *path* from the local syntax for a path to the form used in the path component of a URL. This does not produce a complete URL. The return value will already be quoted using the `quote()` function.

url2pathname(path)

Convert the path component *path* from an encoded URL to the local syntax for a path. This does not accept a complete URL. This function uses `unquote()` to decode *path*.

class URLOpener([proxies[, **x509]])

Base class for opening and reading URLs. Unless you need to support opening objects using schemes other than ‘http:’, ‘ftp:’, ‘gopher:’ or ‘file:’, you probably want to use `FancyURLopener`.

By default, the `URLOpener` class sends a User-Agent: header of ‘urllib/VVV’, where VVV is the `urllib` version number. Applications can define their own User-Agent: header by subclassing `URLOpener` or `FancyURLopener` and setting the class attribute `version` to an appropriate string value in the subclass definition.

The optional *proxies* parameter should be a dictionary mapping scheme names to proxy URLs, where an empty dictionary turns proxies off completely. Its default value is `None`, in which case environmental proxy settings will be used if present, as discussed in the definition of `urlopen()`, above.

Additional keyword parameters, collected in *x509*, may be used for authentication of the client when using the 'https:' scheme. The keywords *key_file* and *cert_file* are supported to provide an SSL key and certificate; both are needed to support client authentication.

`URLopener` objects will raise an `IOError` exception if the server returns an error code.

class `FancyURLopener` (...)

`FancyURLopener` subclasses `URLopener` providing default handling for the following HTTP response codes: 301, 302, 303, 307 and 401. For the 30x response codes listed above, the `Location:` header is used to fetch the actual URL. For 401 response codes (authentication required), basic HTTP authentication is performed. For the 30x response codes, recursion is bounded by the value of the *maxtries* attribute, which defaults to 10.

For all other response codes, the method `http_error_default()` is called which you can override in subclasses to handle the error appropriately.

Note: According to the letter of RFC 2616, 301 and 302 responses to POST requests must not be automatically redirected without confirmation by the user. In reality, browsers do allow automatic redirection of these responses, changing the POST to a GET, and `urllib` reproduces this behaviour.

The parameters to the constructor are the same as those for `URLopener`.

Note: When performing basic authentication, a `FancyURLopener` instance calls its `prompt_user_passwd()` method. The default implementation asks the users for the required information on the controlling terminal. A subclass may override this method to support more appropriate behavior if needed.

exception `ContentTooShortError` (*msg* [, *content*])

This exception is raised when the `urlretrieve()` function detects that the amount of the downloaded data is less than the expected amount (given by the *Content-Length* header). The *content* attribute stores the downloaded (and supposedly truncated) data. New in version 2.5.

Restrictions:

- Currently, only the following protocols are supported: HTTP, (versions 0.9 and 1.0), Gopher (but not Gopher+), FTP, and local files.
- The caching feature of `urlretrieve()` has been disabled until I find the time to hack proper processing of Expiration time headers.
- There should be a function to query whether a particular URL is in the cache.
- For backward compatibility, if a URL appears to point to a local file but the file can't be opened, the URL is re-interpreted using the FTP protocol. This can sometimes cause confusing error messages.
- The `urlopen()` and `urlretrieve()` functions can cause arbitrarily long delays while waiting for a network connection to be set up. This means that it is difficult to build an interactive Web client using these functions without using threads.
- The data returned by `urlopen()` or `urlretrieve()` is the raw data returned by the server. This may be binary data (such as an image), plain text or (for example) HTML. The HTTP protocol provides type information in the reply header, which can be inspected by looking at the `Content-Type:` header. For the Gopher protocol, type information is encoded in the URL; there is currently no easy way to extract it. If the returned data is HTML, you can use the module `htmllib` to parse it.
- The code handling the FTP protocol cannot differentiate between a file and a directory. This can lead to unexpected behavior when attempting to read a URL that points to a file that is not accessible. If the URL ends in a `/`, it is assumed to refer to a directory and will be handled accordingly. But if an attempt to read a file leads to a 550 error (meaning the URL cannot be found or is not accessible, often for permission reasons), then the path is treated as a directory in order to handle the case when a directory is specified by a URL but the trailing `/` has been left off. This can cause misleading results when you try to fetch a file whose read permissions make it inaccessible; the FTP code will try to read it, fail with a 550 error, and then perform a directory

listing for the unreadable file. If fine-grained control is needed, consider using the `ftplib` module, subclassing `FancyURLopener`, or changing `_urlopener` to meet your needs.

- This module does not support the use of proxies which require authentication. This may be implemented in the future.
- Although the `urllib` module contains (undocumented) routines to parse and unparse URL strings, the recommended interface for URL manipulation is in module [urlparse](#).

18.5.1 URLopener Objects

`URLopener` and `FancyURLopener` objects have the following attributes.

open (*fullurl* [, *data*])

Open *fullurl* using the appropriate protocol. This method sets up cache and proxy information, then calls the appropriate open method with its input arguments. If the scheme is not recognized, `open_unknown()` is called. The *data* argument has the same meaning as the *data* argument of `urlopen()`.

open_unknown (*fullurl* [, *data*])

Overridable interface to open unknown URL types.

retrieve (*url* [, *filename* [, *reporthook* [, *data*]]])

Retrieves the contents of *url* and places it in *filename*. The return value is a tuple consisting of a local filename and either a `mimetypes.Message` object containing the response headers (for remote URLs) or `None` (for local URLs). The caller must then open and read the contents of *filename*. If *filename* is not given and the URL refers to a local file, the input filename is returned. If the URL is non-local and *filename* is not given, the filename is the output of `tempfile.mktemp()` with a suffix that matches the suffix of the last path component of the input URL. If *reporthook* is given, it must be a function accepting three numeric parameters. It will be called after each chunk of data is read from the network. *reporthook* is ignored for local URLs.

If the *url* uses the ‘http:’ scheme identifier, the optional *data* argument may be given to specify a POST request (normally the request type is GET). The *data* argument must in standard `application/x-www-form-urlencoded` format; see the `urlencode()` function below.

version

Variable that specifies the user agent of the opener object. To get [urllib](#) to tell servers that it is a particular user agent, set this in a subclass as a class variable or in the constructor before calling the base constructor.

The `FancyURLopener` class offers one additional method that should be overloaded to provide the appropriate behavior:

prompt_user_passwd (*host*, *realm*)

Return information needed to authenticate the user at the given host in the specified security realm. The return value should be a tuple, (*user*, *password*), which can be used for basic authentication.

The implementation prompts for this information on the terminal; an application should override this method to use an appropriate interaction model in the local environment.

18.5.2 Examples

Here is an example session that uses the ‘GET’ method to retrieve a URL containing parameters:

```
>>> import urllib
>>> params = urllib.urlencode({'spam': 1, 'eggs': 2, 'bacon': 0})
>>> f = urllib.urlopen("http://www.musi-cal.com/cgi-bin/query?%s" % params)
>>> print f.read()
```

The following example uses the ‘POST’ method instead:

```
>>> import urllib
>>> params = urllib.urlencode({'spam': 1, 'eggs': 2, 'bacon': 0})
>>> f = urllib.urlopen("http://www.musi-cal.com/cgi-bin/query", params)
>>> print f.read()
```

The following example uses an explicitly specified HTTP proxy, overriding environment settings:

```
>>> import urllib
>>> proxies = {'http': 'http://proxy.example.com:8080/'}
>>> opener = urllib.FancyURLopener(proxies)
>>> f = opener.open("http://www.python.org")
>>> f.read()
```

The following example uses no proxies at all, overriding environment settings:

```
>>> import urllib
>>> opener = urllib.FancyURLopener({})
>>> f = opener.open("http://www.python.org/")
>>> f.read()
```

18.6 urllib2 — extensible library for opening URLs

The `urllib2` module defines functions and classes which help in opening URLs (mostly HTTP) in a complex world — basic and digest authentication, redirections, cookies and more.

The `urllib2` module defines the following functions:

urlopen (*url* [, *data*])

Open the URL *url*, which can be either a string or a `Request` object.

data may be a string specifying additional data to send to the server, or `None` if no such data is needed. Currently HTTP requests are the only ones that use *data*; the HTTP request will be a POST instead of a GET when the *data* parameter is provided. *data* should be a buffer in the standard application/x-www-form-urlencoded format. The `urllib.urlencode()` function takes a mapping or sequence of 2-tuples and returns a string in this format.

This function returns a file-like object with two additional methods:

- `geturl()` — return the URL of the resource retrieved
- `info()` — return the meta-information of the page, as a dictionary-like object

Raises `URLError` on errors.

Note that `None` may be returned if no handler handles the request (though the default installed global `OpenerDirector` uses `UnknownHandler` to ensure this never happens).

install_opener (*opener*)

Install an `OpenerDirector` instance as the default global opener. Installing an opener is only necessary if you want `urlopen` to use that opener; otherwise, simply call `OpenerDirector.open()` instead of `urlopen()`. The code does not check for a real `OpenerDirector`, and any class with the appropriate interface will work.

build_opener ([*handler*, ...])

Return an `OpenerDirector` instance, which chains the handlers in the order given. *handlers* can be either instances of `BaseHandler`, or subclasses of `BaseHandler` (in which case it must be possible to call the constructor without any parameters). Instances of the following classes will be in front of the *handlers*, unless the *handlers* contain them, instances of them or subclasses of them: `ProxyHandler`, `UnknownHandler`, `HTTPHandler`, `HTTPDefaultErrorHandler`, `HTTPRedirectHandler`, `FTPHandler`, `FileHandler`, `HTTPErrorProcessor`.

If the Python installation has SSL support (`socket.ssl()` exists), `HTTPSHandler` will also be added.

Beginning in Python 2.3, a `BaseHandler` subclass may also change its `handler_order` member variable to modify its position in the handlers list.

The following exceptions are raised as appropriate:

exception URLError

The handlers raise this exception (or derived exceptions) when they run into a problem. It is a subclass of `IOError`.

exception HTTPError

A subclass of `URLError`, it can also function as a non-exceptional file-like return value (the same thing that `urlopen()` returns). This is useful when handling exotic HTTP errors, such as requests for authentication.

exception GopherError

A subclass of `URLError`, this is the error raised by the Gopher handler.

The following classes are provided:

class Request (*url* [, *data*] [, *headers*] [, *origin_req_host*] [, *unverifiable*])

This class is an abstraction of a URL request.

url should be a string containing a valid URL.

data may be a string specifying additional data to send to the server, or `None` if no such data is needed. Currently HTTP requests are the only ones that use *data*; the HTTP request will be a POST instead of a GET when the *data* parameter is provided. *data* should be a buffer in the standard application/x-www-form-urlencoded format. The `urllib.urlencode()` function takes a mapping or sequence of 2-tuples and returns a string in this format.

headers should be a dictionary, and will be treated as if `add_header()` was called with each key and value as arguments.

The final two arguments are only of interest for correct handling of third-party HTTP cookies:

origin_req_host should be the request-host of the origin transaction, as defined by RFC 2965. It defaults to `cookielib.request_host(self)`. This is the host name or IP address of the original request that was initiated by the user. For example, if the request is for an image in an HTML document, this should be the request-host of the request for the page containing the image.

unverifiable should indicate whether the request is unverifiable, as defined by RFC 2965. It defaults to `False`. An unverifiable request is one whose URL the user did not have the option to approve. For example, if the request is for an image in an HTML document, and the user had no option to approve the automatic fetching of the image, this should be `true`.

class OpenerDirector ()

The `OpenerDirector` class opens URLs via `BaseHandlers` chained together. It manages the chaining of handlers, and recovery from errors.

class BaseHandler ()

This is the base class for all registered handlers — and handles only the simple mechanics of registration.

class HTTPDefaultErrorHandler ()

A class which defines a default handler for HTTP error responses; all responses are turned into `HTTPError` exceptions.

class HTTPRedirectHandler ()
A class to handle redirections.

class HTTPCookieProcessor ([*cookiejar*])
A class to handle HTTP Cookies.

class ProxyHandler ([*proxies*])
Cause requests to go through a proxy. If *proxies* is given, it must be a dictionary mapping protocol names to URLs of proxies. The default is to read the list of proxies from the environment variables `protocol_proxy`.

class HTTPPasswordMgr ()
Keep a database of (*realm, uri*) -> (*user, password*) mappings.

class HTTPPasswordMgrWithDefaultRealm ()
Keep a database of (*realm, uri*) -> (*user, password*) mappings. A realm of `None` is considered a catch-all realm, which is searched if no other realm fits.

class AbstractBasicAuthHandler ([*password_mgr*])
This is a mixin class that helps with HTTP authentication, both to the remote host and to a proxy. *password_mgr*, if given, should be something that is compatible with `HTTPPasswordMgr`; refer to section 18.6.7 for information on the interface that must be supported.

class HTTPBasicAuthHandler ([*password_mgr*])
Handle authentication with the remote host. *password_mgr*, if given, should be something that is compatible with `HTTPPasswordMgr`; refer to section 18.6.7 for information on the interface that must be supported.

class ProxyBasicAuthHandler ([*password_mgr*])
Handle authentication with the proxy. *password_mgr*, if given, should be something that is compatible with `HTTPPasswordMgr`; refer to section 18.6.7 for information on the interface that must be supported.

class AbstractDigestAuthHandler ([*password_mgr*])
This is a mixin class that helps with HTTP authentication, both to the remote host and to a proxy. *password_mgr*, if given, should be something that is compatible with `HTTPPasswordMgr`; refer to section 18.6.7 for information on the interface that must be supported.

class HTTPDigestAuthHandler ([*password_mgr*])
Handle authentication with the remote host. *password_mgr*, if given, should be something that is compatible with `HTTPPasswordMgr`; refer to section 18.6.7 for information on the interface that must be supported.

class ProxyDigestAuthHandler ([*password_mgr*])
Handle authentication with the proxy. *password_mgr*, if given, should be something that is compatible with `HTTPPasswordMgr`; refer to section 18.6.7 for information on the interface that must be supported.

class HTTPHandler ()
A class to handle opening of HTTP URLs.

class HTTPSHandler ()
A class to handle opening of HTTPS URLs.

class FileHandler ()
Open local files.

class FTPHandler ()
Open FTP URLs.

class CacheFTPHandler ()
Open FTP URLs, keeping a cache of open FTP connections to minimize delays.

class GopherHandler ()
Open gopher URLs.

class UnknownHandler ()
A catch-all class to handle unknown URLs.

18.6.1 Request Objects

The following methods describe all of `Request`'s public interface, and so all must be overridden in subclasses.

add_data (*data*)

Set the `Request` data to *data*. This is ignored by all handlers except HTTP handlers — and there it should be a byte string, and will change the request to be `POST` rather than `GET`.

get_method ()

Return a string indicating the HTTP request method. This is only meaningful for HTTP requests, and currently always returns `'GET'` or `'POST'`.

has_data ()

Return whether the instance has a non-`None` data.

get_data ()

Return the instance's data.

add_header (*key*, *val*)

Add another header to the request. Headers are currently ignored by all handlers except HTTP handlers, where they are added to the list of headers sent to the server. Note that there cannot be more than one header with the same name, and later calls will overwrite previous calls in case the *key* collides. Currently, this is no loss of HTTP functionality, since all headers which have meaning when used more than once have a (header-specific) way of gaining the same functionality using only one header.

add_unredirected_header (*key*, *header*)

Add a header that will not be added to a redirected request. New in version 2.4.

has_header (*header*)

Return whether the instance has the named header (checks both regular and unredirected). New in version 2.4.

get_full_url ()

Return the URL given in the constructor.

get_type ()

Return the type of the URL — also known as the scheme.

get_host ()

Return the host to which a connection will be made.

get_selector ()

Return the selector — the part of the URL that is sent to the server.

set_proxy (*host*, *type*)

Prepare the request by connecting to a proxy server. The *host* and *type* will replace those of the instance, and the instance's selector will be the original URL given in the constructor.

get_origin_req_host ()

Return the request-host of the origin transaction, as defined by RFC 2965. See the documentation for the `Request` constructor.

is_unverifiable ()

Return whether the request is unverifiable, as defined by RFC 2965. See the documentation for the `Request` constructor.

18.6.2 OpenerDirector Objects

`OpenerDirector` instances have the following methods:

add_handler (*handler*)

handler should be an instance of `BaseHandler`. The following methods are searched, and added to the

possible chains (note that HTTP errors are a special case).

- `protocol_open()` — signal that the handler knows how to open *protocol* URLs.
- `http_error_type()` — signal that the handler knows how to handle HTTP errors with HTTP error code *type*.
- `protocol_error()` — signal that the handler knows how to handle errors from (non-http) *protocol*.
- `protocol_request()` — signal that the handler knows how to pre-process *protocol* requests.
- `protocol_response()` — signal that the handler knows how to post-process *protocol* responses.

open (*url* [, *data*])

Open the given *url* (which can be a request object or a string), optionally passing the given *data*. Arguments, return values and exceptions raised are the same as those of `urlopen()` (which simply calls the `open()` method on the currently installed global `OpenerDirector`).

error (*proto* [, *arg* [, ...]])

Handle an error of the given protocol. This will call the registered error handlers for the given protocol with the given arguments (which are protocol specific). The HTTP protocol is a special case which uses the HTTP response code to determine the specific error handler; refer to the `http_error_*()` methods of the handler classes.

Return values and exceptions raised are the same as those of `urlopen()`.

`OpenerDirector` objects open URLs in three stages:

The order in which these methods are called within each stage is determined by sorting the handler instances.

1. Every handler with a method named like `protocol_request()` has that method called to pre-process the request.
2. Handlers with a method named like `protocol_open()` are called to handle the request. This stage ends when a handler either returns a non-None value (ie. a response), or raises an exception (usually `URLError`). Exceptions are allowed to propagate.

In fact, the above algorithm is first tried for methods named `default_open`. If all such methods return `None`, the algorithm is repeated for methods named like `protocol_open()`. If all such methods return `None`, the algorithm is repeated for methods named `unknown_open()`.

Note that the implementation of these methods may involve calls of the parent `OpenerDirector` instance's `.open()` and `.error()` methods.

3. Every handler with a method named like `protocol_response()` has that method called to post-process the response.

18.6.3 BaseHandler Objects

`BaseHandler` objects provide a couple of methods that are directly useful, and others that are meant to be used by derived classes. These are intended for direct use:

add_parent (*director*)

Add a director as parent.

close ()

Remove any parents.

The following members and methods should only be used by classes derived from `BaseHandler`. **Note:** The convention has been adopted that subclasses defining `protocol_request()` or `protocol_response()` methods are named `*Processor`; all others are named `*Handler`.

parent

A valid `OpenerDirector`, which can be used to open using a different protocol, or handle errors.

default_open (*req*)

This method is *not* defined in `BaseHandler`, but subclasses should define it if they want to catch all URLs.

This method, if implemented, will be called by the parent `OpenerDirector`. It should return a file-like object as described in the return value of the `open()` of `OpenerDirector`, or `None`. It should raise `URLError`, unless a truly exceptional thing happens (for example, `MemoryError` should not be mapped to `URLError`).

This method will be called before any protocol-specific open method.

protocol_open (*req*)

This method is *not* defined in `BaseHandler`, but subclasses should define it if they want to handle URLs with the given protocol.

This method, if defined, will be called by the parent `OpenerDirector`. Return values should be the same as for `default_open()`.

unknown_open (*req*)

This method is *not* defined in `BaseHandler`, but subclasses should define it if they want to catch all URLs with no specific registered handler to open it.

This method, if implemented, will be called by the parent `OpenerDirector`. Return values should be the same as for `default_open()`.

http_error_default (*req, fp, code, msg, hdrs*)

This method is *not* defined in `BaseHandler`, but subclasses should override it if they intend to provide a catch-all for otherwise unhandled HTTP errors. It will be called automatically by the `OpenerDirector` getting the error, and should not normally be called in other circumstances.

req will be a `Request` object, *fp* will be a file-like object with the HTTP error body, *code* will be the three-digit code of the error, *msg* will be the user-visible explanation of the code and *hdrs* will be a mapping object with the headers of the error.

Return values and exceptions raised should be the same as those of `urlopen()`.

http_error_nnn (*req, fp, code, msg, hdrs*)

nnn should be a three-digit HTTP error code. This method is also not defined in `BaseHandler`, but will be called, if it exists, on an instance of a subclass, when an HTTP error with code *nnn* occurs.

Subclasses should override this method to handle specific HTTP errors.

Arguments, return values and exceptions raised should be the same as for `http_error_default()`.

protocol_request (*req*)

This method is *not* defined in `BaseHandler`, but subclasses should define it if they want to pre-process requests of the given protocol.

This method, if defined, will be called by the parent `OpenerDirector`. *req* will be a `Request` object. The return value should be a `Request` object.

protocol_response (*req, response*)

This method is *not* defined in `BaseHandler`, but subclasses should define it if they want to post-process responses of the given protocol.

This method, if defined, will be called by the parent `OpenerDirector`. *req* will be a `Request` object. *response* will be an object implementing the same interface as the return value of `urlopen()`. The return value should implement the same interface as the return value of `urlopen()`.

18.6.4 HTTPRedirectHandler Objects

Note: Some HTTP redirections require action from this module's client code. If this is the case, `HTTPError` is raised. See RFC 2616 for details of the precise meanings of the various redirection codes.

redirect_request (*req, fp, code, msg, hdrs*)

Return a Request or None in response to a redirect. This is called by the default implementations of the `http_error_30*` () methods when a redirection is received from the server. If a redirection should take place, return a new Request to allow `http_error_30*` () to perform the redirect. Otherwise, raise HTTPError if no other handler should try to handle this URL, or return None if you can't but another handler might.

Note: The default implementation of this method does not strictly follow RFC 2616, which says that 301 and 302 responses to POST requests must not be automatically redirected without confirmation by the user. In reality, browsers do allow automatic redirection of these responses, changing the POST to a GET, and the default implementation reproduces this behavior.

http_error_301 (*req, fp, code, msg, hdrs*)

Redirect to the `Location:` URL. This method is called by the parent `OpenerDirector` when getting an HTTP 'moved permanently' response.

http_error_302 (*req, fp, code, msg, hdrs*)

The same as `http_error_301()`, but called for the 'found' response.

http_error_303 (*req, fp, code, msg, hdrs*)

The same as `http_error_301()`, but called for the 'see other' response.

http_error_307 (*req, fp, code, msg, hdrs*)

The same as `http_error_301()`, but called for the 'temporary redirect' response.

18.6.5 HTTPCookieProcessor Objects

New in version 2.4.

HTTPCookieProcessor instances have one attribute:

cookiejar

The `cookielib.CookieJar` in which cookies are stored.

18.6.6 ProxyHandler Objects

protocol_open (*request*)

The `ProxyHandler` will have a method `protocol_open()` for every *protocol* which has a proxy in the *proxies* dictionary given in the constructor. The method will modify requests to go through the proxy, by calling `request.set_proxy()`, and call the next handler in the chain to actually execute the protocol.

18.6.7 HTTPPasswordMgr Objects

These methods are available on `HTTPPasswordMgr` and `HTTPPasswordMgrWithDefaultRealm` objects.

add_password (*realm, uri, user, passwd*)

uri can be either a single URI, or a sequence of URIs. *realm*, *user* and *passwd* must be strings. This causes (*user*, *passwd*) to be used as authentication tokens when authentication for *realm* and a super-URI of any of the given URIs is given.

find_user_password (*realm, authuri*)

Get user/password for given realm and URI, if any. This method will return (None, None) if there is no matching user/password.

For `HTTPPasswordMgrWithDefaultRealm` objects, the realm None will be searched if the given *realm* has no matching user/password.

18.6.8 AbstractBasicAuthHandler Objects

http_error_auth_reged (*authreq, host, req, headers*)

Handle an authentication request by getting a user/password pair, and re-trying the request. *authreq* should be the name of the header where the information about the realm is included in the request, *host* specifies the URL and path to authenticate for, *req* should be the (failed) `Request` object, and *headers* should be the error headers.

host is either an authority (e.g. "python.org") or a URL containing an authority component (e.g. "http://python.org/"). In either case, the authority must not contain a userinfo component (so, "python.org" and "python.org:80" are fine, "joe:password@python.org" is not).

18.6.9 HTTPBasicAuthHandler Objects

http_error_401 (*req, fp, code, msg, hdrs*)

Retry the request with authentication information, if available.

18.6.10 ProxyBasicAuthHandler Objects

http_error_407 (*req, fp, code, msg, hdrs*)

Retry the request with authentication information, if available.

18.6.11 AbstractDigestAuthHandler Objects

http_error_auth_reged (*authreq, host, req, headers*)

authreq should be the name of the header where the information about the realm is included in the request, *host* should be the host to authenticate to, *req* should be the (failed) `Request` object, and *headers* should be the error headers.

18.6.12 HTTPDigestAuthHandler Objects

http_error_401 (*req, fp, code, msg, hdrs*)

Retry the request with authentication information, if available.

18.6.13 ProxyDigestAuthHandler Objects

http_error_407 (*req, fp, code, msg, hdrs*)

Retry the request with authentication information, if available.

18.6.14 HTTPHandler Objects

http_open (*req*)

Send an HTTP request, which can be either GET or POST, depending on *req.has_data()*.

18.6.15 HTTPSHandler Objects

https_open (*req*)

Send an HTTPS request, which can be either GET or POST, depending on *req.has_data()*.

18.6.16 FileHandler Objects

file_open (*req*)

Open the file locally, if there is no host name, or the host name is 'localhost'. Change the protocol to ftp otherwise, and retry opening it using parent.

18.6.17 FTPHandler Objects

ftp_open (*req*)

Open the FTP file indicated by *req*. The login is always done with empty username and password.

18.6.18 CacheFTPHandler Objects

CacheFTPHandler objects are FTPHandler objects with the following additional methods:

setTimeout (*t*)

Set timeout of connections to *t* seconds.

setMaxConns (*m*)

Set maximum number of cached connections to *m*.

18.6.19 GopherHandler Objects

gopher_open (*req*)

Open the gopher resource indicated by *req*.

18.6.20 UnknownHandler Objects

unknown_open ()

Raise a URLError exception.

18.6.21 HTTPErrorProcessor Objects

New in version 2.4.

unknown_open ()

Process HTTP error responses.

For 200 error codes, the response object is returned immediately.

For non-200 error codes, this simply passes the job on to the *protocol_error_code*() handler methods, via *OpenerDirector.error()*. Eventually, *urllib2.HTTPDefaultErrorHandler* will raise an *HTTPError* if no other handler handles the error.

18.6.22 Examples

This example gets the python.org main page and displays the first 100 bytes of it:

```
>>> import urllib2
>>> f = urllib2.urlopen('http://www.python.org/')
>>> print f.read(100)
<!DOCTYPE html PUBLIC "-//W3C//DTD HTML 4.01 Transitional//EN">
<?xml-stylesheet href="./css/ht2html
```

Here we are sending a data-stream to the stdin of a CGI and reading the data it returns to us. Note that this example will only work when the Python installation supports SSL.

```
>>> import urllib2
>>> req = urllib2.Request(url='https://localhost/cgi-bin/test.cgi',
...                        data='This data is passed to stdin of the CGI')
>>> f = urllib2.urlopen(req)
>>> print f.read()
Got Data: "This data is passed to stdin of the CGI"
```

The code for the sample CGI used in the above example is:

```
#!/usr/bin/env python
import sys
data = sys.stdin.read()
print 'Content-type: text-plain\n\nGot Data: "%s"' % data
```

Use of Basic HTTP Authentication:

```
import urllib2
# Create an OpenerDirector with support for Basic HTTP Authentication...
auth_handler = urllib2.HTTPBasicAuthHandler()
auth_handler.add_password(realm='PDQ Application',
                          uri='https://mahler:8092/site-updates.py',
                          user='klem',
                          passwd='kadidd!ehopper')
opener = urllib2.build_opener(auth_handler)
# ...and install it globally so it can be used with urlopen.
urllib2.install_opener(opener)
urllib2.urlopen('http://www.example.com/login.html')
```

`build_opener()` provides many handlers by default, including a `ProxyHandler`. By default, `ProxyHandler` uses the environment variables named `<scheme>_proxy`, where `<scheme>` is the URL scheme involved. For example, the `http` proxy environment variable is read to obtain the HTTP proxy's URL.

This example replaces the default `ProxyHandler` with one that uses programatically-supplied proxy URLs, and adds proxy authorization support with `ProxyBasicAuthHandler`.

```

proxy_handler = urllib2.ProxyHandler({'http': 'http://www.example.com:3128/'})
proxy_auth_handler = urllib2.HTTPBasicAuthHandler()
proxy_auth_handler.add_password('realm', 'host', 'username', 'password')

opener = build_opener(proxy_handler, proxy_auth_handler)
# This time, rather than install the OpenerDirector, we use it directly:
opener.open('http://www.example.com/login.html')

```

Adding HTTP headers:

Use the *headers* argument to the Request constructor, or:

```

import urllib2
req = urllib2.Request('http://www.example.com/')
req.add_header('Referer', 'http://www.python.org/')
r = urllib2.urlopen(req)

```

OpenerDirector automatically adds a User-Agent: header to every Request. To change this:

```

import urllib2
opener = urllib2.build_opener()
opener.addheaders = [('User-agent', 'Mozilla/5.0')]
opener.open('http://www.example.com/')

```

Also, remember that a few standard headers (Content-Length:, Content-Type: and Host:) are added when the Request is passed to `urlopen()` (or `OpenerDirector.open()`).

18.7 httplib — HTTP protocol client

This module defines classes which implement the client side of the HTTP and HTTPS protocols. It is normally not used directly — the module `urllib` uses it to handle URLs that use HTTP and HTTPS.

Note: HTTPS support is only available if the `socket` module was compiled with SSL support.

Note: The public interface for this module changed substantially in Python 2.0. The `HTTP` class is retained only for backward compatibility with 1.5.2. It should not be used in new code. Refer to the online docstrings for usage.

The module provides the following classes:

class HTTPConnection (*host* [, *port* [, *strict*]])

An `HTTPConnection` instance represents one transaction with an HTTP server. It should be instantiated passing it a host and optional port number. If no port number is passed, the port is extracted from the host string if it has the form *host:port*, else the default HTTP port (80) is used. When True, the optional parameter *strict* causes `BadStatusLine` to be raised if the status line can't be parsed as a valid HTTP/1.0 or 1.1 status line.

For example, the following calls all create instances that connect to the server at the same host and port:

```

>>> h1 = httplib.HTTPConnection('www.cwi.nl')
>>> h2 = httplib.HTTPConnection('www.cwi.nl:80')
>>> h3 = httplib.HTTPConnection('www.cwi.nl', 80)

```

New in version 2.0.

class HTTPSConnection (*host* [, *port* [, *key_file* [, *cert_file* [, *strict*]]]])

A subclass of `HTTPConnection` that uses SSL for communication with secure servers. Default port is 443.

key_file is the name of a PEM formatted file that contains your private key. *cert_file* is a PEM formatted certificate chain file.

Warning: This does not do any certificate verification!

New in version 2.0.

class HTTPResponse (*sock*[, *debuglevel=0*][, *strict=0*])

Class whose instances are returned upon successful connection. Not instantiated directly by user. New in version 2.0.

The following exceptions are raised as appropriate:

exception HTTPException

The base class of the other exceptions in this module. It is a subclass of `Exception`. New in version 2.0.

exception NotConnected

A subclass of `HTTPException`. New in version 2.0.

exception InvalidURL

A subclass of `HTTPException`, raised if a port is given and is either non-numeric or empty. New in version 2.3.

exception UnknownProtocol

A subclass of `HTTPException`. New in version 2.0.

exception UnknownTransferEncoding

A subclass of `HTTPException`. New in version 2.0.

exception UnimplementedFileMode

A subclass of `HTTPException`. New in version 2.0.

exception IncompleteRead

A subclass of `HTTPException`. New in version 2.0.

exception ImproperConnectionState

A subclass of `HTTPException`. New in version 2.0.

exception CannotSendRequest

A subclass of `ImproperConnectionState`. New in version 2.0.

exception CannotSendHeader

A subclass of `ImproperConnectionState`. New in version 2.0.

exception ResponseNotReady

A subclass of `ImproperConnectionState`. New in version 2.0.

exception BadStatusLine

A subclass of `HTTPException`. Raised if a server responds with a HTTP status code that we don't understand. New in version 2.0.

The constants defined in this module are:

HTTP_PORT

The default port for the HTTP protocol (always 80).

HTTPS_PORT

The default port for the HTTPS protocol (always 443).

and also the following constants for integer status codes:

Constant	Value	Definition
CONTINUE	100	HTTP/1.1, RFC 2616, Section 10.1.1
SWITCHING_PROTOCOLS	101	HTTP/1.1, RFC 2616, Section 10.1.2
PROCESSING	102	WEBDAV, RFC 2518, Section 10.1
OK	200	HTTP/1.1, RFC 2616, Section 10.2.1
CREATED	201	HTTP/1.1, RFC 2616, Section 10.2.2
ACCEPTED	202	HTTP/1.1, RFC 2616, Section 10.2.3
NON_AUTHORITATIVE_INFORMATION	203	HTTP/1.1, RFC 2616, Section 10.2.4
NO_CONTENT	204	HTTP/1.1, RFC 2616, Section 10.2.5
RESET_CONTENT	205	HTTP/1.1, RFC 2616, Section 10.2.6
PARTIAL_CONTENT	206	HTTP/1.1, RFC 2616, Section 10.2.7
MULTI_STATUS	207	WEBDAV RFC 2518, Section 10.2
IM_USED	226	Delta encoding in HTTP, RFC 3229, Section 10.4.1
MULTIPLE_CHOICES	300	HTTP/1.1, RFC 2616, Section 10.3.1
MOVED_PERMANENTLY	301	HTTP/1.1, RFC 2616, Section 10.3.2
FOUND	302	HTTP/1.1, RFC 2616, Section 10.3.3
SEE_OTHER	303	HTTP/1.1, RFC 2616, Section 10.3.4
NOT_MODIFIED	304	HTTP/1.1, RFC 2616, Section 10.3.5
USE_PROXY	305	HTTP/1.1, RFC 2616, Section 10.3.6
TEMPORARY_REDIRECT	307	HTTP/1.1, RFC 2616, Section 10.3.8
BAD_REQUEST	400	HTTP/1.1, RFC 2616, Section 10.4.1
UNAUTHORIZED	401	HTTP/1.1, RFC 2616, Section 10.4.2
PAYMENT_REQUIRED	402	HTTP/1.1, RFC 2616, Section 10.4.3
FORBIDDEN	403	HTTP/1.1, RFC 2616, Section 10.4.4
NOT_FOUND	404	HTTP/1.1, RFC 2616, Section 10.4.5
METHOD_NOT_ALLOWED	405	HTTP/1.1, RFC 2616, Section 10.4.6
NOT_ACCEPTABLE	406	HTTP/1.1, RFC 2616, Section 10.4.7
PROXY_AUTHENTICATION_REQUIRED	407	HTTP/1.1, RFC 2616, Section 10.4.8
REQUEST_TIMEOUT	408	HTTP/1.1, RFC 2616, Section 10.4.9
CONFLICT	409	HTTP/1.1, RFC 2616, Section 10.4.10
GONE	410	HTTP/1.1, RFC 2616, Section 10.4.11
LENGTH_REQUIRED	411	HTTP/1.1, RFC 2616, Section 10.4.12
PRECONDITION_FAILED	412	HTTP/1.1, RFC 2616, Section 10.4.13
REQUEST_ENTITY_TOO_LARGE	413	HTTP/1.1, RFC 2616, Section 10.4.14
REQUEST_URI_TOO_LONG	414	HTTP/1.1, RFC 2616, Section 10.4.15
UNSUPPORTED_MEDIA_TYPE	415	HTTP/1.1, RFC 2616, Section 10.4.16
REQUESTED_RANGE_NOT_SATISFIABLE	416	HTTP/1.1, RFC 2616, Section 10.4.17
EXPECTATION_FAILED	417	HTTP/1.1, RFC 2616, Section 10.4.18
UNPROCESSABLE_ENTITY	422	WEBDAV, RFC 2518, Section 10.3
LOCKED	423	WEBDAV RFC 2518, Section 10.4
FAILED_DEPENDENCY	424	WEBDAV, RFC 2518, Section 10.5
UPGRADE_REQUIRED	426	HTTP Upgrade to TLS, RFC 2817, Section 6
INTERNAL_SERVER_ERROR	500	HTTP/1.1, RFC 2616, Section 10.5.1
NOT_IMPLEMENTED	501	HTTP/1.1, RFC 2616, Section 10.5.2
BAD_GATEWAY	502	HTTP/1.1 RFC 2616, Section 10.5.3
SERVICE_UNAVAILABLE	503	HTTP/1.1, RFC 2616, Section 10.5.4
GATEWAY_TIMEOUT	504	HTTP/1.1 RFC 2616, Section 10.5.5
HTTP_VERSION_NOT_SUPPORTED	505	HTTP/1.1, RFC 2616, Section 10.5.6
INSUFFICIENT_STORAGE	507	WEBDAV, RFC 2518, Section 10.6
NOT_EXTENDED	510	An HTTP Extension Framework, RFC 2774, Section 7

responses

This dictionary maps the HTTP 1.1 status codes to the W3C names.

Example: `httplib.responses[httplib.NOT_FOUND]` is `'Not Found'`. New in version 2.5.

18.7.1 HTTPConnection Objects

`HTTPConnection` instances have the following methods:

request (*method*, *url* [, *body* [, *headers*]])

This will send a request to the server using the HTTP request method *method* and the selector *url*. If the *body* argument is present, it should be a string of data to send after the headers are finished. The header `Content-Length` is automatically set to the correct value. The *headers* argument should be a mapping of extra HTTP headers to send with the request.

getresponse ()

Should be called after a request is sent to get the response from the server. Returns an `HTTPResponse` instance.

Note: Note that you must have read the whole response before you can send a new request to the server.

set_debuglevel (*level*)

Set the debugging level (the amount of debugging output printed). The default debug level is 0, meaning no debugging output is printed.

connect ()

Connect to the server specified when the object was created.

close ()

Close the connection to the server.

As an alternative to using the `request ()` method described above, you can also send your request step by step, by using the four functions below.

putrequest (*request*, *selector* [, *skip_host* [, *skip_accept_encoding*]])

This should be the first call after the connection to the server has been made. It sends a line to the server consisting of the *request* string, the *selector* string, and the HTTP version (`HTTP/1.1`). To disable automatic sending of `Host :` or `Accept-Encoding :` headers (for example to accept additional content encodings), specify *skip_host* or *skip_accept_encoding* with non-False values. Changed in version 2.4: *skip_accept_encoding* argument added.

putheader (*header*, *argument* [, ...])

Send an RFC 822-style header to the server. It sends a line to the server consisting of the header, a colon and a space, and the first argument. If more arguments are given, continuation lines are sent, each consisting of a tab and an argument.

endheaders ()

Send a blank line to the server, signalling the end of the headers.

send (*data*)

Send data to the server. This should be used directly only after the `endheaders ()` method has been called and before `getresponse ()` is called.

18.7.2 HTTPResponse Objects

`HTTPResponse` instances have the following methods and attributes:

read ([*amt*])

Reads and returns the response body, or up to the next *amt* bytes.

getheader (*name* [, *default*])

Get the contents of the header *name*, or *default* if there is no matching header.

getheaders ()

Return a list of (header, value) tuples. New in version 2.4.

msg

A `mimetools.Message` instance containing the response headers.

version

HTTP protocol version used by server. 10 for HTTP/1.0, 11 for HTTP/1.1.

status

Status code returned by server.

reason

Reason phrase returned by server.

18.7.3 Examples

Here is an example session that uses the ‘GET’ method:

```
>>> import httplib
>>> conn = httplib.HTTPConnection("www.python.org")
>>> conn.request("GET", "/index.html")
>>> r1 = conn.getresponse()
>>> print r1.status, r1.reason
200 OK
>>> data1 = r1.read()
>>> conn.request("GET", "/parrot.spam")
>>> r2 = conn.getresponse()
>>> print r2.status, r2.reason
404 Not Found
>>> data2 = r2.read()
>>> conn.close()
```

Here is an example session that shows how to ‘POST’ requests:

```
>>> import httplib, urllib
>>> params = urllib.urlencode({'spam': 1, 'eggs': 2, 'bacon': 0})
>>> headers = {"Content-type": "application/x-www-form-urlencoded",
...           "Accept": "text/plain"}
>>> conn = httplib.HTTPConnection("musi-cal.mojam.com:80")
>>> conn.request("POST", "/cgi-bin/query", params, headers)
>>> response = conn.getresponse()
>>> print response.status, response.reason
200 OK
>>> data = response.read()
>>> conn.close()
```

18.8 ftplib — FTP protocol client

This module defines the class `FTP` and a few related items. The `FTP` class implements the client side of the FTP protocol. You can use this to write Python programs that perform a variety of automated FTP jobs, such as mirroring other ftp servers. It is also used by the module `urllib` to handle URLs that use FTP. For more information on FTP (File Transfer Protocol), see Internet RFC 959.

Here’s a sample session using the `ftplib` module:


```

>>> from ftplib import FTP
>>> ftp = FTP('ftp.cwi.nl') # connect to host, default port
>>> ftp.login()             # user anonymous, passwd anonymous@
>>> ftp.retrlines('LIST')   # list directory contents
total 24418
drwxrwsr-x   5 ftp-usr  pdmaint      1536 Mar 20 09:48 .
dr-xr-srwt 105 ftp-usr  pdmaint      1536 Mar 21 14:32 ..
-rw-r--r--   1 ftp-usr  pdmaint     5305 Mar 20 09:48 INDEX
.
.
.
>>> ftp.retrbinary('RETR README', open('README', 'wb').write)
'226 Transfer complete.'
>>> ftp.quit()

```

The module defines the following items:

class `FTP` (`[host[, user[, passwd[, acct]]]]`)

Return a new instance of the `FTP` class. When *host* is given, the method call `connect(host)` is made. When *user* is given, additionally the method call `login(user, passwd, acct)` is made (where *passwd* and *acct* default to the empty string when not given).

`all_errors`

The set of all exceptions (as a tuple) that methods of `FTP` instances may raise as a result of problems with the FTP connection (as opposed to programming errors made by the caller). This set includes the four exceptions listed below as well as `socket.error` and `IOError`.

`exception error_reply`

Exception raised when an unexpected reply is received from the server.

`exception error_temp`

Exception raised when an error code in the range 400–499 is received.

`exception error_perm`

Exception raised when an error code in the range 500–599 is received.

`exception error_proto`

Exception raised when a reply is received from the server that does not begin with a digit in the range 1–5.

See Also:

[Module `netrc`](#) (section 9.4):

Parser for the `.netrc` file format. The file `.netrc` is typically used by FTP clients to load user authentication information before prompting the user.

The file `Tools/scripts/ftpmirror.py` in the Python source distribution is a script that can mirror FTP sites, or portions thereof, using the `ftplib` module. It can be used as an extended example that applies this module.

18.8.1 FTP Objects

Several methods are available in two flavors: one for handling text files and another for binary files. These are named for the command which is used followed by `'lines'` for the text version or `'binary'` for the binary version.

`FTP` instances have the following methods:

`set_debuglevel` (*level*)

Set the instance's debugging level. This controls the amount of debugging output printed. The default, 0, produces no debugging output. A value of 1 produces a moderate amount of debugging output, generally a

single line per request. A value of 2 or higher produces the maximum amount of debugging output, logging each line sent and received on the control connection.

connect (*host* [, *port*])

Connect to the given host and port. The default port number is 21, as specified by the FTP protocol specification. It is rarely needed to specify a different port number. This function should be called only once for each instance; it should not be called at all if a host was given when the instance was created. All other methods can only be used after a connection has been made.

getwelcome ()

Return the welcome message sent by the server in reply to the initial connection. (This message sometimes contains disclaimers or help information that may be relevant to the user.)

login ([*user* [, *passwd* [, *acct*]]])

Log in as the given *user*. The *passwd* and *acct* parameters are optional and default to the empty string. If no *user* is specified, it defaults to 'anonymous'. If *user* is 'anonymous', the default *passwd* is 'anonymous@'. This function should be called only once for each instance, after a connection has been established; it should not be called at all if a host and user were given when the instance was created. Most FTP commands are only allowed after the client has logged in.

abort ()

Abort a file transfer that is in progress. Using this does not always work, but it's worth a try.

sendcmd (*command*)

Send a simple command string to the server and return the response string.

voidcmd (*command*)

Send a simple command string to the server and handle the response. Return nothing if a response code in the range 200–299 is received. Raise an exception otherwise.

retrbinary (*command*, *callback* [, *maxblocksize* [, *rest*]])

Retrieve a file in binary transfer mode. *command* should be an appropriate 'RETR' command: 'RETR *filename*'. The *callback* function is called for each block of data received, with a single string argument giving the data block. The optional *maxblocksize* argument specifies the maximum chunk size to read on the low-level socket object created to do the actual transfer (which will also be the largest size of the data blocks passed to *callback*). A reasonable default is chosen. *rest* means the same thing as in the `transfercmd()` method.

retrlines (*command* [, *callback*])

Retrieve a file or directory listing in ASCII transfer mode. *command* should be an appropriate 'RETR' command (see `retrbinary()`) or a 'LIST' command (usually just the string 'LIST'). The *callback* function is called for each line, with the trailing CRLF stripped. The default *callback* prints the line to `sys.stdout`.

set_pasv (*boolean*)

Enable "passive" mode if *boolean* is true, other disable passive mode. (In Python 2.0 and before, passive mode was off by default; in Python 2.1 and later, it is on by default.)

storbinary (*command*, *file* [, *blocksize*])

Store a file in binary transfer mode. *command* should be an appropriate 'STOR' command: "STOR *filename*". *file* is an open file object which is read until EOF using its `read()` method in blocks of size *blocksize* to provide the data to be stored. The *blocksize* argument defaults to 8192. Changed in version 2.1: default for *blocksize* added.

storlines (*command*, *file*)

Store a file in ASCII transfer mode. *command* should be an appropriate 'STOR' command (see `storbinary()`). Lines are read until EOF from the open file object *file* using its `readline()` method to provide the data to be stored.

transfercmd (*cmd* [, *rest*])

Initiate a transfer over the data connection. If the transfer is active, send a 'EPRT' or 'PORT' command and the transfer command specified by *cmd*, and accept the connection. If the server is passive, send a 'EPSV' or 'PASV'

command, connect to it, and start the transfer command. Either way, return the socket for the connection.

If optional *rest* is given, a 'REST' command is sent to the server, passing *rest* as an argument. *rest* is usually a byte offset into the requested file, telling the server to restart sending the file's bytes at the requested offset, skipping over the initial bytes. Note however that RFC 959 requires only that *rest* be a string containing characters in the printable range from ASCII code 33 to ASCII code 126. The `transfercmd()` method, therefore, converts *rest* to a string, but no check is performed on the string's contents. If the server does not recognize the 'REST' command, an `error_reply` exception will be raised. If this happens, simply call `transfercmd()` without a *rest* argument.

`ntransfercmd` (*cmd* [, *rest*])

Like `transfercmd()`, but returns a tuple of the data connection and the expected size of the data. If the expected size could not be computed, `None` will be returned as the expected size. *cmd* and *rest* means the same thing as in `transfercmd()`.

`nlst` (*argument* [, ...])

Return a list of files as returned by the 'NLST' command. The optional *argument* is a directory to list (default is the current server directory). Multiple arguments can be used to pass non-standard options to the 'NLST' command.

`dir` (*argument* [, ...])

Produce a directory listing as returned by the 'LIST' command, printing it to standard output. The optional *argument* is a directory to list (default is the current server directory). Multiple arguments can be used to pass non-standard options to the 'LIST' command. If the last argument is a function, it is used as a *callback* function as for `retrlines()`; the default prints to `sys.stdout`. This method returns `None`.

`rename` (*fromname*, *toname*)

Rename file *fromname* on the server to *toname*.

`delete` (*filename*)

Remove the file named *filename* from the server. If successful, returns the text of the response, otherwise raises `error_perm` on permission errors or `error_reply` on other errors.

`cwd` (*pathname*)

Set the current directory on the server.

`mkd` (*pathname*)

Create a new directory on the server.

`pwd` ()

Return the pathname of the current directory on the server.

`rmd` (*dirname*)

Remove the directory named *dirname* on the server.

`size` (*filename*)

Request the size of the file named *filename* on the server. On success, the size of the file is returned as an integer, otherwise `None` is returned. Note that the 'SIZE' command is not standardized, but is supported by many common server implementations.

`quit` ()

Send a 'QUIT' command to the server and close the connection. This is the "polite" way to close a connection, but it may raise an exception if the server responds with an error to the 'QUIT' command. This implies a call to the `close()` method which renders the FTP instance useless for subsequent calls (see below).

`close` ()

Close the connection unilaterally. This should not be applied to an already closed connection such as after a successful call to `quit()`. After this call the FTP instance should not be used any more (after a call to `close()` or `quit()` you cannot reopen the connection by issuing another `login()` method).

18.9 gopherlib — Gopher protocol client

Deprecated since release 2.5. The `gopher` protocol is not in active use anymore.

This module provides a minimal implementation of client side of the Gopher protocol. It is used by the module `urllib` to handle URLs that use the Gopher protocol.

The module defines the following functions:

send_selector (*selector*, *host* [, *port*])

Send a *selector* string to the gopher server at *host* and *port* (default 70). Returns an open file object from which the returned document can be read.

send_query (*selector*, *query*, *host* [, *port*])

Send a *selector* string and a *query* string to a gopher server at *host* and *port* (default 70). Returns an open file object from which the returned document can be read.

Note that the data returned by the Gopher server can be of any type, depending on the first character of the selector string. If the data is text (first character of the selector is '0'), lines are terminated by CRLF, and the data is terminated by a line consisting of a single '.', and a leading '.' should be stripped from lines that begin with '..'. Directory listings (first character of the selector is '1') are transferred using the same protocol.

18.10 poplib — POP3 protocol client

This module defines a class, `POP3`, which encapsulates a connection to a POP3 server and implements the protocol as defined in RFC 1725. The `POP3` class supports both the minimal and optional command sets. Additionally, this module provides a class `POP3_SSL`, which provides support for connecting to POP3 servers that use SSL as an underlying protocol layer.

Note that POP3, though widely supported, is obsolescent. The implementation quality of POP3 servers varies widely, and too many are quite poor. If your mailserver supports IMAP, you would be better off using the `imaplib`. IMAP4 class, as IMAP servers tend to be better implemented.

A single class is provided by the `poplib` module:

class POP3 (*host* [, *port*])

This class implements the actual POP3 protocol. The connection is created when the instance is initialized. If *port* is omitted, the standard POP3 port (110) is used.

class POP3_SSL (*host* [, *port* [, *keyfile* [, *certfile*]]])

This is a subclass of `POP3` that connects to the server over an SSL encrypted socket. If *port* is not specified, 995, the standard POP3-over-SSL port is used. *keyfile* and *certfile* are also optional - they can contain a PEM formatted private key and certificate chain file for the SSL connection.

New in version 2.4.

One exception is defined as an attribute of the `poplib` module:

exception error_proto

Exception raised on any errors. The reason for the exception is passed to the constructor as a string.

See Also:

Module `imaplib` (section 18.11):

The standard Python IMAP module.

Frequently Asked Questions About Fetchmail

(<http://www.catb.org/~esr/fetchmail/fetchmail-FAQ.html>)

The FAQ for the **fetchmail** POP/IMAP client collects information on POP3 server variations and RFC noncompliance that may be useful if you need to write an application based on the POP protocol.

18.10.1 POP3 Objects

All POP3 commands are represented by methods of the same name, in lower-case; most return the response text sent by the server.

An `POP3` instance has the following methods:

set_debuglevel (*level*)

Set the instance's debugging level. This controls the amount of debugging output printed. The default, 0, produces no debugging output. A value of 1 produces a moderate amount of debugging output, generally a single line per request. A value of 2 or higher produces the maximum amount of debugging output, logging each line sent and received on the control connection.

getwelcome ()

Returns the greeting string sent by the POP3 server.

user (*username*)

Send user command, response should indicate that a password is required.

pass_ (*password*)

Send password, response includes message count and mailbox size. Note: the mailbox on the server is locked until `quit` () is called.

apop (*user, secret*)

Use the more secure APOP authentication to log into the POP3 server.

rpop (*user*)

Use RPOP authentication (similar to UNIX r-commands) to log into POP3 server.

stat ()

Get mailbox status. The result is a tuple of 2 integers: (*message count*, *mailbox size*).

list ([*which*])

Request message list, result is in the form (*response*, [*'msg_num octets'*, ...], *octets*). If *which* is set, it is the message to list.

retr (*which*)

Retrieve whole message number *which*, and set its seen flag. Result is in form (*response*, [*'line'*, ...], *octets*).

dele (*which*)

Flag message number *which* for deletion. On most servers deletions are not actually performed until QUIT (the major exception is Eudora QPOP, which deliberately violates the RFCs by doing pending deletes on any disconnect).

rset ()

Remove any deletion marks for the mailbox.

noop ()

Do nothing. Might be used as a keep-alive.

quit ()

Signoff: commit changes, unlock mailbox, drop connection.

top (*which, howmuch*)

Retrieves the message header plus *howmuch* lines of the message after the header of message number *which*. Result is in form (*response*, [*'line'*, ...], *octets*).

The POP3 TOP command this method uses, unlike the RETR command, doesn't set the message's seen flag; unfortunately, TOP is poorly specified in the RFCs and is frequently broken in off-brand servers. Test this method by hand against the POP3 servers you will use before trusting it.

uidl ([*which*])

Return message digest (unique id) list. If *which* is specified, result contains the unique id for that message in the form '*response mesgnum uid*', otherwise result is list (*response*, [*mesgnum uid*, ...], *octets*).

Instances of POP3_SSL have no additional methods. The interface of this subclass is identical to its parent.

18.10.2 POP3 Example

Here is a minimal example (without error checking) that opens a mailbox and retrieves and prints all messages:

```
import getpass, poplib

M = poplib.POP3('localhost')
M.user(getpass.getuser())
M.pass_(getpass.getpass())
numMessages = len(M.list()[1])
for i in range(numMessages):
    for j in M.retr(i+1)[1]:
        print j
```

At the end of the module, there is a test section that contains a more extensive example of usage.

18.11 imaplib — IMAP4 protocol client

This module defines three classes, IMAP4, IMAP4_SSL and IMAP4_stream, which encapsulate a connection to an IMAP4 server and implement a large subset of the IMAP4rev1 client protocol as defined in RFC 2060. It is backward compatible with IMAP4 (RFC 1730) servers, but note that the 'STATUS' command is not supported in IMAP4.

Three classes are provided by the `imaplib` module, IMAP4 is the base class:

class `IMAP4` (`[host[, port]]`)

This class implements the actual IMAP4 protocol. The connection is created and protocol version (IMAP4 or IMAP4rev1) is determined when the instance is initialized. If *host* is not specified, '' (the local host) is used. If *port* is omitted, the standard IMAP4 port (143) is used.

Three exceptions are defined as attributes of the IMAP4 class:

exception `IMAP4.error`

Exception raised on any errors. The reason for the exception is passed to the constructor as a string.

exception `IMAP4.abort`

IMAP4 server errors cause this exception to be raised. This is a sub-class of `IMAP4.error`. Note that closing the instance and instantiating a new one will usually allow recovery from this exception.

exception `IMAP4.readonly`

This exception is raised when a writable mailbox has its status changed by the server. This is a sub-class of `IMAP4.error`. Some other client now has write permission, and the mailbox will need to be re-opened to re-obtain write permission.

There's also a subclass for secure connections:

class `IMAP4_SSL` (`[host[, port[, keyfile[, certfile]]]]`)

This is a subclass derived from `IMAP4` that connects over an SSL encrypted socket (to use this class you need a socket module that was compiled with SSL support). If *host* is not specified, '' (the local host) is used. If *port* is omitted, the standard IMAP4-over-SSL port (993) is used. *keyfile* and *certfile* are also optional - they can contain a PEM formatted private key and certificate chain file for the SSL connection.

The second subclass allows for connections created by a child process:

class IMAP4_stream (*command*)

This is a subclass derived from IMAP4 that connects to the `stdin/stdout` file descriptors created by passing *command* to `os.popen2()`. New in version 2.3.

The following utility functions are defined:

Internaldate2tuple (*datestr*)

Converts an IMAP4 INTERNALDATE string to Coordinated Universal Time. Returns a `time` module tuple.

Int2AP (*num*)

Converts an integer into a string representation using characters from the set [A .. P].

ParseFlags (*flagstr*)

Converts an IMAP4 'FLAGS' response to a tuple of individual flags.

Time2Internaldate (*date_time*)

Converts a `time` module tuple to an IMAP4 'INTERNALDATE' representation. Returns a string in the form: "DD-Mmm-YYYY HH:MM:SS +HHMM" (including double-quotes).

Note that IMAP4 message numbers change as the mailbox changes; in particular, after an 'EXPUNGE' command performs deletions the remaining messages are renumbered. So it is highly advisable to use UIDs instead, with the UID command.

At the end of the module, there is a test section that contains a more extensive example of usage.

See Also:

Documents describing the protocol, and sources and binaries for servers implementing it, can all be found at the University of Washington's *IMAP Information Center* (<http://www.cac.washington.edu/imap/>).

18.11.1 IMAP4 Objects

All IMAP4rev1 commands are represented by methods of the same name, either upper-case or lower-case.

All arguments to commands are converted to strings, except for 'AUTHENTICATE', and the last argument to 'APPEND' which is passed as an IMAP4 literal. If necessary (the string contains IMAP4 protocol-sensitive characters and isn't enclosed with either parentheses or double quotes) each string is quoted. However, the *password* argument to the 'LOGIN' command is always quoted. If you want to avoid having an argument string quoted (eg: the *flags* argument to 'STORE') then enclose the string in parentheses (eg: `r'(\Deleted)'`).

Each command returns a tuple: (*type*, [*data*, ...]) where *type* is usually 'OK' or 'NO', and *data* is either the text from the command response, or mandated results from the command. Each *data* is either a string, or a tuple. If a tuple, then the first part is the header of the response, and the second part contains the data (ie: 'literal' value).

The *message_set* options to commands below is a string specifying one or more messages to be acted upon. It may be a simple message number ('1'), a range of message numbers ('2:4'), or a group of non-contiguous ranges separated by commas ('1:3,6:9'). A range can contain an asterisk to indicate an infinite upper bound ('3:*').

An IMAP4 instance has the following methods:

append (*mailbox, flags, date_time, message*)

Append *message* to named mailbox.

authenticate (*mechanism, authobject*)

Authenticate command — requires response processing.

mechanism specifies which authentication mechanism is to be used - it should appear in the instance variable *capabilities* in the form AUTH=mechanism.

authobject must be a callable object:

```
data = authobject(response)
```

It will be called to process server continuation responses. It should return `data` that will be encoded and sent to server. It should return `None` if the client abort response `*` should be sent instead.

check()

Checkpoint mailbox on server.

close()

Close currently selected mailbox. Deleted messages are removed from writable mailbox. This is the recommended command before `LOGOUT`.

copy(*message_set*, *new_mailbox*)

Copy *message_set* messages onto end of *new_mailbox*.

create(*mailbox*)

Create new mailbox named *mailbox*.

delete(*mailbox*)

Delete old mailbox named *mailbox*.

deleteacl(*mailbox*, *who*)

Delete the ACLs (remove any rights) set for *who* on mailbox. New in version 2.4.

expunge()

Permanently remove deleted items from selected mailbox. Generates an `EXPUNGE` response for each deleted message. Returned data contains a list of `EXPUNGE` message numbers in order received.

fetch(*message_set*, *message_parts*)

Fetch (parts of) messages. *message_parts* should be a string of message part names enclosed within parentheses, eg: `" (UID BODY[TEXT]) "`. Returned data are tuples of message part envelope and data.

getacl(*mailbox*)

Get the `ACL`'s for *mailbox*. The method is non-standard, but is supported by the `Cyrus` server.

getannotation(*mailbox*, *entry*, *attribute*)

Retrieve the specified `ANNOTATION`'s for *mailbox*. The method is non-standard, but is supported by the `Cyrus` server. New in version 2.5.

getquota(*root*)

Get the `quota` *root*'s resource usage and limits. This method is part of the IMAP4 QUOTA extension defined in rfc2087. New in version 2.3.

getquotaroot(*mailbox*)

Get the list of `quota` `roots` for the named *mailbox*. This method is part of the IMAP4 QUOTA extension defined in rfc2087. New in version 2.3.

list(*[directory[, pattern]]*)

List mailbox names in *directory* matching *pattern*. *directory* defaults to the top-level mail folder, and *pattern* defaults to match anything. Returned data contains a list of `LIST` responses.

login(*user*, *password*)

Identify the client using a plaintext password. The *password* will be quoted.

login_cram_md5(*user*, *password*)

Force use of `CRAM-MD5` authentication when identifying the client to protect the password. Will only work if the server `CAPABILITY` response includes the phrase `AUTH=CRAM-MD5`. New in version 2.3.

logout()

Shutdown connection to server. Returns server `BYE` response.

lsub(*[directory[, pattern]]*)

List subscribed mailbox names in directory matching pattern. *directory* defaults to the top level directory and *pattern* defaults to match any mailbox. Returned data are tuples of message part envelope and data.

myrights (*mailbox*)

Show my ACLs for a mailbox (i.e. the rights that I have on mailbox). New in version 2.4.

namespace ()

Returns IMAP namespaces as defined in RFC2342. New in version 2.3.

noop ()

Send 'NOOP' to server.

open (*host*, *port*)

Opens socket to *port* at *host*. The connection objects established by this method will be used in the `read`, `readline`, `send`, and `shutdown` methods. You may override this method.

partial (*message_num*, *message_part*, *start*, *length*)

Fetch truncated part of a message. Returned data is a tuple of message part envelope and data.

proxyauth (*user*)

Assume authentication as *user*. Allows an authorised administrator to proxy into any user's mailbox. New in version 2.3.

read (*size*)

Reads *size* bytes from the remote server. You may override this method.

readline ()

Reads one line from the remote server. You may override this method.

recent ()

Prompt server for an update. Returned data is `None` if no new messages, else value of 'RECENT' response.

rename (*oldmailbox*, *newmailbox*)

Rename mailbox named *oldmailbox* to *newmailbox*.

response (*code*)

Return data for response *code* if received, or `None`. Returns the given code, instead of the usual type.

search (*charset*, *criterion*[, ...])

Search mailbox for matching messages. *charset* may be `None`, in which case no 'CHARSET' will be specified in the request to the server. The IMAP protocol requires that at least one criterion be specified; an exception will be raised when the server returns an error.

Example:

```
# M is a connected IMAP4 instance...
typ, msgnums = M.search(None, 'FROM', '"LDJ"')

# or:
typ, msgnums = M.search(None, '(FROM "LDJ")')
```

select ([*mailbox*[, *readonly*]])

Select a mailbox. Returned data is the count of messages in *mailbox* ('EXISTS' response). The default *mailbox* is 'INBOX'. If the *readonly* flag is set, modifications to the mailbox are not allowed.

send (*data*)

Sends *data* to the remote server. You may override this method.

setacl (*mailbox*, *who*, *what*)

Set an 'ACL' for *mailbox*. The method is non-standard, but is supported by the 'Cyrus' server.

setannotation (*mailbox*, *entry*, *attribute*[, ...])

Set 'ANNOTATION's for *mailbox*. The method is non-standard, but is supported by the 'Cyrus' server. New in version 2.5.

setquota (*root, limits*)

Set the 'quota' *root*'s resource *limits*. This method is part of the IMAP4 QUOTA extension defined in rfc2087. New in version 2.3.

shutdown ()

Close connection established in *open*. You may override this method.

socket ()

Returns socket instance used to connect to server.

sort (*sort_criteria, charset, search_criterion*[, ...])

The *sort* command is a variant of *search* with sorting semantics for the results. Returned data contains a space separated list of matching message numbers.

Sort has two arguments before the *search_criterion* argument(s); a parenthesized list of *sort_criteria*, and the searching *charset*. Note that unlike *search*, the searching *charset* argument is mandatory. There is also a *uid sort* command which corresponds to *sort* the way that *uid search* corresponds to *search*. The *sort* command first searches the mailbox for messages that match the given searching criteria using the *charset* argument for the interpretation of strings in the searching criteria. It then returns the numbers of matching messages.

This is an 'IMAP4rev1' extension command.

status (*mailbox, names*)

Request named status conditions for *mailbox*.

store (*message_set, command, flag_list*)

Alters flag dispositions for messages in mailbox. *command* is specified by section 6.4.6 of RFC 2060 as being one of "FLAGS", "+FLAGS", or "-FLAGS", optionally with a suffix of ".SILENT".

For example, to set the delete flag on all messages:

```
typ, data = M.search(None, 'ALL')
for num in data[0].split():
    M.store(num, '+FLAGS', '\\Deleted')
M.expunge()
```

subscribe (*mailbox*)

Subscribe to new mailbox.

thread (*threading_algorithm, charset, search_criterion*[, ...])

The *thread* command is a variant of *search* with threading semantics for the results. Returned data contains a space separated list of thread members.

Thread members consist of zero or more messages numbers, delimited by spaces, indicating successive parent and child.

Thread has two arguments before the *search_criterion* argument(s); a *threading_algorithm*, and the searching *charset*. Note that unlike *search*, the searching *charset* argument is mandatory. There is also a *uid thread* command which corresponds to *thread* the way that *uid search* corresponds to *search*. The *thread* command first searches the mailbox for messages that match the given searching criteria using the *charset* argument for the interpretation of strings in the searching criteria. It then returns the matching messages threaded according to the specified threading algorithm.

This is an 'IMAP4rev1' extension command. New in version 2.4.

uid (*command, arg*[, ...])

Execute command args with messages identified by UID, rather than message number. Returns response appropriate to command. At least one argument must be supplied; if none are provided, the server will return an error and an exception will be raised.

unsubscribe (*mailbox*)

Unsubscribe from old mailbox.

xatom (*name* [, *arg* [, ...]])

Allow simple extension commands notified by server in ‘CAPABILITY’ response.

Instances of `IMAP4_SSL` have just one additional method:

ssl ()

Returns `SSLObj` instance used for the secure connection with the server.

The following attributes are defined on instances of `IMAP4`:

PROTOCOL_VERSION

The most recent supported protocol in the ‘CAPABILITY’ response from the server.

debug

Integer value to control debugging output. The initialize value is taken from the module variable `Debug`. Values greater than three trace each command.

18.11.2 IMAP4 Example

Here is a minimal example (without error checking) that opens a mailbox and retrieves and prints all messages:

```
import getpass, imaplib

M = imaplib.IMAP4()
M.login(getpass.getuser(), getpass.getpass())
M.select()
typ, data = M.search(None, 'ALL')
for num in data[0].split():
    typ, data = M.fetch(num, '(RFC822)')
    print 'Message %s\n%s\n' % (num, data[0][1])
M.close()
M.logout()
```

18.12 nntplib — NNTP protocol client

This module defines the class `NNTP` which implements the client side of the NNTP protocol. It can be used to implement a news reader or poster, or automated news processors. For more information on NNTP (Network News Transfer Protocol), see Internet RFC 977.

Here are two small examples of how it can be used. To list some statistics about a newsgroup and print the subjects of the last 10 articles:

```

>>> s = NNTP('news.cwi.nl')
>>> resp, count, first, last, name = s.group('comp.lang.python')
>>> print 'Group', name, 'has', count, 'articles, range', first, 'to', last
Group comp.lang.python has 59 articles, range 3742 to 3803
>>> resp, subs = s.xhdr('subject', first + '-' + last)
>>> for id, sub in subs[-10:]: print id, sub
...
3792 Re: Removing elements from a list while iterating...
3793 Re: Who likes Info files?
3794 Emacs and doc strings
3795 a few questions about the Mac implementation
3796 Re: executable python scripts
3797 Re: executable python scripts
3798 Re: a few questions about the Mac implementation
3799 Re: PROPOSAL: A Generic Python Object Interface for Python C Modules
3802 Re: executable python scripts
3803 Re: \POSIX{} wait and SIGCHLD
>>> s.quit()
'205 news.cwi.nl closing connection. Goodbye.'

```

To post an article from a file (this assumes that the article has valid headers):

```

>>> s = NNTP('news.cwi.nl')
>>> f = open('/tmp/article')
>>> s.post(f)
'240 Article posted successfully.'
>>> s.quit()
'205 news.cwi.nl closing connection. Goodbye.'

```

The module itself defines the following items:

class NNTP (*host* [, *port* [, *user* [, *password* [, *readermode*] [, *usenetcrc*]]]])

Return a new instance of the NNTP class, representing a connection to the NNTP server running on host *host*, listening at port *port*. The default *port* is 119. If the optional *user* and *password* are provided, or if suitable credentials are present in `/.netrc` and the optional flag *usenetcrc* is true (the default), the `'AUTHINFO USER'` and `'AUTHINFO PASS'` commands are used to identify and authenticate the user to the server. If the optional flag *readermode* is true, then a `'mode reader'` command is sent before authentication is performed. Reader mode is sometimes necessary if you are connecting to an NNTP server on the local machine and intend to call reader-specific commands, such as `'group'`. If you get unexpected `NNTPPermanentErrors`, you might need to set *readermode*. *readermode* defaults to None. *usenetcrc* defaults to True.

Changed in version 2.4: *usenetcrc* argument added.

exception NNTPError

Derived from the standard exception `Exception`, this is the base class for all exceptions raised by the `nnplib` module.

exception NNTPReplyError

Exception raised when an unexpected reply is received from the server. For backwards compatibility, the exception `error_reply` is equivalent to this class.

exception NNTPTemporaryError

Exception raised when an error code in the range 400–499 is received. For backwards compatibility, the exception `error_temp` is equivalent to this class.

exception NNTPPermanentError

Exception raised when an error code in the range 500–599 is received. For backwards compatibility, the exception `error_perm` is equivalent to this class.

exception NNTPProtocolError

Exception raised when a reply is received from the server that does not begin with a digit in the range 1–5. For backwards compatibility, the exception `error_proto` is equivalent to this class.

exception NNTPDataError

Exception raised when there is some error in the response data. For backwards compatibility, the exception `error_data` is equivalent to this class.

18.12.1 NNTP Objects

NNTP instances have the following methods. The *response* that is returned as the first item in the return tuple of almost all methods is the server's response: a string beginning with a three-digit code. If the server's response indicates an error, the method raises one of the above exceptions.

getwelcome()

Return the welcome message sent by the server in reply to the initial connection. (This message sometimes contains disclaimers or help information that may be relevant to the user.)

set_debuglevel(*level*)

Set the instance's debugging level. This controls the amount of debugging output printed. The default, 0, produces no debugging output. A value of 1 produces a moderate amount of debugging output, generally a single line per request or response. A value of 2 or higher produces the maximum amount of debugging output, logging each line sent and received on the connection (including message text).

newgroups(*date*, *time*, [*file*])

Send a 'NEWGROUPS' command. The *date* argument should be a string of the form 'yymmdd' indicating the date, and *time* should be a string of the form 'hhmmss' indicating the time. Return a pair (*response*, *groups*) where *groups* is a list of group names that are new since the given date and time. If the *file* parameter is supplied, then the output of the 'NEWGROUPS' command is stored in a file. If *file* is a string, then the method will open a file object with that name, write to it then close it. If *file* is a file object, then it will start calling `write()` on it to store the lines of the command output. If *file* is supplied, then the returned *list* is an empty list.

newnews(*group*, *date*, *time*, [*file*])

Send a 'NEWNEWS' command. Here, *group* is a group name or '*', and *date* and *time* have the same meaning as for `newgroups()`. Return a pair (*response*, *articles*) where *articles* is a list of message ids. If the *file* parameter is supplied, then the output of the 'NEWNEWS' command is stored in a file. If *file* is a string, then the method will open a file object with that name, write to it then close it. If *file* is a file object, then it will start calling `write()` on it to store the lines of the command output. If *file* is supplied, then the returned *list* is an empty list.

list([*file*])

Send a 'LIST' command. Return a pair (*response*, *list*) where *list* is a list of tuples. Each tuple has the form (*group*, *last*, *first*, *flag*), where *group* is a group name, *last* and *first* are the last and first article numbers (as strings), and *flag* is 'y' if posting is allowed, 'n' if not, and 'm' if the newsgroup is moderated. (Note the ordering: *last*, *first*.) If the *file* parameter is supplied, then the output of the 'LIST' command is stored in a file. If *file* is a string, then the method will open a file object with that name, write to it then close it. If *file* is a file object, then it will start calling `write()` on it to store the lines of the command output. If *file* is supplied, then the returned *list* is an empty list.

descriptions(*grouppattern*)

Send a 'LIST NEWSGROUPS' command, where *grouppattern* is a wildmat string as specified in RFC2980 (it's essentially the same as DOS or UNIX shell wildcard strings). Return a pair (*response*, *list*), where *list* is a list of tuples containing (*name*, *title*).

New in version 2.4.

description (*group*)

Get a description for a single group *group*. If more than one group matches (if 'group' is a real wildmat string), return the first match. If no group matches, return an empty string.

This elides the response code from the server. If the response code is needed, use `descriptions()`.

New in version 2.4.

group (*name*)

Send a 'GROUP' command, where *name* is the group name. Return a tuple (*response*, *count*, *first*, *last*, *name*) where *count* is the (estimated) number of articles in the group, *first* is the first article number in the group, *last* is the last article number in the group, and *name* is the group name. The numbers are returned as strings.

help ([*file*])

Send a 'HELP' command. Return a pair (*response*, *list*) where *list* is a list of help strings. If the *file* parameter is supplied, then the output of the 'HELP' command is stored in a file. If *file* is a string, then the method will open a file object with that name, write to it then close it. If *file* is a file object, then it will start calling `write()` on it to store the lines of the command output. If *file* is supplied, then the returned *list* is an empty list.

stat (*id*)

Send a 'STAT' command, where *id* is the message id (enclosed in '<' and '>') or an article number (as a string). Return a triple (*response*, *number*, *id*) where *number* is the article number (as a string) and *id* is the message id (enclosed in '<' and '>').

next ()

Send a 'NEXT' command. Return as for `stat()`.

last ()

Send a 'LAST' command. Return as for `stat()`.

head (*id*)

Send a 'HEAD' command, where *id* has the same meaning as for `stat()`. Return a tuple (*response*, *number*, *id*, *list*) where the first three are the same as for `stat()`, and *list* is a list of the article's headers (an uninterpreted list of lines, without trailing newlines).

body (*id*, [*file*])

Send a 'BODY' command, where *id* has the same meaning as for `stat()`. If the *file* parameter is supplied, then the body is stored in a file. If *file* is a string, then the method will open a file object with that name, write to it then close it. If *file* is a file object, then it will start calling `write()` on it to store the lines of the body. Return as for `head()`. If *file* is supplied, then the returned *list* is an empty list.

article (*id*)

Send an 'ARTICLE' command, where *id* has the same meaning as for `stat()`. Return as for `head()`.

slave ()

Send a 'SLAVE' command. Return the server's *response*.

xhdr (*header*, *string*, [*file*])

Send an 'XHDR' command. This command is not defined in the RFC but is a common extension. The *header* argument is a header keyword, e.g. 'subject'. The *string* argument should have the form '*first-last*' where *first* and *last* are the first and last article numbers to search. Return a pair (*response*, *list*), where *list* is a list of pairs (*id*, *text*), where *id* is an article number (as a string) and *text* is the text of the requested header for that article. If the *file* parameter is supplied, then the output of the 'XHDR' command is stored in a file. If *file* is a string, then the method will open a file object with that name, write to it then close it. If *file* is a file object, then it will start calling `write()` on it to store the lines of the command output. If *file* is supplied, then the returned *list* is an empty list.

post (*file*)

Post an article using the 'POST' command. The *file* argument is an open file object which is read until EOF using its `readline()` method. It should be a well-formed news article, including the required headers. The

`post()` method automatically escapes lines beginning with ‘.’.

ihave (*id*, *file*)

Send an ‘IHAVE’ command. *id* is a message id (enclosed in ‘<’ and ‘>’). If the response is not an error, treat *file* exactly as for the `post()` method.

date ()

Return a triple (*response*, *date*, *time*), containing the current date and time in a form suitable for the `newnews()` and `newgroups()` methods. This is an optional NNTP extension, and may not be supported by all servers.

xgtitle (*name*, [*file*])

Process an ‘XGTITLE’ command, returning a pair (*response*, *list*), where *list* is a list of tuples containing (*name*, *title*). If the *file* parameter is supplied, then the output of the ‘XGTITLE’ command is stored in a file. If *file* is a string, then the method will open a file object with that name, write to it then close it. If *file* is a file object, then it will start calling `write()` on it to store the lines of the command output. If *file* is supplied, then the returned *list* is an empty list. This is an optional NNTP extension, and may not be supported by all servers.

RFC2980 says “It is suggested that this extension be deprecated”. Use `descriptions()` or `description()` instead.

xover (*start*, *end*, [*file*])

Return a pair (*resp*, *list*). *list* is a list of tuples, one for each article in the range delimited by the *start* and *end* article numbers. Each tuple is of the form (*article number*, *subject*, *poster*, *date*, *id*, *references*, *size*, *lines*). If the *file* parameter is supplied, then the output of the ‘XOVER’ command is stored in a file. If *file* is a string, then the method will open a file object with that name, write to it then close it. If *file* is a file object, then it will start calling `write()` on it to store the lines of the command output. If *file* is supplied, then the returned *list* is an empty list. This is an optional NNTP extension, and may not be supported by all servers.

xpath (*id*)

Return a pair (*resp*, *path*), where *path* is the directory path to the article with message ID *id*. This is an optional NNTP extension, and may not be supported by all servers.

quit ()

Send a ‘QUIT’ command and close the connection. Once this method has been called, no other methods of the NNTP object should be called.

18.13 smtplib — SMTP protocol client

The `smtplib` module defines an SMTP client session object that can be used to send mail to any Internet machine with an SMTP or ESMTP listener daemon. For details of SMTP and ESMTP operation, consult RFC 821 (*Simple Mail Transfer Protocol*) and RFC 1869 (*SMTP Service Extensions*).

class SMTP ([*host*[, *port*[, *local_hostname*]]])

A SMTP instance encapsulates an SMTP connection. It has methods that support a full repertoire of SMTP and ESMTP operations. If the optional host and port parameters are given, the `SMTP.connect()` method is called with those parameters during initialization. An `SMTPConnectError` is raised if the specified host doesn’t respond correctly.

For normal use, you should only require the initialization/connect, `sendmail()`, and `quit()` methods. An example is included below.

A nice selection of exceptions is defined as well:

exception SMTPException

Base exception class for all exceptions raised by this module.

exception SMTPServerDisconnected

This exception is raised when the server unexpectedly disconnects, or when an attempt is made to use the SMTP

instance before connecting it to a server.

exception SMTPResponseException

Base class for all exceptions that include an SMTP error code. These exceptions are generated in some instances when the SMTP server returns an error code. The error code is stored in the `smtp_code` attribute of the error, and the `smtp_error` attribute is set to the error message.

exception SMTPSenderRefused

Sender address refused. In addition to the attributes set by on all `SMTPResponseException` exceptions, this sets 'sender' to the string that the SMTP server refused.

exception SMTPRecipientsRefused

All recipient addresses refused. The errors for each recipient are accessible through the attribute `recipients`, which is a dictionary of exactly the same sort as `SMTP.sendmail()` returns.

exception SMTPDataError

The SMTP server refused to accept the message data.

exception SMTPConnectError

Error occurred during establishment of a connection with the server.

exception SMTPHeloError

The server refused our 'HELO' message.

exception SMTPAuthenticationError

SMTP authentication went wrong. Most probably the server didn't accept the username/password combination provided.

See Also:

RFC 821, "*Simple Mail Transfer Protocol*"

Protocol definition for SMTP. This document covers the model, operating procedure, and protocol details for SMTP.

RFC 1869, "*SMTP Service Extensions*"

Definition of the ESMTP extensions for SMTP. This describes a framework for extending SMTP with new commands, supporting dynamic discovery of the commands provided by the server, and defines a few additional commands.

18.13.1 SMTP Objects

An SMTP instance has the following methods:

set_debuglevel (*level*)

Set the debug output level. A true value for *level* results in debug messages for connection and for all messages sent to and received from the server.

connect ([*host*, *port*])

Connect to a host on a given port. The defaults are to connect to the local host at the standard SMTP port (25). If the hostname ends with a colon (':') followed by a number, that suffix will be stripped off and the number interpreted as the port number to use. This method is automatically invoked by the constructor if a host is specified during instantiation.

docmd (*cmd*, [*argstring*])

Send a command *cmd* to the server. The optional argument *argstring* is simply concatenated to the command, separated by a space.

This returns a 2-tuple composed of a numeric response code and the actual response line (multiline responses are joined into one long line.)

In normal operation it should not be necessary to call this method explicitly. It is used to implement other

methods and may be useful for testing private extensions.

If the connection to the server is lost while waiting for the reply, `SMTPServerDisconnected` will be raised.

hello (*[hostname]*)

Identify yourself to the SMTP server using 'HELO'. The *hostname* argument defaults to the fully qualified domain name of the local host.

In normal operation it should not be necessary to call this method explicitly. It will be implicitly called by the `sendmail()` when necessary.

ehlo (*[hostname]*)

Identify yourself to an ESMTP server using 'EHLO'. The *hostname* argument defaults to the fully qualified domain name of the local host. Examine the response for ESMTP option and store them for use by `has_extn()`.

Unless you wish to use `has_extn()` before sending mail, it should not be necessary to call this method explicitly. It will be implicitly called by `sendmail()` when necessary.

has_extn (*name*)

Return `True` if *name* is in the set of SMTP service extensions returned by the server, `False` otherwise. Case is ignored.

verify (*address*)

Check the validity of an address on this server using SMTP 'VRFY'. Returns a tuple consisting of code 250 and a full RFC 822 address (including human name) if the user address is valid. Otherwise returns an SMTP error code of 400 or greater and an error string.

Note: Many sites disable SMTP 'VRFY' in order to foil spammers.

login (*user, password*)

Log in on an SMTP server that requires authentication. The arguments are the username and the password to authenticate with. If there has been no previous 'EHLO' or 'HELO' command this session, this method tries ESMTP 'EHLO' first. This method will return normally if the authentication was successful, or may raise the following exceptions:

SMTPHelloErrorThe server didn't reply properly to the 'HELO' greeting.

SMTPAuthenticationErrorThe server didn't accept the username/password combination.

SMTPExceptionNo suitable authentication method was found.

starttls (*[keyfile[, certfile]]*)

Put the SMTP connection in TLS (Transport Layer Security) mode. All SMTP commands that follow will be encrypted. You should then call `ehlo()` again.

If *keyfile* and *certfile* are provided, these are passed to the `socket` module's `ssl()` function.

sendmail (*from_addr, to_addrs, msg[, mail_options, rcpt_options]*)

Send mail. The required arguments are an RFC 822 from-address string, a list of RFC 822 to-address strings (a bare string will be treated as a list with 1 address), and a message string. The caller may pass a list of ESMTP options (such as '8bitmime') to be used in 'MAIL FROM' commands as *mail_options*. ESMTP options (such as 'DSN' commands) that should be used with all 'RCPT' commands can be passed as *rcpt_options*. (If you need to use different ESMTP options to different recipients you have to use the low-level methods such as `mail`, `rcpt` and `data` to send the message.)

Note: The *from_addr* and *to_addrs* parameters are used to construct the message envelope used by the transport agents. The SMTP does not modify the message headers in any way.

If there has been no previous 'EHLO' or 'HELO' command this session, this method tries ESMTP 'EHLO' first. If the server does ESMTP, message size and each of the specified options will be passed to it (if the option is in the feature set the server advertises). If 'EHLO' fails, 'HELO' will be tried and ESMTP options suppressed.

This method will return normally if the mail is accepted for at least one recipient. Otherwise it will throw an exception. That is, if this method does not throw an exception, then someone should get your mail. If this

method does not throw an exception, it returns a dictionary, with one entry for each recipient that was refused. Each entry contains a tuple of the SMTP error code and the accompanying error message sent by the server.

This method may raise the following exceptions:

SMTPRecipientsRefusedAll recipients were refused. Nobody got the mail. The `recipients` attribute of the exception object is a dictionary with information about the refused recipients (like the one returned when at least one recipient was accepted).

SMTPHeloErrorThe server didn't reply properly to the 'HELO' greeting.

SMTPSenderRefusedThe server didn't accept the *from_addr*.

SMTPDataErrorThe server replied with an unexpected error code (other than a refusal of a recipient).

Unless otherwise noted, the connection will be open even after an exception is raised.

quit()

Terminate the SMTP session and close the connection.

Low-level methods corresponding to the standard SMTP/ESMTP commands 'HELP', 'RSET', 'NOOP', 'MAIL', 'RCPT', and 'DATA' are also supported. Normally these do not need to be called directly, so they are not documented here. For details, consult the module code.

18.13.2 SMTP Example

This example prompts the user for addresses needed in the message envelope ('To' and 'From' addresses), and the message to be delivered. Note that the headers to be included with the message must be included in the message as entered; this example doesn't do any processing of the RFC 822 headers. In particular, the 'To' and 'From' addresses must be included in the message headers explicitly.

```

import smtplib

def prompt(prompt):
    return raw_input(prompt).strip()

fromaddr = prompt("From: ")
toaddrs = prompt("To: ").split()
print "Enter message, end with ^D (Unix) or ^Z (Windows):"

# Add the From: and To: headers at the start!
msg = ("From: %s\r\nTo: %s\r\n\r\n"
       % (fromaddr, ", ".join(toaddrs)))
while 1:
    try:
        line = raw_input()
    except EOFError:
        break
    if not line:
        break
    msg = msg + line

print "Message length is " + repr(len(msg))

server = smtplib.SMTP('localhost')
server.set_debuglevel(1)
server.sendmail(fromaddr, toaddrs, msg)
server.quit()

```

18.14 smtpd — SMTP Server

This module offers several classes to implement SMTP servers. One is a generic do-nothing implementation, which can be overridden, while the other two offer specific mail-sending strategies.

18.14.1 SMTPServer Objects

class SMTPServer (*localaddr, remoteaddr*)

Create a new SMTPServer object, which binds to local address *localaddr*. It will treat *remoteaddr* as an upstream SMTP relay. It inherits from `asyncore.dispatcher`, and so will insert itself into `asyncore`'s event loop on instantiation.

process_message (*peer, mailfrom, rcpttos, data*)

Raise `NotImplementedError` exception. Override this in subclasses to do something useful with this message. Whatever was passed in the constructor as *remoteaddr* will be available as the `_remoteaddr` attribute. *peer* is the remote host's address, *mailfrom* is the envelope originator, *rcpttos* are the envelope recipients and *data* is a string containing the contents of the e-mail (which should be in RFC 2822 format).

18.14.2 DebuggingServer Objects

class DebuggingServer (*localaddr, remoteaddr*)

Create a new debugging server. Arguments are as per SMTPServer. Messages will be discarded, and printed on stdout.

18.14.3 PureProxy Objects

class PureProxy (*localaddr*, *remoteaddr*)

Create a new pure proxy server. Arguments are as per `SMTPServer`. Everything will be relayed to *remoteaddr*. Note that running this has a good chance to make you into an open relay, so please be careful.

18.14.4 MailmanProxy Objects

class MailmanProxy (*localaddr*, *remoteaddr*)

Create a new pure proxy server. Arguments are as per `SMTPServer`. Everything will be relayed to *remoteaddr*, unless local mailman configurations knows about an address, in which case it will be handled via mailman. Note that running this has a good chance to make you into an open relay, so please be careful.

18.15 telnetlib — Telnet client

The `telnetlib` module provides a `Telnet` class that implements the Telnet protocol. See RFC 854 for details about the protocol. In addition, it provides symbolic constants for the protocol characters (see below), and for the telnet options. The symbolic names of the telnet options follow the definitions in `arpa/telnet.h`, with the leading `TELOPT_` removed. For symbolic names of options which are traditionally not included in `arpa/telnet.h`, see the module source itself.

The symbolic constants for the telnet commands are: `IAC`, `DONT`, `DO`, `WONT`, `WILL`, `SE` (Subnegotiation End), `NOP` (No Operation), `DM` (Data Mark), `BRK` (Break), `IP` (Interrupt process), `AO` (Abort output), `AYT` (Are You There), `EC` (Erase Character), `EL` (Erase Line), `GA` (Go Ahead), `SB` (Subnegotiation Begin).

class Telnet ([*host* [, *port*]])

`Telnet` represents a connection to a Telnet server. The instance is initially not connected by default; the `open()` method must be used to establish a connection. Alternatively, the host name and optional port number can be passed to the constructor, to, in which case the connection to the server will be established before the constructor returns.

Do not reopen an already connected instance.

This class has many `read_*()` methods. Note that some of them raise `EOFError` when the end of the connection is read, because they can return an empty string for other reasons. See the individual descriptions below.

See Also:

RFC 854, “*Telnet Protocol Specification*”
Definition of the Telnet protocol.

18.15.1 Telnet Objects

`Telnet` instances have the following methods:

read_until (*expected* [, *timeout*])

Read until a given string, *expected*, is encountered or until *timeout* seconds have passed.

When no match is found, return whatever is available instead, possibly the empty string. Raise `EOFError` if the connection is closed and no cooked data is available.

read_all ()

Read all data until EOF; block until connection closed.

read_some()
Read at least one byte of cooked data unless EOF is hit. Return '' if EOF is hit. Block if no data is immediately available.

read_very_eager()
Read everything that can be without blocking in I/O (eager).
Raise `EOFError` if connection closed and no cooked data available. Return '' if no cooked data available otherwise. Do not block unless in the midst of an IAC sequence.

read_eager()
Read readily available data.
Raise `EOFError` if connection closed and no cooked data available. Return '' if no cooked data available otherwise. Do not block unless in the midst of an IAC sequence.

read_lazy()
Process and return data already in the queues (lazy).
Raise `EOFError` if connection closed and no data available. Return '' if no cooked data available otherwise. Do not block unless in the midst of an IAC sequence.

read_very_lazy()
Return any data available in the cooked queue (very lazy).
Raise `EOFError` if connection closed and no data available. Return '' if no cooked data available otherwise. This method never blocks.

read_sb_data()
Return the data collected between a SB/SE pair (suboption begin/end). The callback should access these data when it was invoked with a SE command. This method never blocks.
New in version 2.3.

open(host[, port])
Connect to a host. The optional second argument is the port number, which defaults to the standard Telnet port (23).
Do not try to reopen an already connected instance.

msg(msg[, *args])
Print a debug message when the debug level is > 0. If extra arguments are present, they are substituted in the message using the standard string formatting operator.

set_debuglevel(debuglevel)
Set the debug level. The higher the value of *debuglevel*, the more debug output you get (on `sys.stdout`).

close()
Close the connection.

get_socket()
Return the socket object used internally.

fileno()
Return the file descriptor of the socket object used internally.

write(buffer)
Write a string to the socket, doubling any IAC characters. This can block if the connection is blocked. May raise `socket.error` if the connection is closed.

interact()
Interaction function, emulates a very dumb Telnet client.

mt_interact()
Multithreaded version of `interact()`.

expect (*list*, *timeout*)

Read until one from a list of a regular expressions matches.

The first argument is a list of regular expressions, either compiled (`re.RegexObject` instances) or uncompiled (strings). The optional second argument is a timeout, in seconds; the default is to block indefinitely.

Return a tuple of three items: the index in the list of the first regular expression that matches; the match object returned; and the text read up till and including the match.

If end of file is found and no text was read, raise `EOFError`. Otherwise, when nothing matches, return `(-1, None, text)` where *text* is the text received so far (may be the empty string if a timeout happened).

If a regular expression ends with a greedy match (such as `[.*]`) or if more than one expression can match the same input, the results are indeterministic, and may depend on the I/O timing.

set_option_negotiation_callback (*callback*)

Each time a telnet option is read on the input flow, this *callback* (if set) is called with the following parameters : `callback(telnet socket, command (DO/DONT/WILL/WONT), option)`. No other action is done afterwards by `telnetlib`.

18.15.2 Telnet Example

A simple example illustrating typical use:

```
import getpass
import sys
import telnetlib

HOST = "localhost"
user = raw_input("Enter your remote account: ")
password = getpass.getpass()

tn = telnetlib.Telnet(HOST)

tn.read_until("login: ")
tn.write(user + "\n")
if password:
    tn.read_until("Password: ")
    tn.write(password + "\n")

tn.write("ls\n")
tn.write("exit\n")

print tn.read_all()
```

18.16 uuid — UUID objects according to RFC 4122

New in version 2.5.

This module provides immutable `UUID` objects (the `UUID` class) and the functions `uuid1()`, `uuid3()`, `uuid4()`, `uuid5()` for generating version 1, 3, 4, and 5 UUIDs as specified in RFC 4122.

If all you want is a unique ID, you should probably call `uuid1()` or `uuid4()`. Note that `uuid1()` may compromise privacy since it creates a UUID containing the computer's network address. `uuid4()` creates a random UUID.

class **UUID** ([*hex*[, *bytes*[, *bytes_le*[, *fields*[, *int*[, *version*]]]]])

Create a UUID from either a string of 32 hexadecimal digits, a string of 16 bytes as the *bytes* argument, a string of 16 bytes in little-endian order as the *bytes_le* argument, a tuple of six integers (32-bit *time_low*, 16-bit *time_mid*, 16-bit *time_hi_version*, 8-bit *clock_seq_hi_variant*, 8-bit *clock_seq_low*, 48-bit *node*) as the *fields* argument, or a single 128-bit integer as the *int* argument. When a string of hex digits is given, curly braces, hyphens, and a URN prefix are all optional. For example, these expressions all yield the same UUID:

```
UUID('{12345678-1234-5678-1234-567812345678}')
UUID('12345678123456781234567812345678')
UUID('urn:uuid:12345678-1234-5678-1234-567812345678')
UUID(bytes='\x12\x34\x56\x78'*4)
UUID(bytes_le='\x78\x56\x34\x12\x34\x12\x78\x56' +
              '\x12\x34\x56\x78\x12\x34\x56\x78')
UUID(fields=(0x12345678, 0x1234, 0x5678, 0x12, 0x34, 0x567812345678))
UUID(int=0x12345678123456781234567812345678)
```

Exactly one of *hex*, *bytes*, *bytes_le*, *fields*, or *int* must be given. The *version* argument is optional; if given, the resulting UUID will have its variant and version number set according to RFC 4122, overriding bits in the given *hex*, *bytes*, *bytes_le*, *fields*, or *int*.

UUID instances have these read-only attributes:

bytes

The UUID as a 16-byte string (containing the six integer fields in big-endian byte order).

bytes_le

The UUID as a 16-byte string (with *time_low*, *time_mid*, and *time_hi_version* in little-endian byte order).

fields

A tuple of the six integer fields of the UUID, which are also available as six individual attributes and two derived attributes:

Field	Meaning
<code>time_low</code>	the first 32 bits of the UUID
<code>time_mid</code>	the next 16 bits of the UUID
<code>time_hi_version</code>	the next 16 bits of the UUID
<code>clock_seq_hi_variant</code>	the next 8 bits of the UUID
<code>clock_seq_low</code>	the next 8 bits of the UUID
<code>node</code>	the last 48 bits of the UUID
<code>time</code>	the 60-bit timestamp
<code>clock_seq</code>	the 14-bit sequence number

hex

The UUID as a 32-character hexadecimal string.

int

The UUID as a 128-bit integer.

urn

The UUID as a URN as specified in RFC 4122.

variant

The UUID variant, which determines the internal layout of the UUID. This will be one of the integer constants `RESERVED_NCS`, `RFC_4122`, `RESERVED_MICROSOFT`, or `RESERVED_FUTURE`.

version

The UUID version number (1 through 5, meaningful only when the variant is `RFC_4122`).

The `uuid` module defines the following functions:

getnode ()

Get the hardware address as a 48-bit positive integer. The first time this runs, it may launch a separate program, which could be quite slow. If all attempts to obtain the hardware address fail, we choose a random 48-bit number with its eighth bit set to 1 as recommended in RFC 4122. "Hardware address" means the MAC address of a network interface, and on a machine with multiple network interfaces the MAC address of any one of them may be returned.

uuid1 ([*node*, *clock_seq*]])

Generate a UUID from a host ID, sequence number, and the current time. If *node* is not given, `getnode()` is used to obtain the hardware address. If *clock_seq* is given, it is used as the sequence number; otherwise a random 14-bit sequence number is chosen.

uuid3 (*namespace*, *name*)

Generate a UUID based on the MD5 hash of a namespace identifier (which is a UUID) and a name (which is a string).

uuid4 ()

Generate a random UUID.

uuid5 (*namespace*, *name*)

Generate a UUID based on the SHA-1 hash of a namespace identifier (which is a UUID) and a name (which is a string).

The `uuid` module defines the following namespace identifiers for use with `uuid3()` or `uuid5()`.

NAMESPACE_DNS

When this namespace is specified, the *name* string is a fully-qualified domain name.

NAMESPACE_URL

When this namespace is specified, the *name* string is a URL.

NAMESPACE_OID

When this namespace is specified, the *name* string is an ISO OID.

NAMESPACE_X500

When this namespace is specified, the *name* string is an X.500 DN in DER or a text output format.

The `uuid` module defines the following constants for the possible values of the `variant` attribute:

RESERVED_NCS

Reserved for NCS compatibility.

RFC_4122

Specifies the UUID layout given in RFC 4122.

RESERVED_MICROSOFT

Reserved for Microsoft compatibility.

RESERVED_FUTURE

Reserved for future definition.

See Also:

RFC 4122, "A Universally Unique Identifier (UUID) URN Namespace"

This specification defines a Uniform Resource Name namespace for UUIDs, the internal format of UUIDs, and methods of generating UUIDs.

18.16.1 Example

Here are some examples of typical usage of the `uuid` module:


```

>>> import uuid

# make a UUID based on the host ID and current time
>>> uuid.uuid1()
UUID('a8098c1a-f86e-11da-bd1a-00112444be1e')

# make a UUID using an MD5 hash of a namespace UUID and a name
>>> uuid.uuid3(uuid.NAMESPACE_DNS, 'python.org')
UUID('6fa459ea-ee8a-3ca4-894e-db77e160355e')

# make a random UUID
>>> uuid.uuid4()
UUID('16fd2706-8baf-433b-82eb-8c7fada847da')

# make a UUID using a SHA-1 hash of a namespace UUID and a name
>>> uuid.uuid5(uuid.NAMESPACE_DNS, 'python.org')
UUID('886313e1-3b8a-5372-9b90-0c9aee199e5d')

# make a UUID from a string of hex digits (braces and hyphens ignored)
>>> x = uuid.UUID('{00010203-0405-0607-0809-0a0b0c0d0e0f}')

# convert a UUID to a string of hex digits in standard form
>>> str(x)
'00010203-0405-0607-0809-0a0b0c0d0e0f'

# get the raw 16 bytes of the UUID
>>> x.bytes
'\x00\x01\x02\x03\x04\x05\x06\x07\x08\t\n\x0b\x0c\r\x0e\x0f'

# make a UUID from a 16-byte string
>>> uuid.UUID(bytes=x.bytes)
UUID('00010203-0405-0607-0809-0a0b0c0d0e0f')

```

18.17 urlparse — Parse URLs into components

This module defines a standard interface to break Uniform Resource Locator (URL) strings up in components (addressing scheme, network location, path etc.), to combine the components back into a URL string, and to convert a “relative URL” to an absolute URL given a “base URL.”

The module has been designed to match the Internet RFC on Relative Uniform Resource Locators (and discovered a bug in an earlier draft!). It supports the following URL schemes: `file`, `ftp`, `gopher`, `hdl`, `http`, `https`, `imap`, `mailto`, `mms`, `news`, `nnntp`, `prospero`, `rsync`, `rtsp`, `rtspu`, `sftp`, `shttp`, `sip`, `sips`, `snews`, `svn`, `svn+ssh`, `telnet`, `wais`.

New in version 2.5: Support for the `sftp` and `sips` schemes.

The `urlparse` module defines the following functions:

urlparse (*urlstring* [, *default_scheme* [, *allow_fragments*]])

Parse a URL into six components, returning a 6-tuple. This corresponds to the general structure of a URL: *scheme* : // *netloc* / *path* ; *parameters* ? *query* # *fragment*. Each tuple item is a string, possibly empty. The components are not broken up in smaller parts (for example, the network location is a single string), and % escapes are not expanded. The delimiters as shown above are not part of the result, except for a leading slash in the *path* component, which is retained if present. For example:

```

>>> from urlparse import urlparse
>>> o = urlparse('http://www.cwi.nl:80/%7Eguido/Python.html')
>>> o
('http', 'www.cwi.nl:80', '/%7Eguido/Python.html', '', '', '')
>>> o.scheme
'http'
>>> o.port
80
>>> o.geturl()
'http://www.cwi.nl:80/%7Eguido/Python.html'

```

If the *default_scheme* argument is specified, it gives the default addressing scheme, to be used only if the URL does not specify one. The default value for this argument is the empty string.

If the *allow_fragments* argument is false, fragment identifiers are not allowed, even if the URL's addressing scheme normally does support them. The default value for this argument is `True`.

The return value is actually an instance of a subclass of tuple. This class has the following additional read-only convenience attributes:

Attribute	Index	Value	Value if not present
scheme	0	URL scheme specifier	empty string
netloc	1	Network location part	empty string
path	2	Hierarchical path	empty string
params	3	Parameters for last path element	empty string
query	4	Query component	empty string
fragment	5	Fragment identifier	empty string
username		User name	None
password		Password	None
hostname		Host name (lower case)	None
port		Port number as integer, if present	None

See section 18.17.1, “Results of `urlparse()` and `urlsplit()`,” for more information on the result object.

Changed in version 2.5: Added attributes to return value.

urlunparse (*parts*)

Construct a URL from a tuple as returned by `urlparse()`. The *parts* argument can be any six-item iterable. This may result in a slightly different, but equivalent URL, if the URL that was parsed originally had unnecessary delimiters (for example, a `?` with an empty query; the RFC states that these are equivalent).

urlsplit (*urlstring* [, *default_scheme* [, *allow_fragments*]])

This is similar to `urlparse()`, but does not split the params from the URL. This should generally be used instead of `urlparse()` if the more recent URL syntax allowing parameters to be applied to each segment of the *path* portion of the URL (see RFC 2396) is wanted. A separate function is needed to separate the path segments and parameters. This function returns a 5-tuple: (addressing scheme, network location, path, query, fragment identifier).

The return value is actually an instance of a subclass of tuple. This class has the following additional read-only convenience attributes:

Attribute	Index	Value	Value if not present
scheme	0	URL scheme specifier	empty string
netloc	1	Network location part	empty string
path	2	Hierarchical path	empty string
query	3	Query component	empty string
fragment	4	Fragment identifier	empty string
username		User name	None
password		Password	None
hostname		Host name (lower case)	None
port		Port number as integer, if present	None

See section 18.17.1, “Results of `urlparse()` and `urlsplit()`,” for more information on the result object. New in version 2.2. Changed in version 2.5: Added attributes to return value.

urlunsplit (*parts*)

Combine the elements of a tuple as returned by `urlsplit()` into a complete URL as a string. The *parts* argument can be any five-item iterable. This may result in a slightly different, but equivalent URL, if the URL that was parsed originally had unnecessary delimiters (for example, a `?` with an empty query; the RFC states that these are equivalent). New in version 2.2.

urljoin (*base*, *url* [, *allow_fragments*])

Construct a full (“absolute”) URL by combining a “base URL” (*base*) with another URL (*url*). Informally, this uses components of the base URL, in particular the addressing scheme, the network location and (part of) the path, to provide missing components in the relative URL. For example:

```
>>> from urlparse import urljoin
>>> urljoin('http://www.cwi.nl/%7Eguido/Python.html', 'FAQ.html')
'http://www.cwi.nl/%7Eguido/FAQ.html'
```

The *allow_fragments* argument has the same meaning and default as for `urlparse()`.

Note: If *url* is an absolute URL (that is, starting with `//` or `scheme://`, the *url*’s host name and/or scheme will be present in the result. For example:

```
>>> urljoin('http://www.cwi.nl/%7Eguido/Python.html',
...         '//www.python.org/%7Eguido')
'http://www.python.org/%7Eguido'
```

If you do not want that behavior, preprocess the *url* with `urlsplit()` and `urlunsplit()`, removing possible *scheme* and *netloc* parts.

urldefrag (*url*)

If *url* contains a fragment identifier, returns a modified version of *url* with no fragment identifier, and the fragment identifier as a separate string. If there is no fragment identifier in *url*, returns *url* unmodified and an empty string.

See Also:

RFC 1738, “*Uniform Resource Locators (URL)*”

This specifies the formal syntax and semantics of absolute URLs.

RFC 1808, “*Relative Uniform Resource Locators*”

This Request For Comments includes the rules for joining an absolute and a relative URL, including a fair number of “Abnormal Examples” which govern the treatment of border cases.

RFC 2396, “*Uniform Resource Identifiers (URI): Generic Syntax*”

Document describing the generic syntactic requirements for both Uniform Resource Names (URNs) and Uniform Resource Locators (URLs).

18.17.1 Results of `urlparse()` and `urlsplit()`

The result objects from the `urlparse()` and `urlsplit()` functions are subclasses of the tuple type. These subclasses add the attributes described in those functions, as well as provide an additional method:

geturl ()

Return the re-combined version of the original URL as a string. This may differ from the original URL in that the scheme will always be normalized to lower case and empty components may be dropped. Specifically, empty parameters, queries, and fragment identifiers will be removed.

The result of this method is a fixpoint if passed back through the original parsing function:

```

>>> import urlparse
>>> url = 'HTTP://www.Python.org/doc/#'

>>> r1 = urlparse.urlsplit(url)
>>> r1.geturl()
'http://www.Python.org/doc/'

>>> r2 = urlparse.urlsplit(r1.geturl())
>>> r2.geturl()
'http://www.Python.org/doc/'

```

New in version 2.5.

The following classes provide the implementations of the parse results::

class BaseResult

Base class for the concrete result classes. This provides most of the attribute definitions. It does not provide a `geturl()` method. It is derived from `tuple`, but does not override the `__init__()` or `__new__()` methods.

class ParseResult (*scheme, netloc, path, params, query, fragment*)

Concrete class for `urlparse()` results. The `__new__()` method is overridden to support checking that the right number of arguments are passed.

class SplitResult (*scheme, netloc, path, query, fragment*)

Concrete class for `urlsplit()` results. The `__new__()` method is overridden to support checking that the right number of arguments are passed.

18.18 SocketServer — A framework for network servers

The `SocketServer` module simplifies the task of writing network servers.

There are four basic server classes: `TCPServer` uses the Internet TCP protocol, which provides for continuous streams of data between the client and server. `UDPServer` uses datagrams, which are discrete packets of information that may arrive out of order or be lost while in transit. The more infrequently used `UnixStreamServer` and `UnixDatagramServer` classes are similar, but use UNIX domain sockets; they're not available on non-UNIX platforms. For more details on network programming, consult a book such as W. Richard Steven's *UNIX Network Programming* or Ralph Davis's *Win32 Network Programming*.

These four classes process requests *synchronously*; each request must be completed before the next request can be started. This isn't suitable if each request takes a long time to complete, because it requires a lot of computation, or because it returns a lot of data which the client is slow to process. The solution is to create a separate process or thread to handle each request; the `ForkingMixIn` and `ThreadingMixIn` mix-in classes can be used to support asynchronous behaviour.


Creating a server requires several steps. First, you must create a request handler class by subclassing the `BaseRequestHandler` class and overriding its `handle()` method; this method will process incoming requests. Second, you must instantiate one of the server classes, passing it the server's address and the request handler class. Finally, call the `handle_request()` or `serve_forever()` method of the server object to process one or many requests.

When inheriting from `ThreadingMixIn` for threaded connection behavior, you should explicitly declare how you want your threads to behave on an abrupt shutdown. The `ThreadingMixIn` class defines an attribute `daemon_threads`, which indicates whether or not the server should wait for thread termination. You should set the flag explicitly if you would like threads to behave autonomously; the default is `False`, meaning that Python will not exit until all threads created by `ThreadingMixIn` have exited.

Server classes have the same external methods and attributes, no matter what network protocol they use:

18.18.1 Server Creation Notes

There are five classes in an inheritance diagram, four of which represent synchronous servers of four types:



Note that `UnixDatagramServer` derives from `UDPServer`, not from `UnixStreamServer` — the only difference between an IP and a UNIX stream server is the address family, which is simply repeated in both UNIX server classes.

Forking and threading versions of each type of server can be created using the `ForkingMixIn` and `ThreadingMixIn` mix-in classes. For instance, a threading UDP server class is created as follows:

```
class ThreadingUDPServer(ThreadingMixIn, UDPServer): pass
```

The mix-in class must come first, since it overrides a method defined in `UDPServer`. Setting the various member variables also changes the behavior of the underlying server mechanism.

To implement a service, you must derive a class from `BaseRequestHandler` and redefine its `handle()` method. You can then run various versions of the service by combining one of the server classes with your request handler class. The request handler class must be different for datagram or stream services. This can be hidden by using the handler subclasses `StreamRequestHandler` or `DatagramRequestHandler`.

Of course, you still have to use your head! For instance, it makes no sense to use a forking server if the service contains state in memory that can be modified by different requests, since the modifications in the child process would never reach the initial state kept in the parent process and passed to each child. In this case, you can use a threading server, but you will probably have to use locks to protect the integrity of the shared data.

On the other hand, if you are building an HTTP server where all data is stored externally (for instance, in the file system), a synchronous class will essentially render the service "deaf" while one request is being handled – which may be for a very long time if a client is slow to receive all the data it has requested. Here a threading or forking server is appropriate.

In some cases, it may be appropriate to process part of a request synchronously, but to finish processing in a forked child depending on the request data. This can be implemented by using a synchronous server and doing an explicit fork in the request handler class `handle()` method.

Another approach to handling multiple simultaneous requests in an environment that supports neither threads nor `fork()` (or where these are too expensive or inappropriate for the service) is to maintain an explicit table of partially finished requests and to use `select()` to decide which request to work on next (or whether to handle a new incoming request). This is particularly important for stream services where each client can potentially be connected for a long

time (if threads or subprocesses cannot be used).

18.18.2 Server Objects

fileno()

Return an integer file descriptor for the socket on which the server is listening. This function is most commonly passed to `select.select()`, to allow monitoring multiple servers in the same process.

handle_request()

Process a single request. This function calls the following methods in order: `get_request()`, `verify_request()`, and `process_request()`. If the user-provided `handle()` method of the handler class raises an exception, the server's `handle_error()` method will be called.

serve_forever()

Handle an infinite number of requests. This simply calls `handle_request()` inside an infinite loop.

address_family

The family of protocols to which the server's socket belongs. `socket.AF_INET` and `socket.AF_UNIX` are two possible values.

RequestHandlerClass

The user-provided request handler class; an instance of this class is created for each request.

server_address

The address on which the server is listening. The format of addresses varies depending on the protocol family; see the documentation for the socket module for details. For Internet protocols, this is a tuple containing a string giving the address, and an integer port number: `('127.0.0.1', 80)`, for example.

socket

The socket object on which the server will listen for incoming requests.

The server classes support the following class variables:

allow_reuse_address

Whether the server will allow the reuse of an address. This defaults to `False`, and can be set in subclasses to change the policy.

request_queue_size

The size of the request queue. If it takes a long time to process a single request, any requests that arrive while the server is busy are placed into a queue, up to `request_queue_size` requests. Once the queue is full, further requests from clients will get a "Connection denied" error. The default value is usually 5, but this can be overridden by subclasses.

socket_type

The type of socket used by the server; `socket.SOCK_STREAM` and `socket.SOCK_DGRAM` are two possible values.

There are various server methods that can be overridden by subclasses of base server classes like `TCPServer`; these methods aren't useful to external users of the server object.

finish_request()

Actually processes the request by instantiating `RequestHandlerClass` and calling its `handle()` method.

get_request()

Must accept a request from the socket, and return a 2-tuple containing the *new* socket object to be used to communicate with the client, and the client's address.

handle_error(request, client_address)

This function is called if the `RequestHandlerClass`'s `handle()` method raises an exception. The default action is to print the traceback to standard output and continue handling further requests.

process_request (*request, client_address*)

Calls `finish_request()` to create an instance of the `RequestHandlerClass`. If desired, this function can create a new process or thread to handle the request; the `ForkingMixIn` and `ThreadingMixIn` classes do this.

server_activate ()

Called by the server's constructor to activate the server. The default behavior just listens to the server's socket. May be overridden.

server_bind ()

Called by the server's constructor to bind the socket to the desired address. May be overridden.

verify_request (*request, client_address*)

Must return a Boolean value; if the value is `True`, the request will be processed, and if it's `False`, the request will be denied. This function can be overridden to implement access controls for a server. The default implementation always returns `True`.

18.18.3 RequestHandler Objects

The request handler class must define a new `handle()` method, and can override any of the following methods. A new instance is created for each request.

finish ()

Called after the `handle()` method to perform any clean-up actions required. The default implementation does nothing. If `setup()` or `handle()` raise an exception, this function will not be called.

handle ()

This function must do all the work required to service a request. The default implementation does nothing. Several instance attributes are available to it; the request is available as `self.request`; the client address as `self.client_address`; and the server instance as `self.server`, in case it needs access to per-server information.

The type of `self.request` is different for datagram or stream services. For stream services, `self.request` is a socket object; for datagram services, `self.request` is a string. However, this can be hidden by using the request handler subclasses `StreamRequestHandler` or `DatagramRequestHandler`, which override the `setup()` and `finish()` methods, and provide `self.rfile` and `self.wfile` attributes. `self.rfile` and `self.wfile` can be read or written, respectively, to get the request data or return data to the client.

setup ()

Called before the `handle()` method to perform any initialization actions required. The default implementation does nothing.

18.19 BaseHTTPServer — Basic HTTP server

This module defines two classes for implementing HTTP servers (Web servers). Usually, this module isn't used directly, but is used as a basis for building functioning Web servers. See the [SimpleHTTPServer](#) and [CGIHTTPServer](#) modules.

The first class, `HTTPServer`, is a `SocketServer.TCPServer` subclass. It creates and listens at the HTTP socket, dispatching the requests to a handler. Code to create and run the server looks like this:

```
def run(server_class=BaseHTTPServer.HTTPServer,
        handler_class=BaseHTTPServer.BaseHTTPRequestHandler):
    server_address = ('', 8000)
    httpd = server_class(server_address, handler_class)
    httpd.serve_forever()
```

class HTTPServer (*server_address, RequestHandlerClass*)

This class builds on the `TCPServer` class by storing the server address as instance variables named `server_name` and `server_port`. The server is accessible by the handler, typically through the handler's `server` instance variable.

class BaseHTTPRequestHandler (*request, client_address, server*)

This class is used to handle the HTTP requests that arrive at the server. By itself, it cannot respond to any actual HTTP requests; it must be subclassed to handle each request method (e.g. `GET` or `POST`). `BaseHTTPRequestHandler` provides a number of class and instance variables, and methods for use by subclasses.

The handler will parse the request and the headers, then call a method specific to the request type. The method name is constructed from the request. For example, for the request method `'SPAM'`, the `do_SPAM()` method will be called with no arguments. All of the relevant information is stored in instance variables of the handler. Subclasses should not need to override or extend the `__init__()` method.

`BaseHTTPRequestHandler` has the following instance variables:

client_address

Contains a tuple of the form (*host*, *port*) referring to the client's address.

command

Contains the command (request type). For example, `'GET'`.

path

Contains the request path.

request_version

Contains the version string from the request. For example, `'HTTP/1.0'`.

headers

Holds an instance of the class specified by the `MessageClass` class variable. This instance parses and manages the headers in the HTTP request.

rfile

Contains an input stream, positioned at the start of the optional input data.

wfile

Contains the output stream for writing a response back to the client. Proper adherence to the HTTP protocol must be used when writing to this stream.

`BaseHTTPRequestHandler` has the following class variables:

server_version

Specifies the server software version. You may want to override this. The format is multiple whitespace-separated strings, where each string is of the form `name[/version]`. For example, `'BaseHTTP/0.2'`.

sys_version

Contains the Python system version, in a form usable by the `version_string` method and the `server_version` class variable. For example, `'Python/1.4'`.

error_message_format

Specifies a format string for building an error response to the client. It uses parenthesized, keyed format specifiers, so the format operand must be a dictionary. The `code` key should be an integer, specifying the numeric

HTTP error code value. *message* should be a string containing a (detailed) error message of what occurred, and *explain* should be an explanation of the error code number. Default *message* and *explain* values can found in the *responses* class variable.

protocol_version

This specifies the HTTP protocol version used in responses. If set to `'HTTP/1.1'`, the server will permit HTTP persistent connections; however, your server *must* then include an accurate `Content-Length` header (using `send_header()`) in all of its responses to clients. For backwards compatibility, the setting defaults to `'HTTP/1.0'`.

MessageClass

Specifies a `rfc822.Message`-like class to parse HTTP headers. Typically, this is not overridden, and it defaults to `mimetools.Message`.

responses

This variable contains a mapping of error code integers to two-element tuples containing a short and long message. For example, `{code: (shortmessage, longmessage)}`. The *shortmessage* is usually used as the *message* key in an error response, and *longmessage* as the *explain* key (see the `error_message_format` class variable).

A `BaseHTTPRequestHandler` instance has the following methods:

handle()

Calls `handle_one_request()` once (or, if persistent connections are enabled, multiple times) to handle incoming HTTP requests. You should never need to override it; instead, implement appropriate `do_*()` methods.

handle_one_request()

This method will parse and dispatch the request to the appropriate `do_*()` method. You should never need to override it.

send_error(*code*, *message*)

Sends and logs a complete error reply to the client. The numeric *code* specifies the HTTP error code, with *message* as optional, more specific text. A complete set of headers is sent, followed by text composed using the `error_message_format` class variable.

send_response(*code*, *message*)

Sends a response header and logs the accepted request. The HTTP response line is sent, followed by *Server* and *Date* headers. The values for these two headers are picked up from the `version_string()` and `date_time_string()` methods, respectively.

send_header(*keyword*, *value*)

Writes a specific HTTP header to the output stream. *keyword* should specify the header keyword, with *value* specifying its value.

end_headers()

Sends a blank line, indicating the end of the HTTP headers in the response.

log_request(*code*, *size*)

Logs an accepted (successful) request. *code* should specify the numeric HTTP code associated with the response. If a size of the response is available, then it should be passed as the *size* parameter.

log_error(...)

Logs an error when a request cannot be fulfilled. By default, it passes the message to `log_message()`, so it takes the same arguments (*format* and additional values).

log_message(*format*, ...)

Logs an arbitrary message to `sys.stderr`. This is typically overridden to create custom error logging mechanisms. The *format* argument is a standard `printf`-style format string, where the additional arguments to `log_message()` are applied as inputs to the formatting. The client address and current date and time are prefixed to every message logged.

version_string()

Returns the server software's version string. This is a combination of the `server_version` and `sys_version` class variables.

date_time_string([timestamp])

Returns the date and time given by *timestamp* (which must be in the format returned by `time.time()`), formatted for a message header. If *timestamp* is omitted, it uses the current date and time.

The result looks like 'Sun, 06 Nov 1994 08:49:37 GMT'. New in version 2.5: The *timestamp* parameter.

log_date_time_string()

Returns the current date and time, formatted for logging.

address_string()

Returns the client address, formatted for logging. A name lookup is performed on the client's IP address.

See Also:

[Module CGIHTTPServer](#) (section 18.21):

Extended request handler that supports CGI scripts.

[Module SimpleHTTPServer](#) (section 18.20):

Basic request handler that limits response to files actually under the document root.

18.20 SimpleHTTPServer — Simple HTTP request handler

The `SimpleHTTPServer` module defines a request-handler class, interface-compatible with `BaseHTTPServer.BaseHTTPRequestHandler`, that serves files only from a base directory.

The `SimpleHTTPServer` module defines the following class:

class SimpleHTTPRequestHandler(request, client_address, server)

This class is used to serve files from the current directory and below, directly mapping the directory structure to HTTP requests.

A lot of the work, such as parsing the request, is done by the base class `BaseHTTPServer.BaseHTTPRequestHandler`. This class implements the `do_GET()` and `do_HEAD()` functions.

The `SimpleHTTPRequestHandler` defines the following member variables:

server_version

This will be "SimpleHTTP/" + `__version__`, where `__version__` is defined in the module.

extensions_map

A dictionary mapping suffixes into MIME types. The default is signified by an empty string, and is considered to be `application/octet-stream`. The mapping is used case-insensitively, and so should contain only lower-cased keys.

The `SimpleHTTPRequestHandler` defines the following methods:

do_HEAD()

This method serves the 'HEAD' request type: it sends the headers it would send for the equivalent GET request. See the `do_GET()` method for a more complete explanation of the possible headers.

do_GET()

The request is mapped to a local file by interpreting the request as a path relative to the current working directory.

If the request was mapped to a directory, the directory is checked for a file named `index.html` or `index.htm` (in that order). If found, the file's contents are returned; otherwise a directory listing is generated by calling the `list_directory()` method. This method uses `os.listdir()` to scan the directory,

and returns a 404 error response if the `listdir()` fails.

If the request was mapped to a file, it is opened and the contents are returned. Any `IOError` exception in opening the requested file is mapped to a 404, 'File not found' error. Otherwise, the content type is guessed by calling the `guess_type()` method, which in turn uses the `extensions_map` variable.

A 'Content-type:' header with the guessed content type is output, followed by a 'Content-Length:' header with the file's size and a 'Last-Modified:' header with the file's modification time.

Then follows a blank line signifying the end of the headers, and then the contents of the file are output. If the file's MIME type starts with `text/` the file is opened in text mode; otherwise binary mode is used.

For example usage, see the implementation of the `test()` function. New in version 2.5: The 'Last-Modified' header.

See Also:

[Module `BaseHTTPServer`](#) (section 18.19):

Base class implementation for Web server and request handler.

18.21 `CGIHTTPServer` — CGI-capable HTTP request handler

The `CGIHTTPServer` module defines a request-handler class, interface compatible with `BaseHTTPServer.BaseHTTPRequestHandler` and inherits behavior from `SimpleHTTPServer.SimpleHTTPRequestHandler` but can also run CGI scripts.

Note: This module can run CGI scripts on UNIX and Windows systems; on Mac OS it will only be able to run Python scripts within the same process as itself.

Note: CGI scripts run by the `CGIHTTPRequestHandler` class cannot execute redirects (HTTP code 302), because code 200 (script output follows) is sent prior to execution of the CGI script. This pre-empts the status code.

The `CGIHTTPServer` module defines the following class:

class `CGIHTTPRequestHandler` (*request, client_address, server*)

This class is used to serve either files or output of CGI scripts from the current directory and below. Note that mapping HTTP hierarchic structure to local directory structure is exactly as in `SimpleHTTPServer.SimpleHTTPRequestHandler`.

The class will however, run the CGI script, instead of serving it as a file, if it guesses it to be a CGI script. Only directory-based CGI are used — the other common server configuration is to treat special extensions as denoting CGI scripts.

The `do_GET()` and `do_HEAD()` functions are modified to run CGI scripts and serve the output, instead of serving files, if the request leads to somewhere below the `cgi_directories` path.

The `CGIHTTPRequestHandler` defines the following data member:

`cgi_directories`

This defaults to `['/cgi-bin', '/htbin']` and describes directories to treat as containing CGI scripts.

The `CGIHTTPRequestHandler` defines the following methods:

`do_POST()`

This method serves the 'POST' request type, only allowed for CGI scripts. Error 501, "Can only POST to CGI scripts", is output when trying to POST to a non-CGI url.

Note that CGI scripts will be run with UID of user nobody, for security reasons. Problems with the CGI script will be translated to error 403.

For example usage, see the implementation of the `test()` function.

See Also:

Module `BaseHTTPServer` (section 18.19):

Base class implementation for Web server and request handler.

18.22 `cookielib` — Cookie handling for HTTP clients

New in version 2.4.

The `cookielib` module defines classes for automatic handling of HTTP cookies. It is useful for accessing web sites that require small pieces of data – *cookies* – to be set on the client machine by an HTTP response from a web server, and then returned to the server in later HTTP requests.

Both the regular Netscape cookie protocol and the protocol defined by RFC 2965 are handled. RFC 2965 handling is switched off by default. RFC 2109 cookies are parsed as Netscape cookies and subsequently treated either as Netscape or RFC 2965 cookies according to the 'policy' in effect. Note that the great majority of cookies on the Internet are Netscape cookies. `cookielib` attempts to follow the de-facto Netscape cookie protocol (which differs substantially from that set out in the original Netscape specification), including taking note of the `max-age` and `port` cookie-attributes introduced with RFC 2965. **Note:** The various named parameters found in `Set-Cookie:` and `Set-Cookie2:` headers (eg. `domain` and `expires`) are conventionally referred to as *attributes*. To distinguish them from Python attributes, the documentation for this module uses the term *cookie-attribute* instead.

The module defines the following exception:

exception `LoadError`

Instances of `FileCookieJar` raise this exception on failure to load cookies from a file. **Note:** For backwards-compatibility with Python 2.4 (which raised an `IOError`), `LoadError` is a subclass of `IOError`.

The following classes are provided:

class `CookieJar` (*policy=None*)

policy is an object implementing the `CookiePolicy` interface.

The `CookieJar` class stores HTTP cookies. It extracts cookies from HTTP requests, and returns them in HTTP responses. `CookieJar` instances automatically expire contained cookies when necessary. Subclasses are also responsible for storing and retrieving cookies from a file or database.

class `FileCookieJar` (*filename, delayload=None, policy=None*)

policy is an object implementing the `CookiePolicy` interface. For the other arguments, see the documentation for the corresponding attributes.

A `CookieJar` which can load cookies from, and perhaps save cookies to, a file on disk. Cookies are **NOT** loaded from the named file until either the `load()` or `revert()` method is called. Subclasses of this class are documented in section 18.22.2.

class `CookiePolicy` ()

This class is responsible for deciding whether each cookie should be accepted from / returned to the server.

class `DefaultCookiePolicy` (*blocked_domains=None, allowed_domains=None, netscape=True, rfc2965=False, rfc2109_as_netscape=None, hide_cookie2=False, strict_domain=False, strict_rfc2965_unverifiable=True, strict_ns_unverifiable=False, strict_ns_domain=DefaultCookiePolicy.DomainLiberal, strict_ns_set_initial_dollar=False, strict_ns_set_path=False*)

Constructor arguments should be passed as keyword arguments only. *blocked_domains* is a sequence of domain names that we never accept cookies from, nor return cookies to. *allowed_domains* if not `None`, this is a sequence of the only domains for which we accept and return cookies. For all other arguments, see the documentation for `CookiePolicy` and `DefaultCookiePolicy` objects.

`DefaultCookiePolicy` implements the standard accept / reject rules for Netscape and RFC 2965 cookies. By default, RFC 2109 cookies (ie. cookies received in a `Set-Cookie:` header with a version cookie-attribute of 1) are treated according to the RFC 2965 rules. However, if RFC 2965 handling is turned off or `rfc2109_as_`

netcape is True, RFC 2109 cookies are 'downgraded' by the `CookieJar` instance to Netscape cookies, by setting the `version` attribute of the `Cookie` instance to 0. `DefaultCookiePolicy` also provides some parameters to allow some fine-tuning of policy.

class `Cookie` ()

This class represents Netscape, RFC 2109 and RFC 2965 cookies. It is not expected that users of `cookielib` construct their own `Cookie` instances. Instead, if necessary, call `make_cookies()` on a `CookieJar` instance.

See Also:

[Module `urllib2`](#) (section 18.6):

URL opening with automatic cookie handling.

[Module `Cookie`](#) (section 18.23):

HTTP cookie classes, principally useful for server-side code. The `cookielib` and `Cookie` modules do not depend on each other.

<http://wwwsearch.sf.net/ClientCookie/>

Extensions to this module, including a class for reading Microsoft Internet Explorer cookies on Windows.

http://www.netscape.com/newsref/std/cookie_spec.html

The specification of the original Netscape cookie protocol. Though this is still the dominant protocol, the 'Netscape cookie protocol' implemented by all the major browsers (and `cookielib`) only bears a passing resemblance to the one sketched out in `cookie_spec.html`.

RFC 2109, "*HTTP State Management Mechanism*"

Obsoleted by RFC 2965. Uses Set-Cookie: with version=1.

RFC 2965, "*HTTP State Management Mechanism*"

The Netscape protocol with the bugs fixed. Uses Set-Cookie2: in place of Set-Cookie:. Not widely used.

<http://kristol.org/cookie/errata.html>

Unfinished errata to RFC 2965.

RFC 2964, "*Use of HTTP State Management*"

18.22.1 `CookieJar` and `FileCookieJar` Objects

`CookieJar` objects support the iterator protocol for iterating over contained `Cookie` objects.

`CookieJar` has the following methods:

`add_cookie_header` (*request*)

Add correct Cookie: header to *request*.

If policy allows (ie. the `rfc2965` and `hide_cookie2` attributes of the `CookieJar`'s `CookiePolicy` instance are true and false respectively), the Cookie2: header is also added when appropriate.

The *request* object (usually a `urllib2.Request` instance) must support the methods `get_full_url()`, `get_host()`, `get_type()`, `unverifiable()`, `get_origin_req_host()`, `has_header()`, `get_header()`, `header_items()`, and `add_unredirected_header()`, as documented by `urllib2`.

`extract_cookies` (*response*, *request*)

Extract cookies from HTTP *response* and store them in the `CookieJar`, where allowed by policy.

The `CookieJar` will look for allowable Set-Cookie: and Set-Cookie2: headers in the *response* argument, and store cookies as appropriate (subject to the `CookiePolicy.set_ok()` method's approval).

The *response* object (usually the result of a call to `urllib2.urlopen()`, or similar) should support an `info()` method, which returns an object with a `getallmatchingheaders()` method (usually a `mimetools.Message` instance).

The *request* object (usually a `urllib2.Request` instance) must support the methods `get_full_url()`, `get_host()`, `unverifiable()`, and `get_origin_req_host()`, as documented by `urllib2`. The request is used to set default values for cookie-attributes as well as for checking that the cookie is allowed to be set.

set_policy (*policy*)

Set the `CookiePolicy` instance to be used.

make_cookies (*response*, *request*)

Return sequence of `Cookie` objects extracted from *response* object.

See the documentation for `extract_cookies` for the interfaces required of the *response* and *request* arguments.

set_cookie_if_ok (*cookie*, *request*)

Set a `Cookie` if policy says it's OK to do so.

set_cookie (*cookie*)

Set a `Cookie`, without checking with policy to see whether or not it should be set.

clear ([*domain*[, *path*[, *name*]]])

Clear some cookies.

If invoked without arguments, clear all cookies. If given a single argument, only cookies belonging to that *domain* will be removed. If given two arguments, cookies belonging to the specified *domain* and URL *path* are removed. If given three arguments, then the cookie with the specified *domain*, *path* and *name* is removed.

Raises `KeyError` if no matching cookie exists.

clear_session_cookies ()

Discard all session cookies.

Discards all contained cookies that have a true `discard` attribute (usually because they had either no `max-age` or `expires` cookie-attribute, or an explicit `discard` cookie-attribute). For interactive browsers, the end of a session usually corresponds to closing the browser window.

Note that the `save()` method won't save session cookies anyway, unless you ask otherwise by passing a true *ignore_discard* argument.

`FileCookieJar` implements the following additional methods:

save (*filename*=None, *ignore_discard*=False, *ignore_expires*=False)

Save cookies to a file.

This base class raises `NotImplementedError`. Subclasses may leave this method unimplemented.

filename is the name of file in which to save cookies. If *filename* is not specified, `self.filename` is used (whose default is the value passed to the constructor, if any); if `self.filename` is None, `ValueError` is raised.

ignore_discard: save even cookies set to be discarded. *ignore_expires*: save even cookies that have expired

The file is overwritten if it already exists, thus wiping all the cookies it contains. Saved cookies can be restored later using the `load()` or `revert()` methods.

load (*filename*=None, *ignore_discard*=False, *ignore_expires*=False)

Load cookies from a file.

Old cookies are kept unless overwritten by newly loaded ones.

Arguments are as for `save()`.

The named file must be in the format understood by the class, or `LoadError` will be raised. Also, `IOError` may be raised, for example if the file does not exist. **Note:** For backwards-compatibility with Python 2.4 (which raised an `IOError`), `LoadError` is a subclass of `IOError`.

revert (*filename*=None, *ignore_discard*=False, *ignore_expires*=False)

Clear all cookies and reload cookies from a saved file.

`revert()` can raise the same exceptions as `load()`. If there is a failure, the object's state will not be altered.

`FileCookieJar` instances have the following public attributes:

filename

Filename of default file in which to keep cookies. This attribute may be assigned to.

delayload

If true, load cookies lazily from disk. This attribute should not be assigned to. This is only a hint, since this only affects performance, not behaviour (unless the cookies on disk are changing). A `CookieJar` object may ignore it. None of the `FileCookieJar` classes included in the standard library lazily loads cookies.

18.22.2 FileCookieJar subclasses and co-operation with web browsers

The following `CookieJar` subclasses are provided for reading and writing. Further `CookieJar` subclasses, including one that reads Microsoft Internet Explorer cookies, are available at <http://wwwsearch.sf.net/ClientCookie/>.

class `MozillaCookieJar` (*filename*, *delayload=None*, *policy=None*)

A `FileCookieJar` that can load from and save cookies to disk in the Mozilla `cookies.txt` file format (which is also used by the Lynx and Netscape browsers). **Note:** This loses information about RFC 2965 cookies, and also about newer or non-standard cookie-attributes such as `port`.

Warning: Back up your cookies before saving if you have cookies whose loss / corruption would be inconvenient (there are some subtleties which may lead to slight changes in the file over a load / save round-trip).

Also note that cookies saved while Mozilla is running will get clobbered by Mozilla.

class `LWPCookieJar` (*filename*, *delayload=None*, *policy=None*)

A `FileCookieJar` that can load from and save cookies to disk in format compatible with the libwww-perl library's `Set-Cookie3` file format. This is convenient if you want to store cookies in a human-readable file.

18.22.3 CookiePolicy Objects

Objects implementing the `CookiePolicy` interface have the following methods:

set_ok (*cookie*, *request*)

Return boolean value indicating whether cookie should be accepted from server.

cookie is a `cookieilib.Cookie` instance. *request* is an object implementing the interface defined by the documentation for `CookieJar.extract_cookies()`.

return_ok (*cookie*, *request*)

Return boolean value indicating whether cookie should be returned to server.

cookie is a `cookieilib.Cookie` instance. *request* is an object implementing the interface defined by the documentation for `CookieJar.add_cookie_header()`.

domain_return_ok (*domain*, *request*)

Return false if cookies should not be returned, given cookie domain.

This method is an optimization. It removes the need for checking every cookie with a particular domain (which might involve reading many files). Returning true from `domain_return_ok()` and `path_return_ok()` leaves all the work to `return_ok()`.

If `domain_return_ok()` returns true for the cookie domain, `path_return_ok()` is called for the cookie path. Otherwise, `path_return_ok()` and `return_ok()` are never called for that cookie domain. If `path_return_ok()` returns true, `return_ok()` is called with the `Cookie` object itself for a full check. Otherwise, `return_ok()` is never called for that cookie path.

Note that `domain_return_ok()` is called for every *cookie* domain, not just for the *request* domain. For example, the function might be called with both `".example.com"` and `"www.example.com"` if the request domain is `"www.example.com"`. The same goes for `path_return_ok()`.

The *request* argument is as documented for `return_ok()`.

path_return_ok (*path, request*)

Return false if cookies should not be returned, given cookie path.

See the documentation for `domain_return_ok()`.

In addition to implementing the methods above, implementations of the `CookiePolicy` interface must also supply the following attributes, indicating which protocols should be used, and how. All of these attributes may be assigned to.

netscape

Implement Netscape protocol.

rfc2965

Implement RFC 2965 protocol.

hide_cookie2

Don't add Cookie2: header to requests (the presence of this header indicates to the server that we understand RFC 2965 cookies).

The most useful way to define a `CookiePolicy` class is by subclassing from `DefaultCookiePolicy` and overriding some or all of the methods above. `CookiePolicy` itself may be used as a 'null policy' to allow setting and receiving any and all cookies (this is unlikely to be useful).

18.22.4 DefaultCookiePolicy Objects

Implements the standard rules for accepting and returning cookies.

Both RFC 2965 and Netscape cookies are covered. RFC 2965 handling is switched off by default.

The easiest way to provide your own policy is to override this class and call its methods in your overridden implementations before adding your own additional checks:

```
import cookielib
class MyCookiePolicy(cockielib.DefaultCookiePolicy):
    def set_ok(self, cookie, request):
        if not cookielib.DefaultCookiePolicy.set_ok(self, cookie, request):
            return False
        if i_dont_want_to_store_this_cookie(cookie):
            return False
        return True
```

In addition to the features required to implement the `CookiePolicy` interface, this class allows you to block and allow domains from setting and receiving cookies. There are also some strictness switches that allow you to tighten up the rather loose Netscape protocol rules a little bit (at the cost of blocking some benign cookies).

A domain blacklist and whitelist is provided (both off by default). Only domains not in the blacklist and present in the whitelist (if the whitelist is active) participate in cookie setting and returning. Use the *blocked_domains* constructor argument, and `blocked_domains()` and `set_blocked_domains()` methods (and the corresponding argument and methods for *allowed_domains*). If you set a whitelist, you can turn it off again by setting it to `None`.

Domains in block or allow lists that do not start with a dot must equal the cookie domain to be matched. For example, "example.com" matches a blacklist entry of "example.com", but "www.example.com" does not. Domains that do start with a dot are matched by more specific domains too. For example, both "www.example.com" and "www.coyote.example.com" match ".example.com" (but "example.com" itself does not). IP addresses are an exception, and must match exactly. For example, if `blocked_domains` contains "192.168.1.2" and ".168.1.2", 192.168.1.2 is blocked, but 193.168.1.2 is not.

DefaultCookiePolicy implements the following additional methods:

blocked_domains ()

Return the sequence of blocked domains (as a tuple).

set_blocked_domains (*blocked_domains*)

Set the sequence of blocked domains.

is_blocked (*domain*)

Return whether *domain* is on the blacklist for setting or receiving cookies.

allowed_domains ()

Return None, or the sequence of allowed domains (as a tuple).

set_allowed_domains (*allowed_domains*)

Set the sequence of allowed domains, or None.

is_not_allowed (*domain*)

Return whether *domain* is not on the whitelist for setting or receiving cookies.

DefaultCookiePolicy instances have the following attributes, which are all initialised from the constructor arguments of the same name, and which may all be assigned to.

rfc2109_as_netscape

If true, request that the CookieJar instance downgrade RFC 2109 cookies (ie. cookies received in a Set-Cookie: header with a version cookie-attribute of 1) to Netscape cookies by setting the version attribute of the Cookie instance to 0. The default value is None, in which case RFC 2109 cookies are downgraded if and only if RFC 2965 handling is turned off. Therefore, RFC 2109 cookies are downgraded by default. New in version 2.5.

General strictness switches:

strict_domain

Don't allow sites to set two-component domains with country-code top-level domains like .co.uk, .gov.uk, .co.nz.etc. This is far from perfect and isn't guaranteed to work!

RFC 2965 protocol strictness switches:

strict_rfc2965_unverifiable

Follow RFC 2965 rules on unverifiable transactions (usually, an unverifiable transaction is one resulting from a redirect or a request for an image hosted on another site). If this is false, cookies are *never* blocked on the basis of verifiability

Netscape protocol strictness switches:

strict_ns_unverifiable

apply RFC 2965 rules on unverifiable transactions even to Netscape cookies

strict_ns_domain

Flags indicating how strict to be with domain-matching rules for Netscape cookies. See below for acceptable values.

strict_ns_set_initial_dollar

Ignore cookies in Set-Cookie: headers that have names starting with ' \$ '.

strict_ns_set_path

Don't allow setting cookies whose path doesn't path-match request URI.

strict_ns_domain is a collection of flags. Its value is constructed by or-ing together (for example, DomainStrictNoDots|DomainStrictNonDomain means both flags are set).

DomainStrictNoDots

When setting cookies, the 'host prefix' must not contain a dot (eg. www.foo.bar.com can't set a cookie for .bar.com, because www.foo contains a dot).

DomainStrictNonDomain

Cookies that did not explicitly specify a `domain` cookie-attribute can only be returned to a domain equal to the domain that set the cookie (eg. `spam.example.com` won't be returned cookies from `example.com` that had no `domain` cookie-attribute).

DomainRFC2965Match

When setting cookies, require a full RFC 2965 domain-match.

The following attributes are provided for convenience, and are the most useful combinations of the above flags:

DomainLiberal

Equivalent to 0 (ie. all of the above Netscape domain strictness flags switched off).

DomainStrict

Equivalent to `DomainStrictNoDots | DomainStrictNonDomain`.

18.22.5 Cookie Objects

`Cookie` instances have Python attributes roughly corresponding to the standard cookie-attributes specified in the various cookie standards. The correspondence is not one-to-one, because there are complicated rules for assigning default values, because the `max-age` and `expires` cookie-attributes contain equivalent information, and because RFC 2109 cookies may be 'downgraded' by `cookieilib` from version 1 to version 0 (Netscape) cookies.

Assignment to these attributes should not be necessary other than in rare circumstances in a `CookiePolicy` method. The class does not enforce internal consistency, so you should know what you're doing if you do that.

version

Integer or `None`. Netscape cookies have `version` 0. RFC 2965 and RFC 2109 cookies have a `version` cookie-attribute of 1. However, note that `cookieilib` may 'downgrade' RFC 2109 cookies to Netscape cookies, in which case `version` is 0.

name

Cookie name (a string).

value

Cookie value (a string), or `None`.

port

String representing a port or a set of ports (eg. `'80'`, or `'80,8080'`), or `None`.

path

Cookie path (a string, eg. `'/acme/rocket_launchers'`).

secure

True if cookie should only be returned over a secure connection.

expires

Integer expiry date in seconds since epoch, or `None`. See also the `is_expired()` method.

discard

True if this is a session cookie.

comment

String comment from the server explaining the function of this cookie, or `None`.

comment_url

URL linking to a comment from the server explaining the function of this cookie, or `None`.

rfc2109

True if this cookie was received as an RFC 2109 cookie (ie. the cookie arrived in a `Set-Cookie:` header, and the value of the `Version` cookie-attribute in that header was 1). This attribute is provided because `cookieilib` may

'downgrade' RFC 2109 cookies to Netscape cookies, in which case `version` is 0. New in version 2.5.

port_specified

True if a port or set of ports was explicitly specified by the server (in the Set-Cookie: / Set-Cookie2: header).

domain_specified

True if a domain was explicitly specified by the server.

domain_initial_dot

True if the domain explicitly specified by the server began with a dot ('.').

Cookies may have additional non-standard cookie-attributes. These may be accessed using the following methods:

has_nonstandard_attr (*name*)

Return true if cookie has the named cookie-attribute.

get_nonstandard_attr (*name*, *default=None*)

If cookie has the named cookie-attribute, return its value. Otherwise, return *default*.

set_nonstandard_attr (*name*, *value*)

Set the value of the named cookie-attribute.

The `Cookie` class also defines the following method:

is_expired ([*now=None*])

True if cookie has passed the time at which the server requested it should expire. If *now* is given (in seconds since the epoch), return whether the cookie has expired at the specified time.

18.22.6 Examples

The first example shows the most common usage of `cookieilib`:

```
import cookieilib, urllib2
cj = cookieilib.CookieJar()
opener = urllib2.build_opener(urllib2.HTTPCookieProcessor(cj))
r = opener.open("http://example.com/")
```

This example illustrates how to open a URL using your Netscape, Mozilla, or Lynx cookies (assumes UNIX/Netscape convention for location of the cookies file):

```
import os, cookieilib, urllib2
cj = cookieilib.MozillaCookieJar()
cj.load(os.path.join(os.environ["HOME"], ".netscape/cookies.txt"))
opener = urllib2.build_opener(urllib2.HTTPCookieProcessor(cj))
r = opener.open("http://example.com/")
```

The next example illustrates the use of `DefaultCookiePolicy`. Turn on RFC 2965 cookies, be more strict about domains when setting and returning Netscape cookies, and block some domains from setting cookies or having them returned:

```
import urllib2
from cookielib import CookieJar, DefaultCookiePolicy
policy = DefaultCookiePolicy(
    rfc2965=True, strict_ns_domain=Policy.DomainStrict,
    blocked_domains=["ads.net", ".ads.net"])
cj = CookieJar(policy)
opener = urllib2.build_opener(urllib2.HTTPCookieProcessor(cj))
r = opener.open("http://example.com/")
```

18.23 Cookie — HTTP state management

The `Cookie` module defines classes for abstracting the concept of cookies, an HTTP state management mechanism. It supports both simple string-only cookies, and provides an abstraction for having any serializable data-type as cookie value.

The module formerly strictly applied the parsing rules described in the RFC 2109 and RFC 2068 specifications. It has since been discovered that MSIE 3.0x doesn't follow the character rules outlined in those specs. As a result, the parsing rules used are a bit less strict.

exception `CookieError`

Exception failing because of RFC 2109 invalidity: incorrect attributes, incorrect Set-Cookie: header, etc.

class `BaseCookie` ([*input*])

This class is a dictionary-like object whose keys are strings and whose values are `Morsel` instances. Note that upon setting a key to a value, the value is first converted to a `Morsel` containing the key and the value.

If *input* is given, it is passed to the `load()` method.

class `SimpleCookie` ([*input*])

This class derives from `BaseCookie` and overrides `value_decode()` and `value_encode()` to be the identity and `str()` respectively.

class `SerialCookie` ([*input*])

This class derives from `BaseCookie` and overrides `value_decode()` and `value_encode()` to be the `pickle.loads()` and `pickle.dumps()`.

Deprecated since release 2.3. Reading pickled values from untrusted cookie data is a huge security hole, as pickle strings can be crafted to cause arbitrary code to execute on your server. It is supported for backwards compatibility only, and may eventually go away.

class `SmartCookie` ([*input*])

This class derives from `BaseCookie`. It overrides `value_decode()` to be `pickle.loads()` if it is a valid pickle, and otherwise the value itself. It overrides `value_encode()` to be `pickle.dumps()` unless it is a string, in which case it returns the value itself.

Deprecated since release 2.3. The same security warning from `SerialCookie` applies here.

A further security note is warranted. For backwards compatibility, the `Cookie` module exports a class named `Cookie` which is just an alias for `SmartCookie`. This is probably a mistake and will likely be removed in a future version. You should not use the `Cookie` class in your applications, for the same reason why you should not use the `SerialCookie` class.

See Also:

[Module `cookielib`](#) (section 18.22):

HTTP cookie handling for web *clients*. The `cookielib` and `Cookie` modules do not depend on each other.

RFC 2109, “*HTTP State Management Mechanism*”

This is the state management specification implemented by this module.

18.23.1 Cookie Objects

value_decode (*val*)

Return a decoded value from a string representation. Return value can be any type. This method does nothing in `BaseCookie` — it exists so it can be overridden.

value_encode (*val*)

Return an encoded value. *val* can be any type, but return value must be a string. This method does nothing in `BaseCookie` — it exists so it can be overridden

In general, it should be the case that `value_encode()` and `value_decode()` are inverses on the range of *value_decode*.

output ([*attrs*[, *header*[, *sep*]])

Return a string representation suitable to be sent as HTTP headers. *attrs* and *header* are sent to each `Morsel`'s `output()` method. *sep* is used to join the headers together, and is by default the combination `'\r\n'` (CRLF). Changed in version 2.5: The default separator has been changed from `'\n'` to match the cookie specification.

js_output ([*attrs*])

Return an embeddable JavaScript snippet, which, if run on a browser which supports JavaScript, will act the same as if the HTTP headers was sent.

The meaning for *attrs* is the same as in `output()`.

load (*rawdata*)

If *rawdata* is a string, parse it as an `HTTP_COOKIE` and add the values found there as `Morsels`. If it is a dictionary, it is equivalent to:

```
for k, v in rawdata.items():
    cookie[k] = v
```

18.23.2 Morsel Objects

class Morsel ()

Abstract a key/value pair, which has some RFC 2109 attributes.

`Morsels` are dictionary-like objects, whose set of keys is constant — the valid RFC 2109 attributes, which are

- `expires`
- `path`
- `comment`
- `domain`
- `max-age`
- `secure`
- `version`

The keys are case-insensitive.

value

The value of the cookie.

coded_value

The encoded value of the cookie — this is what should be sent.

key

The name of the cookie.

set (*key*, *value*, *coded_value*)

Set the *key*, *value* and *coded_value* members.

isReservedKey (*K*)

Whether *K* is a member of the set of keys of a `Morsel`.

output ([*attrs* [, *header*]])

Return a string representation of the `Morsel`, suitable to be sent as an HTTP header. By default, all the attributes are included, unless *attrs* is given, in which case it should be a list of attributes to use. *header* is by default "Set-Cookie:".

js_output ([*attrs*])

Return an embeddable JavaScript snippet, which, if run on a browser which supports JavaScript, will act the same as if the HTTP header was sent.

The meaning for *attrs* is the same as in `output()`.

OutputString ([*attrs*])

Return a string representing the `Morsel`, without any surrounding HTTP or JavaScript.

The meaning for *attrs* is the same as in `output()`.

18.23.3 Example

The following example demonstrates how to use the `Cookie` module.

```
>>> import Cookie
>>> C = Cookie.SimpleCookie()
>>> C = Cookie.SerialCookie()
>>> C = Cookie.SmartCookie()
>>> C["fig"] = "newton"
>>> C["sugar"] = "wafer"
>>> print C # generate HTTP headers
Set-Cookie: sugar=wafer
Set-Cookie: fig=newton
>>> print C.output() # same thing
Set-Cookie: sugar=wafer
Set-Cookie: fig=newton
>>> C = Cookie.SmartCookie()
>>> C["rocky"] = "road"
>>> C["rocky"]["path"] = "/cookie"
>>> print C.output(header="Cookie:")
Cookie: rocky=road; Path=/cookie
>>> print C.output(attrs=[], header="Cookie:")
Cookie: rocky=road
>>> C = Cookie.SmartCookie()
>>> C.load("chips=ahoy; vienna=finger") # load from a string (HTTP header)
>>> print C
Set-Cookie: vienna=finger
Set-Cookie: chips=ahoy
>>> C = Cookie.SmartCookie()
>>> C.load('keebler="E=everybody; L=\\"Loves\\"; fudge=\012;"')
>>> print C
Set-Cookie: keebler="E=everybody; L=\"Loves\"; fudge=\012;"
>>> C = Cookie.SmartCookie()
>>> C["oreo"] = "doublestuff"
>>> C["oreo"]["path"] = "/"
>>> print C
Set-Cookie: oreo=doublestuff; Path=/
>>> C = Cookie.SmartCookie()
>>> C["twix"] = "none for you"
>>> C["twix"].value
'none for you'
>>> C = Cookie.SimpleCookie()
>>> C["number"] = 7 # equivalent to C["number"] = str(7)
>>> C["string"] = "seven"
>>> C["number"].value
'7'
>>> C["string"].value
'seven'
>>> print C
Set-Cookie: number=7
Set-Cookie: string=seven
>>> C = Cookie.SerialCookie()
>>> C["number"] = 7
>>> C["string"] = "seven"
>>> C["number"].value
7
>>> C["string"].value
'seven'
>>> print C
Set-Cookie: number="I7\012."
Set-Cookie: string="S'seven'\012p1\012."
>>> C = Cookie.SmartCookie()
>>> C["number"] = 7
>>> C["string"] = "seven"
```

> Cookie module - HTTP state management

```
7
>>> C["string"].value
'seven'
>>> print C
```

18.24 xmlrpclib — XML-RPC client access

New in version 2.2.

XML-RPC is a Remote Procedure Call method that uses XML passed via HTTP as a transport. With it, a client can call methods with parameters on a remote server (the server is named by a URI) and get back structured data. This module supports writing XML-RPC client code; it handles all the details of translating between conformable Python objects and XML on the wire.

class `ServerProxy` (*uri*[, *transport*[, *encoding*[, *verbose*[, *allow_none*[, *use_datetime*]]]]])

A `ServerProxy` instance is an object that manages communication with a remote XML-RPC server. The required first argument is a URI (Uniform Resource Indicator), and will normally be the URL of the server. The optional second argument is a transport factory instance; by default it is an internal `SafeTransport` instance for https: URLs and an internal `HTTPTransport` instance otherwise. The optional third argument is an encoding, by default UTF-8. The optional fourth argument is a debugging flag. If *allow_none* is true, the Python constant `None` will be translated into XML; the default behaviour is for `None` to raise a `TypeError`. This is a commonly-used extension to the XML-RPC specification, but isn't supported by all clients and servers; see <http://ontosys.com/xml-rpc/extensions.php> for a description. The *use_datetime* flag can be used to cause date/time values to be presented as `datetime.datetime` objects; this is false by default. `datetime.datetime`, `datetime.date` and `datetime.time` objects may be passed to calls. `datetime.date` objects are converted with a time of "00:00:00". `datetime.time` objects are converted using today's date.

Both the HTTP and HTTPS transports support the URL syntax extension for HTTP Basic Authentication: `http://user:pass@host:port/path`. The `user:pass` portion will be base64-encoded as an HTTP 'Authorization' header, and sent to the remote server as part of the connection process when invoking an XML-RPC method. You only need to use this if the remote server requires a Basic Authentication user and password.

The returned instance is a proxy object with methods that can be used to invoke corresponding RPC calls on the remote server. If the remote server supports the introspection API, the proxy can also be used to query the remote server for the methods it supports (service discovery) and fetch other server-associated metadata.

`ServerProxy` instance methods take Python basic types and objects as arguments and return Python basic types and classes. Types that are conformable (e.g. that can be marshalled through XML), include the following (and except where noted, they are unmarshalled as the same Python type):

Name	Meaning
<code>boolean</code>	The <code>True</code> and <code>False</code> constants
<code>integers</code>	Pass in directly
<code>floating-point numbers</code>	Pass in directly
<code>strings</code>	Pass in directly
<code>arrays</code>	Any Python sequence type containing conformable elements. Arrays are returned as lists
<code>structures</code>	A Python dictionary. Keys must be strings, values may be any conformable type.
<code>dates</code>	in seconds since the epoch (pass in an instance of the <code>DateTime</code> class) or a <code>datetime.datetime</code>
<code>binary data</code>	pass in an instance of the <code>Binary</code> wrapper class

This is the full set of data types supported by XML-RPC. Method calls may also raise a special `Fault` instance, used to signal XML-RPC server errors, or `ProtocolError` used to signal an error in the HTTP/HTTPS transport layer. Both `Fault` and `ProtocolError` derive from a base class called `Error`. Note that even though starting with Python 2.2 you can subclass builtin types, the `xmlrpclib` module currently does not marshal instances of such subclasses.

When passing strings, characters special to XML such as '<', '>', and '&' will be automatically escaped. However, it's the caller's responsibility to ensure that the string is free of characters that aren't allowed in XML, such as the control characters with ASCII values between 0 and 31 (except, of course, tab, newline and carriage return); failing to do this will result in an XML-RPC request that isn't well-formed XML. If you have to pass arbitrary strings via XML-RPC, use the `Binary` wrapper class described below.

Server is retained as an alias for `ServerProxy` for backwards compatibility. New code should use `ServerProxy`.

Changed in version 2.5: The `use_datetime` flag was added.

See Also:

XML-RPC HOWTO

(<http://www.tldp.org/HOWTO/XML-RPC-HOWTO/index.html>)

A good description of XML operation and client software in several languages. Contains pretty much everything an XML-RPC client developer needs to know.

XML-RPC Hacks page

(<http://xmlrpc-c.sourceforge.net/hacks.php>)

Extensions for various open-source libraries to support introspection and multicall.

18.24.1 ServerProxy Objects

A `ServerProxy` instance has a method corresponding to each remote procedure call accepted by the XML-RPC server. Calling the method performs an RPC, dispatched by both name and argument signature (e.g. the same method name can be overloaded with multiple argument signatures). The RPC finishes by returning a value, which may be either returned data in a conformant type or a `Fault` or `ProtocolError` object indicating an error.

Servers that support the XML introspection API support some common methods grouped under the reserved `system` member:

system.listMethods()

This method returns a list of strings, one for each (non-system) method supported by the XML-RPC server.

system.methodSignature(name)

This method takes one parameter, the name of a method implemented by the XML-RPC server. It returns an array of possible signatures for this method. A signature is an array of types. The first of these types is the return type of the method, the rest are parameters.

Because multiple signatures (ie. overloading) is permitted, this method returns a list of signatures rather than a singleton.

Signatures themselves are restricted to the top level parameters expected by a method. For instance if a method expects one array of structs as a parameter, and it returns a string, its signature is simply "string, array". If it expects three integers and returns a string, its signature is "string, int, int, int".

If no signature is defined for the method, a non-array value is returned. In Python this means that the type of the returned value will be something other than list.

system.methodHelp(name)

This method takes one parameter, the name of a method implemented by the XML-RPC server. It returns a documentation string describing the use of that method. If no such string is available, an empty string is returned. The documentation string may contain HTML markup.

Introspection methods are currently supported by servers written in PHP, C and Microsoft .NET. Partial introspection support is included in recent updates to UserLand Frontier. Introspection support for Perl, Python and Java is available at the [XML-RPC Hacks](#) page.

18.24.2 Boolean Objects

This class may be initialized from any Python value; the instance returned depends only on its truth value. It supports various Python operators through `__cmp__()`, `__repr__()`, `__int__()`, and `__nonzero__()` methods, all implemented in the obvious ways.

It also has the following method, supported mainly for internal use by the unmarshalling code:

encode (*out*)

Write the XML-RPC encoding of this Boolean item to the out stream object.

18.24.3 DateTime Objects

This class may be initialized with seconds since the epoch, a time tuple, an ISO 8601 time/date string, or a `datetime.datetime`, `datetime.date` or `datetime.time` instance. It has the following methods, supported mainly for internal use by the marshalling/unmarshalling code:

decode (*string*)

Accept a string as the instance's new time value.

encode (*out*)

Write the XML-RPC encoding of this `DateTime` item to the *out* stream object.

It also supports certain of Python's built-in operators through `__cmp__()` and `__repr__()` methods.

18.24.4 Binary Objects

This class may be initialized from string data (which may include NULs). The primary access to the content of a `Binary` object is provided by an attribute:

data

The binary data encapsulated by the `Binary` instance. The data is provided as an 8-bit string.

`Binary` objects have the following methods, supported mainly for internal use by the marshalling/unmarshalling code:

decode (*string*)

Accept a base64 string and decode it as the instance's new data.

encode (*out*)

Write the XML-RPC base 64 encoding of this binary item to the out stream object.

It also supports certain of Python's built-in operators through a `__cmp__()` method.

18.24.5 Fault Objects

A `Fault` object encapsulates the content of an XML-RPC fault tag. Fault objects have the following members:

faultCode

A string indicating the fault type.

faultString

A string containing a diagnostic message associated with the fault.

18.24.6 ProtocolError Objects

A `ProtocolError` object describes a protocol error in the underlying transport layer (such as a 404 'not found' error if the server named by the URI does not exist). It has the following members:

url

The URI or URL that triggered the error.

errcode

The error code.

errmsg

The error message or diagnostic string.

headers

A string containing the headers of the HTTP/HTTPS request that triggered the error.

18.24.7 MultiCall Objects

New in version 2.4.

In <http://www.xmlrpc.com/discuss/msgReader%241208>, an approach is presented to encapsulate multiple calls to a remote server into a single request.

class MultiCall (*server*)

Create an object used to boxcar method calls. *server* is the eventual target of the call. Calls can be made to the result object, but they will immediately return `None`, and only store the call name and parameters in the `MultiCall` object. Calling the object itself causes all stored calls to be transmitted as a single `system.multicall` request. The result of this call is a generator; iterating over this generator yields the individual results.

A usage example of this class is

```
multicall = MultiCall(server_proxy)
multicall.add(2, 3)
multicall.get_address("Guido")
add_result, address = multicall()
```

18.24.8 Convenience Functions

boolean (*value*)

Convert any Python value to one of the XML-RPC Boolean constants, `True` or `False`.

dumps (*params*[, *methodname*[, *methodresponse*[, *encoding*[, *allow_none*]]]])

Convert *params* into an XML-RPC request, or into a response if *methodresponse* is true. *params* can be either a tuple of arguments or an instance of the `Fault` exception class. If *methodresponse* is true, only a single value can be returned, meaning that *params* must be of length 1. *encoding*, if supplied, is the encoding to use in the generated XML; the default is UTF-8. Python's `None` value cannot be used in standard XML-RPC; to allow using it via an extension, provide a true value for *allow_none*.

loads (*data*[, *use_datetime*])

Convert an XML-RPC request or response into Python objects, a (*params*, *methodname*). *params* is a tuple of argument; *methodname* is a string, or `None` if no method name is present in the packet. If the XML-RPC packet represents a fault condition, this function will raise a `Fault` exception. The *use_datetime* flag can be used to cause date/time values to be presented as `datetime.datetime` objects; this is false by default. Note that even if you call an XML-RPC method with `datetime.date` or `datetime.time` objects, they are converted to `DateTime` objects internally, so only `datetime.datetime` objects will be returned.

Changed in version 2.5: The *use_datetime* flag was added.

18.24.9 Example of Client Usage

```
# simple test program (from the XML-RPC specification)
from xmlrpclib import ServerProxy, Error

# server = ServerProxy("http://localhost:8000") # local server
server = ServerProxy("http://betty.userland.com")

print server

try:
    print server.examples.getStateName(41)
except Error, v:
    print "ERROR", v
```

To access an XML-RPC server through a proxy, you need to define a custom transport. The following example, written by NoboNobo, shows how:

```
import xmlrpclib, httplib

class ProxiedTransport(xmlrpclib.Transport):
    def set_proxy(self, proxy):
        self.proxy = proxy
    def make_connection(self, host):
        self.realhost = host
    h = httplib.HTTP(self.proxy)
    return h
    def send_request(self, connection, handler, request_body):
        connection.putrequest("POST", 'http://%s%s' % (self.realhost, handler))
    def send_host(self, connection, host):
        connection.putheader('Host', self.realhost)

p = ProxiedTransport()
p.set_proxy('proxy-server:8080')
server = xmlrpclib.Server('http://time.xmlrpc.com/RPC2', transport=p)
print server.currentTime.getCurrentTime()
```

18.25 SimpleXMLRPCServer — Basic XML-RPC server

New in version 2.2.

The `SimpleXMLRPCServer` module provides a basic server framework for XML-RPC servers written in Python. Servers can either be free standing, using `SimpleXMLRPCServer`, or embedded in a CGI environment, using `CGIXMLRPCRequestHandler`.

class SimpleXMLRPCServer (*addr*[, *requestHandler*[, *logRequests*[, *allow_none*[, *encoding*]]]])

Create a new server instance. This class provides methods for registration of functions that can be called by the XML-RPC protocol. The *requestHandler* parameter should be a factory for request handler instances; it defaults to `SimpleXMLRPCRequestHandler`. The *addr* and *requestHandler* parameters are passed to the `SocketServer.TCPServer` constructor. If *logRequests* is true (the default), requests will be logged; setting this parameter to false will turn off logging. The *allow_none* and *encoding* parameters are passed on to `xmlrpclib` and control the XML-RPC responses that will be returned from the server. Changed in version

2.5: The *allow_none* and *encoding* parameters were added.

class **CGIXMLRPCRequestHandler** (*[allow_none[, encoding]]*)

Create a new instance to handle XML-RPC requests in a CGI environment. The *allow_none* and *encoding* parameters are passed on to `xmlrpc.lib` and control the XML-RPC responses that will be returned from the server. New in version 2.3. Changed in version 2.5: The *allow_none* and *encoding* parameters were added.

class **SimpleXMLRPCRequestHandler** ()

Create a new request handler instance. This request handler supports POST requests and modifies logging so that the *logRequests* parameter to the `SimpleXMLRPCServer` constructor parameter is honored.

18.25.1 SimpleXMLRPCServer Objects

The `SimpleXMLRPCServer` class is based on `SocketServer.TCPServer` and provides a means of creating simple, stand alone XML-RPC servers.

register_function (*function[, name]*)

Register a function that can respond to XML-RPC requests. If *name* is given, it will be the method name associated with *function*, otherwise *function.__name__* will be used. *name* can be either a normal or Unicode string, and may contain characters not legal in Python identifiers, including the period character.

register_instance (*instance[, allow_dotted_names]*)

Register an object which is used to expose method names which have not been registered using `register_function()`. If *instance* contains a `_dispatch()` method, it is called with the requested method name and the parameters from the request. Its API is `def _dispatch(self, method, params)` (note that *params* does not represent a variable argument list). If it calls an underlying function to perform its task, that function is called as `func(*params)`, expanding the parameter list. The return value from `_dispatch()` is returned to the client as the result. If *instance* does not have a `_dispatch()` method, it is searched for an attribute matching the name of the requested method.

If the optional *allow_dotted_names* argument is true and the instance does not have a `_dispatch()` method, then if the requested method name contains periods, each component of the method name is searched for individually, with the effect that a simple hierarchical search is performed. The value found from this search is then called with the parameters from the request, and the return value is passed back to the client.

Warning: Enabling the *allow_dotted_names* option allows intruders to access your module's global variables and may allow intruders to execute arbitrary code on your machine. Only use this option on a secure, closed network.

Changed in version 2.3.5, 2.4.1: *allow_dotted_names* was added to plug a security hole; prior versions are insecure.

register_introspection_functions ()

Registers the XML-RPC introspection functions `system.listMethods`, `system.methodHelp` and `system.methodSignature`. New in version 2.3.

register_multicall_functions ()

Registers the XML-RPC multicall function `system.multicall`.

rpc_paths

An attribute value that must be a tuple listing valid path portions of the URL for receiving XML-RPC requests. Requests posted to other paths will result in a 404 “no such page” HTTP error. If this tuple is empty, all paths will be considered valid. The default value is `(' / ', ' /RPC2')`. New in version 2.5.

Example:

```

from SimpleXMLRPCServer import SimpleXMLRPCServer

# Create server
server = SimpleXMLRPCServer(("localhost", 8000))
server.register_introspection_functions()

# Register pow() function; this will use the value of
# pow.__name__ as the name, which is just 'pow'.
server.register_function(pow)

# Register a function under a different name
def adder_function(x,y):
    return x + y
server.register_function(adder_function, 'add')

# Register an instance; all the methods of the instance are
# published as XML-RPC methods (in this case, just 'div').
class MyFuncs:
    def div(self, x, y):
        return x // y

server.register_instance(MyFuncs())

# Run the server's main loop
server.serve_forever()

```

The following client code will call the methods made available by the preceding server:

```

import xmlrpclib

s = xmlrpclib.Server('http://localhost:8000')
print s.pow(2,3) # Returns 2**3 = 8
print s.add(2,3) # Returns 5
print s.div(5,2) # Returns 5//2 = 2

# Print list of available methods
print s.system.listMethods()

```

18.25.2 CGIXMLRPCRequestHandler

The `CGIXMLRPCRequestHandler` class can be used to handle XML-RPC requests sent to Python CGI scripts.

register_function (*function* [, *name*])

Register a function that can respond to XML-RPC requests. If *name* is given, it will be the method name associated with function, otherwise *function.__name__* will be used. *name* can be either a normal or Unicode string, and may contain characters not legal in Python identifiers, including the period character.

register_instance (*instance*)

Register an object which is used to expose method names which have not been registered using `register_function()`. If instance contains a `_dispatch()` method, it is called with the requested method name and the parameters from the request; the return value is returned to the client as the result. If instance does not have a `_dispatch()` method, it is searched for an attribute matching the name of the requested method; if the requested method name contains periods, each component of the method name is searched for individually,

with the effect that a simple hierarchical search is performed. The value found from this search is then called with the parameters from the request, and the return value is passed back to the client.

register_introspection_functions()

Register the XML-RPC introspection functions `system.listMethods`, `system.methodHelp` and `system.methodSignature`.

register_multicall_functions()

Register the XML-RPC multicall function `system.multicall`.

handle_request ([*request_text* = None])

Handle a XML-RPC request. If *request_text* is given, it should be the POST data provided by the HTTP server, otherwise the contents of `stdin` will be used.

Example:

```
class MyFuncs:
    def div(self, x, y) : return x // y

handler = CGIXMLRPCRequestHandler()
handler.register_function(pow)
handler.register_function(lambda x,y: x+y, 'add')
handler.register_introspection_functions()
handler.register_instance(MyFuncs())
handler.handle_request()
```

18.26 DocXMLRPCServer — Self-documenting XML-RPC server

New in version 2.3.

The `DocXMLRPCServer` module extends the classes found in `SimpleXMLRPCServer` to serve HTML documentation in response to HTTP GET requests. Servers can either be free standing, using `DocXMLRPCServer`, or embedded in a CGI environment, using `DocCGIXMLRPCRequestHandler`.

class DocXMLRPCServer (*addr* [, *requestHandler* [, *logRequests*]])

Create a new server instance. All parameters have the same meaning as for `SimpleXMLRPCServer.SimpleXMLRPCServer`; *requestHandler* defaults to `DocXMLRPCRequestHandler`.

class DocCGIXMLRPCRequestHandler ()

Create a new instance to handle XML-RPC requests in a CGI environment.

class DocXMLRPCRequestHandler ()

Create a new request handler instance. This request handler supports XML-RPC POST requests, documentation GET requests, and modifies logging so that the *logRequests* parameter to the `DocXMLRPCServer` constructor parameter is honored.

18.26.1 DocXMLRPCServer Objects

The `DocXMLRPCServer` class is derived from `SimpleXMLRPCServer.SimpleXMLRPCServer` and provides a means of creating self-documenting, stand alone XML-RPC servers. HTTP POST requests are handled as XML-RPC method calls. HTTP GET requests are handled by generating pydoc-style HTML documentation. This allows a server to provide its own web-based documentation.

set_server_title (*server_title*)

Set the title used in the generated HTML documentation. This title will be used inside the HTML "title" element.

set_server_name (*server_name*)

Set the name used in the generated HTML documentation. This name will appear at the top of the generated documentation inside a "h1" element.

set_server_documentation (*server_documentation*)

Set the description used in the generated HTML documentation. This description will appear as a paragraph, below the server name, in the documentation.

18.26.2 DocCGIXMLRPCRequestHandler

The `DocCGIXMLRPCRequestHandler` class is derived from `SimpleXMLRPCServer.CGIXMLRPCRequestHandler` and provides a means of creating self-documenting, XML-RPC CGI scripts. HTTP POST requests are handled as XML-RPC method calls. HTTP GET requests are handled by generating pydoc-style HTML documentation. This allows a server to provide its own web-based documentation.

set_server_title (*server_title*)

Set the title used in the generated HTML documentation. This title will be used inside the HTML "title" element.

set_server_name (*server_name*)

Set the name used in the generated HTML documentation. This name will appear at the top of the generated documentation inside a "h1" element.

set_server_documentation (*server_documentation*)

Set the description used in the generated HTML documentation. This description will appear as a paragraph, below the server name, in the documentation.

Multimedia Services

The modules described in this chapter implement various algorithms or interfaces that are mainly useful for multimedia applications. They are available at the discretion of the installation. Here's an overview:

audioop	Manipulate raw audio data.
imageop	Manipulate raw image data.
aifc	Read and write audio files in AIFF or AIFC format.
sunau	Provide an interface to the Sun AU sound format.
wave	Provide an interface to the WAV sound format.
chunk	Module to read IFF chunks.
colorsys	Conversion functions between RGB and other color systems.
rgbimg	Read and write image files in "SGI RGB" format (the module is <i>not</i> SGI specific though!).
imghdr	Determine the type of image contained in a file or byte stream.
sndhdr	Determine type of a sound file.
ossaudiodev	Access to OSS-compatible audio devices.

19.1 `audioop` — Manipulate raw audio data

The `audioop` module contains some useful operations on sound fragments. It operates on sound fragments consisting of signed integer samples 8, 16 or 32 bits wide, stored in Python strings. This is the same format as used by the `al` and `sunaudiodev` modules. All scalar items are integers, unless specified otherwise.

This module provides support for a-LAW, u-LAW and Intel/DVI ADPCM encodings.

A few of the more complicated operations only take 16-bit samples, otherwise the sample size (in bytes) is always a parameter of the operation.

The module defines the following variables and functions:

exception error

This exception is raised on all errors, such as unknown number of bytes per sample, etc.

add (*fragment1, fragment2, width*)

Return a fragment which is the addition of the two samples passed as parameters. *width* is the sample width in bytes, either 1, 2 or 4. Both fragments should have the same length.

adpcm2lin (*adpcmfragment, width, state*)

Decode an Intel/DVI ADPCM coded fragment to a linear fragment. See the description of `lin2adpcm()` for details on ADPCM coding. Return a tuple (*sample, newstate*) where the sample has the width specified in *width*.

alaw2lin (*fragment, width*)

Convert sound fragments in a-LAW encoding to linearly encoded sound fragments. a-LAW encoding always

uses 8 bits samples, so *width* refers only to the sample width of the output fragment here. New in version 2.5.

avg (*fragment*, *width*)

Return the average over all samples in the fragment.

avgpp (*fragment*, *width*)

Return the average peak-peak value over all samples in the fragment. No filtering is done, so the usefulness of this routine is questionable.

bias (*fragment*, *width*, *bias*)

Return a fragment that is the original fragment with a bias added to each sample.

cross (*fragment*, *width*)

Return the number of zero crossings in the fragment passed as an argument.

findfactor (*fragment*, *reference*)

Return a factor F such that `rms (add (fragment, mul (reference, -F)))` is minimal, i.e., return the factor with which you should multiply *reference* to make it match as well as possible to *fragment*. The fragments should both contain 2-byte samples.

The time taken by this routine is proportional to `len (fragment)`.

findfit (*fragment*, *reference*)

Try to match *reference* as well as possible to a portion of *fragment* (which should be the longer fragment). This is (conceptually) done by taking slices out of *fragment*, using `findfactor()` to compute the best match, and minimizing the result. The fragments should both contain 2-byte samples. Return a tuple (*offset*, *factor*) where *offset* is the (integer) offset into *fragment* where the optimal match started and *factor* is the (floating-point) factor as per `findfactor()`.

findmax (*fragment*, *length*)

Search *fragment* for a slice of length *length* samples (not bytes!) with maximum energy, i.e., return *i* for which `rms (fragment [i*2:(i+length)*2])` is maximal. The fragments should both contain 2-byte samples.

The routine takes time proportional to `len (fragment)`.

getsample (*fragment*, *width*, *index*)

Return the value of sample *index* from the fragment.

lin2adpcm (*fragment*, *width*, *state*)

Convert samples to 4 bit Intel/DVI ADPCM encoding. ADPCM coding is an adaptive coding scheme, whereby each 4 bit number is the difference between one sample and the next, divided by a (varying) step. The Intel/DVI ADPCM algorithm has been selected for use by the IMA, so it may well become a standard.

state is a tuple containing the state of the coder. The coder returns a tuple (*adpcmfrag*, *newstate*), and the *newstate* should be passed to the next call of `lin2adpcm()`. In the initial call, `None` can be passed as the state. *adpcmfrag* is the ADPCM coded fragment packed 2 4-bit values per byte.

lin2alaw (*fragment*, *width*)

Convert samples in the audio fragment to a-LAW encoding and return this as a Python string. a-LAW is an audio encoding format whereby you get a dynamic range of about 13 bits using only 8 bit samples. It is used by the Sun audio hardware, among others. New in version 2.5.

lin2lin (*fragment*, *width*, *newwidth*)

Convert samples between 1-, 2- and 4-byte formats.

lin2ulaw (*fragment*, *width*)

Convert samples in the audio fragment to u-LAW encoding and return this as a Python string. u-LAW is an audio encoding format whereby you get a dynamic range of about 14 bits using only 8 bit samples. It is used by the Sun audio hardware, among others.

minmax (*fragment*, *width*)

Return a tuple consisting of the minimum and maximum values of all samples in the sound fragment.

max (*fragment*, *width*)

Return the maximum of the *absolute value* of all samples in a fragment.

maxpp (*fragment*, *width*)

Return the maximum peak-peak value in the sound fragment.

mul (*fragment*, *width*, *factor*)

Return a fragment that has all samples in the original fragment multiplied by the floating-point value *factor*. Overflow is silently ignored.

ratecv (*fragment*, *width*, *nchannels*, *inrate*, *outrate*, *state* [, *weightA* [, *weightB*]])

Convert the frame rate of the input fragment.

state is a tuple containing the state of the converter. The converter returns a tuple (*newfragment*, *newstate*), and *newstate* should be passed to the next call of `ratecv()`. The initial call should pass `None` as the state.

The *weightA* and *weightB* arguments are parameters for a simple digital filter and default to 1 and 0 respectively.

reverse (*fragment*, *width*)

Reverse the samples in a fragment and returns the modified fragment.

rms (*fragment*, *width*)

Return the root-mean-square of the fragment, i.e.

$$\sqrt{\frac{\sum S_i^2}{n}}$$

This is a measure of the power in an audio signal.

tomono (*fragment*, *width*, *lfactor*, *rfactor*)

Convert a stereo fragment to a mono fragment. The left channel is multiplied by *lfactor* and the right channel by *rfactor* before adding the two channels to give a mono signal.

tostereo (*fragment*, *width*, *lfactor*, *rfactor*)

Generate a stereo fragment from a mono fragment. Each pair of samples in the stereo fragment are computed from the mono sample, whereby left channel samples are multiplied by *lfactor* and right channel samples by *rfactor*.

ulaw2lin (*fragment*, *width*)

Convert sound fragments in u-LAW encoding to linearly encoded sound fragments. u-LAW encoding always uses 8 bits samples, so *width* refers only to the sample width of the output fragment here.

Note that operations such as `mul()` or `max()` make no distinction between mono and stereo fragments, i.e. all samples are treated equal. If this is a problem the stereo fragment should be split into two mono fragments first and recombined later. Here is an example of how to do that:

```
def mul_stereo(sample, width, lfactor, rfactor):
    lsample = audioop.tomono(sample, width, 1, 0)
    rsample = audioop.tomono(sample, width, 0, 1)
    lsample = audioop.mul(lsample, width, lfactor)
    rsample = audioop.mul(rsample, width, rfactor)
    lsample = audioop.tostereo(lsample, width, 1, 0)
    rsample = audioop.tostereo(rsample, width, 0, 1)
    return audioop.add(lsample, rsample, width)
```

If you use the ADPCM coder to build network packets and you want your protocol to be stateless (i.e. to be able to tolerate packet loss) you should not only transmit the data but also the state. Note that you should send the *initial* state (the one you passed to `lin2adpcm()`) along to the decoder, not the final state (as returned by the coder). If you want to use `struct.struct()` to store the state in binary you can code the first element (the predicted value) in 16 bits and the second (the delta index) in 8.

The ADPCM coders have never been tried against other ADPCM coders, only against themselves. It could well be that I misinterpreted the standards in which case they will not be interoperable with the respective standards.

The `find*()` routines might look a bit funny at first sight. They are primarily meant to do echo cancellation. A reasonably fast way to do this is to pick the most energetic piece of the output sample, locate that in the input sample and subtract the whole output sample from the input sample:

```
def echocancel(outputdata, inputdata):
    pos = audioop.findmax(outputdata, 800)      # one tenth second
    out_test = outputdata[pos*2:]
    in_test = inputdata[pos*2:]
    ipos, factor = audioop.findfit(in_test, out_test)
    # Optional (for better cancellation):
    # factor = audioop.findfactor(in_test[ipos*2:ipos*2+len(out_test)],
    #                             out_test)
    prefill = '\0'*(pos+ipos)*2
    postfill = '\0'*(len(inputdata)-len(prefill)-len(outputdata))
    outputdata = prefill + audioop.mul(outputdata,2,-factor) + postfill
    return audioop.add(inputdata, outputdata, 2)
```

19.2 imageop — Manipulate raw image data

The `imageop` module contains some useful operations on images. It operates on images consisting of 8 or 32 bit pixels stored in Python strings. This is the same format as used by `gl.rectwrite()` and the `imgfile` module.

The module defines the following variables and functions:

exception error

This exception is raised on all errors, such as unknown number of bits per pixel, etc.

crop (image, psize, width, height, x0, y0, x1, y1)

Return the selected part of *image*, which should be *width* by *height* in size and consist of pixels of *psize* bytes. *x0*, *y0*, *x1* and *y1* are like the `gl.rectread()` parameters, i.e. the boundary is included in the new image. The new boundaries need not be inside the picture. Pixels that fall outside the old image will have their value set to zero. If *x0* is bigger than *x1* the new image is mirrored. The same holds for the y coordinates.

scale (image, psize, width, height, newwidth, newheight)

Return *image* scaled to size *newwidth* by *newheight*. No interpolation is done, scaling is done by simple-minded pixel duplication or removal. Therefore, computer-generated images or dithered images will not look nice after scaling.

tovideo (image, psize, width, height)

Run a vertical low-pass filter over an image. It does so by computing each destination pixel as the average of two vertically-aligned source pixels. The main use of this routine is to forestall excessive flicker if the image is displayed on a video device that uses interlacing, hence the name.

grey2mono (image, width, height, threshold)

Convert a 8-bit deep greyscale image to a 1-bit deep image by thresholding all the pixels. The resulting image is tightly packed and is probably only useful as an argument to `mono2grey()`.

dither2mono (image, width, height)

Convert an 8-bit greyscale image to a 1-bit monochrome image using a (simple-minded) dithering algorithm.

mono2grey (image, width, height, p0, p1)

Convert a 1-bit monochrome image to an 8 bit greyscale or color image. All pixels that are zero-valued on input get value *p0* on output and all one-value input pixels get value *p1* on output. To convert a monochrome

black-and-white image to greyscale pass the values 0 and 255 respectively.

grey2grey4 (*image*, *width*, *height*)

Convert an 8-bit greyscale image to a 4-bit greyscale image without dithering.

grey2grey2 (*image*, *width*, *height*)

Convert an 8-bit greyscale image to a 2-bit greyscale image without dithering.

dither2grey2 (*image*, *width*, *height*)

Convert an 8-bit greyscale image to a 2-bit greyscale image with dithering. As for `dither2mono()`, the dithering algorithm is currently very simple.

grey42grey (*image*, *width*, *height*)

Convert a 4-bit greyscale image to an 8-bit greyscale image.

grey22grey (*image*, *width*, *height*)

Convert a 2-bit greyscale image to an 8-bit greyscale image.

backward_compatible

If set to 0, the functions in this module use a non-backward compatible way of representing multi-byte pixels on little-endian systems. The SGI for which this module was originally written is a big-endian system, so setting this variable will have no effect. However, the code wasn't originally intended to run on anything else, so it made assumptions about byte order which are not universal. Setting this variable to 0 will cause the byte order to be reversed on little-endian systems, so that it then is the same as on big-endian systems.

19.3 aifc — Read and write AIFF and AIFC files

This module provides support for reading and writing AIFF and AIFF-C files. AIFF is Audio Interchange File Format, a format for storing digital audio samples in a file. AIFF-C is a newer version of the format that includes the ability to compress the audio data.

Caveat: Some operations may only work under IRIX; these will raise `ImportError` when attempting to import the `cl` module, which is only available on IRIX.

Audio files have a number of parameters that describe the audio data. The sampling rate or frame rate is the number of times per second the sound is sampled. The number of channels indicate if the audio is mono, stereo, or quadro. Each frame consists of one sample per channel. The sample size is the size in bytes of each sample. Thus a frame consists of $nchannels * samplesize$ bytes, and a second's worth of audio consists of $nchannels * samplesize * framerate$ bytes.

For example, CD quality audio has a sample size of two bytes (16 bits), uses two channels (stereo) and has a frame rate of 44,100 frames/second. This gives a frame size of 4 bytes ($2 * 2$), and a second's worth occupies $2 * 2 * 44100$ bytes (176,400 bytes).

Module `aifc` defines the following function:

open (*file* [, *mode*])

Open an AIFF or AIFF-C file and return an object instance with methods that are described below. The argument *file* is either a string naming a file or a file object. *mode* must be `'r'` or `'rb'` when the file must be opened for reading, or `'w'` or `'wb'` when the file must be opened for writing. If omitted, *file.mode* is used if it exists, otherwise `'rb'` is used. When used for writing, the file object should be seekable, unless you know ahead of time how many samples you are going to write in total and use `writeframesraw()` and `setnframes()`.

Objects returned by `open()` when a file is opened for reading have the following methods:

getnchannels ()

Return the number of audio channels (1 for mono, 2 for stereo).

getsampwidth ()

Return the size in bytes of individual samples.

getframerate()
Return the sampling rate (number of audio frames per second).

getnframes()
Return the number of audio frames in the file.

getcomptype()
Return a four-character string describing the type of compression used in the audio file. For AIFF files, the returned value is 'NONE'.

getcompname()
Return a human-readable description of the type of compression used in the audio file. For AIFF files, the returned value is 'not compressed'.

getparams()
Return a tuple consisting of all of the above values in the above order.

getmarkers()
Return a list of markers in the audio file. A marker consists of a tuple of three elements. The first is the mark ID (an integer), the second is the mark position in frames from the beginning of the data (an integer), the third is the name of the mark (a string).

getmark(id)
Return the tuple as described in `getmarkers()` for the mark with the given *id*.

readframes(nframes)
Read and return the next *nframes* frames from the audio file. The returned data is a string containing for each frame the uncompressed samples of all channels.

rewind()
Rewind the read pointer. The next `readframes()` will start from the beginning.

setpos(pos)
Seek to the specified frame number.

tell()
Return the current frame number.

close()
Close the AIFF file. After calling this method, the object can no longer be used.

Objects returned by `open()` when a file is opened for writing have all the above methods, except for `readframes()` and `setpos()`. In addition the following methods exist. The `get*()` methods can only be called after the corresponding `set*()` methods have been called. Before the first `writeframes()` or `writeframesraw()`, all parameters except for the number of frames must be filled in.

aiff()
Create an AIFF file. The default is that an AIFF-C file is created, unless the name of the file ends in '.aiff' in which case the default is an AIFF file.

aifc()
Create an AIFF-C file. The default is that an AIFF-C file is created, unless the name of the file ends in '.aiff' in which case the default is an AIFF file.

setnchannels(nchannels)
Specify the number of channels in the audio file.

setsampwidth(width)
Specify the size in bytes of audio samples.

setframerate(rate)
Specify the sampling frequency in frames per second.

setnframes (*nframes*)

Specify the number of frames that are to be written to the audio file. If this parameter is not set, or not set correctly, the file needs to support seeking.

setcomptype (*type, name*)

Specify the compression type. If not specified, the audio data will not be compressed. In AIFF files, compression is not possible. The name parameter should be a human-readable description of the compression type, the type parameter should be a four-character string. Currently the following compression types are supported: NONE, ULAW, ALAW, G722.

setparams (*nchannels, sampwidth, framerate, comptype, compname*)

Set all the above parameters at once. The argument is a tuple consisting of the various parameters. This means that it is possible to use the result of a `getparams()` call as argument to `setparams()`.

setmark (*id, pos, name*)

Add a mark with the given id (larger than 0), and the given name at the given position. This method can be called at any time before `close()`.

tell ()

Return the current write position in the output file. Useful in combination with `setmark()`.

writeframes (*data*)

Write data to the output file. This method can only be called after the audio file parameters have been set.

writeframesraw (*data*)

Like `writeframes()`, except that the header of the audio file is not updated.

close ()

Close the AIFF file. The header of the file is updated to reflect the actual size of the audio data. After calling this method, the object can no longer be used.

19.4 sunau — Read and write Sun AU files

The `sunau` module provides a convenient interface to the Sun AU sound format. Note that this module is interface-compatible with the modules `aifc` and `wave`.

An audio file consists of a header followed by the data. The fields of the header are:

Field	Contents
magic word	The four bytes <code>'.snd'</code> .
header size	Size of the header, including info, in bytes.
data size	Physical size of the data, in bytes.
encoding	Indicates how the audio samples are encoded.
sample rate	The sampling rate.
# of channels	The number of channels in the samples.
info	ASCII string giving a description of the audio file (padded with null bytes).

Apart from the info field, all header fields are 4 bytes in size. They are all 32-bit unsigned integers encoded in big-endian byte order.

The `sunau` module defines the following functions:

open (*file, mode*)

If *file* is a string, open the file by that name, otherwise treat it as a seekable file-like object. *mode* can be any of

`'r'` Read only mode.

`'w'` Write only mode.

Note that it does not allow read/write files.

A *mode* of 'r' returns a `AU_read` object, while a *mode* of 'w' or 'wb' returns a `AU_write` object.

openfp (*file, mode*)

A synonym for `open`, maintained for backwards compatibility.

The `sunau` module defines the following exception:

exception Error

An error raised when something is impossible because of Sun AU specs or implementation deficiency.

The `sunau` module defines the following data items:

AUDIO_FILE_MAGIC

An integer every valid Sun AU file begins with, stored in big-endian form. This is the string '.snd' interpreted as an integer.

AUDIO_FILE_ENCODING_MULAW_8

AUDIO_FILE_ENCODING_LINEAR_8

AUDIO_FILE_ENCODING_LINEAR_16

AUDIO_FILE_ENCODING_LINEAR_24

AUDIO_FILE_ENCODING_LINEAR_32

AUDIO_FILE_ENCODING_ALAW_8

Values of the encoding field from the AU header which are supported by this module.

AUDIO_FILE_ENCODING_FLOAT

AUDIO_FILE_ENCODING_DOUBLE

AUDIO_FILE_ENCODING_ADPCM_G721

AUDIO_FILE_ENCODING_ADPCM_G722

AUDIO_FILE_ENCODING_ADPCM_G723_3

AUDIO_FILE_ENCODING_ADPCM_G723_5

Additional known values of the encoding field from the AU header, but which are not supported by this module.

19.4.1 AU_read Objects

`AU_read` objects, as returned by `open()` above, have the following methods:

close()

Close the stream, and make the instance unusable. (This is called automatically on deletion.)

getnchannels()

Returns number of audio channels (1 for mono, 2 for stereo).

getsampwidth()

Returns sample width in bytes.

getframerate()

Returns sampling frequency.

getnframes()

Returns number of audio frames.

getcomptype()

Returns compression type. Supported compression types are 'ULAW', 'ALAW' and 'NONE'.

getcompname()

Human-readable version of `getcomptype()`. The supported types have the respective names 'CCITT G.711 u-law', 'CCITT G.711 A-law' and 'not compressed'.

getparams()

Returns a tuple (*nchannels*, *sampwidth*, *framerate*, *nframes*, *comptype*, *compname*), equivalent to out-

put of the `get*()` methods.

readframes (*n*)

Reads and returns at most *n* frames of audio, as a string of bytes. The data will be returned in linear format. If the original data is in u-LAW format, it will be converted.

rewind ()

Rewind the file pointer to the beginning of the audio stream.

The following two methods define a term “position” which is compatible between them, and is otherwise implementation dependent.

setpos (*pos*)

Set the file pointer to the specified position. Only values returned from `tell()` should be used for *pos*.

tell ()

Return current file pointer position. Note that the returned value has nothing to do with the actual position in the file.

The following two functions are defined for compatibility with the `aifc`, and don’t do anything interesting.

getmarkers ()

Returns `None`.

getmark (*id*)

Raise an error.

19.4.2 AU_write Objects

AU_write objects, as returned by `open()` above, have the following methods:

setnchannels (*n*)

Set the number of channels.

setsampwidth (*n*)

Set the sample width (in bytes.)

setframerate (*n*)

Set the frame rate.

setnframes (*n*)

Set the number of frames. This can be later changed, when and if more frames are written.

setcomptype (*type, name*)

Set the compression type and description. Only ‘NONE’ and ‘ULAW’ are supported on output.

setparams (*tuple*)

The *tuple* should be (*nchannels, sampwidth, framerate, nframes, comptype, compname*), with values valid for the `set*()` methods. Set all parameters.

tell ()

Return current position in the file, with the same disclaimer for the `AU_read.tell()` and `AU_read.setpos()` methods.

writeframesraw (*data*)

Write audio frames, without correcting *nframes*.

writeframes (*data*)

Write audio frames and make sure *nframes* is correct.

close ()

Make sure *nframes* is correct, and close the file.

This method is called upon deletion.

Note that it is invalid to set any parameters after calling `writeframes()` or `writeframesraw()`.

19.5 wave — Read and write WAV files

The `wave` module provides a convenient interface to the WAV sound format. It does not support compression/decompression, but it does support mono/stereo.

The `wave` module defines the following function and exception:

open (*file* [, *mode*])

If *file* is a string, open the file by that name, other treat it as a seekable file-like object. *mode* can be any of

'r', 'rb' Read only mode.

'w', 'wb' Write only mode.

Note that it does not allow read/write WAV files.

A *mode* of 'r' or 'rb' returns a `Wave_read` object, while a *mode* of 'w' or 'wb' returns a `Wave_write` object. If *mode* is omitted and a file-like object is passed as *file*, *file.mode* is used as the default value for *mode* (the 'b' flag is still added if necessary).

openfp (*file*, *mode*)

A synonym for `open()`, maintained for backwards compatibility.

exception Error

An error raised when something is impossible because it violates the WAV specification or hits an implementation deficiency.

19.5.1 Wave_read Objects

`Wave_read` objects, as returned by `open()`, have the following methods:

close ()

Close the stream, and make the instance unusable. This is called automatically on object collection.

getnchannels ()

Returns number of audio channels (1 for mono, 2 for stereo).

getsampwidth ()

Returns sample width in bytes.

getframerate ()

Returns sampling frequency.

getnframes ()

Returns number of audio frames.

getcomptype ()

Returns compression type ('NONE' is the only supported type).

getcompname ()

Human-readable version of `getcomptype()`. Usually 'not compressed' parallels 'NONE'.

getparams ()

Returns a tuple (*nchannels*, *sampwidth*, *framerate*, *nframes*, *comptype*, *compname*), equivalent to output of the `get*()` methods.

readframes (*n*)
Reads and returns at most *n* frames of audio, as a string of bytes.

rewind ()
Rewind the file pointer to the beginning of the audio stream.

The following two methods are defined for compatibility with the `aifc` module, and don't do anything interesting.

getmarkers ()
Returns `None`.

getmark (*id*)
Raise an error.

The following two methods define a term “position” which is compatible between them, and is otherwise implementation dependent.

setpos (*pos*)
Set the file pointer to the specified position.

tell ()
Return current file pointer position.

19.5.2 Wave_write Objects

Wave_write objects, as returned by `open()`, have the following methods:

close ()
Make sure *nframes* is correct, and close the file. This method is called upon deletion.

setnchannels (*n*)
Set the number of channels.

setsampwidth (*n*)
Set the sample width to *n* bytes.

setframerate (*n*)
Set the frame rate to *n*.

setnframes (*n*)
Set the number of frames to *n*. This will be changed later if more frames are written.

setcomptype (*type*, *name*)
Set the compression type and description. At the moment, only compression type ‘NONE’ is supported, meaning no compression.

setparams (*tuple*)
The *tuple* should be (*nchannels*, *sampwidth*, *framerate*, *nframes*, *comptype*, *compname*), with values valid for the `set*()` methods. Sets all parameters.

tell ()
Return current position in the file, with the same disclaimer for the `Wave_read.tell()` and `Wave_read.setpos()` methods.

writeframesraw (*data*)
Write audio frames, without correcting *nframes*.

writeframes (*data*)
Write audio frames and make sure *nframes* is correct.

Note that it is invalid to set any parameters after calling `writeframes()` or `writeframesraw()`, and any attempt to do so will raise `wave.Error`.

19.6 chunk — Read IFF chunked data

This module provides an interface for reading files that use EA IFF 85 chunks.¹ This format is used in at least the Audio Interchange File Format (AIFF/AIFF-C) and the Real Media File Format (RMFF). The WAVE audio file format is closely related and can also be read using this module.

A chunk has the following structure:

Offset	Length	Contents
0	4	Chunk ID
4	4	Size of chunk in big-endian byte order, not including the header
8	<i>n</i>	Data bytes, where <i>n</i> is the size given in the preceding field
8 + <i>n</i>	0 or 1	Pad byte needed if <i>n</i> is odd and chunk alignment is used

The ID is a 4-byte string which identifies the type of chunk.

The size field (a 32-bit value, encoded using big-endian byte order) gives the size of the chunk data, not including the 8-byte header.

Usually an IFF-type file consists of one or more chunks. The proposed usage of the `Chunk` class defined here is to instantiate an instance at the start of each chunk and read from the instance until it reaches the end, after which a new instance can be instantiated. At the end of the file, creating a new instance will fail with a `EOFError` exception.

class `Chunk` (*file* [, *align*, *bigendian*, *inclheader*])

Class which represents a chunk. The *file* argument is expected to be a file-like object. An instance of this class is specifically allowed. The only method that is needed is `read()`. If the methods `seek()` and `tell()` are present and don't raise an exception, they are also used. If these methods are present and raise an exception, they are expected to not have altered the object. If the optional argument *align* is true, chunks are assumed to be aligned on 2-byte boundaries. If *align* is false, no alignment is assumed. The default value is true. If the optional argument *bigendian* is false, the chunk size is assumed to be in little-endian order. This is needed for WAVE audio files. The default value is true. If the optional argument *inclheader* is true, the size given in the chunk header includes the size of the header. The default value is false.

A `Chunk` object supports the following methods:

`getname()`

Returns the name (ID) of the chunk. This is the first 4 bytes of the chunk.

`getsize()`

Returns the size of the chunk.

`close()`

Close and skip to the end of the chunk. This does not close the underlying file.

The remaining methods will raise `IOError` if called after the `close()` method has been called.

`isatty()`

Returns `False`.

`seek(pos` [, *whence*])

Set the chunk's current position. The *whence* argument is optional and defaults to 0 (absolute file positioning); other values are 1 (seek relative to the current position) and 2 (seek relative to the file's end). There is no return value. If the underlying file does not allow seek, only forward seeks are allowed.

`tell()`

Return the current position into the chunk.

`read([size])`

Read at most *size* bytes from the chunk (less if the read hits the end of the chunk before obtaining *size* bytes).

¹“EA IFF 85” Standard for Interchange Format Files, Jerry Morrison, Electronic Arts, January 1985.

If the *size* argument is negative or omitted, read all data until the end of the chunk. The bytes are returned as a string object. An empty string is returned when the end of the chunk is encountered immediately.

skip()

Skip to the end of the chunk. All further calls to `read()` for the chunk will return `''`. If you are not interested in the contents of the chunk, this method should be called so that the file points to the start of the next chunk.

19.7 colorsys — Conversions between color systems

The `colorsys` module defines bidirectional conversions of color values between colors expressed in the RGB (Red Green Blue) color space used in computer monitors and three other coordinate systems: YIQ, HLS (Hue Lightness Saturation) and HSV (Hue Saturation Value). Coordinates in all of these color spaces are floating point values. In the YIQ space, the Y coordinate is between 0 and 1, but the I and Q coordinates can be positive or negative. In all other spaces, the coordinates are all between 0 and 1.

More information about color spaces can be found at <http://www.poynton.com/ColorFAQ.html>.

The `colorsys` module defines the following functions:

rgb_to_yiq(*r, g, b*)

Convert the color from RGB coordinates to YIQ coordinates.

yiq_to_rgb(*y, i, q*)

Convert the color from YIQ coordinates to RGB coordinates.

rgb_to_hls(*r, g, b*)

Convert the color from RGB coordinates to HLS coordinates.

hls_to_rgb(*h, l, s*)

Convert the color from HLS coordinates to RGB coordinates.

rgb_to_hsv(*r, g, b*)

Convert the color from RGB coordinates to HSV coordinates.

hsv_to_rgb(*h, s, v*)

Convert the color from HSV coordinates to RGB coordinates.

Example:

```
>>> import colorsys
>>> colorsys.rgb_to_hsv(.3, .4, .2)
(0.25, 0.5, 0.4)
>>> colorsys.hsv_to_rgb(0.25, 0.5, 0.4)
(0.3, 0.4, 0.2)
```

19.8 rgbimg — Read and write “SGI RGB” files

Deprecated since release 2.5. This module is not maintained anymore and seems to be unused.

The `rgbimg` module allows Python programs to access SGI `imglib` image files (also known as ‘`rgb`’ files). The module is far from complete, but is provided anyway since the functionality that there is enough in some cases. Currently, colormap files are not supported.

Note: This module is only built by default for 32-bit platforms; it is not expected to work properly on other systems.

The module defines the following variables and functions:

exception error

This exception is raised on all errors, such as unsupported file type, etc.

sizeofimage (file)

This function returns a tuple (x, y) where x and y are the size of the image in pixels. Only 4 byte RGBA pixels, 3 byte RGB pixels, and 1 byte greyscale pixels are currently supported.

longimagedata (file)

This function reads and decodes the image on the specified file, and returns it as a Python string. The string has 4 byte RGBA pixels. The bottom left pixel is the first in the string. This format is suitable to pass to `gl.glrectwrite()`, for instance.

longstoimage (data, x, y, z, file)

This function writes the RGBA data in *data* to image file *file*. x and y give the size of the image. z is 1 if the saved image should be 1 byte greyscale, 3 if the saved image should be 3 byte RGB data, or 4 if the saved images should be 4 byte RGBA data. The input data always contains 4 bytes per pixel. These are the formats returned by `gl.glrectread()`.

ttob (flag)

This function sets a global flag which defines whether the scan lines of the image are read or written from bottom to top (flag is zero, compatible with SGI GL) or from top to bottom (flag is one, compatible with X). The default is zero.

19.9 imghdr — Determine the type of an image

The `imghdr` module determines the type of image contained in a file or byte stream.

The `imghdr` module defines the following function:

what (filename[, h])

Tests the image data contained in the file named by *filename*, and returns a string describing the image type. If optional h is provided, the *filename* is ignored and h is assumed to contain the byte stream to test.

The following image types are recognized, as listed below with the return value from `what()`:

Value	Image format
'rgb'	SGI ImgLib Files
'gif'	GIF 87a and 89a Files
'pbm'	Portable Bitmap Files
'pgm'	Portable Graymap Files
'ppm'	Portable Pixmap Files
'tiff'	TIFF Files
'rast'	Sun Raster Files
'xbm'	X Bitmap Files
'jpeg'	JPEG data in JFIF or Exif formats
'bmp'	BMP files
'png'	Portable Network Graphics

New in version 2.5: Exif detection.

You can extend the list of file types `imghdr` can recognize by appending to this variable:

tests

A list of functions performing the individual tests. Each function takes two arguments: the byte-stream and an open file-like object. When `what()` is called with a byte-stream, the file-like object will be `None`.

The test function should return a string describing the image type if the test succeeded, or `None` if it failed.

Example:

```
>>> import imghdr
>>> imghdr.what('/tmp/bass.gif')
'gif'
```

19.10 sndhdr — Determine type of sound file

The `sndhdr` provides utility functions which attempt to determine the type of sound data which is in a file. When these functions are able to determine what type of sound data is stored in a file, they return a tuple (*type*, *sampling_rate*, *channels*, *frames*, *bits_per_sample*). The value for *type* indicates the data type and will be one of the strings 'aifc', 'aiff', 'au', 'hcom', 'sndr', 'sndt', 'voc', 'wav', '8svx', 'sb', 'ub', or 'ul'. The *sampling_rate* will be either the actual value or 0 if unknown or difficult to decode. Similarly, *channels* will be either the number of channels or 0 if it cannot be determined or if the value is difficult to decode. The value for *frames* will be either the number of frames or -1. The last item in the tuple, *bits_per_sample*, will either be the sample size in bits or 'A' for A-LAW or 'U' for u-LAW.

what (*filename*)

Determines the type of sound data stored in the file *filename* using `whathdr()`. If it succeeds, returns a tuple as described above, otherwise `None` is returned.

whathdr (*filename*)

Determines the type of sound data stored in a file based on the file header. The name of the file is given by *filename*. This function returns a tuple as described above on success, or `None`.

19.11 ossaudiodev — Access to OSS-compatible audio devices

New in version 2.3.

This module allows you to access the OSS (Open Sound System) audio interface. OSS is available for a wide range of open-source and commercial Unices, and is the standard audio interface for Linux and recent versions of FreeBSD.

See Also:

Open Sound System Programmer's Guide

(<http://www.opensound.com/pguide/oss.pdf>)

the official documentation for the OSS C API

The module defines a large number of constants supplied by the OSS device driver; see `<sys/soundcard.h>` on either Linux or FreeBSD for a listing.

`ossaudiodev` defines the following variables and functions:

exception OSSAudioError

This exception is raised on certain errors. The argument is a string describing what went wrong.

(If `ossaudiodev` receives an error from a system call such as `open()`, `write()`, or `ioctl()`, it raises `IOError`. Errors detected directly by `ossaudiodev` result in `OSSAudioError`.)

(For backwards compatibility, the exception class is also available as `ossaudiodev.error`.)

open ([*device*,]*mode*)

Open an audio device and return an OSS audio device object. This object supports many file-like methods, such as `read()`, `write()`, and `fileno()` (although there are subtle differences between conventional UNIX

read/write semantics and those of OSS audio devices). It also supports a number of audio-specific methods; see below for the complete list of methods.

device is the audio device filename to use. If it is not specified, this module first looks in the environment variable `AUDIODEV` for a device to use. If not found, it falls back to `/dev/dsp`.

mode is one of `'r'` for read-only (record) access, `'w'` for write-only (playback) access and `'rw'` for both. Since many sound cards only allow one process to have the recorder or player open at a time, it is a good idea to open the device only for the activity needed. Further, some sound cards are half-duplex: they can be opened for reading or writing, but not both at once.

Note the unusual calling syntax: the *first* argument is optional, and the second is required. This is a historical artifact for compatibility with the older `linuxaudiodev` module which `ossaudiodev` supersedes.

openmixer ([*device*])

Open a mixer device and return an OSS mixer device object. *device* is the mixer device filename to use. If it is not specified, this module first looks in the environment variable `MIXERDEV` for a device to use. If not found, it falls back to `/dev/mixer`.

19.11.1 Audio Device Objects

Before you can write to or read from an audio device, you must call three methods in the correct order:

1. `setfmt()` to set the output format
2. `channels()` to set the number of channels
3. `speed()` to set the sample rate

Alternately, you can use the `setparameters()` method to set all three audio parameters at once. This is more convenient, but may not be as flexible in all cases.

The audio device objects returned by `open()` define the following methods and (read-only) attributes:

close()

Explicitly close the audio device. When you are done writing to or reading from an audio device, you should explicitly close it. A closed device cannot be used again.

fileno()

Return the file descriptor associated with the device.

read(*size*)

Read *size* bytes from the audio input and return them as a Python string. Unlike most UNIX device drivers, OSS audio devices in blocking mode (the default) will block `read()` until the entire requested amount of data is available.

write(*data*)

Write the Python string *data* to the audio device and return the number of bytes written. If the audio device is in blocking mode (the default), the entire string is always written (again, this is different from usual UNIX device semantics). If the device is in non-blocking mode, some data may not be written—see `writeall()`.

writeall(*data*)

Write the entire Python string *data* to the audio device: waits until the audio device is able to accept data, writes as much data as it will accept, and repeats until *data* has been completely written. If the device is in blocking mode (the default), this has the same effect as `write()`; `writeall()` is only useful in non-blocking mode. Has no return value, since the amount of data written is always equal to the amount of data supplied.

The following methods each map to exactly one `ioctl()` system call. The correspondence is obvious: for example, `setfmt()` corresponds to the `SNDCTL_DSP_SETFMT` `ioctl`, and `sync()` to `SNDCTL_DSP_SYNC` (this can be useful when consulting the OSS documentation). If the underlying `ioctl()` fails, they all raise `IOError`.

nonblock()

Put the device into non-blocking mode. Once in non-blocking mode, there is no way to return it to blocking mode.

getfmts()

Return a bitmask of the audio output formats supported by the soundcard. Some of the formats supported by OSS are:

Format	Description
AFMT_MU_LAW	a logarithmic encoding (used by Sun .au files and /dev/audio)
AFMT_A_LAW	a logarithmic encoding
AFMT_IMA_ADPCM	a 4:1 compressed format defined by the Interactive Multimedia Association
AFMT_U8	Unsigned, 8-bit audio
AFMT_S16_LE	Signed, 16-bit audio, little-endian byte order (as used by Intel processors)
AFMT_S16_BE	Signed, 16-bit audio, big-endian byte order (as used by 68k, PowerPC, Sparc)
AFMT_S8	Signed, 8 bit audio
AFMT_U16_LE	Unsigned, 16-bit little-endian audio
AFMT_U16_BE	Unsigned, 16-bit big-endian audio

Consult the OSS documentation for a full list of audio formats, and note that most devices support only a subset of these formats. Some older devices only support AFMT_U8; the most common format used today is AFMT_S16_LE.

setfmt(format)

Try to set the current audio format to *format*—see `getfmts()` for a list. Returns the audio format that the device was set to, which may not be the requested format. May also be used to return the current audio format—do this by passing an “audio format” of AFMT_QUERY.

channels(nchannels)

Set the number of output channels to *nchannels*. A value of 1 indicates monophonic sound, 2 stereophonic. Some devices may have more than 2 channels, and some high-end devices may not support mono. Returns the number of channels the device was set to.

speed(samplerate)

Try to set the audio sampling rate to *samplerate* samples per second. Returns the rate actually set. Most sound devices don’t support arbitrary sampling rates. Common rates are:

Rate	Description
8000	default rate for /dev/audio
11025	speech recording
22050	
44100	CD quality audio (at 16 bits/sample and 2 channels)
96000	DVD quality audio (at 24 bits/sample)

sync()

Wait until the sound device has played every byte in its buffer. (This happens implicitly when the device is closed.) The OSS documentation recommends closing and re-opening the device rather than using `sync()`.

reset()

Immediately stop playing or recording and return the device to a state where it can accept commands. The OSS documentation recommends closing and re-opening the device after calling `reset()`.

post()

Tell the driver that there is likely to be a pause in the output, making it possible for the device to handle the pause more intelligently. You might use this after playing a spot sound effect, before waiting for user input, or before doing disk I/O.

The following convenience methods combine several `ioctl`s, or one `ioctl` and some simple calculations.

setparameters(format, nchannels, samplerate [, strict=False])

Set the key audio sampling parameters—sample format, number of channels, and sampling rate—in one

method call. *format*, *nchannels*, and *samplerate* should be as specified in the `setfmt()`, `channels()`, and `speed()` methods. If *strict* is true, `setparameters()` checks to see if each parameter was actually set to the requested value, and raises `OSSAudioError` if not. Returns a tuple (*format*, *nchannels*, *samplerate*) indicating the parameter values that were actually set by the device driver (i.e., the same as the return values of `setfmt()`, `channels()`, and `speed()`).

For example,

```
(fmt, channels, rate) = dsp.setparameters(fmt, channels, rate)
```

is equivalent to

```
fmt = dsp.setfmt(fmt)
channels = dsp.channels(channels)
rate = dsp.rate(channels)
```

bufsize()

Returns the size of the hardware buffer, in samples.

obufcount()

Returns the number of samples that are in the hardware buffer yet to be played.

obuffree()

Returns the number of samples that could be queued into the hardware buffer to be played without blocking.

Audio device objects also support several read-only attributes:

closed

Boolean indicating whether the device has been closed.

name

String containing the name of the device file.

mode

The I/O mode for the file, either "r", "rw", or "w".

19.11.2 Mixer Device Objects

The mixer object provides two file-like methods:

close()

This method closes the open mixer device file. Any further attempts to use the mixer after this file is closed will raise an `IOError`.

fileno()

Returns the file handle number of the open mixer device file.

The remaining methods are specific to audio mixing:

controls()

This method returns a bitmask specifying the available mixer controls ("Control" being a specific mixable "channel", such as `SOUND_MIXER_PCM` or `SOUND_MIXER_SYNTH`). This bitmask indicates a subset of all available mixer controls—the `SOUND_MIXER_*` constants defined at module level. To determine if, for example, the current mixer object supports a PCM mixer, use the following Python code:

```
mixer=ossaudiodev.openmixer()
if mixer.controls() & (1 << ossaudiodev.SOUND_MIXER_PCM):
    # PCM is supported
    ... code ...
```

For most purposes, the `SOUND_MIXER_VOLUME` (master volume) and `SOUND_MIXER_PCM` controls should suffice—but code that uses the mixer should be flexible when it comes to choosing mixer controls. On the Gravis Ultrasound, for example, `SOUND_MIXER_VOLUME` does not exist.

`stereocontrols()`

Returns a bitmask indicating stereo mixer controls. If a bit is set, the corresponding control is stereo; if it is unset, the control is either monophonic or not supported by the mixer (use in combination with `controls()` to determine which).

See the code example for the `controls()` function for an example of getting data from a bitmask.

`recontrols()`

Returns a bitmask specifying the mixer controls that may be used to record. See the code example for `controls()` for an example of reading from a bitmask.

`get(control)`

Returns the volume of a given mixer control. The returned volume is a 2-tuple (`left_volume`, `right_volume`). Volumes are specified as numbers from 0 (silent) to 100 (full volume). If the control is monophonic, a 2-tuple is still returned, but both volumes are the same.

Raises `OSSAudioError` if an invalid control was specified, or `IOError` if an unsupported control is specified.

`set(control, (left, right))`

Sets the volume for a given mixer control to (`left`, `right`). `left` and `right` must be ints and between 0 (silent) and 100 (full volume). On success, the new volume is returned as a 2-tuple. Note that this may not be exactly the same as the volume specified, because of the limited resolution of some soundcard's mixers.

Raises `OSSAudioError` if an invalid mixer control was specified, or if the specified volumes were out-of-range.

`get_recsrc()`

This method returns a bitmask indicating which control(s) are currently being used as a recording source.

`set_recsrc(bitmask)`

Call this function to specify a recording source. Returns a bitmask indicating the new recording source (or sources) if successful; raises `IOError` if an invalid source was specified. To set the current recording source to the microphone input:

```
mixer.setrecsrc (1 << ossaudiodev.SOUND_MIXER_MIC)
```


Graphical User Interfaces with Tk

Tk/Tcl has long been an integral part of Python. It provides a robust and platform independent windowing toolkit, that is available to Python programmers using the `Tkinter` module, and its extension, the `Tix` module.

The `Tkinter` module is a thin object-oriented layer on top of Tcl/Tk. To use `Tkinter`, you don't need to write Tcl code, but you will need to consult the Tk documentation, and occasionally the Tcl documentation. `Tkinter` is a set of wrappers that implement the Tk widgets as Python classes. In addition, the internal module `_tkinter` provides a threadsafe mechanism which allows Python and Tcl to interact.

Tk is not the only GUI for Python; see section 20.6, “Other User Interface Modules and Packages,” for more information on other GUI toolkits for Python.

Tkinter	Interface to Tcl/Tk for graphical user interfaces
Tix	Tk Extension Widgets for Tkinter
ScrolledText	Text widget with a vertical scroll bar.
turtle	An environment for turtle graphics.

20.1 Tkinter — Python interface to Tcl/Tk

The `Tkinter` module (“Tk interface”) is the standard Python interface to the Tk GUI toolkit. Both Tk and `Tkinter` are available on most UNIX platforms, as well as on Windows and Macintosh systems. (Tk itself is not part of Python; it is maintained at ActiveState.)

See Also:

Python Tkinter Resources

(<http://www.python.org/topics/tkinter/>)

The Python Tkinter Topic Guide provides a great deal of information on using Tk from Python and links to other sources of information on Tk.

An Introduction to Tkinter

(<http://www.pythonware.com/library/an-introduction-to-tkinter.htm>)

Fredrik Lundh's on-line reference material.

Tkinter reference: a GUI for Python

(<http://www.nmt.edu/tcc/help/pubs/lang.html>)

On-line reference material.

Tkinter for JPython

(<http://jtkinter.sourceforge.net>)

The Jython interface to Tkinter.

Python and Tkinter Programming

(<http://www.amazon.com/exec/obidos/ASIN/1884777813>)

20.1.1 Tkinter Modules

Most of the time, the `Tkinter` module is all you really need, but a number of additional modules are available as well. The Tk interface is located in a binary module named `_tkinter`. This module contains the low-level interface to Tk, and should never be used directly by application programmers. It is usually a shared library (or DLL), but might in some cases be statically linked with the Python interpreter.

In addition to the Tk interface module, `Tkinter` includes a number of Python modules. The two most important modules are the `Tkinter` module itself, and a module called `Tkconstants`. The former automatically imports the latter, so to use Tkinter, all you need to do is to import one module:

```
import Tkinter
```

Or, more often:

```
from Tkinter import *
```

class Tk (*screenName=None, baseName=None, className='Tk', useTk=1*)

The Tk class is instantiated without arguments. This creates a toplevel widget of Tk which usually is the main window of an application. Each instance has its own associated Tcl interpreter. Changed in version 2.4: The *useTk* parameter was added.

Tcl (*screenName=None, baseName=None, className='Tk', useTk=0*)

The Tcl function is a factory function which creates an object much like that created by the Tk class, except that it does not initialize the Tk subsystem. This is most often useful when driving the Tcl interpreter in an environment where one doesn't want to create extraneous toplevel windows, or where one cannot (such as UNIX/Linux systems without an X server). An object created by the Tcl object can have a Toplevel window created (and the Tk subsystem initialized) by calling its `loadtk` method. New in version 2.4.

Other modules that provide Tk support include:

ScrolledText Text widget with a vertical scroll bar built in.

tkColorChooser Dialog to let the user choose a color.

tkCommonDialog Base class for the dialogs defined in the other modules listed here.

tkFileDialog Common dialogs to allow the user to specify a file to open or save.

tkFont Utilities to help work with fonts.

tkMessageBox Access to standard Tk dialog boxes.

tkSimpleDialog Basic dialogs and convenience functions.

Tkdnd Drag-and-drop support for `Tkinter`. This is experimental and should become deprecated when it is replaced with the Tk DND.

turtle Turtle graphics in a Tk window.

20.1.2 Tkinter Life Preserver

This section is not designed to be an exhaustive tutorial on either Tk or Tkinter. Rather, it is intended as a stop gap, providing some introductory orientation on the system.

Credits:

- Tkinter was written by Steen Lumholt and Guido van Rossum.
- Tk was written by John Ousterhout while at Berkeley.
- This Life Preserver was written by Matt Conway at the University of Virginia.
- The html rendering, and some liberal editing, was produced from a FrameMaker version by Ken Manheimer.
- Fredrik Lundh elaborated and revised the class interface descriptions, to get them current with Tk 4.2.
- Mike Clarkson converted the documentation to \LaTeX , and compiled the User Interface chapter of the reference manual.

How To Use This Section

This section is designed in two parts: the first half (roughly) covers background material, while the second half can be taken to the keyboard as a handy reference.

When trying to answer questions of the form “how do I do blah”, it is often best to find out how to do “blah” in straight Tk, and then convert this back into the corresponding `Tkinter` call. Python programmers can often guess at the correct Python command by looking at the Tk documentation. This means that in order to use Tkinter, you will have to know a little bit about Tk. This document can’t fulfill that role, so the best we can do is point you to the best documentation that exists. Here are some hints:

- The authors strongly suggest getting a copy of the Tk man pages. Specifically, the man pages in the `man` directory are most useful. The `man3` man pages describe the C interface to the Tk library and thus are not especially helpful for script writers.
- Addison-Wesley publishes a book called *Tcl and the Tk Toolkit* by John Ousterhout (ISBN 0-201-63337-X) which is a good introduction to Tcl and Tk for the novice. The book is not exhaustive, and for many details it defers to the man pages.
- ‘Tkinter.py’ is a last resort for most, but can be a good place to go when nothing else makes sense.

See Also:

ActiveState Tcl Home Page

(<http://tcl.activestate.com/>)

The Tk/Tcl development is largely taking place at ActiveState.

Tcl and the Tk Toolkit

(<http://www.amazon.com/exec/obidos/ASIN/020163337X>)

The book by John Ousterhout, the inventor of Tcl.

Practical Programming in Tcl and Tk

(<http://www.amazon.com/exec/obidos/ASIN/0130220280>)

Brent Welch’s encyclopedic book.

A Simple Hello World Program

```
from Tkinter import *

class Application(Frame):
    def say_hi(self):
        print "hi there, everyone!"

    def createWidgets(self):
        self.QUIT = Button(self)
        self.QUIT["text"] = "QUIT"
        self.QUIT["fg"] = "red"
        self.QUIT["command"] = self.quit

        self.QUIT.pack({"side": "left"})

        self.hi_there = Button(self)
        self.hi_there["text"] = "Hello",
        self.hi_there["command"] = self.say_hi

        self.hi_there.pack({"side": "left"})

    def __init__(self, master=None):
        Frame.__init__(self, master)
        self.pack()
        self.createWidgets()

root = Tk()
app = Application(master=root)
app.mainloop()
root.destroy()
```

20.1.3 A (Very) Quick Look at Tcl/Tk

The class hierarchy looks complicated, but in actual practice, application programmers almost always refer to the classes at the very bottom of the hierarchy.

Notes:

- These classes are provided for the purposes of organizing certain functions under one namespace. They aren't meant to be instantiated independently.
- The `Tk` class is meant to be instantiated only once in an application. Application programmers need not instantiate one explicitly, the system creates one whenever any of the other classes are instantiated.
- The `Widget` class is not meant to be instantiated, it is meant only for subclassing to make "real" widgets (in C++, this is called an 'abstract class').

To make use of this reference material, there will be times when you will need to know how to read short passages of Tk and how to identify the various parts of a Tk command. (See section 20.1.4 for the `Tkinter` equivalents of what's below.)

Tk scripts are Tcl programs. Like all Tcl programs, Tk scripts are just lists of tokens separated by spaces. A Tk widget is just its *class*, the *options* that help configure it, and the *actions* that make it do useful things.

To make a widget in Tk, the command is always of the form:


```
classCommand newPathname options
```

classCommand denotes which kind of widget to make (a button, a label, a menu...)

newPathname is the new name for this widget. All names in Tk must be unique. To help enforce this, widgets in Tk are named with *pathnames*, just like files in a file system. The top level widget, the *root*, is called `.` (period) and children are delimited by more periods. For example, `.myApp.controlPanel.okButton` might be the name of a widget.

options configure the widget's appearance and in some cases, its behavior. The options come in the form of a list of flags and values. Flags are preceded by a '-', like UNIX shell command flags, and values are put in quotes if they are more than one word.

For example:

button	.fred	-fg red -text "hi there"
^	^	└──────────────────┘
class	new	options
command	widget	(-opt val -opt val ...)

Once created, the pathname to the widget becomes a new command. This new *widget command* is the programmer's handle for getting the new widget to perform some *action*. In C, you'd express this as `someAction(fred, someOptions)`, in C++, you would express this as `fred.someAction(someOptions)`, and in Tk, you say:

```
.fred someAction someOptions
```

Note that the object name, `.fred`, starts with a dot.

As you'd expect, the legal values for *someAction* will depend on the widget's class: `.fred disable` works if fred is a button (fred gets greyed out), but does not work if fred is a label (disabling of labels is not supported in Tk).

The legal values of *someOptions* is action dependent. Some actions, like `disable`, require no arguments, others, like a text-entry box's `delete` command, would need arguments to specify what range of text to delete.

20.1.4 Mapping Basic Tk into Tkinter

Class commands in Tk correspond to class constructors in Tkinter.

button .fred	=====>	fred = Button()
--------------	--------	-----------------

The master of an object is implicit in the new name given to it at creation time. In Tkinter, masters are specified explicitly.

button .panel.fred	=====>	fred = Button(panel)
--------------------	--------	----------------------

The configuration options in Tk are given in lists of hyphenated tags followed by values. In Tkinter, options are specified

as keyword-arguments in the instance constructor, and keyword-args for configure calls or as instance indices, in dictionary style, for established instances. See section 20.1.6 on setting options.

```
button .fred -fg red          =====> fred = Button(panel, fg = "red")
.fred configure -fg red      =====> fred["fg"] = red
OR ==> fred.config(fg = "red")
```

In Tk, to perform an action on a widget, use the widget name as a command, and follow it with an action name, possibly with arguments (options). In Tkinter, you call methods on the class instance to invoke actions on the widget. The actions (methods) that a given widget can perform are listed in the Tkinter.py module.

```
.fred invoke                  =====> fred.invoke()
```

To give a widget to the packer (geometry manager), you call pack with optional arguments. In Tkinter, the Pack class holds all this functionality, and the various forms of the pack command are implemented as methods. All widgets in Tkinter are subclassed from the Packer, and so inherit all the packing methods. See the Tix module documentation for additional information on the Form geometry manager.

```
pack .fred -side left        =====> fred.pack(side = "left")
```

20.1.5 How Tk and Tkinter are Related

Note: This was derived from a graphical image; the image will be used more directly in a subsequent version of this document.

From the top down:

Your App Here (Python) A Python application makes a Tkinter call.

Tkinter (Python Module) This call (say, for example, creating a button widget), is implemented in the *Tkinter* module, which is written in Python. This Python function will parse the commands and the arguments and convert them into a form that makes them look as if they had come from a Tk script instead of a Python script.

tkinter (C) These commands and their arguments will be passed to a C function in the *tkinter* - note the lowercase - extension module.

Tk Widgets (C and Tcl) This C function is able to make calls into other C modules, including the C functions that make up the Tk library. Tk is implemented in C and some Tcl. The Tcl part of the Tk widgets is used to bind certain default behaviors to widgets, and is executed once at the point where the Python Tkinter module is imported. (The user never sees this stage).

Tk (C) The Tk part of the Tk Widgets implement the final mapping to ...

Xlib (C) the Xlib library to draw graphics on the screen.

20.1.6 Handy Reference

Setting Options

Options control things like the color and border width of a widget. Options can be set in three ways:

At object creation time, using keyword arguments :

```
fred = Button(self, fg = "red", bg = "blue")
```

After object creation, treating the option name like a dictionary index :

```
fred["fg"] = "red"  
fred["bg"] = "blue"
```

Use the `config()` method to update multiple attrs subsequent to object creation :

```
fred.config(fg = "red", bg = "blue")
```

For a complete explanation of a given option and its behavior, see the Tk man pages for the widget in question.

Note that the man pages list "STANDARD OPTIONS" and "WIDGET SPECIFIC OPTIONS" for each widget. The former is a list of options that are common to many widgets, the latter are the options that are idiosyncratic to that particular widget. The Standard Options are documented on the *options(3)* man page.

No distinction between standard and widget-specific options is made in this document. Some options don't apply to some kinds of widgets. Whether a given widget responds to a particular option depends on the class of the widget; buttons have a `command` option, labels do not.

The options supported by a given widget are listed in that widget's man page, or can be queried at runtime by calling the `config()` method without arguments, or by calling the `keys()` method on that widget. The return value of these calls is a dictionary whose key is the name of the option as a string (for example, `'relief'`) and whose values are 5-tuples.

Some options, like `bg` are synonyms for common options with long names (`bg` is shorthand for "background"). Passing the `config()` method the name of a shorthand option will return a 2-tuple, not 5-tuple. The 2-tuple passed back will contain the name of the synonym and the "real" option (such as `('bg', 'background')`).

Index	Meaning	Example
0	option name	<code>'relief'</code>
1	option name for database lookup	<code>'relief'</code>
2	option class for database lookup	<code>'Relief'</code>
3	default value	<code>'raised'</code>
4	current value	<code>'groove'</code>

Example:

```
>>> print fred.config()  
{ 'relief' : ('relief', 'relief', 'Relief', 'raised', 'groove') }
```

Of course, the dictionary printed will include all the options available and their values. This is meant only as an example.

The Packer

The packer is one of Tk's geometry-management mechanisms.

Geometry managers are used to specify the relative positioning of the positioning of widgets within their container - their mutual *master*. In contrast to the more cumbersome *placer* (which is used less commonly, and we do not cover here), the packer takes qualitative relationship specification - *above*, *to the left of*, *filling*, etc - and works everything out to determine the exact placement coordinates for you.

The size of any *master* widget is determined by the size of the "slave widgets" inside. The packer is used to control where slave widgets appear inside the master into which they are packed. You can pack widgets into frames, and frames into other frames, in order to achieve the kind of layout you desire. Additionally, the arrangement is dynamically adjusted to accommodate incremental changes to the configuration, once it is packed.

Note that widgets do not appear until they have had their geometry specified with a geometry manager. It's a common early mistake to leave out the geometry specification, and then be surprised when the widget is created but nothing appears. A widget will appear only after it has had, for example, the packer's `pack()` method applied to it.

The `pack()` method can be called with keyword-option/value pairs that control where the widget is to appear within its container, and how it is to behave when the main application window is resized. Here are some examples:

```
fred.pack()                # defaults to side = "top"
fred.pack(side = "left")
fred.pack(expand = 1)
```

Packer Options

For more extensive information on the packer and the options that it can take, see the man pages and page 183 of John Ousterhout's book.

anchor Anchor type. Denotes where the packer is to place each slave in its parcel.

expand Boolean, 0 or 1.

fill Legal values: 'x', 'y', 'both', 'none'.

ipadx and ipady A distance - designating internal padding on each side of the slave widget.

padx and pady A distance - designating external padding on each side of the slave widget.

side Legal values are: 'left', 'right', 'top', 'bottom'.

Coupling Widget Variables

The current-value setting of some widgets (like text entry widgets) can be connected directly to application variables by using special options. These options are `variable`, `textvariable`, `onvalue`, `offvalue`, and `value`. This connection works both ways: if the variable changes for any reason, the widget it's connected to will be updated to reflect the new value.

Unfortunately, in the current implementation of `Tkinter` it is not possible to hand over an arbitrary Python variable to a widget through a `variable` or `textvariable` option. The only kinds of variables for which this works are variables that are subclassed from a class called `Variable`, defined in the `Tkinter` module.

There are many useful subclasses of `Variable` already defined: `StringVar`, `IntVar`, `DoubleVar`, and `BooleanVar`. To read the current value of such a variable, call the `get()` method on it, and to change its value you call the `set()` method. If you follow this protocol, the widget will always track the value of the variable, with no further intervention on your part.

For example:

```

class App(Frame):
    def __init__(self, master=None):
        Frame.__init__(self, master)
        self.pack()

        self.entrythingy = Entry()
        self.entrythingy.pack()

        # here is the application variable
        self.contents = StringVar()
        # set it to some value
        self.contents.set("this is a variable")
        # tell the entry widget to watch this variable
        self.entrythingy["textvariable"] = self.contents

        # and here we get a callback when the user hits return.
        # we will have the program print out the value of the
        # application variable when the user hits return
        self.entrythingy.bind('<Key-Return>',
                               self.print_contents)

    def print_contents(self, event):
        print "hi. contents of entry is now ---->", \
              self.contents.get()

```

The Window Manager

In Tk, there is a utility command, `wm`, for interacting with the window manager. Options to the `wm` command allow you to control things like titles, placement, icon bitmaps, and the like. In [Tkinter](#), these commands have been implemented as methods on the `Wm` class. Toplevel widgets are subclassed from the `Wm` class, and so can call the `Wm` methods directly.

To get at the toplevel window that contains a given widget, you can often just refer to the widget's master. Of course if the widget has been packed inside of a frame, the master won't represent a toplevel window. To get at the toplevel window that contains an arbitrary widget, you can call the `_root()` method. This method begins with an underscore to denote the fact that this function is part of the implementation, and not an interface to Tk functionality.

Here are some examples of typical usage:

```

from Tkinter import *
class App(Frame):
    def __init__(self, master=None):
        Frame.__init__(self, master)
        self.pack()

# create the application
myapp = App()

#
# here are method calls to the window manager class
#
myapp.master.title("My Do-Nothing Application")
myapp.master.maxsize(1000, 400)

# start the program
myapp.mainloop()

```

Tk Option Data Types

anchor Legal values are points of the compass: "n", "ne", "e", "se", "s", "sw", "w", "nw", and also "center".

bitmap There are eight built-in, named bitmaps: 'error', 'gray25', 'gray50', 'hourglass', 'info', 'questhead', 'question', 'warning'. To specify an X bitmap filename, give the full path to the file, preceded with an @, as in "@usr/contrib/bitmap/gumby.bit".

boolean You can pass integers 0 or 1 or the strings "yes" or "no".

callback This is any Python function that takes no arguments. For example:

```

def print_it():
    print "hi there"
fred["command"] = print_it

```

color Colors can be given as the names of X colors in the rgb.txt file, or as strings representing RGB values in 4 bit: "#RGB", 8 bit: "#RRGGBB", 12 bit: "#RRRGGBBB", or 16 bit: "#RRRRGGGGBBBB" ranges, where R,G,B here represent any legal hex digit. See page 160 of Ousterhout's book for details.

cursor The standard X cursor names from 'cursorfont.h' can be used, without the XC_ prefix. For example to get a hand cursor (XC_hand2), use the string "hand2". You can also specify a bitmap and mask file of your own. See page 179 of Ousterhout's book.

distance Screen distances can be specified in either pixels or absolute distances. Pixels are given as numbers and absolute distances as strings, with the trailing character denoting units: c for centimetres, i for inches, m for millimetres, p for printer's points. For example, 3.5 inches is expressed as "3.5i".

font Tk uses a list font name format, such as {courier 10 bold}. Font sizes with positive numbers are measured in points; sizes with negative numbers are measured in pixels.

geometry This is a string of the form 'widthxheight', where width and height are measured in pixels for most widgets (in characters for widgets displaying text). For example: fred["geometry"] = "200x100".

justify Legal values are the strings: "left", "center", "right", and "fill".

region This is a string with four space-delimited elements, each of which is a legal distance (see above). For example: "2 3 4 5" and "3i 2i 4.5i 2i" and "3c 2c 4c 10.43c" are all legal regions.

relief Determines what the border style of a widget will be. Legal values are: "raised", "sunken", "flat", "groove", and "ridge".

scrollcommand This is almost always the `set()` method of some scrollbar widget, but can be any widget method that takes a single argument. Refer to the file 'Demo/tkinter/matt/canvas-with-scrollbars.py' in the Python source distribution for an example.

wrap Must be one of: "none", "char", or "word".

Bindings and Events

The `bind` method from the widget command allows you to watch for certain events and to have a callback function trigger when that event type occurs. The form of the `bind` method is:

```
def bind(self, sequence, func, add='')
```

where:

sequence is a string that denotes the target kind of event. (See the `bind` man page and page 201 of John Ousterhout's book for details).

func is a Python function, taking one argument, to be invoked when the event occurs. An `Event` instance will be passed as the argument. (Functions deployed this way are commonly known as *callbacks*.)

add is optional, either "" or '+'. Passing an empty string denotes that this binding is to replace any other bindings that this event is associated with. Preceding with a '+' means that this function is to be added to the list of functions bound to this event type.

For example:

```
def turnRed(self, event):
    event.widget["activeforeground"] = "red"

self.button.bind("<Enter>", self.turnRed)
```

Notice how the `widget` field of the event is being accessed in the `turnRed()` callback. This field contains the widget that caught the X event. The following table lists the other event fields you can access, and how they are denoted in Tk, which can be useful when referring to the Tk man pages.

Tk	Tkinter Event Field	Tk	Tkinter Event Field
--	-----	--	-----
%f	focus	%A	char
%h	height	%E	send_event
%k	keycode	%K	keysym
%s	state	%N	keysym_num
%t	time	%T	type
%w	width	%W	widget
%x	x	%X	x_root
%y	y	%Y	y_root

The index Parameter

A number of widgets require “index” parameters to be passed. These are used to point at a specific place in a Text widget, or to particular characters in an Entry widget, or to particular menu items in a Menu widget.

Entry widget indexes (index, view index, etc.) Entry widgets have options that refer to character positions in the text being displayed. You can use these [Tkinter](#) functions to access these special points in text widgets:

AtEnd() refers to the last position in the text

AtInsert() refers to the point where the text cursor is

AtSelFirst() indicates the beginning point of the selected text

AtSelLast() denotes the last point of the selected text and finally

At(x[, y]) refers to the character at pixel location *x*, *y* (with *y* not used in the case of a text entry widget, which contains a single line of text).

Text widget indexes The index notation for Text widgets is very rich and is best described in the Tk man pages.

Menu indexes (menu.invoke(), menu.entryconfig(), etc.) Some options and methods for menus manipulate specific menu entries. Anytime a menu index is needed for an option or a parameter, you may pass in:

- an integer which refers to the numeric position of the entry in the widget, counted from the top, starting with 0;
- the string 'active', which refers to the menu position that is currently under the cursor;
- the string "last" which refers to the last menu item;
- An integer preceded by @, as in @6, where the integer is interpreted as a y pixel coordinate in the menu's coordinate system;
- the string "none", which indicates no menu entry at all, most often used with menu.activate() to deactivate all entries, and finally,
- a text string that is pattern matched against the label of the menu entry, as scanned from the top of the menu to the bottom. Note that this index type is considered after all the others, which means that matches for menu items labelled last, active, or none may be interpreted as the above literals, instead.

Images

Bitmap/Pixmap images can be created through the subclasses of `Tkinter.Image`:

- `BitmapImage` can be used for X11 bitmap data.
- `PhotoImage` can be used for GIF and PPM/PGM color bitmaps.

Either type of image is created through either the `file` or the `data` option (other options are available as well).

The image object can then be used wherever an `image` option is supported by some widget (e.g. labels, buttons, menus). In these cases, Tk will not keep a reference to the image. When the last Python reference to the image object is deleted, the image data is deleted as well, and Tk will display an empty box wherever the image was used.

20.2 Tix — Extension widgets for Tk

The `Tix` (Tk Interface Extension) module provides an additional rich set of widgets. Although the standard Tk library has many useful widgets, they are far from complete. The `Tix` library provides most of the commonly needed widgets that are missing from standard Tk: `HList`, `ComboBox`, `Control` (a.k.a. `SpinBox`) and an assortment of scrollable widgets. `Tix` also includes many more widgets that are generally useful in a wide range of applications: `NoteBook`, `FileEntry`, `PanedWindow`, etc; there are more than 40 of them.

With all these new widgets, you can introduce new interaction techniques into applications, creating more useful and more intuitive user interfaces. You can design your application by choosing the most appropriate widgets to match the special needs of your application and users.

See Also:

Tix Homepage

(<http://tix.sourceforge.net/>)

The home page for `Tix`. This includes links to additional documentation and downloads.

Tix Man Pages

(<http://tix.sourceforge.net/dist/current/man/>)

On-line version of the man pages and reference material.

Tix Programming Guide

(<http://tix.sourceforge.net/dist/current/docs/tix-book/tix.book.html>)

On-line version of the programmer's reference material.

Tix Development Applications

(<http://tix.sourceforge.net/Tide/>)

`Tix` applications for development of `Tix` and `Tkinter` programs. `Tide` applications work under Tk or `Tkinter`, and include **`TixInspect`**, an inspector to remotely modify and debug `Tix`/`Tk`/`Tkinter` applications.

20.2.1 Using Tix

class `Tix` (`screenName` [, `baseName` [, `className`]])

Toplevel widget of `Tix` which represents mostly the main window of an application. It has an associated Tcl interpreter.

Classes in the `Tix` module subclasses the classes in the `Tkinter` module. The former imports the latter, so to use `Tix` with `Tkinter`, all you need to do is to import one module. In general, you can just import `Tix`, and replace the toplevel call to `Tkinter.Tk` with `Tix.Tk`:

```
import Tix
from Tkconstants import *
root = Tix.Tk()
```

To use `Tix`, you must have the `Tix` widgets installed, usually alongside your installation of the Tk widgets. To test your installation, try the following:

```
import Tix
root = Tix.Tk()
root.tk.eval('package require Tix')
```

If this fails, you have a Tk installation problem which must be resolved before proceeding. Use the environment variable `TIK_LIBRARY` to point to the installed `Tix` library directory, and make sure you have the dynamic object library ('`tix8183.dll`' or '`libtix8183.so`') in the same directory that contains your Tk dynamic object library ('`tk8183.dll`'

or 'libtk8183.so'). The directory with the dynamic object library should also have a file called 'pkgIndex.tcl' (case sensitive), which contains the line:

```
package ifneeded Tix 8.1 [list load "[file join $dir tix8183.dll]" Tix]
```

20.2.2 Tix Widgets

Tix introduces over 40 widget classes to the **Tkinter** repertoire. There is a demo of all the **Tix** widgets in the 'Demo/tix' directory of the standard distribution.

Basic Widgets

class Balloon()

A **Balloon** widget pops up over a widget to provide help. When the user moves the cursor inside a widget to which a **Balloon** widget has been bound, a small pop-up window with a descriptive message will be shown on the screen.

class ButtonBox()

The **ButtonBox** widget creates a box of buttons, such as is commonly used for `Ok Cancel`.

class ComboBox()

The **ComboBox** widget is similar to the combo box control in MS Windows. The user can select a choice by either typing in the entry subwidget or selecting from the listbox subwidget.

class Control()

The **Control** widget is also known as the **SpinBox** widget. The user can adjust the value by pressing the two arrow buttons or by entering the value directly into the entry. The new value will be checked against the user-defined upper and lower limits.

class LabelEntry()

The **LabelEntry** widget packages an entry widget and a label into one mega widget. It can be used to simplify the creation of "entry-form" type of interface.

class LabelFrame()

The **LabelFrame** widget packages a frame widget and a label into one mega widget. To create widgets inside a **LabelFrame** widget, one creates the new widgets relative to the `frame` subwidget and manage them inside the `frame` subwidget.

class Meter()

The **Meter** widget can be used to show the progress of a background job which may take a long time to execute.

class OptionMenu()

The **OptionMenu** widget creates a menu button of options.

class PopupMenu()

The **PopupMenu** widget can be used as a replacement of the `tk_popup` command. The advantage of the **Tix** **PopupMenu** widget is it requires less application code to manipulate.

class Select()

The **Select** widget is a container of button subwidgets. It can be used to provide radio-box or check-box style of selection options for the user.

class StdButtonBox()

The **StdButtonBox** widget is a group of standard buttons for Motif-like dialog boxes.

File Selectors

class DirList ()

The [DirList](#) widget displays a list view of a directory, its previous directories and its sub-directories. The user can choose one of the directories displayed in the list or change to another directory.

class DirTree ()

The [DirTree](#) widget displays a tree view of a directory, its previous directories and its sub-directories. The user can choose one of the directories displayed in the list or change to another directory.

class DirSelectDialog ()

The [DirSelectDialog](#) widget presents the directories in the file system in a dialog window. The user can use this dialog window to navigate through the file system to select the desired directory.

class DirSelectBox ()

The [DirSelectBox](#) is similar to the standard Motif(TM) directory-selection box. It is generally used for the user to choose a directory. [DirSelectBox](#) stores the directories mostly recently selected into a [ComboBox](#) widget so that they can be quickly selected again.

class ExFileSelectBox ()

The [ExFileSelectBox](#) widget is usually embedded in a [tixExFileSelectDialog](#) widget. It provides an convenient method for the user to select files. The style of the [ExFileSelectBox](#) widget is very similar to the standard file dialog on MS Windows 3.1.

class FileSelectBox ()

The [FileSelectBox](#) is similar to the standard Motif(TM) file-selection box. It is generally used for the user to choose a file. [FileSelectBox](#) stores the files mostly recently selected into a [ComboBox](#) widget so that they can be quickly selected again.

class FileEntry ()

The [FileEntry](#) widget can be used to input a filename. The user can type in the filename manually. Alternatively, the user can press the button widget that sits next to the entry, which will bring up a file selection dialog.

Hierachical ListBox

class HList ()

The [HList](#) widget can be used to display any data that have a hierarchical structure, for example, file system directory trees. The list entries are indented and connected by branch lines according to their places in the hierarchy.

class CheckList ()

The [CheckList](#) widget displays a list of items to be selected by the user. [CheckList](#) acts similarly to the Tk [checkbutton](#) or [radiobutton](#) widgets, except it is capable of handling many more items than [checkbuttons](#) or [radiobuttons](#).

class Tree ()

The [Tree](#) widget can be used to display hierarchical data in a tree form. The user can adjust the view of the tree by opening or closing parts of the tree.

Tabular ListBox

class TList ()

The [TList](#) widget can be used to display data in a tabular format. The list entries of a [TList](#) widget are similar to the entries in the Tk [listbox](#) widget. The main differences are (1) the [TList](#) widget can display the list entries in a two dimensional format and (2) you can use graphical images as well as multiple colors and fonts for the list entries.

Manager Widgets

class PanedWindow ()

The **PanedWindow** widget allows the user to interactively manipulate the sizes of several panes. The panes can be arranged either vertically or horizontally. The user changes the sizes of the panes by dragging the resize handle between two panes.

class ListNoteBook ()

The **ListNoteBook** widget is very similar to the **TixNoteBook** widget: it can be used to display many windows in a limited space using a notebook metaphor. The notebook is divided into a stack of pages (windows). At one time only one of these pages can be shown. The user can navigate through these pages by choosing the name of the desired page in the **hlist** subwidget.

class NoteBook ()

The **NoteBook** widget can be used to display many windows in a limited space using a notebook metaphor. The notebook is divided into a stack of pages. At one time only one of these pages can be shown. The user can navigate through these pages by choosing the visual “tabs” at the top of the **NoteBook** widget.

Image Types

The **Tix** module adds:

- **pixmap** capabilities to all **Tix** and **Tkinter** widgets to create color images from XPM files.
- **Compound** image types can be used to create images that consists of multiple horizontal lines; each line is composed of a series of items (texts, bitmaps, images or spaces) arranged from left to right. For example, a compound image can be used to display a bitmap and a text string simultaneously in a **Tk Button** widget.

Miscellaneous Widgets

class InputOnly ()

The **InputOnly** widgets are to accept inputs from the user, which can be done with the **bind** command (UNIX only).

Form Geometry Manager

In addition, **Tix** augments **Tkinter** by providing:

class Form ()

The **Form** geometry manager based on attachment rules for all **Tk** widgets.

20.2.3 Tix Commands

class tixCommand ()

The **tix commands** provide access to miscellaneous elements of **Tix**’s internal state and the **Tix** application context. Most of the information manipulated by these methods pertains to the application as a whole, or to a screen or display, rather than to a particular window.

To view the current settings, the common usage is:

```
import Tix
root = Tix.Tk()
print root.tix_configure()
```

tix_configure ([*cnf*,] ***kw*)

Query or modify the configuration options of the Tix application context. If no option is specified, returns a dictionary all of the available options. If option is specified with no value, then the method returns a list describing the one named option (this list will be identical to the corresponding sublist of the value returned if no option is specified). If one or more option-value pairs are specified, then the method modifies the given option(s) to have the given value(s); in this case the method returns an empty string. Option may be any of the configuration options.

tix_cget (*option*)

Returns the current value of the configuration option given by *option*. Option may be any of the configuration options.

tix_getbitmap (*name*)

Locates a bitmap file of the name *name*.xpm or *name* in one of the bitmap directories (see the `tix_addbitmapdir()` method). By using `tix_getbitmap()`, you can avoid hard coding the pathnames of the bitmap files in your application. When successful, it returns the complete pathname of the bitmap file, prefixed with the character '@'. The returned value can be used to configure the `bitmap` option of the Tk and Tix widgets.

tix_addbitmapdir (*directory*)

Tix maintains a list of directories under which the `tix_getimage()` and `tix_getbitmap()` methods will search for image files. The standard bitmap directory is '\$TIX.LIBRARY/bitmaps'. The `tix_addbitmapdir()` method adds *directory* into this list. By using this method, the image files of an applications can also be located using the `tix_getimage()` or `tix_getbitmap()` method.

tix_filedialog ([*dlgclass*])

Returns the file selection dialog that may be shared among different calls from this application. This method will create a file selection dialog widget when it is called the first time. This dialog will be returned by all subsequent calls to `tix_filedialog()`. An optional *dlgclass* parameter can be passed as a string to specified what type of file selection dialog widget is desired. Possible options are `tix`, `FileSelectDialog` or `tixExFileSelectDialog`.

tix_getimage (*self*, *name*)

Locates an image file of the name 'name.xpm', 'name.xbm' or 'name.ppm' in one of the bitmap directories (see the `tix_addbitmapdir()` method above). If more than one file with the same name (but different extensions) exist, then the image type is chosen according to the depth of the X display: xbm images are chosen on monochrome displays and color images are chosen on color displays. By using `tix_getimage()`, you can avoid hard coding the pathnames of the image files in your application. When successful, this method returns the name of the newly created image, which can be used to configure the `image` option of the Tk and Tix widgets.

tix_option_get (*name*)

Gets the options maintained by the Tix scheme mechanism.

tix_resetoptions (*newScheme*, *newFontSet*[, *newScmPrio*])

Resets the scheme and fontset of the Tix application to *newScheme* and *newFontSet*, respectively. This affects only those widgets created after this call. Therefore, it is best to call the `resetoptions` method before the creation of any widgets in a Tix application.

The optional parameter *newScmPrio* can be given to reset the priority level of the Tk options set by the Tix schemes.

Because of the way Tk handles the X option database, after Tix has been imported and initied, it is not possible to reset the color schemes and font sets using the `tix_config()` method. Instead, the `tix_resetoptions()` method must be used.

20.3 ScrolledText — Scrolled Text Widget

The `ScrolledText` module provides a class of the same name which implements a basic text widget which has a vertical scroll bar configured to do the “right thing.” Using the `ScrolledText` class is a lot easier than setting up a text widget and scroll bar directly. The constructor is the same as that of the `Tkinter.Text` class.

The text widget and scrollbar are packed together in a `Frame`, and the methods of the `Grid` and `Pack` geometry managers are acquired from the `Frame` object. This allows the `ScrolledText` widget to be used directly to achieve most normal geometry management behavior.

Should more specific control be necessary, the following attributes are available:

frame

The frame which surrounds the text and scroll bar widgets.

vbar

The scroll bar widget.

20.4 `turtle` — Turtle graphics for Tk

The `turtle` module provides turtle graphics primitives, in both an object-oriented and procedure-oriented ways. Because it uses `Tkinter` for the underlying graphics, it needs a version of python installed with Tk support.

The procedural interface uses a pen and a canvas which are automagically created when any of the functions are called.

The `turtle` module defines the following functions:

degrees()

Set angle measurement units to degrees.

radians()

Set angle measurement units to radians.

setup(kwargs)**

Sets the size and position of the main window. Keywords are:

- **width**: either a size in pixels or a fraction of the screen. The default is 50% of the screen.
- **height**: either a size in pixels or a fraction of the screen. The default is 50% of the screen.
- **startx**: starting position in pixels from the left edge of the screen. `None` is the default value and centers the window horizontally on screen.
- **starty**: starting position in pixels from the top edge of the screen. `None` is the default value and centers the window vertically on screen.

Examples:

```
# Uses default geometry: 50% x 50% of screen, centered.
setup()

# Sets window to 200x200 pixels, in upper left of screen
setup (width=200, height=200, startx=0, starty=0)

# Sets window to 75% of screen by 50% of screen, and centers it.
setup(width=.75, height=0.5, startx=None, starty=None)
```

title(title_str)

Set the window’s title to *title*.

done()

Enters the Tk main loop. The window will continue to be displayed until the user closes it or the process is killed.

reset ()
Clear the screen, re-center the pen, and set variables to the default values.

clear ()
Clear the screen.

tracer (*flag*)
Set tracing on/off (according to whether *flag* is true or not). Tracing means line are drawn more slowly, with an animation of an arrow along the line.

speed (*speed*)
Set the speed of the turtle. Valid values for the parameter *speed* are 'fastest' (no delay), 'fast', (delay 5ms), 'normal' (delay 10ms), 'slow' (delay 15ms), and 'slowest' (delay 20ms). New in version 2.5.

delay (*delay*)
Set the speed of the turtle to *delay*, which is given in ms. New in version 2.5.

forward (*distance*)
Go forward *distance* steps.

backward (*distance*)
Go backward *distance* steps.

left (*angle*)
Turn left *angle* units. Units are by default degrees, but can be set via the `degrees()` and `radians()` functions.

right (*angle*)
Turn right *angle* units. Units are by default degrees, but can be set via the `degrees()` and `radians()` functions.

up ()
Move the pen up — stop drawing.

down ()
Move the pen down — draw when moving.

width (*width*)
Set the line width to *width*.

color (*s*)
color ((*r*, *g*, *b*))
color (*r*, *g*, *b*)
Set the pen color. In the first form, the color is specified as a Tk color specification as a string. The second form specifies the color as a tuple of the RGB values, each in the range [0..1]. For the third form, the color is specified giving the RGB values as three separate parameters (each in the range [0..1]).

write (*text*[, *move*])
Write *text* at the current pen position. If *move* is true, the pen is moved to the bottom-right corner of the text. By default, *move* is false.

fill (*flag*)
The complete specifications are rather complex, but the recommended usage is: call `fill(1)` before drawing a path you want to fill, and call `fill(0)` when you finish to draw the path.

begin_fill ()
Switch turtle into filling mode; Must eventually be followed by a corresponding `end_fill()` call. Otherwise it will be ignored. New in version 2.5.

end_fill ()
End filling mode, and fill the shape; equivalent to `fill(0)`. New in version 2.5.

circle (*radius*[, *extent*])

Draw a circle with radius *radius* whose center-point is *radius* units left of the turtle. *extent* determines which part of a circle is drawn: if not given it defaults to a full circle.

If *extent* is not a full circle, one endpoint of the arc is the current pen position. The arc is drawn in a counter clockwise direction if *radius* is positive, otherwise in a clockwise direction. In the process, the direction of the turtle is changed by the amount of the *extent*.

goto (*x*, *y*)

goto ((*x*, *y*))

Go to co-ordinates *x*, *y*. The co-ordinates may be specified either as two separate arguments or as a 2-tuple.

towards (*x*, *y*)

Return the angle of the line from the turtle's position to the point *x*, *y*. The co-ordinates may be specified either as two separate arguments, as a 2-tuple, or as another pen object. New in version 2.5.

heading ()

Return the current orientation of the turtle. New in version 2.3.

setheading (*angle*)

Set the orientation of the turtle to *angle*. New in version 2.3.

position ()

Return the current location of the turtle as an (*x*, *y*) pair. New in version 2.3.

setx (*x*)

Set the x coordinate of the turtle to *x*. New in version 2.3.

sety (*y*)

Set the y coordinate of the turtle to *y*. New in version 2.3.

window_width ()

Return the width of the canvas window. New in version 2.3.

window_height ()

Return the height of the canvas window. New in version 2.3.

This module also does `from math import *`, so see the documentation for the [math](#) module for additional constants and functions useful for turtle graphics.

demo ()

Exercise the module a bit.

exception Error

Exception raised on any error caught by this module.

For examples, see the code of the `demo ()` function.

This module defines the following classes:

class Pen ()

Define a pen. All above functions can be called as a methods on the given pen. The constructor automatically creates a canvas do be drawn on.

class Turtle ()

Define a pen. This is essentially a synonym for `Pen ()`; `Turtle` is an empty subclass of `Pen`.

class RawPen (*canvas*)

Define a pen which draws on a canvas *canvas*. This is useful if you want to use the module to create graphics in a “real” program.

20.4.1 Turtle, Pen and RawPen Objects

Most of the global functions available in the module are also available as methods of the `Turtle`, `Pen` and `RawPen` classes, affecting only the state of the given pen.

The only method which is more powerful as a method is `degrees()`, which takes an optional argument letting you specify the number of units corresponding to a full circle:

degrees (*[fullcircle]*)

fullcircle is by default 360. This can cause the pen to have any angular units whatever: give *fullcircle* $2*\pi$ for radians, or 400 for gradians.

20.5 Idle

Idle is the Python IDE built with the `Tkinter` GUI toolkit.

IDLE has the following features:

- coded in 100% pure Python, using the `Tkinter` GUI toolkit
- cross-platform: works on Windows and UNIX (on Mac OS, there are currently problems with Tcl/Tk)
- multi-window text editor with multiple undo, Python colorizing and many other features, e.g. smart indent and call tips
- Python shell window (a.k.a. interactive interpreter)
- debugger (not complete, but you can set breakpoints, view and step)

20.5.1 Menus

File menu

New window create a new editing window

Open... open an existing file

Open module... open an existing module (searches `sys.path`)

Class browser show classes and methods in current file

Path browser show `sys.path` directories, modules, classes and methods

Save save current window to the associated file (unsaved windows have a * before and after the window title)

Save As... save current window to new file, which becomes the associated file

Save Copy As... save current window to different file without changing the associated file

Close close current window (asks to save if unsaved)

Exit close all windows and quit IDLE (asks to save if unsaved)

Edit menu

Undo Undo last change to current window (max 1000 changes)

Redo Redo last undone change to current window

Cut Copy selection into system-wide clipboard; then delete selection

Copy Copy selection into system-wide clipboard

Paste Insert system-wide clipboard into window

Select All Select the entire contents of the edit buffer

Find... Open a search dialog box with many options

Find again Repeat last search

Find selection Search for the string in the selection

Find in Files... Open a search dialog box for searching files

Replace... Open a search-and-replace dialog box

Go to line Ask for a line number and show that line

Indent region Shift selected lines right 4 spaces

Dedent region Shift selected lines left 4 spaces

Comment out region Insert ## in front of selected lines

Uncomment region Remove leading # or ## from selected lines

Tabify region Turns *leading* stretches of spaces into tabs

Untabify region Turn *all* tabs into the right number of spaces

Expand word Expand the word you have typed to match another word in the same buffer; repeat to get a different expansion

Format Paragraph Reformat the current blank-line-separated paragraph

Import module Import or reload the current module

Run script Execute the current file in the `__main__` namespace

Windows menu

Zoom Height toggles the window between normal size (24x80) and maximum height.

The rest of this menu lists the names of all open windows; select one to bring it to the foreground (deiconifying it if necessary).

Debug menu (in the Python Shell window only)

Go to file/line look around the insert point for a filename and linenumber, open the file, and show the line.

Open stack viewer show the stack traceback of the last exception

Debugger toggle Run commands in the shell under the debugger

JIT Stack viewer toggle Open stack viewer on traceback

20.5.2 Basic editing and navigation

- **Backspace** deletes to the left; **Del** deletes to the right
- **Arrow keys** and **Page Up/Page Down** to move around
- **Home/End** go to begin/end of line
- **C-Home/C-End** go to begin/end of file
- Some **Emacs** bindings may also work, including **C-B**, **C-P**, **C-A**, **C-E**, **C-D**, **C-L**

Automatic indentation

After a block-opening statement, the next line is indented by 4 spaces (in the Python Shell window by one tab). After certain keywords (break, return etc.) the next line is dedented. In leading indentation, **Backspace** deletes up to 4 spaces if they are there. **Tab** inserts 1-4 spaces (in the Python Shell window one tab). See also the indent/dedent region commands in the edit menu.

Python Shell window

- **C-C** interrupts executing command
- **C-D** sends end-of-file; closes window if typed at a '>>>' prompt
- **Alt-p** retrieves previous command matching what you have typed
- **Alt-n** retrieves next
- **Return** while on any previous command retrieves that command
- **Alt-/** (Expand word) is also useful here

20.5.3 Syntax colors

The coloring is applied in a background “thread,” so you may occasionally see uncolorized text. To change the color scheme, edit the `[Colors]` section in ‘config.txt’.

Python syntax colors: **Keywords** orange

Strings green

Comments red

Definitions blue

Shell colors: Console output brown

stdout blue

stderr dark green

stdin black

Command line usage

```
idle.py [-c command] [-d] [-e] [-s] [-t title] [arg] ...
```

```
-c command  run this command
-d          enable debugger
-e          edit mode; arguments are files to be edited
-s          run $IDLESTARTUP or $PYTHONSTARTUP first
-t title    set title of shell window
```

If there are arguments:

1. If **-e** is used, arguments are files opened for editing and `sys.argv` reflects the arguments passed to IDLE itself.
2. Otherwise, if **-c** is used, all arguments are placed in `sys.argv[1:..]`, with `sys.argv[0]` set to `'-c'`.
3. Otherwise, if neither **-e** nor **-c** is used, the first argument is a script which is executed with the remaining arguments in `sys.argv[1:..]` and `sys.argv[0]` set to the script name. If the script name is `'-'`, no script is executed but an interactive Python session is started; the arguments are still available in `sys.argv`.

20.6 Other Graphical User Interface Packages

There are an number of extension widget sets to [Tkinter](#).

Python megawidgets

(<http://pmw.sourceforge.net/>)

is a toolkit for building high-level compound widgets in Python using the [Tkinter](#) module. It consists of a set of base classes and a library of flexible and extensible megawidgets built on this foundation. These megawidgets include notebooks, comboboxes, selection widgets, paned widgets, scrolled widgets, dialog windows, etc. Also, with the Pmw.Blt interface to BLT, the busy, graph, stripchart, tabset and vector commands are be available.

The initial ideas for Pmw were taken from the Tk `itcl` extensions [`incr Tk`] by Michael McLennan and [`incr Widgets`] by Mark Ulberts. Several of the megawidgets are direct translations from the `itcl` to Python. It offers most of the range of widgets that [`incr Widgets`] does, and is almost as complete as Tix, lacking however Tix's fast `HList` widget for drawing trees.

Tkinter3000 Widget Construction Kit (WCK)

(<http://tkinter.effbot.org/>)

is a library that allows you to write new Tkinter widgets in pure Python. The WCK framework gives you full control over widget creation, configuration, screen appearance, and event handling. WCK widgets can be very fast and light-weight, since they can operate directly on Python data structures, without having to transfer data through the Tk/Tcl layer.

Other GUI packages are also available for Python:

wxPython

(<http://www.wxpython.org>)

wxPython is a cross-platform GUI toolkit for Python that is built around the popular [wxWidgets](#) C++ toolkit. It provides a native look and feel for applications on Windows, Mac OS X, and UNIX systems by using each platform's native widgets where ever possible, (GTK+ on UNIX-like systems). In addition to an extensive set of widgets, wxPython provides classes for online documentation and context sensitive help, printing, HTML viewing, low-level device context drawing, drag and drop, system clipboard access, an XML-based resource format and more, including an ever growing library of user-contributed modules. Both the wxWidgets and wxPython projects are under active development and continuous improvement, and have active and helpful user and developer communities.

wxPython in Action

(<http://www.amazon.com/exec/obidos/ASIN/1932394621>)

The wxPython book, by Noel Rappin and Robin Dunn.

PyQt

PyQt is a **sip**-wrapped binding to the Qt toolkit. Qt is an extensive C++ GUI toolkit that is available for UNIX, Windows and Mac OS X. **sip** is a tool for generating bindings for C++ libraries as Python classes, and is specifically designed for Python. An online manual is available at <http://www.opendocspublishing.com/pyqt/> (errata are located at <http://www.valdyas.org/python/book.html>).

PyKDE

(<http://www.riverbankcomputing.co.uk/pykde/index.php>)

PyKDE is a **sip**-wrapped interface to the KDE desktop libraries. KDE is a desktop environment for UNIX computers; the graphical components are based on Qt.

FXPy

(<http://fxpy.sourceforge.net/>)

is a Python extension module which provides an interface to the [FOX](#) GUI. FOX is a C++ based Toolkit for developing Graphical User Interfaces easily and effectively. It offers a wide, and growing, collection of Controls, and provides state of the art facilities such as drag and drop, selection, as well as OpenGL widgets for 3D graphical manipulation. FOX also implements icons, images, and user-convenience features such as status line help, and tooltips.

Even though FOX offers a large collection of controls already, FOX leverages C++ to allow programmers to easily build additional Controls and GUI elements, simply by taking existing controls, and creating a derived class which simply adds or redefines the desired behavior.

PyGTK

(<http://www.daa.com.au/~james/software/pygtk/>)

is a set of bindings for the [GTK](#) widget set. It provides an object oriented interface that is slightly higher level than the C one. It automatically does all the type casting and reference counting that you would have to do normally with the C API. There are also [bindings](#) to [GNOME](#), and a [tutorial](#) is available.

Internationalization

The modules described in this chapter help you write software that is independent of language and locale by providing mechanisms for selecting a language to be used in program messages or by tailoring output to match local conventions.

The list of modules described in this chapter is:

gettext Multilingual internationalization services.
locale Internationalization services.

21.1 gettext — Multilingual internationalization services

The `gettext` module provides internationalization (I18N) and localization (L10N) services for your Python modules and applications. It supports both the GNU `gettext` message catalog API and a higher level, class-based API that may be more appropriate for Python files. The interface described below allows you to write your module and application messages in one natural language, and provide a catalog of translated messages for running under different natural languages.

Some hints on localizing your Python modules and applications are also given.

21.1.1 GNU `gettext` API

The `gettext` module defines the following API, which is very similar to the GNU **gettext** API. If you use this API you will affect the translation of your entire application globally. Often this is what you want if your application is monolingual, with the choice of language dependent on the locale of your user. If you are localizing a Python module, or if your application needs to switch languages on the fly, you probably want to use the class-based API instead.

bindtextdomain (*domain* [, *localedir*])

Bind the *domain* to the locale directory *localedir*. More concretely, `gettext` will look for binary ‘.mo’ files for the given domain using the path (on UNIX): ‘*localedir*/*language*/LC_MESSAGES/*domain*.mo’, where *languages* is searched for in the environment variables `LANGUAGE`, `LC_ALL`, `LC_MESSAGES`, and `LANG` respectively.

If *localedir* is omitted or `None`, then the current binding for *domain* is returned.¹

bind_textdomain_codeset (*domain* [, *codeset*])

Bind the *domain* to *codeset*, changing the encoding of strings returned by the `gettext()` family of functions. If *codeset* is omitted, then the current binding is returned.

New in version 2.4.

¹The default locale directory is system dependent; for example, on RedHat Linux it is ‘`/usr/share/locale`’, but on Solaris it is ‘`/usr/lib/locale`’. The `gettext` module does not try to support these system dependent defaults; instead its default is ‘`sys.prefix/share/locale`’. For this reason, it is always best to call `bindtextdomain()` with an explicit absolute path at the start of your application.

textdomain ([*domain*])

Change or query the current global domain. If *domain* is `None`, then the current global domain is returned, otherwise the global domain is set to *domain*, which is returned.

gettext (*message*)

Return the localized translation of *message*, based on the current global domain, language, and locale directory. This function is usually aliased as `_` in the local namespace (see examples below).

lgettext (*message*)

Equivalent to `gettext()`, but the translation is returned in the preferred system encoding, if no other encoding was explicitly set with `bind_textdomain_codeset()`.

New in version 2.4.

dgettext (*domain*, *message*)

Like `gettext()`, but look the message up in the specified *domain*.

ldgettext (*domain*, *message*)

Equivalent to `dgettext()`, but the translation is returned in the preferred system encoding, if no other encoding was explicitly set with `bind_textdomain_codeset()`.

New in version 2.4.

ngettext (*singular*, *plural*, *n*)

Like `gettext()`, but consider plural forms. If a translation is found, apply the plural formula to *n*, and return the resulting message (some languages have more than two plural forms). If no translation is found, return *singular* if *n* is 1; return *plural* otherwise.

The Plural formula is taken from the catalog header. It is a C or Python expression that has a free variable *n*; the expression evaluates to the index of the plural in the catalog. See the GNU gettext documentation for the precise syntax to be used in `.po` files and the formulas for a variety of languages.

New in version 2.3.

lngettext (*singular*, *plural*, *n*)

Equivalent to `ngettext()`, but the translation is returned in the preferred system encoding, if no other encoding was explicitly set with `bind_textdomain_codeset()`.

New in version 2.4.

dngettext (*domain*, *singular*, *plural*, *n*)

Like `ngettext()`, but look the message up in the specified *domain*.

New in version 2.3.

ldngettext (*domain*, *singular*, *plural*, *n*)

Equivalent to `dngettext()`, but the translation is returned in the preferred system encoding, if no other encoding was explicitly set with `bind_textdomain_codeset()`.

New in version 2.4.

Note that GNU **gettext** also defines a `dcgettext()` method, but this was deemed not useful and so it is currently unimplemented.

Here's an example of typical usage for this API:

```
import gettext
gettext.bindtextdomain('myapplication', '/path/to/my/language/directory')
gettext.textdomain('myapplication')
_ = gettext.gettext
# ...
print _('This is a translatable string.')
```


21.1.2 Class-based API

The class-based API of the `gettext` module gives you more flexibility and greater convenience than the GNU `gettext` API. It is the recommended way of localizing your Python applications and modules. `gettext` defines a “translations” class which implements the parsing of GNU ‘.mo’ format files, and has methods for returning either standard 8-bit strings or Unicode strings. Instances of this “translations” class can also install themselves in the built-in namespace as the function `_()`.

find(*domain*[, *localedir*[, *languages*[, *all*]]])

This function implements the standard ‘.mo’ file search algorithm. It takes a *domain*, identical to what `textdomain()` takes. Optional *localedir* is as in `bindtextdomain()`. Optional *languages* is a list of strings, where each string is a language code.

If *localedir* is not given, then the default system locale directory is used.² If *languages* is not given, then the following environment variables are searched: `LANGUAGE`, `LC_ALL`, `LC_MESSAGES`, and `LANG`. The first one returning a non-empty value is used for the *languages* variable. The environment variables should contain a colon separated list of languages, which will be split on the colon to produce the expected list of language code strings.

`find()` then expands and normalizes the languages, and then iterates through them, searching for an existing file built of these components:

‘*localedir*/*language*/LC_MESSAGES/*domain*.mo’

The first such file name that exists is returned by `find()`. If no such file is found, then `None` is returned. If *all* is given, it returns a list of all file names, in the order in which they appear in the *languages* list or the environment variables.

translation(*domain*[, *localedir*[, *languages*[, *class_*[, *fallback*[, *codeset*]]]]])

Return a `Translations` instance based on the *domain*, *localedir*, and *languages*, which are first passed to `find()` to get a list of the associated ‘.mo’ file paths. Instances with identical ‘.mo’ file names are cached. The actual class instantiated is either *class_* if provided, otherwise `GNUTranslations`. The class’s constructor must take a single file object argument. If provided, *codeset* will change the charset used to encode translated strings.

If multiple files are found, later files are used as fallbacks for earlier ones. To allow setting the fallback, `copy.copy` is used to clone each translation object from the cache; the actual instance data is still shared with the cache.

If no ‘.mo’ file is found, this function raises `IOError` if *fallback* is false (which is the default), and returns a `NullTranslations` instance if *fallback* is true.

Changed in version 2.4: Added the *codeset* parameter.

install(*domain*[, *localedir*[, *unicode* [, *codeset* [, *names*]]]])

This installs the function `_` in Python’s builtin namespace, based on *domain*, *localedir*, and *codeset* which are passed to the function `translation()`. The *unicode* flag is passed to the resulting translation object’s `install` method.

For the *names* parameter, please see the description of the translation object’s `install` method.

As seen below, you usually mark the strings in your application that are candidates for translation, by wrapping them in a call to the `_()` function, like this:

```
print _('This string will be translated.')
```

For convenience, you want the `_()` function to be installed in Python’s builtin namespace, so it is easily accessible in all modules of your application.

Changed in version 2.4: Added the *codeset* parameter. Changed in version 2.5: Added the *names* parameter.

²See the footnote for `bindtextdomain()` above.

The `NullTranslations` class

Translation classes are what actually implement the translation of original source file message strings to translated message strings. The base class used by all translation classes is `NullTranslations`; this provides the basic interface you can use to write your own specialized translation classes. Here are the methods of `NullTranslations`:

`__init__` (*[fp]*)

Takes an optional file object *fp*, which is ignored by the base class. Initializes “protected” instance variables *_info* and *_charset* which are set by derived classes, as well as *_fallback*, which is set through `add_fallback`. It then calls `self._parse(fp)` if *fp* is not `None`.

`_parse` (*fp*)

No-op’d in the base class, this method takes file object *fp*, and reads the data from the file, initializing its message catalog. If you have an unsupported message catalog file format, you should override this method to parse your format.

`add_fallback` (*fallback*)

Add *fallback* as the fallback object for the current translation object. A translation object should consult the fallback if it cannot provide a translation for a given message.

`gettext` (*message*)

If a fallback has been set, forward `gettext()` to the fallback. Otherwise, return the translated message. Overridden in derived classes.

`lgettext` (*message*)

If a fallback has been set, forward `lgettext()` to the fallback. Otherwise, return the translated message. Overridden in derived classes.

New in version 2.4.

`ugettext` (*message*)

If a fallback has been set, forward `ugettext()` to the fallback. Otherwise, return the translated message as a Unicode string. Overridden in derived classes.

`ngettext` (*singular, plural, n*)

If a fallback has been set, forward `ngettext()` to the fallback. Otherwise, return the translated message. Overridden in derived classes.

New in version 2.3.

`lngettext` (*singular, plural, n*)

If a fallback has been set, forward `ngettext()` to the fallback. Otherwise, return the translated message. Overridden in derived classes.

New in version 2.4.

`ungettext` (*singular, plural, n*)

If a fallback has been set, forward `ungettext()` to the fallback. Otherwise, return the translated message as a Unicode string. Overridden in derived classes.

New in version 2.3.

`info` ()

Return the “protected” *_info* variable.

`charset` ()

Return the “protected” *_charset* variable.

`output_charset` ()

Return the “protected” *_output_charset* variable, which defines the encoding used to return translated messages.

New in version 2.4.

set_output_charset (*charset*)

Change the “protected” `_output_charset` variable, which defines the encoding used to return translated messages.

New in version 2.4.

install ([*unicode* [, *names*]])

If the *unicode* flag is false, this method installs `self.gettext()` into the built-in namespace, binding it to `_`. If *unicode* is true, it binds `self.ugettext()` instead. By default, *unicode* is false.

If the *names* parameter is given, it must be a sequence containing the names of functions you want to install in the builtin namespace in addition to `_()`. Supported names are `'gettext'` (bound to `self.gettext()` or `self.ugettext()` according to the *unicode* flag), `'ngettext'` (bound to `self.ngettext()` or `self.ungettext()` according to the *unicode* flag), `'lgettext'` and `'lngettext'`.

Note that this is only one way, albeit the most convenient way, to make the `_` function available to your application. Because it affects the entire application globally, and specifically the built-in namespace, localized modules should never install `_`. Instead, they should use this code to make `_` available to their module:

```
import gettext
t = gettext.translation('mymodule', ...)
_ = t.gettext
```

This puts `_` only in the module’s global namespace and so only affects calls within this module.

Changed in version 2.5: Added the *names* parameter.

The GNUTranslations class

The `gettext` module provides one additional class derived from `NullTranslations`: `GNUTranslations`. This class overrides `_parse()` to enable reading GNU **gettext** format `'mo'` files in both big-endian and little-endian format. It also coerces both message ids and message strings to Unicode.

`GNUTranslations` parses optional meta-data out of the translation catalog. It is convention with GNU **gettext** to include meta-data as the translation for the empty string. This meta-data is in RFC 822-style `key: value` pairs, and should contain the `Project-Id-Version` key. If the key `Content-Type` is found, then the `charset` property is used to initialize the “protected” `_charset` instance variable, defaulting to `None` if not found. If the `charset` encoding is specified, then all message ids and message strings read from the catalog are converted to Unicode using this encoding. The `ugettext()` method always returns a Unicode, while the `gettext()` returns an encoded 8-bit string. For the message id arguments of both methods, either Unicode strings or 8-bit strings containing only US-ASCII characters are acceptable. Note that the Unicode version of the methods (i.e. `ugettext()` and `ungettext()`) are the recommended interface to use for internationalized Python programs.

The entire set of key/value pairs are placed into a dictionary and set as the “protected” `_info` instance variable.

If the `'mo'` file’s magic number is invalid, or if other problems occur while reading the file, instantiating a `GNUTranslations` class can raise `IOError`.

The following methods are overridden from the base class implementation:

gettext (*message*)

Look up the *message* id in the catalog and return the corresponding message string, as an 8-bit string encoded with the catalog’s `charset` encoding, if known. If there is no entry in the catalog for the *message* id, and a fallback has been set, the look up is forwarded to the fallback’s `gettext()` method. Otherwise, the *message* id is returned.

lgettext (*message*)

Equivalent to `gettext()`, but the translation is returned in the preferred system encoding, if no other encoding was explicitly set with `set_output_charset()`.

New in version 2.4.

ugettext (*message*)

Look up the *message* id in the catalog and return the corresponding message string, as a Unicode string. If there is no entry in the catalog for the *message* id, and a fallback has been set, the look up is forwarded to the fallback's `ugettext()` method. Otherwise, the *message* id is returned.

ngettext (*singular, plural, n*)

Do a plural-forms lookup of a message id. *singular* is used as the message id for purposes of lookup in the catalog, while *n* is used to determine which plural form to use. The returned message string is an 8-bit string encoded with the catalog's charset encoding, if known.

If the message id is not found in the catalog, and a fallback is specified, the request is forwarded to the fallback's `ngettext()` method. Otherwise, when *n* is 1 *singular* is returned, and *plural* is returned in all other cases.

New in version 2.3.

lgettext (*singular, plural, n*)

Equivalent to `gettext()`, but the translation is returned in the preferred system encoding, if no other encoding was explicitly set with `set_output_charset()`.

New in version 2.4.

ungettext (*singular, plural, n*)

Do a plural-forms lookup of a message id. *singular* is used as the message id for purposes of lookup in the catalog, while *n* is used to determine which plural form to use. The returned message string is a Unicode string.

If the message id is not found in the catalog, and a fallback is specified, the request is forwarded to the fallback's `ungettext()` method. Otherwise, when *n* is 1 *singular* is returned, and *plural* is returned in all other cases.

Here is an example:

```
n = len(os.listdir('.'))
cat = GNUTranslations(somefile)
message = cat.ungettext(
    'There is %(num)d file in this directory',
    'There are %(num)d files in this directory',
    n) % {'num': n}
```

New in version 2.3.

Solaris message catalog support

The Solaris operating system defines its own binary '.mo' file format, but since no documentation can be found on this format, it is not supported at this time.

The Catalog constructor

GNOME uses a version of the `gettext` module by James Henstridge, but this version has a slightly different API. Its documented usage was:

```
import gettext
cat = gettext.Catalog(domain, localedir)
_ = cat.gettext
print _('hello world')
```

For compatibility with this older module, the function `Catalog()` is an alias for the `translation()` function described above.

One difference between this module and Henstridge's: his catalog objects supported access through a mapping API, but this appears to be unused and so is not currently supported.

21.1.3 Internationalizing your programs and modules

Internationalization (I18N) refers to the operation by which a program is made aware of multiple languages. Localization (L10N) refers to the adaptation of your program, once internationalized, to the local language and cultural habits. In order to provide multilingual messages for your Python programs, you need to take the following steps:

1. prepare your program or module by specially marking translatable strings
2. run a suite of tools over your marked files to generate raw messages catalogs
3. create language specific translations of the message catalogs
4. use the `gettext` module so that message strings are properly translated

In order to prepare your code for I18N, you need to look at all the strings in your files. Any string that needs to be translated should be marked by wrapping it in `_('...')` — that is, a call to the function `_()`. For example:

```
filename = 'mylog.txt'
message = _('writing a log message')
fp = open(filename, 'w')
fp.write(message)
fp.close()
```

In this example, the string `'writing a log message'` is marked as a candidate for translation, while the strings `'mylog.txt'` and `'w'` are not.

The Python distribution comes with two tools which help you generate the message catalogs once you've prepared your source code. These may or may not be available from a binary distribution, but they can be found in a source distribution, in the `'Tools/i18n'` directory.

The **pygettext**³ program scans all your Python source code looking for the strings you previously marked as translatable. It is similar to the GNU **gettext** program except that it understands all the intricacies of Python source code, but knows nothing about C or C++ source code. You don't need GNU **gettext** unless you're also going to be translating C code (such as C extension modules).

pygettext generates textual Uniform-style human readable message catalog `'pot'` files, essentially structured human readable files which contain every marked string in the source code, along with a placeholder for the translation strings. **pygettext** is a command line script that supports a similar command line interface as **xgettext**; for details on its use, run:

```
pygettext.py --help
```

Copies of these `'pot'` files are then handed over to the individual human translators who write language-specific versions for every supported natural language. They send you back the filled in language-specific versions as a `'po'` file. Using the **msgfmt.py**⁴ program (in the `'Tools/i18n'` directory), you take the `'po'` files from your translators and generate the machine-readable `'mo'` binary catalog files. The `'mo'` files are what the `gettext` module uses for the actual translation processing during run-time.

³François Pinard has written a program called **xpot** which does a similar job. It is available as part of his **po-utils** package at <http://po-utils.progiciels-bpi.ca/>.

⁴**msgfmt.py** is binary compatible with GNU **msgfmt** except that it provides a simpler, all-Python implementation. With this and **pygettext.py**, you generally won't need to install the GNU **gettext** package to internationalize your Python applications.

How you use the `gettext` module in your code depends on whether you are internationalizing a single module or your entire application. The next two sections will discuss each case.

Localizing your module

If you are localizing your module, you must take care not to make global changes, e.g. to the built-in namespace. You should not use the GNU `gettext` API but instead the class-based API.

Let's say your module is called "spam" and the module's various natural language translation '.mo' files reside in '/usr/share/locale' in GNU **gettext** format. Here's what you would put at the top of your module:

```
import gettext
t = gettext.translation('spam', '/usr/share/locale')
_ = t.lgettext
```

If your translators were providing you with Unicode strings in their '.po' files, you'd instead do:

```
import gettext
t = gettext.translation('spam', '/usr/share/locale')
_ = t.ugettext
```

Localizing your application

If you are localizing your application, you can install the `_()` function globally into the built-in namespace, usually in the main driver file of your application. This will let all your application-specific files just use `_('...')` without having to explicitly install it in each file.

In the simple case then, you need only add the following bit of code to the main driver file of your application:

```
import gettext
gettext.install('myapplication')
```

If you need to set the locale directory or the *unicode* flag, you can pass these into the `install()` function:

```
import gettext
gettext.install('myapplication', '/usr/share/locale', unicode=1)
```

Changing languages on the fly

If your program needs to support many languages at the same time, you may want to create multiple translation instances and then switch between them explicitly, like so:

```

import gettext

lang1 = gettext.translation('myapplication', languages=['en'])
lang2 = gettext.translation('myapplication', languages=['fr'])
lang3 = gettext.translation('myapplication', languages=['de'])

# start by using language1
lang1.install()

# ... time goes by, user selects language 2
lang2.install()

# ... more time goes by, user selects language 3
lang3.install()

```

Deferred translations

In most coding situations, strings are translated where they are coded. Occasionally however, you need to mark strings for translation, but defer actual translation until later. A classic example is:

```

animals = ['mollusk',
           'albatross',
           'rat',
           'penguin',
           'python',
           ]
# ...
for a in animals:
    print a

```

Here, you want to mark the strings in the `animals` list as being translatable, but you don't actually want to translate them until they are printed.

Here is one way you can handle this situation:

```

def _(message): return message

animals = [_('mollusk'),
           _('albatross'),
           _('rat'),
           _('penguin'),
           _('python'),
           ]

del _

# ...
for a in animals:
    print _(a)

```

This works because the dummy definition of `_()` simply returns the string unchanged. And this dummy definition will temporarily override any definition of `_()` in the built-in namespace (until the `del` command). Take care, though

if you have a previous definition of `_` in the local namespace.

Note that the second use of `_()` will not identify “a” as being translatable to the **pygettext** program, since it is not a string.

Another way to handle this is with the following example:

```
def N_(message): return message

animals = [N_('mollusk'),
           N_('albatross'),
           N_('rat'),
           N_('penguin'),
           N_('python'),
           ]

# ...
for a in animals:
    print _(a)
```

In this case, you are marking translatable strings with the function `N_()`,⁵ which won’t conflict with any definition of `_()`. However, you will need to teach your message extraction program to look for translatable strings marked with `N_()`. **pygettext** and **xpot** both support this through the use of command line switches.

`gettext()` vs. `lgettext()`

In Python 2.4 the `lgettext()` family of functions were introduced. The intention of these functions is to provide an alternative which is more compliant with the current implementation of GNU `gettext`. Unlike `gettext()`, which returns strings encoded with the same codeset used in the translation file, `lgettext()` will return strings encoded with the preferred system encoding, as returned by `locale.getpreferredencoding()`. Also notice that Python 2.4 introduces new functions to explicitly choose the codeset used in translated strings. If a codeset is explicitly set, even `lgettext()` will return translated strings in the requested codeset, as would be expected in the GNU `gettext` implementation.

21.1.4 Acknowledgements

The following people contributed code, feedback, design suggestions, previous implementations, and valuable experience to the creation of this module:

- Peter Funk
- James Henstridge
- Juan David Ibáñez Palomar
- Marc-André Lemburg
- Martin von Löwis
- François Pinard
- Barry Warsaw
- Gustavo Niemeyer

⁵The choice of `N_()` here is totally arbitrary; it could have just as easily been `MarkThisStringForTranslation()`.

21.2 locale — Internationalization services

The `locale` module opens access to the POSIX locale database and functionality. The POSIX locale mechanism allows programmers to deal with certain cultural issues in an application, without requiring the programmer to know all the specifics of each country where the software is executed.

The `locale` module is implemented on top of the `_locale` module, which in turn uses an ANSI C locale implementation if available.

The `locale` module defines the following exception and functions:

exception Error

Exception raised when `setlocale()` fails.

setlocale(*category*[, *locale*])

If *locale* is specified, it may be a string, a tuple of the form (*language code*, *encoding*), or `None`. If it is a tuple, it is converted to a string using the locale aliasing engine. If *locale* is given and not `None`, `setlocale()` modifies the locale setting for the *category*. The available categories are listed in the data description below. The value is the name of a locale. An empty string specifies the user's default settings. If the modification of the locale fails, the exception `Error` is raised. If successful, the new locale setting is returned.

If *locale* is omitted or `None`, the current setting for *category* is returned.

`setlocale()` is not thread safe on most systems. Applications typically start with a call of

```
import locale
locale.setlocale(locale.LC_ALL, '')
```

This sets the locale for all categories to the user's default setting (typically specified in the `LANG` environment variable). If the locale is not changed thereafter, using multithreading should not cause problems.

Changed in version 2.0: Added support for tuple values of the *locale* parameter.

localeconv()

Returns the database of the local conventions as a dictionary. This dictionary has the following strings as keys:

Category	Key	Meaning
LC_NUMERIC	'decimal_point'	Decimal point character.
	'grouping'	Sequence of numbers specifying which relative positions the 'thousands_sep' is expected. If the sequence is terminated with CHAR_MAX, no further grouping is performed. If the sequence terminates with a 0, the last group size is repeatedly used.
LC_MONETARY	'thousands_sep'	Character used between groups.
	'int_curr_symbol'	International currency symbol.
	'currency_symbol'	Local currency symbol.
	'p_cs_precedes/n_cs_precedes'	Whether the currency symbol precedes the value (for positive resp. negative values).
	'p_sep_by_space/n_sep_by_space'	Whether the currency symbol is separated from the value by a space (for positive resp. negative values).
	'mon_decimal_point'	Decimal point used for monetary values.
	'frac_digits'	Number of fractional digits used in local formatting of monetary values.
	'int_frac_digits'	Number of fractional digits used in international formatting of monetary values.
	'mon_thousands_sep'	Group separator used for monetary values.
	'mon_grouping'	Equivalent to 'grouping', used for monetary values.
	'positive_sign'	Symbol used to annotate a positive monetary value.
	'negative_sign'	Symbol used to annotate a negative monetary value.
	'p_sign_posn/n_sign_posn'	The position of the sign (for positive resp. negative values), see below.

All numeric values can be set to CHAR_MAX to indicate that there is no value specified in this locale.

The possible values for 'p_sign_posn' and 'n_sign_posn' are given below.

Value	Explanation
0	Currency and value are surrounded by parentheses.
1	The sign should precede the value and currency symbol.
2	The sign should follow the value and currency symbol.
3	The sign should immediately precede the value.
4	The sign should immediately follow the value.
CHAR_MAX	Nothing is specified in this locale.

nl_langinfo (*option*)

Return some locale-specific information as a string. This function is not available on all systems, and the set of possible options might also vary across platforms. The possible argument values are numbers, for which symbolic constants are available in the locale module.

getdefaultlocale ([*envvars*])

Tries to determine the default locale settings and returns them as a tuple of the form (*language code*, *encoding*).

According to POSIX, a program which has not called `setlocale(LC_ALL, '')` runs using the portable 'C' locale. Calling `setlocale(LC_ALL, '')` lets it use the default locale as defined by the LANG variable. Since we do not want to interfere with the current locale setting we thus emulate the behavior in the way described above.

To maintain compatibility with other platforms, not only the LANG variable is tested, but a list of variables given as *envvars* parameter. The first found to be defined will be used. *envvars* defaults to the search path used in GNU gettext; it must always contain the variable name 'LANG'. The GNU gettext search path contains 'LANGUAGE', 'LC_ALL', 'LC_CTYPE', and 'LANG', in that order.

Except for the code 'C', the language code corresponds to RFC 1766. *language code* and *encoding* may be None if their values cannot be determined. New in version 2.0.

getlocale ([*category*])

Returns the current setting for the given locale category as sequence containing *language code*, *encoding*. *category* may be one of the LC_* values except LC_ALL. It defaults to LC_CTYPE.

Except for the code 'C', the language code corresponds to RFC 1766. *language code* and *encoding* may be None if their values cannot be determined. New in version 2.0.

getpreferredencoding ([*do_setlocale*])

Return the encoding used for text data, according to user preferences. User preferences are expressed differently on different systems, and might not be available programmatically on some systems, so this function only returns a guess.

On some systems, it is necessary to invoke `setlocale` to obtain the user preferences, so this function is not thread-safe. If invoking `setlocale` is not necessary or desired, *do_setlocale* should be set to `False`.

New in version 2.3.

normalize (*localename*)

Returns a normalized locale code for the given locale name. The returned locale code is formatted for use with `setlocale()`. If normalization fails, the original name is returned unchanged.

If the given encoding is not known, the function defaults to the default encoding for the locale code just like `setlocale()`. New in version 2.0.

resetlocale ([*category*])

Sets the locale for *category* to the default setting.

The default setting is determined by calling `getdefaultlocale()`. *category* defaults to LC_ALL. New in version 2.0.

strcoll (*string1*, *string2*)

Compares two strings according to the current LC_COLLATE setting. As any other compare function, returns a negative, or a positive value, or 0, depending on whether *string1* collates before or after *string2* or is equal to it.

strxfrm (*string*)

Transforms a string to one that can be used for the built-in function `cmp()`, and still returns locale-aware results. This function can be used when the same string is compared repeatedly, e.g. when collating a sequence of strings.

format (*format*, *val* [, *grouping* [, *monetary*]])

Formats a number *val* according to the current LC_NUMERIC setting. The format follows the conventions of the % operator. For floating point values, the decimal point is modified if appropriate. If *grouping* is true, also takes the grouping into account.

If *monetary* is true, the conversion uses monetary thousands separator and grouping strings.

Please note that this function will only work for exactly one %char specifier. For whole format strings, use `format_string()`.

Changed in version 2.5: Added the *monetary* parameter.

format_string (*format*, *val* [, *grouping*])

Processes formatting specifiers as in `format %val`, but takes the current locale settings into account.

New in version 2.5.

currency (*val* [, *symbol* [, *grouping* [, *international*]])

Formats a number *val* according to the current LC_MONETARY settings.

The returned string includes the currency symbol if *symbol* is true, which is the default. If *grouping* is true (which is not the default), grouping is done with the value. If *international* is true (which is not the default), the international currency symbol is used.

Note that this function will not work with the 'C' locale, so you have to set a locale via `setlocale()` first.

New in version 2.5.

str (*float*)

Formats a floating point number using the same format as the built-in function `str (float)`, but takes the decimal point into account.

atof (*string*)

Converts a string to a floating point number, following the `LC_NUMERIC` settings.

atoi (*string*)

Converts a string to an integer, following the `LC_NUMERIC` conventions.

LC_CTYPE

Locale category for the character type functions. Depending on the settings of this category, the functions of module `string` dealing with case change their behaviour.

LC_COLLATE

Locale category for sorting strings. The functions `strcoll()` and `strxfrm()` of the `locale` module are affected.

LC_TIME

Locale category for the formatting of time. The function `time.strftime()` follows these conventions.

LC_MONETARY

Locale category for formatting of monetary values. The available options are available from the `localeconv()` function.

LC_MESSAGES

Locale category for message display. Python currently does not support application specific locale-aware messages. Messages displayed by the operating system, like those returned by `os.strerror()` might be affected by this category.

LC_NUMERIC

Locale category for formatting numbers. The functions `format()`, `atoi()`, `atof()` and `str()` of the `locale` module are affected by that category. All other numeric formatting operations are not affected.

LC_ALL

Combination of all locale settings. If this flag is used when the locale is changed, setting the locale for all categories is attempted. If that fails for any category, no category is changed at all. When the locale is retrieved using this flag, a string indicating the setting for all categories is returned. This string can be later used to restore the settings.

CHAR_MAX

This is a symbolic constant used for different values returned by `localeconv()`.

The `nl_langinfo` function accepts one of the following keys. Most descriptions are taken from the corresponding description in the GNU C library.

CODESET

Return a string with the name of the character encoding used in the selected locale.

D_T_FMT

Return a string that can be used as a format string for `strftime(3)` to represent time and date in a locale-specific way.

D_FMT

Return a string that can be used as a format string for `strftime(3)` to represent a date in a locale-specific way.

T_FMT

Return a string that can be used as a format string for `strftime(3)` to represent a time in a locale-specific way.

T_FMT_AMPM

The return value can be used as a format string for 'strftime' to represent time in the am/pm format.

DAY_1 ... DAY_7

Return name of the n-th day of the week. **Warning:** This follows the US convention of `DAY_1` being Sunday, not the international convention (ISO 8601) that Monday is the first day of the week.

ABDAY_1 . . . ABDAY_7

Return abbreviated name of the n-th day of the week.

MON_1 . . . MON_12

Return name of the n-th month.

ABMON_1 . . . ABMON_12

Return abbreviated name of the n-th month.

RADIXCHAR

Return radix character (decimal dot, decimal comma, etc.)

THOUSEP

Return separator character for thousands (groups of three digits).

YESEXPR

Return a regular expression that can be used with the `regex` function to recognize a positive response to a yes/no question. **Warning:** The expression is in the syntax suitable for the `regex()` function from the C library, which might differ from the syntax used in [re](#).

NOEXPR

Return a regular expression that can be used with the `regex(3)` function to recognize a negative response to a yes/no question.

CRNCYSTR

Return the currency symbol, preceded by `"-"` if the symbol should appear before the value, `"+"` if the symbol should appear after the value, or `"."` if the symbol should replace the radix character.

ERA

The return value represents the era used in the current locale.

Most locales do not define this value. An example of a locale which does define this value is the Japanese one. In Japan, the traditional representation of dates includes the name of the era corresponding to the then-emperor's reign.

Normally it should not be necessary to use this value directly. Specifying the `E` modifier in their format strings causes the `strftime` function to use this information. The format of the returned string is not specified, and therefore you should not assume knowledge of it on different systems.

ERA_YEAR

The return value gives the year in the relevant era of the locale.

ERA_D_T_FMT

This return value can be used as a format string for `strftime` to represent dates and times in a locale-specific era-based way.

ERA_D_FMT

This return value can be used as a format string for `strftime` to represent time in a locale-specific era-based way.

ALT_DIGITS

The return value is a representation of up to 100 values used to represent the values 0 to 99.

Example:

```

>>> import locale
>>> loc = locale.getlocale(locale.LC_ALL) # get current locale
>>> locale.setlocale(locale.LC_ALL, 'de_DE') # use German locale; name might vary with platform
>>> locale.strcoll('f\xe4n', 'foo') # compare a string containing an umlaut
>>> locale.setlocale(locale.LC_ALL, '') # use user's preferred locale
>>> locale.setlocale(locale.LC_ALL, 'C') # use default (C) locale
>>> locale.setlocale(locale.LC_ALL, loc) # restore saved locale

```

21.2.1 Background, details, hints, tips and caveats

The C standard defines the locale as a program-wide property that may be relatively expensive to change. On top of that, some implementation are broken in such a way that frequent locale changes may cause core dumps. This makes the locale somewhat painful to use correctly.

Initially, when a program is started, the locale is the ‘C’ locale, no matter what the user’s preferred locale is. The program must explicitly say that it wants the user’s preferred locale settings by calling `setlocale(LC_ALL, '')`.

It is generally a bad idea to call `setlocale()` in some library routine, since as a side effect it affects the entire program. Saving and restoring it is almost as bad: it is expensive and affects other threads that happen to run before the settings have been restored.

If, when coding a module for general use, you need a locale independent version of an operation that is affected by the locale (such as `string.lower()`, or certain formats used with `time.strftime()`), you will have to find a way to do it without using the standard library routine. Even better is convincing yourself that using locale settings is okay. Only as a last resort should you document that your module is not compatible with non-‘C’ locale settings.

The case conversion functions in the `string` module are affected by the locale settings. When a call to the `setlocale()` function changes the `LC_CTYPE` settings, the variables `string.lowercase`, `string.uppercase` and `string.letters` are recalculated. Note that code that uses these variable through ‘from ... import ...’, e.g. `from string import letters`, is not affected by subsequent `setlocale()` calls.

The only way to perform numeric operations according to the locale is to use the special functions defined by this module: `atof()`, `atoi()`, `format()`, `str()`.

21.2.2 For extension writers and programs that embed Python

Extension modules should never call `setlocale()`, except to find out what the current locale is. But since the return value can only be used portably to restore it, that is not very useful (except perhaps to find out whether or not the locale is ‘C’).

When Python code uses the `locale` module to change the locale, this also affects the embedding application. If the embedding application doesn’t want this to happen, it should remove the `_locale` extension module (which does all the work) from the table of built-in modules in the ‘config.c’ file, and make sure that the `_locale` module is not accessible as a shared library.

21.2.3 Access to message catalogs

The `locale` module exposes the C library’s `gettext` interface on systems that provide this interface. It consists of the functions `gettext()`, `dgettext()`, `dcgettext()`, `textdomain()`, `bindtextdomain()`, and `bind_textdomain_codeset()`. These are similar to the same functions in the `gettext` module, but use the C library’s binary format for message catalogs, and the C library’s search algorithms for locating message catalogs.

Python applications should normally find no need to invoke these functions, and should use `gettext` instead. A known exception to this rule are applications that link use additional C libraries which internally invoke `gettext()` or `dcgettext()`. For these applications, it may be necessary to bind the text domain, so that the libraries can properly locate their message catalogs.

Program Frameworks

The modules described in this chapter are frameworks that will largely dictate the structure of your program. Currently the modules described here are all oriented toward writing command-line interfaces.

The full list of modules described in this chapter is:

- `cmd` Build line-oriented command interpreters.
- `shlex` Simple lexical analysis for UNIX shell-like languages.

22.1 `cmd` — Support for line-oriented command interpreters

The `Cmd` class provides a simple framework for writing line-oriented command interpreters. These are often useful for test harnesses, administrative tools, and prototypes that will later be wrapped in a more sophisticated interface.

class `Cmd` (`[completekey[, stdin[, stdout]]`)

A `Cmd` instance or subclass instance is a line-oriented interpreter framework. There is no good reason to instantiate `Cmd` itself; rather, it's useful as a superclass of an interpreter class you define yourself in order to inherit `Cmd`'s methods and encapsulate action methods.

The optional argument `completekey` is the `readline` name of a completion key; it defaults to `Tab`. If `completekey` is not `None` and `readline` is available, command completion is done automatically.

The optional arguments `stdin` and `stdout` specify the input and output file objects that the `Cmd` instance or subclass instance will use for input and output. If not specified, they will default to `sys.stdin` and `sys.stdout`.

Changed in version 2.3: The `stdin` and `stdout` parameters were added.

22.1.1 `Cmd` Objects

A `Cmd` instance has the following methods:

cmdloop (`[intro]`)

Repeatedly issue a prompt, accept input, parse an initial prefix off the received input, and dispatch to action methods, passing them the remainder of the line as argument.

The optional argument is a banner or intro string to be issued before the first prompt (this overrides the `intro` class member).

If the `readline` module is loaded, input will automatically inherit **bash**-like history-list editing (e.g. `Control-P` scrolls back to the last command, `Control-N` forward to the next one, `Control-F` moves the cursor to the right non-destructively, `Control-B` moves the cursor to the left non-destructively, etc.).

An end-of-file on input is passed back as the string `'EOF'`.

An interpreter instance will recognize a command name `'foo'` if and only if it has a method `do_foo()`. As a special case, a line beginning with the character `'?'` is dispatched to the method `do_help()`. As another

special case, a line beginning with the character ‘!’ is dispatched to the method `do_shell()` (if such a method is defined).

This method will return when the `postcmd()` method returns a true value. The *stop* argument to `postcmd()` is the return value from the command’s corresponding `do_*` method.

If completion is enabled, completing commands will be done automatically, and completing of commands args is done by calling `complete_foo()` with arguments *text*, *line*, *begidx*, and *endidx*. *text* is the string prefix we are attempting to match: all returned matches must begin with it. *line* is the current input line with leading whitespace removed, *begidx* and *endidx* are the beginning and ending indexes of the prefix text, which could be used to provide different completion depending upon which position the argument is in.

All subclasses of `Cmd` inherit a predefined `do_help()`. This method, called with an argument ‘*bar*’, invokes the corresponding method `help_bar()`. With no argument, `do_help()` lists all available help topics (that is, all commands with corresponding `help_*` methods), and also lists any undocumented commands.

onecmd(*str*)

Interpret the argument as though it had been typed in response to the prompt. This may be overridden, but should not normally need to be; see the `precmd()` and `postcmd()` methods for useful execution hooks. The return value is a flag indicating whether interpretation of commands by the interpreter should stop. If there is a `do_*` method for the command *str*, the return value of that method is returned, otherwise the return value from the `default()` method is returned.

emptyline()

Method called when an empty line is entered in response to the prompt. If this method is not overridden, it repeats the last nonempty command entered.

default(*line*)

Method called on an input line when the command prefix is not recognized. If this method is not overridden, it prints an error message and returns.

completedefault(*text*, *line*, *begidx*, *endidx*)

Method called to complete an input line when no command-specific `complete_*` method is available. By default, it returns an empty list.

precmd(*line*)

Hook method executed just before the command line *line* is interpreted, but after the input prompt is generated and issued. This method is a stub in `Cmd`; it exists to be overridden by subclasses. The return value is used as the command which will be executed by the `onecmd()` method; the `precmd()` implementation may re-write the command or simply return *line* unchanged.

postcmd(*stop*, *line*)

Hook method executed just after a command dispatch is finished. This method is a stub in `Cmd`; it exists to be overridden by subclasses. *line* is the command line which was executed, and *stop* is a flag which indicates whether execution will be terminated after the call to `postcmd()`; this will be the return value of the `onecmd()` method. The return value of this method will be used as the new value for the internal flag which corresponds to *stop*; returning false will cause interpretation to continue.

preloop()

Hook method executed once when `cmdloop()` is called. This method is a stub in `Cmd`; it exists to be overridden by subclasses.

postloop()

Hook method executed once when `cmdloop()` is about to return. This method is a stub in `Cmd`; it exists to be overridden by subclasses.

Instances of `Cmd` subclasses have some public instance variables:

prompt

The prompt issued to solicit input.

identchars

The string of characters accepted for the command prefix.

lastcmd

The last nonempty command prefix seen.

intro

A string to issue as an intro or banner. May be overridden by giving the `cmdloop()` method an argument.

doc_header

The header to issue if the help output has a section for documented commands.

misc_header

The header to issue if the help output has a section for miscellaneous help topics (that is, there are `help_*()` methods without corresponding `do_*()` methods).

undoc_header

The header to issue if the help output has a section for undocumented commands (that is, there are `do_*()` methods without corresponding `help_*()` methods).

ruler

The character used to draw separator lines under the help-message headers. If empty, no ruler line is drawn. It defaults to '='.

use_rawinput

A flag, defaulting to true. If true, `cmdloop()` uses `raw_input()` to display a prompt and read the next command; if false, `sys.stdout.write()` and `sys.stdin.readline()` are used. (This means that by importing [readline](#), on systems that support it, the interpreter will automatically support **Emacs**-like line editing and command-history keystrokes.)

22.2 shlex — Simple lexical analysis

New in version 1.5.2.

The `shlex` class makes it easy to write lexical analyzers for simple syntaxes resembling that of the UNIX shell. This will often be useful for writing minilanguages, (for example, in run control files for Python applications) or for parsing quoted strings.

Note: The `shlex` module currently does not support Unicode input.

The `shlex` module defines the following functions:

split(*s*[, *comments*])

Split the string *s* using shell-like syntax. If *comments* is `False` (the default), the parsing of comments in the given string will be disabled (setting the `commenters` member of the `shlex` instance to the empty string). This function operates in POSIX mode. New in version 2.3. **Note:** Since the `split()` function instantiates a `shlex` instance, passing `None` for *s* will read the string to split from standard input.

The `shlex` module defines the following class:

class shlex([*instream*[, *infile*[, *posix*]])

A `shlex` instance or subclass instance is a lexical analyzer object. The initialization argument, if present, specifies where to read characters from. It must be a file-/stream-like object with `read()` and `readline()` methods, or a string (strings are accepted since Python 2.3). If no argument is given, input will be taken from `sys.stdin`. The second optional argument is a filename string, which sets the initial value of the `infile` member. If the *instream* argument is omitted or equal to `sys.stdin`, this second argument defaults to "stdin". The *posix* argument was introduced in Python 2.3, and defines the operational mode. When *posix* is not true (default), the `shlex` instance will operate in compatibility mode. When operating in POSIX mode, `shlex` will try to be as close as possible to the POSIX shell parsing rules. See section 22.2.1.

See Also:

Module `ConfigParser` (section 9.2):

Parser for configuration files similar to the Windows ‘.ini’ files.

22.2.1 shlex Objects

A `shlex` instance has the following methods:

get_token()

Return a token. If tokens have been stacked using `push_token()`, pop a token off the stack. Otherwise, read one from the input stream. If reading encounters an immediate end-of-file, `self.eof` is returned (the empty string (‘’) in non-POSIX mode, and `None` in POSIX mode).

push_token(str)

Push the argument onto the token stack.

read_token()

Read a raw token. Ignore the pushback stack, and do not interpret source requests. (This is not ordinarily a useful entry point, and is documented here only for the sake of completeness.)

sourcehook(filename)

When `shlex` detects a source request (see `source` below) this method is given the following token as argument, and expected to return a tuple consisting of a filename and an open file-like object.

Normally, this method first strips any quotes off the argument. If the result is an absolute pathname, or there was no previous source request in effect, or the previous source was a stream (such as `sys.stdin`), the result is left alone. Otherwise, if the result is a relative pathname, the directory part of the name of the file immediately before it on the source inclusion stack is prepended (this behavior is like the way the C preprocessor handles `#include "file.h"`).

The result of the manipulations is treated as a filename, and returned as the first component of the tuple, with `open()` called on it to yield the second component. (Note: this is the reverse of the order of arguments in instance initialization!)

This hook is exposed so that you can use it to implement directory search paths, addition of file extensions, and other namespace hacks. There is no corresponding ‘close’ hook, but a `shlex` instance will call the `close()` method of the sourced input stream when it returns EOF.

For more explicit control of source stacking, use the `push_source()` and `pop_source()` methods.

push_source(stream[, filename])

Push an input source stream onto the input stack. If the filename argument is specified it will later be available for use in error messages. This is the same method used internally by the `sourcehook` method. New in version 2.1.

pop_source()

Pop the last-pushed input source from the input stack. This is the same method used internally when the lexer reaches EOF on a stacked input stream. New in version 2.1.

error_leader([file[, line]])

This method generates an error message leader in the format of a UNIX C compiler error label; the format is ‘“%s”, line %d: ’, where the ‘%s’ is replaced with the name of the current source file and the ‘%d’ with the current input line number (the optional arguments can be used to override these).

This convenience is provided to encourage `shlex` users to generate error messages in the standard, parseable format understood by Emacs and other UNIX tools.

Instances of `shlex` subclasses have some public instance variables which either control lexical analysis or can be used for debugging:

commenters

The string of characters that are recognized as comment beginners. All characters from the comment beginner to end of line are ignored. Includes just ‘#’ by default.

wordchars

The string of characters that will accumulate into multi-character tokens. By default, includes all ASCII alphanumeric characters and underscore.

whitespace

Characters that will be considered whitespace and skipped. Whitespace bounds tokens. By default, includes space, tab, linefeed and carriage-return.

escape

Characters that will be considered as escape. This will be only used in POSIX mode, and includes just `'\'` by default. New in version 2.3.

quotes

Characters that will be considered string quotes. The token accumulates until the same quote is encountered again (thus, different quote types protect each other as in the shell.) By default, includes ASCII single and double quotes.

escapedquotes

Characters in `quotes` that will interpret escape characters defined in `escape`. This is only used in POSIX mode, and includes just `"` by default. New in version 2.3.

whitespace_split

If `True`, tokens will only be split in whitespaces. This is useful, for example, for parsing command lines with `shlex`, getting tokens in a similar way to shell arguments. New in version 2.3.

infile

The name of the current input file, as initially set at class instantiation time or stacked by later source requests. It may be useful to examine this when constructing error messages.

istream

The input stream from which this `shlex` instance is reading characters.

source

This member is `None` by default. If you assign a string to it, that string will be recognized as a lexical-level inclusion request similar to the `'source'` keyword in various shells. That is, the immediately following token will be opened as a filename and input taken from that stream until EOF, at which point the `close()` method of that stream will be called and the input source will again become the original input stream. Source requests may be stacked any number of levels deep.

debug

If this member is numeric and 1 or more, a `shlex` instance will print verbose progress output on its behavior. If you need to use this, you can read the module source code to learn the details.

lineno

Source line number (count of newlines seen so far plus one).

token

The token buffer. It may be useful to examine this when catching exceptions.

eof

Token used to determine end of file. This will be set to the empty string (`' '`), in non-POSIX mode, and to `None` in POSIX mode. New in version 2.3.

22.2.2 Parsing Rules

When operating in non-POSIX mode, `shlex` will try to obey to the following rules.

- Quote characters are not recognized within words (`Do"Not"Separate` is parsed as the single word `Do"Not"Separate`);

- Escape characters are not recognized;
- Enclosing characters in quotes preserve the literal value of all characters within the quotes;
- Closing quotes separate words (`"Do"Separate` is parsed as `"Do"` and `Separate`);
- If `whitespace_split` is `False`, any character not declared to be a word character, whitespace, or a quote will be returned as a single-character token. If it is `True`, `shlex` will only split words in whitespaces;
- EOF is signaled with an empty string (`' '`);
- It's not possible to parse empty strings, even if quoted.

When operating in POSIX mode, `shlex` will try to obey to the following parsing rules.

- Quotes are stripped out, and do not separate words (`"Do"Not"Separate"` is parsed as the single word `DoNotSeparate`);
- Non-quoted escape characters (e.g. `'\'`) preserve the literal value of the next character that follows;
- Enclosing characters in quotes which are not part of `escapedquotes` (e.g. `' '`) preserve the literal value of all characters within the quotes;
- Enclosing characters in quotes which are part of `escapedquotes` (e.g. `" "`) preserves the literal value of all characters within the quotes, with the exception of the characters mentioned in `escape`. The escape characters retain its special meaning only when followed by the quote in use, or the escape character itself. Otherwise the escape character will be considered a normal character.
- EOF is signaled with a `None` value;
- Quoted empty strings (`' '`) are allowed;

Development Tools

The modules described in this chapter help you write software. For example, the `pydoc` module takes a module and generates documentation based on the module's contents. The `doctest` and `unittest` modules contains frameworks for writing unit tests that automatically exercise code and verify that the expected output is produced.

The list of modules described in this chapter is:

<code>pydoc</code>	Documentation generator and online help system.
<code>doctest</code>	A framework for verifying interactive Python examples.
<code>unittest</code>	Unit testing framework for Python.
<code>test</code>	Regression tests package containing the testing suite for Python.
<code>test.test_support</code>	Support for Python regression tests.

23.1 `pydoc` — Documentation generator and online help system

New in version 2.1.

The `pydoc` module automatically generates documentation from Python modules. The documentation can be presented as pages of text on the console, served to a Web browser, or saved to HTML files.

The built-in function `help()` invokes the online help system in the interactive interpreter, which uses `pydoc` to generate its documentation as text on the console. The same text documentation can also be viewed from outside the Python interpreter by running **pydoc** as a script at the operating system's command prompt. For example, running

```
pydoc sys
```

at a shell prompt will display documentation on the `sys` module, in a style similar to the manual pages shown by the UNIX **man** command. The argument to **pydoc** can be the name of a function, module, or package, or a dotted reference to a class, method, or function within a module or module in a package. If the argument to **pydoc** looks like a path (that is, it contains the path separator for your operating system, such as a slash in UNIX), and refers to an existing Python source file, then documentation is produced for that file.

Specifying a **-w** flag before the argument will cause HTML documentation to be written out to a file in the current directory, instead of displaying text on the console.

Specifying a **-k** flag before the argument will search the synopsis lines of all available modules for the keyword given as the argument, again in a manner similar to the UNIX **man** command. The synopsis line of a module is the first line of its documentation string.

You can also use **pydoc** to start an HTTP server on the local machine that will serve documentation to visiting Web browsers. **pydoc -p 1234** will start a HTTP server on port 1234, allowing you to browse the documentation at `http://localhost:1234/` in your preferred Web browser. **pydoc -g** will start the server and additionally

bring up a small `Tkinter`-based graphical interface to help you search for documentation pages.

When `pydoc` generates documentation, it uses the current environment and path to locate modules. Thus, invoking `pydoc spam` documents precisely the version of the module you would get if you started the Python interpreter and typed `'import spam'`.

Module docs for core modules are assumed to reside in <http://www.python.org/doc/current/lib/>. This can be overridden by setting the `PYTHONDOS` environment variable to a different URL or to a local directory containing the Library Reference Manual pages.

23.2 `doctest` — Test interactive Python examples

The `doctest` module searches for pieces of text that look like interactive Python sessions, and then executes those sessions to verify that they work exactly as shown. There are several common ways to use `doctest`:

- To check that a module's docstrings are up-to-date by verifying that all interactive examples still work as documented.
- To perform regression testing by verifying that interactive examples from a test file or a test object work as expected.
- To write tutorial documentation for a package, liberally illustrated with input-output examples. Depending on whether the examples or the expository text are emphasized, this has the flavor of "literate testing" or "executable documentation".

Here's a complete but small example module:


```

"""
This is the "example" module.

The example module supplies one function, factorial(). For example,

>>> factorial(5)
120
"""

def factorial(n):
    """Return the factorial of n, an exact integer >= 0.

    If the result is small enough to fit in an int, return an int.
    Else return a long.

    >>> [factorial(n) for n in range(6)]
    [1, 1, 2, 6, 24, 120]
    >>> [factorial(long(n)) for n in range(6)]
    [1, 1, 2, 6, 24, 120]
    >>> factorial(30)
    265252859812191058636308480000000L
    >>> factorial(30L)
    265252859812191058636308480000000L
    >>> factorial(-1)
    Traceback (most recent call last):
        ...
    ValueError: n must be >= 0

    Factorials of floats are OK, but the float must be an exact integer:
    >>> factorial(30.1)
    Traceback (most recent call last):
        ...
    ValueError: n must be exact integer
    >>> factorial(30.0)
    265252859812191058636308480000000L

    It must also not be ridiculously large:
    >>> factorial(1e100)
    Traceback (most recent call last):
        ...
    OverflowError: n too large
    """

```

```

import math
if not n >= 0:
    raise ValueError("n must be >= 0")
if math.floor(n) != n:
    raise ValueError("n must be exact integer")
if n+1 == n: # catch a value like 1e300
    raise OverflowError("n too large")
result = 1
factor = 2
while factor <= n:
    result *= factor
    factor += 1
return result

def _test():
    import doctest
    doctest.testmod()

if __name__ == "__main__":
    _test()

```

If you run ‘example.py’ directly from the command line, `doctest` works its magic:

```

$ python example.py
$

```

There’s no output! That’s normal, and it means all the examples worked. Pass `-v` to the script, and `doctest` prints a detailed log of what it’s trying, and prints a summary at the end:

```

$ python example.py -v
Trying:
    factorial(5)
Expecting:
    120
ok
Trying:
    [factorial(n) for n in range(6)]
Expecting:
    [1, 1, 2, 6, 24, 120]
ok
Trying:
    [factorial(long(n)) for n in range(6)]
Expecting:
    [1, 1, 2, 6, 24, 120]
ok

```

And so on, eventually ending with:

```

Trying:
    factorial(1e100)
Expecting:
    Traceback (most recent call last):
        ...
    OverflowError: n too large
ok
1 items had no tests:
    __main__._test
2 items passed all tests:
   1 tests in __main__
   8 tests in __main__.factorial
9 tests in 3 items.
9 passed and 0 failed.
Test passed.
$

```

That’s all you need to know to start making productive use of `doctest`! Jump in. The following sections provide full details. Note that there are many examples of doctests in the standard Python test suite and libraries. Especially useful examples can be found in the standard test file ‘Lib/test/test.doctest.py’.

23.2.1 Simple Usage: Checking Examples in Docstrings

The simplest way to start using doctest (but not necessarily the way you’ll continue to do it) is to end each module `M` with:

```

def _test():
    import doctest
    doctest.testmod()

if __name__ == "__main__":
    _test()

```

`doctest` then examines docstrings in module `M`.

Running the module as a script causes the examples in the docstrings to get executed and verified:

```
python M.py
```

This won’t display anything unless an example fails, in which case the failing example(s) and the cause(s) of the failure(s) are printed to stdout, and the final line of output is ‘***Test Failed*** *N* failures.’, where *N* is the number of examples that failed.

Run it with the `-v` switch instead:

```
python M.py -v
```

and a detailed report of all examples tried is printed to standard output, along with assorted summaries at the end.

You can force verbose mode by passing `verbose=True` to `testmod()`, or prohibit it by passing `verbose=False`. In either of those cases, `sys.argv` is not examined by `testmod()` (so passing `-v` or not has no effect).

For more information on `testmod()`, see section 23.2.4.

23.2.2 Simple Usage: Checking Examples in a Text File

Another simple application of `doctest` is testing interactive examples in a text file. This can be done with the `testfile()` function:

```
import doctest
doctest.testfile("example.txt")
```

That short script executes and verifies any interactive Python examples contained in the file ‘example.txt’. The file content is treated as if it were a single giant docstring; the file doesn’t need to contain a Python program! For example, perhaps ‘example.txt’ contains this:

```
The ``example`` module
=====

Using ``factorial``
-----

This is an example text file in reStructuredText format. First import
``factorial`` from the ``example`` module:

    >>> from example import factorial

Now use it:

    >>> factorial(6)
    120
```

Running `doctest.testfile("example.txt")` then finds the error in this documentation:

```
File "./example.txt", line 14, in example.txt
Failed example:
    factorial(6)
Expected:
    120
Got:
    720
```

As with `testmod()`, `testfile()` won’t display anything unless an example fails. If an example does fail, then the failing example(s) and the cause(s) of the failure(s) are printed to stdout, using the same format as `testmod()`.

By default, `testfile()` looks for files in the calling module’s directory. See section 23.2.4 for a description of the optional arguments that can be used to tell it to look for files in other locations.

Like `testmod()`, `testfile()`’s verbosity can be set with the `-v` command-line switch or with the optional keyword argument `verbose`.

For more information on `testfile()`, see section 23.2.4.

23.2.3 How It Works

This section examines in detail how doctest works: which docstrings it looks at, how it finds interactive examples, what execution context it uses, how it handles exceptions, and how option flags can be used to control its behavior. This is the information that you need to know to write doctest examples; for information about actually running doctest on these examples, see the following sections.

Which Docstrings Are Examined?

The module docstring, and all function, class and method docstrings are searched. Objects imported into the module are not searched.

In addition, if `M.__test__` exists and "is true", it must be a dict, and each entry maps a (string) name to a function object, class object, or string. Function and class object docstrings found from `M.__test__` are searched, and strings are treated as if they were docstrings. In output, a key `K` in `M.__test__` appears with name

```
<name of M>.__test__.K
```

Any classes found are recursively searched similarly, to test docstrings in their contained methods and nested classes. Changed in version 2.4: A "private name" concept is deprecated and no longer documented.

How are Docstring Examples Recognized?

In most cases a copy-and-paste of an interactive console session works fine, but doctest isn't trying to do an exact emulation of any specific Python shell. All hard tab characters are expanded to spaces, using 8-column tab stops. If you don't believe tabs should mean that, too bad: don't use hard tabs, or write your own `DocTestParser` class.

Changed in version 2.4: Expanding tabs to spaces is new; previous versions tried to preserve hard tabs, with confusing results.

```
>>> # comments are ignored
>>> x = 12
>>> x
12
>>> if x == 13:
...     print "yes"
... else:
...     print "no"
...     print "NO"
...     print "NO!!!"
...
no
NO
NO!!!
>>>
```

Any expected output must immediately follow the final `'>>> '` or `'... '` line containing the code, and the expected output (if any) extends to the next `'>>> '` or all-whitespace line.

The fine print:

- Expected output cannot contain an all-whitespace line, since such a line is taken to signal the end of expected

output. If expected output does contain a blank line, put `<BLANKLINE>` in your doctest example each place a blank line is expected. Changed in version 2.4: `<BLANKLINE>` was added; there was no way to use expected output containing empty lines in previous versions.

- Output to stdout is captured, but not output to stderr (exception tracebacks are captured via a different means).
- If you continue a line via backslashing in an interactive session, or for any other reason use a backslash, you should use a raw docstring, which will preserve your backslashes exactly as you type them:

```
>>> def f(x):
...     r'''Backslashes in a raw docstring: m\n'''
>>> print f.__doc__
Backslashes in a raw docstring: m\n
```

Otherwise, the backslash will be interpreted as part of the string. For example, the `\"` above would be interpreted as a newline character. Alternatively, you can double each backslash in the doctest version (and not use a raw string):

```
>>> def f(x):
...     '''Backslashes in a raw docstring: m\\n'''
>>> print f.__doc__
Backslashes in a raw docstring: m\n
```

- The starting column doesn't matter:

```
>>> assert "Easy!"
>>> import math
>>> math.floor(1.9)
1.0
```

and as many leading whitespace characters are stripped from the expected output as appeared in the initial `'>>> '` line that started the example.

What's the Execution Context?

By default, each time `doctest` finds a docstring to test, it uses a *shallow copy* of `M`'s globals, so that running tests doesn't change the module's real globals, and so that one test in `M` can't leave behind crumbs that accidentally allow another test to work. This means examples can freely use any names defined at top-level in `M`, and names defined earlier in the docstring being run. Examples cannot see names defined in other docstrings.

You can force use of your own dict as the execution context by passing `globs=your_dict` to `testmod()` or `testfile()` instead.

What About Exceptions?

No problem, provided that the traceback is the only output produced by the example: just paste in the traceback.¹ Since tracebacks contain details that are likely to change rapidly (for example, exact file paths and line numbers), this is one case where doctest works hard to be flexible in what it accepts.

Simple example:

¹Examples containing both expected output and an exception are not supported. Trying to guess where one ends and the other begins is too error-prone, and that also makes for a confusing test.

```
>>> [1, 2, 3].remove(42)
Traceback (most recent call last):
  File "<stdin>", line 1, in ?
ValueError: list.remove(x): x not in list
```

That doctest succeeds if `ValueError` is raised, with the `'list.remove(x): x not in list'` detail as shown.

The expected output for an exception must start with a traceback header, which may be either of the following two lines, indented the same as the first line of the example:

```
Traceback (most recent call last):
Traceback (innermost last):
```

The traceback header is followed by an optional traceback stack, whose contents are ignored by doctest. The traceback stack is typically omitted, or copied verbatim from an interactive session.

The traceback stack is followed by the most interesting part: the line(s) containing the exception type and detail. This is usually the last line of a traceback, but can extend across multiple lines if the exception has a multi-line detail:

```
>>> raise ValueError('multi\n    line\ndetail')
Traceback (most recent call last):
  File "<stdin>", line 1, in ?
ValueError: multi
    line
detail
```

The last three lines (starting with `ValueError`) are compared against the exception's type and detail, and the rest are ignored.

Best practice is to omit the traceback stack, unless it adds significant documentation value to the example. So the last example is probably better as:

```
>>> raise ValueError('multi\n    line\ndetail')
Traceback (most recent call last):
...
ValueError: multi
    line
detail
```

Note that tracebacks are treated very specially. In particular, in the rewritten example, the use of `'...'` is independent of doctest's `ELLIPSIS` option. The ellipsis in that example could be left out, or could just as well be three (or three hundred) commas or digits, or an indented transcript of a Monty Python skit.

Some details you should read once, but won't need to remember:

- Doctest can't guess whether your expected output came from an exception traceback or from ordinary printing. So, e.g., an example that expects `'ValueError: 42 is prime'` will pass whether `ValueError` is actually raised or if the example merely prints that traceback text. In practice, ordinary output rarely begins with a traceback header line, so this doesn't create real problems.
- Each line of the traceback stack (if present) must be indented further than the first line of the example, *or* start

with a non-alphanumeric character. The first line following the traceback header indented the same and starting with an alphanumeric is taken to be the start of the exception detail. Of course this does the right thing for genuine tracebacks.

- When the `IGNORE_EXCEPTION_DETAIL` doctest option is specified, everything following the leftmost colon is ignored.
- The interactive shell omits the traceback header line for some `SyntaxErrors`. But doctest uses the traceback header line to distinguish exceptions from non-exceptions. So in the rare case where you need to test a `SyntaxError` that omits the traceback header, you will need to manually add the traceback header line to your test example.
- For some `SyntaxErrors`, Python displays the character position of the syntax error, using a `^` marker:

```
>>> 1 1
      File "<stdin>", line 1
        1 1
          ^
SyntaxError: invalid syntax
```

Since the lines showing the position of the error come before the exception type and detail, they are not checked by doctest. For example, the following test would pass, even though it puts the `^` marker in the wrong location:

```
>>> 1 1
Traceback (most recent call last):
  File "<stdin>", line 1
    1 1
    ^
SyntaxError: invalid syntax
```

Changed in version 2.4: The ability to handle a multi-line exception detail, and the `IGNORE_EXCEPTION_DETAIL` doctest option, were added.

Option Flags and Directives

A number of option flags control various aspects of doctest's behavior. Symbolic names for the flags are supplied as module constants, which can be or'ed together and passed to various functions. The names can also be used in doctest directives (see below).

The first group of options define test semantics, controlling aspects of how doctest decides whether actual output matches an example's expected output:

DONT_ACCEPT_TRUE_FOR_1

By default, if an expected output block contains just `1`, an actual output block containing just `1` or just `True` is considered to be a match, and similarly for `0` versus `False`. When `DONT_ACCEPT_TRUE_FOR_1` is specified, neither substitution is allowed. The default behavior caters to that Python changed the return type of many functions from integer to boolean; doctests expecting "little integer" output still work in these cases. This option will probably go away, but not for several years.

DONT_ACCEPT_BLANKLINE

By default, if an expected output block contains a line containing only the string `<BLANKLINE>`, then that line will match a blank line in the actual output. Because a genuinely blank line delimits the expected output, this is the only way to communicate that a blank line is expected. When `DONT_ACCEPT_BLANKLINE` is specified, this substitution is not allowed.

NORMALIZE_WHITESPACE

When specified, all sequences of whitespace (blanks and newlines) are treated as equal. Any sequence of whitespace within the expected output will match any sequence of whitespace within the actual output. By default, whitespace must match exactly. `NORMALIZE_WHITESPACE` is especially useful when a line of expected output is very long, and you want to wrap it across multiple lines in your source.

ELLIPSIS

When specified, an ellipsis marker (`. . .`) in the expected output can match any substring in the actual output. This includes substrings that span line boundaries, and empty substrings, so it's best to keep usage of this simple. Complicated uses can lead to the same kinds of "oops, it matched too much!" surprises that `['.*']` is prone to in regular expressions.

IGNORE_EXCEPTION_DETAIL

When specified, an example that expects an exception passes if an exception of the expected type is raised, even if the exception detail does not match. For example, an example expecting `'ValueError: 42'` will pass if the actual exception raised is `'ValueError: 3*14'`, but will fail, e.g., if `TypeError` is raised.

Note that a similar effect can be obtained using `ELLIPSIS`, and `IGNORE_EXCEPTION_DETAIL` may go away when Python releases prior to 2.4 become uninteresting. Until then, `IGNORE_EXCEPTION_DETAIL` is the only clear way to write a doctest that doesn't care about the exception detail yet continues to pass under Python releases prior to 2.4 (doctest directives appear to be comments to them). For example,

```
>>> (1, 2)[3] = 'moo' #doctest: +IGNORE_EXCEPTION_DETAIL
Traceback (most recent call last):
  File "<stdin>", line 1, in ?
TypeError: object doesn't support item assignment
```

passes under Python 2.4 and Python 2.3. The detail changed in 2.4, to say "does not" instead of "doesn't".

SKIP

When specified, do not run the example at all. This can be useful in contexts where doctest examples serve as both documentation and test cases, and an example should be included for documentation purposes, but should not be checked. E.g., the example's output might be random; or the example might depend on resources which would be unavailable to the test driver.

The `SKIP` flag can also be used for temporarily "commenting out" examples.

COMPARISON_FLAGS

A bitmask or'ing together all the comparison flags above.

The second group of options controls how test failures are reported:

REPORT_UDIFF

When specified, failures that involve multi-line expected and actual outputs are displayed using a unified diff.

REPORT_CDIFF

When specified, failures that involve multi-line expected and actual outputs will be displayed using a context diff.

REPORT_NDIFF

When specified, differences are computed by `difflib.Differ`, using the same algorithm as the popular `'ndiff.py'` utility. This is the only method that marks differences within lines as well as across lines. For example, if a line of expected output contains digit 1 where actual output contains letter l, a line is inserted with a caret marking the mismatching column positions.

REPORT_ONLY_FIRST_FAILURE

When specified, display the first failing example in each doctest, but suppress output for all remaining examples. This will prevent doctest from reporting correct examples that break because of earlier failures; but it might also hide incorrect examples that fail independently of the first failure. When `REPORT_ONLY_FIRST_FAILURE` is specified, the remaining examples are still run, and still count towards the total number of failures reported;

only the output is suppressed.

REPORTING_FLAGS

A bitmask or'ing together all the reporting flags above.

”Doctest directives” may be used to modify the option flags for individual examples. Doctest directives are expressed as a special Python comment following an example’s source code:

```
directive          ::=  "#" "doctest:" directive_options
directive_options  ::=  directive_option ("," directive_option)*
directive_option   ::=  on_or_off directive_option_name
on_or_off          ::=  "+" | "-"
directive_option_name ::=  "DONT_ACCEPT_BLANKLINE" | "NORMALIZE_WHITESPACE" | ...
```

Whitespace is not allowed between the + or – and the directive option name. The directive option name can be any of the option flag names explained above.

An example’s doctest directives modify doctest’s behavior for that single example. Use + to enable the named behavior, or – to disable it.

For example, this test passes:

```
>>> print range(20) #doctest: +NORMALIZE_WHITESPACE
[0, 1, 2, 3, 4, 5, 6, 7, 8, 9,
10, 11, 12, 13, 14, 15, 16, 17, 18, 19]
```

Without the directive it would fail, both because the actual output doesn’t have two blanks before the single-digit list elements, and because the actual output is on a single line. This test also passes, and also requires a directive to do so:

```
>>> print range(20) # doctest:+ELLIPSIS
[0, 1, ..., 18, 19]
```

Multiple directives can be used on a single physical line, separated by commas:

```
>>> print range(20) # doctest: +ELLIPSIS, +NORMALIZE_WHITESPACE
[0, 1, ..., 18, 19]
```

If multiple directive comments are used for a single example, then they are combined:

```
>>> print range(20) # doctest: +ELLIPSIS
...                # doctest: +NORMALIZE_WHITESPACE
[0, 1, ..., 18, 19]
```

As the previous example shows, you can add ‘...’ lines to your example containing only directives. This can be useful when an example is too long for a directive to comfortably fit on the same line:

```
>>> print range(5) + range(10,20) + range(30,40) + range(50,60)
... # doctest: +ELLIPSIS
[0, ..., 4, 10, ..., 19, 30, ..., 39, 50, ..., 59]
```

Note that since all options are disabled by default, and directives apply only to the example they appear in, enabling

options (via + in a directive) is usually the only meaningful choice. However, option flags can also be passed to functions that run doctests, establishing different defaults. In such cases, disabling an option via - in a directive can be useful.

Changed in version 2.4: Constants `DONT_ACCEPT_BLANKLINE`, `NORMALIZE_WHITESPACE`, `ELLIPSIS`, `IGNORE_EXCEPTION_DETAIL`, `REPORT_UDIFF`, `REPORT_CDIFF`, `REPORT_NDIFF`, `REPORT_ONLY_FIRST_FAILURE`, `COMPARISON_FLAGS` and `REPORTING_FLAGS` were added; by default `<BLANKLINE>` in expected output matches an empty line in actual output; and doctest directives were added. Changed in version 2.5: Constant `SKIP` was added.

There's also a way to register new option flag names, although this isn't useful unless you intend to extend `doctest` internals via subclassing:

register_optionflag (*name*)

Create a new option flag with a given name, and return the new flag's integer value. `register_optionflag()` can be used when subclassing `OutputChecker` or `DocTestRunner` to create new options that are supported by your subclasses. `register_optionflag` should always be called using the following idiom:

```
MY_FLAG = register_optionflag('MY_FLAG')
```

New in version 2.4.

Warnings

`doctest` is serious about requiring exact matches in expected output. If even a single character doesn't match, the test fails. This will probably surprise you a few times, as you learn exactly what Python does and doesn't guarantee about output. For example, when printing a dict, Python doesn't guarantee that the key-value pairs will be printed in any particular order, so a test like

```
>>> foo()
{"Hermione": "hippogryph", "Harry": "broomstick"}
```

is vulnerable! One workaround is to do

```
>>> foo() == {"Hermione": "hippogryph", "Harry": "broomstick"}
True
```

instead. Another is to do

```
>>> d = foo().items()
>>> d.sort()
>>> d
[('Harry', 'broomstick'), ('Hermione', 'hippogryph')]
```

There are others, but you get the idea.

Another bad idea is to print things that embed an object address, like

```
>>> id(1.0) # certain to fail some of the time
7948648
>>> class C: pass
>>> C() # the default repr() for instances embeds an address
<__main__.C instance at 0x00AC18F0>
```

The ELLIPSIS directive gives a nice approach for the last example:

```
>>> C() #doctest: +ELLIPSIS
<__main__.C instance at 0x...>
```

Floating-point numbers are also subject to small output variations across platforms, because Python defers to the platform C library for float formatting, and C libraries vary widely in quality here.

```
>>> 1./7 # risky
0.14285714285714285
>>> print 1./7 # safer
0.142857142857
>>> print round(1./7, 6) # much safer
0.142857
```

Numbers of the form $I/2 \cdot **J$ are safe across all platforms, and I often contrive doctest examples to produce numbers of that form:

```
>>> 3./4 # utterly safe
0.75
```

Simple fractions are also easier for people to understand, and that makes for better documentation.

23.2.4 Basic API

The functions `testmod()` and `testfile()` provide a simple interface to doctest that should be sufficient for most basic uses. For a less formal introduction to these two functions, see sections 23.2.1 and 23.2.2.

testfile (*filename* [, *module_relative*] [, *name*] [, *package*] [, *globs*] [, *verbose*] [, *report*] [, *optionflags*] [, *extraglobs*] [, *raise_on_error*] [, *parser*] [, *encoding*])

All arguments except *filename* are optional, and should be specified in keyword form.

Test examples in the file named *filename*. Return ‘(*failure_count*, *test_count*)’.

Optional argument *module_relative* specifies how the filename should be interpreted:

- If *module_relative* is `True` (the default), then *filename* specifies an OS-independent module-relative path. By default, this path is relative to the calling module’s directory; but if the *package* argument is specified, then it is relative to that package. To ensure OS-independence, *filename* should use / characters to separate path segments, and may not be an absolute path (i.e., it may not begin with /).
- If *module_relative* is `False`, then *filename* specifies an OS-specific path. The path may be absolute or relative; relative paths are resolved with respect to the current working directory.

Optional argument *name* gives the name of the test; by default, or if `None`, `os.path.basename(filename)`

is used.

Optional argument *package* is a Python package or the name of a Python package whose directory should be used as the base directory for a module-relative filename. If no package is specified, then the calling module's directory is used as the base directory for module-relative filenames. It is an error to specify *package* if *module_relative* is `False`.

Optional argument *globs* gives a dict to be used as the globals when executing examples. A new shallow copy of this dict is created for the doctest, so its examples start with a clean slate. By default, or if `None`, a new empty dict is used.

Optional argument *extraglobs* gives a dict merged into the globals used to execute examples. This works like `dict.update()`: if *globs* and *extraglobs* have a common key, the associated value in *extraglobs* appears in the combined dict. By default, or if `None`, no extra globals are used. This is an advanced feature that allows parameterization of doctests. For example, a doctest can be written for a base class, using a generic name for the class, then reused to test any number of subclasses by passing an *extraglobs* dict mapping the generic name to the subclass to be tested.

Optional argument *verbose* prints lots of stuff if true, and prints only failures if false; by default, or if `None`, it's true if and only if `'-v'` is in `sys.argv`.

Optional argument *report* prints a summary at the end when true, else prints nothing at the end. In verbose mode, the summary is detailed, else the summary is very brief (in fact, empty if all tests passed).

Optional argument *optionflags* or's together option flags. See section 23.2.3.

Optional argument *raise_on_error* defaults to false. If true, an exception is raised upon the first failure or unexpected exception in an example. This allows failures to be post-mortem debugged. Default behavior is to continue running examples.

Optional argument *parser* specifies a `DocTestParser` (or subclass) that should be used to extract tests from the files. It defaults to a normal parser (i.e., `DocTestParser()`).

Optional argument *encoding* specifies an encoding that should be used to convert the file to unicode.

New in version 2.4.

Changed in version 2.5: The parameter *encoding* was added.

testmod (*m* [, *name*] [, *globs*] [, *verbose*] [, *report*] [, *optionflags*] [, *extraglobs*] [, *raise_on_error*] [, *exclude_empty*])

All arguments are optional, and all except for *m* should be specified in keyword form.

Test examples in docstrings in functions and classes reachable from module *m* (or module `__main__` if *m* is not supplied or is `None`), starting with *m*.`__doc__`.

Also test examples reachable from dict *m*.`__test__`, if it exists and is not `None`. *m*.`__test__` maps names (strings) to functions, classes and strings; function and class docstrings are searched for examples; strings are searched directly, as if they were docstrings.

Only docstrings attached to objects belonging to module *m* are searched.

Return `(failure_count, test_count)`.

Optional argument *name* gives the name of the module; by default, or if `None`, *m*.`__name__` is used.

Optional argument *exclude_empty* defaults to false. If true, objects for which no doctests are found are excluded from consideration. The default is a backward compatibility hack, so that code still using `doctest.master.summarize()` in conjunction with `testmod()` continues to get output for objects with no tests. The *exclude_empty* argument to the newer `DocTestFinder` constructor defaults to true.

Optional arguments *extraglobs*, *verbose*, *report*, *optionflags*, *raise_on_error*, and *globs* are the same as for function `testfile()` above, except that *globs* defaults to *m*.`__dict__`.

Changed in version 2.3: The parameter *optionflags* was added.

Changed in version 2.4: The parameters *extraglobs*, *raise_on_error* and *exclude_empty* were added.

Changed in version 2.5: The optional argument *isprivate*, deprecated in 2.4, was removed.

There's also a function to run the doctests associated with a single object. This function is provided for backward compatibility. There are no plans to deprecate it, but it's rarely useful:

run_docstring_examples (*f*, *globs* [, *verbose*] [, *name*] [, *compileflags*] [, *optionflags*])

Test examples associated with object *f*; for example, *f* may be a module, function, or class object.

A shallow copy of dictionary argument *globs* is used for the execution context.

Optional argument *name* is used in failure messages, and defaults to "NoName".

If optional argument *verbose* is true, output is generated even if there are no failures. By default, output is generated only in case of an example failure.

Optional argument *compileflags* gives the set of flags that should be used by the Python compiler when running the examples. By default, or if None, flags are deduced corresponding to the set of future features found in *globs*.

Optional argument *optionflags* works as for function `testfile()` above.

23.2.5 Unittest API

As your collection of doctest'ed modules grows, you'll want a way to run all their doctests systematically. Prior to Python 2.4, `doctest` had a barely documented `Tester` class that supplied a rudimentary way to combine doctests from multiple modules. `Tester` was feeble, and in practice most serious Python testing frameworks build on the `unittest` module, which supplies many flexible ways to combine tests from multiple sources. So, in Python 2.4, `doctest`'s `Tester` class is deprecated, and `doctest` provides two functions that can be used to create `unittest` test suites from modules and text files containing doctests. These test suites can then be run using `unittest` test runners:

```
import unittest
import doctest
import my_module_with_doctests, and_another

suite = unittest.TestSuite()
for mod in my_module_with_doctests, and_another:
    suite.addTest(doctest.DocTestSuite(mod))
runner = unittest.TextTestRunner()
runner.run(suite)
```

There are two main functions for creating `unittest.TestSuite` instances from text files and modules with doctests:

DocFileSuite ([*module_relative*] [, *package*] [, *setUp*] [, *tearDown*] [, *globs*] [, *optionflags*] [, *parser*] [, *encoding*])

Convert doctest tests from one or more text files to a `unittest.TestSuite`.

The returned `unittest.TestSuite` is to be run by the unittest framework and runs the interactive examples in each file. If an example in any file fails, then the synthesized unit test fails, and a `failureException` exception is raised showing the name of the file containing the test and a (sometimes approximate) line number.

Pass one or more paths (as strings) to text files to be examined.

Options may be provided as keyword arguments:

Optional argument *module_relative* specifies how the filenames in *paths* should be interpreted:

- If *module_relative* is True (the default), then each filename specifies an OS-independent module-relative path. By default, this path is relative to the calling module's directory; but if the *package* argument is specified, then it is relative to that package. To ensure OS-independence, each filename should use / characters to separate path segments, and may not be an absolute path (i.e., it may not begin with /).

- If `module_relative` is `False`, then each filename specifies an OS-specific path. The path may be absolute or relative; relative paths are resolved with respect to the current working directory.

Optional argument `package` is a Python package or the name of a Python package whose directory should be used as the base directory for module-relative filenames. If no package is specified, then the calling module's directory is used as the base directory for module-relative filenames. It is an error to specify `package` if `module_relative` is `False`.

Optional argument `setUp` specifies a set-up function for the test suite. This is called before running the tests in each file. The `setUp` function will be passed a `DocTest` object. The `setUp` function can access the test globals as the `globals` attribute of the test passed.

Optional argument `tearDown` specifies a tear-down function for the test suite. This is called after running the tests in each file. The `tearDown` function will be passed a `DocTest` object. The `setUp` function can access the test globals as the `globals` attribute of the test passed.

Optional argument `globals` is a dictionary containing the initial global variables for the tests. A new copy of this dictionary is created for each test. By default, `globals` is a new empty dictionary.

Optional argument `optionflags` specifies the default doctest options for the tests, created by or-ing together individual option flags. See section 23.2.3. See function `set_unittest_reportflags()` below for a better way to set reporting options.

Optional argument `parser` specifies a `DocTestParser` (or subclass) that should be used to extract tests from the files. It defaults to a normal parser (i.e., `DocTestParser()`).

Optional argument `encoding` specifies an encoding that should be used to convert the file to unicode.

New in version 2.4.

Changed in version 2.5: The global `__file__` was added to the globals provided to doctests loaded from a text file using `DocFileSuite()`.

Changed in version 2.5: The parameter `encoding` was added.

DocTestSuite (`[module]`, `[globals]`, `[extraglobs]`, `[test_finder]`, `[setUp]`, `[tearDown]`, `[checker]`)

Convert doctest tests for a module to a `unittest.TestSuite`.

The returned `unittest.TestSuite` is to be run by the unittest framework and runs each doctest in the module. If any of the doctests fail, then the synthesized unit test fails, and a `failureException` exception is raised showing the name of the file containing the test and a (sometimes approximate) line number.

Optional argument `module` provides the module to be tested. It can be a module object or a (possibly dotted) module name. If not specified, the module calling this function is used.

Optional argument `globals` is a dictionary containing the initial global variables for the tests. A new copy of this dictionary is created for each test. By default, `globals` is a new empty dictionary.

Optional argument `extraglobs` specifies an extra set of global variables, which is merged into `globals`. By default, no extra globals are used.

Optional argument `test_finder` is the `DocTestFinder` object (or a drop-in replacement) that is used to extract doctests from the module.

Optional arguments `setUp`, `tearDown`, and `optionflags` are the same as for function `DocFileSuite()` above.

New in version 2.3.

Changed in version 2.4: The parameters `globals`, `extraglobs`, `test_finder`, `setUp`, `tearDown`, and `optionflags` were added; this function now uses the same search technique as `testmod()`.

Under the covers, `DocTestSuite()` creates a `unittest.TestSuite` out of `doctest.DocTestCase` instances, and `DocTestCase` is a subclass of `unittest.TestCase`. `DocTestCase` isn't documented here (it's an internal detail), but studying its code can answer questions about the exact details of `unittest` integration.

Similarly, `DocFileSuite()` creates a `unittest.TestSuite` out of `doctest.DocFileCase` instances, and `DocFileCase` is a subclass of `DocTestCase`.

So both ways of creating a `unittest.TestSuite` run instances of `DocTestCase`. This is important for a subtle reason: when you run `doctest` functions yourself, you can control the `doctest` options in use directly, by passing option flags to `doctest` functions. However, if you're writing a `unittest` framework, `unittest` ultimately controls when and how tests get run. The framework author typically wants to control `doctest` reporting options (perhaps, e.g., specified by command line options), but there's no way to pass options through `unittest` to `doctest` test runners.

For this reason, `doctest` also supports a notion of `doctest` reporting flags specific to `unittest` support, via this function:

set_unittest_reportflags (*flags*)

Set the `doctest` reporting flags to use.

Argument *flags* or's together option flags. See section 23.2.3. Only "reporting flags" can be used.

This is a module-global setting, and affects all future doctests run by module `unittest`: the `runTest()` method of `DocTestCase` looks at the option flags specified for the test case when the `DocTestCase` instance was constructed. If no reporting flags were specified (which is the typical and expected case), `doctest`'s `unittest` reporting flags are or'ed into the option flags, and the option flags so augmented are passed to the `DocTestRunner` instance created to run the doctest. If any reporting flags were specified when the `DocTestCase` instance was constructed, `doctest`'s `unittest` reporting flags are ignored.

The value of the `unittest` reporting flags in effect before the function was called is returned by the function.

New in version 2.4.

23.2.6 Advanced API

The basic API is a simple wrapper that's intended to make `doctest` easy to use. It is fairly flexible, and should meet most users' needs; however, if you require more fine-grained control over testing, or wish to extend `doctest`'s capabilities, then you should use the advanced API.


The advanced API revolves around two container classes, which are used to store the interactive examples extracted from `doctest` cases:

- **Example**: A single python statement, paired with its expected output.
- **DocTest**: A collection of **Examples**, typically extracted from a single docstring or text file.

Additional processing classes are defined to find, parse, and run, and check `doctest` examples:

- **DocTestFinder**: Finds all docstrings in a given module, and uses a **DocTestParser** to create a **DocTest** from every docstring that contains interactive examples.
- **DocTestParser**: Creates a **DocTest** object from a string (such as an object's docstring).
- **DocTestRunner**: Executes the examples in a **DocTest**, and uses an **OutputChecker** to verify their output.
- **OutputChecker**: Compares the actual output from a `doctest` example with the expected output, and decides whether they match.

The relationships among these processing classes are summarized in the following diagram:



DocTest Objects

class DocTest (*examples, globs, name, filename, lineno, docstring*)

A collection of doctest examples that should be run in a single namespace. The constructor arguments are used to initialize the member variables of the same names. New in version 2.4.

`DocTest` defines the following member variables. They are initialized by the constructor, and should not be modified directly.

examples

A list of `Example` objects encoding the individual interactive Python examples that should be run by this test.

globs

The namespace (aka globals) that the examples should be run in. This is a dictionary mapping names to values. Any changes to the namespace made by the examples (such as binding new variables) will be reflected in `globs` after the test is run.

name

A string name identifying the `DocTest`. Typically, this is the name of the object or file that the test was extracted from.

filename

The name of the file that this `DocTest` was extracted from; or `None` if the filename is unknown, or if the `DocTest` was not extracted from a file.

lineno

The line number within `filename` where this `DocTest` begins, or `None` if the line number is unavailable. This line number is zero-based with respect to the beginning of the file.

docstring

The string that the test was extracted from, or `'None'` if the string is unavailable, or if the test was not extracted from a string.

Example Objects

class Example (*source, want[, exc_msg][, lineno][, indent][, options]*)

A single interactive example, consisting of a Python statement and its expected output. The constructor arguments are used to initialize the member variables of the same names. New in version 2.4.

`Example` defines the following member variables. They are initialized by the constructor, and should not be modified directly.

source

A string containing the example's source code. This source code consists of a single Python statement, and always ends with a newline; the constructor adds a newline when necessary.

want

The expected output from running the example's source code (either from stdout, or a traceback in case of exception). `want` ends with a newline unless no output is expected, in which case it's an empty string. The constructor adds a newline when necessary.

exc_msg

The exception message generated by the example, if the example is expected to generate an exception; or `None` if it is not expected to generate an exception. This exception message is compared against the return value of `traceback.format_exception_only()`. `exc_msg` ends with a newline unless it's `None`. The constructor adds a newline if needed.

lineno

The line number within the string containing this example where the example begins. This line number is zero-based with respect to the beginning of the containing string.

indent

The example's indentation in the containing string, i.e., the number of space characters that precede the example's first prompt.

options

A dictionary mapping from option flags to `True` or `False`, which is used to override default options for this example. Any option flags not contained in this dictionary are left at their default value (as specified by the `DocTestRunner`'s `optionflags`). By default, no options are set.

DocTestFinder objects

class DocTestFinder (`[verbose]`, `[parser]`, `[recurse]`, `[exclude_empty]`)

A processing class used to extract the `DocTests` that are relevant to a given object, from its docstring and the docstrings of its contained objects. `DocTests` can currently be extracted from the following object types: modules, functions, classes, methods, staticmethods, classmethods, and properties.

The optional argument `verbose` can be used to display the objects searched by the finder. It defaults to `False` (no output).

The optional argument `parser` specifies the `DocTestParser` object (or a drop-in replacement) that is used to extract doctests from docstrings.

If the optional argument `recurse` is false, then `DocTestFinder.find()` will only examine the given object, and not any contained objects.

If the optional argument `exclude_empty` is false, then `DocTestFinder.find()` will include tests for objects with empty docstrings.

New in version 2.4.

`DocTestFinder` defines the following method:

find (`obj`, `[name]`, `[module]`, `[globs]`, `[extraglobs]`)

Return a list of the `DocTests` that are defined by `obj`'s docstring, or by any of its contained objects' docstrings.

The optional argument `name` specifies the object's name; this name will be used to construct names for the returned `DocTests`. If `name` is not specified, then `obj.__name__` is used.

The optional parameter `module` is the module that contains the given object. If the module is not specified or is `None`, then the test finder will attempt to automatically determine the correct module. The object's module is used:

- As a default namespace, if `globs` is not specified.
- To prevent the `DocTestFinder` from extracting `DocTests` from objects that are imported from other modules. (Contained objects with modules other than `module` are ignored.)
- To find the name of the file containing the object.

- To help find the line number of the object within its file.

If `module` is `False`, no attempt to find the module will be made. This is obscure, of use mostly in testing doctest itself: if `module` is `False`, or is `None` but cannot be found automatically, then all objects are considered to belong to the (non-existent) module, so all contained objects will (recursively) be searched for doctests.

The globals for each `DocTest` is formed by combining *globs* and *extraglobs* (bindings in *extraglobs* override bindings in *globs*). A new shallow copy of the globals dictionary is created for each `DocTest`. If *globs* is not specified, then it defaults to the module's `__dict__`, if specified, or `{}` otherwise. If *extraglobs* is not specified, then it defaults to `{}`.

DocTestParser objects

class DocTestParser ()

A processing class used to extract interactive examples from a string, and use them to create a `DocTest` object. New in version 2.4.

`DocTestParser` defines the following methods:

get_doctest (*string*, *globs*, *name*, *filename*, *lineno*)

Extract all doctest examples from the given string, and collect them into a `DocTest` object.

globs, *name*, *filename*, and *lineno* are attributes for the new `DocTest` object. See the documentation for `DocTest` for more information.

get_examples (*string* [, *name*])

Extract all doctest examples from the given string, and return them as a list of `Example` objects. Line numbers are 0-based. The optional argument *name* is a name identifying this string, and is only used for error messages.

parse (*string* [, *name*])

Divide the given string into examples and intervening text, and return them as a list of alternating `Examples` and strings. Line numbers for the `Examples` are 0-based. The optional argument *name* is a name identifying this string, and is only used for error messages.

DocTestRunner objects

class DocTestRunner ([*checker*] [, *verbose*] [, *optionflags*])

A processing class used to execute and verify the interactive examples in a `DocTest`.

The comparison between expected outputs and actual outputs is done by an `OutputChecker`. This comparison may be customized with a number of option flags; see section 23.2.3 for more information. If the option flags are insufficient, then the comparison may also be customized by passing a subclass of `OutputChecker` to the constructor.

The test runner's display output can be controlled in two ways. First, an output function can be passed to `TestRunner.run()`; this function will be called with strings that should be displayed. It defaults to `sys.stdout.write`. If capturing the output is not sufficient, then the display output can be also customized by subclassing `DocTestRunner`, and overriding the methods `report_start`, `report_success`, `report_unexpected_exception`, and `report_failure`.

The optional keyword argument *checker* specifies the `OutputChecker` object (or drop-in replacement) that should be used to compare the expected outputs to the actual outputs of doctest examples.

The optional keyword argument *verbose* controls the `DocTestRunner`'s verbosity. If *verbose* is `True`, then information is printed about each example, as it is run. If *verbose* is `False`, then only failures are printed. If *verbose* is unspecified, or `None`, then verbose output is used iff the command-line switch `-v` is used.

The optional keyword argument *optionflags* can be used to control how the test runner compares expected output to actual output, and how it displays failures. For more information, see section 23.2.3.

New in version 2.4.

DocTestParser defines the following methods:

report_start (*out*, *test*, *example*)

Report that the test runner is about to process the given example. This method is provided to allow subclasses of DocTestRunner to customize their output; it should not be called directly.

example is the example about to be processed. *test* is the test containing *example*. *out* is the output function that was passed to DocTestRunner.run().

report_success (*out*, *test*, *example*, *got*)

Report that the given example ran successfully. This method is provided to allow subclasses of DocTestRunner to customize their output; it should not be called directly.

example is the example about to be processed. *got* is the actual output from the example. *test* is the test containing *example*. *out* is the output function that was passed to DocTestRunner.run().

report_failure (*out*, *test*, *example*, *got*)

Report that the given example failed. This method is provided to allow subclasses of DocTestRunner to customize their output; it should not be called directly.

example is the example about to be processed. *got* is the actual output from the example. *test* is the test containing *example*. *out* is the output function that was passed to DocTestRunner.run().

report_unexpected_exception (*out*, *test*, *example*, *exc_info*)

Report that the given example raised an unexpected exception. This method is provided to allow subclasses of DocTestRunner to customize their output; it should not be called directly.

example is the example about to be processed. *exc_info* is a tuple containing information about the unexpected exception (as returned by sys.exc_info()). *test* is the test containing *example*. *out* is the output function that was passed to DocTestRunner.run().

run (*test* [, *compileflags*] [, *out*] [, *clear_globs*])

Run the examples in *test* (a DocTest object), and display the results using the writer function *out*.

The examples are run in the namespace *test.globs*. If *clear_globs* is true (the default), then this namespace will be cleared after the test runs, to help with garbage collection. If you would like to examine the namespace after the test completes, then use *clear_globs=False*.

compileflags gives the set of flags that should be used by the Python compiler when running the examples. If not specified, then it will default to the set of future-import flags that apply to *globs*.

The output of each example is checked using the DocTestRunner's output checker, and the results are formatted by the DocTestRunner.report_* methods.

summarize ([*verbose*])

Print a summary of all the test cases that have been run by this DocTestRunner, and return a tuple '(failure_count, test_count)'.

The optional *verbose* argument controls how detailed the summary is. If the verbosity is not specified, then the DocTestRunner's verbosity is used.

OutputChecker objects

class OutputChecker ()

A class used to check the whether the actual output from a doctest example matches the expected output. OutputChecker defines two methods: *check_output*, which compares a given pair of outputs, and returns true if they match; and *output_difference*, which returns a string describing the differences between two outputs. New in version 2.4.

OutputChecker defines the following methods:

check_output (*want*, *got*, *optionflags*)

Return True iff the actual output from an example (*got*) matches the expected output (*want*). These strings are

always considered to match if they are identical; but depending on what option flags the test runner is using, several non-exact match types are also possible. See section 23.2.3 for more information about option flags.

output_difference (*example*, *got*, *optionflags*)

Return a string describing the differences between the expected output for a given example (*example*) and the actual output (*got*). *optionflags* is the set of option flags used to compare *want* and *got*.

23.2.7 Debugging

Doctest provides several mechanisms for debugging doctest examples:

- Several functions convert doctests to executable Python programs, which can be run under the Python debugger, `pdb`.
- The `DebugRunner` class is a subclass of `DocTestRunner` that raises an exception for the first failing example, containing information about that example. This information can be used to perform post-mortem debugging on the example.
- The `unittest` cases generated by `DocTestSuite()` support the `debug()` method defined by `unittest.TestCase`.
- You can add a call to `pdb.set_trace()` in a doctest example, and you'll drop into the Python debugger when that line is executed. Then you can inspect current values of variables, and so on. For example, suppose 'a.py' contains just this module docstring:

```
"""
>>> def f(x):
...     g(x*2)
>>> def g(x):
...     print x+3
...     import pdb; pdb.set_trace()
>>> f(3)
9
"""
```

Then an interactive Python session may look like this:

```

>>> import a, doctest
>>> doctest.testmod(a)
--Return--
> <doctest a[1]>(3)g()->None
-> import pdb; pdb.set_trace()
(Pdb) list
1      def g(x):
2          print x+3
3  ->      import pdb; pdb.set_trace()
[EOF]
(Pdb) print x
6
(Pdb) step
--Return--
> <doctest a[0]>(2)f()->None
-> g(x*2)
(Pdb) list
1      def f(x):
2  ->      g(x*2)
[EOF]
(Pdb) print x
3
(Pdb) step
--Return--
> <doctest a[2]>(1)?()->None
-> f(3)
(Pdb) cont
(0, 3)
>>>

```

Changed in version 2.4: The ability to use `pdb.set_trace()` usefully inside doctests was added.

Functions that convert doctests to Python code, and possibly run the synthesized code under the debugger:

script_from_examples(*s*)

Convert text with examples to a script.

Argument *s* is a string containing doctest examples. The string is converted to a Python script, where doctest examples in *s* are converted to regular code, and everything else is converted to Python comments. The generated script is returned as a string. For example,

```

import doctest
print doctest.script_from_examples(r"""
    Set x and y to 1 and 2.
    >>> x, y = 1, 2

    Print their sum:
    >>> print x+y
    3
""")

```

displays:

```

# Set x and y to 1 and 2.
x, y = 1, 2
#
# Print their sum:
print x+y
# Expected:
## 3

```

This function is used internally by other functions (see below), but can also be useful when you want to transform an interactive Python session into a Python script.

New in version 2.4.

testsource (*module*, *name*)

Convert the doctest for an object to a script.

Argument *module* is a module object, or dotted name of a module, containing the object whose doctests are of interest. Argument *name* is the name (within the module) of the object with the doctests of interest. The result is a string, containing the object's docstring converted to a Python script, as described for `script_from_examples()` above. For example, if module 'a.py' contains a top-level function `f()`, then

```

import a, doctest
print doctest.testsource(a, "a.f")

```

prints a script version of function `f()`'s docstring, with doctests converted to code, and the rest placed in comments.

New in version 2.3.

debug (*module*, *name* [, *pm*])

Debug the doctests for an object.

The *module* and *name* arguments are the same as for function `testsource()` above. The synthesized Python script for the named object's docstring is written to a temporary file, and then that file is run under the control of the Python debugger, `pdb`.

A shallow copy of *module*.`__dict__` is used for both local and global execution context.

Optional argument *pm* controls whether post-mortem debugging is used. If *pm* has a true value, the script file is run directly, and the debugger gets involved only if the script terminates via raising an unhandled exception. If it does, then post-mortem debugging is invoked, via `pdb.post_mortem()`, passing the traceback object from the unhandled exception. If *pm* is not specified, or is false, the script is run under the debugger from the start, via passing an appropriate `execfile()` call to `pdb.run()`.

New in version 2.3.

Changed in version 2.4: The *pm* argument was added.

debug_src (*src* [, *pm*] [, *globs*])

Debug the doctests in a string.

This is like function `debug()` above, except that a string containing doctest examples is specified directly, via the *src* argument.

Optional argument *pm* has the same meaning as in function `debug()` above.

Optional argument *globs* gives a dictionary to use as both local and global execution context. If not specified, or None, an empty dictionary is used. If specified, a shallow copy of the dictionary is used.

New in version 2.4.

The `DebugRunner` class, and the special exceptions it may raise, are of most interest to testing framework authors, and will only be sketched here. See the source code, and especially `DebugRunner`'s docstring (which is a doctest!) for more details:

class **DebugRunner** ([*checker*] [, *verbose*] [, *optionflags*])

A subclass of `DocTestRunner` that raises an exception as soon as a failure is encountered. If an unexpected exception occurs, an `UnexpectedException` exception is raised, containing the test, the example, and the original exception. If the output doesn't match, then a `DocTestFailure` exception is raised, containing the test, the example, and the actual output.

For information about the constructor parameters and methods, see the documentation for `DocTestRunner` in section 23.2.6.

There are two exceptions that may be raised by `DebugRunner` instances:

exception **DocTestFailure** (*test*, *example*, *got*)

An exception thrown by `DocTestRunner` to signal that a doctest example's actual output did not match its expected output. The constructor arguments are used to initialize the member variables of the same names.

`DocTestFailure` defines the following member variables:

test

The `DocTest` object that was being run when the example failed.

example

The `Example` that failed.

got

The example's actual output.

exception **UnexpectedException** (*test*, *example*, *exc_info*)

An exception thrown by `DocTestRunner` to signal that a doctest example raised an unexpected exception. The constructor arguments are used to initialize the member variables of the same names.

`UnexpectedException` defines the following member variables:

test

The `DocTest` object that was being run when the example failed.

example

The `Example` that failed.

exc_info

A tuple containing information about the unexpected exception, as returned by `sys.exc_info()`.

23.2.8 Soapbox

As mentioned in the introduction, `doctest` has grown to have three primary uses:

1. Checking examples in docstrings.
2. Regression testing.
3. Executable documentation / literate testing.

These uses have different requirements, and it is important to distinguish them. In particular, filling your docstrings with obscure test cases makes for bad documentation.

When writing a docstring, choose docstring examples with care. There's an art to this that needs to be learned—it may not be natural at first. Examples should add genuine value to the documentation. A good example can often be worth many words. If done with care, the examples will be invaluable for your users, and will pay back the time it takes to collect them many times over as the years go by and things change. I'm still amazed at how often one of my `doctest` examples stops working after a "harmless" change.

Doctest also makes an excellent tool for regression testing, especially if you don't skimp on explanatory text. By interleaving prose and examples, it becomes much easier to keep track of what's actually being tested, and why. When

a test fails, good prose can make it much easier to figure out what the problem is, and how it should be fixed. It's true that you could write extensive comments in code-based testing, but few programmers do. Many have found that using doctest approaches instead leads to much clearer tests. Perhaps this is simply because doctest makes writing prose a little easier than writing code, while writing comments in code is a little harder. I think it goes deeper than just that: the natural attitude when writing a doctest-based test is that you want to explain the fine points of your software, and illustrate them with examples. This in turn naturally leads to test files that start with the simplest features, and logically progress to complications and edge cases. A coherent narrative is the result, instead of a collection of isolated functions that test isolated bits of functionality seemingly at random. It's a different attitude, and produces different results, blurring the distinction between testing and explaining.

Regression testing is best confined to dedicated objects or files. There are several options for organizing tests:

- Write text files containing test cases as interactive examples, and test the files using `testfile()` or `DocFileSuite()`. This is recommended, although is easiest to do for new projects, designed from the start to use doctest.
- Define functions named `_regrtest_topic` that consist of single docstrings, containing test cases for the named topics. These functions can be included in the same file as the module, or separated out into a separate test file.
- Define a `__test__` dictionary mapping from regression test topics to docstrings containing test cases.

23.3 unittest — Unit testing framework

New in version 2.1.

The Python unit testing framework, sometimes referred to as “PyUnit,” is a Python language version of JUnit, by Kent Beck and Erich Gamma. JUnit is, in turn, a Java version of Kent’s Smalltalk testing framework. Each is the de facto standard unit testing framework for its respective language.

`unittest` supports test automation, sharing of setup and shutdown code for tests, aggregation of tests into collections, and independence of the tests from the reporting framework. The `unittest` module provides classes that make it easy to support these qualities for a set of tests.

To achieve this, `unittest` supports some important concepts:

test fixture

A *test fixture* represents the preparation needed to perform one or more tests, and any associated cleanup actions. This may involve, for example, creating temporary or proxy databases, directories, or starting a server process.

test case

A *test case* is the smallest unit of testing. It checks for a specific response to a particular set of inputs. `unittest` provides a base class, `TestCase`, which may be used to create new test cases.

test suite

A *test suite* is a collection of test cases, test suites, or both. It is used to aggregate tests that should be executed together.

test runner

A *test runner* is a component which orchestrates the execution of tests and provides the outcome to the user. The runner may use a graphical interface, a textual interface, or return a special value to indicate the results of executing the tests.

The test case and test fixture concepts are supported through the `TestCase` and `FunctionTestCase` classes; the former should be used when creating new tests, and the latter can be used when integrating existing test code with

a `unittest`-driven framework. When building test fixtures using `TestCase`, the `setUp()` and `tearDown()` methods can be overridden to provide initialization and cleanup for the fixture. With `FunctionTestCase`, existing functions can be passed to the constructor for these purposes. When the test is run, the fixture initialization is run first; if it succeeds, the cleanup method is run after the test has been executed, regardless of the outcome of the test. Each instance of the `TestCase` will only be used to run a single test method, so a new fixture is created for each test.

Test suites are implemented by the `TestSuite` class. This class allows individual tests and test suites to be aggregated; when the suite is executed, all tests added directly to the suite and in “child” test suites are run.

A test runner is an object that provides a single method, `run()`, which accepts a `TestCase` or `TestSuite` object as a parameter, and returns a result object. The class `TestResult` is provided for use as the result object. `unittest` provides the `TextTestRunner` as an example test runner which reports test results on the standard error stream by default. Alternate runners can be implemented for other environments (such as graphical environments) without any need to derive from a specific class.

See Also:

[Module `doctest`](#) (section 23.2):

Another test-support module with a very different flavor.

Simple Smalltalk Testing: With Patterns

(<http://www.XProgramming.com/testfram.htm>)

Kent Beck’s original paper on testing frameworks using the pattern shared by `unittest`.

23.3.1 Basic example

The `unittest` module provides a rich set of tools for constructing and running tests. This section demonstrates that a small subset of the tools suffice to meet the needs of most users.

Here is a short script to test three functions from the `random` module:

```
import random
import unittest

class TestSequenceFunctions(unittest.TestCase):

    def setUp(self):
        self.seq = range(10)

    def testshuffle(self):
        # make sure the shuffled sequence does not lose any elements
        random.shuffle(self.seq)
        self.seq.sort()
        self.assertEqual(self.seq, range(10))

    def testchoice(self):
        element = random.choice(self.seq)
        self.assertIn(element, self.seq)

    def testsample(self):
        self.assertRaises(ValueError, random.sample, self.seq, 20)
        for element in random.sample(self.seq, 5):
            self.assertIn(element, self.seq)

if __name__ == '__main__':
    unittest.main()
```

A testcase is created by subclassing `unittest.TestCase`. The three individual tests are defined with methods whose names start with the letters ‘test’. This naming convention informs the test runner about which methods represent tests.

The crux of each test is a call to `assertEqual()` to check for an expected result; `assert_()` to verify a condition; or `assertRaises()` to verify that an expected exception gets raised. These methods are used instead of the `assert` statement so the test runner can accumulate all test results and produce a report.

When a `setUp()` method is defined, the test runner will run that method prior to each test. Likewise, if a `tearDown()` method is defined, the test runner will invoke that method after each test. In the example, `setUp()` was used to create a fresh sequence for each test.

The final block shows a simple way to run the tests. `unittest.main()` provides a command line interface to the test script. When run from the command line, the above script produces an output that looks like this:

```
...
-----
Ran 3 tests in 0.000s

OK
```

Instead of `unittest.main()`, there are other ways to run the tests with a finer level of control, less terse output, and no requirement to be run from the command line. For example, the last two lines may be replaced with:

```
suite = unittest.TestLoader().loadTestsFromTestCase(TestSequenceFunctions)
unittest.TextTestRunner(verbosity=2).run(suite)
```

Running the revised script from the interpreter or another script produces the following output:

```
testchoice (__main__.TestSequenceFunctions) ... ok
testsample (__main__.TestSequenceFunctions) ... ok
testshuffle (__main__.TestSequenceFunctions) ... ok

-----
Ran 3 tests in 0.110s

OK
```

The above examples show the most commonly used `unittest` features which are sufficient to meet many everyday testing needs. The remainder of the documentation explores the full feature set from first principles.

23.3.2 Organizing test code

The basic building blocks of unit testing are *test cases* — single scenarios that must be set up and checked for correctness. In `unittest`, test cases are represented by instances of `unittest.TestCase` class. To make your own test cases you must write subclasses of `TestCase`, or use `FunctionTestCase`.

An instance of a `TestCase`-derived class is an object that can completely run a single test method, together with optional set-up and tidy-up code.

The testing code of a `TestCase` instance should be entirely self contained, such that it can be run either in isolation or in arbitrary combination with any number of other test cases.

The simplest `TestCase` subclass will simply override the `runTest()` method in order to perform specific testing code:

```
import unittest

class DefaultWidgetSizeTestCase(unittest.TestCase):
    def runTest(self):
        widget = Widget('The widget')
        self.assertEqual(widget.size(), (50, 50), 'incorrect default size')
```

Note that in order to test something, we use the one of the `assert*()` or `fail*()` methods provided by the `TestCase` base class. If the test fails, an exception will be raised, and `unittest` will identify the test case as a *failure*. Any other exceptions will be treated as *errors*. This helps you identify where the problem is: *failures* are caused by incorrect results - a 5 where you expected a 6. *Errors* are caused by incorrect code - e.g., a `TypeError` caused by an incorrect function call.

The way to run a test case will be described later. For now, note that to construct an instance of such a test case, we call its constructor without arguments:

```
testCase = DefaultWidgetSizeTestCase()
```

Now, such test cases can be numerous, and their set-up can be repetitive. In the above case, constructing a `Widget` in each of 100 `Widget` test case subclasses would mean unsightly duplication.

Luckily, we can factor out such set-up code by implementing a method called `setUp()`, which the testing framework will automatically call for us when we run the test:

```
import unittest

class SimpleWidgetTestCase(unittest.TestCase):
    def setUp(self):
        self.widget = Widget('The widget')

class DefaultWidgetSizeTestCase(SimpleWidgetTestCase):
    def runTest(self):
        self.failUnless(self.widget.size() == (50,50),
                        'incorrect default size')

class WidgetResizeTestCase(SimpleWidgetTestCase):
    def runTest(self):
        self.widget.resize(100,150)
        self.failUnless(self.widget.size() == (100,150),
                        'wrong size after resize')
```

If the `setUp()` method raises an exception while the test is running, the framework will consider the test to have suffered an error, and the `runTest()` method will not be executed.

Similarly, we can provide a `tearDown()` method that tidies up after the `runTest()` method has been run:

```
import unittest

class SimpleWidgetTestCase(unittest.TestCase):
    def setUp(self):
        self.widget = Widget('The widget')

    def tearDown(self):
        self.widget.dispose()
        self.widget = None
```

If `setUp()` succeeded, the `tearDown()` method will be run whether `runTest()` succeeded or not.

Such a working environment for the testing code is called a *fixture*.

Often, many small test cases will use the same fixture. In this case, we would end up subclassing `SimpleWidgetTestCase` into many small one-method classes such as `DefaultWidgetSizeTestCase`. This is time-consuming and discouraging, so in the same vein as JUnit, `unittest` provides a simpler mechanism:

```
import unittest

class WidgetTestCase(unittest.TestCase):
    def setUp(self):
        self.widget = Widget('The widget')

    def tearDown(self):
        self.widget.dispose()
        self.widget = None

    def testDefaultSize(self):
        self.failUnless(self.widget.size() == (50,50),
                        'incorrect default size')

    def testResize(self):
        self.widget.resize(100,150)
        self.failUnless(self.widget.size() == (100,150),
                        'wrong size after resize')
```

Here we have not provided a `runTest()` method, but have instead provided two different test methods. Class instances will now each run one of the `test*()` methods, with `self.widget` created and destroyed separately for each instance. When creating an instance we must specify the test method it is to run. We do this by passing the method name in the constructor:

```
defaultSizeTestCase = WidgetTestCase('testDefaultSize')
resizeTestCase = WidgetTestCase('testResize')
```

Test case instances are grouped together according to the features they test. `unittest` provides a mechanism for this: the *test suite*, represented by `unittest`'s `TestSuite` class:

```
widgetTestSuite = unittest.TestSuite()
widgetTestSuite.addTest(WidgetTestCase('testDefaultSize'))
widgetTestSuite.addTest(WidgetTestCase('testResize'))
```

For the ease of running tests, as we will see later, it is a good idea to provide in each test module a callable object that returns a pre-built test suite:

```
def suite():
    suite = unittest.TestSuite()
    suite.addTest(WidgetTestCase('testDefaultSize'))
    suite.addTest(WidgetTestCase('testResize'))
    return suite
```

or even:

```
def suite():
    tests = ['testDefaultSize', 'testResize']

    return unittest.TestSuite(map(WidgetTestCase, tests))
```

Since it is a common pattern to create a `TestCase` subclass with many similarly named test functions, `unittest` provides a `TestLoader` class that can be used to automate the process of creating a test suite and populating it with individual tests. For example,

```
suite = unittest.TestLoader().loadTestsFromTestCase(WidgetTestCase)
```

will create a test suite that will run `WidgetTestCase.testDefaultSize()` and `WidgetTestCase.testResize`. `TestLoader` uses the 'test' method name prefix to identify test methods automatically.

Note that the order in which the various test cases will be run is determined by sorting the test function names with the built-in `cmp()` function.

Often it is desirable to group suites of test cases together, so as to run tests for the whole system at once. This is easy, since `TestSuite` instances can be added to a `TestSuite` just as `TestCase` instances can be added to a `TestSuite`:

```
suite1 = module1.TheTestSuite()
suite2 = module2.TheTestSuite()
alltests = unittest.TestSuite([suite1, suite2])
```

You can place the definitions of test cases and test suites in the same modules as the code they are to test (such as 'widget.py'), but there are several advantages to placing the test code in a separate module, such as 'test.widget.py':

- The test module can be run standalone from the command line.
- The test code can more easily be separated from shipped code.
- There is less temptation to change test code to fit the code it tests without a good reason.
- Test code should be modified much less frequently than the code it tests.
- Tested code can be refactored more easily.
- Tests for modules written in C must be in separate modules anyway, so why not be consistent?
- If the testing strategy changes, there is no need to change the source code.

23.3.3 Re-using old test code

Some users will find that they have existing test code that they would like to run from `unittest`, without converting every old test function to a `TestCase` subclass.

For this reason, `unittest` provides a `FunctionTestCase` class. This subclass of `TestCase` can be used to wrap an existing test function. Set-up and tear-down functions can also be provided.

Given the following test function:

```
def testSomething():
    something = makeSomething()
    assert something.name is not None
    # ...
```

one can create an equivalent test case instance as follows:

```
testcase = unittest.FunctionTestCase(testSomething)
```

If there are additional set-up and tear-down methods that should be called as part of the test case's operation, they can also be provided like so:

```
testcase = unittest.FunctionTestCase(testSomething,
                                     setUp=makeSomethingDB,
                                     tearDown=deleteSomethingDB)
```

To make migrating existing test suites easier, `unittest` supports tests raising `AssertionError` to indicate test failure. However, it is recommended that you use the explicit `TestCase.fail*()` and `TestCase.assert*()` methods instead, as future versions of `unittest` may treat `AssertionError` differently.

Note: Even though `FunctionTestCase` can be used to quickly convert an existing test base over to a `unittest`-based system, this approach is not recommended. Taking the time to set up proper `TestCase` subclasses will make future test refactorings infinitely easier.

23.3.4 Classes and functions

class `TestCase` (*[methodName]*)

Instances of the `TestCase` class represent the smallest testable units in the `unittest` universe. This class is intended to be used as a base class, with specific tests being implemented by concrete subclasses. This class implements the interface needed by the test runner to allow it to drive the test, and methods that the test code can use to check for and report various kinds of failure.

Each instance of `TestCase` will run a single test method: the method named *methodName*. If you remember, we had an earlier example that went something like this:

```
def suite():
    suite = unittest.TestSuite()
    suite.addTest(WidgetTestCase('testDefaultSize'))
    suite.addTest(WidgetTestCase('testResize'))
    return suite
```

Here, we create two instances of `WidgetTestCase`, each of which runs a single test.

methodName defaults to 'runTest'.

class `FunctionTestCase` (*testFunc*[, *setUp*[, *tearDown*[, *description*]]])

This class implements the portion of the `TestCase` interface which allows the test runner to drive the test, but does not provide the methods which test code can use to check and report errors. This is used to create test cases using legacy test code, allowing it to be integrated into a `unittest`-based test framework.

class `TestSuite` ([*tests*])

This class represents an aggregation of individual tests cases and test suites. The class presents the interface needed by the test runner to allow it to be run as any other test case. Running a `TestSuite` instance is the same as iterating over the suite, running each test individually.

If *tests* is given, it must be an iterable of individual test cases or other test suites that will be used to build the suite initially. Additional methods are provided to add test cases and suites to the collection later on.

class `TestLoader` ()

This class is responsible for loading tests according to various criteria and returning them wrapped in a `TestSuite`. It can load all tests within a given module or `TestCase` subclass.

class `TestResult` ()

This class is used to compile information about which tests have succeeded and which have failed.

defaultTestLoader

Instance of the `TestLoader` class intended to be shared. If no customization of the `TestLoader` is needed, this instance can be used instead of repeatedly creating new instances.

class `TextTestRunner` ([*stream*[, *descriptions*[, *verbosity*]]])

A basic test runner implementation which prints results on standard error. It has a few configurable parameters, but is essentially very simple. Graphical applications which run test suites should provide alternate implementations.

main ([*module*[, *defaultTest*[, *argv*[, *testRunner*[, *testLoader*]]]])

A command-line program that runs a set of tests; this is primarily for making test modules conveniently executable. The simplest use for this function is to include the following line at the end of a test script:

```
if __name__ == '__main__':
    unittest.main()
```

In some cases, the existing tests may have been written using the `doctest` module. If so, that module provides a `DocTestSuite` class that can automatically build `unittest.TestSuite` instances from the existing `doctest`-based tests. New in version 2.3.

23.3.5 TestCase Objects

Each `TestCase` instance represents a single test, but each concrete subclass may be used to define multiple tests — the concrete class represents a single test fixture. The fixture is created and cleaned up for each test case.

`TestCase` instances provide three groups of methods: one group used to run the test, another used by the test implementation to check conditions and report failures, and some inquiry methods allowing information about the test itself to be gathered.

Methods in the first group (running the test) are:

setUp ()

Method called to prepare the test fixture. This is called immediately before calling the test method; any exception raised by this method will be considered an error rather than a test failure. The default implementation does nothing.

tearDown ()

Method called immediately after the test method has been called and the result recorded. This is called even if the test method raised an exception, so the implementation in subclasses may need to be particularly careful about checking internal state. Any exception raised by this method will be considered an error rather than a test failure. This method will only be called if the `setUp()` succeeds, regardless of the outcome of the test method. The default implementation does nothing.

run(`[result]`)

Run the test, collecting the result into the test result object passed as *result*. If *result* is omitted or `None`, a temporary result object is created (by calling the `defaultTestCase()` method) and used; this result object is not returned to `run()`'s caller.

The same effect may be had by simply calling the `TestCase` instance.

debug()

Run the test without collecting the result. This allows exceptions raised by the test to be propagated to the caller, and can be used to support running tests under a debugger.

The test code can use any of the following methods to check for and report failures.

assert_(*expr*[, *msg*])

failUnless(*expr*[, *msg*])

Signal a test failure if *expr* is false; the explanation for the error will be *msg* if given, otherwise it will be `None`.

assertEqual(*first*, *second*[, *msg*])

failUnlessEqual(*first*, *second*[, *msg*])

Test that *first* and *second* are equal. If the values do not compare equal, the test will fail with the explanation given by *msg*, or `None`. Note that using `failUnlessEqual()` improves upon doing the comparison as the first parameter to `failUnless()`: the default value for *msg* can be computed to include representations of both *first* and *second*.

assertNotEqual(*first*, *second*[, *msg*])

failIfEqual(*first*, *second*[, *msg*])

Test that *first* and *second* are not equal. If the values do compare equal, the test will fail with the explanation given by *msg*, or `None`. Note that using `failIfEqual()` improves upon doing the comparison as the first parameter to `failUnless()` is that the default value for *msg* can be computed to include representations of both *first* and *second*.

assertAlmostEqual(*first*, *second*[, *places*[, *msg*]])

failUnlessAlmostEqual(*first*, *second*[, *places*[, *msg*]])

Test that *first* and *second* are approximately equal by computing the difference, rounding to the given number of *places*, and comparing to zero. Note that comparing a given number of decimal places is not the same as comparing a given number of significant digits. If the values do not compare equal, the test will fail with the explanation given by *msg*, or `None`.

assertNotAlmostEqual(*first*, *second*[, *places*[, *msg*]])

failIfAlmostEqual(*first*, *second*[, *places*[, *msg*]])

Test that *first* and *second* are not approximately equal by computing the difference, rounding to the given number of *places*, and comparing to zero. Note that comparing a given number of decimal places is not the same as comparing a given number of significant digits. If the values do not compare equal, the test will fail with the explanation given by *msg*, or `None`.

assertRaises(*exception*, *callable*, ...)

failUnlessRaises(*exception*, *callable*, ...)

Test that an exception is raised when *callable* is called with any positional or keyword arguments that are also passed to `assertRaises()`. The test passes if *exception* is raised, is an error if another exception is raised, or fails if no exception is raised. To catch any of a group of exceptions, a tuple containing the exception classes may be passed as *exception*.

failIf(*expr*[, *msg*])

The inverse of the `failUnless()` method is the `failIf()` method. This signals a test failure if *expr* is true,

with *msg* or `None` for the error message.

fail (*[msg]*)

Signals a test failure unconditionally, with *msg* or `None` for the error message.

failureException

This class attribute gives the exception raised by the `test()` method. If a test framework needs to use a specialized exception, possibly to carry additional information, it must subclass this exception in order to “play fair” with the framework. The initial value of this attribute is `AssertionError`.

Testing frameworks can use the following methods to collect information on the test:

countTestCases ()

Return the number of tests represented by this test object. For `TestCase` instances, this will always be 1.

defaultTestResult ()

Return an instance of the test result class that should be used for this test case class (if no other result instance is provided to the `run()` method).

For `TestCase` instances, this will always be an instance of `TestResult`; subclasses of `TestCase` should override this as necessary.

id ()

Return a string identifying the specific test case. This is usually the full name of the test method, including the module and class name.

shortDescription ()

Returns a one-line description of the test, or `None` if no description has been provided. The default implementation of this method returns the first line of the test method’s docstring, if available, or `None`.

23.3.6 TestSuite Objects

`TestSuite` objects behave much like `TestCase` objects, except they do not actually implement a test. Instead, they are used to aggregate tests into groups of tests that should be run together. Some additional methods are available to add tests to `TestSuite` instances:

addTest (*test*)

Add a `TestCase` or `TestSuite` to the suite.

addTests (*tests*)

Add all the tests from an iterable of `TestCase` and `TestSuite` instances to this test suite.

This is equivalent to iterating over *tests*, calling `addTest()` for each element.

`TestSuite` shares the following methods with `TestCase`:

run (*result*)

Run the tests associated with this suite, collecting the result into the test result object passed as *result*. Note that unlike `TestCase.run()`, `TestSuite.run()` requires the result object to be passed in.

debug ()

Run the tests associated with this suite without collecting the result. This allows exceptions raised by the test to be propagated to the caller and can be used to support running tests under a debugger.

countTestCases ()

Return the number of tests represented by this test object, including all individual tests and sub-suites.

In the typical usage of a `TestSuite` object, the `run()` method is invoked by a `TestRunner` rather than by the end-user test harness.

23.3.7 TestResult Objects

A `TestResult` object stores the results of a set of tests. The `TestCase` and `TestSuite` classes ensure that results are properly recorded; test authors do not need to worry about recording the outcome of tests.

Testing frameworks built on top of `unittest` may want access to the `TestResult` object generated by running a set of tests for reporting purposes; a `TestResult` instance is returned by the `TestRunner.run()` method for this purpose.

`TestResult` instances have the following attributes that will be of interest when inspecting the results of running a set of tests:

errors

A list containing 2-tuples of `TestCase` instances and strings holding formatted tracebacks. Each tuple represents a test which raised an unexpected exception. Changed in version 2.2: Contains formatted tracebacks instead of `sys.exc_info()` results.

failures

A list containing 2-tuples of `TestCase` instances and strings holding formatted tracebacks. Each tuple represents a test where a failure was explicitly signalled using the `TestCase.fail*()` or `TestCase.assert*()` methods. Changed in version 2.2: Contains formatted tracebacks instead of `sys.exc_info()` results.

testsRun

The total number of tests run so far.

wasSuccessful()

Returns `True` if all tests run so far have passed, otherwise returns `False`.

stop()

This method can be called to signal that the set of tests being run should be aborted by setting the `TestResult`'s `shouldStop` attribute to `True`. `TestRunner` objects should respect this flag and return without running any additional tests.

For example, this feature is used by the `TextTestRunner` class to stop the test framework when the user signals an interrupt from the keyboard. Interactive tools which provide `TestRunner` implementations can use this in a similar manner.

The following methods of the `TestResult` class are used to maintain the internal data structures, and may be extended in subclasses to support additional reporting requirements. This is particularly useful in building tools which support interactive reporting while tests are being run.

startTest(test)

Called when the test case *test* is about to be run.

The default implementation simply increments the instance's `testsRun` counter.

stopTest(test)

Called after the test case *test* has been executed, regardless of the outcome.

The default implementation does nothing.

addError(test, err)

Called when the test case *test* raises an unexpected exception *err* is a tuple of the form returned by `sys.exc_info()`: (*type*, *value*, *traceback*).

The default implementation appends (*test*, *err*) to the instance's `errors` attribute.

addFailure(test, err)

Called when the test case *test* signals a failure. *err* is a tuple of the form returned by `sys.exc_info()`: (*type*, *value*, *traceback*).

The default implementation appends (*test*, *err*) to the instance's `failures` attribute.

addSuccess (*test*)

Called when the test case *test* succeeds.

The default implementation does nothing.

23.3.8 TestLoader Objects

The `TestLoader` class is used to create test suites from classes and modules. Normally, there is no need to create an instance of this class; the `unittest` module provides an instance that can be shared as `unittest.defaultTestLoader`. Using a subclass or instance, however, allows customization of some configurable properties.

`TestLoader` objects have the following methods:

loadTestsFromTestCase (*testCaseClass*)

Return a suite of all tests cases contained in the `TestCase`-derived *testCaseClass*.

loadTestsFromModule (*module*)

Return a suite of all tests cases contained in the given module. This method searches *module* for classes derived from `TestCase` and creates an instance of the class for each test method defined for the class.

Warning: While using a hierarchy of `TestCase`-derived classes can be convenient in sharing fixtures and helper functions, defining test methods on base classes that are not intended to be instantiated directly does not play well with this method. Doing so, however, can be useful when the fixtures are different and defined in subclasses.

loadTestsFromName (*name* [, *module*])

Return a suite of all tests cases given a string specifier.

The specifier *name* is a “dotted name” that may resolve either to a module, a test case class, a test method within a test case class, a `TestSuite` instance, or a callable object which returns a `TestCase` or `TestSuite` instance. These checks are applied in the order listed here; that is, a method on a possible test case class will be picked up as “a test method within a test case class”, rather than “a callable object”.

For example, if you have a module `SampleTests` containing a `TestCase`-derived class `SampleTestCase` with three test methods (`test_one()`, `test_two()`, and `test_three()`), the specifier `'SampleTests.SampleTestCase'` would cause this method to return a suite which will run all three test methods. Using the specifier `'SampleTests.SampleTestCase.test_two'` would cause it to return a test suite which will run only the `test_two()` test method. The specifier can refer to modules and packages which have not been imported; they will be imported as a side-effect.

The method optionally resolves *name* relative to the given *module*.

loadTestsFromNames (*names* [, *module*])

Similar to `loadTestsFromName()`, but takes a sequence of names rather than a single name. The return value is a test suite which supports all the tests defined for each name.

getTestCaseNames (*testCaseClass*)

Return a sorted sequence of method names found within *testCaseClass*; this should be a subclass of `TestCase`.

The following attributes of a `TestLoader` can be configured either by subclassing or assignment on an instance:

testMethodPrefix

String giving the prefix of method names which will be interpreted as test methods. The default value is `'test'`.

This affects `getTestCaseNames()` and all the `loadTestsFrom*` methods.

sortTestMethodsUsing

Function to be used to compare method names when sorting them in `getTestCaseNames()` and all the `loadTestsFrom*` methods. The default value is the built-in `cmp()` function; the attribute can also be set to `None` to disable the sort.

suiteClass

Callable object that constructs a test suite from a list of tests. No methods on the resulting object are needed. The default value is the `TestSuite` class.

This affects all the `loadTestsFrom*()` methods.

23.4 `test` — Regression tests package for Python

The `test` package contains all regression tests for Python as well as the modules `test.test_support` and `test.regrtest`. `test.test_support` is used to enhance your tests while `test.regrtest` drives the testing suite.

Each module in the `test` package whose name starts with ‘`test_`’ is a testing suite for a specific module or feature. All new tests should be written using the `unittest` module; using `unittest` is not required but makes the tests more flexible and maintenance of the tests easier. Some older tests are written to use `doctest` and a “traditional” testing style; these styles of tests will not be covered.

See Also:

Module `unittest` (section 23.3):

Writing PyUnit regression tests.

Module `doctest` (section 23.2):

Tests embedded in documentation strings.

23.4.1 Writing Unit Tests for the `test` package

It is preferred that tests for the `test` package use the `unittest` module and follow a few guidelines. One is to name the test module by starting it with ‘`test_`’ and end it with the name of the module being tested. The test methods in the test module should start with ‘`test_`’ and end with a description of what the method is testing. This is needed so that the methods are recognized by the test driver as test methods. Also, no documentation string for the method should be included. A comment (such as ‘`#Tests function returns only True or False`’) should be used to provide documentation for test methods. This is done because documentation strings get printed out if they exist and thus what test is being run is not stated.

A basic boilerplate is often used:

```

import unittest
from test import test_support

class MyTestCase1(unittest.TestCase):

    # Only use setUp() and tearDown() if necessary

    def setUp(self):
        ... code to execute in preparation for tests ...

    def tearDown(self):
        ... code to execute to clean up after tests ...

    def test_feature_one(self):
        # Test feature one.
        ... testing code ...

    def test_feature_two(self):
        # Test feature two.
        ... testing code ...

    ... more test methods ...

class MyTestCase2(unittest.TestCase):
    ... same structure as MyTestCase1 ...

... more test classes ...

def test_main():
    test_support.run_unittest(MyTestCase1,
                              MyTestCase2,
                              ... list other tests ...
                              )

if __name__ == '__main__':
    test_main()

```

This boilerplate code allows the testing suite to be run by `test.regrtest` as well as on its own as a script.

The goal for regression testing is to try to break code. This leads to a few guidelines to be followed:

- The testing suite should exercise all classes, functions, and constants. This includes not just the external API that is to be presented to the outside world but also "private" code.
- Whitebox testing (examining the code being tested when the tests are being written) is preferred. Blackbox testing (testing only the published user interface) is not complete enough to make sure all boundary and edge cases are tested.
- Make sure all possible values are tested including invalid ones. This makes sure that not only all valid values are acceptable but also that improper values are handled correctly.
- Exhaust as many code paths as possible. Test where branching occurs and thus tailor input to make sure as many different paths through the code are taken.
- Add an explicit test for any bugs discovered for the tested code. This will make sure that the error does not crop up again if the code is changed in the future.
- Make sure to clean up after your tests (such as close and remove all temporary files).

- If a test is dependent on a specific condition of the operating system then verify the condition already exists before attempting the test.
- Import as few modules as possible and do it as soon as possible. This minimizes external dependencies of tests and also minimizes possible anomalous behavior from side-effects of importing a module.
- Try to maximize code reuse. On occasion, tests will vary by something as small as what type of input is used. Minimize code duplication by subclassing a basic test class with a class that specifies the input:

```
class TestFuncAcceptsSequences(unittest.TestCase):

    func = mySuperWhammyFunction

    def test_func(self):
        self.func(self.arg)

class AcceptLists(TestFuncAcceptsSequences):
    arg = [1,2,3]

class AcceptStrings(TestFuncAcceptsSequences):
    arg = 'abc'

class AcceptTuples(TestFuncAcceptsSequences):
    arg = (1,2,3)
```

See Also:

Test Driven Development

A book by Kent Beck on writing tests before code.

23.4.2 Running tests using `test.regrtest`

`test.regrtest` can be used as a script to drive Python's regression test suite. Running the script by itself automatically starts running all regression tests in the `test` package. It does this by finding all modules in the package whose name starts with `'test_'`, importing them, and executing the function `test_main()` if present. The names of tests to execute may also be passed to the script. Specifying a single regression test (**`python regrtest.py test.spam.py`**) will minimize output and only print whether the test passed or failed and thus minimize output.

Running `test.regrtest` directly allows what resources are available for tests to use to be set. You do this by using the **`-u`** command-line option. Run **`python regrtest.py -uall`** to turn on all resources; specifying **`all`** as an option for **`-u`** enables all possible resources. If all but one resource is desired (a more common case), a comma-separated list of resources that are not desired may be listed after **`all`**. The command **`python regrtest.py -uall,-audio,-largefile`** will run `test.regrtest` with all resources except the **`audio`** and **`largefile`** resources. For a list of all resources and more command-line options, run **`python regrtest.py -h`**.

Some other ways to execute the regression tests depend on what platform the tests are being executed on. On UNIX, you can run **`make test`** at the top-level directory where Python was built. On Windows, executing **`rt.bat`** from your 'PCBuild' directory will run all regression tests.

23.5 `test.test_support` — Utility functions for tests

The `test.test_support` module provides support for Python's regression tests.

This module defines the following exceptions:

exception `TestFailed`

Exception to be raised when a test fails.

exception `TestSkipped`

Subclass of `TestFailed`. Raised when a test is skipped. This occurs when a needed resource (such as a network connection) is not available at the time of testing.

exception `ResourceDenied`

Subclass of `TestSkipped`. Raised when a resource (such as a network connection) is not available. Raised by the `requires()` function.

The `test.test_support` module defines the following constants:

`verbose`

True when verbose output is enabled. Should be checked when more detailed information is desired about a running test. `verbose` is set by `test.regrtest`.

`have_unicode`

True when Unicode support is available.

`is_jython`

True if the running interpreter is Jython.

`TESTFN`

Set to the path that a temporary file may be created at. Any temporary that is created should be closed and unlinked (removed).

The `test.test_support` module defines the following functions:

`forget(module_name)`

Removes the module named *module_name* from `sys.modules` and deletes any byte-compiled files of the module.

`is_resource_enabled(resource)`

Returns True if *resource* is enabled and available. The list of available resources is only set when `test.regrtest` is executing the tests.

`requires(resource[, msg])`

Raises `ResourceDenied` if *resource* is not available. *msg* is the argument to `ResourceDenied` if it is raised. Always returns true if called by a function whose `__name__` is `'__main__'`. Used when tests are executed by `test.regrtest`.

`findfile(filename)`

Return the path to the file named *filename*. If no match is found *filename* is returned. This does not equal a failure since it could be the path to the file.

`run_unittest(*classes)`

Execute `unittest.TestCase` subclasses passed to the function. The function scans the classes for methods starting with the prefix `'test_'` and executes the tests individually. This is the preferred way to execute tests.

`run_suite(suite[, testclass])`

Execute the `unittest.TestSuite` instance *suite*. The optional argument *testclass* accepts one of the test classes in the suite so as to print out more detailed information on where the testing suite originated from.

The Python Debugger

The module `pdb` defines an interactive source code debugger for Python programs. It supports setting (conditional) breakpoints and single stepping at the source line level, inspection of stack frames, source code listing, and evaluation of arbitrary Python code in the context of any stack frame. It also supports post-mortem debugging and can be called under program control.

The debugger is extensible — it is actually defined as the class `Pdb`. This is currently undocumented but easily understood by reading the source. The extension interface uses the modules `bdb` (undocumented) and `cmd`.

The debugger's prompt is `'(Pdb) '`. Typical usage to run a program under control of the debugger is:

```
>>> import pdb
>>> import mymodule
>>> pdb.run('mymodule.test()')
> <string>(0)?()
(Pdb) continue
> <string>(1)?()
(Pdb) continue
NameError: 'spam'
> <string>(1)?()
(Pdb)
```

`'pdb.py'` can also be invoked as a script to debug other scripts. For example:

```
python -m pdb myscript.py
```

When invoked as a script, `pdb` will automatically enter post-mortem debugging if the program being debugged exits abnormally. After post-mortem debugging (or after normal exit of the program), `pdb` will restart the program. Automatic restarting preserves `pdb`'s state (such as breakpoints) and in most cases is more useful than quitting the debugger upon program's exit. New in version 2.4: Restarting post-mortem behavior added.

Typical usage to inspect a crashed program is:

```

>>> import pdb
>>> import mymodule
>>> mymodule.test()
Traceback (most recent call last):
  File "<stdin>", line 1, in ?
  File "./mymodule.py", line 4, in test
    test2()
  File "./mymodule.py", line 3, in test2
    print spam
NameError: spam
>>> pdb.pm()
> ./mymodule.py(3)test2()
-> print spam
(Pdb)

```

The module defines the following functions; each enters the debugger in a slightly different way:

run (*statement* [, *globals* [, *locals*]])

Execute the *statement* (given as a string) under debugger control. The debugger prompt appears before any code is executed; you can set breakpoints and type ‘continue’, or you can step through the statement using ‘step’ or ‘next’ (all these commands are explained below). The optional *globals* and *locals* arguments specify the environment in which the code is executed; by default the dictionary of the module `__main__` is used. (See the explanation of the `exec` statement or the `eval()` built-in function.)

runeval (*expression* [, *globals* [, *locals*]])

Evaluate the *expression* (given as a string) under debugger control. When `runeval()` returns, it returns the value of the expression. Otherwise this function is similar to `run()`.

runcall (*function* [, *argument*, ...])

Call the *function* (a function or method object, not a string) with the given arguments. When `runcall()` returns, it returns whatever the function call returned. The debugger prompt appears as soon as the function is entered.

set_trace ()

Enter the debugger at the calling stack frame. This is useful to hard-code a breakpoint at a given point in a program, even if the code is not otherwise being debugged (e.g. when an assertion fails).

post_mortem (*traceback*)

Enter post-mortem debugging of the given *traceback* object.

pm ()

Enter post-mortem debugging of the traceback found in `sys.last_traceback`.

24.1 Debugger Commands

The debugger recognizes the following commands. Most commands can be abbreviated to one or two letters; e.g. ‘h(elp)’ means that either ‘h’ or ‘help’ can be used to enter the help command (but not ‘he’ or ‘hel’, nor ‘H’ or ‘Help’ or ‘HELP’). Arguments to commands must be separated by whitespace (spaces or tabs). Optional arguments are enclosed in square brackets (‘[]’) in the command syntax; the square brackets must not be typed. Alternatives in the command syntax are separated by a vertical bar (‘|’).

Entering a blank line repeats the last command entered. Exception: if the last command was a ‘list’ command, the next 11 lines are listed.

Commands that the debugger doesn’t recognize are assumed to be Python statements and are executed in the context of the program being debugged. Python statements can also be prefixed with an exclamation point (‘!’). This is a

powerful way to inspect the program being debugged; it is even possible to change a variable or call a function. When an exception occurs in such a statement, the exception name is printed but the debugger's state is not changed.

Multiple commands may be entered on a single line, separated by `;;`. (A single `;` is not used as it is the separator for multiple commands in a line that is passed to the Python parser.) No intelligence is applied to separating the commands; the input is split at the first `;;` pair, even if it is in the middle of a quoted string.

The debugger supports aliases. Aliases can have parameters which allows one a certain level of adaptability to the context under examination.

If a file `.pdbrc` exists in the user's home directory or in the current directory, it is read in and executed as if it had been typed at the debugger prompt. This is particularly useful for aliases. If both files exist, the one in the home directory is read first and aliases defined there can be overridden by the local file.

h(elp) [*command*] Without argument, print the list of available commands. With a *command* as argument, print help about that command. `'help pdb'` displays the full documentation file; if the environment variable `PAGER` is defined, the file is piped through that command instead. Since the *command* argument must be an identifier, `'help exec'` must be entered to get help on the `!` command.

w(here) Print a stack trace, with the most recent frame at the bottom. An arrow indicates the current frame, which determines the context of most commands.

d(own) Move the current frame one level down in the stack trace (to a newer frame).

u(p) Move the current frame one level up in the stack trace (to an older frame).

b(break) [[*filename:*]*lineno* | *function* [, *condition*]] With a *lineno* argument, set a break there in the current file. With a *function* argument, set a break at the first executable statement within that function. The line number may be prefixed with a filename and a colon, to specify a breakpoint in another file (probably one that hasn't been loaded yet). The file is searched on `sys.path`. Note that each breakpoint is assigned a number to which all the other breakpoint commands refer.

If a second argument is present, it is an expression which must evaluate to true before the breakpoint is honored.

Without argument, list all breaks, including for each breakpoint, the number of times that breakpoint has been hit, the current ignore count, and the associated condition if any.

tbreak [[*filename:*]*lineno* | *function* [, *condition*]] Temporary breakpoint, which is removed automatically when it is first hit. The arguments are the same as `break`.

cl(ear) [*bpnumber* [*bpnumber* ...]] With a space separated list of breakpoint numbers, clear those breakpoints. Without argument, clear all breaks (but first ask confirmation).

disable [*bpnumber* [*bpnumber* ...]] Disables the breakpoints given as a space separated list of breakpoint numbers. Disabling a breakpoint means it cannot cause the program to stop execution, but unlike clearing a breakpoint, it remains in the list of breakpoints and can be (re-)enabled.

enable [*bpnumber* [*bpnumber* ...]] Enables the breakpoints specified.

ignore *bpnumber* [*count*] Sets the ignore count for the given breakpoint number. If *count* is omitted, the ignore count is set to 0. A breakpoint becomes active when the ignore count is zero. When non-zero, the count is decremented each time the breakpoint is reached and the breakpoint is not disabled and any associated condition evaluates to true.

condition *bpnumber* [*condition*] Condition is an expression which must evaluate to true before the breakpoint is honored. If condition is absent, any existing condition is removed; i.e., the breakpoint is made unconditional.

commands [*bpnumber*] Specify a list of commands for breakpoint number *bpnumber*. The commands themselves appear on the following lines. Type a line containing just `'end'` to terminate the commands. An example:

```
(Pdb) commands 1
(com) print some_variable
(com) end
(Pdb)
```

To remove all commands from a breakpoint, type `commands` and follow it immediately with `end`; that is, give no commands.

With no *bnumber* argument, `commands` refers to the last breakpoint set.

You can use breakpoint commands to start your program up again. Simply use the `continue` command, or `step`, or any other command that resumes execution.

Specifying any command resuming execution (currently `continue`, `step`, `next`, `return`, `jump`, `quit` and their abbreviations) terminates the command list (as if that command was immediately followed by `end`). This is because any time you resume execution (even with a simple `next` or `step`), you may encounter another breakpoint—which could have its own command list, leading to ambiguities about which list to execute.

If you use the `'silent'` command in the command list, the usual message about stopping at a breakpoint is not printed. This may be desirable for breakpoints that are to print a specific message and then `continue`. If none of the other commands print anything, you see no sign that the breakpoint was reached.

New in version 2.5.

s(step) Execute the current line, stop at the first possible occasion (either in a function that is called or on the next line in the current function).

n(ext) Continue execution until the next line in the current function is reached or it returns. (The difference between `'next'` and `'step'` is that `'step'` stops inside a called function, while `'next'` executes called functions at (nearly) full speed, only stopping at the next line in the current function.)

r(eturn) Continue execution until the current function returns.

c(ontinue) Continue execution, only stop when a breakpoint is encountered.

j(ump) lineno Set the next line that will be executed. Only available in the bottom-most frame. This lets you jump back and execute code again, or jump forward to skip code that you don't want to run.

It should be noted that not all jumps are allowed — for instance it is not possible to jump into the middle of a `for` loop or out of a `finally` clause.

l(list) [first[, last]] List source code for the current file. Without arguments, list 11 lines around the current line or continue the previous listing. With one argument, list 11 lines around at that line. With two arguments, list the given range; if the second argument is less than the first, it is interpreted as a count.

a(rgs) Print the argument list of the current function.

p expression Evaluate the *expression* in the current context and print its value. **Note:** `'print'` can also be used, but is not a debugger command — this executes the Python `print` statement.

pp expression Like the `'p'` command, except the value of the expression is pretty-printed using the `pprint` module.

alias [name [command]] Creates an alias called *name* that executes *command*. The command must *not* be enclosed in quotes. Replaceable parameters can be indicated by `'%1'`, `'%2'`, and so on, while `'%*'` is replaced by all the parameters. If no command is given, the current alias for *name* is shown. If no arguments are given, all aliases are listed.

Aliases may be nested and can contain anything that can be legally typed at the `pdb` prompt. Note that internal `pdb` commands *can* be overridden by aliases. Such a command is then hidden until the alias is removed. Aliasing is recursively applied to the first word of the command line; all other words in the line are left alone.

As an example, here are two useful aliases (especially when placed in the `'pdbrc'` file):

```
#Print instance variables (usage "pi classInst")
alias pi for k in %1.__dict__.keys(): print "%1.",k,"=",%1.__dict__[k]
#Print instance variables in self
alias ps pi self
```

unalias *name* Deletes the specified alias.

[!]*statement* Execute the (one-line) *statement* in the context of the current stack frame. The exclamation point can be omitted unless the first word of the statement resembles a debugger command. To set a global variable, you can prefix the assignment command with a 'global' command on the same line, e.g.:

```
(Pdb) global list_options; list_options = ['-l']
(Pdb)
```

q(uit) Quit from the debugger. The program being executed is aborted.

24.2 How It Works

Some changes were made to the interpreter:

- `sys.settrace(func)` sets the global trace function
- there can also a local trace function (see later)

Trace functions have three arguments: *frame*, *event*, and *arg*. *frame* is the current stack frame. *event* is a string: 'call', 'line', 'return', 'exception', 'c_call', 'c_return', or 'c_exception'. *arg* depends on the event type.

The global trace function is invoked (with *event* set to 'call') whenever a new local scope is entered; it should return a reference to the local trace function to be used that scope, or `None` if the scope shouldn't be traced.

The local trace function should return a reference to itself (or to another function for further tracing in that scope), or `None` to turn off tracing in that scope.

Instance methods are accepted (and very useful!) as trace functions.

The events have the following meaning:

'call' A function is called (or some other code block entered). The global trace function is called; *arg* is `None`; the return value specifies the local trace function.

'line' The interpreter is about to execute a new line of code (sometimes multiple line events on one line exist). The local trace function is called; *arg* is `None`; the return value specifies the new local trace function.

'return' A function (or other code block) is about to return. The local trace function is called; *arg* is the value that will be returned. The trace function's return value is ignored.

'exception' An exception has occurred. The local trace function is called; *arg* is a triple (*exception*, *value*, *traceback*); the return value specifies the new local trace function.

'c_call' A C function is about to be called. This may be an extension function or a builtin. *arg* is the C function object.

'c_return' A C function has returned. *arg* is `None`.

'c_exception' A C function has thrown an exception. *arg* is `None`.

Note that as an exception is propagated down the chain of callers, an `'exception'` event is generated at each level. For more information on code and frame objects, refer to the [Python Reference Manual](#).

The Python Profilers

Copyright © 1994, by InfoSeek Corporation, all rights reserved.

Written by James Roskind.¹

Permission to use, copy, modify, and distribute this Python software and its associated documentation for any purpose (subject to the restriction in the following sentence) without fee is hereby granted, provided that the above copyright notice appears in all copies, and that both that copyright notice and this permission notice appear in supporting documentation, and that the name of InfoSeek not be used in advertising or publicity pertaining to distribution of the software without specific, written prior permission. This permission is explicitly restricted to the copying and modification of the software to remain in Python, compiled Python, or other languages (such as C) wherein the modified or derived code is exclusively imported into a Python module.

INFOSEEK CORPORATION DISCLAIMS ALL WARRANTIES WITH REGARD TO THIS SOFTWARE, INCLUDING ALL IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS. IN NO EVENT SHALL INFOSEEK CORPORATION BE LIABLE FOR ANY SPECIAL, INDIRECT OR CONSEQUENTIAL DAMAGES OR ANY DAMAGES WHATSOEVER RESULTING FROM LOSS OF USE, DATA OR PROFITS, WHETHER IN AN ACTION OF CONTRACT, NEGLIGENCE OR OTHER TORTIOUS ACTION, ARISING OUT OF OR IN CONNECTION WITH THE USE OR PERFORMANCE OF THIS SOFTWARE.

The profiler was written after only programming in Python for 3 weeks. As a result, it is probably clumsy code, but I don't know for sure yet 'cause I'm a beginner :-). I did work hard to make the code run fast, so that profiling would be a reasonable thing to do. I tried not to repeat code fragments, but I'm sure I did some stuff in really awkward ways at times. Please send suggestions for improvements to: jar@netscape.com. I won't promise *any* support. ...but I'd appreciate the feedback.

25.1 Introduction to the profilers

A *profiler* is a program that describes the run time performance of a program, providing a variety of statistics. This documentation describes the profiler functionality provided in the modules `profile` and `pstats`. This profiler provides *deterministic profiling* of any Python programs. It also provides a series of report generation tools to allow users to rapidly examine the results of a profile operation.

The Python standard library provides three different profilers:

1. `profile`, a pure Python module, described in the sequel. Copyright © 1994, by InfoSeek Corporation. Changed in version 2.4: also reports the time spent in calls to built-in functions and methods.
2. `cProfile`, a module written in C, with a reasonable overhead that makes it suitable for profiling long-running programs. Based on `lsprof`, contributed by Brett Rosen and Ted Czotter. New in version 2.5.

¹Updated and converted to L^AT_EX by Guido van Rossum. Further updated by Armin Rigo to integrate the documentation for the new `cProfile` module of Python 2.5.

3. `hotshot`, a C module focusing on minimizing the overhead while profiling, at the expense of long data post-processing times. Changed in version 2.5: the results should be more meaningful than in the past: the timing core contained a critical bug.

The `profile` and `cProfile` modules export the same interface, so they are mostly interchangeable; `cProfile` has a much lower overhead but is not so far as well-tested and might not be available on all systems. `cProfile` is really a compatibility layer on top of the internal `_lsprof` module. The `hotshot` module is reserved to specialized usages.

25.2 Instant User's Manual

This section is provided for users that “don’t want to read the manual.” It provides a very brief overview, and allows a user to rapidly perform profiling on an existing application.

To profile an application with a main entry point of `foo()`, you would add the following to your module:

```
import cProfile
cProfile.run('foo()')
```

(Use `profile` instead of `cProfile` if the latter is not available on your system.)

The above action would cause `foo()` to be run, and a series of informative lines (the profile) to be printed. The above approach is most useful when working with the interpreter. If you would like to save the results of a profile into a file for later examination, you can supply a file name as the second argument to the `run()` function:

```
import cProfile
cProfile.run('foo()', 'fooprof')
```

The file ‘`cProfile.py`’ can also be invoked as a script to profile another script. For example:

```
python -m cProfile myscript.py
```

‘`cProfile.py`’ accepts two optional arguments on the command line:

```
cProfile.py [-o output_file] [-s sort_order]
```

`-s` only applies to standard output (`-o` is not supplied). Look in the `Stats` documentation for valid sort values.

When you wish to review the profile, you should use the methods in the `pstats` module. Typically you would load the statistics data as follows:

```
import pstats
p = pstats.Stats('fooprof')
```

The class `Stats` (the above code just created an instance of this class) has a variety of methods for manipulating and printing the data that was just read into `p`. When you ran `cProfile.run()` above, what was printed was the result of three method calls:


```
p.strip_dirs().sort_stats(-1).print_stats()
```

The first method removed the extraneous path from all the module names. The second method sorted all the entries according to the standard module/line/name string that is printed. The third method printed out all the statistics. You might try the following sort calls:

```
p.sort_stats('name')
p.print_stats()
```

The first call will actually sort the list by function name, and the second call will print out the statistics. The following are some interesting calls to experiment with:

```
p.sort_stats('cumulative').print_stats(10)
```

This sorts the profile by cumulative time in a function, and then only prints the ten most significant lines. If you want to understand what algorithms are taking time, the above line is what you would use.

If you were looking to see what functions were looping a lot, and taking a lot of time, you would do:

```
p.sort_stats('time').print_stats(10)
```

to sort according to time spent within each function, and then print the statistics for the top ten functions.

You might also try:

```
p.sort_stats('file').print_stats('__init__')
```

This will sort all the statistics by file name, and then print out statistics for only the class init methods (since they are spelled with `__init__` in them). As one final example, you could try:

```
p.sort_stats('time', 'cum').print_stats(.5, 'init')
```

This line sorts statistics with a primary key of time, and a secondary key of cumulative time, and then prints out some of the statistics. To be specific, the list is first culled down to 50% (re: `.5`) of its original size, then only lines containing `init` are maintained, and that sub-sub-list is printed.

If you wondered what functions called the above functions, you could now (`p` is still sorted according to the last criteria) do:

```
p.print_callers(.5, 'init')
```

and you would get a list of callers for each of the listed functions.

If you want more functionality, you're going to have to read the manual, or guess what the following functions do:

```
p.print_callees()
p.add('fooprof')
```

Invoked as a script, the `pstats` module is a statistics browser for reading and examining profile dumps. It has a simple line-oriented interface (implemented using `cmd`) and interactive help.

25.3 What Is Deterministic Profiling?

Deterministic profiling is meant to reflect the fact that all *function call*, *function return*, and *exception* events are monitored, and precise timings are made for the intervals between these events (during which time the user's code is executing). In contrast, *statistical profiling* (which is not done by this module) randomly samples the effective instruction pointer, and deduces where time is being spent. The latter technique traditionally involves less overhead (as the code does not need to be instrumented), but provides only relative indications of where time is being spent.

In Python, since there is an interpreter active during execution, the presence of instrumented code is not required to do deterministic profiling. Python automatically provides a *hook* (optional callback) for each event. In addition, the interpreted nature of Python tends to add so much overhead to execution, that deterministic profiling tends to only add small processing overhead in typical applications. The result is that deterministic profiling is not that expensive, yet provides extensive run time statistics about the execution of a Python program.

Call count statistics can be used to identify bugs in code (surprising counts), and to identify possible inline-expansion points (high call counts). Internal time statistics can be used to identify “hot loops” that should be carefully optimized. Cumulative time statistics should be used to identify high level errors in the selection of algorithms. Note that the unusual handling of cumulative times in this profiler allows statistics for recursive implementations of algorithms to be directly compared to iterative implementations.

25.4 Reference Manual – `profile` and `cProfile`

The primary entry point for the profiler is the global function `profile.run()` (resp. `cProfile.run()`). It is typically used to create any profile information. The reports are formatted and printed using methods of the class `pstats.Stats`. The following is a description of all of these standard entry points and functions. For a more in-depth view of some of the code, consider reading the later section on Profiler Extensions, which includes discussion of how to derive “better” profilers from the classes presented, or reading the source code for these modules.

run (*command* [, *filename*])

This function takes a single argument that can be passed to the `exec` statement, and an optional file name. In all cases this routine attempts to `exec` its first argument, and gather profiling statistics from the execution. If no file name is present, then this function automatically prints a simple profiling report, sorted by the standard name string (file/line/function-name) that is presented in each line. The following is a typical output from such a call:

```
2706 function calls (2004 primitive calls) in 4.504 CPU seconds

Ordered by: standard name

ncalls  tottime  percall  cumtime  percall filename:lineno(function)
      2     0.006    0.003    0.953    0.477 pobject.py:75(save_objects)
    43/3     0.533    0.012    0.749    0.250 pobject.py:99(evaluate)
...
```

The first line indicates that 2706 calls were monitored. Of those calls, 2004 were *primitive*. We define *primi-*

tive to mean that the call was not induced via recursion. The next line: `Ordered by: standard name`, indicates that the text string in the far right column was used to sort the output. The column headings include:

ncalls for the number of calls,

tottime for the total time spent in the given function (and excluding time made in calls to sub-functions),

percall is the quotient of `tottime` divided by `ncalls`

cumtime is the total time spent in this and all subfunctions (from invocation till exit). This figure is accurate *even* for recursive functions.

percall is the quotient of `cumtime` divided by primitive calls

filename:lineno(function) provides the respective data of each function

When there are two numbers in the first column (for example, ‘43/3’), then the latter is the number of primitive calls, and the former is the actual number of calls. Note that when the function does not recurse, these two values are the same, and only the single figure is printed.

runcatx (*command*, *globals*, *locals*[, *filename*])

This function is similar to `run()`, with added arguments to supply the `globals` and `locals` dictionaries for the *command* string.

Analysis of the profiler data is done using the `Stats` class.

Note: The `Stats` class is defined in the `pstats` module.

class Stats (*filename*[, *stream*=`sys.stdout`[, ...]])

This class constructor creates an instance of a “statistics object” from a *filename* (or set of filenames). `Stats` objects are manipulated by methods, in order to print useful reports. You may specify an alternate output stream by giving the keyword argument, *stream*.

The file selected by the above constructor must have been created by the corresponding version of `profile` or `cProfile`. To be specific, there is *no* file compatibility guaranteed with future versions of this profiler, and there is no compatibility with files produced by other profilers.

If several files are provided, all the statistics for identical functions will be coalesced, so that an overall view of several processes can be considered in a single report. If additional files need to be combined with data in an existing `Stats` object, the `add()` method can be used.

Changed in version 2.5: The *stream* parameter was added.

25.4.1 The Stats Class

`Stats` objects have the following methods:

strip_dirs ()

This method for the `Stats` class removes all leading path information from file names. It is very useful in reducing the size of the printout to fit within (close to) 80 columns. This method modifies the object, and the stripped information is lost. After performing a strip operation, the object is considered to have its entries in a “random” order, as it was just after object initialization and loading. If `strip_dirs()` causes two function names to be indistinguishable (they are on the same line of the same filename, and have the same function name), then the statistics for these two entries are accumulated into a single entry.

add (*filename*[, ...])

This method of the `Stats` class accumulates additional profiling information into the current profiling object. Its arguments should refer to filenames created by the corresponding version of `profile.run()` or `cProfile.run()`. Statistics for identically named (re: file, line, name) functions are automatically accumulated into single function statistics.

dump_stats (*filename*)

Save the data loaded into the `Stats` object to a file named *filename*. The file is created if it does not exist, and is overwritten if it already exists. This is equivalent to the method of the same name on the `profile.Profile` and `cProfile.Profile` classes. New in version 2.3.

sort_stats (*key*[, ...])

This method modifies the `Stats` object by sorting it according to the supplied criteria. The argument is typically a string identifying the basis of a sort (example: `'time'` or `'name'`).

When more than one key is provided, then additional keys are used as secondary criteria when there is equality in all keys selected before them. For example, `sort_stats('name', 'file')` will sort all the entries according to their function name, and resolve all ties (identical function names) by sorting by file name.

Abbreviations can be used for any key names, as long as the abbreviation is unambiguous. The following are the keys currently defined:

Valid Arg	Meaning
<code>'calls'</code>	call count
<code>'cumulative'</code>	cumulative time
<code>'file'</code>	file name
<code>'module'</code>	file name
<code>'pcalls'</code>	primitive call count
<code>'line'</code>	line number
<code>'name'</code>	function name
<code>'nfl'</code>	name/file/line
<code>'stdname'</code>	standard name
<code>'time'</code>	internal time

Note that all sorts on statistics are in descending order (placing most time consuming items first), where as name, file, and line number searches are in ascending order (alphabetical). The subtle distinction between `'nfl'` and `'stdname'` is that the standard name is a sort of the name as printed, which means that the embedded line numbers get compared in an odd way. For example, lines 3, 20, and 40 would (if the file names were the same) appear in the string order 20, 3 and 40. In contrast, `'nfl'` does a numeric compare of the line numbers. In fact, `sort_stats('nfl')` is the same as `sort_stats('name', 'file', 'line')`.

For backward-compatibility reasons, the numeric arguments `-1`, `0`, `1`, and `2` are permitted. They are interpreted as `'stdname'`, `'calls'`, `'time'`, and `'cumulative'` respectively. If this old style format (numeric) is used, only one sort key (the numeric key) will be used, and additional arguments will be silently ignored.

reverse_order ()

This method for the `Stats` class reverses the ordering of the basic list within the object. Note that by default ascending vs descending order is properly selected based on the sort key of choice.

print_stats ([*restriction*, ...])

This method for the `Stats` class prints out a report as described in the `profile.run()` definition.

The order of the printing is based on the last `sort_stats()` operation done on the object (subject to caveats in `add()` and `strip_dirs()`).

The arguments provided (if any) can be used to limit the list down to the significant entries. Initially, the list is taken to be the complete set of profiled functions. Each restriction is either an integer (to select a count of lines), or a decimal fraction between 0.0 and 1.0 inclusive (to select a percentage of lines), or a regular expression (to pattern match the standard name that is printed; as of Python 1.5b1, this uses the Perl-style regular expression syntax defined by the `re` module). If several restrictions are provided, then they are applied sequentially. For example:

```
print_stats(.1, 'foo:')
```

would first limit the printing to first 10% of list, and then only print functions that were part of filename `.*foo:*`. In contrast, the command:

```
print_stats('foo:', .1)
```

would limit the list to all functions having file names `.*foo:`, and then proceed to only print the first 10% of them.

print_callers (*[restriction, ...]*)

This method for the `Stats` class prints a list of all functions that called each function in the profiled database. The ordering is identical to that provided by `print_stats()`, and the definition of the restricting argument is also identical. Each caller is reported on its own line. The format differs slightly depending on the profiler that produced the stats:

- With `profile`, a number is shown in parentheses after each caller to show how many times this specific call was made. For convenience, a second non-parenthesized number repeats the cumulative time spent in the function at the right.
- With `cProfile`, each caller is preceded by three numbers: the number of times this specific call was made, and the total and cumulative times spent in the current function while it was invoked by this specific caller.

print_callees (*[restriction, ...]*)

This method for the `Stats` class prints a list of all function that were called by the indicated function. Aside from this reversal of direction of calls (re: called vs was called by), the arguments and ordering are identical to the `print_callers()` method.

25.5 Limitations

One limitation has to do with accuracy of timing information. There is a fundamental problem with deterministic profilers involving accuracy. The most obvious restriction is that the underlying “clock” is only ticking at a rate (typically) of about .001 seconds. Hence no measurements will be more accurate than the underlying clock. If enough measurements are taken, then the “error” will tend to average out. Unfortunately, removing this first error induces a second source of error.

The second problem is that it “takes a while” from when an event is dispatched until the profiler’s call to get the time actually *gets* the state of the clock. Similarly, there is a certain lag when exiting the profiler event handler from the time that the clock’s value was obtained (and then squirreled away), until the user’s code is once again executing. As a result, functions that are called many times, or call many functions, will typically accumulate this error. The error that accumulates in this fashion is typically less than the accuracy of the clock (less than one clock tick), but it *can* accumulate and become very significant.

The problem is more important with `profile` than with the lower-overhead `cProfile`. For this reason, `profile` provides a means of calibrating itself for a given platform so that this error can be probabilistically (on the average) removed. After the profiler is calibrated, it will be more accurate (in a least square sense), but it will sometimes produce negative numbers (when call counts are exceptionally low, and the gods of probability work against you :-).) Do *not* be alarmed by negative numbers in the profile. They should *only* appear if you have calibrated your profiler, and the results are actually better than without calibration.

25.6 Calibration

The profiler of the `profile` module subtracts a constant from each event handling time to compensate for the overhead of calling the time function, and socking away the results. By default, the constant is 0. The following procedure can be used to obtain a better constant for a given platform (see discussion in section Limitations above).

```
import profile
pr = profile.Profile()
for i in range(5):
    print pr.calibrate(10000)
```

The method executes the number of Python calls given by the argument, directly and again under the profiler, measuring the time for both. It then computes the hidden overhead per profiler event, and returns that as a float. For example, on an 800 MHz Pentium running Windows 2000, and using Python's `time.clock()` as the timer, the magical number is about `12.5e-6`.

The object of this exercise is to get a fairly consistent result. If your computer is *very* fast, or your timer function has poor resolution, you might have to pass 100000, or even 1000000, to get consistent results.

When you have a consistent answer, there are three ways you can use it:²

```
import profile

# 1. Apply computed bias to all Profile instances created hereafter.
profile.Profile.bias = your_computed_bias

# 2. Apply computed bias to a specific Profile instance.
pr = profile.Profile()
pr.bias = your_computed_bias

# 3. Specify computed bias in instance constructor.
pr = profile.Profile(bias=your_computed_bias)
```

If you have a choice, you are better off choosing a smaller constant, and then your results will “less often” show up as negative in profile statistics.

25.7 Extensions — Deriving Better Profilers

The `Profile` class of both modules, `profile` and `cProfile`, were written so that derived classes could be developed to extend the profiler. The details are not described here, as doing this successfully requires an expert understanding of how the `Profile` class works internally. Study the source code of the module carefully if you want to pursue this.

If all you want to do is change how current time is determined (for example, to force use of wall-clock time or elapsed process time), pass the timing function you want to the `Profile` class constructor:

```
pr = profile.Profile(your_time_func)
```

The resulting profiler will then call `your_time_func()`.

`profile.Profile` `your_time_func()` should return a single number, or a list of numbers whose sum is the current time (like what `os.times()` returns). If the function returns a single time number, or the list of returned numbers has length 2, then you will get an especially fast version of the dispatch routine.

Be warned that you should calibrate the profiler class for the timer function that you choose. For most machines,

²Prior to Python 2.2, it was necessary to edit the profiler source code to embed the bias as a literal number. You still can, but that method is no longer described, because no longer needed.

a timer that returns a lone integer value will provide the best results in terms of low overhead during profiling. (`os.times()` is *pretty* bad, as it returns a tuple of floating point values). If you want to substitute a better timer in the cleanest fashion, derive a class and hardwire a replacement dispatch method that best handles your timer call, along with the appropriate calibration constant.

cProfile.Profile `your_time_func()` should return a single number. If it returns plain integers, you can also invoke the class constructor with a second argument specifying the real duration of one unit of time. For example, if `your_integer_time_func()` returns times measured in thousands of seconds, you would construct the `Profile` instance as follows:

```
pr = profile.Profile(your_integer_time_func, 0.001)
```

As the `cProfile.Profile` class cannot be calibrated, custom timer functions should be used with care and should be as fast as possible. For the best results with a custom timer, it might be necessary to hard-code it in the C source of the internal `_lsprof` module.

25.8 hotshot — High performance logging profiler

New in version 2.2.

This module provides a nicer interface to the `_hotshot` C module. Hotshot is a replacement for the existing `profile` module. As it's written mostly in C, it should result in a much smaller performance impact than the existing `profile` module.

Note: The `hotshot` module focuses on minimizing the overhead while profiling, at the expense of long data post-processing times. For common usages it is recommended to use `cProfile` instead. `hotshot` is not maintained and might be removed from the standard library in the future.

Changed in version 2.5: the results should be more meaningful than in the past: the timing core contained a critical bug.

Warning: The `hotshot` profiler does not yet work well with threads. It is useful to use an unthreaded script to run the profiler over the code you're interested in measuring if at all possible.

class Profile (`logfile` [, `lineevents` [, `linetimings`]])

The profiler object. The argument `logfile` is the name of a log file to use for logged profile data. The argument `lineevents` specifies whether to generate events for every source line, or just on function call/return. It defaults to 0 (only log function call/return). The argument `linetimings` specifies whether to record timing information. It defaults to 1 (store timing information).

25.8.1 Profile Objects

Profile objects have the following methods:

addinfo (`key`, `value`)

Add an arbitrary labelled value to the profile output.

close ()

Close the logfile and terminate the profiler.

fileno ()

Return the file descriptor of the profiler's log file.

run (*cmd*)
 Profile an `exec`-compatible string in the script environment. The globals from the `__main__` module are used as both the globals and locals for the script.

runcall (*func*, **args*, ***keywords*)
 Profile a single call of a callable. Additional positional and keyword arguments may be passed along; the result of the call is returned, and exceptions are allowed to propagate cleanly, while ensuring that profiling is disabled on the way out.

runctx (*cmd*, *globals*, *locals*)
 Evaluate an `exec`-compatible string in a specific environment. The string is compiled before profiling begins.

start ()
 Start the profiler.

stop ()
 Stop the profiler.

25.8.2 Using hotshot data

New in version 2.2.

This module loads hotshot profiling data into the standard `pstats` `Stats` objects.

load (*filename*)
 Load hotshot data from *filename*. Returns an instance of the `pstats.Stats` class.

See Also:

[Module `profile`](#) (section 25.4):
 The `profile` module's `Stats` class

25.8.3 Example Usage

Note that this example runs the python “benchmark” `pystones`. It can take some time to run, and will produce large output files.

```
>>> import hotshot, hotshot.stats, test.pystone
>>> prof = hotshot.Profile("stones.prof")
>>> benchtime, stones = prof.runcall(test.pystone.pystones)
>>> prof.close()
>>> stats = hotshot.stats.load("stones.prof")
>>> stats.strip_dirs()
>>> stats.sort_stats('time', 'calls')
>>> stats.print_stats(20)
      850004 function calls in 10.090 CPU seconds

Ordered by: internal time, call count
```

ncalls	tottime	percall	cumtime	percall	filename:lineno(function)
1	3.295	3.295	10.090	10.090	pystone.py:79(Proc0)
150000	1.315	0.000	1.315	0.000	pystone.py:203(Proc7)
50000	1.313	0.000	1.463	0.000	pystone.py:229(Func2)
.					
.					
.					

25.9 `timeit` — Measure execution time of small code snippets

New in version 2.3.

This module provides a simple way to time small bits of Python code. It has both command line as well as callable interfaces. It avoids a number of common traps for measuring execution times. See also Tim Peters' introduction to the "Algorithms" chapter in the *Python Cookbook*, published by O'Reilly.

The module defines the following public class:

```
class Timer ([stmt='pass' [, setup='pass' [, timer=timer function]]])
```

Class for timing execution speed of small code snippets.

The constructor takes a statement to be timed, an additional statement used for setup, and a timer function. Both statements default to 'pass'; the timer function is platform-dependent (see the module doc string). The statements may contain newlines, as long as they don't contain multi-line string literals.

To measure the execution time of the first statement, use the `timeit()` method. The `repeat()` method is a convenience to call `timeit()` multiple times and return a list of results.

```
print_exc ([file=None])
```

Helper to print a traceback from the timed code.

Typical use:

```
t = Timer(...)          # outside the try/except
try:
    t.timeit(...)        # or t.repeat(...)
except:
    t.print_exc()
```

The advantage over the standard traceback is that source lines in the compiled template will be displayed. The optional *file* argument directs where the traceback is sent; it defaults to `sys.stderr`.

```
repeat ([repeat=3 [, number=1000000]])
```

Call `timeit()` a few times.

This is a convenience function that calls the `timeit()` repeatedly, returning a list of results. The first argument specifies how many times to call `timeit()`. The second argument specifies the *number* argument for `timeit()`.

Note: It's tempting to calculate mean and standard deviation from the result vector and report these. However, this is not very useful. In a typical case, the lowest value gives a lower bound for how fast your machine can run the given code snippet; higher values in the result vector are typically not caused by variability in Python's speed, but by other processes interfering with your timing accuracy. So the `min()` of the result is probably the only number you should be interested in. After that, you should look at the entire vector and apply common sense rather than statistics.

```
timeit ([number=1000000])
```

Time *number* executions of the main statement. This executes the setup statement once, and then returns the time it takes to execute the main statement a number of times, measured in seconds as a float. The argument is the number of times through the loop, defaulting to one million. The main statement, the setup statement and the timer function to be used are passed to the constructor.

Note: By default, `timeit()` temporarily turns off garbage collection during the timing. The advantage of this approach is that it makes independent timings more comparable. This disadvantage is that GC may be an important component of the performance of the function being measured. If so, GC can be re-enabled as the first statement in the *setup* string. For example:

```
timeit.Timer('for i in xrange(10): oct(i)', 'gc.enable()').timeit()
```

25.9.1 Command Line Interface

When called as a program from the command line, the following form is used:

```
python -m timeit [-n N] [-r N] [-s S] [-t] [-c] [-h] [statement ...]
```

where the following options are understood:

- n N/--number=N** how many times to execute 'statement'
- r N/--repeat=N** how many times to repeat the timer (default 3)
- s S/--setup=S** statement to be executed once initially (default 'pass')
- t/--time** use `time.time()` (default on all platforms but Windows)
- c/--clock** use `time.clock()` (default on Windows)
- v/--verbose** print raw timing results; repeat for more digits precision
- h/--help** print a short usage message and exit

A multi-line statement may be given by specifying each line as a separate statement argument; indented lines are possible by enclosing an argument in quotes and using leading spaces. Multiple **-s** options are treated similarly.

If **-n** is not given, a suitable number of loops is calculated by trying successive powers of 10 until the total time is at least 0.2 seconds.

The default timer function is platform dependent. On Windows, `time.clock()` has microsecond granularity but `time.time()`'s granularity is 1/60th of a second; on UNIX, `time.clock()` has 1/100th of a second granularity and `time.time()` is much more precise. On either platform, the default timer functions measure wall clock time, not the CPU time. This means that other processes running on the same computer may interfere with the timing. The best thing to do when accurate timing is necessary is to repeat the timing a few times and use the best time. The **-r** option is good for this; the default of 3 repetitions is probably enough in most cases. On UNIX, you can use `time.clock()` to measure CPU time.

Note: There is a certain baseline overhead associated with executing a pass statement. The code here doesn't try to hide it, but you should be aware of it. The baseline overhead can be measured by invoking the program without arguments.

The baseline overhead differs between Python versions! Also, to fairly compare older Python versions to Python 2.3, you may want to use Python's **-O** option for the older versions to avoid timing `SET_LINENO` instructions.

25.9.2 Examples

Here are two example sessions (one using the command line, one using the module interface) that compare the cost of using `hasattr()` vs. `try/except` to test for missing and present object attributes.

```
% timeit.py 'try:' ' str.__nonzero__ 'except AttributeError:' ' pass'
100000 loops, best of 3: 15.7 usec per loop
% timeit.py 'if hasattr(str, "__nonzero__"): pass'
100000 loops, best of 3: 4.26 usec per loop
% timeit.py 'try:' ' int.__nonzero__ 'except AttributeError:' ' pass'
1000000 loops, best of 3: 1.43 usec per loop
% timeit.py 'if hasattr(int, "__nonzero__"): pass'
100000 loops, best of 3: 2.23 usec per loop
```

```

>>> import timeit
>>> s = """\
... try:
...     str.__nonzero__
... except AttributeError:
...     pass
... """
>>> t = timeit.Timer(stmt=s)
>>> print "%.2f usec/pass" % (1000000 * t.timeit(number=100000)/100000)
17.09 usec/pass
>>> s = """\
... if hasattr(str, '__nonzero__'): pass
... """
>>> t = timeit.Timer(stmt=s)
>>> print "%.2f usec/pass" % (1000000 * t.timeit(number=100000)/100000)
4.85 usec/pass
>>> s = """\
... try:
...     int.__nonzero__
... except AttributeError:
...     pass
... """
>>> t = timeit.Timer(stmt=s)
>>> print "%.2f usec/pass" % (1000000 * t.timeit(number=100000)/100000)
1.97 usec/pass
>>> s = """\
... if hasattr(int, '__nonzero__'): pass
... """
>>> t = timeit.Timer(stmt=s)
>>> print "%.2f usec/pass" % (1000000 * t.timeit(number=100000)/100000)
3.15 usec/pass

```

To give the `timeit` module access to functions you define, you can pass a setup parameter which contains an import statement:

```

def test():
    "Stupid test function"
    L = []
    for i in range(100):
        L.append(i)

if __name__=='__main__':
    from timeit import Timer
    t = Timer("test()", "from __main__ import test")
    print t.timeit()

```

25.10 `trace` — Trace or track Python statement execution

The `trace` module allows you to trace program execution, generate annotated statement coverage listings, print caller/callee relationships and list functions executed during a program run. It can be used in another program or from the command line.

25.10.1 Command Line Usage

The `trace` module can be invoked from the command line. It can be as simple as

```
python -m trace --count somefile.py ...
```

The above will generate annotated listings of all Python modules imported during the execution of 'somefile.py'.

The following command-line arguments are supported:

--trace, -t Display lines as they are executed.

--count, -c Produce a set of annotated listing files upon program completion that shows how many times each statement was executed.

--report, -r Produce an annotated list from an earlier program run that used the **--count** and **--file** arguments.

--no-report, -R Do not generate annotated listings. This is useful if you intend to make several runs with **--count** then produce a single set of annotated listings at the end.

--listfuncs, -l List the functions executed by running the program.

--trackcalls, -T Generate calling relationships exposed by running the program.

--file, -f Name a file containing (or to contain) counts.

--coverdir, -C Name a directory in which to save annotated listing files.

--missing, -m When generating annotated listings, mark lines which were not executed with '>>>>>>'.

--summary, -s When using **--count** or **--report**, write a brief summary to stdout for each file processed.

--ignore-module Ignore the named module and its submodules (if it is a package). May be given multiple times.

--ignore-dir Ignore all modules and packages in the named directory and subdirectories. May be given multiple times.

25.10.2 Programming Interface

```
class Trace ([count=1[, trace=1[, countfuncs=0[, countcallers=0[, ignoremods=(), ignoredirs=(), in-  
file=None[, outfile=None ]]]]]])
```

Create an object to trace execution of a single statement or expression. All parameters are optional. *count* enables counting of line numbers. *trace* enables line execution tracing. *countfuncs* enables listing of the functions called during the run. *countcallers* enables call relationship tracking. *ignoremods* is a list of modules or packages to ignore. *ignoredirs* is a list of directories whose modules or packages should be ignored. *infile* is the file from which to read stored count information. *outfile* is a file in which to write updated count information.

```
run (cmd)
```

Run *cmd* under control of the `Trace` object with the current tracing parameters.

```
runctx (cmd[, globals=None[, locals=None ]])
```

Run *cmd* under control of the `Trace` object with the current tracing parameters in the defined global and local environments. If not defined, *globals* and *locals* default to empty dictionaries.

```
runfunc (func, *args, **kwargs)
```

Call *func* with the given arguments under control of the `Trace` object with the current tracing parameters.

This is a simple example showing the use of this module:

```
import sys
import trace

# create a Trace object, telling it what to ignore, and whether to
# do tracing or line-counting or both.
tracer = trace.Trace(
    ignoredirs=[sys.prefix, sys.exec_prefix],
    trace=0,
    count=1)

# run the new command using the given tracer
tracer.run('main()')

# make a report, placing output in /tmp
r = tracer.results()
r.write_results(show_missing=True, coverdir="/tmp")
```


Python Runtime Services

The modules described in this chapter provide a wide range of services related to the Python interpreter and its interaction with its environment. Here's an overview:

<code>sys</code>	Access system-specific parameters and functions.
<code>__builtin__</code>	The module that provides the built-in namespace.
<code>__main__</code>	The environment where the top-level script is run.
<code>warnings</code>	Issue warning messages and control their disposition.
<code>contextlib</code>	Utilities for <code>with</code> -statement contexts.
<code>atexit</code>	Register and execute cleanup functions.
<code>traceback</code>	Print or retrieve a stack traceback.
<code>__future__</code>	Future statement definitions
<code>gc</code>	Interface to the cycle-detecting garbage collector.
<code>inspect</code>	Extract information and source code from live objects.
<code>site</code>	A standard way to reference site-specific modules.
<code>user</code>	A standard way to reference user-specific modules.
<code>fpectl</code>	Provide control for floating point exception handling.

26.1 `sys` — System-specific parameters and functions

This module provides access to some variables used or maintained by the interpreter and to functions that interact strongly with the interpreter. It is always available.

`argv`

The list of command line arguments passed to a Python script. `argv[0]` is the script name (it is operating system dependent whether this is a full pathname or not). If the command was executed using the `-c` command line option to the interpreter, `argv[0]` is set to the string `'-c'`. If no script name was passed to the Python interpreter, `argv[0]` is the empty string.

`byteorder`

An indicator of the native byte order. This will have the value `'big'` on big-endian (most-significant byte first) platforms, and `'little'` on little-endian (least-significant byte first) platforms. New in version 2.0.

`subversion`

A triple (repo, branch, version) representing the Subversion information of the Python interpreter. *repo* is the name of the repository, `'CPython'`. *branch* is a string of one of the forms `'trunk'`, `'branches/name'` or `'tags/name'`. *version* is the output of `svnversion`, if the interpreter was built from a Subversion checkout; it contains the revision number (range) and possibly a trailing `'M'` if there were local modifications. If the tree was exported (or `svnversion` was not available), it is the revision of `Include/patchlevel.h` if the branch is a tag. Otherwise, it is `None`. New in version 2.5.

`builtin_module_names`

A tuple of strings giving the names of all modules that are compiled into this Python interpreter. (This informa-

tion is not available in any other way — `modules.keys()` only lists the imported modules.)

copyright

A string containing the copyright pertaining to the Python interpreter.

`_current_frames()`

Return a dictionary mapping each thread's identifier to the topmost stack frame currently active in that thread at the time the function is called. Note that functions in the `traceback` module can build the call stack given such a frame.

This is most useful for debugging deadlock: this function does not require the deadlocked threads' cooperation, and such threads' call stacks are frozen for as long as they remain deadlocked. The frame returned for a non-deadlocked thread may bear no relationship to that thread's current activity by the time calling code examines the frame.

This function should be used for internal and specialized purposes only. New in version 2.5.

dllhandle

Integer specifying the handle of the Python DLL. Availability: Windows.

displayhook (*value*)

If *value* is not `None`, this function prints it to `sys.stdout`, and saves it in `__builtin__.__`.

`sys.displayhook` is called on the result of evaluating an expression entered in an interactive Python session. The display of these values can be customized by assigning another one-argument function to `sys.displayhook`.

excepthook (*type*, *value*, *traceback*)

This function prints out a given traceback and exception to `sys.stderr`.

When an exception is raised and uncaught, the interpreter calls `sys.excepthook` with three arguments, the exception class, exception instance, and a traceback object. In an interactive session this happens just before control is returned to the prompt; in a Python program this happens just before the program exits. The handling of such top-level exceptions can be customized by assigning another three-argument function to `sys.excepthook`.

`__displayhook__` `__excepthook__`

These objects contain the original values of `displayhook` and `excepthook` at the start of the program. They are saved so that `displayhook` and `excepthook` can be restored in case they happen to get replaced with broken objects.

exc_info()

This function returns a tuple of three values that give information about the exception that is currently being handled. The information returned is specific both to the current thread and to the current stack frame. If the current stack frame is not handling an exception, the information is taken from the calling stack frame, or its caller, and so on until a stack frame is found that is handling an exception. Here, "handling an exception" is defined as "executing or having executed an except clause." For any stack frame, only information about the most recently handled exception is accessible.

If no exception is being handled anywhere on the stack, a tuple containing three `None` values is returned. Otherwise, the values returned are (*type*, *value*, *traceback*). Their meaning is: *type* gets the exception type of the exception being handled (a class object); *value* gets the exception parameter (its *associated value* or the second argument to `raise`, which is always a class instance if the exception type is a class object); *traceback* gets a traceback object (see the Reference Manual) which encapsulates the call stack at the point where the exception originally occurred.

If `exc_clear()` is called, this function will return three `None` values until either another exception is raised in the current thread or the execution stack returns to a frame where another exception is being handled.

Warning: Assigning the *traceback* return value to a local variable in a function that is handling an exception will cause a circular reference. This will prevent anything referenced by a local variable in the same function or by the traceback from being garbage collected. Since most functions don't need access to the traceback, the

best solution is to use something like `exctype, value = sys.exc_info()[2]` to extract only the exception type and value. If you do need the traceback, make sure to delete it after use (best done with a `try ... finally` statement) or to call `exc_info()` in a function that does not itself handle an exception. **Note:** Beginning with Python 2.2, such cycles are automatically reclaimed when garbage collection is enabled and they become unreachable, but it remains more efficient to avoid creating cycles.

exc_clear()

This function clears all information relating to the current or last exception that occurred in the current thread. After calling this function, `exc_info()` will return three `None` values until another exception is raised in the current thread or the execution stack returns to a frame where another exception is being handled.

This function is only needed in only a few obscure situations. These include logging and error handling systems that report information on the last or current exception. This function can also be used to try to free resources and trigger object finalization, though no guarantee is made as to what objects will be freed, if any. New in version 2.3.

exc_type

exc_value

exc_traceback

Deprecated since release 1.5. Use `exc_info()` instead.

Since they are global variables, they are not specific to the current thread, so their use is not safe in a multi-threaded program. When no exception is being handled, `exc_type` is set to `None` and the other two are undefined.

exec_prefix

A string giving the site-specific directory prefix where the platform-dependent Python files are installed; by default, this is also `'/usr/local'`. This can be set at build time with the **--exec-prefix** argument to the **configure** script. Specifically, all configuration files (e.g. the `'pyconfig.h'` header file) are installed in the directory `exec_prefix + '/lib/pythonversion/config'`, and shared library modules are installed in `exec_prefix + '/lib/pythonversion/lib-dynload'`, where *version* is equal to `version[:3]`.

executable

A string giving the name of the executable binary for the Python interpreter, on systems where this makes sense.

exit([arg])

Exit from Python. This is implemented by raising the `SystemExit` exception, so cleanup actions specified by finally clauses of `try` statements are honored, and it is possible to intercept the exit attempt at an outer level. The optional argument *arg* can be an integer giving the exit status (defaulting to zero), or another type of object. If it is an integer, zero is considered “successful termination” and any nonzero value is considered “abnormal termination” by shells and the like. Most systems require it to be in the range 0-127, and produce undefined results otherwise. Some systems have a convention for assigning specific meanings to specific exit codes, but these are generally underdeveloped; UNIX programs generally use 2 for command line syntax errors and 1 for all other kind of errors. If another type of object is passed, `None` is equivalent to passing zero, and any other object is printed to `sys.stderr` and results in an exit code of 1. In particular, `sys.exit("some error message")` is a quick way to exit a program when an error occurs.

exitfunc

This value is not actually defined by the module, but can be set by the user (or by a program) to specify a cleanup action at program exit. When set, it should be a parameterless function. This function will be called when the interpreter exits. Only one function may be installed in this way; to allow multiple functions which will be called at termination, use the `atexit` module. **Note:** The exit function is not called when the program is killed by a signal, when a Python fatal internal error is detected, or when `os._exit()` is called. **Deprecated since release 2.4.** Use `atexit` instead.

getcheckinterval()

Return the interpreter’s “check interval”; see `setcheckinterval()`. New in version 2.3.

getdefaultencoding()

Return the name of the current default string encoding used by the Unicode implementation. New in version

2.0.

getdlopenflags()

Return the current value of the flags that are used for `dlopen()` calls. The flag constants are defined in the `dl` and `DLFCN` modules. Availability: UNIX. New in version 2.2.

getfilesystemencoding()

Return the name of the encoding used to convert Unicode filenames into system file names, or `None` if the system default encoding is used. The result value depends on the operating system:

- On Windows 9x, the encoding is “mbcs”.
- On Mac OS X, the encoding is “utf-8”.
- On UNIX, the encoding is the user’s preference according to the result of `nl_langinfo(CODESET)`, or `None` if the `nl_langinfo(CODESET)` failed.
- On Windows NT+, file names are Unicode natively, so no conversion is performed. `getfilesystemencoding()` still returns ‘mbcs’, as this is the encoding that applications should use when they explicitly want to convert Unicode strings to byte strings that are equivalent when used as file names.

New in version 2.3.

getrefcount(object)

Return the reference count of the *object*. The count returned is generally one higher than you might expect, because it includes the (temporary) reference as an argument to `getrefcount()`.

getrecursionlimit()

Return the current value of the recursion limit, the maximum depth of the Python interpreter stack. This limit prevents infinite recursion from causing an overflow of the C stack and crashing Python. It can be set by `setrecursionlimit()`.

_getframe([depth])

Return a frame object from the call stack. If optional integer *depth* is given, return the frame object that many calls below the top of the stack. If that is deeper than the call stack, `ValueError` is raised. The default for *depth* is zero, returning the frame at the top of the call stack.

This function should be used for internal and specialized purposes only.

getwindowsversion()

Return a tuple containing five components, describing the Windows version currently running. The elements are *major*, *minor*, *build*, *platform*, and *text*. *text* contains a string while all other values are integers.

platform may be one of the following values:

Constant	Platform
0 (VER_PLATFORM_WIN32s)	Win32s on Windows 3.1
1 (VER_PLATFORM_WIN32_WINDOWS)	Windows 95/98/ME
2 (VER_PLATFORM_WIN32_NT)	Windows NT/2000/XP
3 (VER_PLATFORM_WIN32_CE)	Windows CE

This function wraps the Win32 `GetVersionEx()` function; see the Microsoft documentation for more information about these fields.

Availability: Windows. New in version 2.3.

hexversion

The version number encoded as a single integer. This is guaranteed to increase with each version, including proper support for non-production releases. For example, to test that the Python interpreter is at least version 1.5.2, use:

```

if sys.hexversion >= 0x010502F0:
    # use some advanced feature
    ...
else:
    # use an alternative implementation or warn the user
    ...

```

This is called ‘hexversion’ since it only really looks meaningful when viewed as the result of passing it to the built-in `hex()` function. The `version_info` value may be used for a more human-friendly encoding of the same information. New in version 1.5.2.

last_type

last_value

last_traceback

These three variables are not always defined; they are set when an exception is not handled and the interpreter prints an error message and a stack traceback. Their intended use is to allow an interactive user to import a debugger module and engage in post-mortem debugging without having to re-execute the command that caused the error. (Typical use is ‘`import pdb; pdb.pm()`’ to enter the post-mortem debugger; see chapter 24, “The Python Debugger,” for more information.)

The meaning of the variables is the same as that of the return values from `exc_info()` above. (Since there is only one interactive thread, thread-safety is not a concern for these variables, unlike for `exc_type` etc.)

maxint

The largest positive integer supported by Python’s regular integer type. This is at least $2^{31}-1$. The largest negative integer is `-maxint-1` — the asymmetry results from the use of 2’s complement binary arithmetic.

maxunicode

An integer giving the largest supported code point for a Unicode character. The value of this depends on the configuration option that specifies whether Unicode characters are stored as UCS-2 or UCS-4.

modules

This is a dictionary that maps module names to modules which have already been loaded. This can be manipulated to force reloading of modules and other tricks. Note that removing a module from this dictionary is *not* the same as calling `reload()` on the corresponding module object.

path

A list of strings that specifies the search path for modules. Initialized from the environment variable `PYTHONPATH`, plus an installation-dependent default.

As initialized upon program startup, the first item of this list, `path[0]`, is the directory containing the script that was used to invoke the Python interpreter. If the script directory is not available (e.g. if the interpreter is invoked interactively or if the script is read from standard input), `path[0]` is the empty string, which directs Python to search modules in the current directory first. Notice that the script directory is inserted *before* the entries inserted as a result of `PYTHONPATH`.

A program is free to modify this list for its own purposes.

Changed in version 2.3: Unicode strings are no longer ignored.

platform

This string contains a platform identifier, e.g. ‘`sunos5`’ or ‘`linux1`’. This can be used to append platform-specific components to `path`, for instance.

prefix

A string giving the site-specific directory prefix where the platform independent Python files are installed; by default, this is the string ‘`/usr/local`’. This can be set at build time with the `--prefix` argument to the **configure** script. The main collection of Python library modules is installed in the directory `prefix + '/lib/pythonversion'` while the platform independent header files (all except ‘`pyconfig.h`’) are stored in `prefix + '/include/pythonversion'`, where *version* is equal to `version[:3]`.

ps1
ps2

Strings specifying the primary and secondary prompt of the interpreter. These are only defined if the interpreter is in interactive mode. Their initial values in this case are '`>>>`' and '`...`'. If a non-string object is assigned to either variable, its `str()` is re-evaluated each time the interpreter prepares to read a new interactive command; this can be used to implement a dynamic prompt.

setcheckinterval (*interval*)

Set the interpreter's "check interval". This integer value determines how often the interpreter checks for periodic things such as thread switches and signal handlers. The default is 100, meaning the check is performed every 100 Python virtual instructions. Setting it to a larger value may increase performance for programs using threads. Setting it to a value ≤ 0 checks every virtual instruction, maximizing responsiveness as well as overhead.

setdefaultencoding (*name*)

Set the current default string encoding used by the Unicode implementation. If *name* does not match any available encoding, `LookupError` is raised. This function is only intended to be used by the `site` module implementation and, where needed, by `sitecustomize`. Once used by the `site` module, it is removed from the `sys` module's namespace. New in version 2.0.

setdlopenflags (*n*)

Set the flags used by the interpreter for `dlopen()` calls, such as when the interpreter loads extension modules. Among other things, this will enable a lazy resolving of symbols when importing a module, if called as `sys.setdlopenflags(0)`. To share symbols across extension modules, call as `sys.setdlopenflags(dl.RTLD_NOW | dl.RTLD_GLOBAL)`. Symbolic names for the flag modules can be either found in the `dl` module, or in the `DLFCN` module. If `DLFCN` is not available, it can be generated from `'usr/include/dlfcn.h'` using the **h2py** script. Availability: UNIX. New in version 2.2.

setprofile (*profilefunc*)

Set the system's profile function, which allows you to implement a Python source code profiler in Python. See chapter 25 for more information on the Python profiler. The system's profile function is called similarly to the system's trace function (see `settrace()`), but it isn't called for each executed line of code (only on call and return, but the return event is reported even when an exception has been set). The function is thread-specific, but there is no way for the profiler to know about context switches between threads, so it does not make sense to use this in the presence of multiple threads. Also, its return value is not used, so it can simply return `None`.

setrecursionlimit (*limit*)

Set the maximum depth of the Python interpreter stack to *limit*. This limit prevents infinite recursion from causing an overflow of the C stack and crashing Python.

The highest possible limit is platform-dependent. A user may need to set the limit higher when she has a program that requires deep recursion and a platform that supports a higher limit. This should be done with care, because a too-high limit can lead to a crash.

settrace (*tracefunc*)

Set the system's trace function, which allows you to implement a Python source code debugger in Python. See section 24.2, "How It Works," in the chapter on the Python debugger. The function is thread-specific; for a debugger to support multiple threads, it must be registered using `settrace()` for each thread being debugged.

Note: The `settrace()` function is intended only for implementing debuggers, profilers, coverage tools and the like. Its behavior is part of the implementation platform, rather than part of the language definition, and thus may not be available in all Python implementations.

settsdump (*on_flag*)

Activate dumping of VM measurements using the Pentium timestamp counter, if *on_flag* is true. Deactivate these dumps if *on_flag* is off. The function is available only if Python was compiled with **--with-tsc**. To understand the output of this dump, read 'Python/ceval.c' in the Python sources. New in version 2.4.

stdin
stdout
stderr

File objects corresponding to the interpreter's standard input, output and error streams. `stdin` is used for all interpreter input except for scripts but including calls to `input()` and `raw_input()`. `stdout` is used for the output of `print` and expression statements and for the prompts of `input()` and `raw_input()`. The interpreter's own prompts and (almost all of) its error messages go to `stderr`. `stdout` and `stderr` needn't be built-in file objects: any object is acceptable as long as it has a `write()` method that takes a string argument. (Changing these objects doesn't affect the standard I/O streams of processes executed by `os.popen()`, `os.system()` or the `exec*()` family of functions in the `os` module.)

`__stdin__`
`__stdout__`
`__stderr__`

These objects contain the original values of `stdin`, `stderr` and `stdout` at the start of the program. They are used during finalization, and could be useful to restore the actual files to known working file objects in case they have been overwritten with a broken object.

tracebacklimit

When this variable is set to an integer value, it determines the maximum number of levels of traceback information printed when an unhandled exception occurs. The default is 1000. When set to 0 or less, all traceback information is suppressed and only the exception type and value are printed.

version

A string containing the version number of the Python interpreter plus additional information on the build number and compiler used. It has a value of the form '*version* (*#build_number*, *build_date*, *build_time*) [*compiler*]' . The first three characters are used to identify the version in the installation directories (where appropriate on each platform). An example:

```
>>> import sys
>>> sys.version
'1.5.2 (#0 Apr 13 1999, 10:51:12) [MSC 32 bit (Intel)]'
```

api_version

The C API version for this interpreter. Programmers may find this useful when debugging version conflicts between Python and extension modules. New in version 2.3.

version_info

A tuple containing the five components of the version number: *major*, *minor*, *micro*, *releaselevel*, and *serial*. All values except *releaselevel* are integers; the release level is 'alpha', 'beta', 'candidate', or 'final'. The `version_info` value corresponding to the Python version 2.0 is (2, 0, 0, 'final', 0). New in version 2.0.

warnoptions

This is an implementation detail of the warnings framework; do not modify this value. Refer to the [warnings](#) module for more information on the warnings framework.

winver

The version number used to form registry keys on Windows platforms. This is stored as string resource 1000 in the Python DLL. The value is normally the first three characters of `version`. It is provided in the `sys` module for informational purposes; modifying this value has no effect on the registry keys used by Python. Availability: Windows.

See Also:

[Module site](#) (section 26.11):

This describes how to use .pth files to extend `sys.path`.

26.2 `__builtin__` — Built-in objects

This module provides direct access to all ‘built-in’ identifiers of Python; for example, `__builtin__.open` is the full name for the built-in function `open()`. See chapter 2, “Built-in Objects.”

This module is not normally accessed explicitly by most applications, but can be useful in modules that provide objects with the same name as a built-in value, but in which the built-in of that name is also needed. For example, in a module that wants to implement an `open()` function that wraps the built-in `open()`, this module can be used directly:

```
import __builtin__

def open(path):
    f = __builtin__.open(path, 'r')
    return UpperCaser(f)

class UpperCaser:
    '''Wrapper around a file that converts output to upper-case.'''

    def __init__(self, f):
        self._f = f

    def read(self, count=-1):
        return self._f.read(count).upper()

# ...
```

As an implementation detail, most modules have the name `__builtins__` (note the ‘s’) made available as part of their globals. The value of `__builtins__` is normally either this module or the value of this module’s `__dict__` attribute. Since this is an implementation detail, it may not be used by alternate implementations of Python.

26.3 `__main__` — Top-level script environment

This module represents the (otherwise anonymous) scope in which the interpreter’s main program executes — commands read either from standard input, from a script file, or from an interactive prompt. It is this environment in which the idiomatic “conditional script” stanza causes a script to run:

```
if __name__ == "__main__":
    main()
```

26.4 `warnings` — Warning control

New in version 2.1.

Warning messages are typically issued in situations where it is useful to alert the user of some condition in a program, where that condition (normally) doesn’t warrant raising an exception and terminating the program. For example, one might want to issue a warning when a program uses an obsolete module.

Python programmers issue warnings by calling the `warn()` function defined in this module. (C programmers use `PyErr_Warn()`; see the [Python/C API Reference Manual](#) for details).

Warning messages are normally written to `sys.stderr`, but their disposition can be changed flexibly, from ignoring all warnings to turning them into exceptions. The disposition of warnings can vary based on the warning category (see

below), the text of the warning message, and the source location where it is issued. Repetitions of a particular warning for the same source location are typically suppressed.

There are two stages in warning control: first, each time a warning is issued, a determination is made whether a message should be issued or not; next, if a message is to be issued, it is formatted and printed using a user-settable hook.

The determination whether to issue a warning message is controlled by the warning filter, which is a sequence of matching rules and actions. Rules can be added to the filter by calling `filterwarnings()` and reset to its default state by calling `resetwarnings()`.

The printing of warning messages is done by calling `showwarning()`, which may be overridden; the default implementation of this function formats the message by calling `formatwarning()`, which is also available for use by custom implementations.

26.4.1 Warning Categories

There are a number of built-in exceptions that represent warning categories. This categorization is useful to be able to filter out groups of warnings. The following warnings category classes are currently defined:

Class	Description
<code>Warning</code>	This is the base class of all warning category classes. It is a subclass of <code>Exception</code> .
<code>UserWarning</code>	The default category for <code>warn()</code> .
<code>DeprecationWarning</code>	Base category for warnings about deprecated features.
<code>SyntaxWarning</code>	Base category for warnings about dubious syntactic features.
<code>RuntimeWarning</code>	Base category for warnings about dubious runtime features.
<code>FutureWarning</code>	Base category for warnings about constructs that will change semantically in the future.
<code>PendingDeprecationWarning</code>	Base category for warnings about features that will be deprecated in the future (ignored by default).
<code>ImportWarning</code>	Base category for warnings triggered during the process of importing a module (ignored by default).
<code>UnicodeWarning</code>	Base category for warnings related to Unicode.

While these are technically built-in exceptions, they are documented here, because conceptually they belong to the warnings mechanism.

User code can define additional warning categories by subclassing one of the standard warning categories. A warning category must always be a subclass of the `Warning` class.

26.4.2 The Warnings Filter

The warnings filter controls whether warnings are ignored, displayed, or turned into errors (raising an exception).

Conceptually, the warnings filter maintains an ordered list of filter specifications; any specific warning is matched against each filter specification in the list in turn until a match is found; the match determines the disposition of the match. Each entry is a tuple of the form *(action, message, category, module, lineno)*, where:

- *action* is one of the following strings:

Value	Disposition
"error"	turn matching warnings into exceptions
"ignore"	never print matching warnings
"always"	always print matching warnings
"default"	print the first occurrence of matching warnings for each location where the warning is issued
"module"	print the first occurrence of matching warnings for each module where the warning is issued
"once"	print only the first occurrence of matching warnings, regardless of location

- *message* is a string containing a regular expression that the warning message must match (the match is compiled to always be case-insensitive)
- *category* is a class (a subclass of `Warning`) of which the warning category must be a subclass in order to match
- *module* is a string containing a regular expression that the module name must match (the match is compiled to be case-sensitive)
- *lineno* is an integer that the line number where the warning occurred must match, or 0 to match all line numbers

Since the `Warning` class is derived from the built-in `Exception` class, to turn a warning into an error we simply `raise category(message)`.

The warnings filter is initialized by **-W** options passed to the Python interpreter command line. The interpreter saves the arguments for all **-W** options without interpretation in `sys.warnoptions`; the `warnings` module parses these when it is first imported (invalid options are ignored, after printing a message to `sys.stderr`).

The warnings that are ignored by default may be enabled by passing **-Wd** to the interpreter. This enables default handling for all warnings, including those that are normally ignored by default. This is particular useful for enabling `ImportWarning` when debugging problems importing a developed package. `ImportWarning` can also be enabled explicitly in Python code using:

```
warnings.simplefilter('default', ImportWarning)
```

26.4.3 Available Functions

warn (*message* [, *category* [, *stacklevel*]])

Issue a warning, or maybe ignore it or raise an exception. The *category* argument, if given, must be a warning category class (see above); it defaults to `UserWarning`. Alternatively *message* can be a `Warning` instance, in which case *category* will be ignored and `message.__class__` will be used. In this case the message text will be `str(message)`. This function raises an exception if the particular warning issued is changed into an error by the warnings filter see above. The *stacklevel* argument can be used by wrapper functions written in Python, like this:

```
def deprecation(message):
    warnings.warn(message, DeprecationWarning, stacklevel=2)
```

This makes the warning refer to `deprecation()`'s caller, rather than to the source of `deprecation()` itself (since the latter would defeat the purpose of the warning message).

warn_explicit (*message*, *category*, *filename*, *lineno* [, *module* [, *registry* [, *module_globals*]]])

This is a low-level interface to the functionality of `warn()`, passing in explicitly the message, category, filename and line number, and optionally the module name and the registry (which should be the `__warningregistry__` dictionary of the module). The module name defaults to the filename with `.py` stripped; if no registry is passed, the warning is never suppressed. *message* must be a string and *category* a subclass of `Warning` or *message* may be a `Warning` instance, in which case *category* will be ignored.

module_globals, if supplied, should be the global namespace in use by the code for which the warning is issued. (This argument is used to support displaying source for modules found in zipfiles or other non-filesystem import sources, and was added in Python 2.5.)

showwarning (*message*, *category*, *filename*, *lineno* [, *file*])

Write a warning to a file. The default implementation calls `formatwarning(message, category, filename, lineno)` and writes the resulting string to *file*, which defaults to `sys.stderr`. You may replace this function with an alternative implementation by assigning to `warnings.showwarning`.

formatwarning (*message*, *category*, *filename*, *lineno*)

Format a warning the standard way. This returns a string which may contain embedded newlines and ends in a newline.

filterwarnings (*action*[, *message*[, *category*[, *module*[, *lineno*[, *append*]]]]])

Insert an entry into the list of warnings filters. The entry is inserted at the front by default; if *append* is true, it is inserted at the end. This checks the types of the arguments, compiles the message and module regular expressions, and inserts them as a tuple in the list of warnings filters. Entries closer to the front of the list override entries later in the list, if both match a particular warning. Omitted arguments default to a value that matches everything.

simplefilter (*action*[, *category*[, *lineno*[, *append*]]])

Insert a simple entry into the list of warnings filters. The meaning of the function parameters is as for `filterwarnings()`, but regular expressions are not needed as the filter inserted always matches any message in any module as long as the category and line number match.

resetwarnings ()

Reset the warnings filter. This discards the effect of all previous calls to `filterwarnings()`, including that of the **-W** command line options and calls to `simplefilter()`.

26.5 contextlib — Utilities for with-statement contexts.

New in version 2.5.

This module provides utilities for common tasks involving the `with` statement.

Functions provided:

contextmanager (*func*)

This function is a decorator that can be used to define a factory function for `with` statement context managers, without needing to create a class or separate `__enter__()` and `__exit__()` methods.

A simple example (this is not recommended as a real way of generating HTML!):

```
from __future__ import with_statement
from contextlib import contextmanager

@contextmanager
def tag(name):
    print "<%s>" % name
    yield
    print "</%s>" % name

>>> with tag("h1"):
...     print "foo"
...
<h1>
foo
</h1>
```

The function being decorated must return a generator-iterator when called. This iterator must yield exactly one value, which will be bound to the targets in the `with` statement's `as` clause, if any.

At the point where the generator yields, the block nested in the `with` statement is executed. The generator is then resumed after the block is exited. If an unhandled exception occurs in the block, it is reraised inside the generator at the point where the yield occurred. Thus, you can use a `try...except...finally` statement to trap the error (if any), or ensure that some cleanup takes place. If an exception is trapped merely in order to log it or to perform some action (rather than to suppress it entirely), the generator must reraise that exception. Otherwise

the generator context manager will indicate to the `with` statement that the exception has been handled, and execution will resume with the statement immediately following the `with` statement.

nested(*mgr1*[, *mgr2*[, ...]])

Combine multiple context managers into a single nested context manager.

Code like this:

```
from contextlib import nested

with nested(A, B, C) as (X, Y, Z):
    do_something()
```

is equivalent to this:

```
with A as X:
    with B as Y:
        with C as Z:
            do_something()
```

Note that if the `__exit__()` method of one of the nested context managers indicates an exception should be suppressed, no exception information will be passed to any remaining outer context managers. Similarly, if the `__exit__()` method of one of the nested managers raises an exception, any previous exception state will be lost; the new exception will be passed to the `__exit__()` methods of any remaining outer context managers. In general, `__exit__()` methods should avoid raising exceptions, and in particular they should not re-raise a passed-in exception.

closing(*thing*)

Return a context manager that closes *thing* upon completion of the block. This is basically equivalent to:

```
from contextlib import contextmanager

@contextmanager
def closing(thing):
    try:
        yield thing
    finally:
        thing.close()
```

And lets you write code like this:

```
from __future__ import with_statement
from contextlib import closing
import urllib

with closing(urllib.urlopen('http://www.python.org')) as page:
    for line in page:
        print line
```

without needing to explicitly close `page`. Even if an error occurs, `page.close()` will be called when the `with` block is exited.

See Also:

PEP 0343, “The “*with*” statement”

The specification, background, and examples for the Python `with` statement.

26.6 atexit — Exit handlers

New in version 2.0.

The `atexit` module defines a single function to register cleanup functions. Functions thus registered are automatically executed upon normal interpreter termination.

Note: the functions registered via this module are not called when the program is killed by a signal, when a Python fatal internal error is detected, or when `os._exit()` is called.

This is an alternate interface to the functionality provided by the `sys.exitfunc` variable.

Note: This module is unlikely to work correctly when used with other code that sets `sys.exitfunc`. In particular, other core Python modules are free to use `atexit` without the programmer's knowledge. Authors who use `sys.exitfunc` should convert their code to use `atexit` instead. The simplest way to convert code that sets `sys.exitfunc` is to import `atexit` and register the function that had been bound to `sys.exitfunc`.

register (*func* [, **args* [, ***kwargs*]])

Register *func* as a function to be executed at termination. Any optional arguments that are to be passed to *func* must be passed as arguments to `register()`.

At normal program termination (for instance, if `sys.exit()` is called or the main module's execution completes), all functions registered are called in last in, first out order. The assumption is that lower level modules will normally be imported before higher level modules and thus must be cleaned up later.

If an exception is raised during execution of the exit handlers, a traceback is printed (unless `SystemExit` is raised) and the exception information is saved. After all exit handlers have had a chance to run the last exception to be raised is re-raised.

See Also:

[Module `readline`](#) (section 15.7):

Useful example of `atexit` to read and write [readline](#) history files.

26.6.1 atexit Example

The following simple example demonstrates how a module can initialize a counter from a file when it is imported and save the counter's updated value automatically when the program terminates without relying on the application making an explicit call into this module at termination.

```
try:
    _count = int(open("/tmp/counter").read())
except IOError:
    _count = 0

def incrcounter(n):
    global _count
    _count = _count + n

def savecounter():
    open("/tmp/counter", "w").write("%d" % _count)

import atexit
atexit.register(savecounter)
```

Positional and keyword arguments may also be passed to `register()` to be passed along to the registered function when it is called:

```

def goodbye(name, adjective):
    print 'Goodbye, %s, it was %s to meet you.' % (name, adjective)

import atexit
atexit.register(goodbye, 'Donny', 'nice')

# or:
atexit.register(goodbye, adjective='nice', name='Donny')

```

26.7 traceback — Print or retrieve a stack traceback

This module provides a standard interface to extract, format and print stack traces of Python programs. It exactly mimics the behavior of the Python interpreter when it prints a stack trace. This is useful when you want to print stack traces under program control, such as in a “wrapper” around the interpreter.

The module uses traceback objects — this is the object type that is stored in the variables `sys.exc_traceback` (deprecated) and `sys.last_traceback` and returned as the third item from `sys.exc_info()`.

The module defines the following functions:

print_tb(*traceback*[, *limit*[, *file*]])

Print up to *limit* stack trace entries from *traceback*. If *limit* is omitted or `None`, all entries are printed. If *file* is omitted or `None`, the output goes to `sys.stderr`; otherwise it should be an open file or file-like object to receive the output.

print_exception(*type*, *value*, *traceback*[, *limit*[, *file*]])

Print exception information and up to *limit* stack trace entries from *traceback* to *file*. This differs from `print_tb()` in the following ways: (1) if *traceback* is not `None`, it prints a header “Traceback (most recent call last):”; (2) it prints the exception *type* and *value* after the stack trace; (3) if *type* is `SyntaxError` and *value* has the appropriate format, it prints the line where the syntax error occurred with a caret indicating the approximate position of the error.

print_exc([*limit*[, *file*]])

This is a shorthand for `print_exception(sys.exc_type, sys.exc_value, sys.exc_traceback, limit, file)`. (In fact, it uses `sys.exc_info()` to retrieve the same information in a thread-safe way instead of using the deprecated variables.)

format_exc([*limit*])

This is like `print_exc(limit)` but returns a string instead of printing to a file. New in version 2.4.

print_last([*limit*[, *file*]])

This is a shorthand for `print_exception(sys.last_type, sys.last_value, sys.last_traceback, limit, file)`.

print_stack([*f*[, *limit*[, *file*]])

This function prints a stack trace from its invocation point. The optional *f* argument can be used to specify an alternate stack frame to start. The optional *limit* and *file* arguments have the same meaning as for `print_exception()`.

extract_tb(*traceback*[, *limit*])

Return a list of up to *limit* “pre-processed” stack trace entries extracted from the traceback object *traceback*. It is useful for alternate formatting of stack traces. If *limit* is omitted or `None`, all entries are extracted. A “pre-processed” stack trace entry is a quadruple (*filename*, *line number*, *function name*, *text*) representing the information that is usually printed for a stack trace. The *text* is a string with leading and trailing whitespace stripped; if the source is not available it is `None`.

extract_stack (*f* [, *limit*])

Extract the raw traceback from the current stack frame. The return value has the same format as for `extract_tb()`. The optional *f* and *limit* arguments have the same meaning as for `print_stack()`.

format_list (*list*)

Given a list of tuples as returned by `extract_tb()` or `extract_stack()`, return a list of strings ready for printing. Each string in the resulting list corresponds to the item with the same index in the argument list. Each string ends in a newline; the strings may contain internal newlines as well, for those items whose source text line is not `None`.

format_exception_only (*type*, *value*)

Format the exception part of a traceback. The arguments are the exception type and value such as given by `sys.last_type` and `sys.last_value`. The return value is a list of strings, each ending in a newline. Normally, the list contains a single string; however, for `SyntaxError` exceptions, it contains several lines that (when printed) display detailed information about where the syntax error occurred. The message indicating which exception occurred is the always last string in the list.

format_exception (*type*, *value*, *tb* [, *limit*])

Format a stack trace and the exception information. The arguments have the same meaning as the corresponding arguments to `print_exception()`. The return value is a list of strings, each ending in a newline and some containing internal newlines. When these lines are concatenated and printed, exactly the same text is printed as does `print_exception()`.

format_tb (*tb* [, *limit*])

A shorthand for `format_list(extract_tb(tb, limit))`.

format_stack (*f* [, *limit*])

A shorthand for `format_list(extract_stack(f, limit))`.

tb_lineno (*tb*)

This function returns the current line number set in the traceback object. This function was necessary because in versions of Python prior to 2.3 when the `-O` flag was passed to Python the `tb.tb_lineno` was not updated correctly. This function has no use in versions past 2.3.

26.7.1 Traceback Example

This simple example implements a basic read-eval-print loop, similar to (but less useful than) the standard Python interactive interpreter loop. For a more complete implementation of the interpreter loop, refer to the [code](#) module.

```
import sys, traceback

def run_user_code(envdir):
    source = raw_input(">>> ")
    try:
        exec source in envdir
    except:
        print "Exception in user code:"
        print '-'*60
        traceback.print_exc(file=sys.stdout)
        print '-'*60

envdir = {}
while 1:
    run_user_code(envdir)
```

26.8 `__future__` — Future statement definitions

`__future__` is a real module, and serves three purposes:

- To avoid confusing existing tools that analyze import statements and expect to find the modules they're importing.
- To ensure that future statements run under releases prior to 2.1 at least yield runtime exceptions (the import of `__future__` will fail, because there was no module of that name prior to 2.1).
- To document when incompatible changes were introduced, and when they will be — or were — made mandatory. This is a form of executable documentation, and can be inspected programatically via importing `__future__` and examining its contents.

Each statement in '`__future__.py`' is of the form:

```
FeatureName = "_Feature(" OptionalRelease ", " MandatoryRelease ", "  
                    CompilerFlag ") "
```

where, normally, *OptionalRelease* is less than *MandatoryRelease*, and both are 5-tuples of the same form as `sys.version_info`:

```
(PY_MAJOR_VERSION, # the 2 in 2.1.0a3; an int  
PY_MINOR_VERSION, # the 1; an int  
PY_MICRO_VERSION, # the 0; an int  
PY_RELEASE_LEVEL, # "alpha", "beta", "candidate" or "final"; string  
PY_RELEASE_SERIAL # the 3; an int  
)
```

OptionalRelease records the first release in which the feature was accepted.

In the case of a *MandatoryRelease* that has not yet occurred, *MandatoryRelease* predicts the release in which the feature will become part of the language.

Else *MandatoryRelease* records when the feature became part of the language; in releases at or after that, modules no longer need a future statement to use the feature in question, but may continue to use such imports.

MandatoryRelease may also be `None`, meaning that a planned feature got dropped.

Instances of class `_Feature` have two corresponding methods, `getOptionalRelease()` and `getMandatoryRelease()`.

CompilerFlag is the (bitfield) flag that should be passed in the fourth argument to the builtin function `compile()` to enable the feature in dynamically compiled code. This flag is stored in the `compiler_flag` attribute on `_Feature` instances.

No feature description will ever be deleted from `__future__`.

26.9 `gc` — Garbage Collector interface

This module provides an interface to the optional garbage collector. It provides the ability to disable the collector, tune the collection frequency, and set debugging options. It also provides access to unreachable objects that the collector found but cannot free. Since the collector supplements the reference counting already used in Python, you can disable the collector if you are sure your program does not create reference cycles. Automatic collection can be disabled by

calling `gc.disable()`. To debug a leaking program call `gc.set_debug(gc.DEBUG_LEAK)`. Notice that this includes `gc.DEBUG_SAVEALL`, causing garbage-collected objects to be saved in `gc.garbage` for inspection.

The `gc` module provides the following functions:

enable()

Enable automatic garbage collection.

disable()

Disable automatic garbage collection.

isenabled()

Returns true if automatic collection is enabled.

collect([generation])

With no arguments, run a full collection. The optional argument *generation* may be an integer specifying which generation to collect (from 0 to 2). A `ValueError` is raised if the generation number is invalid. The number of unreachable objects found is returned.

Changed in version 2.5: The optional *generation* argument was added.

set_debug(flags)

Set the garbage collection debugging flags. Debugging information will be written to `sys.stderr`. See below for a list of debugging flags which can be combined using bit operations to control debugging.

get_debug()

Return the debugging flags currently set.

get_objects()

Returns a list of all objects tracked by the collector, excluding the list returned. New in version 2.2.

set_threshold(threshold0[, threshold1[, threshold2]])

Set the garbage collection thresholds (the collection frequency). Setting *threshold0* to zero disables collection.

The GC classifies objects into three generations depending on how many collection sweeps they have survived. New objects are placed in the youngest generation (generation 0). If an object survives a collection it is moved into the next older generation. Since generation 2 is the oldest generation, objects in that generation remain there after a collection. In order to decide when to run, the collector keeps track of the number object allocations and deallocations since the last collection. When the number of allocations minus the number of deallocations exceeds *threshold0*, collection starts. Initially only generation 0 is examined. If generation 0 has been examined more than *threshold1* times since generation 1 has been examined, then generation 1 is examined as well. Similarly, *threshold2* controls the number of collections of generation 1 before collecting generation 2.

get_count()

Return the current collection counts as a tuple of (*count0*, *count1*, *count2*). New in version 2.5.

get_threshold()

Return the current collection thresholds as a tuple of (*threshold0*, *threshold1*, *threshold2*).

get_referrers(*objs)

Return the list of objects that directly refer to any of *objs*. This function will only locate those containers which support garbage collection; extension types which do refer to other objects but do not support garbage collection will not be found.

Note that objects which have already been dereferenced, but which live in cycles and have not yet been collected by the garbage collector can be listed among the resulting referrers. To get only currently live objects, call `collect()` before calling `get_referrers()`.

Care must be taken when using objects returned by `get_referrers()` because some of them could still be under construction and hence in a temporarily invalid state. Avoid using `get_referrers()` for any purpose other than debugging.

New in version 2.2.

get_referents (*objs)

Return a list of objects directly referred to by any of the arguments. The referents returned are those objects visited by the arguments' C-level `tp_traverse` methods (if any), and may not be all objects actually directly reachable. `tp_traverse` methods are supported only by objects that support garbage collection, and are only required to visit objects that may be involved in a cycle. So, for example, if an integer is directly reachable from an argument, that integer object may or may not appear in the result list.

New in version 2.3.

The following variable is provided for read-only access (you can mutate its value but should not rebind it):

garbage

A list of objects which the collector found to be unreachable but could not be freed (uncollectable objects). By default, this list contains only objects with `__del__()` methods.¹ Objects that have `__del__()` methods and are part of a reference cycle cause the entire reference cycle to be uncollectable, including objects not necessarily in the cycle but reachable only from it. Python doesn't collect such cycles automatically because, in general, it isn't possible for Python to guess a safe order in which to run the `__del__()` methods. If you know a safe order, you can force the issue by examining the *garbage* list, and explicitly breaking cycles due to your objects within the list. Note that these objects are kept alive even so by virtue of being in the *garbage* list, so they should be removed from *garbage* too. For example, after breaking cycles, do `del gc.garbage[:]` to empty the list. It's generally better to avoid the issue by not creating cycles containing objects with `__del__()` methods, and *garbage* can be examined in that case to verify that no such cycles are being created.

If `DEBUG_SAVEALL` is set, then all unreachable objects will be added to this list rather than freed.

The following constants are provided for use with `set_debug()`:

DEBUG_STATS

Print statistics during collection. This information can be useful when tuning the collection frequency.

DEBUG_COLLECTABLE

Print information on collectable objects found.

DEBUG_UNCOLLECTABLE

Print information of uncollectable objects found (objects which are not reachable but cannot be freed by the collector). These objects will be added to the *garbage* list.

DEBUG_INSTANCES

When `DEBUG_COLLECTABLE` or `DEBUG_UNCOLLECTABLE` is set, print information about instance objects found.

DEBUG_OBJECTS

When `DEBUG_COLLECTABLE` or `DEBUG_UNCOLLECTABLE` is set, print information about objects other than instance objects found.

DEBUG_SAVEALL

When set, all unreachable objects found will be appended to *garbage* rather than being freed. This can be useful for debugging a leaking program.

DEBUG_LEAK

The debugging flags necessary for the collector to print information about a leaking program (equal to `DEBUG_COLLECTABLE | DEBUG_UNCOLLECTABLE | DEBUG_INSTANCES | DEBUG_OBJECTS | DEBUG_SAVEALL`).

26.10 inspect — Inspect live objects

New in version 2.1.

¹Prior to Python 2.2, the list contained all instance objects in unreachable cycles, not only those with `__del__()` methods.

The `inspect` module provides several useful functions to help get information about live objects such as modules, classes, methods, functions, tracebacks, frame objects, and code objects. For example, it can help you examine the contents of a class, retrieve the source code of a method, extract and format the argument list for a function, or get all the information you need to display a detailed traceback.

There are four main kinds of services provided by this module: type checking, getting source code, inspecting classes and functions, and examining the interpreter stack.

26.10.1 Types and members

The `getmembers()` function retrieves the members of an object such as a class or module. The eleven functions whose names begin with “is” are mainly provided as convenient choices for the second argument to `getmembers()`. They also help you determine when you can expect to find the following special attributes:

Type	Attribute	Description	Notes
module	<code>__doc__</code>	documentation string	
	<code>__file__</code>	filename (missing for built-in modules)	
class	<code>__doc__</code>	documentation string	
	<code>__module__</code>	name of module in which this class was defined	
method	<code>__doc__</code>	documentation string	(1)
	<code>__name__</code>	name with which this method was defined	
	<code>im_class</code>	class object that asked for this method	
	<code>im_func</code>	function object containing implementation of method	
	<code>im_self</code>	instance to which this method is bound, or <code>None</code>	
function	<code>__doc__</code>	documentation string	
	<code>__name__</code>	name with which this function was defined	
	<code>func_code</code>	code object containing compiled function bytecode	
	<code>func_defaults</code>	tuple of any default values for arguments	
	<code>func_doc</code>	(same as <code>__doc__</code>)	
	<code>func_globals</code>	global namespace in which this function was defined	
traceback	<code>func_name</code>	(same as <code>__name__</code>)	
	<code>tb_frame</code>	frame object at this level	
	<code>tb_lasti</code>	index of last attempted instruction in bytecode	
	<code>tb_lineno</code>	current line number in Python source code	
frame	<code>tb_next</code>	next inner traceback object (called by this level)	
	<code>f_back</code>	next outer frame object (this frame's caller)	
	<code>f_builtins</code>	built-in namespace seen by this frame	
	<code>f_code</code>	code object being executed in this frame	
code	<code>f_exc_traceback</code>	traceback if raised in this frame, or <code>None</code>	
	<code>f_exc_type</code>	exception type if raised in this frame, or <code>None</code>	
	<code>f_exc_value</code>	exception value if raised in this frame, or <code>None</code>	
	<code>f_globals</code>	global namespace seen by this frame	
	<code>f_lasti</code>	index of last attempted instruction in bytecode	
	<code>f_lineno</code>	current line number in Python source code	
	<code>f_locals</code>	local namespace seen by this frame	
	<code>f_restricted</code>	0 or 1 if frame is in restricted execution mode	
	<code>f_trace</code>	tracing function for this frame, or <code>None</code>	
	<code>co_argcount</code>	number of arguments (not including <code>*</code> or <code>**</code> args)	
	<code>co_code</code>	string of raw compiled bytecode	
builtin	<code>co_consts</code>	tuple of constants used in the bytecode	
	<code>co_filename</code>	name of file in which this code object was created	
	<code>co_firstlineno</code>	number of first line in Python source code	
	<code>co_flags</code>	bitmap: 1=optimized 2=newlocals 4= <code>*arg</code> 8= <code>**arg</code>	
	<code>co_lnotab</code>	encoded mapping of line numbers to bytecode indices	
	<code>co_name</code>	name with which this code object was defined	
	<code>co_names</code>	tuple of names of local variables	
	<code>co_nlocals</code>	number of local variables	
	<code>co_stacksize</code>	virtual machine stack space required	
	<code>co_varnames</code>	tuple of names of arguments and local variables	
	<code>__doc__</code>	documentation string	
builtin	<code>__name__</code>	original name of this function or method	
	<code>__self__</code>	instance to which a method is bound, or <code>None</code>	

Note:

(1) Changed in version 2.2: `im_class` used to refer to the class that defined the method.

getmembers (*object*[, *predicate*])

Return all the members of an object in a list of (name, value) pairs sorted by name. If the optional *predicate* argument is supplied, only members for which the predicate returns a true value are included.

getmoduleinfo (*path*)

Return a tuple of values that describe how Python will interpret the file identified by *path* if it is a module, or *None* if it would not be identified as a module. The return tuple is (*name*, *suffix*, *mode*, *mtype*), where *name* is the name of the module without the name of any enclosing package, *suffix* is the trailing part of the file name (which may not be a dot-delimited extension), *mode* is the `open()` mode that would be used ('r' or 'rb'), and *mtype* is an integer giving the type of the module. *mtype* will have a value which can be compared to the constants defined in the `imp` module; see the documentation for that module for more information on module types.

getmodulename (*path*)

Return the name of the module named by the file *path*, without including the names of enclosing packages. This uses the same algorithm as the interpreter uses when searching for modules. If the name cannot be matched according to the interpreter's rules, *None* is returned.

ismodule (*object*)

Return true if the object is a module.

isclass (*object*)

Return true if the object is a class.

ismethod (*object*)

Return true if the object is a method.

isfunction (*object*)

Return true if the object is a Python function or unnamed (lambda) function.

istraceback (*object*)

Return true if the object is a traceback.

isframe (*object*)

Return true if the object is a frame.

iscode (*object*)

Return true if the object is a code.

isbuiltin (*object*)

Return true if the object is a built-in function.

isroutine (*object*)

Return true if the object is a user-defined or built-in function or method.

ismethoddescriptor (*object*)

Return true if the object is a method descriptor, but not if `ismethod()` or `isclass()` or `isfunction()` are true.

This is new as of Python 2.2, and, for example, is true of `int.__add__`. An object passing this test has a `__get__` attribute but not a `__set__` attribute, but beyond that the set of attributes varies. `__name__` is usually sensible, and `__doc__` often is.

Methods implemented via descriptors that also pass one of the other tests return false from the `ismethoddescriptor()` test, simply because the other tests promise more – you can, e.g., count on having the `im_func` attribute (etc) when an object passes `ismethod()`.

isdatadescriptor (*object*)

Return true if the object is a data descriptor.

Data descriptors have both a `__get__` and a `__set__` attribute. Examples are properties (defined in Python), getsets, and members. The latter two are defined in C and there are more specific tests available for those types, which is robust across Python implementations. Typically, data descriptors will also have `__name__` and `__doc__` attributes (properties, getsets, and members have both of these attributes), but this is not guaranteed. New in version 2.3.

isgetsetdescriptor (*object*)

Return true if the object is a getset descriptor.

getsets are attributes defined in extension modules via `PyGetSetDef` structures. For Python implementations without such types, this method will always return `False`. New in version 2.5.

ismemberdescriptor (*object*)

Return true if the object is a member descriptor.

Member descriptors are attributes defined in extension modules via `PyMemberDef` structures. For Python implementations without such types, this method will always return `False`. New in version 2.5.

26.10.2 Retrieving source code

getdoc (*object*)

Get the documentation string for an object. All tabs are expanded to spaces. To clean up docstrings that are indented to line up with blocks of code, any whitespace than can be uniformly removed from the second line onwards is removed.

getcomments (*object*)

Return in a single string any lines of comments immediately preceding the object's source code (for a class, function, or method), or at the top of the Python source file (if the object is a module).

getfile (*object*)

Return the name of the (text or binary) file in which an object was defined. This will fail with a `TypeError` if the object is a built-in module, class, or function.

getmodule (*object*)

Try to guess which module an object was defined in.

getsourcefile (*object*)

Return the name of the Python source file in which an object was defined. This will fail with a `TypeError` if the object is a built-in module, class, or function.

getsourcelines (*object*)

Return a list of source lines and starting line number for an object. The argument may be a module, class, method, function, traceback, frame, or code object. The source code is returned as a list of the lines corresponding to the object and the line number indicates where in the original source file the first line of code was found. An `IOError` is raised if the source code cannot be retrieved.

getsource (*object*)

Return the text of the source code for an object. The argument may be a module, class, method, function, traceback, frame, or code object. The source code is returned as a single string. An `IOError` is raised if the source code cannot be retrieved.

26.10.3 Classes and functions

getclasstree (*classes* [, *unique*])

Arrange the given list of classes into a hierarchy of nested lists. Where a nested list appears, it contains classes derived from the class whose entry immediately precedes the list. Each entry is a 2-tuple containing a class and a tuple of its base classes. If the *unique* argument is true, exactly one entry appears in the returned structure for each class in the given list. Otherwise, classes using multiple inheritance and their descendants will appear multiple times.

getargspec (*func*)

Get the names and default values of a function's arguments. A tuple of four things is returned: (*args*, *varargs*, *varkw*, *defaults*). *args* is a list of the argument names (it may contain nested lists). *varargs* and *varkw* are the

names of the `*` and `**` arguments or `None`. *defaults* is a tuple of default argument values or `None` if there are no default arguments; if this tuple has *n* elements, they correspond to the last *n* elements listed in *args*.

getargvalues (*frame*)

Get information about arguments passed into a particular frame. A tuple of four things is returned: (*args*, *varargs*, *varkw*, *locals*). *args* is a list of the argument names (it may contain nested lists). *varargs* and *varkw* are the names of the `*` and `**` arguments or `None`. *locals* is the locals dictionary of the given frame.

formatargspec (*args*[, *varargs*, *varkw*, *defaults*, *formatarg*, *formatvarargs*, *formatvarkw*, *formatvalue*, *join*])

Format a pretty argument spec from the four values returned by `getargspec()`. The *format** arguments are the corresponding optional formatting functions that are called to turn names and values into strings.

formatargvalues (*args*[, *varargs*, *varkw*, *locals*, *formatarg*, *formatvarargs*, *formatvarkw*, *formatvalue*, *join*])

Format a pretty argument spec from the four values returned by `getargvalues()`. The *format** arguments are the corresponding optional formatting functions that are called to turn names and values into strings.

getmro (*cls*)

Return a tuple of class *cls*'s base classes, including *cls*, in method resolution order. No class appears more than once in this tuple. Note that the method resolution order depends on *cls*'s type. Unless a very peculiar user-defined metatype is in use, *cls* will be the first element of the tuple.

26.10.4 The interpreter stack

When the following functions return “frame records,” each record is a tuple of six items: the frame object, the filename, the line number of the current line, the function name, a list of lines of context from the source code, and the index of the current line within that list.

Warning: Keeping references to frame objects, as found in the first element of the frame records these functions return, can cause your program to create reference cycles. Once a reference cycle has been created, the lifespan of all objects which can be accessed from the objects which form the cycle can become much longer even if Python's optional cycle detector is enabled. If such cycles must be created, it is important to ensure they are explicitly broken to avoid the delayed destruction of objects and increased memory consumption which occurs. Though the cycle detector will catch these, destruction of the frames (and local variables) can be made deterministic by removing the cycle in a `finally` clause. This is also important if the cycle detector was disabled when Python was compiled or using `gc.disable()`. For example:

```
def handle_stackframe_without_leak():
    frame = inspect.currentframe()
    try:
        # do something with the frame
    finally:
        del frame
```

The optional *context* argument supported by most of these functions specifies the number of lines of context to return, which are centered around the current line.

getframeinfo (*frame*[, *context*])

Get information about a frame or traceback object. A 5-tuple is returned, the last five elements of the frame's frame record.

getouterframes (*frame*[, *context*])

Get a list of frame records for a frame and all outer frames. These frames represent the calls that lead to the creation of *frame*. The first entry in the returned list represents *frame*; the last entry represents the outermost call on *frame*'s stack.

getinnerframes (*traceback*[, *context*])

Get a list of frame records for a traceback's frame and all inner frames. These frames represent calls made as a consequence of *frame*. The first entry in the list represents *traceback*; the last entry represents where the exception was raised.

currentframe ()

Return the frame object for the caller's stack frame.

stack ([*context*])

Return a list of frame records for the caller's stack. The first entry in the returned list represents the caller; the last entry represents the outermost call on the stack.

trace ([*context*])

Return a list of frame records for the stack between the current frame and the frame in which an exception currently being handled was raised in. The first entry in the list represents the caller; the last entry represents where the exception was raised.

26.11 `site` — Site-specific configuration hook

This module is automatically imported during initialization. The automatic import can be suppressed using the interpreter's `-S` option.

Importing this module will append site-specific paths to the module search path.

It starts by constructing up to four directories from a head and a tail part. For the head part, it uses `sys.prefix` and `sys.exec_prefix`; empty heads are skipped. For the tail part, it uses the empty string and then `'lib/site-packages'` (on Windows) or `'lib/python2.5/site-packages'` and then `'lib/site-python'` (on UNIX and Macintosh). For each of the distinct head-tail combinations, it sees if it refers to an existing directory, and if so, adds it to `sys.path` and also inspects the newly added path for configuration files.

A path configuration file is a file whose name has the form `'package.pth'` and exists in one of the four directories mentioned above; its contents are additional items (one per line) to be added to `sys.path`. Non-existing items are never added to `sys.path`, but no check is made that the item refers to a directory (rather than a file). No item is added to `sys.path` more than once. Blank lines and lines beginning with `#` are skipped. Lines starting with `import` are executed.

For example, suppose `sys.prefix` and `sys.exec_prefix` are set to `'/usr/local'`. The Python 2.5.2 library is then installed in `'/usr/local/lib/python2.5'` (where only the first three characters of `sys.version` are used to form the installation path name). Suppose this has a subdirectory `'/usr/local/lib/python2.5/site-packages'` with three subsubdirectories, `'foo'`, `'bar'` and `'spam'`, and two path configuration files, `'foo.pth'` and `'bar.pth'`. Assume `'foo.pth'` contains the following:

```
# foo package configuration

foo
bar
bletch
```

and `'bar.pth'` contains:

```
# bar package configuration

bar
```

Then the following directories are added to `sys.path`, in this order:

```
/usr/local/lib/python2.3/site-packages/bar
/usr/local/lib/python2.3/site-packages/foo
```

Note that ‘bletch’ is omitted because it doesn’t exist; the ‘bar’ directory precedes the ‘foo’ directory because ‘bar.pth’ comes alphabetically before ‘foo.pth’; and ‘spam’ is omitted because it is not mentioned in either path configuration file.

After these path manipulations, an attempt is made to import a module named `sitecustomize`, which can perform arbitrary site-specific customizations. If this import fails with an `ImportError` exception, it is silently ignored.

Note that for some non-UNIX systems, `sys.prefix` and `sys.exec_prefix` are empty, and the path manipulations are skipped; however the import of `sitecustomize` is still attempted.

26.12 `user` — User-specific configuration hook

As a policy, Python doesn’t run user-specified code on startup of Python programs. (Only interactive sessions execute the script specified in the `PYTHONSTARTUP` environment variable if it exists).

However, some programs or sites may find it convenient to allow users to have a standard customization file, which gets run when a program requests it. This module implements such a mechanism. A program that wishes to use the mechanism must execute the statement

```
import user
```

The `user` module looks for a file ‘`.pythonrc.py`’ in the user’s home directory and if it can be opened, executes it (using `execfile()`) in its own (the module `user`’s) global namespace. Errors during this phase are not caught; that’s up to the program that imports the `user` module, if it wishes. The home directory is assumed to be named by the `HOME` environment variable; if this is not set, the current directory is used.

The user’s ‘`.pythonrc.py`’ could conceivably test for `sys.version` if it wishes to do different things depending on the Python version.

A warning to users: be very conservative in what you place in your ‘`.pythonrc.py`’ file. Since you don’t know which programs will use it, changing the behavior of standard modules or functions is generally not a good idea.

A suggestion for programmers who wish to use this mechanism: a simple way to let users specify options for your package is to have them define variables in their ‘`.pythonrc.py`’ file that you test in your module. For example, a module `spam` that has a verbosity level can look for a variable `user.spam_verbosity`, as follows:

```
import user

verbosity = bool(getattr(user, "spam_verbosity", 0))
```

(The three-argument form of `getattr()` is used in case the user has not defined `spam_verbosity` in their ‘`.pythonrc.py`’ file.)

Programs with extensive customization needs are better off reading a program-specific customization file.

Programs with security or privacy concerns should *not* import this module; a user can easily break into a program by placing arbitrary code in the ‘`.pythonrc.py`’ file.

Modules for general use should *not* import this module; it may interfere with the operation of the importing program.

See Also:

[Module `site`](#) (section 26.11):

Site-wide customization mechanism.

26.13 `fpectl` — Floating point exception control

Note: The `fpectl` module is not built by default, and its usage is discouraged and may be dangerous except in the hands of experts. See also the section 26.13.2 on limitations for more details.

Most computers carry out floating point operations in conformance with the so-called IEEE-754 standard. On any real computer, some floating point operations produce results that cannot be expressed as a normal floating point value. For example, try

```
>>> import math
>>> math.exp(1000)
inf
>>> math.exp(1000) / math.exp(1000)
nan
```

(The example above will work on many platforms. DEC Alpha may be one exception.) "Inf" is a special, non-numeric value in IEEE-754 that stands for "infinity", and "nan" means "not a number." Note that, other than the non-numeric results, nothing special happened when you asked Python to carry out those calculations. That is in fact the default behaviour prescribed in the IEEE-754 standard, and if it works for you, stop reading now.

In some circumstances, it would be better to raise an exception and stop processing at the point where the faulty operation was attempted. The `fpectl` module is for use in that situation. It provides control over floating point units from several hardware manufacturers, allowing the user to turn on the generation of SIGFPE whenever any of the IEEE-754 exceptions Division by Zero, Overflow, or Invalid Operation occurs. In tandem with a pair of wrapper macros that are inserted into the C code comprising your python system, SIGFPE is trapped and converted into the Python `FloatingPointError` exception.

The `fpectl` module defines the following functions and may raise the given exception:

`turnon_sigfpe()`

Turn on the generation of SIGFPE, and set up an appropriate signal handler.

`turnoff_sigfpe()`

Reset default handling of floating point exceptions.

exception `FloatingPointError`

After `turnon_sigfpe()` has been executed, a floating point operation that raises one of the IEEE-754 exceptions Division by Zero, Overflow, or Invalid operation will in turn raise this standard Python exception.

26.13.1 Example

The following example demonstrates how to start up and test operation of the `fpectl` module.


```

>>> import fpectl
>>> import fpetest
>>> fpectl.turnon_sigfpe()
>>> fpetest.test()
overflow          PASS
FloatingPointError: Overflow

div by 0          PASS
FloatingPointError: Division by zero
[ more output from test elided ]
>>> import math
>>> math.exp(1000)
Traceback (most recent call last):
  File "<stdin>", line 1, in ?
FloatingPointError: in math_1

```

26.13.2 Limitations and other considerations

Setting up a given processor to trap IEEE-754 floating point errors currently requires custom code on a per-architecture basis. You may have to modify `fpectl` to control your particular hardware.

Conversion of an IEEE-754 exception to a Python exception requires that the wrapper macros `PyFPE_START_PROTECT` and `PyFPE_END_PROTECT` be inserted into your code in an appropriate fashion. Python itself has been modified to support the `fpectl` module, but many other codes of interest to numerical analysts have not.

The `fpectl` module is not thread-safe.

See Also:

Some files in the source distribution may be interesting in learning more about how this module operates. The include file `'Include/pyfpe.h'` discusses the implementation of this module at some length. `'Modules/fpetestmodule.c'` gives several examples of use. Many additional examples can be found in `'Objects/floatobject.c'`.

Custom Python Interpreters

The modules described in this chapter allow writing interfaces similar to Python's interactive interpreter. If you want a Python interpreter that supports some special feature in addition to the Python language, you should look at the `code` module. (The `codeop` module is lower-level, used to support compiling a possibly-incomplete chunk of Python code.)

The full list of modules described in this chapter is:

- `code` Base classes for interactive Python interpreters.
- `codeop` Compile (possibly incomplete) Python code.

27.1 `code` — Interpreter base classes

The `code` module provides facilities to implement read-eval-print loops in Python. Two classes and convenience functions are included which can be used to build applications which provide an interactive interpreter prompt.

class `InteractiveInterpreter` (`[locals]`)

This class deals with parsing and interpreter state (the user's namespace); it does not deal with input buffering or prompting or input file naming (the filename is always passed in explicitly). The optional `locals` argument specifies the dictionary in which code will be executed; it defaults to a newly created dictionary with key `'__name__'` set to `'__console__'` and key `'__doc__'` set to `None`.

class `InteractiveConsole` (`[locals[, filename]]`)

Closely emulate the behavior of the interactive Python interpreter. This class builds on `InteractiveInterpreter` and adds prompting using the familiar `sys.ps1` and `sys.ps2`, and input buffering.

function `interact` (`[banner[, readfunc[, local]]]`)

Convenience function to run a read-eval-print loop. This creates a new instance of `InteractiveConsole` and sets `readfunc` to be used as the `raw_input()` method, if provided. If `local` is provided, it is passed to the `InteractiveConsole` constructor for use as the default namespace for the interpreter loop. The `interact()` method of the instance is then run with `banner` passed as the banner to use, if provided. The console object is discarded after use.

function `compile_command` (`source[, filename[, symbol]]`)

This function is useful for programs that want to emulate Python's interpreter main loop (a.k.a. the read-eval-print loop). The tricky part is to determine when the user has entered an incomplete command that can be completed by entering more text (as opposed to a complete command or a syntax error). This function *almost* always makes the same decision as the real interpreter main loop.

`source` is the source string; `filename` is the optional filename from which source was read, defaulting to `'<input>'`; and `symbol` is the optional grammar start symbol, which should be either `'single'` (the default) or `'eval'`.

Returns a code object (the same as `compile(source, filename, symbol)`) if the command is complete and valid; `None` if the command is incomplete; raises `SyntaxError` if the command is complete and contains a syntax error, or raises `OverflowError` or `ValueError` if the command contains an invalid literal.

27.1.1 Interactive Interpreter Objects

runsource (*source* [, *filename* [, *symbol*]])

Compile and run some source in the interpreter. Arguments are the same as for `compile_command()`; the default for *filename* is '`<input>`', and for *symbol* is '`single`'. One several things can happen:

- The input is incorrect; `compile_command()` raised an exception (`SyntaxError` or `OverflowError`). A syntax traceback will be printed by calling the `showsyntaxerror()` method. `runsource()` returns `False`.
- The input is incomplete, and more input is required; `compile_command()` returned `None`. `runsource()` returns `True`.
- The input is complete; `compile_command()` returned a code object. The code is executed by calling the `runcode()` (which also handles run-time exceptions, except for `SystemExit`). `runsource()` returns `False`.

The return value can be used to decide whether to use `sys.ps1` or `sys.ps2` to prompt the next line.

runcode (*code*)

Execute a code object. When an exception occurs, `showtraceback()` is called to display a traceback. All exceptions are caught except `SystemExit`, which is allowed to propagate.

A note about `KeyboardInterrupt`: this exception may occur elsewhere in this code, and may not always be caught. The caller should be prepared to deal with it.

showsyntaxerror ([*filename*])

Display the syntax error that just occurred. This does not display a stack trace because there isn't one for syntax errors. If *filename* is given, it is stuffed into the exception instead of the default filename provided by Python's parser, because it always uses '`<string>`' when reading from a string. The output is written by the `write()` method.

showtraceback ()

Display the exception that just occurred. We remove the first stack item because it is within the interpreter object implementation. The output is written by the `write()` method.

write (*data*)

Write a string to the standard error stream (`sys.stderr`). Derived classes should override this to provide the appropriate output handling as needed.

27.1.2 Interactive Console Objects

The `InteractiveConsole` class is a subclass of `InteractiveInterpreter`, and so offers all the methods of the interpreter objects as well as the following additions.

interact ([*banner*])

Closely emulate the interactive Python console. The optional banner argument specify the banner to print before the first interaction; by default it prints a banner similar to the one printed by the standard Python interpreter, followed by the class name of the console object in parentheses (so as not to confuse this with the real interpreter – since it's so close!).

push (*line*)

Push a line of source text to the interpreter. The line should not have a trailing newline; it may have internal

newlines. The line is appended to a buffer and the interpreter's `runsource()` method is called with the concatenated contents of the buffer as source. If this indicates that the command was executed or invalid, the buffer is reset; otherwise, the command is incomplete, and the buffer is left as it was after the line was appended. The return value is `True` if more input is required, `False` if the line was dealt with in some way (this is the same as `runsource()`).

resetbuffer()

Remove any unhandled source text from the input buffer.

raw_input([prompt])

Write a prompt and read a line. The returned line does not include the trailing newline. When the user enters the EOF key sequence, `EOFError` is raised. The base implementation uses the built-in function `raw_input()`; a subclass may replace this with a different implementation.

27.2 codeop — Compile Python code

The `codeop` module provides utilities upon which the Python read-eval-print loop can be emulated, as is done in the `code` module. As a result, you probably don't want to use the module directly; if you want to include such a loop in your program you probably want to use the `code` module instead.

There are two parts to this job:

1. Being able to tell if a line of input completes a Python statement: in short, telling whether to print `'>>> '` or `'... '` next.
2. Remembering which future statements the user has entered, so subsequent input can be compiled with these in effect.

The `codeop` module provides a way of doing each of these things, and a way of doing them both.

To do just the former:

compile_command(source[, filename[, symbol]])

Tries to compile *source*, which should be a string of Python code and return a code object if *source* is valid Python code. In that case, the filename attribute of the code object will be *filename*, which defaults to `'<input>'`. Returns `None` if *source* is *not* valid Python code, but is a prefix of valid Python code.

If there is a problem with *source*, an exception will be raised. `SyntaxError` is raised if there is invalid Python syntax, and `OverflowError` or `ValueError` if there is an invalid literal.

The *symbol* argument determines whether *source* is compiled as a statement (`'single'`, the default) or as an expression (`'eval'`). Any other value will cause `ValueError` to be raised.

Caveat: It is possible (but not likely) that the parser stops parsing with a successful outcome before reaching the end of the source; in this case, trailing symbols may be ignored instead of causing an error. For example, a backslash followed by two newlines may be followed by arbitrary garbage. This will be fixed once the API for the parser is better.

class Compile()

Instances of this class have `__call__()` methods identical in signature to the built-in function `compile()`, but with the difference that if the instance compiles program text containing a `__future__` statement, the instance 'remembers' and compiles all subsequent program texts with the statement in force.

class CommandCompiler()

Instances of this class have `__call__()` methods identical in signature to `compile_command()`; the difference is that if the instance compiles program text containing a `__future__` statement, the instance 'remembers' and compiles all subsequent program texts with the statement in force.

A note on version compatibility: the `Compile` and `CommandCompiler` are new in Python 2.2. If you want to enable the future-tracking features of 2.2 but also retain compatibility with 2.1 and earlier versions of Python you can either write

```
try:
    from codeop import CommandCompiler
    compile_command = CommandCompiler()
    del CommandCompiler
except ImportError:
    from codeop import compile_command
```

which is a low-impact change, but introduces possibly unwanted global state into your program, or you can write:

```
try:
    from codeop import CommandCompiler
except ImportError:
    def CommandCompiler():
        from codeop import compile_command
        return compile_command
```

and then call `CommandCompiler` every time you need a fresh compiler object.

Restricted Execution

Warning: In Python 2.3 these modules have been disabled due to various known and not readily fixable security holes. The modules are still documented here to help in reading old code that uses the `rexec` and `Bastion` modules.

Restricted execution is the basic framework in Python that allows for the segregation of trusted and untrusted code. The framework is based on the notion that trusted Python code (a *supervisor*) can create a “padded cell” (or environment) with limited permissions, and run the untrusted code within this cell. The untrusted code cannot break out of its cell, and can only interact with sensitive system resources through interfaces defined and managed by the trusted code. The term “restricted execution” is favored over “safe-Python” since true safety is hard to define, and is determined by the way the restricted environment is created. Note that the restricted environments can be nested, with inner cells creating subcells of lesser, but never greater, privilege.

An interesting aspect of Python’s restricted execution model is that the interfaces presented to untrusted code usually have the same names as those presented to trusted code. Therefore no special interfaces need to be learned to write code designed to run in a restricted environment. And because the exact nature of the padded cell is determined by the supervisor, different restrictions can be imposed, depending on the application. For example, it might be deemed “safe” for untrusted code to read any file within a specified directory, but never to write a file. In this case, the supervisor may redefine the built-in `open()` function so that it raises an exception whenever the *mode* parameter is `'w'`. It might also perform a `chroot()`-like operation on the *filename* parameter, such that root is always relative to some safe “sandbox” area of the filesystem. In this case, the untrusted code would still see an built-in `open()` function in its environment, with the same calling interface. The semantics would be identical too, with `IOErrors` being raised when the supervisor determined that an unallowable parameter is being used.

The Python run-time determines whether a particular code block is executing in restricted execution mode based on the identity of the `__builtins__` object in its global variables: if this is (the dictionary of) the standard `__builtin__` module, the code is deemed to be unrestricted, else it is deemed to be restricted.

Python code executing in restricted mode faces a number of limitations that are designed to prevent it from escaping from the padded cell. For instance, the function object attribute `func_globals` and the class and instance object attribute `__dict__` are unavailable.

Two modules provide the framework for setting up restricted execution environments:

`rexec` Basic restricted execution framework.
`Bastion` Providing restricted access to objects.

See Also:

Grail Home Page
(<http://grail.sourceforge.net/>)

Grail, an Internet browser written in Python, uses these modules to support Python applets. More information on the use of Python’s restricted execution mode in Grail is available on the Web site.

28.1 `rexec` — Restricted execution framework

Changed in version 2.3: Disabled module.

Warning: The documentation has been left in place to help in reading old code that uses the module.

This module contains the `RExec` class, which supports `r_eval()`, `r_execfile()`, `r_exec()`, and `r_import()` methods, which are restricted versions of the standard Python functions `eval()`, `execfile()` and the `exec` and `import` statements. Code executed in this restricted environment will only have access to modules and functions that are deemed safe; you can subclass `RExec` to add or remove capabilities as desired.

Warning: While the `rexec` module is designed to perform as described below, it does have a few known vulnerabilities which could be exploited by carefully written code. Thus it should not be relied upon in situations requiring “production ready” security. In such situations, execution via sub-processes or very careful “cleansing” of both code and data to be processed may be necessary. Alternatively, help in patching known `rexec` vulnerabilities would be welcomed.

Note: The `RExec` class can prevent code from performing unsafe operations like reading or writing disk files, or using TCP/IP sockets. However, it does not protect against code using extremely large amounts of memory or processor time.

class `RExec` (`[hooks[, verbose]]`)

Returns an instance of the `RExec` class.

`hooks` is an instance of the `RHooks` class or a subclass of it. If it is omitted or `None`, the default `RHooks` class is instantiated. Whenever the `rexec` module searches for a module (even a built-in one) or reads a module’s code, it doesn’t actually go out to the file system itself. Rather, it calls methods of an `RHooks` instance that was passed to or created by its constructor. (Actually, the `RExec` object doesn’t make these calls — they are made by a module loader object that’s part of the `RExec` object. This allows another level of flexibility, which can be useful when changing the mechanics of `import` within the restricted environment.)

By providing an alternate `RHooks` object, we can control the file system accesses made to import a module, without changing the actual algorithm that controls the order in which those accesses are made. For instance, we could substitute an `RHooks` object that passes all filesystem requests to a file server elsewhere, via some RPC mechanism such as ILU. Grail’s applet loader uses this to support importing applets from a URL for a directory.

If `verbose` is true, additional debugging output may be sent to standard output.

It is important to be aware that code running in a restricted environment can still call the `sys.exit()` function. To disallow restricted code from exiting the interpreter, always protect calls that cause restricted code to run with a `try/except` statement that catches the `SystemExit` exception. Removing the `sys.exit()` function from the restricted environment is not sufficient — the restricted code could still use `raise SystemExit`. Removing `SystemExit` is not a reasonable option; some library code makes use of this and would break were it not available.

See Also:

Grail Home Page

(<http://grail.sourceforge.net/>)

Grail is a Web browser written entirely in Python. It uses the `rexec` module as a foundation for supporting Python applets, and can be used as an example usage of this module.

28.1.1 `RExec` Objects

`RExec` instances support the following methods:

`r_eval` (*code*)

code must either be a string containing a Python expression, or a compiled code object, which will be evaluated

in the restricted environment's `__main__` module. The value of the expression or code object will be returned.

r_exec (*code*)

code must either be a string containing one or more lines of Python code, or a compiled code object, which will be executed in the restricted environment's `__main__` module.

r_execfile (*filename*)

Execute the Python code contained in the file *filename* in the restricted environment's `__main__` module.

Methods whose names begin with 's_' are similar to the functions beginning with 'r_', but the code will be granted access to restricted versions of the standard I/O streams `sys.stdin`, `sys.stderr`, and `sys.stdout`.

s_eval (*code*)

code must be a string containing a Python expression, which will be evaluated in the restricted environment.

s_exec (*code*)

code must be a string containing one or more lines of Python code, which will be executed in the restricted environment.

s_execfile (*code*)

Execute the Python code contained in the file *filename* in the restricted environment.

RExec objects must also support various methods which will be implicitly called by code executing in the restricted environment. Overriding these methods in a subclass is used to change the policies enforced by a restricted environment.

r_import (*modulename* [, *globals* [, *locals* [, *fromlist*]]])

Import the module *modulename*, raising an `ImportError` exception if the module is considered unsafe.

r_open (*filename* [, *mode* [, *bufsize*]])

Method called when `open()` is called in the restricted environment. The arguments are identical to those of `open()`, and a file object (or a class instance compatible with file objects) should be returned. RExec's default behaviour is allow opening any file for reading, but forbidding any attempt to write a file. See the example below for an implementation of a less restrictive `r_open()`.

r_reload (*module*)

Reload the module object *module*, re-parsing and re-initializing it.

r_unload (*module*)

Unload the module object *module* (remove it from the restricted environment's `sys.modules` dictionary).

And their equivalents with access to restricted standard I/O streams:

s_import (*modulename* [, *globals* [, *locals* [, *fromlist*]]])

Import the module *modulename*, raising an `ImportError` exception if the module is considered unsafe.

s_reload (*module*)

Reload the module object *module*, re-parsing and re-initializing it.

s_unload (*module*)

Unload the module object *module*.

28.1.2 Defining restricted environments

The `RExec` class has the following class attributes, which are used by the `__init__()` method. Changing them on an existing instance won't have any effect; instead, create a subclass of `RExec` and assign them new values in the class definition. Instances of the new class will then use those new values. All these attributes are tuples of strings.

nok_builtin_names

Contains the names of built-in functions which will *not* be available to programs running in the restricted environment. The value for `RExec` is `('open', 'reload', '__import__')`. (This gives the exceptions,

because by far the majority of built-in functions are harmless. A subclass that wants to override this variable should probably start with the value from the base class and concatenate additional forbidden functions — when new dangerous built-in functions are added to Python, they will also be added to this module.)

ok_builtin_modules

Contains the names of built-in modules which can be safely imported. The value for `RExec` is (`'audioop', 'array', 'binascii', 'cmath', 'errno', 'imageop', 'marshal', 'math', 'md5', 'operator', 'parser', 'regex', 'select', 'sha', '_sre', 'strop', 'struct', 'time'`). A similar remark about overriding this variable applies — use the value from the base class as a starting point.

ok_path

Contains the directories which will be searched when an `import` is performed in the restricted environment. The value for `RExec` is the same as `sys.path` (at the time the module is loaded) for unrestricted code.

ok_posix_names

Contains the names of the functions in the `os` module which will be available to programs running in the restricted environment. The value for `RExec` is (`'error', 'fstat', 'listdir', 'lstat', 'readlink', 'stat', 'times', 'uname', 'getpid', 'getppid', 'getcwd', 'getuid', 'getgid', 'geteuid', 'getegid'`).

ok_sys_names

Contains the names of the functions and variables in the `sys` module which will be available to programs running in the restricted environment. The value for `RExec` is (`'ps1', 'ps2', 'copyright', 'version', 'platform', 'exit', 'maxint'`).

ok_file_types

Contains the file types from which modules are allowed to be loaded. Each file type is an integer constant defined in the `imp` module. The meaningful values are `PY_SOURCE`, `PY_COMPILED`, and `C_EXTENSION`. The value for `RExec` is (`C_EXTENSION, PY_SOURCE`). Adding `PY_COMPILED` in subclasses is not recommended; an attacker could exit the restricted execution mode by putting a forged byte-compiled file (`.pyc`) anywhere in your file system, for example by writing it to `/tmp` or uploading it to the `/incoming` directory of your public FTP server.

28.1.3 An example

Let us say that we want a slightly more relaxed policy than the standard `RExec` class. For example, if we're willing to allow files in `/tmp` to be written, we can subclass the `RExec` class:

```
class TmpWriterRExec(rexec.RExec):
    def r_open(self, file, mode='r', buf=-1):
        if mode in ('r', 'rb'):
            pass
        elif mode in ('w', 'wb', 'a', 'ab'):
            # check filename : must begin with /tmp/
            if file[:5] != '/tmp/':
                raise IOError, "can't write outside /tmp"
            elif (string.find(file, '/../') >= 0 or
                  file[:3] == '../' or file[-3:] == '/../'):
                raise IOError, "'..' in filename forbidden"
            else: raise IOError, "Illegal open() mode"
        return open(file, mode, buf)
```

Notice that the above code will occasionally forbid a perfectly valid filename; for example, code in the restricted environment won't be able to open a file called `/tmp/foo/../bar`. To fix this, the `r_open()` method would have to simplify the filename to `/tmp/bar`, which would require splitting apart the filename and performing various operations

on it. In cases where security is at stake, it may be preferable to write simple code which is sometimes overly restrictive, instead of more general code that is also more complex and may harbor a subtle security hole.

28.2 Bastion — Restricting access to objects

Changed in version 2.3: Disabled module.

Warning: The documentation has been left in place to help in reading old code that uses the module.

According to the dictionary, a bastion is “a fortified area or position”, or “something that is considered a stronghold.” It’s a suitable name for this module, which provides a way to forbid access to certain attributes of an object. It must always be used with the `rexec` module, in order to allow restricted-mode programs access to certain safe attributes of an object, while denying access to other, unsafe attributes.

Bastion (*object* [, *filter* [, *name* [, *class*]]])

Protect the object *object*, returning a bastion for the object. Any attempt to access one of the object’s attributes will have to be approved by the *filter* function; if the access is denied an `AttributeError` exception will be raised.

If present, *filter* must be a function that accepts a string containing an attribute name, and returns true if access to that attribute will be permitted; if *filter* returns false, the access is denied. The default filter denies access to any function beginning with an underscore (`'_'`). The bastion’s string representation will be `<Bastion for name>` if a value for *name* is provided; otherwise, `repr(object)` will be used.

class, if present, should be a subclass of `BastionClass`; see the code in `'bastion.py'` for the details. Overriding the default `BastionClass` will rarely be required.

class BastionClass (*getfunc*, *name*)

Class which actually implements bastion objects. This is the default class used by `Bastion()`. The *getfunc* parameter is a function which returns the value of an attribute which should be exposed to the restricted execution environment when called with the name of the attribute as the only parameter. *name* is used to construct the `repr()` of the `BastionClass` instance.

Importing Modules

The modules described in this chapter provide new ways to import other Python modules and hooks for customizing the import process.

The full list of modules described in this chapter is:

<code>imp</code>	Access the implementation of the <code>import</code> statement.
<code>zipimport</code>	support for importing Python modules from ZIP archives.
<code>pkgutil</code>	Utilities to support extension of packages.
<code>modulefinder</code>	Find modules used by a script.
<code>runpy</code>	Locate and execute Python modules as scripts

29.1 `imp` — Access the `import` internals

This module provides an interface to the mechanisms used to implement the `import` statement. It defines the following constants and functions:

`get_magic()`

Return the magic string value used to recognize byte-compiled code files (`.pyc` files). (This value may be different for each Python version.)

`get_suffixes()`

Return a list of triples, each describing a particular type of module. Each triple has the form `(suffix, mode, type)`, where `suffix` is a string to be appended to the module name to form the filename to search for, `mode` is the mode string to pass to the built-in `open()` function to open the file (this can be `'r'` for text files or `'rb'` for binary files), and `type` is the file type, which has one of the values `PY_SOURCE`, `PY_COMPILED`, or `C_EXTENSION`, described below.

`find_module(name[, path])`

Try to find the module `name` on the search path `path`. If `path` is a list of directory names, each directory is searched for files with any of the suffixes returned by `get_suffixes()` above. Invalid names in the list are silently ignored (but all list items must be strings). If `path` is omitted or `None`, the list of directory names given by `sys.path` is searched, but first it searches a few special places: it tries to find a built-in module with the given name (`C_BUILTIN`), then a frozen module (`PY_FROZEN`), and on some systems some other places are looked in as well (on the Mac, it looks for a resource (`PY_RESOURCE`); on Windows, it looks in the registry which may point to a specific file).

If search is successful, the return value is a triple `(file, pathname, description)` where `file` is an open file object positioned at the beginning, `pathname` is the pathname of the file found, and `description` is a triple as contained in the list returned by `get_suffixes()` describing the kind of module found. If the module does not live in a file, the returned `file` is `None`, `filename` is the empty string, and the `description` tuple contains empty strings for its suffix and mode; the module type is as indicated in parentheses above. If the search is unsuccessful, `ImportError` is raised. Other exceptions indicate problems with the arguments or environment.

This function does not handle hierarchical module names (names containing dots). In order to find *P.M*, that is, submodule *M* of package *P*, use `find_module()` and `load_module()` to find and load package *P*, and then use `find_module()` with the *path* argument set to *P.__path__*. When *P* itself has a dotted name, apply this recipe recursively.

load_module (*name*, *file*, *filename*, *description*)

Load a module that was previously found by `find_module()` (or by an otherwise conducted search yielding compatible results). This function does more than importing the module: if the module was already imported, it is equivalent to a `reload()`! The *name* argument indicates the full module name (including the package name, if this is a submodule of a package). The *file* argument is an open file, and *filename* is the corresponding file name; these can be `None` and `''`, respectively, when the module is not being loaded from a file. The *description* argument is a tuple, as would be returned by `get_suffixes()`, describing what kind of module must be loaded.

If the load is successful, the return value is the module object; otherwise, an exception (usually `ImportError`) is raised.

Important: the caller is responsible for closing the *file* argument, if it was not `None`, even when an exception is raised. This is best done using a `try ... finally` statement.

new_module (*name*)

Return a new empty module object called *name*. This object is *not* inserted in `sys.modules`.

lock_held ()

Return `True` if the import lock is currently held, else `False`. On platforms without threads, always return `False`.

On platforms with threads, a thread executing an import holds an internal lock until the import is complete. This lock blocks other threads from doing an import until the original import completes, which in turn prevents other threads from seeing incomplete module objects constructed by the original thread while in the process of completing its import (and the imports, if any, triggered by that).

acquire_lock ()

Acquires the interpreter's import lock for the current thread. This lock should be used by import hooks to ensure thread-safety when importing modules. On platforms without threads, this function does nothing. New in version 2.3.

release_lock ()

Release the interpreter's import lock. On platforms without threads, this function does nothing. New in version 2.3.

The following constants with integer values, defined in this module, are used to indicate the search result of `find_module()`.

PY_SOURCE

The module was found as a source file.

PY_COMPILED

The module was found as a compiled code object file.

C_EXTENSION

The module was found as dynamically loadable shared library.

PY_RESOURCE

The module was found as a Mac OS 9 resource. This value can only be returned on a Mac OS 9 or earlier Macintosh.

PKG_DIRECTORY

The module was found as a package directory.

C_BUILTIN

The module was found as a built-in module.

PY_FROZEN

The module was found as a frozen module (see `init_frozen()`).

The following constant and functions are obsolete; their functionality is available through `find_module()` or `load_module()`. They are kept around for backward compatibility:

SEARCH_ERROR

Unused.

init_builtin(*name*)

Initialize the built-in module called *name* and return its module object. If the module was already initialized, it will be initialized *again*. A few modules cannot be initialized twice — attempting to initialize these again will raise an `ImportError` exception. If there is no built-in module called *name*, `None` is returned.

init_frozen(*name*)

Initialize the frozen module called *name* and return its module object. If the module was already initialized, it will be initialized *again*. If there is no frozen module called *name*, `None` is returned. (Frozen modules are modules written in Python whose compiled byte-code object is incorporated into a custom-built Python interpreter by Python's **freeze** utility. See 'Tools/freeze/' for now.)

is_builtin(*name*)

Return 1 if there is a built-in module called *name* which can be initialized again. Return -1 if there is a built-in module called *name* which cannot be initialized again (see `init_builtin()`). Return 0 if there is no built-in module called *name*.

is_frozen(*name*)

Return `True` if there is a frozen module (see `init_frozen()`) called *name*, or `False` if there is no such module.

load_compiled(*name*, *pathname*, [*file*])

Load and initialize a module implemented as a byte-compiled code file and return its module object. If the module was already initialized, it will be initialized *again*. The *name* argument is used to create or access a module object. The *pathname* argument points to the byte-compiled code file. The *file* argument is the byte-compiled code file, open for reading in binary mode, from the beginning. It must currently be a real file object, not a user-defined class emulating a file.

load_dynamic(*name*, *pathname*, [*file*])

Load and initialize a module implemented as a dynamically loadable shared library and return its module object. If the module was already initialized, it will be initialized *again*. Some modules don't like that and may raise an exception. The *pathname* argument must point to the shared library. The *name* argument is used to construct the name of the initialization function: an external C function called '`initname()`' in the shared library is called. The optional *file* argument is ignored. (Note: using shared libraries is highly system dependent, and not all systems support it.)

load_source(*name*, *pathname*, [*file*])

Load and initialize a module implemented as a Python source file and return its module object. If the module was already initialized, it will be initialized *again*. The *name* argument is used to create or access a module object. The *pathname* argument points to the source file. The *file* argument is the source file, open for reading as text, from the beginning. It must currently be a real file object, not a user-defined class emulating a file. Note that if a properly matching byte-compiled file (with suffix `.pyc` or `.pyo`) exists, it will be used instead of parsing the given source file.

class NullImporter(*path_string*)

The `NullImporter` type is a PEP 302 import hook that handles non-directory path strings by failing to find any modules. Calling this type with an existing directory or empty string raises `ImportError`. Otherwise, a `NullImporter` instance is returned.

Python adds instances of this type to `sys.path_importer_cache` for any path entries that are not directories and are not handled by any other path hooks on `sys.path_hooks`. Instances have only one method:

find_module(*fullname*, [*path*])

This method always returns `None`, indicating that the requested module could not be found.
New in version 2.5.

29.1.1 Examples

The following function emulates what was the standard import statement up to Python 1.4 (no hierarchical module names). (This *implementation* wouldn't work in that version, since `find_module()` has been extended and `load_module()` has been added in 1.4.)

```
import imp
import sys

def __import__(name, globals=None, locals=None, fromlist=None):
    # Fast path: see if the module has already been imported.
    try:
        return sys.modules[name]
    except KeyError:
        pass

    # If any of the following calls raises an exception,
    # there's a problem we can't handle -- let the caller handle it.

    fp, pathname, description = imp.find_module(name)

    try:
        return imp.load_module(name, fp, pathname, description)
    finally:
        # Since we may exit via an exception, close fp explicitly.
        if fp:
            fp.close()
```

A more complete example that implements hierarchical module names and includes a `reload()` function can be found in the module `knee`. The `knee` module can be found in 'Demo/imputil/' in the Python source distribution.

29.2 zipimport — Import modules from Zip archives

New in version 2.3.

This module adds the ability to import Python modules (`*.py`, `*.py[co]`) and packages from ZIP-format archives. It is usually not needed to use the `zipimport` module explicitly; it is automatically used by the builtin import mechanism for `sys.path` items that are paths to ZIP archives.

Typically, `sys.path` is a list of directory names as strings. This module also allows an item of `sys.path` to be a string naming a ZIP file archive. The ZIP archive can contain a subdirectory structure to support package imports, and a path within the archive can be specified to only import from a subdirectory. For example, the path `'/tmp/example.zip/lib/'` would only import from the `'lib/'` subdirectory within the archive.

Any files may be present in the ZIP archive, but only files `*.py` and `*.py[co]` are available for import. ZIP import of dynamic modules (`*.pyd`, `*.so`) is disallowed. Note that if an archive only contains `*.py` files, Python will not attempt to modify the archive by adding the corresponding `*.pyc` or `*.pyo` file, meaning that if a ZIP archive doesn't contain `*.pyc` files, importing may be rather slow.

Using the built-in `reload()` function will fail if called on a module loaded from a ZIP archive; it is unlikely that `reload()` would be needed, since this would imply that the ZIP has been altered during runtime.

The available attributes of this module are:

exception `ZipImportError`

Exception raised by `zipimporter` objects. It's a subclass of `ImportError`, so it can be caught as `ImportError`, too.

class `zipimporter`

The class for importing ZIP files. See “*zipimporter Objects*” (section 29.2.1) for constructor details.

See Also:

PKZIP Application Note

(http://www.pkware.com/business_and_developers/developer/appnote/)

Documentation on the ZIP file format by Phil Katz, the creator of the format and algorithms used.

PEP 0273, “*Import Modules from Zip Archives*”

Written by James C. Ahlstrom, who also provided an implementation. Python 2.3 follows the specification in PEP 273, but uses an implementation written by Just van Rossum that uses the import hooks described in PEP 302.

PEP 0302, “*New Import Hooks*”

The PEP to add the import hooks that help this module work.

29.2.1 `zipimporter` Objects

class `zipimporter` (*archivepath*)

Create a new `zipimporter` instance. *archivepath* must be a path to a zipfile. `ZipImportError` is raised if *archivepath* doesn't point to a valid ZIP archive.

`find_module` (*fullname* [, *path*])

Search for a module specified by *fullname*. *fullname* must be the fully qualified (dotted) module name. It returns the `zipimporter` instance itself if the module was found, or `None` if it wasn't. The optional *path* argument is ignored—it's there for compatibility with the importer protocol.

`get_code` (*fullname*)

Return the code object for the specified module. Raise `ZipImportError` if the module couldn't be found.

`get_data` (*pathname*)

Return the data associated with *pathname*. Raise `IOError` if the file wasn't found.

`get_source` (*fullname*)

Return the source code for the specified module. Raise `ZipImportError` if the module couldn't be found, return `None` if the archive does contain the module, but has no source for it.

`is_package` (*fullname*)

Return `True` if the module specified by *fullname* is a package. Raise `ZipImportError` if the module couldn't be found.

`load_module` (*fullname*)

Load the module specified by *fullname*. *fullname* must be the fully qualified (dotted) module name. It returns the imported module, or raises `ZipImportError` if it wasn't found.

29.2.2 Examples

Here is an example that imports a module from a ZIP archive - note that the `zipimport` module is not explicitly used.

```

$ unzip -l /tmp/example.zip
Archive:  /tmp/example.zip
  Length      Date    Time    Name
  -----
      8467   11-26-02  22:30   jwzthreading.py
  -----
      8467                   1 file
$ ./python
Python 2.3 (#1, Aug 1 2003, 19:54:32)
>>> import sys
>>> sys.path.insert(0, '/tmp/example.zip') # Add .zip file to front of path
>>> import jwzthreading
>>> jwzthreading.__file__
'/tmp/example.zip/jwzthreading.py'

```

29.3 pkgutil — Package extension utility

New in version 2.3.

This module provides a single function:

extend_path (*path*, *name*)

Extend the search path for the modules which comprise a package. Intended use is to place the following code in a package's `__init__.py`:

```

from pkgutil import extend_path
__path__ = extend_path(__path__, __name__)

```

This will add to the package's `__path__` all subdirectories of directories on `sys.path` named after the package. This is useful if one wants to distribute different parts of a single logical package as multiple directories.

It also looks for `*.pkg` files beginning where `*` matches the *name* argument. This feature is similar to `*.pth` files (see the [site](#) module for more information), except that it doesn't special-case lines starting with `import`. A `*.pkg` file is trusted at face value: apart from checking for duplicates, all entries found in a `*.pkg` file are added to the path, regardless of whether they exist on the filesystem. (This is a feature.)

If the input path is not a list (as is the case for frozen packages) it is returned unchanged. The input path is not modified; an extended copy is returned. Items are only appended to the copy at the end.

It is assumed that `sys.path` is a sequence. Items of `sys.path` that are not (Unicode or 8-bit) strings referring to existing directories are ignored. Unicode items on `sys.path` that cause errors when used as filenames may cause this function to raise an exception (in line with `os.path.isdir()` behavior).

29.4 modulefinder — Find modules used by a script

New in version 2.3.

This module provides a `ModuleFinder` class that can be used to determine the set of modules imported by a script. `modulefinder.py` can also be run as a script, giving the filename of a Python script as its argument, after which a report of the imported modules will be printed.

AddPackagePath (*pkg_name*, *path*)

Record that the package named *pkg_name* can be found in the specified *path*.

ReplacePackage (*oldname*, *newname*)

Allows specifying that the module named *oldname* is in fact the package named *newname*. The most common usage would be to handle how the `_xmlplus` package replaces the `xml` package.

class ModuleFinder ([*path=None*, *debug=0*, *excludes=[]*, *replace_paths=[]*])

This class provides `run_script()` and `report()` methods to determine the set of modules imported by a script. *path* can be a list of directories to search for modules; if not specified, `sys.path` is used. *debug* sets the debugging level; higher values make the class print debugging messages about what it's doing. *excludes* is a list of module names to exclude from the analysis. *replace_paths* is a list of (*oldpath*, *newpath*) tuples that will be replaced in module paths.

report ()

Print a report to standard output that lists the modules imported by the script and their paths, as well as modules that are missing or seem to be missing.

run_script (*pathname*)

Analyze the contents of the *pathname* file, which must contain Python code.

29.5 runpy — Locating and executing Python modules.

New in version 2.5.

The `runpy` module is used to locate and run Python modules without importing them first. Its main use is to implement the `-m` command line switch that allows scripts to be located using the Python module namespace rather than the filesystem.

When executed as a script, the module effectively operates as follows:

```
del sys.argv[0] # Remove the runpy module from the arguments
run_module(sys.argv[0], run_name="__main__", alter_sys=True)
```

The `runpy` module provides a single function:

run_module (*mod_name*[, *init_globals*] [, *run_name*] [, *alter_sys*])

Execute the code of the specified module and return the resulting module globals dictionary. The module's code is first located using the standard import mechanism (refer to PEP 302 for details) and then executed in a fresh module namespace.

The optional dictionary argument *init_globals* may be used to pre-populate the globals dictionary before the code is executed. The supplied dictionary will not be modified. If any of the special global variables below are defined in the supplied dictionary, those definitions are overridden by the `run_module` function.

The special global variables `__name__`, `__file__`, `__loader__` and `__builtins__` are set in the globals dictionary before the module code is executed.

`__name__` is set to *run_name* if this optional argument is supplied, and the *mod_name* argument otherwise.

`__loader__` is set to the PEP 302 module loader used to retrieve the code for the module (This loader may be a wrapper around the standard import mechanism).

`__file__` is set to the name provided by the module loader. If the loader does not make filename information available, this variable is set to `None`.

`__builtins__` is automatically initialised with a reference to the top level namespace of the `__builtin__` module.

If the argument *alter_sys* is supplied and evaluates to `True`, then `sys.argv[0]` is updated with the value of `__file__` and `sys.modules[__name__]` is updated with a temporary module object for the module

being executed. Both `sys.argv[0]` and `sys.modules[__name__]` are restored to their original values before the function returns.

Note that this manipulation of `sys` is not thread-safe. Other threads may see the partially initialised module, as well as the altered list of arguments. It is recommended that the `sys` module be left alone when invoking this function from threaded code.

See Also:

PEP 338, “*Executing modules as scripts*”

PEP written and implemented by Nick Coghlan.

Python Language Services

Python provides a number of modules to assist in working with the Python language. These modules support tokenizing, parsing, syntax analysis, bytecode disassembly, and various other facilities.

These modules include:

<code>parser</code>	Access parse trees for Python source code.
<code>symbol</code>	Constants representing internal nodes of the parse tree.
<code>token</code>	Constants representing terminal nodes of the parse tree.
<code>keyword</code>	Test whether a string is a keyword in Python.
<code>tokenize</code>	Lexical scanner for Python source code.
<code>tabnanny</code>	Tool for detecting white space related problems in Python source files in a directory tree.
<code>pyclbr</code>	Supports information extraction for a Python class browser.
<code>py_compile</code>	Compile Python source files to byte-code files.
<code>compileall</code>	Tools for byte-compiling all Python source files in a directory tree.
<code>dis</code>	Disassembler for Python byte code.
<code>pickletools</code>	Contains extensive comments about the pickle protocols and pickle-machine opcodes, as well as some useful functions.
<code>distutils</code>	Support for building and installing Python modules into an existing Python installation.

30.1 `parser` — Access Python parse trees

The `parser` module provides an interface to Python's internal parser and byte-code compiler. The primary purpose for this interface is to allow Python code to edit the parse tree of a Python expression and create executable code from this. This is better than trying to parse and modify an arbitrary Python code fragment as a string because parsing is performed in a manner identical to the code forming the application. It is also faster.

There are a few things to note about this module which are important to making use of the data structures created. This is not a tutorial on editing the parse trees for Python code, but some examples of using the `parser` module are presented.

Most importantly, a good understanding of the Python grammar processed by the internal parser is required. For full information on the language syntax, refer to the [Python Language Reference](#). The parser itself is created from a grammar specification defined in the file 'Grammar/Grammar' in the standard Python distribution. The parse trees stored in the AST objects created by this module are the actual output from the internal parser when created by the `expr()` or `suite()` functions, described below. The AST objects created by `sequence2ast()` faithfully simulate those structures. Be aware that the values of the sequences which are considered "correct" will vary from one version of Python to another as the formal grammar for the language is revised. However, transporting code from one Python version to another as source text will always allow correct parse trees to be created in the target version, with the only restriction being that migrating to an older version of the interpreter will not support more recent language constructs. The parse trees are not typically compatible from one version to another, whereas source code has always been forward-compatible.

Each element of the sequences returned by `ast2list()` or `ast2tuple()` has a simple form. Sequences representing non-terminal elements in the grammar always have a length greater than one. The first element is an integer which identifies a production in the grammar. These integers are given symbolic names in the C header file 'Include/graminit.h' and the Python module `symbol`. Each additional element of the sequence represents a component of the production as recognized in the input string: these are always sequences which have the same form as the parent. An important aspect of this structure which should be noted is that keywords used to identify the parent node type, such as the keyword `if` in an `if_stmt`, are included in the node tree without any special treatment. For example, the `if` keyword is represented by the tuple `(1, 'if')`, where 1 is the numeric value associated with all `NAME` tokens, including variable and function names defined by the user. In an alternate form returned when line number information is requested, the same token might be represented as `(1, 'if', 12)`, where the 12 represents the line number at which the terminal symbol was found.

Terminal elements are represented in much the same way, but without any child elements and the addition of the source text which was identified. The example of the `if` keyword above is representative. The various types of terminal symbols are defined in the C header file 'Include/token.h' and the Python module `token`.

The AST objects are not required to support the functionality of this module, but are provided for three purposes: to allow an application to amortize the cost of processing complex parse trees, to provide a parse tree representation which conserves memory space when compared to the Python list or tuple representation, and to ease the creation of additional modules in C which manipulate parse trees. A simple "wrapper" class may be created in Python to hide the use of AST objects.

The `parser` module defines functions for a few distinct purposes. The most important purposes are to create AST objects and to convert AST objects to other representations such as parse trees and compiled code objects, but there are also functions which serve to query the type of parse tree represented by an AST object.

See Also:

Module `symbol` (section 30.2):

Useful constants representing internal nodes of the parse tree.

Module `token` (section 30.3):

Useful constants representing leaf nodes of the parse tree and functions for testing node values.

30.1.1 Creating AST Objects

AST objects may be created from source code or from a parse tree. When creating an AST object from source, different functions are used to create the 'eval' and 'exec' forms.

expr (*source*)

The `expr()` function parses the parameter *source* as if it were an input to `'compile(source, 'file.py', 'eval')'`. If the parse succeeds, an AST object is created to hold the internal parse tree representation, otherwise an appropriate exception is thrown.

suite (*source*)

The `suite()` function parses the parameter *source* as if it were an input to `'compile(source, 'file.py', 'exec')'`. If the parse succeeds, an AST object is created to hold the internal parse tree representation, otherwise an appropriate exception is thrown.

sequence2ast (*sequence*)

This function accepts a parse tree represented as a sequence and builds an internal representation if possible. If it can validate that the tree conforms to the Python grammar and all nodes are valid node types in the host version of Python, an AST object is created from the internal representation and returned to the caller. If there is a problem creating the internal representation, or if the tree cannot be validated, a `ParserError` exception is thrown. An AST object created this way should not be assumed to compile correctly; normal exceptions thrown by compilation may still be initiated when the AST object is passed to `compileast()`. This may indicate problems not related to syntax (such as a `MemoryError` exception), but may also be due to constructs such as the result of parsing `del f(0)`, which escapes the Python parser but is checked by the bytecode compiler.

Sequences representing terminal tokens may be represented as either two-element lists of the form `(1, 'name')` or as three-element lists of the form `(1, 'name', 56)`. If the third element is present, it is assumed to be a valid line number. The line number may be specified for any subset of the terminal symbols in the input tree.

tuple2ast (*sequence*)

This is the same function as `sequence2ast()`. This entry point is maintained for backward compatibility.

30.1.2 Converting AST Objects

AST objects, regardless of the input used to create them, may be converted to parse trees represented as list- or tuple-trees, or may be compiled into executable code objects. Parse trees may be extracted with or without line numbering information.

ast2list (*ast* [, *line_info*])

This function accepts an AST object from the caller in *ast* and returns a Python list representing the equivalent parse tree. The resulting list representation can be used for inspection or the creation of a new parse tree in list form. This function does not fail so long as memory is available to build the list representation. If the parse tree will only be used for inspection, `ast2tuple()` should be used instead to reduce memory consumption and fragmentation. When the list representation is required, this function is significantly faster than retrieving a tuple representation and converting that to nested lists.

If *line_info* is true, line number information will be included for all terminal tokens as a third element of the list representing the token. Note that the line number provided specifies the line on which the token *ends*. This information is omitted if the flag is false or omitted.

ast2tuple (*ast* [, *line_info*])

This function accepts an AST object from the caller in *ast* and returns a Python tuple representing the equivalent parse tree. Other than returning a tuple instead of a list, this function is identical to `ast2list()`.

If *line_info* is true, line number information will be included for all terminal tokens as a third element of the list representing the token. This information is omitted if the flag is false or omitted.

compileast (*ast* [, *filename* = '<ast>'])

The Python byte compiler can be invoked on an AST object to produce code objects which can be used as part of an `exec` statement or a call to the built-in `eval()` function. This function provides the interface to the compiler, passing the internal parse tree from *ast* to the parser, using the source file name specified by the *filename* parameter. The default value supplied for *filename* indicates that the source was an AST object.

Compiling an AST object may result in exceptions related to compilation; an example would be a `SyntaxError` caused by the parse tree for `del f(0)`: this statement is considered legal within the formal grammar for Python but is not a legal language construct. The `SyntaxError` raised for this condition is actually generated by the Python byte-compiler normally, which is why it can be raised at this point by the `parser` module. Most causes of compilation failure can be diagnosed programmatically by inspection of the parse tree.

30.1.3 Queries on AST Objects

Two functions are provided which allow an application to determine if an AST was created as an expression or a suite. Neither of these functions can be used to determine if an AST was created from source code via `expr()` or `suite()` or from a parse tree via `sequence2ast()`.

isexpr (*ast*)

When *ast* represents an 'eval' form, this function returns true, otherwise it returns false. This is useful, since code objects normally cannot be queried for this information using existing built-in functions. Note that the code objects created by `compileast()` cannot be queried like this either, and are identical to those created by the built-in `compile()` function.

issuite (*ast*)

This function mirrors `isexpr()` in that it reports whether an AST object represents an 'exec' form, commonly known as a "suite." It is not safe to assume that this function is equivalent to `'not isexpr(ast)'`, as additional syntactic fragments may be supported in the future.

30.1.4 Exceptions and Error Handling

The parser module defines a single exception, but may also pass other built-in exceptions from other portions of the Python runtime environment. See each function for information about the exceptions it can raise.

exception `ParserError`

Exception raised when a failure occurs within the parser module. This is generally produced for validation failures rather than the built in `SyntaxError` thrown during normal parsing. The exception argument is either a string describing the reason of the failure or a tuple containing a sequence causing the failure from a parse tree passed to `sequence2ast()` and an explanatory string. Calls to `sequence2ast()` need to be able to handle either type of exception, while calls to other functions in the module will only need to be aware of the simple string values.

Note that the functions `compileast()`, `expr()`, and `suite()` may throw exceptions which are normally thrown by the parsing and compilation process. These include the built in exceptions `MemoryError`, `OverflowError`, `SyntaxError`, and `SystemError`. In these cases, these exceptions carry all the meaning normally associated with them. Refer to the descriptions of each function for detailed information.

30.1.5 AST Objects

Ordered and equality comparisons are supported between AST objects. Pickling of AST objects (using the `pickle` module) is also supported.

ASTType

The type of the objects returned by `expr()`, `suite()` and `sequence2ast()`.

AST objects have the following methods:

compile (*[filename]*)

Same as `compileast(ast, filename)`.

isexpr ()

Same as `isexpr(ast)`.

issuite ()

Same as `issuite(ast)`.

tolist (*[line_info]*)

Same as `ast2list(ast, line_info)`.

totuple (*[line_info]*)

Same as `ast2tuple(ast, line_info)`.

30.1.6 Examples

The parser modules allows operations to be performed on the parse tree of Python source code before the bytecode is generated, and provides for inspection of the parse tree for information gathering purposes. Two examples are presented. The simple example demonstrates emulation of the `compile()` built-in function and the complex example shows the use of a parse tree for information discovery.

Emulation of `compile()`

While many useful operations may take place between parsing and bytecode generation, the simplest operation is to do nothing. For this purpose, using the `parser` module to produce an intermediate data structure is equivalent to the code

```
>>> code = compile('a + 5', 'file.py', 'eval')
>>> a = 5
>>> eval(code)
10
```

The equivalent operation using the `parser` module is somewhat longer, and allows the intermediate internal parse tree to be retained as an AST object:

```
>>> import parser
>>> ast = parser.expr('a + 5')
>>> code = ast.compile('file.py')
>>> a = 5
>>> eval(code)
10
```

An application which needs both AST and code objects can package this code into readily available functions:

```
import parser

def load_suite(source_string):
    ast = parser.suite(source_string)
    return ast, ast.compile()

def load_expression(source_string):
    ast = parser.expr(source_string)
    return ast, ast.compile()
```

Information Discovery

Some applications benefit from direct access to the parse tree. The remainder of this section demonstrates how the parse tree provides access to module documentation defined in docstrings without requiring that the code being examined be loaded into a running interpreter via `import`. This can be very useful for performing analyses of untrusted code.

Generally, the example will demonstrate how the parse tree may be traversed to distill interesting information. Two functions and a set of classes are developed which provide programmatic access to high level function and class definitions provided by a module. The classes extract information from the parse tree and provide access to the information at a useful semantic level, one function provides a simple low-level pattern matching capability, and the other function defines a high-level interface to the classes by handling file operations on behalf of the caller. All source files mentioned here which are not part of the Python installation are located in the ‘Demo/parser/’ directory of the distribution.

The dynamic nature of Python allows the programmer a great deal of flexibility, but most modules need only a limited measure of this when defining classes, functions, and methods. In this example, the only definitions that will be considered are those which are defined in the top level of their context, e.g., a function defined by a `def` statement at

column zero of a module, but not a function defined within a branch of an `if ... else` construct, though there are some good reasons for doing so in some situations. Nesting of definitions will be handled by the code developed in the example.

To construct the upper-level extraction methods, we need to know what the parse tree structure looks like and how much of it we actually need to be concerned about. Python uses a moderately deep parse tree so there are a large number of intermediate nodes. It is important to read and understand the formal grammar used by Python. This is specified in the file ‘Grammar/Grammar’ in the distribution. Consider the simplest case of interest when searching for docstrings: a module consisting of a docstring and nothing else. (See file ‘docstring.py’.)

```
"""Some documentation.
"""
```

Using the interpreter to take a look at the parse tree, we find a bewildering mass of numbers and parentheses, with the documentation buried deep in nested tuples.

```
>>> import parser
>>> import pprint
>>> ast = parser.suite(open('docstring.py').read())
>>> tup = ast.totuple()
>>> pprint.pprint(tup)
(257,
 (264,
  (265,
   (266,
    (267,
     (307,
      (287,
       (288,
        (289,
         (290,
          (292,
           (293,
            (294,
             (295,
              (296,
               (297,
                (298,
                 (299,
                  (300, (3, '"""Some documentation.\n"""')))))))))))))))
    (4, '')),
  (4, '')),
 (0, ''))
```

The numbers at the first element of each node in the tree are the node types; they map directly to terminal and non-terminal symbols in the grammar. Unfortunately, they are represented as integers in the internal representation, and the Python structures generated do not change that. However, the `symbol` and `token` modules provide symbolic names for the node types and dictionaries which map from the integers to the symbolic names for the node types.

In the output presented above, the outermost tuple contains four elements: the integer 257 and three additional tuples. Node type 257 has the symbolic name `file_input`. Each of these inner tuples contains an integer as the first element; these integers, 264, 4, and 0, represent the node types `stmt`, `NEWLINE`, and `ENDMARKER`, respectively. Note that these values may change depending on the version of Python you are using; consult ‘symbol.py’ and ‘token.py’ for details of the mapping. It should be fairly clear that the outermost node is related primarily to the input source rather than the contents of the file, and may be disregarded for the moment. The `stmt` node is much more interesting. In

particular, all docstrings are found in subtrees which are formed exactly as this node is formed, with the only difference being the string itself. The association between the docstring in a similar tree and the defined entity (class, function, or module) which it describes is given by the position of the docstring subtree within the tree defining the described structure.

By replacing the actual docstring with something to signify a variable component of the tree, we allow a simple pattern matching approach to check any given subtree for equivalence to the general pattern for docstrings. Since the example demonstrates information extraction, we can safely require that the tree be in tuple form rather than list form, allowing a simple variable representation to be `['variable_name']`. A simple recursive function can implement the pattern matching, returning a Boolean and a dictionary of variable name to value mappings. (See file `'example.py'`.)

```
from types import ListType, TupleType

def match(pattern, data, vars=None):
    if vars is None:
        vars = {}
    if type(pattern) is ListType:
        vars[pattern[0]] = data
        return 1, vars
    if type(pattern) is not TupleType:
        return (pattern == data), vars
    if len(data) != len(pattern):
        return 0, vars
    for pattern, data in map(None, pattern, data):
        same, vars = match(pattern, data, vars)
        if not same:
            break
    return same, vars
```

Using this simple representation for syntactic variables and the symbolic node types, the pattern for the candidate docstring subtrees becomes fairly readable. (See file `'example.py'`.)

```

import symbol
import token

DOCSTRING_STMT_PATTERN = (
    symbol.stmt,
    (symbol.simple_stmt,
     (symbol.small_stmt,
      (symbol.expr_stmt,
       (symbol.testlist,
        (symbol.test,
         (symbol.and_test,
          (symbol.not_test,
           (symbol.comparison,
            (symbol.expr,
             (symbol.xor_expr,
              (symbol.and_expr,
               (symbol.shift_expr,
                (symbol.arith_expr,
                 (symbol.term,
                  (symbol.factor,
                   (symbol.power,
                    (symbol.atom,
                     (token.STRING, ['docstring']))
                    ))))))))))))))),
     (token.NEWLINE, ''))
)

```

Using the `match()` function with this pattern, extracting the module docstring from the parse tree created previously is easy:

```

>>> found, vars = match(DOCSTRING_STMT_PATTERN, tup[1])
>>> found
1
>>> vars
{'docstring': '""Some documentation.\n""'}

```

Once specific data can be extracted from a location where it is expected, the question of where information can be expected needs to be answered. When dealing with docstrings, the answer is fairly simple: the docstring is the first `stmt` node in a code block (`file_input` or `suite` node types). A module consists of a single `file_input` node, and class and function definitions each contain exactly one `suite` node. Classes and functions are readily identified as subtrees of code block nodes which start with `(stmt, (compound_stmt, (classdef, ... or (stmt, (compound_stmt, (funcdef, ...`. Note that these subtrees cannot be matched by `match()` since it does not support multiple sibling nodes to match without regard to number. A more elaborate matching function could be used to overcome this limitation, but this is sufficient for the example.

Given the ability to determine whether a statement might be a docstring and extract the actual string from the statement, some work needs to be performed to walk the parse tree for an entire module and extract information about the names defined in each context of the module and associate any docstrings with the names. The code to perform this work is not complicated, but bears some explanation.

The public interface to the classes is straightforward and should probably be somewhat more flexible. Each “major” block of the module is described by an object providing several methods for inquiry and a constructor which accepts at least the subtree of the complete parse tree which it represents. The `ModuleInfo` constructor accepts an optional *name* parameter since it cannot otherwise determine the name of the module.

The public classes include `ClassInfo`, `FunctionInfo`, and `ModuleInfo`. All objects provide the methods

`get_name()`, `get_docstring()`, `get_class_names()`, and `get_class_info()`. The `ClassInfo` objects support `get_method_names()` and `get_method_info()` while the other classes provide `get_function_names()` and `get_function_info()`.

Within each of the forms of code block that the public classes represent, most of the required information is in the same form and is accessed in the same way, with classes having the distinction that functions defined at the top level are referred to as “methods.” Since the difference in nomenclature reflects a real semantic distinction from functions defined outside of a class, the implementation needs to maintain the distinction. Hence, most of the functionality of the public classes can be implemented in a common base class, `SuiteInfoBase`, with the accessors for function and method information provided elsewhere. Note that there is only one class which represents function and method information; this parallels the use of the `def` statement to define both types of elements.

Most of the accessor functions are declared in `SuiteInfoBase` and do not need to be overridden by subclasses. More importantly, the extraction of most information from a parse tree is handled through a method called by the `SuiteInfoBase` constructor. The example code for most of the classes is clear when read alongside the formal grammar, but the method which recursively creates new information objects requires further examination. Here is the relevant part of the `SuiteInfoBase` definition from ‘example.py’:

```
class SuiteInfoBase:
    _docstring = ''
    _name = ''

    def __init__(self, tree = None):
        self._class_info = {}
        self._function_info = {}
        if tree:
            self._extract_info(tree)

    def _extract_info(self, tree):
        # extract docstring
        if len(tree) == 2:
            found, vars = match(DOCSTRING_STMT_PATTERN[1], tree[1])
        else:
            found, vars = match(DOCSTRING_STMT_PATTERN, tree[3])
        if found:
            self._docstring = eval(vars['docstring'])
        # discover inner definitions
        for node in tree[1:]:
            found, vars = match(COMPOUND_STMT_PATTERN, node)
            if found:
                cstmt = vars['compound']
                if cstmt[0] == symbol.funcdef:
                    name = cstmt[2][1]
                    self._function_info[name] = FunctionInfo(cstmt)
                elif cstmt[0] == symbol.classdef:
                    name = cstmt[2][1]
                    self._class_info[name] = ClassInfo(cstmt)
```

After initializing some internal state, the constructor calls the `_extract_info()` method. This method performs the bulk of the information extraction which takes place in the entire example. The extraction has two distinct phases: the location of the docstring for the parse tree passed in, and the discovery of additional definitions within the code block represented by the parse tree.

The initial `if` test determines whether the nested suite is of the “short form” or the “long form.” The short form is used when the code block is on the same line as the definition of the code block, as in

```
def square(x): "Square an argument."; return x ** 2
```

while the long form uses an indented block and allows nested definitions:

```
def make_power(exp):
    "Make a function that raises an argument to the exponent 'exp'."
    def raiser(x, y=exp):
        return x ** y
    return raiser
```

When the short form is used, the code block may contain a docstring as the first, and possibly only, `small_stmt` element. The extraction of such a docstring is slightly different and requires only a portion of the complete pattern used in the more common case. As implemented, the docstring will only be found if there is only one `small_stmt` node in the `simple_stmt` node. Since most functions and methods which use the short form do not provide a docstring, this may be considered sufficient. The extraction of the docstring proceeds using the `match()` function as described above, and the value of the docstring is stored as an attribute of the `SuiteInfoBase` object.

After docstring extraction, a simple definition discovery algorithm operates on the `stmt` nodes of the `suite` node. The special case of the short form is not tested; since there are no `stmt` nodes in the short form, the algorithm will silently skip the single `simple_stmt` node and correctly not discover any nested definitions.

Each statement in the code block is categorized as a class definition, function or method definition, or something else. For the definition statements, the name of the element defined is extracted and a representation object appropriate to the definition is created with the defining subtree passed as an argument to the constructor. The representation objects are stored in instance variables and may be retrieved by name using the appropriate accessor methods.

The public classes provide any accessors required which are more specific than those provided by the `SuiteInfoBase` class, but the real extraction algorithm remains common to all forms of code blocks. A high-level function can be used to extract the complete set of information from a source file. (See file 'example.py'.)

```
def get_docs(fileName):
    import os
    import parser

    source = open(fileName).read()
    basename = os.path.basename(os.path.splitext(fileName)[0])
    ast = parser.suite(source)
    return ModuleInfo(ast.totuple(), basename)
```

This provides an easy-to-use interface to the documentation of a module. If information is required which is not extracted by the code of this example, the code may be extended at clearly defined points to provide additional capabilities.

30.2 `symbol` — Constants used with Python parse trees

This module provides constants which represent the numeric values of internal nodes of the parse tree. Unlike most Python constants, these use lower-case names. Refer to the file 'Grammar/Grammar' in the Python distribution for the definitions of the names in the context of the language grammar. The specific numeric values which the names map to may change between Python versions.

This module also provides one additional data object:

sym_name

Dictionary mapping the numeric values of the constants defined in this module back to name strings, allowing more human-readable representation of parse trees to be generated.

See Also:

[Module parser](#) (section 30.1):

The second example for the [parser](#) module shows how to use the `symbol` module.

30.3 `token` — Constants used with Python parse trees

This module provides constants which represent the numeric values of leaf nodes of the parse tree (terminal tokens). Refer to the file ‘Grammar/Grammar’ in the Python distribution for the definitions of the names in the context of the language grammar. The specific numeric values which the names map to may change between Python versions.

This module also provides one data object and some functions. The functions mirror definitions in the Python C header files.

tok_name

Dictionary mapping the numeric values of the constants defined in this module back to name strings, allowing more human-readable representation of parse trees to be generated.

ISTERMINAL (*x*)

Return true for terminal token values.

ISNONTERMINAL (*x*)

Return true for non-terminal token values.

ISEOF (*x*)

Return true if *x* is the marker indicating the end of input.

See Also:

[Module parser](#) (section 30.1):

The second example for the [parser](#) module shows how to use the `symbol` module.

30.4 `keyword` — Testing for Python keywords

This module allows a Python program to determine if a string is a keyword.

iskeyword (*s*)

Return true if *s* is a Python keyword.

kwlist

Sequence containing all the keywords defined for the interpreter. If any keywords are defined to only be active when particular `__future__` statements are in effect, these will be included as well.

30.5 `tokenize` — Tokenizer for Python source

The `tokenize` module provides a lexical scanner for Python source code, implemented in Python. The scanner in this module returns comments as tokens as well, making it useful for implementing “pretty-printers,” including colorizers for on-screen displays.

The primary entry point is a generator:

generate_tokens (*readline*)

The `generate_tokens()` generator requires one argument, *readline*, which must be a callable object which provides the same interface as the `readline()` method of built-in file objects (see section 3.9). Each call to the function should return one line of input as a string.

The generator produces 5-tuples with these members: the token type; the token string; a 2-tuple (*srow*, *scol*) of ints specifying the row and column where the token begins in the source; a 2-tuple (*erow*, *ecol*) of ints specifying the row and column where the token ends in the source; and the line on which the token was found. The line passed is the *logical* line; continuation lines are included. New in version 2.2.

An older entry point is retained for backward compatibility:

`tokenize` (*readline* [, *tokeneater*])

The `tokenize()` function accepts two parameters: one representing the input stream, and one providing an output mechanism for `tokenize()`.

The first parameter, *readline*, must be a callable object which provides the same interface as the `readline()` method of built-in file objects (see section 3.9). Each call to the function should return one line of input as a string. Alternately, *readline* may be a callable object that signals completion by raising `StopIteration`. Changed in version 2.5: Added `StopIteration` support.

The second parameter, *tokeneater*, must also be a callable object. It is called once for each token, with five arguments, corresponding to the tuples generated by `generate_tokens()`.

All constants from the `token` module are also exported from `tokenize`, as are two additional token type values that might be passed to the *tokeneater* function by `tokenize()`:

COMMENT

Token value used to indicate a comment.

NL

Token value used to indicate a non-terminating newline. The `NEWLINE` token indicates the end of a logical line of Python code; `NL` tokens are generated when a logical line of code is continued over multiple physical lines.

Another function is provided to reverse the tokenization process. This is useful for creating tools that tokenize a script, modify the token stream, and write back the modified script.

`untokenize` (*iterable*)

Converts tokens back into Python source code. The *iterable* must return sequences with at least two elements, the token type and the token string. Any additional sequence elements are ignored.

The reconstructed script is returned as a single string. The result is guaranteed to tokenize back to match the input so that the conversion is lossless and round-trips are assured. The guarantee applies only to the token type and token string as the spacing between tokens (column positions) may change. New in version 2.5.

Example of a script re-writer that transforms float literals into `Decimal` objects:


```

def decistmt(s):
    """Substitute Decimals for floats in a string of statements.

    >>> from decimal import Decimal
    >>> s = 'print +21.3e-5*-.1234/81.7'
    >>> decistmt(s)
    "print +Decimal ('21.3e-5')*-Decimal ('.1234')/Decimal ('81.7') "

    >>> exec(s)
    -3.21716034272e-007
    >>> exec(decistmt(s))
    -3.217160342717258261933904529E-7

    """
    result = []
    g = generate_tokens(StringIO(s).readline)    # tokenize the string
    for toknum, tokval, _, _, _ in g:
        if toknum == NUMBER and '.' in tokval:    # replace NUMBER tokens
            result.extend([
                (NAME, 'Decimal'),
                (OP, '('),
                (STRING, repr(tokval)),
                (OP, ')')
            ])
        else:
            result.append((toknum, tokval))
    return untokenize(result)

```

30.6 tabnanny — Detection of ambiguous indentation

For the time being this module is intended to be called as a script. However it is possible to import it into an IDE and use the function `check()` described below.

Warning: The API provided by this module is likely to change in future releases; such changes may not be backward compatible.

check (*file_or_dir*)

If *file_or_dir* is a directory and not a symbolic link, then recursively descend the directory tree named by *file_or_dir*, checking all `.py` files along the way. If *file_or_dir* is an ordinary Python source file, it is checked for whitespace related problems. The diagnostic messages are written to standard output using the print statement.

verbose

Flag indicating whether to print verbose messages. This is incremented by the `-v` option if called as a script.

filename_only

Flag indicating whether to print only the filenames of files containing whitespace related problems. This is set to true by the `-q` option if called as a script.

exception NannyNag

Raised by `token eater()` if detecting an ambiguous indent. Captured and handled in `check()`.

token eater (*type, token, start, end, line*)

This function is used by `check()` as a callback parameter to the function `tokenize.tokenize()`.

See Also:

Module `tokenize` (section 30.5):

Lexical scanner for Python source code.

30.7 `pyclbr` — Python class browser support

The `pyclbr` can be used to determine some limited information about the classes, methods and top-level functions defined in a module. The information provided is sufficient to implement a traditional three-pane class browser. The information is extracted from the source code rather than by importing the module, so this module is safe to use with untrusted source code. This restriction makes it impossible to use this module with modules not implemented in Python, including many standard and optional extension modules.

`readmodule` (*module* [, *path*])

Read a module and return a dictionary mapping class names to class descriptor objects. The parameter *module* should be the name of a module as a string; it may be the name of a module within a package. The *path* parameter should be a sequence, and is used to augment the value of `sys.path`, which is used to locate module source code.

`readmodule_ex` (*module* [, *path*])

Like `readmodule()`, but the returned dictionary, in addition to mapping class names to class descriptor objects, also maps top-level function names to function descriptor objects. Moreover, if the module being read is a package, the key `'__path__'` in the returned dictionary has as its value a list which contains the package search path.

30.7.1 Class Descriptor Objects

The class descriptor objects used as values in the dictionary returned by `readmodule()` and `readmodule_ex()` provide the following data members:

`module`

The name of the module defining the class described by the class descriptor.

`name`

The name of the class.

`super`

A list of class descriptors which describe the immediate base classes of the class being described. Classes which are named as superclasses but which are not discoverable by `readmodule()` are listed as a string with the class name instead of class descriptors.

`methods`

A dictionary mapping method names to line numbers.

`file`

Name of the file containing the `class` statement defining the class.

`lineno`

The line number of the `class` statement within the file named by *file*.

30.7.2 Function Descriptor Objects

The function descriptor objects used as values in the dictionary returned by `readmodule_ex()` provide the following data members:

`module`

The name of the module defining the function described by the function descriptor.

name

The name of the function.

file

Name of the file containing the `def` statement defining the function.

lineno

The line number of the `def` statement within the file named by `file`.

30.8 `py_compile` — Compile Python source files

The `py_compile` module provides a function to generate a byte-code file from a source file, and another function used when the module source file is invoked as a script.

Though not often needed, this function can be useful when installing modules for shared use, especially if some of the users may not have permission to write the byte-code cache files in the directory containing the source code.

exception `PyCompileError`

Exception raised when an error occurs while attempting to compile the file.

`compile` (`file` [, `cfile` [, `dfile` [, `doraise`]]])

Compile a source file to byte-code and write out the byte-code cache file. The source code is loaded from the file name `file`. The byte-code is written to `cfile`, which defaults to `file + 'c'` ('o' if optimization is enabled in the current interpreter). If `dfile` is specified, it is used as the name of the source file in error messages instead of `file`. If `doraise` is true, a `PyCompileError` is raised when an error is encountered while compiling `file`. If `doraise` is false (the default), an error string is written to `sys.stderr`, but no exception is raised.

`main` ([`args`])

Compile several source files. The files named in `args` (or on the command line, if `args` is not specified) are compiled and the resulting bytecode is cached in the normal manner. This function does not search a directory structure to locate source files; it only compiles files named explicitly.

When this module is run as a script, the `main()` is used to compile all the files named on the command line.

See Also:

[Module `compileall`](#) (section 30.9):

Utilities to compile all Python source files in a directory tree.

30.9 `compileall` — Byte-compile Python libraries

This module provides some utility functions to support installing Python libraries. These functions compile Python source files in a directory tree, allowing users without permission to write to the libraries to take advantage of cached byte-code files.

The source file for this module may also be used as a script to compile Python sources in directories named on the command line or in `sys.path`.

`compile_dir` (`dir` [, `maxlevels` [, `ddir` [, `force` [, `rx` [, `quiet`]]]]])

Recursively descend the directory tree named by `dir`, compiling all '.py' files along the way. The `maxlevels` parameter is used to limit the depth of the recursion; it defaults to 10. If `ddir` is given, it is used as the base path from which the filenames used in error messages will be generated. If `force` is true, modules are re-compiled even if the timestamps are up to date.

If `rx` is given, it specifies a regular expression of file names to exclude from the search; that expression is searched for in the full path.

If `quiet` is true, nothing is printed to the standard output in normal operation.

compile_path([*skip_curdir*[, *maxlevels*[, *force*]]])

Byte-compile all the ‘.py’ files found along `sys.path`. If *skip_curdir* is true (the default), the current directory is not included in the search. The *maxlevels* and *force* parameters default to 0 and are passed to the `compile_dir()` function.

To force a recompile of all the ‘.py’ files in the ‘Lib/’ subdirectory and all its subdirectories:

```
import compileall

compileall.compile_dir('Lib/', force=True)

# Perform same compilation, excluding files in .svn directories.
import re
compileall.compile_dir('Lib/', rx=re.compile('/[.]svn'), force=True)
```

See Also:

[Module `py_compile`](#) (section 30.8):

Byte-compile a single source file.

30.10 `dis` — Disassembler for Python byte code

The `dis` module supports the analysis of Python byte code by disassembling it. Since there is no Python assembler, this module defines the Python assembly language. The Python byte code which this module takes as an input is defined in the file ‘Include/opcode.h’ and used by the compiler and the interpreter.

Example: Given the function `myfunc`:

```
def myfunc(alist):
    return len(alist)
```

the following command can be used to get the disassembly of `myfunc()`:

```
>>> dis.dis(myfunc)
2          0 LOAD_GLOBAL              0 (len)
          3 LOAD_FAST                0 (alist)
          6 CALL_FUNCTION              1
          9 RETURN_VALUE
```

(The “2” is a line number).

The `dis` module defines the following functions and constants:

dis([*bytesource*])

Disassemble the *bytesource* object. *bytesource* can denote either a module, a class, a method, a function, or a code object. For a module, it disassembles all functions. For a class, it disassembles all methods. For a single code sequence, it prints one line per byte code instruction. If no object is provided, it disassembles the last traceback.

distb([*tb*])

Disassembles the top-of-stack function of a traceback, using the last traceback if none was passed. The instruction causing the exception is indicated.

disassemble(*code*[, *lasti*])

Disassembles a code object, indicating the last instruction if *lasti* was provided. The output is divided in the following columns:

- 1.the line number, for the first instruction of each line
- 2.the current instruction, indicated as ‘-->’,
- 3.a labelled instruction, indicated with ‘>>’,
- 4.the address of the instruction,
- 5.the operation code name,
- 6.operation parameters, and
- 7.interpretation of the parameters in parentheses.

The parameter interpretation recognizes local and global variable names, constant values, branch targets, and compare operators.

disco(*code*[, *lasti*])

A synonym for `disassemble`. It is more convenient to type, and kept for compatibility with earlier Python releases.

opname

Sequence of operation names, indexable using the byte code.

opmap

Dictionary mapping byte codes to operation names.

cmp_op

Sequence of all compare operation names.

hasconst

Sequence of byte codes that have a constant parameter.

hasfree

Sequence of byte codes that access a free variable.

hasname

Sequence of byte codes that access an attribute by name.

hasjrel

Sequence of byte codes that have a relative jump target.

hasjabs

Sequence of byte codes that have an absolute jump target.

haslocal

Sequence of byte codes that access a local variable.

hascompare

Sequence of byte codes of Boolean operations.

30.10.1 Python Byte Code Instructions

The Python compiler currently generates the following byte code instructions.

STOP_CODE

Indicates end-of-code to the compiler, not used by the interpreter.

NOP

Do nothing code. Used as a placeholder by the bytecode optimizer.

POP_TOP

Removes the top-of-stack (TOS) item.

ROT_TWO

Swaps the two top-most stack items.

ROT_THREE

Lifts second and third stack item one position up, moves top down to position three.

ROT_FOUR

Lifts second, third and forth stack item one position up, moves top down to position four.

DUP_TOP

Duplicates the reference on top of the stack.

Unary Operations take the top of the stack, apply the operation, and push the result back on the stack.

UNARY_POSITIVE

Implements `TOS = +TOS`.

UNARY_NEGATIVE

Implements `TOS = -TOS`.

UNARY_NOT

Implements `TOS = not TOS`.

UNARY_CONVERT

Implements `TOS = `TOS``.

UNARY_INVERT

Implements `TOS = ~TOS`.

GET_ITER

Implements `TOS = iter(TOS)`.

Binary operations remove the top of the stack (TOS) and the second top-most stack item (TOS1) from the stack. They perform the operation, and put the result back on the stack.

BINARY_POWER

Implements `TOS = TOS1 ** TOS`.

BINARY_MULTIPLY

Implements `TOS = TOS1 * TOS`.

BINARY_DIVIDE

Implements `TOS = TOS1 / TOS` when from `__future__` import `division` is not in effect.

BINARY_FLOOR_DIVIDE

Implements `TOS = TOS1 // TOS`.

BINARY_TRUE_DIVIDE

Implements `TOS = TOS1 / TOS` when from `__future__` import `division` is in effect.

BINARY_MODULO

Implements `TOS = TOS1 % TOS`.

BINARY_ADD

Implements `TOS = TOS1 + TOS`.

BINARY_SUBTRACT

Implements `TOS = TOS1 - TOS`.

BINARY_SUBSCR

Implements `TOS = TOS1[TOS]`.

BINARY_LSHIFT

Implements `TOS = TOS1 << TOS`.

BINARY_RSHIFT

Implements `TOS = TOS1 >> TOS`.

BINARY_AND

Implements `TOS = TOS1 & TOS`.

BINARY_XOR

Implements `TOS = TOS1 ^ TOS`.

BINARY_OR

Implements `TOS = TOS1 | TOS`.

In-place operations are like binary operations, in that they remove TOS and TOS1, and push the result back on the stack, but the operation is done in-place when TOS1 supports it, and the resulting TOS may be (but does not have to be) the original TOS1.

INPLACE_POWER

Implements in-place `TOS = TOS1 ** TOS`.

INPLACE_MULTIPLY

Implements in-place `TOS = TOS1 * TOS`.

INPLACE_DIVIDE

Implements in-place `TOS = TOS1 / TOS` when from `__future__` import `division` is not in effect.

INPLACE_FLOOR_DIVIDE

Implements in-place `TOS = TOS1 // TOS`.

INPLACE_TRUE_DIVIDE

Implements in-place `TOS = TOS1 / TOS` when from `__future__` import `division` is in effect.

INPLACE_MODULO

Implements in-place `TOS = TOS1 % TOS`.

INPLACE_ADD

Implements in-place `TOS = TOS1 + TOS`.

INPLACE_SUBTRACT

Implements in-place `TOS = TOS1 - TOS`.

INPLACE_LSHIFT

Implements in-place `TOS = TOS1 << TOS`.

INPLACE_RSHIFT

Implements in-place `TOS = TOS1 >> TOS`.

INPLACE_AND

Implements in-place `TOS = TOS1 & TOS`.

INPLACE_XOR

Implements in-place `TOS = TOS1 ^ TOS`.

INPLACE_OR

Implements in-place `TOS = TOS1 | TOS`.

The slice opcodes take up to three parameters.

SLICE+0

Implements `TOS = TOS[:]`.

SLICE+1

Implements `TOS = TOS1[TOS:]`.

SLICE+2

Implements `TOS = TOS1[:TOS]`.

SLICE+3

Implements `TOS = TOS2[TOS1:TOS]`.

Slice assignment needs even an additional parameter. As any statement, they put nothing on the stack.

STORE_SLICE+0

Implements `TOS[:] = TOS1`.

STORE_SLICE+1

Implements `TOS1[TOS:] = TOS2`.

STORE_SLICE+2

Implements `TOS1[:TOS] = TOS2`.

STORE_SLICE+3

Implements `TOS2[TOS1:TOS] = TOS3`.

DELETE_SLICE+0

Implements `del TOS[:]`.

DELETE_SLICE+1

Implements `del TOS1[TOS:]`.

DELETE_SLICE+2

Implements `del TOS1[:TOS]`.

DELETE_SLICE+3

Implements `del TOS2[TOS1:TOS]`.

STORE_SUBSCR

Implements `TOS1[TOS] = TOS2`.

DELETE_SUBSCR

Implements `del TOS1[TOS]`.

Miscellaneous opcodes.

PRINT_EXPR

Implements the expression statement for the interactive mode. TOS is removed from the stack and printed. In non-interactive mode, an expression statement is terminated with `POP_STACK`.

PRINT_ITEM

Prints TOS to the file-like object bound to `sys.stdout`. There is one such instruction for each item in the `print` statement.

PRINT_ITEM_TO

Like `PRINT_ITEM`, but prints the item second from TOS to the file-like object at TOS. This is used by the extended `print` statement.

PRINT_NEWLINE

Prints a new line on `sys.stdout`. This is generated as the last operation of a `print` statement, unless the statement ends with a comma.

PRINT_NEWLINE_TO

Like `PRINT_NEWLINE`, but prints the new line on the file-like object on the TOS. This is used by the extended `print` statement.

BREAK_LOOP

Terminates a loop due to a `break` statement.

CONTINUE_LOOP *target*
 Continues a loop due to a `continue` statement. *target* is the address to jump to (which should be a `FOR_ITER` instruction).

LIST_APPEND
 Calls `list.append(TOS1, TOS)`. Used to implement list comprehensions.

LOAD_LOCALS
 Pushes a reference to the locals of the current scope on the stack. This is used in the code for a class definition: After the class body is evaluated, the locals are passed to the class definition.

RETURN_VALUE
 Returns with TOS to the caller of the function.

YIELD_VALUE
 Pops TOS and yields it from a generator.

IMPORT_STAR
 Loads all symbols not starting with `'_'` directly from the module TOS to the local namespace. The module is popped after loading all names. This opcode implements `from module import *`.

EXEC_STMT
 Implements `exec TOS2, TOS1, TOS`. The compiler fills missing optional parameters with `None`.

POP_BLOCK
 Removes one block from the block stack. Per frame, there is a stack of blocks, denoting nested loops, try statements, and such.

END_FINALLY
 Terminates a `finally` clause. The interpreter recalls whether the exception has to be re-raised, or whether the function returns, and continues with the outer-next block.

BUILD_CLASS
 Creates a new class object. TOS is the methods dictionary, TOS1 the tuple of the names of the base classes, and TOS2 the class name.

All of the following opcodes expect arguments. An argument is two bytes, with the more significant byte last.

STORE_NAME *namei*
 Implements `name = TOS`. *namei* is the index of *name* in the attribute `co_names` of the code object. The compiler tries to use `STORE_LOCAL` or `STORE_GLOBAL` if possible.

DELETE_NAME *namei*
 Implements `del name`, where *namei* is the index into `co_names` attribute of the code object.

UNPACK_SEQUENCE *count*
 Unpacks TOS into *count* individual values, which are put onto the stack right-to-left.

DUP_TOPX *count*
 Duplicate *count* items, keeping them in the same order. Due to implementation limits, *count* should be between 1 and 5 inclusive.

STORE_ATTR *namei*
 Implements `TOS.name = TOS1`, where *namei* is the index of *name* in `co_names`.

DELETE_ATTR *namei*
 Implements `del TOS.name`, using *namei* as index into `co_names`.

STORE_GLOBAL *namei*
 Works as `STORE_NAME`, but stores the name as a global.

DELETE_GLOBAL *namei*
 Works as `DELETE_NAME`, but deletes a global name.

LOAD_CONST *consti*
Pushes 'co_consts [*consti*]' onto the stack.

LOAD_NAME *namei*
Pushes the value associated with 'co_names [*namei*]' onto the stack.

BUILD_TUPLE *count*
Creates a tuple consuming *count* items from the stack, and pushes the resulting tuple onto the stack.

BUILD_LIST *count*
Works as BUILD_TUPLE, but creates a list.

BUILD_MAP *zero*
Pushes a new empty dictionary object onto the stack. The argument is ignored and set to zero by the compiler.

LOAD_ATTR *namei*
Replaces TOS with `getattr(TOS, co_names [namei])`.

COMPARE_OP *opname*
Performs a Boolean operation. The operation name can be found in `cmp_op [opname]`.

IMPORT_NAME *namei*
Imports the module `co_names [namei]`. The module object is pushed onto the stack. The current namespace is not affected: for a proper import statement, a subsequent STORE_FAST instruction modifies the namespace.

IMPORT_FROM *namei*
Loads the attribute `co_names [namei]` from the module found in TOS. The resulting object is pushed onto the stack, to be subsequently stored by a STORE_FAST instruction.

JUMP_FORWARD *delta*
Increments byte code counter by *delta*.

JUMP_IF_TRUE *delta*
If TOS is true, increment the byte code counter by *delta*. TOS is left on the stack.

JUMP_IF_FALSE *delta*
If TOS is false, increment the byte code counter by *delta*. TOS is not changed.

JUMP_ABSOLUTE *target*
Set byte code counter to *target*.

FOR_ITER *delta*
TOS is an iterator. Call its `next()` method. If this yields a new value, push it on the stack (leaving the iterator below it). If the iterator indicates it is exhausted TOS is popped, and the byte code counter is incremented by *delta*.

LOAD_GLOBAL *namei*
Loads the global named `co_names [namei]` onto the stack.

SETUP_LOOP *delta*
Pushes a block for a loop onto the block stack. The block spans from the current instruction with a size of *delta* bytes.

SETUP_EXCEPT *delta*
Pushes a try block from a try-except clause onto the block stack. *delta* points to the first except block.

SETUP_FINALLY *delta*
Pushes a try block from a try-except clause onto the block stack. *delta* points to the finally block.

LOAD_FAST *var_num*
Pushes a reference to the local `co_varnames [var_num]` onto the stack.

STORE_FAST *var_num*
Stores TOS into the local `co_varnames [var_num]`.

DELETE_FAST *var_num*
 Deletes local `co_varnames[var_num]`.

LOAD_CLOSURE *i*
 Pushes a reference to the cell contained in slot *i* of the cell and free variable storage. The name of the variable is `co_cellvars[i]` if *i* is less than the length of `co_cellvars`. Otherwise it is `co_freevars[i - len(co_cellvars)]`.

LOAD_DEREF *i*
 Loads the cell contained in slot *i* of the cell and free variable storage. Pushes a reference to the object the cell contains on the stack.

STORE_DEREF *i*
 Stores TOS into the cell contained in slot *i* of the cell and free variable storage.

SET_LINENO *lineno*
 This opcode is obsolete.

RAISE_VARARGS *argc*
 Raises an exception. *argc* indicates the number of parameters to the raise statement, ranging from 0 to 3. The handler will find the traceback as TOS2, the parameter as TOS1, and the exception as TOS.

CALL_FUNCTION *argc*
 Calls a function. The low byte of *argc* indicates the number of positional parameters, the high byte the number of keyword parameters. On the stack, the opcode finds the keyword parameters first. For each keyword argument, the value is on top of the key. Below the keyword parameters, the positional parameters are on the stack, with the right-most parameter on top. Below the parameters, the function object to call is on the stack.

MAKE_FUNCTION *argc*
 Pushes a new function object on the stack. TOS is the code associated with the function. The function object is defined to have *argc* default parameters, which are found below TOS.

MAKE_CLOSURE *argc*
 Creates a new function object, sets its `func_closure` slot, and pushes it on the stack. TOS is the code associated with the function. If the code object has *N* free variables, the next *N* items on the stack are the cells for these variables. The function also has *argc* default parameters, where are found before the cells.

BUILD_SLICE *argc*
 Pushes a slice object on the stack. *argc* must be 2 or 3. If it is 2, `slice(TOS1, TOS)` is pushed; if it is 3, `slice(TOS2, TOS1, TOS)` is pushed. See the `slice()` built-in function for more information.

EXTENDED_ARG *ext*
 Prefixes any opcode which has an argument too big to fit into the default two bytes. *ext* holds two additional bytes which, taken together with the subsequent opcode's argument, comprise a four-byte argument, *ext* being the two most-significant bytes.

CALL_FUNCTION_VAR *argc*
 Calls a function. *argc* is interpreted as in `CALL_FUNCTION`. The top element on the stack contains the variable argument list, followed by keyword and positional arguments.

CALL_FUNCTION_KW *argc*
 Calls a function. *argc* is interpreted as in `CALL_FUNCTION`. The top element on the stack contains the keyword arguments dictionary, followed by explicit keyword and positional arguments.

CALL_FUNCTION_VAR_KW *argc*
 Calls a function. *argc* is interpreted as in `CALL_FUNCTION`. The top element on the stack contains the keyword arguments dictionary, followed by the variable-arguments tuple, followed by explicit keyword and positional arguments.

HAVE_ARGUMENT
 This is not really an opcode. It identifies the dividing line between opcodes which don't take arguments <

HAVE_ARGUMENT and those which do >= HAVE_ARGUMENT.

30.11 `pickletools` — Tools for pickle developers.

New in version 2.3.

This module contains various constants relating to the intimate details of the `pickle` module, some lengthy comments about the implementation, and a few useful functions for analyzing pickled data. The contents of this module are useful for Python core developers who are working on the `pickle` and `cPickle` implementations; ordinary users of the `pickle` module probably won't find the `pickletools` module relevant.

dis (*pickle* [, *out*=None, *memo*=None, *indentlevel*=4])

Outputs a symbolic disassembly of the pickle to the file-like object *out*, defaulting to `sys.stdout`. *pickle* can be a string or a file-like object. *memo* can be a Python dictionary that will be used as the pickle's memo; it can be used to perform disassemblies across multiple pickles created by the same pickler. Successive levels, indicated by MARK opcodes in the stream, are indented by *indentlevel* spaces.

genops (*pickle*)

Provides an iterator over all of the opcodes in a pickle, returning a sequence of (*opcode*, *arg*, *pos*) triples. *opcode* is an instance of an `OpcodeInfo` class; *arg* is the decoded value, as a Python object, of the opcode's argument; *pos* is the position at which this opcode is located. *pickle* can be a string or a file-like object.

30.12 `distutils` — Building and installing Python modules

The `distutils` package provides support for building and installing additional modules into a Python installation. The new modules may be either 100%-pure Python, or may be extension modules written in C, or may be collections of Python packages which include modules coded in both Python and C.

This package is discussed in two separate documents which are included in the Python documentation package. To learn about distributing new modules using the `distutils` facilities, read [Distributing Python Modules](#); this includes documentation needed to extend `distutils`. To learn about installing Python modules, whether or not the author made use of the `distutils` package, read [Installing Python Modules](#).

See Also:

Distributing Python Modules

([../dist/dist.html](#))

The manual for developers and packagers of Python modules. This describes how to prepare `distutils`-based packages so that they may be easily installed into an existing Python installation.

Installing Python Modules

([../inst/inst.html](#))

An “administrators” manual which includes information on installing modules into an existing Python installation. You do not need to be a Python programmer to read this manual.

Python compiler package

The Python compiler package is a tool for analyzing Python source code and generating Python bytecode. The compiler contains libraries to generate an abstract syntax tree from Python source code and to generate Python bytecode from the tree.

The `compiler` package is a Python source to bytecode translator written in Python. It uses the built-in parser and standard `parser` module to generate a concrete syntax tree. This tree is used to generate an abstract syntax tree (AST) and then Python bytecode.

The full functionality of the package duplicates the builtin compiler provided with the Python interpreter. It is intended to match its behavior almost exactly. Why implement another compiler that does the same thing? The package is useful for a variety of purposes. It can be modified more easily than the builtin compiler. The AST it generates is useful for analyzing Python source code.

This chapter explains how the various components of the `compiler` package work. It blends reference material with a tutorial.

The following modules are part of the `compiler` package:

31.1 The basic interface

The top-level of the package defines four functions. If you import `compiler`, you will get these functions and a collection of modules contained in the package.

parse (*buf*)

Returns an abstract syntax tree for the Python source code in *buf*. The function raises `SyntaxError` if there is an error in the source code. The return value is a `compiler.ast.Module` instance that contains the tree.

parseFile (*path*)

Return an abstract syntax tree for the Python source code in the file specified by *path*. It is equivalent to `parse(open(path).read())`.

walk (*ast*, *visitor* [, *verbose*])

Do a pre-order walk over the abstract syntax tree *ast*. Call the appropriate method on the *visitor* instance for each node encountered.

compile (*source*, *filename*, *mode*, *flags=None*, *dont_inherit=None*)

Compile the string *source*, a Python module, statement or expression, into a code object that can be executed by the `exec` statement or `eval()`. This function is a replacement for the built-in `compile()` function.

The *filename* will be used for run-time error messages.

The *mode* must be 'exec' to compile a module, 'single' to compile a single (interactive) statement, or 'eval' to compile an expression.

The *flags* and *dont_inherit* arguments affect future-related statements, but are not supported yet.

compileFile (*source*)

Compiles the file *source* and generates a .pyc file.

The compiler package contains the following modules: `ast`, `consts`, `future`, `misc`, `pyassem`, `pycodegen`, `symbols`, `transformer`, and `visitor`.

31.2 Limitations

There are some problems with the error checking of the compiler package. The interpreter detects syntax errors in two distinct phases. One set of errors is detected by the interpreter's parser, the other set by the compiler. The compiler package relies on the interpreter's parser, so it gets the first phases of error checking for free. It implements the second phase itself, and that implementation is incomplete. For example, the compiler package does not raise an error if a name appears more than once in an argument list: `def f(x, x): ...`

A future version of the compiler should fix these problems.

31.3 Python Abstract Syntax

The `compiler.ast` module defines an abstract syntax for Python. In the abstract syntax tree, each node represents a syntactic construct. The root of the tree is `Module` object.

The abstract syntax offers a higher level interface to parsed Python source code. The `parser` module and the compiler written in C for the Python interpreter use a concrete syntax tree. The concrete syntax is tied closely to the grammar description used for the Python parser. Instead of a single node for a construct, there are often several levels of nested nodes that are introduced by Python's precedence rules.

The abstract syntax tree is created by the `compiler.transformer` module. The transformer relies on the builtin Python parser to generate a concrete syntax tree. It generates an abstract syntax tree from the concrete tree.

The `transformer` module was created by Greg Stein and Bill Tutt for an experimental Python-to-C compiler. The current version contains a number of modifications and improvements, but the basic form of the abstract syntax and of the transformer are due to Stein and Tutt.

31.3.1 AST Nodes

The `compiler.ast` module is generated from a text file that describes each node type and its elements. Each node type is represented as a class that inherits from the abstract base class `compiler.ast.Node` and defines a set of named attributes for child nodes.

class Node ()

The `Node` instances are created automatically by the parser generator. The recommended interface for specific `Node` instances is to use the public attributes to access child nodes. A public attribute may be bound to a single node or to a sequence of nodes, depending on the `Node` type. For example, the `bases` attribute of the `Class` node, is bound to a list of base class nodes, and the `doc` attribute is bound to a single node.

Each `Node` instance has a `lineno` attribute which may be `None`. XXX Not sure what the rules are for which nodes will have a useful `lineno`.

All `Node` objects offer the following methods:

getChildren ()

Returns a flattened list of the child nodes and objects in the order they occur. Specifically, the order of the nodes

is the order in which they appear in the Python grammar. Not all of the children are `Node` instances. The names of functions and classes, for example, are plain strings.

getChildNodes()

Returns a flattened list of the child nodes in the order they occur. This method is like `getChildren()`, except that it only returns those children that are `Node` instances.

Two examples illustrate the general structure of `Node` classes. The `while` statement is defined by the following grammar production:

```
while_stmt:      "while" expression ":" suite
               ["else" ":" suite]
```

The `While` node has three attributes: `test`, `body`, and `else_`. (If the natural name for an attribute is also a Python reserved word, it can't be used as an attribute name. An underscore is appended to the word to make it a legal identifier, hence `else_` instead of `else`.)

The `if` statement is more complicated because it can include several tests.

```
if_stmt: 'if' test ':' suite ('elif' test ':' suite)* ['else' ':' suite]
```

The `If` node only defines two attributes: `tests` and `else_`. The `tests` attribute is a sequence of test expression, consequent body pairs. There is one pair for each `if/elif` clause. The first element of the pair is the test expression. The second elements is a `Stmt` node that contains the code to execute if the test is true.

The `getChildren()` method of `If` returns a flat list of child nodes. If there are three `if/elif` clauses and no `else` clause, then `getChildren()` will return a list of six elements: the first test expression, the first `Stmt`, the second test expression, etc.

The following table lists each of the `Node` subclasses defined in `compiler.ast` and each of the public attributes available on their instances. The values of most of the attributes are themselves `Node` instances or sequences of instances. When the value is something other than an instance, the type is noted in the comment. The attributes are listed in the order in which they are returned by `getChildren()` and `getChildNodes()`.

Node type	Attribute	Value
Add	left	left operand
	right	right operand
And	nodes	list of operands
AssAttr		<i>attribute as target of assignment</i>
	expr	expression on the left-hand side of the dot
	attrname	the attribute name, a string
	flags	XXX
AssList	nodes	list of list elements being assigned to
AssName	name	name being assigned to
	flags	XXX
AssTuple	nodes	list of tuple elements being assigned to
Assert	test	the expression to be tested
	fail	the value of the <code>AssertionError</code>
Assign	nodes	a list of assignment targets, one per equal sign
	expr	the value being assigned
AugAssign	node	
	op	
	expr	

Node type	Attribute	Value
Backquote	expr	
Bitand	nodes	
Bitor	nodes	
Bitxor	nodes	
Break		
CallFunc	node	expression for the callee
	args	a list of arguments
	star_args	the extended *-arg value
	dstar_args	the extended **-arg value
Class	name	the name of the class, a string
	bases	a list of base classes
	doc	doc string, a string or None
	code	the body of the class statement
Compare	expr	
	ops	
Const	value	
Continue		
Decorators	nodes	List of function decorator expressions
Dict	items	
Discard	expr	
Div	left	
	right	
Ellipsis		
Expression	node	
Exec	expr	
	locals	
	globals	
FloorDiv	left	
	right	
For	assign	
	list	
	body	
	else_	
From	modname	
	names	
Function	decorators	Decorators or None
	name	name used in def, a string
	argnames	list of argument names, as strings
	defaults	list of default values
	flags	xxx
	doc	doc string, a string or None
	code	the body of the function
GenExpr	code	
GenExprFor	assign	
	iter	
	ifs	
GenExprIf	test	
GenExprInner	expr	
	quals	
Getattr	expr	
	attrname	
Global	names	

Node type	Attribute	Value
If	tests else_	
Import	names	
Invert	expr	
Keyword	name expr	
Lambda	argnames defaults flags code	
LeftShift	left right	
List	nodes	
ListComp	expr quals	
ListCompFor	assign list ifs	
ListCompIf	test	
Mod	left right	
Module	doc node	doc string, a string or None body of the module, a Stmt
Mul	left right	
Name	name	
Not	expr	
Or	nodes	
Pass		
Power	left right	
Print	nodes dest	
Printnl	nodes dest	
Raise	expr1 expr2 expr3	
Return	value	
RightShift	left right	
Slice	expr flags lower upper	
Sliceobj	nodes	list of statements
Stmt	nodes	
Sub	left right	
Subscript	expr flags subs	

Node type	Attribute	Value
TryExcept	body handlers else_	
TryFinally	body final	
Tuple	nodes	
UnaryAdd	expr	
UnarySub	expr	
While	test body else_	
With	expr vars body	
Yield	value	

31.3.2 Assignment nodes

There is a collection of nodes used to represent assignments. Each assignment statement in the source code becomes a single `Assign` node in the AST. The `nodes` attribute is a list that contains a node for each assignment target. This is necessary because assignment can be chained, e.g. `a = b = 2`. Each Node in the list will be one of the following classes: `AssAttr`, `AssList`, `AssName`, or `AssTuple`.

Each target assignment node will describe the kind of object being assigned to: `AssName` for a simple name, e.g. `a = 1`. `AssAttr` for an attribute assigned, e.g. `a.x = 1`. `AssList` and `AssTuple` for list and tuple expansion respectively, e.g. `a, b, c = a_tuple`.

The target assignment nodes also have a `flags` attribute that indicates whether the node is being used for assignment or in a delete statement. The `AssName` is also used to represent a delete statement, e.g. `del x`.

When an expression contains several attribute references, an assignment or delete statement will contain only one `AssAttr` node – for the final attribute reference. The other attribute references will be represented as `Getattr` nodes in the `expr` attribute of the `AssAttr` instance.

31.3.3 Examples

This section shows several simple examples of ASTs for Python source code. The examples demonstrate how to use the `parse()` function, what the repr of an AST looks like, and how to access attributes of an AST node.

The first module defines a single function. Assume it is stored in `'/tmp/doublelib.py'`.

```
"""This is an example module.

This is the docstring.
"""

def double(x):
    "Return twice the argument"
    return x * 2
```

In the interactive interpreter session below, I have reformatted the long AST reprs for readability. The AST reprs use unqualified class names. If you want to create an instance from a repr, you must import the class names from the `compiler.ast` module.

```
>>> import compiler
>>> mod = compiler.parseFile("/tmp/doublelib.py")
>>> mod
Module('This is an example module.\n\nThis is the docstring.\n',
      Stmt([Function(None, 'double', ['x'], [], 0,
                    'Return twice the argument',
                    Stmt([Return(Mul((Name('x'), Const(2))))]))]))
>>> from compiler.ast import *
>>> Module('This is an example module.\n\nThis is the docstring.\n',
...      Stmt([Function(None, 'double', ['x'], [], 0,
...                    'Return twice the argument',
...                    Stmt([Return(Mul((Name('x'), Const(2))))]))]))
Module('This is an example module.\n\nThis is the docstring.\n',
      Stmt([Function(None, 'double', ['x'], [], 0,
                    'Return twice the argument',
                    Stmt([Return(Mul((Name('x'), Const(2))))]))]))
>>> mod.doc
'This is an example module.\n\nThis is the docstring.\n'
>>> for node in mod.node.nodes:
...     print node
...
Function(None, 'double', ['x'], [], 0, 'Return twice the argument',
      Stmt([Return(Mul((Name('x'), Const(2))))]))
>>> func = mod.node.nodes[0]
>>> func.code
Stmt([Return(Mul((Name('x'), Const(2))))])
```

31.4 Using Visitors to Walk ASTs

The visitor pattern is ... The `compiler` package uses a variant on the visitor pattern that takes advantage of Python's introspection features to eliminate the need for much of the visitor's infrastructure.

The classes being visited do not need to be programmed to accept visitors. The visitor need only define visit methods for classes it is specifically interested in; a default visit method can handle the rest.

XXX The magic `visit()` method for visitors.

walk (*tree*, *visitor*_[, *verbose*])

class ASTVisitor ()

The `ASTVisitor` is responsible for walking over the tree in the correct order. A walk begins with a call to `preorder()`. For each node, it checks the *visitor* argument to `preorder()` for a method named 'visitNodeName,' where *NodeName* is the name of the node's class, e.g. for a `While` node a `visitWhile()` would be called. If the method exists, it is called with the node as its first argument.

The visitor method for a particular node type can control how child nodes are visited during the walk. The `ASTVisitor` modifies the visitor argument by adding a visit method to the visitor; this method can be used to visit a particular child node. If no visitor is found for a particular node type, the `default()` method is called.

`ASTVisitor` objects have the following methods:

XXX describe extra arguments

default (*node*[, ...])
dispatch (*node*[, ...])
preorder (*tree*, *visitor*)

31.5 Bytecode Generation

The code generator is a visitor that emits bytecodes. Each visit method can call the `emit()` method to emit a new bytecode. The basic code generator is specialized for modules, classes, and functions. An assembler converts that emitted instructions to the low-level bytecode format. It handles things like generation of constant lists of code objects and calculation of jump offsets.

Abstract Syntax Trees

New in version 2.5.

The `_ast` module helps Python applications to process trees of the Python abstract syntax grammar. The Python compiler currently provides read-only access to such trees, meaning that applications can only create a tree for a given piece of Python source code; generating byte code from a (potentially modified) tree is not supported. The abstract syntax itself might change with each Python release; this module helps to find out programmatically what the current grammar looks like.

An abstract syntax tree can be generated by passing `_ast.PyCF_ONLY_AST` as a flag to the `compile` builtin function. The result will be a tree of objects whose classes all inherit from `_ast.AST`.

The actual classes are derived from the `Parser/Python.asdl` file, which is reproduced below. There is one class defined for each left-hand side symbol in the abstract grammar (for example, `_ast.stmt` or `_ast.expr`). In addition, there is one class defined for each constructor on the right-hand side; these classes inherit from the classes for the left-hand side trees. For example, `_ast.BinOp` inherits from `_ast.expr`. For production rules with alternatives (aka "sums"), the left-hand side class is abstract: only instances of specific constructor nodes are ever created.

Each concrete class has an attribute `_fields` which gives the names of all child nodes.

Each instance of a concrete class has one attribute for each child node, of the type as defined in the grammar. For example, `_ast.BinOp` instances have an attribute `left` of type `_ast.expr`. Instances of `_ast.expr` and `_ast.stmt` subclasses also have `lineno` and `col_offset` attributes. The `lineno` is the line number of source text (1 indexed so the first line is line 1) and the `col_offset` is the utf8 byte offset of the first token that generated the node. The utf8 offset is recorded because the parser uses utf8 internally.

If these attributes are marked as optional in the grammar (using a question mark), the value might be `None`. If the attributes can have zero-or-more values (marked with an asterisk), the values are represented as Python lists.

32.1 Abstract Grammar

The module defines a string constant `__version__` which is the decimal subversion revision number of the file shown below.

The abstract grammar is currently defined as follows:

```
-- ASDL's five builtin types are identifier, int, string, object, bool

module Python version "$Revision: 43614 $"
{
  mod = Module(stmt* body)
    | Interactive(stmt* body)
    | Expression(expr body)
```

```

-- not really an actual node but useful in Jython's typesystem.
| Suite(stmt* body)

stmt = FunctionDef(identifier name, arguments args,
                    stmt* body, expr* decorators)
| ClassDef(identifier name, expr* bases, stmt* body)
| Return(expr? value)

| Delete(expr* targets)
| Assign(expr* targets, expr value)
| AugAssign(expr target, operator op, expr value)

-- not sure if bool is allowed, can always use int
| Print(expr? dest, expr* values, bool nl)

-- use 'orelse' because else is a keyword in target languages
| For(expr target, expr iter, stmt* body, stmt* orelse)
| While(expr test, stmt* body, stmt* orelse)
| If(expr test, stmt* body, stmt* orelse)
| With(expr context_expr, expr? optional_vars, stmt* body)

-- 'type' is a bad name
| Raise(expr? type, expr? inst, expr? tback)
| TryExcept(stmt* body, excepthandler* handlers, stmt* orelse)
| TryFinally(stmt* body, stmt* finalbody)
| Assert(expr test, expr? msg)

| Import(alias* names)
| ImportFrom(identifier module, alias* names, int? level)

-- Doesn't capture requirement that locals must be
-- defined if globals is
-- still supports use as a function!
| Exec(expr body, expr? globals, expr? locals)

| Global(identifier* names)
| Expr(expr value)
| Pass | Break | Continue

-- XXX Jython will be different
-- col_offset is the byte offset in the utf8 string the parser uses
attributes (int lineno, int col_offset)

-- BoolOp() can use left & right?
expr = BoolOp(boolop op, expr* values)
| BinOp(expr left, operator op, expr right)
| UnaryOp(unaryop op, expr operand)
| Lambda(arguments args, expr body)
| IfExp(expr test, expr body, expr orelse)
| Dict(expr* keys, expr* values)
| ListComp(expr elt, comprehension* generators)
| GeneratorExp(expr elt, comprehension* generators)
-- the grammar constrains where yield expressions can occur
| Yield(expr? value)
-- need sequences for compare to distinguish between
-- x < 4 < 3 and (x < 4) < 3
| Compare(expr left, cmpop* ops, expr* comparators)
| Call(expr func, expr* args, keyword* keywords,

```

```

expr? starargs, expr? kwargs)
    | Repr(expr value)
    | Num(object n) -- a number as a PyObject.
    | Str(string s) -- need to specify raw, unicode, etc?
    -- other literals? bools?

    -- the following expression can appear in assignment context
    | Attribute(expr value, identifier attr, expr_context ctx)
    | Subscript(expr value, slice slice, expr_context ctx)
    | Name(identifier id, expr_context ctx)
    | List(expr* elts, expr_context ctx)
    | Tuple(expr *elts, expr_context ctx)

    -- col_offset is the byte offset in the utf8 string the parser uses
    attributes (int lineno, int col_offset)

expr_context = Load | Store | Del | AugLoad | AugStore | Param

slice = Ellipsis | Slice(expr? lower, expr? upper, expr? step)
    | ExtSlice(slice* dims)
    | Index(expr value)

boolop = And | Or

operator = Add | Sub | Mult | Div | Mod | Pow | LShift
    | RShift | BitOr | BitXor | BitAnd | FloorDiv

unaryop = Invert | Not | UAdd | USub

cmpop = Eq | NotEq | Lt | LtE | Gt | GtE | Is | IsNot | In | NotIn

comprehension = (expr target, expr iter, expr* ifs)

-- not sure what to call the first argument for raise and except
-- TODO(jhylton): Figure out if there is a better way to handle
--                 lineno and col_offset fields, particularly when
--                 ast is exposed to Python.
excepthandler = (expr? type, expr? name, stmt* body, int lineno,
    int col_offset)

arguments = (expr* args, identifier? vararg,
    identifier? kwarg, expr* defaults)

    -- keyword arguments supplied to call
    keyword = (identifier arg, expr value)

    -- import name with optional 'as' alias.
    alias = (identifier name, identifier? asname)
}

```


Miscellaneous Services

The modules described in this chapter provide miscellaneous services that are available in all Python versions. Here's an overview:

formatter Generic output formatter and device interface.

33.1 `formatter` — Generic output formatting

This module supports two interface definitions, each with multiple implementations. The *formatter* interface is used by the `HTMLParser` class of the `htmllib` module, and the *writer* interface is required by the *formatter* interface.

Formatter objects transform an abstract flow of formatting events into specific output events on writer objects. Formatters manage several stack structures to allow various properties of a writer object to be changed and restored; writers need not be able to handle relative changes nor any sort of “change back” operation. Specific writer properties which may be controlled via formatter objects are horizontal alignment, font, and left margin indentations. A mechanism is provided which supports providing arbitrary, non-exclusive style settings to a writer as well. Additional interfaces facilitate formatting events which are not reversible, such as paragraph separation.

Writer objects encapsulate device interfaces. Abstract devices, such as file formats, are supported as well as physical devices. The provided implementations all work with abstract devices. The interface makes available mechanisms for setting the properties which formatter objects manage and inserting data into the output.

33.1.1 The Formatter Interface

Interfaces to create formatters are dependent on the specific formatter class being instantiated. The interfaces described below are the required interfaces which all formatters must support once initialized.

One data element is defined at the module level:

AS_IS

Value which can be used in the font specification passed to the `push_font()` method described below, or as the new value to any other `push_property()` method. Pushing the `AS_IS` value allows the corresponding `pop_property()` method to be called without having to track whether the property was changed.

The following attributes are defined for formatter instance objects:

writer

The writer instance with which the formatter interacts.

end_paragraph (*blanklines*)

Close any open paragraphs and insert at least *blanklines* before the next paragraph.

add_line_break ()

Add a hard line break if one does not already exist. This does not break the logical paragraph.

add_hor_rule (*args, **kw)

Insert a horizontal rule in the output. A hard break is inserted if there is data in the current paragraph, but the logical paragraph is not broken. The arguments and keywords are passed on to the writer's `send_line_break()` method.

add_flow_data (data)

Provide data which should be formatted with collapsed whitespace. Whitespace from preceding and successive calls to `add_flow_data()` is considered as well when the whitespace collapse is performed. The data which is passed to this method is expected to be word-wrapped by the output device. Note that any word-wrapping still must be performed by the writer object due to the need to rely on device and font information.

add_literal_data (data)

Provide data which should be passed to the writer unchanged. Whitespace, including newline and tab characters, are considered legal in the value of *data*.

add_label_data (format, counter)

Insert a label which should be placed to the left of the current left margin. This should be used for constructing bulleted or numbered lists. If the *format* value is a string, it is interpreted as a format specification for *counter*, which should be an integer. The result of this formatting becomes the value of the label; if *format* is not a string it is used as the label value directly. The label value is passed as the only argument to the writer's `send_label_data()` method. Interpretation of non-string label values is dependent on the associated writer.

Format specifications are strings which, in combination with a counter value, are used to compute label values. Each character in the format string is copied to the label value, with some characters recognized to indicate a transform on the counter value. Specifically, the character 'l' represents the counter value formatter as an Arabic number, the characters 'A' and 'a' represent alphabetic representations of the counter value in upper and lower case, respectively, and 'I' and 'i' represent the counter value in Roman numerals, in upper and lower case. Note that the alphabetic and roman transforms require that the counter value be greater than zero.

flush_softspace ()

Send any pending whitespace buffered from a previous call to `add_flow_data()` to the associated writer object. This should be called before any direct manipulation of the writer object.

push_alignment (align)

Push a new alignment setting onto the alignment stack. This may be `AS_IS` if no change is desired. If the alignment value is changed from the previous setting, the writer's `new_alignment()` method is called with the *align* value.

pop_alignment ()

Restore the previous alignment.

push_font ((size, italic, bold, teletype))

Change some or all font properties of the writer object. Properties which are not set to `AS_IS` are set to the values passed in while others are maintained at their current settings. The writer's `new_font()` method is called with the fully resolved font specification.

pop_font ()

Restore the previous font.

push_margin (margin)

Increase the number of left margin indentations by one, associating the logical tag *margin* with the new indentation. The initial margin level is 0. Changed values of the logical tag must be true values; false values other than `AS_IS` are not sufficient to change the margin.

pop_margin ()

Restore the previous margin.

push_style (*styles)

Push any number of arbitrary style specifications. All styles are pushed onto the styles stack in order. A tuple

representing the entire stack, including AS_IS values, is passed to the writer's `new_styles()` method.

pop_style(`[n = 1]`)

Pop the last *n* style specifications passed to `push_style()`. A tuple representing the revised stack, including AS_IS values, is passed to the writer's `new_styles()` method.

set_spacing(*spacing*)

Set the spacing style for the writer.

assert_line_data(`[flag = 1]`)

Inform the formatter that data has been added to the current paragraph out-of-band. This should be used when the writer has been manipulated directly. The optional *flag* argument can be set to false if the writer manipulations produced a hard line break at the end of the output.

33.1.2 Formatter Implementations

Two implementations of formatter objects are provided by this module. Most applications may use one of these classes without modification or subclassing.

class NullFormatter(`[writer]`)

A formatter which does nothing. If *writer* is omitted, a `NullWriter` instance is created. No methods of the writer are called by `NullFormatter` instances. Implementations should inherit from this class if implementing a writer interface but don't need to inherit any implementation.

class AbstractFormatter(*writer*)

The standard formatter. This implementation has demonstrated wide applicability to many writers, and may be used directly in most circumstances. It has been used to implement a full-featured World Wide Web browser.

33.1.3 The Writer Interface

Interfaces to create writers are dependent on the specific writer class being instantiated. The interfaces described below are the required interfaces which all writers must support once initialized. Note that while most applications can use the `AbstractFormatter` class as a formatter, the writer must typically be provided by the application.

flush()

Flush any buffered output or device control events.

new_alignment(*align*)

Set the alignment style. The *align* value can be any object, but by convention is a string or `None`, where `None` indicates that the writer's "preferred" alignment should be used. Conventional *align* values are 'left', 'center', 'right', and 'justify'.

new_font(*font*)

Set the font style. The value of *font* will be `None`, indicating that the device's default font should be used, or a tuple of the form (*size*, *italic*, *bold*, *teletype*). *Size* will be a string indicating the size of font that should be used; specific strings and their interpretation must be defined by the application. The *italic*, *bold*, and *teletype* values are Boolean values specifying which of those font attributes should be used.

new_margin(*margin*, *level*)

Set the margin level to the integer *level* and the logical tag to *margin*. Interpretation of the logical tag is at the writer's discretion; the only restriction on the value of the logical tag is that it not be a false value for non-zero values of *level*.

new_spacing(*spacing*)

Set the spacing style to *spacing*.

new_styles(*styles*)

Set additional styles. The *styles* value is a tuple of arbitrary values; the value AS_IS should be ignored. The

styles tuple may be interpreted either as a set or as a stack depending on the requirements of the application and writer implementation.

send_line_break()

Break the current line.

send_paragraph(*blankline*)

Produce a paragraph separation of at least *blankline* blank lines, or the equivalent. The *blankline* value will be an integer. Note that the implementation will receive a call to `send_line_break()` before this call if a line break is needed; this method should not include ending the last line of the paragraph. It is only responsible for vertical spacing between paragraphs.

send_hor_rule(*args, **kw)

Display a horizontal rule on the output device. The arguments to this method are entirely application- and writer-specific, and should be interpreted with care. The method implementation may assume that a line break has already been issued via `send_line_break()`.

send_flowng_data(*data*)

Output character data which may be word-wrapped and re-flowed as needed. Within any sequence of calls to this method, the writer may assume that spans of multiple whitespace characters have been collapsed to single space characters.

send_literal_data(*data*)

Output character data which has already been formatted for display. Generally, this should be interpreted to mean that line breaks indicated by newline characters should be preserved and no new line breaks should be introduced. The data may contain embedded newline and tab characters, unlike data provided to the `send_formatted_data()` interface.

send_label_data(*data*)

Set *data* to the left of the current left margin, if possible. The value of *data* is not restricted; treatment of non-string values is entirely application- and writer-dependent. This method will only be called at the beginning of a line.

33.1.4 Writer Implementations

Three implementations of the writer object interface are provided as examples by this module. Most applications will need to derive new writer classes from the `NullWriter` class.

class NullWriter()

A writer which only provides the interface definition; no actions are taken on any methods. This should be the base class for all writers which do not need to inherit any implementation methods.

class AbstractWriter()

A writer which can be used in debugging formatters, but not much else. Each method simply announces itself by printing its name and arguments on standard output.

class DumbWriter([*file*], *maxcol* = 72))

Simple writer class which writes output on the file object passed in as *file* or, if *file* is omitted, on standard output. The output is simply word-wrapped to the number of columns specified by *maxcol*. This class is suitable for reflowing a sequence of paragraphs.

SGI IRIX Specific Services

The modules described in this chapter provide interfaces to features that are unique to SGI's IRIX operating system (versions 4 and 5).

al	Audio functions on the SGI.
AL	Constants used with the al module.
cd	Interface to the CD-ROM on Silicon Graphics systems.
fl	FORMS library for applications with graphical user interfaces.
FL	Constants used with the fl module.
flp	Functions for loading stored FORMS designs.
fm	<i>Font Manager</i> interface for SGI workstations.
gl	Functions from the Silicon Graphics <i>Graphics Library</i> .
DEVICE	Constants used with the gl module.
GL	Constants used with the gl module.
imgfile	Support for SGI <i>imglib</i> files.
jpeg	Read and write image files in compressed JPEG format.

34.1 al — Audio functions on the SGI

This module provides access to the audio facilities of the SGI Indy and Indigo workstations. See section 3A of the IRIX man pages for details. You'll need to read those man pages to understand what these functions do! Some of the functions are not available in IRIX releases before 4.0.5. Again, see the manual to check whether a specific function is available on your platform.

All functions and methods defined in this module are equivalent to the C functions with 'AL' prefixed to their name.

Symbolic constants from the C header file `<audio.h>` are defined in the standard module **AL**, see below.

Warning: The current version of the audio library may dump core when bad argument values are passed rather than returning an error status. Unfortunately, since the precise circumstances under which this may happen are undocumented and hard to check, the Python interface can provide no protection against this kind of problems. (One example is specifying an excessive queue size — there is no documented upper limit.)

The module defines the following functions:

openport (*name*, *direction*[, *config*])

The *name* and *direction* arguments are strings. The optional *config* argument is a configuration object as returned by `newconfig()`. The return value is an *audio port object*; methods of audio port objects are described below.

newconfig ()

The return value is a new *audio configuration object*; methods of audio configuration objects are described below.

queryparams (*device*)

The *device* argument is an integer. The return value is a list of integers containing the data returned by `ALqueryparams()`.

getparams (*device*, *list*)

The *device* argument is an integer. The *list* argument is a list such as returned by `queryparams()`; it is modified in place (!).

setparams (*device*, *list*)

The *device* argument is an integer. The *list* argument is a list such as returned by `queryparams()`.

34.1.1 Configuration Objects

Configuration objects returned by `newconfig()` have the following methods:

getqueuesize ()

Return the queue size.

setqueuesize (*size*)

Set the queue size.

getwidth ()

Get the sample width.

setwidth (*width*)

Set the sample width.

getchannels ()

Get the channel count.

setchannels (*nchannels*)

Set the channel count.

getsampfmt ()

Get the sample format.

setsampfmt (*sampfmt*)

Set the sample format.

getfloatmax ()

Get the maximum value for floating sample formats.

setfloatmax (*floatmax*)

Set the maximum value for floating sample formats.

34.1.2 Port Objects

Port objects, as returned by `openport()`, have the following methods:

closeport ()

Close the port.

getfd ()

Return the file descriptor as an int.

getfilled ()

Return the number of filled samples.

getfillable ()

Return the number of fillable samples.

readsamps (*nsamples*)

Read a number of samples from the queue, blocking if necessary. Return the data as a string containing the raw data, (e.g., 2 bytes per sample in big-endian byte order (high byte, low byte) if you have set the sample width to 2 bytes).

writesamps (*samples*)

Write samples into the queue, blocking if necessary. The samples are encoded as described for the `readsamps()` return value.

getfillpoint ()

Return the 'fill point'.

setfillpoint (*fillpoint*)

Set the 'fill point'.

getconfig ()

Return a configuration object containing the current configuration of the port.

setconfig (*config*)

Set the configuration from the argument, a configuration object.

getstatus (*list*)

Get status information on last error.

34.2 AL — Constants used with the `al` module

This module defines symbolic constants needed to use the built-in module `al` (see above); they are equivalent to those defined in the C header file `<audio.h>` except that the name prefix 'AL_' is omitted. Read the module source for a complete list of the defined names. Suggested use:

```
import al
from AL import *
```

34.3 `cd` — CD-ROM access on SGI systems

This module provides an interface to the Silicon Graphics CD library. It is available only on Silicon Graphics systems.

The way the library works is as follows. A program opens the CD-ROM device with `open()` and creates a parser to parse the data from the CD with `createparser()`. The object returned by `open()` can be used to read data from the CD, but also to get status information for the CD-ROM device, and to get information about the CD, such as the table of contents. Data from the CD is passed to the parser, which parses the frames, and calls any callback functions that have previously been added.

An audio CD is divided into *tracks* or *programs* (the terms are used interchangeably). Tracks can be subdivided into *indices*. An audio CD contains a *table of contents* which gives the starts of the tracks on the CD. Index 0 is usually the pause before the start of a track. The start of the track as given by the table of contents is normally the start of index 1.

Positions on a CD can be represented in two ways. Either a frame number or a tuple of three values, minutes, seconds and frames. Most functions use the latter representation. Positions can be both relative to the beginning of the CD, and to the beginning of the track.

Module `cd` defines the following functions and constants:

createparser ()

Create and return an opaque parser object. The methods of the parser object are described below.

msftoframe (*minutes, seconds, frames*)

Converts a (*minutes, seconds, frames*) triple representing time in absolute time code into the corresponding CD frame number.

open ([*device* [, *mode*]])

Open the CD-ROM device. The return value is an opaque player object; methods of the player object are described below. The device is the name of the SCSI device file, e.g. `'/dev/scsi/sc0d410'`, or `None`. If omitted or `None`, the hardware inventory is consulted to locate a CD-ROM drive. The *mode*, if not omitted, should be the string `'r'`.

The module defines the following variables:

exception error

Exception raised on various errors.

DATASIZE

The size of one frame's worth of audio data. This is the size of the audio data as passed to the callback of type `audio`.

BLOCKSIZE

The size of one uninterpreted frame of audio data.

The following variables are states as returned by `getstatus()`:

READY

The drive is ready for operation loaded with an audio CD.

NODISC

The drive does not have a CD loaded.

CDROM

The drive is loaded with a CD-ROM. Subsequent play or read operations will return I/O errors.

ERROR

An error occurred while trying to read the disc or its table of contents.

PLAYING

The drive is in CD player mode playing an audio CD through its audio jacks.

PAUSED

The drive is in CD layer mode with play paused.

STILL

The equivalent of `PAUSED` on older (non 3301) model Toshiba CD-ROM drives. Such drives have never been shipped by SGI.

audio

pnum

index

ptime

atime

catalog

ident

control

Integer constants describing the various types of parser callbacks that can be set by the `addcallback()` method of CD parser objects (see below).

34.3.1 Player Objects

Player objects (returned by `open()`) have the following methods:

allowremoval()

Unlocks the eject button on the CD-ROM drive permitting the user to eject the caddy if desired.

bestreadsize()

Returns the best value to use for the *num_frames* parameter of the `readda()` method. Best is defined as the value that permits a continuous flow of data from the CD-ROM drive.

close()

Frees the resources associated with the player object. After calling `close()`, the methods of the object should no longer be used.

eject()

Ejects the caddy from the CD-ROM drive.

getstatus()

Returns information pertaining to the current state of the CD-ROM drive. The returned information is a tuple with the following values: *state*, *track*, *rtime*, *atime*, *ttime*, *first*, *last*, *scsi_audio*, *cur_block*. *rtime* is the time relative to the start of the current track; *atime* is the time relative to the beginning of the disc; *ttime* is the total time on the disc. For more information on the meaning of the values, see the man page `CDgetstatus(3dm)`. The value of *state* is one of the following: `ERROR`, `NODISC`, `READY`, `PLAYING`, `PAUSED`, `STILL`, or `CDROM`.

gettrackinfo(track)

Returns information about the specified track. The returned information is a tuple consisting of two elements, the start time of the track and the duration of the track.

msftoblock(min, sec, frame)

Converts a minutes, seconds, frames triple representing a time in absolute time code into the corresponding logical block number for the given CD-ROM drive. You should use `msftoframe()` rather than `msftoblock()` for comparing times. The logical block number differs from the frame number by an offset required by certain CD-ROM drives.

play(start, play)

Starts playback of an audio CD in the CD-ROM drive at the specified track. The audio output appears on the CD-ROM drive's headphone and audio jacks (if fitted). Play stops at the end of the disc. *start* is the number of the track at which to start playing the CD; if *play* is 0, the CD will be set to an initial paused state. The method `togglepause()` can then be used to commence play.

playabs(minutes, seconds, frames, play)

Like `play()`, except that the start is given in minutes, seconds, and frames instead of a track number.

playtrack(start, play)

Like `play()`, except that playing stops at the end of the track.

playtrackabs(track, minutes, seconds, frames, play)

Like `play()`, except that playing begins at the specified absolute time and ends at the end of the specified track.

preventremoval()

Locks the eject button on the CD-ROM drive thus preventing the user from arbitrarily ejecting the caddy.

readda(num_frames)

Reads the specified number of frames from an audio CD mounted in the CD-ROM drive. The return value is a string representing the audio frames. This string can be passed unaltered to the `parseframe()` method of the parser object.

seek(minutes, seconds, frames)

Sets the pointer that indicates the starting point of the next read of digital audio data from a CD-ROM. The pointer is set to an absolute time code location specified in *minutes*, *seconds*, and *frames*. The return value is the logical block number to which the pointer has been set.

seekblock(block)

Sets the pointer that indicates the starting point of the next read of digital audio data from a CD-ROM. The pointer is set to the specified logical block number. The return value is the logical block number to which the pointer has been set.

seektrack (*track*)

Sets the pointer that indicates the starting point of the next read of digital audio data from a CD-ROM. The pointer is set to the specified track. The return value is the logical block number to which the pointer has been set.

stop ()

Stops the current playing operation.

togglepause ()

Pauses the CD if it is playing, and makes it play if it is paused.

34.3.2 Parser Objects

Parser objects (returned by `createparser()`) have the following methods:

addcallback (*type, func, arg*)

Adds a callback for the parser. The parser has callbacks for eight different types of data in the digital audio data stream. Constants for these types are defined at the `cd` module level (see above). The callback is called as follows: *func* (*arg, type, data*), where *arg* is the user supplied argument, *type* is the particular type of callback, and *data* is the data returned for this *type* of callback. The type of the data depends on the *type* of callback as follows:

Type	Value
audio	String which can be passed unmodified to <code>al.writesamps()</code> .
pnum	Integer giving the program (track) number.
index	Integer giving the index number.
ptime	Tuple consisting of the program time in minutes, seconds, and frames.
atime	Tuple consisting of the absolute time in minutes, seconds, and frames.
catalog	String of 13 characters, giving the catalog number of the CD.
ident	String of 12 characters, giving the ISRC identification number of the recording. The string consists of two characters country code, three characters owner code, two characters giving the year, and five characters giving a serial number.
control	Integer giving the control bits from the CD subcode data

deleteparser ()

Deletes the parser and frees the memory it was using. The object should not be used after this call. This call is done automatically when the last reference to the object is removed.

parseframe (*frame*)

Parses one or more frames of digital audio data from a CD such as returned by `readadda()`. It determines which subcodes are present in the data. If these subcodes have changed since the last frame, then `parseframe()` executes a callback of the appropriate type passing to it the subcode data found in the frame. Unlike the `C` function, more than one frame of digital audio data can be passed to this method.

removecallback (*type*)

Removes the callback for the given *type*.

resetparser ()

Resets the fields of the parser used for tracking subcodes to an initial state. `resetparser()` should be called after the disc has been changed.

34.4 fl — FORMS library for graphical user interfaces

This module provides an interface to the FORMS Library by Mark Overmars. The source for the library can be retrieved by anonymous ftp from host `'ftp.cs.ruu.nl'`, directory `'SGI/FORMS'`. It was last tested with version 2.0b.

Most functions are literal translations of their C equivalents, dropping the initial `'fl_'` from their name. Constants used by the library are defined in module [FL](#) described below.

The creation of objects is a little different in Python than in C: instead of the 'current form' maintained by the library to which new FORMS objects are added, all functions that add a FORMS object to a form are methods of the Python object representing the form. Consequently, there are no Python equivalents for the C functions `fl_addto_form()` and `fl_end_form()`, and the equivalent of `fl_bgn_form()` is called `fl.make_form()`.

Watch out for the somewhat confusing terminology: FORMS uses the word *object* for the buttons, sliders etc. that you can place in a form. In Python, 'object' means any value. The Python interface to FORMS introduces two new Python object types: form objects (representing an entire form) and FORMS objects (representing one button, slider etc.). Hopefully this isn't too confusing.

There are no 'free objects' in the Python interface to FORMS, nor is there an easy way to add object classes written in Python. The FORMS interface to GL event handling is available, though, so you can mix FORMS with pure GL windows.

Please note: importing `fl` implies a call to the GL function `foreground()` and to the FORMS routine `fl_init()`.

34.4.1 Functions Defined in Module `fl`

Module `fl` defines the following functions. For more information about what they do, see the description of the equivalent C function in the FORMS documentation:

`make_form` (*type, width, height*)

Create a form with given type, width and height. This returns a *form* object, whose methods are described below.

`do_forms` ()

The standard FORMS main loop. Returns a Python object representing the FORMS object needing interaction, or the special value `FL.EVENT`.

`check_forms` ()

Check for FORMS events. Returns what `do_forms()` above returns, or `None` if there is no event that immediately needs interaction.

`set_event_callback` (*function*)

Set the event callback function.

`set_graphics_mode` (*rgbmode, doublebuffering*)

Set the graphics modes.

`get_rgbmode` ()

Return the current rgb mode. This is the value of the C global variable `fl_rgbmode`.

`show_message` (*str1, str2, str3*)

Show a dialog box with a three-line message and an OK button.

`show_question` (*str1, str2, str3*)

Show a dialog box with a three-line message and YES and NO buttons. It returns 1 if the user pressed YES, 0 if NO.

`show_choice` (*str1, str2, str3, but1[, but2[, but3]]*)

Show a dialog box with a three-line message and up to three buttons. It returns the number of the button clicked

by the user (1, 2 or 3).

show_input (*prompt, default*)

Show a dialog box with a one-line prompt message and text field in which the user can enter a string. The second argument is the default input string. It returns the string value as edited by the user.

show_file_selector (*message, directory, pattern, default*)

Show a dialog box in which the user can select a file. It returns the absolute filename selected by the user, or None if the user presses Cancel.

get_directory ()

get_pattern ()

get_filename ()

These functions return the directory, pattern and filename (the tail part only) selected by the user in the last `show_file_selector()` call.

qdevice (*dev*)

unqdevice (*dev*)

isqueued (*dev*)

qtest ()

qread ()

qreset ()

qenter (*dev, val*)

get_mouse ()

tie (*button, valuator1, valuator2*)

These functions are the FORMS interfaces to the corresponding GL functions. Use these if you want to handle some GL events yourself when using `fl.do_events()`. When a GL event is detected that FORMS cannot handle, `fl.do_forms()` returns the special value `FL.EVENT` and you should call `fl.qread()` to read the event from the queue. Don't use the equivalent GL functions!

color ()

mapcolor ()

getmcolor ()

See the description in the FORMS documentation of `fl_color()`, `fl_mapcolor()` and `fl_getmcolor()`.

34.4.2 Form Objects

Form objects (returned by `make_form()` above) have the following methods. Each method corresponds to a C function whose name is prefixed with 'fl_'; and whose first argument is a form pointer; please refer to the official FORMS documentation for descriptions.

All the `add_*()` methods return a Python object representing the FORMS object. Methods of FORMS objects are described below. Most kinds of FORMS object also have some methods specific to that kind; these methods are listed here.

show_form (*placement, bordertype, name*)

Show the form.

hide_form ()

Hide the form.

redraw_form ()

Redraw the form.

set_form_position (*x, y*)

Set the form's position.

freeze_form()
Freeze the form.

unfreeze_form()
Unfreeze the form.

activate_form()
Activate the form.

deactivate_form()
Deactivate the form.

bgn_group()
Begin a new group of objects; return a group object.

end_group()
End the current group of objects.

find_first()
Find the first object in the form.

find_last()
Find the last object in the form.

add_box(*type, x, y, w, h, name*)
Add a box object to the form. No extra methods.

add_text(*type, x, y, w, h, name*)
Add a text object to the form. No extra methods.

add_clock(*type, x, y, w, h, name*)
Add a clock object to the form.
Method: `get_clock()`.

add_button(*type, x, y, w, h, name*)
Add a button object to the form.
Methods: `get_button()`, `set_button()`.

add_lightbutton(*type, x, y, w, h, name*)
Add a lightbutton object to the form.
Methods: `get_button()`, `set_button()`.

add_roundbutton(*type, x, y, w, h, name*)
Add a roundbutton object to the form.
Methods: `get_button()`, `set_button()`.

add_slider(*type, x, y, w, h, name*)
Add a slider object to the form.
Methods: `set_slider_value()`, `get_slider_value()`, `set_slider_bounds()`,
`get_slider_bounds()`, `set_slider_return()`, `set_slider_size()`,
`set_slider_precision()`, `set_slider_step()`.

add_valslider(*type, x, y, w, h, name*)
Add a valslider object to the form.
Methods: `set_slider_value()`, `get_slider_value()`, `set_slider_bounds()`,
`get_slider_bounds()`, `set_slider_return()`, `set_slider_size()`,
`set_slider_precision()`, `set_slider_step()`.

add_dial(*type, x, y, w, h, name*)
Add a dial object to the form.
Methods: `set_dial_value()`, `get_dial_value()`, `set_dial_bounds()`,
`get_dial_bounds()`.

add_positioner (*type, x, y, w, h, name*)
 Add a positioner object to the form.
 Methods: `set_positioner_xvalue()`, `set_positioner_yvalue()`,
`set_positioner_xbounds()`, `set_positioner_ybounds()`, `get_positioner_xvalue()`,
`get_positioner_yvalue()`, `get_positioner_xbounds()`, `get_positioner_ybounds()`.

add_counter (*type, x, y, w, h, name*)
 Add a counter object to the form.
 Methods: `set_counter_value()`, `get_counter_value()`, `set_counter_bounds()`,
`set_counter_step()`, `set_counter_precision()`, `set_counter_return()`.

add_input (*type, x, y, w, h, name*)
 Add an input object to the form.
 Methods: `set_input()`, `get_input()`, `set_input_color()`, `set_input_return()`.

add_menu (*type, x, y, w, h, name*)
 Add a menu object to the form.
 Methods: `set_menu()`, `get_menu()`, `addto_menu()`.

add_choice (*type, x, y, w, h, name*)
 Add a choice object to the form.
 Methods: `set_choice()`, `get_choice()`, `clear_choice()`, `addto_choice()`,
`replace_choice()`, `delete_choice()`, `get_choice_text()`, `set_choice_fontsize()`,
`set_choice_fontstyle()`.

add_browser (*type, x, y, w, h, name*)
 Add a browser object to the form.
 Methods: `set_browser_topleftine()`, `clear_browser()`, `add_browser_line()`,
`addto_browser()`, `insert_browser_line()`, `delete_browser_line()`,
`replace_browser_line()`, `get_browser_line()`, `load_browser()`,
`get_browser_maxline()`, `select_browser_line()`, `deselect_browser_line()`,
`deselect_browser()`, `isselected_browser_line()`, `get_browser()`,
`set_browser_fontsize()`, `set_browser_fontstyle()`, `set_browser_specialkey()`.

add_timer (*type, x, y, w, h, name*)
 Add a timer object to the form.
 Methods: `set_timer()`, `get_timer()`.

Form objects have the following data attributes; see the FORMS documentation:

Name	C Type	Meaning
<code>window</code>	<code>int</code> (read-only)	GL window id
<code>w</code>	<code>float</code>	form width
<code>h</code>	<code>float</code>	form height
<code>x</code>	<code>float</code>	form x origin
<code>y</code>	<code>float</code>	form y origin
<code>deactivated</code>	<code>int</code>	nonzero if form is deactivated
<code>visible</code>	<code>int</code>	nonzero if form is visible
<code>frozen</code>	<code>int</code>	nonzero if form is frozen
<code>doublebuf</code>	<code>int</code>	nonzero if double buffering on

34.4.3 FORMS Objects

Besides methods specific to particular kinds of FORMS objects, all FORMS objects also have the following methods:

set_call_back (*function, argument*)
 Set the object's callback function and argument. When the object needs interaction, the callback function will be

called with two arguments: the object, and the callback argument. (FORMS objects without a callback function are returned by `fl.do_forms()` or `fl.check_forms()` when they need interaction.) Call this method without arguments to remove the callback function.

delete_object()
Delete the object.

show_object()
Show the object.

hide_object()
Hide the object.

redraw_object()
Redraw the object.

freeze_object()
Freeze the object.

unfreeze_object()
Unfreeze the object.

FORMS objects have these data attributes; see the FORMS documentation:

Name	C Type	Meaning
objclass	int (read-only)	object class
type	int (read-only)	object type
boxtype	int	box type
x	float	x origin
y	float	y origin
w	float	width
h	float	height
col1	int	primary color
col2	int	secondary color
align	int	alignment
lcol	int	label color
lsize	float	label font size
label	string	label string
lstyle	int	label style
pushed	int (read-only)	(see FORMS docs)
focus	int (read-only)	(see FORMS docs)
belowmouse	int (read-only)	(see FORMS docs)
frozen	int (read-only)	(see FORMS docs)
active	int (read-only)	(see FORMS docs)
input	int (read-only)	(see FORMS docs)
visible	int (read-only)	(see FORMS docs)
radio	int (read-only)	(see FORMS docs)
automatic	int (read-only)	(see FORMS docs)

34.5 FL — Constants used with the fl module

This module defines symbolic constants needed to use the built-in module `fl` (see above); they are equivalent to those defined in the C header file `<forms.h>` except that the name prefix ‘FL_’ is omitted. Read the module source for a complete list of the defined names. Suggested use:

```
import fl
from FL import *
```

34.6 flp — Functions for loading stored FORMS designs

This module defines functions that can read form definitions created by the ‘form designer’ (**fdesign**) program that comes with the FORMS library (see module [fl](#) above).

For now, see the file ‘flp.doc’ in the Python library source directory for a description.

XXX A complete description should be inserted here!

34.7 fm — *Font Manager* interface

This module provides access to the IRIS *Font Manager* library. It is available only on Silicon Graphics machines. See also: *4Sight User’s Guide*, section 1, chapter 5: “Using the IRIS Font Manager.”

This is not yet a full interface to the IRIS Font Manager. Among the unsupported features are: matrix operations; cache operations; character operations (use string operations instead); some details of font info; individual glyph metrics; and printer matching.

It supports the following operations:

init()
Initialization function. Calls `fm_init()`. It is normally not necessary to call this function, since it is called automatically the first time the `fm` module is imported.

findfont(fontname)
Return a font handle object. Calls `fm_findfont(fontname)`.

enumerate()
Returns a list of available font names. This is an interface to `fm_enumerate()`.

prstr(string)
Render a string using the current font (see the `setfont()` font handle method below). Calls `fm_prstr(string)`.

setpath(string)
Sets the font search path. Calls `fm_setpath(string)`. (XXX Does not work!?)

fontpath()
Returns the current font search path.

Font handle objects support the following operations:

scalefont(factor)
Returns a handle for a scaled version of this font. Calls `fm_scalefont(fh, factor)`.

setfont()
Makes this font the current font. Note: the effect is undone silently when the font handle object is deleted. Calls `fm_setfont(fh)`.

getfontname()
Returns this font’s name. Calls `fm_getfontname(fh)`.

getcomment()
Returns the comment string associated with this font. Raises an exception if there is none. Calls


```
fmgetcomment(fh).
```

getfontinfo()

Returns a tuple giving some pertinent data about this font. This is an interface to `fmgetfontinfo()`. The returned tuple contains the following numbers: (*printermatched*, *fixed_width*, *xorig*, *yorig*, *xsize*, *ysize*, *height*, *nglyphs*).

getstrwidth(string)

Returns the width, in pixels, of *string* when drawn in this font. Calls `fmgetstrwidth(fh, string)`.

34.8 gl — *Graphics Library* interface

This module provides access to the Silicon Graphics *Graphics Library*. It is available only on Silicon Graphics machines.

Warning: Some illegal calls to the GL library cause the Python interpreter to dump core. In particular, the use of most GL calls is unsafe before the first window is opened.

The module is too large to document here in its entirety, but the following should help you to get started. The parameter conventions for the C functions are translated to Python as follows:

- All (short, long, unsigned) int values are represented by Python integers.
- All float and double values are represented by Python floating point numbers. In most cases, Python integers are also allowed.
- All arrays are represented by one-dimensional Python lists. In most cases, tuples are also allowed.
- All string and character arguments are represented by Python strings, for instance, `winopen('Hi There!')` and `rotate(900, 'z')`.
- All (short, long, unsigned) integer arguments or return values that are only used to specify the length of an array argument are omitted. For example, the C call

```
lmdef(deftype, index, np, props)
```

is translated to Python as

```
lmdef(deftype, index, props)
```

- Output arguments are omitted from the argument list; they are transmitted as function return values instead. If more than one value must be returned, the return value is a tuple. If the C function has both a regular return value (that is not omitted because of the previous rule) and an output argument, the return value comes first in the tuple. Examples: the C call

```
getmcolor(i, &red, &green, &blue)
```

is translated to Python as

```
red, green, blue = getmcolor(i)
```

The following functions are non-standard or have special argument conventions:

varray (*argument*)

Equivalent to but faster than a number of `v3d()` calls. The *argument* is a list (or tuple) of points. Each point must be a tuple of coordinates (x, y, z) or (x, y) . The points may be 2- or 3-dimensional but must all have the same dimension. Float and int values may be mixed however. The points are always converted to 3D double precision points by assuming $z = 0.0$ if necessary (as indicated in the man page), and for each point `v3d()` is called.

nvarray ()

Equivalent to but faster than a number of `n3f` and `v3f` calls. The argument is an array (list or tuple) of pairs of normals and points. Each pair is a tuple of a point and a normal for that point. Each point or normal must be a tuple of coordinates (x, y, z) . Three coordinates must be given. Float and int values may be mixed. For each pair, `n3f()` is called for the normal, and then `v3f()` is called for the point.

vnarray ()

Similar to `nvarray()` but the pairs have the point first and the normal second.

nurbssurface (*s_k, t_k, ctl, s_ord, t_ord, type*)

Defines a nurbs surface. The dimensions of `ctl[][]` are computed as follows: $[\text{len}(s_k) - s_ord], [\text{len}(t_k) - t_ord]$.

nurbscurve (*knots, ctlpoints, order, type*)

Defines a nurbs curve. The length of `ctlpoints` is $\text{len}(knots) - order$.

pwlcurve (*points, type*)

Defines a piecewise-linear curve. *points* is a list of points. *type* must be `N_ST`.

pick (*n*)

select (*n*)

The only argument to these functions specifies the desired size of the pick or select buffer.

endpick ()

endselect ()

These functions have no arguments. They return a list of integers representing the used part of the pick/select buffer. No method is provided to detect buffer overrun.

Here is a tiny but complete example GL program in Python:

```

import gl, GL, time

def main():
    gl.foreground()
    gl.prefposition(500, 900, 500, 900)
    w = gl.winopen('CrissCross')
    gl.ortho2(0.0, 400.0, 0.0, 400.0)
    gl.color(GL.WHITE)
    gl.clear()
    gl.color(GL.RED)
    gl.bgnline()
    gl.v2f(0.0, 0.0)
    gl.v2f(400.0, 400.0)
    gl.endline()
    gl.bgnline()
    gl.v2f(400.0, 0.0)
    gl.v2f(0.0, 400.0)
    gl.endline()
    time.sleep(5)

main()

```

See Also:

PyOpenGL: The Python OpenGL Binding

(<http://pyopengl.sourceforge.net/>)

An interface to OpenGL is also available; see information about the **PyOpenGL** project online at <http://pyopengl.sourceforge.net/>. This may be a better option if support for SGI hardware from before about 1996 is not required.

34.9 DEVICE — Constants used with the `gl` module

This module defines the constants used by the Silicon Graphics *Graphics Library* that C programmers find in the header file `<gl/device.h>`. Read the module source file for details.

34.10 GL — Constants used with the `gl` module

This module contains constants used by the Silicon Graphics *Graphics Library* from the C header file `<gl/gl.h>`. Read the module source file for details.

34.11 `imgfile` — Support for SGI `imglib` files

The `imgfile` module allows Python programs to access SGI `imglib` image files (also known as ‘.rgb’ files). The module is far from complete, but is provided anyway since the functionality that there is enough in some cases. Currently, colormap files are not supported.

The module defines the following variables and functions:

exception error

This exception is raised on all errors, such as unsupported file type, etc.

getsizes (*file*)

This function returns a tuple (*x*, *y*, *z*) where *x* and *y* are the size of the image in pixels and *z* is the number of bytes per pixel. Only 3 byte RGB pixels and 1 byte greyscale pixels are currently supported.

read (*file*)

This function reads and decodes the image on the specified file, and returns it as a Python string. The string has either 1 byte greyscale pixels or 4 byte RGBA pixels. The bottom left pixel is the first in the string. This format is suitable to pass to `gl.rectwrite()`, for instance.

readscaled (*file*, *x*, *y*, *filter* [, *blur*])

This function is identical to `read` but it returns an image that is scaled to the given *x* and *y* sizes. If the *filter* and *blur* parameters are omitted scaling is done by simply dropping or duplicating pixels, so the result will be less than perfect, especially for computer-generated images.

Alternatively, you can specify a filter to use to smooth the image after scaling. The filter forms supported are 'impulse', 'box', 'triangle', 'quadratic' and 'gaussian'. If a filter is specified *blur* is an optional parameter specifying the blurriness of the filter. It defaults to 1.0.

`readscaled()` makes no attempt to keep the aspect ratio correct, so that is the users' responsibility.

ttob (*flag*)

This function sets a global flag which defines whether the scan lines of the image are read or written from bottom to top (*flag* is zero, compatible with SGI GL) or from top to bottom (*flag* is one, compatible with X). The default is zero.

write (*file*, *data*, *x*, *y*, *z*)

This function writes the RGB or greyscale data in *data* to image file *file*. *x* and *y* give the size of the image, *z* is 1 for 1 byte greyscale images or 3 for RGB images (which are stored as 4 byte values of which only the lower three bytes are used). These are the formats returned by `gl.rectread()`.

34.12 jpeg — Read and write JPEG files

The module `jpeg` provides access to the jpeg compressor and decompressor written by the Independent JPEG Group (IJG). JPEG is a standard for compressing pictures; it is defined in ISO 10918. For details on JPEG or the Independent JPEG Group software refer to the JPEG standard or the documentation provided with the software.

A portable interface to JPEG image files is available with the Python Imaging Library (PIL) by Fredrik Lundh. Information on PIL is available at <http://www.pythonware.com/products/pil/>.

The `jpeg` module defines an exception and some functions.

exception error

Exception raised by `compress()` and `decompress()` in case of errors.

compress (*data*, *w*, *h*, *b*)

Treat data as a pixmap of width *w* and height *h*, with *b* bytes per pixel. The data is in SGI GL order, so the first pixel is in the lower-left corner. This means that `gl.rectread()` return data can immediately be passed to `compress()`. Currently only 1 byte and 4 byte pixels are allowed, the former being treated as greyscale and the latter as RGB color. `compress()` returns a string that contains the compressed picture, in JFIF format.

decompress (*data*)

Data is a string containing a picture in JFIF format. It returns a tuple (*data*, *width*, *height*, *bytesperpixel*). Again, the data is suitable to pass to `gl.rectwrite()`.

setoption (*name*, *value*)

Set various options. Subsequent `compress()` and `decompress()` calls will use these options. The following options are available:

Option	Effect
'forcegray'	Force output to be grayscale, even if input is RGB.
'quality'	Set the quality of the compressed image to a value between 0 and 100 (default is 75). This only affects compression.
'optimize'	Perform Huffman table optimization. Takes longer, but results in smaller compressed image. This only affects compression.
'smooth'	Perform inter-block smoothing on uncompressed image. Only useful for low-quality images. This only affects decompression.

See Also:

JPEG Still Image Data Compression Standard

The canonical reference for the JPEG image format, by Pennebaker and Mitchell.

Information Technology - Digital Compression and Coding of Continuous-tone Still Images - Requirements and Guidelines
(<http://www.w3.org/Graphics/JPEG/itu-t81.pdf>)

The ISO standard for JPEG is also published as ITU T.81. This is available online in PDF form.

SunOS Specific Services

The modules described in this chapter provide interfaces to features that are unique to SunOS 5 (also known as Solaris version 2).

35.1 sunaudiodev — Access to Sun audio hardware

This module allows you to access the Sun audio interface. The Sun audio hardware is capable of recording and playing back audio data in u-LAW format with a sample rate of 8K per second. A full description can be found in the *audio(7I)* manual page.

The module `SUNAUDIODEV` defines constants which may be used with this module.

This module defines the following variables and functions:

exception error

This exception is raised on all errors. The argument is a string describing what went wrong.

open (mode)

This function opens the audio device and returns a Sun audio device object. This object can then be used to do I/O on. The *mode* parameter is one of `'r'` for record-only access, `'w'` for play-only access, `'rw'` for both and `'control'` for access to the control device. Since only one process is allowed to have the recorder or player open at the same time it is a good idea to open the device only for the activity needed. See *audio(7I)* for details.

As per the manpage, this module first looks in the environment variable `AUDIODEV` for the base audio device filename. If not found, it falls back to `/dev/audio`. The control device is calculated by appending `"ctl"` to the base audio device.

35.1.1 Audio Device Objects

The audio device objects are returned by `open()` define the following methods (except `control` objects which only provide `getinfo()`, `setinfo()`, `fileno()`, and `drain()`):

close()

This method explicitly closes the device. It is useful in situations where deleting the object does not immediately close it since there are other references to it. A closed device should not be used again.

fileno()

Returns the file descriptor associated with the device. This can be used to set up `SIGPOLL` notification, as described below.

drain()

This method waits until all pending output is processed and then returns. Calling this method is often not necessary: destroying the object will automatically close the audio device and this will do an implicit drain.

flush()

This method discards all pending output. It can be used to avoid the slow response to a user's stop request (due to buffering of up to one second of sound).

getinfo()

This method retrieves status information like input and output volume, etc. and returns it in the form of an audio status object. This object has no methods but it contains a number of attributes describing the current device status. The names and meanings of the attributes are described in `<sun/audioio.h>` and in the *audio(7I)* manual page. Member names are slightly different from their C counterparts: a status object is only a single structure. Members of the `play` substructure have `'o_'` prepended to their name and members of the `record` structure have `'i_'`. So, the C member `play.sample_rate` is accessed as `o_sample_rate`, `record.gain` as `i_gain` and `monitor_gain` plainly as `monitor_gain`.

ibufcount()

This method returns the number of samples that are buffered on the recording side, i.e. the program will not block on a `read()` call of so many samples.

obufcount()

This method returns the number of samples buffered on the playback side. Unfortunately, this number cannot be used to determine a number of samples that can be written without blocking since the kernel output queue length seems to be variable.

read(size)

This method reads *size* samples from the audio input and returns them as a Python string. The function blocks until enough data is available.

setinfo(status)

This method sets the audio device status parameters. The *status* parameter is an device status object as returned by `getinfo()` and possibly modified by the program.

write(samples)

`write` is passed a Python string containing audio samples to be played. If there is enough buffer space free it will immediately return, otherwise it will block.

The audio device supports asynchronous notification of various events, through the SIGPOLL signal. Here's an example of how you might enable this in Python:

```
def handle_sigpoll(signum, frame):
    print 'I got a SIGPOLL update'

import fcntl, signal, STROPTS

signal.signal(signal.SIGPOLL, handle_sigpoll)
fcntl.ioctl(audio_obj.fileno(), STROPTS.I_SETSIG, STROPTS.S_MSG)
```

35.2 SUNAUDIODEV — Constants used with sunaudiodev

This is a companion module to `sunaudiodev` which defines useful symbolic constants like `MIN_GAIN`, `MAX_GAIN`, `SPEAKER`, etc. The names of the constants are the same names as used in the C include file `<sun/audioio.h>`, with the leading string `'AUDIO_'` stripped.

MS Windows Specific Services

This chapter describes modules that are only available on MS Windows platforms.

msilib	Creation of Microsoft Installer files, and CAB files.
msvcrt	Miscellaneous useful routines from the MS VC++ runtime.
_winreg	Routines and objects for manipulating the Windows registry.
winsound	Access to the sound-playing machinery for Windows.

36.1 msilib — Read and write Microsoft Installer files

New in version 2.5.

The `msilib` supports the creation of Microsoft Installer (`.msi`) files. Because these files often contain an embedded “cabinet” file (`.cab`), it also exposes an API to create CAB files. Support for reading `.cab` files is currently not implemented; read support for the `.msi` database is possible.

This package aims to provide complete access to all tables in an `.msi` file, therefore, it is a fairly low-level API. Two primary applications of this package are the `distutils` command `bdist_msi`, and the creation of Python installer package itself (although that currently uses a different version of `msilib`).

The package contents can be roughly split into four parts: low-level CAB routines, low-level MSI routines, higher-level MSI routines, and standard table structures.

FCICreate (*cabname, files*)

Create a new CAB file named *cabname*. *files* must be a list of tuples, each containing the name of the file on disk, and the name of the file inside the CAB file.

The files are added to the CAB file in the order they appear in the list. All files are added into a single CAB file, using the MSZIP compression algorithm.

Callbacks to Python for the various steps of MSI creation are currently not exposed.

UUIDCreate ()

Return the string representation of a new unique identifier. This wraps the Windows API functions `UuidCreate` and `UuidToString`.

OpenDatabase (*path, persist*)

Return a new database object by calling `MsiOpenDatabase`. *path* is the file name of the MSI file; *persist* can be one of the constants `MSIDBOPEN_CREATEDIRECT`, `MSIDBOPEN_CREATE`, `MSIDBOPEN_DIRECT`, `MSIDBOPEN_READONLY`, or `MSIDBOPEN_TRANSACT`, and may include the flag `MSIDBOPEN_PATCHFILE`. See the Microsoft documentation for the meaning of these flags; depending on the flags, an existing database is opened, or a new one created.

CreateRecord (*count*)

Return a new record object by calling `MSICreateRecord`. *count* is the number of fields of the record.

init_database (*name, schema, ProductName, ProductCode, ProductVersion, Manufacturer*)

Create and return a new database *name*, initialize it with *schema*, and set the properties *ProductName*, *ProductCode*, *ProductVersion*, and *Manufacturer*.

schema must be a module object containing *tables* and *_Validation_records* attributes; typically, *msilib.schema* should be used.

The database will contain just the schema and the validation records when this function returns.

add_data (*database, records*)

Add all *records* to *database*. *records* should be a list of tuples, each one containing all fields of a record according to the schema of the table. For optional fields, *None* can be passed.

Field values can be int or long numbers, strings, or instances of the *Binary* class.

class Binary (*filename*)

Represents entries in the *Binary* table; inserting such an object using *add_data* reads the file named *filename* into the table.

add_tables (*database, module*)

Add all table content from *module* to *database*. *module* must contain an attribute *tables* listing all tables for which content should be added, and one attribute per table that has the actual content.

This is typically used to install the sequence tables.

add_stream (*database, name, path*)

Add the file *path* into the *_Stream* table of *database*, with the stream name *name*.

gen_uuid ()

Return a new UUID, in the format that MSI typically requires (i.e. in curly braces, and with all hexdigits in upper-case).

See Also:

FCICreateFile

(<http://msdn.microsoft.com/library/default.asp?url=/library/en-us/devnotes/winprog/fcicreate.asp>)

UuidCreate

(<http://msdn.microsoft.com/library/default.asp?url=/library/en-us/rpc/rpc/uuidcreate.asp>)

UuidToString

(<http://msdn.microsoft.com/library/default.asp?url=/library/en-us/rpc/rpc/uuidtostring.asp>)

36.1.1 Database Objects

OpenView (*sql*)

Return a view object, by calling *MSIDatabaseOpenView*. *sql* is the SQL statement to execute.

Commit ()

Commit the changes pending in the current transaction, by calling *MSIDatabaseCommit*.

GetSummaryInformation (*count*)

Return a new summary information object, by calling *MsiGetSummaryInformation*. *count* is the maximum number of updated values.

See Also:

MSIDatabaseOpenView

(<http://msdn.microsoft.com/library/default.asp?url=/library/en-us/msi/setup/msidatabaseopenview.asp>)

MSIDatabaseCommit

(<http://msdn.microsoft.com/library/default.asp?url=/library/en-us/msi/setup/msidatabasecommit.asp>)

MsiGetSummaryInformation

(<http://msdn.microsoft.com/library/default.asp?url=/library/en-us/msi/setup/msigetsummaryinformation.asp>)

36.1.2 View Objects

Execute ([*params=None*])

Execute the SQL query of the view, through `MsiViewExecute`. *params* is an optional record describing actual values of the parameter tokens in the query.

GetColumnInfo (*kind*)

Return a record describing the columns of the view, through calling `MsiViewGetColumnInfo`. *kind* can be either `MSICOLINFO_NAMES` or `MSICOLINFO_TYPES`.

Fetch ()

Return a result record of the query, through calling `MsiViewFetch`.

Modify (*kind*, *data*)

Modify the view, by calling `MsiViewModify`. *kind* can be one of `MSIMODIFY_SEEK`, `MSIMODIFY_REFRESH`, `MSIMODIFY_INSERT`, `MSIMODIFY_UPDATE`, `MSIMODIFY_ASSIGN`, `MSIMODIFY_REPLACE`, `MSIMODIFY_MERGE`, `MSIMODIFY_DELETE`, `MSIMODIFY_INSERT_TEMPORARY`, `MSIMODIFY_VALIDATE`, `MSIMODIFY_VALIDATE_NEW`, `MSIMODIFY_VALIDATE_FIELD`, or `MSIMODIFY_VALIDATE_DELETE`.

data must be a record describing the new data.

Close ()

Close the view, through `MsiViewClose`.

See Also:

MsiViewExecute

(<http://msdn.microsoft.com/library/default.asp?url=/library/en-us/msi/setup/msiviewexecute.asp>)

MsiViewGetColumnInfo

(<http://msdn.microsoft.com/library/default.asp?url=/library/en-us/msi/setup/msiviewgetcolumninfo.asp>)

MsiViewFetch

(<http://msdn.microsoft.com/library/default.asp?url=/library/en-us/msi/setup/msiviewfetch.asp>)

MsiViewModify

(<http://msdn.microsoft.com/library/default.asp?url=/library/en-us/msi/setup/msiviewmodify.asp>)

MsiViewClose

(<http://msdn.microsoft.com/library/default.asp?url=/library/en-us/msi/setup/msiviewclose.asp>)

36.1.3 Summary Information Objects

GetProperty (*field*)

Return a property of the summary, through `MsiSummaryInfoGetProperty`. *field* is the name of the property, and can be one of the constants `PID_CODEPAGE`, `PID_TITLE`, `PID_SUBJECT`, `PID_AUTHOR`, `PID_KEYWORDS`, `PID_COMMENTS`, `PID_TEMPLATE`, `PID_LASTAUTHOR`, `PID_REVNUMBER`, `PID_LASTPRINTED`, `PID_CREATE_DTM`, `PID_LASTSAVE_DTM`, `PID_PAGECOUNT`, `PID_WORDCOUNT`, `PID_CHARCOUNT`, `PID_APPNAME`, or `PID_SECURITY`.

GetPropertyCount ()

Return the number of summary properties, through `MsiSummaryInfoGetPropertyCount`.

SetProperty (*field*, *value*)

Set a property through `MsiSummaryInfoSetProperty`. *field* can have the same values as in `GetProperty`, *value* is the new value of the property. Possible value types are integer and string.

Persist ()

Write the modified properties to the summary information stream, using `MsiSummaryInfoPersist`.

See Also:*MsiSummaryInfoGetProperty*

(<http://msdn.microsoft.com/library/default.asp?url=/library/en-us/msi/setup/msisummaryinfogetproperty.asp>)

MsiSummaryInfoGetPropertyCount

(<http://msdn.microsoft.com/library/default.asp?url=/library/en-us/msi/setup/msisummaryinfogetpropertycount.asp>)

MsiSummaryInfoSetProperty

(<http://msdn.microsoft.com/library/default.asp?url=/library/en-us/msi/setup/msisummaryinfosetProperty.asp>)

MsiSummaryInfoPersist

(<http://msdn.microsoft.com/library/default.asp?url=/library/en-us/msi/setup/msisummaryinfopersist.asp>)

36.1.4 Record Objects

GetFieldCount ()

Return the number of fields of the record, through `MsiRecordGetFieldCount`.

SetString (field, value)

Set *field* to *value* through `MsiRecordSetString`. *field* must be an integer; *value* a string.

SetStream (field, value)

Set *field* to the contents of the file named *value*, through `MsiRecordSetStream`. *field* must be an integer; *value* a string.

SetInteger (field, value)

Set *field* to *value* through `MsiRecordSetInteger`. Both *field* and *value* must be an integer.

ClearData ()

Set all fields of the record to 0, through `MsiRecordClearData`.

See Also:*MsiRecordGetFieldCount*

(<http://msdn.microsoft.com/library/default.asp?url=/library/en-us/msi/setup/msirecordgetfieldcount.asp>)

MsiRecordSetString

(<http://msdn.microsoft.com/library/default.asp?url=/library/en-us/msi/setup/msirecordsetstring.asp>)

MsiRecordSetStream

(<http://msdn.microsoft.com/library/default.asp?url=/library/en-us/msi/setup/msirecordsetstream.asp>)

MsiRecordSetInteger

(<http://msdn.microsoft.com/library/default.asp?url=/library/en-us/msi/setup/msirecordsetinteger.asp>)

MsiRecordClear

(<http://msdn.microsoft.com/library/default.asp?url=/library/en-us/msi/setup/msirecordclear.asp>)

36.1.5 Errors

All wrappers around MSI functions raise `MsiError`; the string inside the exception will contain more detail.

36.1.6 CAB Objects

class CAB (name)

The class `CAB` represents a CAB file. During MSI construction, files will be added simultaneously to the `Files`

table, and to a CAB file. Then, when all files have been added, the CAB file can be written, then added to the MSI file.

name is the name of the CAB file in the MSI file.

append (*full*, *logical*)

Add the file with the pathname *full* to the CAB file, under the name *logical*. If there is already a file named *logical*, a new file name is created.

Return the index of the file in the CAB file, and the new name of the file inside the CAB file.

append (*database*)

Generate a CAB file, add it as a stream to the MSI file, put it into the `Media` table, and remove the generated file from the disk.

36.1.7 Directory Objects

class Directory (*database*, *cab*, *basedir*, *physical*, *logical*, *default*, *component*, [*componentflags*])

Create a new directory in the Directory table. There is a current component at each point in time for the directory, which is either explicitly created through `start_component`, or implicitly when files are added for the first time. Files are added into the current component, and into the cab file. To create a directory, a base directory object needs to be specified (can be `None`), the path to the physical directory, and a logical directory name. *default* specifies the DefaultDir slot in the directory table. *componentflags* specifies the default flags that new components get.

start_component ([*component*[, *feature*[, *flags*[, *keyfile*[, *uuid*]]]])

Add an entry to the Component table, and make this component the current component for this directory. If no component name is given, the directory name is used. If no *feature* is given, the current feature is used. If no *flags* are given, the directory's default flags are used. If no *keyfile* is given, the KeyPath is left null in the Component table.

add_file (*file*[, *src*[, *version*[, *language*]]])

Add a file to the current component of the directory, starting a new one if there is no current component. By default, the file name in the source and the file table will be identical. If the *src* file is specified, it is interpreted relative to the current directory. Optionally, a *version* and a *language* can be specified for the entry in the File table.

glob (*pattern*[, *exclude*])

Add a list of files to the current component as specified in the glob pattern. Individual files can be excluded in the *exclude* list.

remove_pyc ()

Remove `.pyc/.pyo` files on uninstall.

See Also:

Directory Table

(http://msdn.microsoft.com/library/en-us/msi/setup/directory_table.asp)

File Table

(http://msdn.microsoft.com/library/en-us/msi/setup/file_table.asp)

Component Table

(http://msdn.microsoft.com/library/en-us/msi/setup/component_table.asp)

FeatureComponents Table

(http://msdn.microsoft.com/library/en-us/msi/setup/featurecomponents_table.asp)

36.1.8 Features

class Feature (*database, id, title, desc, display* [, *level=1* [, *parent* [, *directory* [, *attributes=0*]]]])

Add a new record to the `Feature` table, using the values *id*, *parent.id*, *title*, *desc*, *display*, *level*, *directory*, and *attributes*. The resulting feature object can be passed to the `start_component` method of `Directory`.

set_current ()

Make this feature the current feature of `msilib`. New components are automatically added to the default feature, unless a feature is explicitly specified.

See Also:

Feature Table

(http://msdn.microsoft.com/library/en-us/msi/setup/feature_table.asp)

36.1.9 GUI classes

`msilib` provides several classes that wrap the GUI tables in an MSI database. However, no standard user interface is provided; use `bdist_msi` to create MSI files with a user-interface for installing Python packages.

class Control (*dlg, name*)

Base class of the dialog controls. *dlg* is the dialog object the control belongs to, and *name* is the control's name.

event (*event, argument* [, *condition = "1"* [, *ordering*]])

Make an entry into the `ControlEvent` table for this control.

mapping (*event, attribute*)

Make an entry into the `EventMapping` table for this control.

condition (*action, condition*)

Make an entry into the `ControlCondition` table for this control.

class RadioButtonGroup (*dlg, name, property*)

Create a radio button control named *name*. *property* is the installer property that gets set when a radio button is selected.

add (*name, x, y, width, height, text* [, *value*])

Add a radio button named *name* to the group, at the coordinates *x*, *y*, *width*, *height*, and with the label *text*. If *value* is omitted, it defaults to *name*.

class Dialog (*db, name, x, y, w, h, attr, title, first, default, cancel*)

Return a new `Dialog` object. An entry in the `Dialog` table is made, with the specified coordinates, dialog attributes, title, name of the first, default, and cancel controls.

control (*name, type, x, y, width, height, attributes, property, text, control_next, help*)

Return a new `Control` object. An entry in the `Control` table is made with the specified parameters.

This is a generic method; for specific types, specialized methods are provided.

text (*name, x, y, width, height, attributes, text*)

Add and return a `Text` control.

bitmap (*name, x, y, width, height, text*)

Add and return a `Bitmap` control.

line (*name, x, y, width, height*)

Add and return a `Line` control.

pushbutton (*name, x, y, width, height, attributes, text, next_control*)

Add and return a `PushButton` control.

radiogroup (*name, x, y, width, height, attributes, property, text, next_control*)

Add and return a `RadioButtonGroup` control.

checkbox (*name, x, y, width, height, attributes, property, text, next_control*)

Add and return a `CheckBox` control.

See Also:

Dialog Table

(http://msdn.microsoft.com/library/en-us/msi/setup/dialog_table.asp)

Control Table

(http://msdn.microsoft.com/library/en-us/msi/setup/control_table.asp)

Control Types

(<http://msdn.microsoft.com/library/en-us/msi/setup/controls.asp>)

ControlCondition Table

(http://msdn.microsoft.com/library/en-us/msi/setup/controlcondition_table.asp)

ControlEvents Table

(http://msdn.microsoft.com/library/en-us/msi/setup/controlevent_table.asp)

EventMapping Table

(http://msdn.microsoft.com/library/en-us/msi/setup/eventmapping_table.asp)

RadioButton Table

(http://msdn.microsoft.com/library/en-us/msi/setup/radiobutton_table.asp)

36.1.10 Precomputed tables

`msilib` provides a few subpackages that contain only schema and table definitions. Currently, these definitions are based on MSI version 2.0.

schema

This is the standard MSI schema for MSI 2.0, with the *tables* variable providing a list of table definitions, and *_Validation_records* providing the data for MSI validation.

sequence

This module contains table contents for the standard sequence tables: *AdminExecuteSequence*, *AdminUISequence*, *AdvtExecuteSequence*, *InstallExecuteSequence*, and *InstallUISequence*.

text

This module contains definitions for the *UIText* and *ActionText* tables, for the standard installer actions.

36.2 `msvcrt` – Useful routines from the MS VC++ runtime

These functions provide access to some useful capabilities on Windows platforms. Some higher-level modules use these functions to build the Windows implementations of their services. For example, the `getpass` module uses this in the implementation of the `getpass()` function.

Further documentation on these functions can be found in the Platform API documentation.

36.2.1 File Operations

locking (*fd, mode, nbytes*)

Lock part of a file based on file descriptor *fd* from the C runtime. Raises `IOError` on failure. The locked region of the file extends from the current file position for *nbytes* bytes, and may continue beyond the end of the

file. *mode* must be one of the `LK_*` constants listed below. Multiple regions in a file may be locked at the same time, but may not overlap. Adjacent regions are not merged; they must be unlocked individually.

`LK_LOCK`

`LK_RLCK`

Locks the specified bytes. If the bytes cannot be locked, the program immediately tries again after 1 second. If, after 10 attempts, the bytes cannot be locked, `IOError` is raised.

`LK_NBLCK`

`LK_NBLCK`

Locks the specified bytes. If the bytes cannot be locked, `IOError` is raised.

`LK_UNLCK`

Unlocks the specified bytes, which must have been previously locked.

`setmode (fd, flags)`

Set the line-end translation mode for the file descriptor *fd*. To set it to text mode, *flags* should be `os.O_TEXT`; for binary, it should be `os.O_BINARY`.

`open_osfhandle (handle, flags)`

Create a C runtime file descriptor from the file handle *handle*. The *flags* parameter should be a bit-wise OR of `os.O_APPEND`, `os.O_RDONLY`, and `os.O_TEXT`. The returned file descriptor may be used as a parameter to `os.fdopen()` to create a file object.

`get_osfhandle (fd)`

Return the file handle for the file descriptor *fd*. Raises `IOError` if *fd* is not recognized.

36.2.2 Console I/O

`kbhit ()`

Return true if a keypress is waiting to be read.

`getch ()`

Read a keypress and return the resulting character. Nothing is echoed to the console. This call will block if a keypress is not already available, but will not wait for `Enter` to be pressed. If the pressed key was a special function key, this will return `'\000'` or `'\xe0'`; the next call will return the keycode. The `Control-C` keypress cannot be read with this function.

`getche ()`

Similar to `getch()`, but the keypress will be echoed if it represents a printable character.

`putch (char)`

Print the character *char* to the console without buffering.

`ungetch (char)`

Cause the character *char* to be “pushed back” into the console buffer; it will be the next character read by `getch()` or `getche()`.

36.2.3 Other Functions

`heapmin ()`

Force the `malloc()` heap to clean itself up and return unused blocks to the operating system. This only works on Windows NT. On failure, this raises `IOError`.

36.3 `_winreg` – Windows registry access

New in version 2.0.

These functions expose the Windows registry API to Python. Instead of using an integer as the registry handle, a handle object is used to ensure that the handles are closed correctly, even if the programmer neglects to explicitly close them.

This module exposes a very low-level interface to the Windows registry; it is expected that in the future a new `winreg` module will be created offering a higher-level interface to the registry API.

This module offers the following functions:

CloseKey (*hkey*)

Closes a previously opened registry key. The *hkey* argument specifies a previously opened key.

Note that if *hkey* is not closed using this method (or via `handle.Close()`), it is closed when the *hkey* object is destroyed by Python.

ConnectRegistry (*computer_name*, *key*)

Establishes a connection to a predefined registry handle on another computer, and returns a *handle object*

computer_name is the name of the remote computer, of the form `r"\\computername"`. If `None`, the local computer is used.

key is the predefined handle to connect to.

The return value is the handle of the opened key. If the function fails, an `EnvironmentError` exception is raised.

CreateKey (*key*, *sub_key*)

Creates or opens the specified key, returning a *handle object*

key is an already open key, or one of the predefined `HKEY_*` constants.

sub_key is a string that names the key this method opens or creates.

If *key* is one of the predefined keys, *sub_key* may be `None`. In that case, the handle returned is the same key handle passed in to the function.

If the key already exists, this function opens the existing key.

The return value is the handle of the opened key. If the function fails, an `EnvironmentError` exception is raised.

DeleteKey (*key*, *sub_key*)

Deletes the specified key.

key is an already open key, or any one of the predefined `HKEY_*` constants.

sub_key is a string that must be a subkey of the key identified by the *key* parameter. This value must not be `None`, and the key may not have subkeys.

This method can not delete keys with subkeys.

If the method succeeds, the entire key, including all of its values, is removed. If the method fails, an `EnvironmentError` exception is raised.

DeleteValue (*key*, *value*)

Removes a named value from a registry key.

key is an already open key, or one of the predefined `HKEY_*` constants.

value is a string that identifies the value to remove.

EnumKey (*key*, *index*)

Enumerates subkeys of an open registry key, returning a string.

key is an already open key, or any one of the predefined `HKEY_*` constants.

index is an integer that identifies the index of the key to retrieve.

The function retrieves the name of one subkey each time it is called. It is typically called repeatedly until an `EnvironmentError` exception is raised, indicating, no more values are available.

EnumValue (*key*, *index*)

Enumerates values of an open registry key, returning a tuple.

key is an already open key, or any one of the predefined HKEY_* constants.

index is an integer that identifies the index of the value to retrieve.

The function retrieves the name of one subkey each time it is called. It is typically called repeatedly, until an `EnvironmentError` exception is raised, indicating no more values.

The result is a tuple of 3 items:

Index	Meaning
0	A string that identifies the value name
1	An object that holds the value data, and whose type depends on the underlying registry type
2	An integer that identifies the type of the value data

FlushKey (*key*)

Writes all the attributes of a key to the registry.

key is an already open key, or one of the predefined HKEY_* constants.

It is not necessary to call `RegFlushKey` to change a key. Registry changes are flushed to disk by the registry using its lazy flusher. Registry changes are also flushed to disk at system shutdown. Unlike `CloseKey()`, the `FlushKey()` method returns only when all the data has been written to the registry. An application should only call `FlushKey()` if it requires absolute certainty that registry changes are on disk.

If you don't know whether a FlushKey() call is required, it probably isn't.

RegLoadKey (*key*, *sub_key*, *file_name*)

Creates a subkey under the specified key and stores registration information from a specified file into that subkey.

key is an already open key, or any of the predefined HKEY_* constants.

sub_key is a string that identifies the sub_key to load.

file_name is the name of the file to load registry data from. This file must have been created with the `SaveKey()` function. Under the file allocation table (FAT) file system, the filename may not have an extension.

A call to `LoadKey()` fails if the calling process does not have the `SE_RESTORE_PRIVILEGE` privilege. Note that privileges are different than permissions - see the Win32 documentation for more details.

If *key* is a handle returned by `ConnectRegistry()`, then the path specified in *fileName* is relative to the remote computer.

The Win32 documentation implies *key* must be in the HKEY_USER or HKEY_LOCAL_MACHINE tree. This may or may not be true.

OpenKey (*key*, *sub_key* [, *res* = 0] [, *sam* = KEY_READ])

Opens the specified key, returning a *handle object*

key is an already open key, or any one of the predefined HKEY_* constants.

sub_key is a string that identifies the sub_key to open.

res is a reserved integer, and must be zero. The default is zero.

sam is an integer that specifies an access mask that describes the desired security access for the key. Default is KEY_READ

The result is a new handle to the specified key.

If the function fails, `EnvironmentError` is raised.

OpenKeyEx ()

The functionality of `OpenKeyEx()` is provided via `OpenKey()`, by the use of default arguments.

QueryInfoKey (*key*)

Returns information about a key, as a tuple.

key is an already open key, or one of the predefined `HKEY_*` constants.

The result is a tuple of 3 items:

Index	Meaning
0	An integer giving the number of sub keys this key has.
1	An integer giving the number of values this key has.
2	A long integer giving when the key was last modified (if available) as 100's of nanoseconds since Jan 1, 1600.

QueryValue (*key*, *sub_key*)

Retrieves the unnamed value for a key, as a string

key is an already open key, or one of the predefined `HKEY_*` constants.

sub_key is a string that holds the name of the subkey with which the value is associated. If this parameter is `None` or empty, the function retrieves the value set by the `SetValue()` method for the key identified by *key*.

Values in the registry have name, type, and data components. This method retrieves the data for a key's first value that has a `NULL` name. But the underlying API call doesn't return the type, *Lame Lame Lame*, **DO NOT USE THIS!!!**

QueryValueEx (*key*, *value_name*)

Retrieves the type and data for a specified value name associated with an open registry key.

key is an already open key, or one of the predefined `HKEY_*` constants.

value_name is a string indicating the value to query.

The result is a tuple of 2 items:

Index	Meaning
0	The value of the registry item.
1	An integer giving the registry type for this value.

SaveKey (*key*, *file_name*)

Saves the specified key, and all its subkeys to the specified file.

key is an already open key, or one of the predefined `HKEY_*` constants.

file_name is the name of the file to save registry data to. This file cannot already exist. If this filename includes an extension, it cannot be used on file allocation table (FAT) file systems by the `LoadKey()`, `ReplaceKey()` or `RestoreKey()` methods.

If *key* represents a key on a remote computer, the path described by *file_name* is relative to the remote computer. The caller of this method must possess the `SeBackupPrivilege` security privilege. Note that privileges are different than permissions - see the Win32 documentation for more details.

This function passes `NULL` for *security_attributes* to the API.

SetValue (*key*, *sub_key*, *type*, *value*)

Associates a value with a specified key.

key is an already open key, or one of the predefined `HKEY_*` constants.

sub_key is a string that names the subkey with which the value is associated.

type is an integer that specifies the type of the data. Currently this must be `REG_SZ`, meaning only strings are supported. Use the `SetValueEx()` function for support for other data types.

value is a string that specifies the new value.

If the key specified by the *sub_key* parameter does not exist, the `SetValue` function creates it.

Value lengths are limited by available memory. Long values (more than 2048 bytes) should be stored as files with the filenames stored in the configuration registry. This helps the registry perform efficiently.

The key identified by the *key* parameter must have been opened with `KEY_SET_VALUE` access.

SetValueEx (*key*, *value_name*, *reserved*, *type*, *value*)

Stores data in the value field of an open registry key.

key is an already open key, or one of the predefined `HKEY_*` constants.

value_name is a string that names the subkey with which the value is associated.

type is an integer that specifies the type of the data. This should be one of the following constants defined in this module:

Constant	Meaning
<code>REG_BINARY</code>	Binary data in any form.
<code>REG_DWORD</code>	A 32-bit number.
<code>REG_DWORD_LITTLE_ENDIAN</code>	A 32-bit number in little-endian format.
<code>REG_DWORD_BIG_ENDIAN</code>	A 32-bit number in big-endian format.
<code>REG_EXPAND_SZ</code>	Null-terminated string containing references to environment variables ('%PATH%').
<code>REG_LINK</code>	A Unicode symbolic link.
<code>REG_MULTI_SZ</code>	A sequence of null-terminated strings, terminated by two null characters. (Python handles this termination automatically.)
<code>REG_NONE</code>	No defined value type.
<code>REG_RESOURCE_LIST</code>	A device-driver resource list.
<code>REG_SZ</code>	A null-terminated string.

reserved can be anything - zero is always passed to the API.

value is a string that specifies the new value.

This method can also set additional value and type information for the specified key. The key identified by the *key* parameter must have been opened with `KEY_SET_VALUE` access.

To open the key, use the `CreateKeyEx()` or `OpenKey()` methods.

Value lengths are limited by available memory. Long values (more than 2048 bytes) should be stored as files with the filenames stored in the configuration registry. This helps the registry perform efficiently.

36.3.1 Registry Handle Objects

This object wraps a Windows `HKEY` object, automatically closing it when the object is destroyed. To guarantee cleanup, you can call either the `Close()` method on the object, or the `CloseKey()` function.

All registry functions in this module return one of these objects.

All registry functions in this module which accept a handle object also accept an integer, however, use of the handle object is encouraged.

Handle objects provide semantics for `__nonzero__()` - thus

```
if handle:
    print "Yes"
```

will print `Yes` if the handle is currently valid (has not been closed or detached).

The object also support comparison semantics, so handle objects will compare true if they both reference the same underlying Windows handle value.

Handle objects can be converted to an integer (e.g., using the builtin `int()` function), in which case the underlying Windows handle value is returned. You can also use the `Detach()` method to return the integer handle, and also disconnect the Windows handle from the handle object.

Close ()

Closes the underlying Windows handle.

If the handle is already closed, no error is raised.

Detach ()

Detaches the Windows handle from the handle object.

The result is an integer (or long on 64 bit Windows) that holds the value of the handle before it is detached. If the handle is already detached or closed, this will return zero.

After calling this function, the handle is effectively invalidated, but the handle is not closed. You would call this function when you need the underlying Win32 handle to exist beyond the lifetime of the handle object.

36.4 winsound — Sound-playing interface for Windows

New in version 1.5.2.

The `winsound` module provides access to the basic sound-playing machinery provided by Windows platforms. It includes functions and several constants.

Beep (*frequency, duration*)

Beep the PC's speaker. The *frequency* parameter specifies frequency, in hertz, of the sound, and must be in the range 37 through 32,767. The *duration* parameter specifies the number of milliseconds the sound should last. If the system is not able to beep the speaker, `RuntimeError` is raised. **Note:** Under Windows 95 and 98, the Windows `Beep ()` function exists but is useless (it ignores its arguments). In that case Python simulates it via direct port manipulation (added in version 2.1). It's unknown whether that will work on all systems. New in version 1.6.

PlaySound (*sound, flags*)

Call the underlying `PlaySound ()` function from the Platform API. The *sound* parameter may be a filename, audio data as a string, or `None`. Its interpretation depends on the value of *flags*, which can be a bit-wise ORed combination of the constants described below. If the system indicates an error, `RuntimeError` is raised.

MessageBeep ([*type=MB_OK*])

Call the underlying `MessageBeep ()` function from the Platform API. This plays a sound as specified in the registry. The *type* argument specifies which sound to play; possible values are `-1`, `MB_ICONASTERISK`, `MB_ICONEXCLAMATION`, `MB_ICONHAND`, `MB_ICONQUESTION`, and `MB_OK`, all described below. The value `-1` produces a “simple beep”; this is the final fallback if a sound cannot be played otherwise. New in version 2.3.

SND_FILENAME

The *sound* parameter is the name of a WAV file. Do not use with `SND_ALIAS`.

SND_ALIAS

The *sound* parameter is a sound association name from the registry. If the registry contains no such name, play the system default sound unless `SND_NODEFAULT` is also specified. If no default sound is registered, raise `RuntimeError`. Do not use with `SND_FILENAME`.

All Win32 systems support at least the following; most systems support many more:

PlaySound () name	Corresponding Control Panel Sound name
'SystemAsterisk'	Asterisk
'SystemExclamation'	Exclamation
'SystemExit'	Exit Windows
'SystemHand'	Critical Stop
'SystemQuestion'	Question

For example:

```

import winsound
# Play Windows exit sound.
winsound.PlaySound("SystemExit", winsound.SND_ALIAS)

# Probably play Windows default sound, if any is registered (because
# "*" probably isn't the registered name of any sound).
winsound.PlaySound("*", winsound.SND_ALIAS)

```

SND_LOOP

Play the sound repeatedly. The `SND_ASYNC` flag must also be used to avoid blocking. Cannot be used with `SND_MEMORY`.

SND_MEMORY

The *sound* parameter to `PlaySound()` is a memory image of a WAV file, as a string.

Note: This module does not support playing from a memory image asynchronously, so a combination of this flag and `SND_ASYNC` will raise `RuntimeError`.

SND_PURGE

Stop playing all instances of the specified sound.

SND_ASYNC

Return immediately, allowing sounds to play asynchronously.

SND_NODEFAULT

If the specified sound cannot be found, do not play the system default sound.

SND_NOSTOP

Do not interrupt sounds currently playing.

SND_NOWAIT

Return immediately if the sound driver is busy.

MB_ICONASTERISK

Play the `SystemDefault` sound.

MB_ICONEXCLAMATION

Play the `SystemExclamation` sound.

MB_ICONHAND

Play the `SystemHand` sound.

MB_ICONQUESTION

Play the `SystemQuestion` sound.

MB_OK

Play the `SystemDefault` sound.

Undocumented Modules

Here's a quick listing of modules that are currently undocumented, but that should be documented. Feel free to contribute documentation for them! (Send via email to docs@python.org.)

The idea and original contents for this chapter were taken from a posting by Fredrik Lundh; the specific contents of this chapter have been substantially revised.

A.1 Frameworks

Frameworks tend to be harder to document, but are well worth the effort spent.

None at this time.

A.2 Miscellaneous useful utilities

Some of these are very old and/or not very robust; marked with “hmm.”

bdb — A generic Python debugger base class (used by `pdb`).

ihooks — Import hook support (for `rexec`; may become obsolete).

A.3 Platform specific modules

These modules are used to implement the `os.path` module, and are not documented beyond this mention. There's little need to document these.

ntpath — Implementation of `os.path` on Win32, Win64, WinCE, and OS/2 platforms.

posixpath — Implementation of `os.path` on POSIX.

bsddb185 — Backwards compatibility module for systems which still use the Berkeley DB 1.85 module. It is normally only available on certain BSD UNIX-based systems. It should never be used directly.

A.4 Multimedia

audiodev — Platform-independent API for playing audio data.

linuxaudiodev — Play audio data on the Linux audio device. Replaced in Python 2.3 by the `ossaudiodev` module.

sunaudio — Interpret Sun audio headers (may become obsolete or a tool/demo).

toaiff — Convert “arbitrary” sound files to AIFF files; should probably become a tool or demo. Requires the external program **sox**.

A.5 Obsolete

These modules are not normally available for import; additional work must be done to make them available.

These extension modules written in C are not built by default. Under UNIX, these must be enabled by uncommenting the appropriate lines in ‘Modules/Setup’ in the build tree and either rebuilding Python if the modules are statically linked, or building and installing the shared object if using dynamically-loaded extensions.

timing — Measure time intervals to high resolution (use `time.clock()` instead).

A.6 SGI-specific Extension modules

The following are SGI specific, and may be out of touch with the current version of reality.

c1 — Interface to the SGI compression library.

sv — Interface to the “simple video” board on SGI Indigo (obsolete hardware).

Reporting Bugs

Python is a mature programming language which has established a reputation for stability. In order to maintain this reputation, the developers would like to know of any deficiencies you find in Python or its documentation.

Before submitting a report, you will be required to log into SourceForge; this will make it possible for the developers to contact you for additional information if needed. It is not possible to submit a bug report anonymously.

All bug reports should be submitted via the Python Bug Tracker at (<http://bugs.python.org>). The bug tracker offers a Web form which allows pertinent information to be entered and submitted to the developers.

The first step in filing a report is to determine whether the problem has already been reported. The advantage in doing so, aside from saving the developers time, is that you learn what has been done to fix it; it may be that the problem has already been fixed for the next release, or additional information is needed (in which case you are welcome to provide it if you can!). To do this, search the bug database using the search box on the top side of the page.

If the problem you're reporting is not already in the bug tracker, go back to the Python Bug Tracker. Select the "Create new" link at the left of the page to open the bug reporting form.

The submission form has a number of fields. The only fields that are required are the "Title" and "Type" fields. For the title, enter a *very* short description of the problem; less than ten words is good. In the "Change Note" field, describe the problem in detail, including what you expected to happen and what did happen. Be sure to include the version of Python you used, whether any extension modules were involved, and what hardware and software platform you were using (including version information as appropriate).

The only other field that you may want to set is the "Components" field, which allows you to place the bug report into broad categories (such as "Documentation" or "Library").

Each bug report will be assigned to a developer who will determine what needs to be done to correct the problem. You will receive an update each time action is taken on the bug.

See Also:

How to Report Bugs Effectively

(<http://www.mice.cs.ucl.ac.uk/multimedia/software/documentation/ReportingBugs.html>)

Article which goes into some detail about how to create a useful bug report. This describes what kind of information is useful and why it is useful.

Bug Writing Guidelines

(<http://www.mozilla.org/quality/bug-writing-guidelines.html>)

Information about writing a good bug report. Some of this is specific to the Mozilla project, but describes general good practices.

History and License

C.1 History of the software

Python was created in the early 1990s by Guido van Rossum at Stichting Mathematisch Centrum (CWI, see <http://www.cwi.nl/>) in the Netherlands as a successor of a language called ABC. Guido remains Python's principal author, although it includes many contributions from others.

In 1995, Guido continued his work on Python at the Corporation for National Research Initiatives (CNRI, see <http://www.cnri.reston.va.us/>) in Reston, Virginia where he released several versions of the software.

In May 2000, Guido and the Python core development team moved to BeOpen.com to form the BeOpen PythonLabs team. In October of the same year, the PythonLabs team moved to Digital Creations (now Zope Corporation; see <http://www.zope.com/>). In 2001, the Python Software Foundation (PSF, see <http://www.python.org/psf/>) was formed, a non-profit organization created specifically to own Python-related Intellectual Property. Zope Corporation is a sponsoring member of the PSF.

All Python releases are Open Source (see <http://www.opensource.org/> for the Open Source Definition). Historically, most, but not all, Python releases have also been GPL-compatible; the table below summarizes the various releases.

Release	Derived from	Year	Owner	GPL compatible?
0.9.0 thru 1.2	n/a	1991-1995	CWI	yes
1.3 thru 1.5.2	1.2	1995-1999	CNRI	yes
1.6	1.5.2	2000	CNRI	no
2.0	1.6	2000	BeOpen.com	no
1.6.1	1.6	2001	CNRI	no
2.1	2.0+1.6.1	2001	PSF	no
2.0.1	2.0+1.6.1	2001	PSF	yes
2.1.1	2.1+2.0.1	2001	PSF	yes
2.2	2.1.1	2001	PSF	yes
2.1.2	2.1.1	2002	PSF	yes
2.1.3	2.1.2	2002	PSF	yes
2.2.1	2.2	2002	PSF	yes
2.2.2	2.2.1	2002	PSF	yes
2.2.3	2.2.2	2002-2003	PSF	yes
2.3	2.2.2	2002-2003	PSF	yes
2.3.1	2.3	2002-2003	PSF	yes
2.3.2	2.3.1	2003	PSF	yes
2.3.3	2.3.2	2003	PSF	yes
2.3.4	2.3.3	2004	PSF	yes
2.3.5	2.3.4	2005	PSF	yes
2.4	2.3	2004	PSF	yes
2.4.1	2.4	2005	PSF	yes
2.4.2	2.4.1	2005	PSF	yes
2.4.3	2.4.2	2006	PSF	yes
2.4.4	2.4.3	2006	PSF	yes
2.5	2.4	2006	PSF	yes
2.5.1	2.5	2007	PSF	yes
2.5.2	2.5.1	2008	PSF	yes

Note: GPL-compatible doesn't mean that we're distributing Python under the GPL. All Python licenses, unlike the GPL, let you distribute a modified version without making your changes open source. The GPL-compatible licenses make it possible to combine Python with other software that is released under the GPL; the others don't.

Thanks to the many outside volunteers who have worked under Guido's direction to make these releases possible.

C.2 Terms and conditions for accessing or otherwise using Python

PSF LICENSE AGREEMENT FOR PYTHON 2.5.2

1. This LICENSE AGREEMENT is between the Python Software Foundation ("PSF"), and the Individual or Organization ("Licensee") accessing and otherwise using Python 2.5.2 software in source or binary form and its associated documentation.
2. Subject to the terms and conditions of this License Agreement, PSF hereby grants Licensee a nonexclusive, royalty-free, world-wide license to reproduce, analyze, test, perform and/or display publicly, prepare derivative works, distribute, and otherwise use Python 2.5.2 alone or in any derivative version, provided, however, that PSF's License Agreement and PSF's notice of copyright, i.e., "Copyright © 2001-2008 Python Software Foundation; All Rights Reserved" are retained in Python 2.5.2 alone or in any derivative version prepared by Licensee.
3. In the event Licensee prepares a derivative work that is based on or incorporates Python 2.5.2 or any part thereof, and wants to make the derivative work available to others as provided herein, then Licensee hereby agrees to include in any such work a brief summary of the changes made to Python 2.5.2.

4. PSF is making Python 2.5.2 available to Licensee on an “AS IS” basis. PSF MAKES NO REPRESENTATIONS OR WARRANTIES, EXPRESS OR IMPLIED. BY WAY OF EXAMPLE, BUT NOT LIMITATION, PSF MAKES NO AND DISCLAIMS ANY REPRESENTATION OR WARRANTY OF MERCHANTABILITY OR FITNESS FOR ANY PARTICULAR PURPOSE OR THAT THE USE OF PYTHON 2.5.2 WILL NOT INFRINGE ANY THIRD PARTY RIGHTS.
5. PSF SHALL NOT BE LIABLE TO LICENSEE OR ANY OTHER USERS OF PYTHON 2.5.2 FOR ANY INCIDENTAL, SPECIAL, OR CONSEQUENTIAL DAMAGES OR LOSS AS A RESULT OF MODIFYING, DISTRIBUTING, OR OTHERWISE USING PYTHON 2.5.2, OR ANY DERIVATIVE THEREOF, EVEN IF ADVISED OF THE POSSIBILITY THEREOF.
6. This License Agreement will automatically terminate upon a material breach of its terms and conditions.
7. Nothing in this License Agreement shall be deemed to create any relationship of agency, partnership, or joint venture between PSF and Licensee. This License Agreement does not grant permission to use PSF trademarks or trade name in a trademark sense to endorse or promote products or services of Licensee, or any third party.
8. By copying, installing or otherwise using Python 2.5.2, Licensee agrees to be bound by the terms and conditions of this License Agreement.

BEOPEN.COM LICENSE AGREEMENT FOR PYTHON 2.0
BEOPEN PYTHON OPEN SOURCE LICENSE AGREEMENT VERSION 1

1. This LICENSE AGREEMENT is between BeOpen.com (“BeOpen”), having an office at 160 Saratoga Avenue, Santa Clara, CA 95051, and the Individual or Organization (“Licensee”) accessing and otherwise using this software in source or binary form and its associated documentation (“the Software”).
2. Subject to the terms and conditions of this BeOpen Python License Agreement, BeOpen hereby grants Licensee a non-exclusive, royalty-free, world-wide license to reproduce, analyze, test, perform and/or display publicly, prepare derivative works, distribute, and otherwise use the Software alone or in any derivative version, provided, however, that the BeOpen Python License is retained in the Software, alone or in any derivative version prepared by Licensee.
3. BeOpen is making the Software available to Licensee on an “AS IS” basis. BEOPEN MAKES NO REPRESENTATIONS OR WARRANTIES, EXPRESS OR IMPLIED. BY WAY OF EXAMPLE, BUT NOT LIMITATION, BEOPEN MAKES NO AND DISCLAIMS ANY REPRESENTATION OR WARRANTY OF MERCHANTABILITY OR FITNESS FOR ANY PARTICULAR PURPOSE OR THAT THE USE OF THE SOFTWARE WILL NOT INFRINGE ANY THIRD PARTY RIGHTS.
4. BEOPEN SHALL NOT BE LIABLE TO LICENSEE OR ANY OTHER USERS OF THE SOFTWARE FOR ANY INCIDENTAL, SPECIAL, OR CONSEQUENTIAL DAMAGES OR LOSS AS A RESULT OF USING, MODIFYING OR DISTRIBUTING THE SOFTWARE, OR ANY DERIVATIVE THEREOF, EVEN IF ADVISED OF THE POSSIBILITY THEREOF.
5. This License Agreement will automatically terminate upon a material breach of its terms and conditions.
6. This License Agreement shall be governed by and interpreted in all respects by the law of the State of California, excluding conflict of law provisions. Nothing in this License Agreement shall be deemed to create any relationship of agency, partnership, or joint venture between BeOpen and Licensee. This License Agreement does not grant permission to use BeOpen trademarks or trade names in a trademark sense to endorse or promote products or services of Licensee, or any third party. As an exception, the “BeOpen Python” logos available at <http://www.pythonlabs.com/logos.html> may be used according to the permissions granted on that web page.
7. By copying, installing or otherwise using the software, Licensee agrees to be bound by the terms and conditions of this License Agreement.

CNRI LICENSE AGREEMENT FOR PYTHON 1.6.1

1. This LICENSE AGREEMENT is between the Corporation for National Research Initiatives, having an office at 1895 Preston White Drive, Reston, VA 20191 (“CNRI”), and the Individual or Organization (“Licensee”) accessing and otherwise using Python 1.6.1 software in source or binary form and its associated documentation.
2. Subject to the terms and conditions of this License Agreement, CNRI hereby grants Licensee a nonexclusive, royalty-free, world-wide license to reproduce, analyze, test, perform and/or display publicly, prepare derivative works, distribute, and otherwise use Python 1.6.1 alone or in any derivative version, provided, however, that CNRI’s License Agreement and CNRI’s notice of copyright, i.e., “Copyright © 1995-2001 Corporation for National Research Initiatives; All Rights Reserved” are retained in Python 1.6.1 alone or in any derivative version prepared by Licensee. Alternately, in lieu of CNRI’s License Agreement, Licensee may substitute the following text (omitting the quotes): “Python 1.6.1 is made available subject to the terms and conditions in CNRI’s License Agreement. This Agreement together with Python 1.6.1 may be located on the Internet using the following unique, persistent identifier (known as a handle): 1895.22/1013. This Agreement may also be obtained from a proxy server on the Internet using the following URL: <http://hdl.handle.net/1895.22/1013>.”
3. In the event Licensee prepares a derivative work that is based on or incorporates Python 1.6.1 or any part thereof, and wants to make the derivative work available to others as provided herein, then Licensee hereby agrees to include in any such work a brief summary of the changes made to Python 1.6.1.
4. CNRI is making Python 1.6.1 available to Licensee on an “AS IS” basis. CNRI MAKES NO REPRESENTATIONS OR WARRANTIES, EXPRESS OR IMPLIED. BY WAY OF EXAMPLE, BUT NOT LIMITATION, CNRI MAKES NO AND DISCLAIMS ANY REPRESENTATION OR WARRANTY OF MERCHANTABILITY OR FITNESS FOR ANY PARTICULAR PURPOSE OR THAT THE USE OF PYTHON 1.6.1 WILL NOT INFRINGE ANY THIRD PARTY RIGHTS.
5. CNRI SHALL NOT BE LIABLE TO LICENSEE OR ANY OTHER USERS OF PYTHON 1.6.1 FOR ANY INCIDENTAL, SPECIAL, OR CONSEQUENTIAL DAMAGES OR LOSS AS A RESULT OF MODIFYING, DISTRIBUTING, OR OTHERWISE USING PYTHON 1.6.1, OR ANY DERIVATIVE THEREOF, EVEN IF ADVISED OF THE POSSIBILITY THEREOF.
6. This License Agreement will automatically terminate upon a material breach of its terms and conditions.
7. This License Agreement shall be governed by the federal intellectual property law of the United States, including without limitation the federal copyright law, and, to the extent such U.S. federal law does not apply, by the law of the Commonwealth of Virginia, excluding Virginia’s conflict of law provisions. Notwithstanding the foregoing, with regard to derivative works based on Python 1.6.1 that incorporate non-separable material that was previously distributed under the GNU General Public License (GPL), the law of the Commonwealth of Virginia shall govern this License Agreement only as to issues arising under or with respect to Paragraphs 4, 5, and 7 of this License Agreement. Nothing in this License Agreement shall be deemed to create any relationship of agency, partnership, or joint venture between CNRI and Licensee. This License Agreement does not grant permission to use CNRI trademarks or trade name in a trademark sense to endorse or promote products or services of Licensee, or any third party.
8. By clicking on the “ACCEPT” button where indicated, or by copying, installing or otherwise using Python 1.6.1, Licensee agrees to be bound by the terms and conditions of this License Agreement.

ACCEPT

CWI LICENSE AGREEMENT FOR PYTHON 0.9.0 THROUGH 1.2

Copyright © 1991 - 1995, Stichting Mathematisch Centrum Amsterdam, The Netherlands. All rights reserved.

Permission to use, copy, modify, and distribute this software and its documentation for any purpose and without fee is hereby granted, provided that the above copyright notice appear in all copies and that both that copyright notice and this permission notice appear in supporting documentation, and that the name of Stichting Mathematisch Centrum or CWI not be used in advertising or publicity pertaining to distribution of the software without specific, written prior permission.

STICHTING MATHEMATISCH CENTRUM DISCLAIMS ALL WARRANTIES WITH REGARD TO THIS SOFTWARE, INCLUDING ALL IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS, IN NO EVENT

SHALL STICHTING MATHEMATISCH CENTRUM BE LIABLE FOR ANY SPECIAL, INDIRECT OR CONSEQUENTIAL DAMAGES OR ANY DAMAGES WHATSOEVER RESULTING FROM LOSS OF USE, DATA OR PROFITS, WHETHER IN AN ACTION OF CONTRACT, NEGLIGENCE OR OTHER TORTIOUS ACTION, ARISING OUT OF OR IN CONNECTION WITH THE USE OR PERFORMANCE OF THIS SOFTWARE.

C.3 Licenses and Acknowledgements for Incorporated Software

This section is an incomplete, but growing list of licenses and acknowledgements for third-party software incorporated in the Python distribution.

C.3.1 Mersenne Twister

The `_random` module includes code based on a download from <http://www.math.keio.ac.jp/matu-moto/MT2002/emt19937ar.html>. The following are the verbatim comments from the original code:

A C-program for MT19937, with initialization improved 2002/1/26.
Coded by Takuji Nishimura and Makoto Matsumoto.

Before using, initialize the state by using `init_genrand(seed)`
or `init_by_array(init_key, key_length)`.

Copyright (C) 1997 - 2002, Makoto Matsumoto and Takuji Nishimura,
All rights reserved.

Redistribution and use in source and binary forms, with or without
modification, are permitted provided that the following conditions
are met:

1. Redistributions of source code must retain the above copyright
notice, this list of conditions and the following disclaimer.
2. Redistributions in binary form must reproduce the above copyright
notice, this list of conditions and the following disclaimer in the
documentation and/or other materials provided with the distribution.
3. The names of its contributors may not be used to endorse or promote
products derived from this software without specific prior written
permission.

THIS SOFTWARE IS PROVIDED BY THE COPYRIGHT HOLDERS AND CONTRIBUTORS
"AS IS" AND ANY EXPRESS OR IMPLIED WARRANTIES, INCLUDING, BUT NOT
LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR
A PARTICULAR PURPOSE ARE DISCLAIMED. IN NO EVENT SHALL THE COPYRIGHT OWNER OR
CONTRIBUTORS BE LIABLE FOR ANY DIRECT, INDIRECT, INCIDENTAL, SPECIAL,
EXEMPLARY, OR CONSEQUENTIAL DAMAGES (INCLUDING, BUT NOT LIMITED TO,
PROCUREMENT OF SUBSTITUTE GOODS OR SERVICES; LOSS OF USE, DATA, OR
PROFITS; OR BUSINESS INTERRUPTION) HOWEVER CAUSED AND ON ANY THEORY OF
LIABILITY, WHETHER IN CONTRACT, STRICT LIABILITY, OR TORT (INCLUDING
NEGLIGENCE OR OTHERWISE) ARISING IN ANY WAY OUT OF THE USE OF THIS
SOFTWARE, EVEN IF ADVISED OF THE POSSIBILITY OF SUCH DAMAGE.

Any feedback is very welcome.
<http://www.math.keio.ac.jp/matsumoto/emt.html>
email: matsumoto@math.keio.ac.jp

C.3.2 Sockets

The `socket` module uses the functions, `getaddrinfo`, and `getnameinfo`, which are coded in separate source files from the WIDE Project, <http://www.wide.ad.jp/about/index.html>.

Copyright (C) 1995, 1996, 1997, and 1998 WIDE Project.
All rights reserved.

Redistribution and use in source and binary forms, with or without modification, are permitted provided that the following conditions are met:

1. Redistributions of source code must retain the above copyright notice, this list of conditions and the following disclaimer.
2. Redistributions in binary form must reproduce the above copyright notice, this list of conditions and the following disclaimer in the documentation and/or other materials provided with the distribution.
3. Neither the name of the project nor the names of its contributors may be used to endorse or promote products derived from this software without specific prior written permission.

THIS SOFTWARE IS PROVIDED BY THE PROJECT AND CONTRIBUTORS ``AS IS'' AND GAI_ANY EXPRESS OR IMPLIED WARRANTIES, INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE ARE DISCLAIMED. IN NO EVENT SHALL THE PROJECT OR CONTRIBUTORS BE LIABLE FOR GAI_ANY DIRECT, INDIRECT, INCIDENTAL, SPECIAL, EXEMPLARY, OR CONSEQUENTIAL DAMAGES (INCLUDING, BUT NOT LIMITED TO, PROCUREMENT OF SUBSTITUTE GOODS OR SERVICES; LOSS OF USE, DATA, OR PROFITS; OR BUSINESS INTERRUPTION) HOWEVER CAUSED AND ON GAI_ANY THEORY OF LIABILITY, WHETHER IN CONTRACT, STRICT LIABILITY, OR TORT (INCLUDING NEGLIGENCE OR OTHERWISE) ARISING IN GAI_ANY WAY OUT OF THE USE OF THIS SOFTWARE, EVEN IF ADVISED OF THE POSSIBILITY OF SUCH DAMAGE.

C.3.3 Floating point exception control

The source for the `fpectl` module includes the following notice:

```

-----
/                               Copyright (c) 1996.                               \
|                               The Regents of the University of California.          |
|                               All rights reserved.                                |
|                                                                                 |
| Permission to use, copy, modify, and distribute this software for                |
| any purpose without fee is hereby granted, provided that this entire             |
| notice is included in all copies of any software which is or                   |
| includes a copy or modification of this software and in all                   |
| copies of the supporting documentation for such software.                      |
|                                                                                 |
| This work was produced at the University of California, Lawrence                 |
| Livermore National Laboratory under contract no. W-7405-ENG-48                 |
| between the U.S. Department of Energy and The Regents of the                 |
| University of California for the operation of UC LLNL.                        |
|                                                                                 |
|                               DISCLAIMER                                           |
|                                                                                 |
| This software was prepared as an account of work sponsored by an               |
| agency of the United States Government. Neither the United States              |
| Government nor the University of California nor any of their em-              |
| ployees, makes any warranty, express or implied, or assumes any               |
| liability or responsibility for the accuracy, completeness, or                 |
| usefulness of any information, apparatus, product, or process                 |
| disclosed, or represents that its use would not infringe                     |
| privately-owned rights. Reference herein to any specific commercial            |
| products, process, or service by trade name, trademark,                      |
| manufacturer, or otherwise, does not necessarily constitute or                |
| imply its endorsement, recommendation, or favoring by the United              |
| States Government or the University of California. The views and               |
| opinions of authors expressed herein do not necessarily state or               |
| reflect those of the United States Government or the University                |
| of California, and shall not be used for advertising or product                |
| \ endorsement purposes.                                                         /
-----

```

C.3.4 MD5 message digest algorithm

The source code for the `md5` module contains the following notice:

Copyright (C) 1999, 2002 Aladdin Enterprises. All rights reserved.

This software is provided 'as-is', without any express or implied warranty. In no event will the authors be held liable for any damages arising from the use of this software.

Permission is granted to anyone to use this software for any purpose, including commercial applications, and to alter it and redistribute it freely, subject to the following restrictions:

1. The origin of this software must not be misrepresented; you must not claim that you wrote the original software. If you use this software in a product, an acknowledgment in the product documentation would be appreciated but is not required.
2. Altered source versions must be plainly marked as such, and must not be misrepresented as being the original software.
3. This notice may not be removed or altered from any source distribution.

L. Peter Deutsch
ghost@aladdin.com

Independent implementation of MD5 (RFC 1321).

This code implements the MD5 Algorithm defined in RFC 1321, whose text is available at
<http://www.ietf.org/rfc/rfc1321.txt>

The code is derived from the text of the RFC, including the test suite (section A.5) but excluding the rest of Appendix A. It does not include any code or documentation that is identified in the RFC as being copyrighted.

The original and principal author of md5.h is L. Peter Deutsch <ghost@aladdin.com>. Other authors are noted in the change history that follows (in reverse chronological order):

2002-04-13 lpd Removed support for non-ANSI compilers; removed references to Ghostscript; clarified derivation from RFC 1321; now handles byte order either statically or dynamically.

1999-11-04 lpd Edited comments slightly for automatic TOC extraction.

1999-10-18 lpd Fixed typo in header comment (ansi2knr rather than md5); added conditionalization for C++ compilation from Martin Purschke <purschke@bnl.gov>.

1999-05-03 lpd Original version.

C.3.5 Asynchronous socket services

The `asynchat` and `asyncore` modules contain the following notice:

Copyright 1996 by Sam Rushing

All Rights Reserved

Permission to use, copy, modify, and distribute this software and its documentation for any purpose and without fee is hereby granted, provided that the above copyright notice appear in all copies and that both that copyright notice and this permission notice appear in supporting documentation, and that the name of Sam Rushing not be used in advertising or publicity pertaining to distribution of the software without specific, written prior permission.

SAM RUSHING DISCLAIMS ALL WARRANTIES WITH REGARD TO THIS SOFTWARE, INCLUDING ALL IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS, IN NO EVENT SHALL SAM RUSHING BE LIABLE FOR ANY SPECIAL, INDIRECT OR CONSEQUENTIAL DAMAGES OR ANY DAMAGES WHATSOEVER RESULTING FROM LOSS OF USE, DATA OR PROFITS, WHETHER IN AN ACTION OF CONTRACT, NEGLIGENCE OR OTHER TORTIOUS ACTION, ARISING OUT OF OR IN CONNECTION WITH THE USE OR PERFORMANCE OF THIS SOFTWARE.

C.3.6 Cookie management

The Cookie module contains the following notice:

Copyright 2000 by Timothy O'Malley <timo@alum.mit.edu>

All Rights Reserved

Permission to use, copy, modify, and distribute this software and its documentation for any purpose and without fee is hereby granted, provided that the above copyright notice appear in all copies and that both that copyright notice and this permission notice appear in supporting documentation, and that the name of Timothy O'Malley not be used in advertising or publicity pertaining to distribution of the software without specific, written prior permission.

Timothy O'Malley DISCLAIMS ALL WARRANTIES WITH REGARD TO THIS SOFTWARE, INCLUDING ALL IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS, IN NO EVENT SHALL Timothy O'Malley BE LIABLE FOR ANY SPECIAL, INDIRECT OR CONSEQUENTIAL DAMAGES OR ANY DAMAGES WHATSOEVER RESULTING FROM LOSS OF USE, DATA OR PROFITS, WHETHER IN AN ACTION OF CONTRACT, NEGLIGENCE OR OTHER TORTIOUS ACTION, ARISING OUT OF OR IN CONNECTION WITH THE USE OR PERFORMANCE OF THIS SOFTWARE.

C.3.7 Profiling

The profile and pstats modules contain the following notice:

Copyright 1994, by InfoSeek Corporation, all rights reserved.
Written by James Roskind

Permission to use, copy, modify, and distribute this Python software and its associated documentation for any purpose (subject to the restriction in the following sentence) without fee is hereby granted, provided that the above copyright notice appears in all copies, and that both that copyright notice and this permission notice appear in supporting documentation, and that the name of InfoSeek not be used in advertising or publicity pertaining to distribution of the software without specific, written prior permission. This permission is explicitly restricted to the copying and modification of the software to remain in Python, compiled Python, or other languages (such as C) wherein the modified or derived code is exclusively imported into a Python module.

INFOSEEK CORPORATION DISCLAIMS ALL WARRANTIES WITH REGARD TO THIS SOFTWARE, INCLUDING ALL IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS. IN NO EVENT SHALL INFOSEEK CORPORATION BE LIABLE FOR ANY SPECIAL, INDIRECT OR CONSEQUENTIAL DAMAGES OR ANY DAMAGES WHATSOEVER RESULTING FROM LOSS OF USE, DATA OR PROFITS, WHETHER IN AN ACTION OF CONTRACT, NEGLIGENCE OR OTHER TORTIOUS ACTION, ARISING OUT OF OR IN CONNECTION WITH THE USE OR PERFORMANCE OF THIS SOFTWARE.

C.3.8 Execution tracing

The `trace` module contains the following notice:

portions copyright 2001, Autonomous Zones Industries, Inc., all rights...
err... reserved and offered to the public under the terms of the
Python 2.2 license.
Author: Zooko O'Whielacronx
<http://zooko.com/>
<mailto:zooko@zooko.com>

Copyright 2000, Mojam Media, Inc., all rights reserved.
Author: Skip Montanaro

Copyright 1999, Bioreason, Inc., all rights reserved.
Author: Andrew Dalke

Copyright 1995-1997, Automatrix, Inc., all rights reserved.
Author: Skip Montanaro

Copyright 1991-1995, Stichting Mathematisch Centrum, all rights reserved.

Permission to use, copy, modify, and distribute this Python software and
its associated documentation for any purpose without fee is hereby
granted, provided that the above copyright notice appears in all copies,
and that both that copyright notice and this permission notice appear in
supporting documentation, and that the name of neither Automatrix,
Bioreason or Mojam Media be used in advertising or publicity pertaining to
distribution of the software without specific, written prior permission.

C.3.9 UUencode and UUdecode functions

The `uu` module contains the following notice:

Copyright 1994 by Lance Ellinghouse
Cathedral City, California Republic, United States of America.

All Rights Reserved

Permission to use, copy, modify, and distribute this software and its documentation for any purpose and without fee is hereby granted, provided that the above copyright notice appear in all copies and that both that copyright notice and this permission notice appear in supporting documentation, and that the name of Lance Ellinghouse not be used in advertising or publicity pertaining to distribution of the software without specific, written prior permission.

LANCE ELLINGHOUSE DISCLAIMS ALL WARRANTIES WITH REGARD TO THIS SOFTWARE, INCLUDING ALL IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS, IN NO EVENT SHALL LANCE ELLINGHOUSE CENTRUM BE LIABLE FOR ANY SPECIAL, INDIRECT OR CONSEQUENTIAL DAMAGES OR ANY DAMAGES WHATSOEVER RESULTING FROM LOSS OF USE, DATA OR PROFITS, WHETHER IN AN ACTION OF CONTRACT, NEGLIGENCE OR OTHER TORTIOUS ACTION, ARISING OUT OF OR IN CONNECTION WITH THE USE OR PERFORMANCE OF THIS SOFTWARE.

Modified by Jack Jansen, CWI, July 1995:

- Use binascii module to do the actual line-by-line conversion between ascii and binary. This results in a 1000-fold speedup. The C version is still 5 times faster, though.
- Arguments more compliant with python standard

C.3.10 XML Remote Procedure Calls

The `xmlrpc.lib` module contains the following notice:

The XML-RPC client interface is

Copyright (c) 1999-2002 by Secret Labs AB
Copyright (c) 1999-2002 by Fredrik Lundh

By obtaining, using, and/or copying this software and/or its associated documentation, you agree that you have read, understood, and will comply with the following terms and conditions:

Permission to use, copy, modify, and distribute this software and its associated documentation for any purpose and without fee is hereby granted, provided that the above copyright notice appears in all copies, and that both that copyright notice and this permission notice appear in supporting documentation, and that the name of Secret Labs AB or the author not be used in advertising or publicity pertaining to distribution of the software without specific, written prior permission.

SECRET LABS AB AND THE AUTHOR DISCLAIMS ALL WARRANTIES WITH REGARD TO THIS SOFTWARE, INCLUDING ALL IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS. IN NO EVENT SHALL SECRET LABS AB OR THE AUTHOR BE LIABLE FOR ANY SPECIAL, INDIRECT OR CONSEQUENTIAL DAMAGES OR ANY DAMAGES WHATSOEVER RESULTING FROM LOSS OF USE, DATA OR PROFITS, WHETHER IN AN ACTION OF CONTRACT, NEGLIGENCE OR OTHER TORTIOUS ACTION, ARISING OUT OF OR IN CONNECTION WITH THE USE OR PERFORMANCE OF THIS SOFTWARE.

MODULE INDEX

Symbols

`__builtin__`, 833
`__future__`, 842
`__main__`, 834
`_winreg`, 940

A

`aifc`, 697
`AL`, 915
`al`, 913
`anydbm`, 375
`array`, 125
`asynchat`, 595
`asyncore`, 592
`atexit`, 839
`audioop`, 693

B

`base64`, 251
`BaseHTTPServer`, 667
`Bastion`, 863
`binascii`, 253
`binhex`, 253
`bisect`, 124
`bsddb`, 379
`bz2`, 346

C

`calendar`, 113
`cd`, 915
`cgi`, 602
`CGIHTTPServer`, 671
`gitb`, 609
`chunk`, 704
`cmath`, 151
`cmd`, 757
`code`, 855
`codecs`, 77
`codeop`, 857
`collections`, 116
`colorsys`, 705

`commands`, 569
`compileall`, 887
`compiler`, 897
`compiler.ast`, 898
`compiler.visitor`, 903
`ConfigParser`, 310
`contextlib`, 837
`Cookie`, 680
`cookielib`, 672
`copy`, 143
`copy_reg`, 371
`cPickle`, 370
`cProfile`, 814
`crypt`, 556
`cStringIO`, 75
`csv`, 303
`ctypes`, 500
`curses`, 472
`curses.ascii`, 488
`curses.panel`, 491
`curses.textpad`, 487
`curses.wrapper`, 488

D

`datetime`, 95
`dbhash`, 378
`dbm`, 376
`decimal`, 153
`DEVICE`, 927
`difflib`, 65
`dircache`, 340
`dis`, 888
`distutils`, 896
`dl`, 557
`doctest`, 764
`DocXMLRPCServer`, 691
`dumbdbm`, 382
`dummy_thread`, 546
`dummy_threading`, 547

E

`email`, 189

- email.charset, 203
- email.encoders, 206
- email.errors, 206
- email.generator, 198
- email.header, 201
- email.iterators, 209
- email.message, 190
- email.mime, 199
 - email.mime.audio, 199
 - email.mime.base, 199
 - email.mime.image, 199
 - email.mime.message, 199
 - email.mime.multipart, 199
 - email.mime.nonmultipart, 199
 - email.mime.text, 199
- email.parser, 196
- email.utils, 207
- encodings.idna, 89
- encodings.utf-8-sig, 90
- errno, 494
- exceptions, 17

F

- fcntl, 560
- filecmp, 333
- fileinput, 328
- FL, 923
- fl, 919
- flp, 924
- fm, 924
- fnmatch, 337
- formatter, 909
- fpectl, 852
- fpformat, 93
- ftplib, 636
- functools, 181

G

- gc, 842
- gdbm, 377
- getopt, 447
- getpass, 472
- gettext, 739
- GL, 927
- gl, 925
- glob, 336
- gopherlib, 640
- grp, 556
- gzip, 345

H

- hashlib, 319
- heapq, 121
- hmac, 321

- hotshot, 819
- hotshot.stats, 820
- htmlentitydefs, 264
- htmllib, 262
- HTMLParser, 257
- httplib, 632

I

- imageop, 696
- imaplib, 642
- imgfile, 927
- imghdr, 706
- imp, 865
- inspect, 844
- itertools, 172

J

- jpeg, 928

K

- keyword, 883

L

- linecache, 338
- locale, 749
- logging, 450

M

- mailbox, 218
- mailcap, 218
- marshal, 373
- math, 149
- md5, 321
- mhlib, 237
- mimetools, 239
- mimetypes, 241
- MimeWriter, 243
- mimify, 244
- mmap, 547
- modulefinder, 870
- msilib, 933
- msvcrt, 939
- multifile, 245
- mutex, 132

N

- netrc, 314
- new, 143
- nis, 567
- nntplib, 647

O

- operator, 182
- optparse, 420

os, 395
os.path, 325
ossaudiodev, 707

P

parser, 873
pdb, 805
pickle, 359
pickletools, 896
pipes, 562
pkgutil, 870
platform, 492
popen2, 590
poplib, 640
posix, 553
posixfile, 563
pprint, 144
profile, 814
pstats, 815
pty, 560
pwd, 554
py_compile, 887
pyclbr, 886
pydoc, 763

Q

Queue, 133
quopri, 255

R

random, 169
re, 52
readline, 549
repr, 147
resource, 565
rexec, 860
rfc822, 247
rgbimg, 705
rlcompleter, 551
robotparser, 313
runpy, 871

S

sched, 131
ScrolledText, 729
select, 535
sets, 128
sgmlib, 259
sha, 322
shelve, 371
shlex, 759
shutil, 338
signal, 588
SimpleHTTPServer, 670

SimpleXMLRPCServer, 688
site, 850
smtpd, 655
smtplib, 651
sndhdr, 707
socket, 577
SocketServer, 664
spwd, 555
sqlite3, 383
stat, 330
statvfs, 332
string, 47
StringIO, 74
stringprep, 91
struct, 62
subprocess, 571
sunau, 699
SUNAUDIODEV, 932
sunaudiodev, 931
symbol, 882
sys, 827
syslog, 568

T

tabnanny, 885
tarfile, 351
telnetlib, 656
tempfile, 334
termios, 558
test, 801
test.test_support, 803
textwrap, 75
thread, 536
threading, 538
time, 415
timeit, 821
Tix, 725
Tkinter, 713
token, 883
tokenize, 883
trace, 823
traceback, 840
tty, 559
turtle, 730
types, 140

U

unicodedata, 90
unittest, 789
urllib, 617
urllib2, 622
urlparse, 661
user, 851
UserDict, 138

- UserList, 139
- UserString, 140
- uu, 256
- uuid, 658

W

- warnings, 834
- wave, 702
- weakref, 134
- webbrowser, 599
- whichdb, 376
- winsound, 945
- wsgiref, 610
 - wsgiref.handlers, 614
 - wsgiref.headers, 611
 - wsgiref.simple_server, 612
 - wsgiref.util, 610
 - wsgiref.validate, 613

X

- xdrlib, 315
- xml.dom, 272
 - xml.dom.minidom, 282
 - xml.dom.pulldom, 287
- xml.etree.ElementTree, 298
- xml.parsers.expat, 264
- xml.sax, 288
 - xml.sax.handler, 289
 - xml.sax.saxutils, 293
 - xml.sax.xmlreader, 294
- xmlrpclib, 684

Z

- zipfile, 348
- zipimport, 868
- zlib, 343

INDEX

Symbols

- `.ini`
 - file, 310
- `.pdbrc`
 - file, 807
- `.pythonrc.py`
 - file, 851
- `iprotocol.proxy`, 624
- `==`
 - operator, 24
- `%` formatting, 32
- `%` interpolation, 32
- `_CData` (class in `ctypes`), 530
- `_FuncPtr` (class in `ctypes`), 525
- `_SimpleCData` (class in `ctypes`), 530
- `__abs__()` (in module operator), 183
- `__add__()`
 - AddressList method, 250
 - in module operator, 183
- `__and__()` (in module operator), 183
- `__bases__` (class attribute), 45
- `__builtin__` (built-in module), **833**
- `__class__` (instance attribute), 45
- `__cmp__()` (instance method), 24
- `__concat__()` (in module operator), 184
- `__contains__()`
 - in module operator, 184
 - Mailbox method, 220
 - Message method, 192
- `__copy__()` (copy protocol), 144
- `__deepcopy__()` (copy protocol), 144
- `__delitem__()`
 - in module operator, 185
 - Mailbox method, 219
 - Message method, 192
 - MH method, 224
- `__delslice__()` (in module operator), 185
- `__dict__`
 - instance attribute, 364
 - object attribute, 45
- `__displayhook__` (data in `sys`), 828
- `__div__()` (in module operator), 183
- `__enter__()` (context manager method), 42
- `__eq__()`
 - Charset method, 205
 - Header method, 203
 - in module operator, 183
- `__excepthook__` (data in `sys`), 828
- `__exit__()` (context manager method), 42
- `__floordiv__()` (in module operator), 183
- `__future__` (standard module), **842**
- `__ge__()` (in module operator), 183
- `__getinitargs__()` (copy protocol), 364
- `__getitem__()`
 - in module operator, 185
 - Mailbox method, 220
 - Message method, 192
- `__getnewargs__()` (copy protocol), 364
- `__getslice__()` (in module operator), 185
- `__getstate__()` (copy protocol), 364
- `__gt__()` (in module operator), 183
- `__iadd__()`
 - AddressList method, 250
 - in module operator, 185
- `__iand__()` (in module operator), 185
- `__iconcat__()` (in module operator), 185
- `__idiv__()` (in module operator), 185
- `__ifloordiv__()` (in module operator), 186
- `__ilshift__()` (in module operator), 186
- `__imod__()` (in module operator), 186
- `__import__()` (in module), 3
- `__imul__()` (in module operator), 186
- `__index__()` (in module operator), 184
- `__init__()`
 - method, 461
 - in module `difflib`, 66
 - instance constructor, 364
 - NullTranslations method, 742
- `__inv__()` (in module operator), 183
- `__invert__()` (in module operator), 183
- `__ior__()` (in module operator), 186
- `__ipow__()` (in module operator), 186
- `__irepeat__()` (in module operator), 186

- `__irshift__()` (in module operator), 186
- `__isub__()`
 - AddressList method, 251
 - in module operator, 186
- `__iter__()`
 - container method, 26
 - iterator method, 27
 - Mailbox method, 220
- `__itruediv__()` (in module operator), 186
- `__ixor__()` (in module operator), 186
- `__le__()` (in module operator), 183
- `__len__()`
 - AddressList method, 250
 - Mailbox method, 220
 - Message method, 191
- `__lshift__()` (in module operator), 184
- `__lt__()` (in module operator), 183
- `__main__` (built-in module), **834**
- `__members__` (object attribute), 45
- `__methods__` (object attribute), 45
- `__missing__()` (method), 120
- `__mod__()` (in module operator), 184
- `__mul__()` (in module operator), 184
- `__name__` (class attribute), 45
- `__ne__()`
 - Header method, 203, 205
 - in module operator, 183
- `__neg__()` (in module operator), 184
- `__not__()` (in module operator), 183
- `__or__()` (in module operator), 184
- `__pos__()` (in module operator), 184
- `__pow__()` (in module operator), 184
- `__repeat__()` (in module operator), 185
- `__repr__()` (netrc method), 314
- `__rshift__()` (in module operator), 184
- `__setitem__()`
 - in module operator, 185
 - Mailbox method, 220
 - Maildir method, 222
 - Message method, 192
- `__setslice__()` (in module operator), 185
- `__setstate__()` (copy protocol), 364
- `__stderr__` (data in sys), 833
- `__stdin__` (data in sys), 833
- `__stdout__` (data in sys), 833
- `__str__()`
 - AddressList method, 250
 - Charset method, 205
 - date method, 100
 - datetime method, 105
 - Header method, 203
 - Message method, 190
 - time method, 107
- `__sub__()`

- AddressList method, 250
- in module operator, 184
- `__truediv__()` (in module operator), 184
- `__unicode__()` (Header method), 203
- `__xor__()` (in module operator), 184
- `_anonymous_` (Structure attribute), 533
- `_b_base_` (.CData attribute), 530
- `_b_needsfree_` (.CData attribute), 530
- `_current_frames()` (in module sys), 828
- `_exit()` (in module os), 409
- `_fields_` (Structure attribute), 533
- `_flush()` (BaseHandler method), 615
- `_getframe()` (in module sys), 830
- `_handle` (PyDLL attribute), 524
- `_locale` (built-in module), 749
- `_name` (PyDLL attribute), 524
- `_objects_` (.CData attribute), 530
- `_pack_` (Structure attribute), 533
- `_parse()` (NullTranslations method), 742
- `_setroot()` (ElementTree method), 300
- `_structure()` (in module email.iterators), 209
- `_urloper` (data in urllib), 618
- `_winreg` (extension module), **940**
- `_write()` (BaseHandler method), 615

A

A-LAW, 699, 707

a-LAW, 693

`a2b_base64()` (in module binascii), 254

`a2b_hex()` (in module binascii), 254

`a2b_hqx()` (in module binascii), 254

`a2b_qp()` (in module binascii), 254

`a2b_uu()` (in module binascii), 253

`ABDAY_1` ... `ABDAY_7` (data in locale), 753

`ABMON_1` ... `ABMON_12` (data in locale), 753

`abort()`

FTP method, 638

in module os, 408

`above()` (method), 491

`abs()`

Context method, 160

in module , 4

in module operator, 183

`abspath()` (in module os.path), 325

`AbstractBasicAuthHandler` (class in urllib2), 624

`AbstractDigestAuthHandler` (class in urllib2), 624

`AbstractFormatter` (class in formatter), 911

`AbstractWriter` (class in formatter), 912

`ac_in_buffer_size` (data in asynchat), 595

`ac_out_buffer_size` (data in asynchat), 596

`accept()`

dispatcher method, 594

socket method, 581

- accept2dayear (data in time), 416
- access () (in module os), 402
- acos ()
 - in module cmath, 151
 - in module math, 150
- acosh () (in module cmath), 151
- acquire ()
 - method, 461
 - Condition method, 542
 - lock method, 537
 - Semaphore method, 543
 - Timer method, 540, 541
- acquire_lock () (in module imp), 866
- activate_form () (form method), 921
- activeCount () (in module threading), 538
- add ()
 - Context method, 160
 - in module audioop, 693
 - in module operator, 183
 - Mailbox method, 219
 - Maildir method, 222
 - RadioButtonGroup method, 938
 - Stats method, 815
 - TarFile method, 354
- add_alias () (in module email.charset), 206
- add_box () (form method), 921
- add_browser () (form method), 922
- add_button () (form method), 921
- add_cgi_vars () (BaseHandler method), 615
- add_charset () (in module email.charset), 205
- add_choice () (form method), 922
- add_clock () (form method), 921
- add_codec () (in module email.charset), 206
- add_cookie_header () (CookieJar method), 673
- add_counter () (form method), 922
- add_data ()
 - in module msilib, 934
 - Request method, 625
- add_dial () (form method), 921
- add_fallback () (NullTranslations method), 742
- add_file () (Directory method), 937
- add_flag ()
 - MaildirMessage method, 227
 - mboxMessage method, 229
 - MMDFMessage method, 233
- add_flowng_data () (formatter method), 910
- add_folder ()
 - Maildir method, 222
 - MH method, 224
- add_handler () (OpenerDirector method), 625
- add_header ()
 - Headers method, 612
 - Message method, 192
 - Request method, 625
- add_history () (in module readline), 550
- add_hor_rule () (formatter method), 910
- add_input () (form method), 922
- add_label () (BabylMessage method), 231
- add_label_data () (formatter method), 910
- add_lightbutton () (form method), 921
- add_line_break () (formatter method), 909
- add_literal_data () (formatter method), 910
- add_menu () (form method), 922
- add_parent () (BaseHandler method), 626
- add_password () (HTTPPasswordMgr method), 628
- add_positioner () (form method), 921
- add_roundbutton () (form method), 921
- add_section () (SafeConfigParser method), 311
- add_sequence () (MHMessage method), 230
- add_slider () (form method), 921
- add_stream () (in module msilib), 934
- add_tables () (in module msilib), 934
- add_text () (form method), 921
- add_timer () (form method), 922
- add_type () (in module mimetypes), 241
- add_unredirected_header () (Request method), 625
- add_valslider () (form method), 921
- addcallback () (CD parser method), 918
- addch () (window method), 478
- addError () (TestResult method), 799
- addFailure () (TestResult method), 799
- addfile () (TarFile method), 354
- addFilter () (method), 455, 461
- addHandler () (method), 455
- addheader () (MimeWriter method), 243
- addinfo () (Profile method), 819
- addLevelName () (in module logging), 453
- addnstr () (window method), 478
- AddPackagePath () (in module modulefinder), 870
- address_family (data in SocketServer), 666
- address_string () (BaseHTTPRequestHandler method), 670
- AddressList (class in rfc822), 248
- addresslist (AddressList attribute), 251
- addressof () (in module ctypes), 528
- addstr () (window method), 478
- addSuccess () (TestResult method), 800
- addTest () (TestSuite method), 798
- addTests () (TestSuite method), 798
- adjusted () (Decimal method), 157
- adler32 () (in module zlib), 343
- ADPCM, Intel/DVI, 693
- adpcm2lin () (in module audioop), 693
- AES
 - algorithm, 319
- AF_INET (data in socket), 578
- AF_INET6 (data in socket), 578

AF_UNIX (data in socket), 578
 AI_* (data in socket), 578
 aifc () (aifc method), 698
 aifc (standard module), **697**
 AIFF, 697, 704
 aiff () (aifc method), 698
 AIFF-C, 697, 704
 AL (standard module), 913, **915**
 al (built-in module), **913**
 alarm () (in module signal), 589
 alaw2lin () (in module audioop), 693
 algorithm
 AES, 319
 alignment () (in module ctypes), 528
 all () (in module), 4
 all_errors (data in ftplib), 637
 all_features (data in xml.sax.handler), 290
 all_properties (data in xml.sax.handler), 291
 allocate_lock () (in module thread), 537
 allow_reuse_address (data in SocketServer), 666
 allowed_domains () (DefaultCookiePolicy method),
 677
 allowremoval () (CD player method), 917
 alt () (in module curses.ascii), 490
 ALT_DIGITS (data in locale), 753
 altsep (data in os), 414
 altzone (data in time), 416
 anchor_bgn () (HTMLParser method), 263
 anchor_end () (HTMLParser method), 263
 and
 operator, 23, 24
 and_ () (in module operator), 183
 annotate () (in module dircache), 340
 any () (in module), 4
 anydbm (standard module), **375**
 api_version (data in sys), 833
 apop () (POP3_SSL method), 641
 append ()
 method, 116
 array method, 126
 CAB method, 937
 Header method, 202
 IMAP4_stream method, 643
 list method, 35
 Template method, 563
 appendChild () (Node method), 276
 appendleft () (method), 116
 application_uri () (in module wsgiref.util), 610
 apply () (in module), 17
 architecture () (in module platform), 492
 aRepr (data in repr), 147
 args (tuple attribute), 182
 argtypes (_FuncPtr attribute), 525
 ArgumentError () (exception in ctypes), 525
 argv (data in sys), 827
 arithmetic, 25
 ArithmeticError (exception in exceptions), 18
 array () (in module array), 125
 array (built-in module), **125**
 arrays, 125
 ArrayType (data in array), 125
 article () (NNTP method), 650
 AS_IS (data in formatter), 909
 as_string () (Message method), 190
 as_tuple () (Decimal method), 157
 ascii () (in module curses.ascii), 490
 ascii_letters (data in string), 47
 ascii_lowercase (data in string), 47
 ascii_uppercase (data in string), 47
 asctime () (in module time), 416
 asin ()
 in module cmath, 152
 in module math, 150
 asinh () (in module cmath), 152
 assert
 statement, 18
 assert_ () (TestCase method), 797
 assert_line_data () (formatter method), 911
 assertAlmostEqual () (TestCase method), 797
 assertEquals () (TestCase method), 797
 AssertionError (exception in exceptions), 18
 assertNotAlmostEqual () (TestCase method), 797
 assertNotEqual () (TestCase method), 797
 assertRaises () (TestCase method), 797
 assignment
 extended slice, 35
 slice, 35
 subscript, 35
 ast2list () (in module parser), 875
 ast2tuple () (in module parser), 875
 astimezone () (datetime method), 104
 ASTType (data in parser), 876
 ASTVisitor (class in compiler.visitor), 903
 async_chat (class in asynchat), 595
 asynchat (standard module), **595**
 asyncore (built-in module), **592**
 atan ()
 in module cmath, 152
 in module math, 150
 atan2 () (in module math), 150
 atanh () (in module cmath), 152
 atexit (standard module), **839**
 atime (data in cd), 916
 atof ()
 in module locale, 752
 in module string, 50
 atoi ()
 in module locale, 752

- in module string, 50
- atol() (in module string), 50
- attach() (Message method), 191
- AttlistDeclHandler() (xmlparser method), 267
- attrgetter() (in module operator), 187
- AttributeError (exception in exceptions), 18
- attributes (Node attribute), 275
- AttributesImpl (class in xml.sax.xmlreader), 295
- AttributesNSImpl (class in xml.sax.xmlreader), 295
- attroff() (window method), 478
- attron() (window method), 478
- attrset() (window method), 478
- audio (data in cd), 916
- Audio Interchange File Format, 697, 704
- AUDIO_FILE_ENCODING_ADPCM_G721 (data in sunau), 700
- AUDIO_FILE_ENCODING_ADPCM_G722 (data in sunau), 700
- AUDIO_FILE_ENCODING_ADPCM_G723_3 (data in sunau), 700
- AUDIO_FILE_ENCODING_ADPCM_G723_5 (data in sunau), 700
- AUDIO_FILE_ENCODING_ALAW_8 (data in sunau), 700
- AUDIO_FILE_ENCODING_DOUBLE (data in sunau), 700
- AUDIO_FILE_ENCODING_FLOAT (data in sunau), 700
- AUDIO_FILE_ENCODING_LINEAR_16 (data in sunau), 700
- AUDIO_FILE_ENCODING_LINEAR_24 (data in sunau), 700
- AUDIO_FILE_ENCODING_LINEAR_32 (data in sunau), 700
- AUDIO_FILE_ENCODING_LINEAR_8 (data in sunau), 700
- AUDIO_FILE_ENCODING_MULAW_8 (data in sunau), 700
- AUDIO_FILE_MAGIC (data in sunau), 700
- AUDIODEV, 708
- audioop (built-in module), **693**
- authenticate() (IMAP4_stream method), 643
- authenticators() (netrc method), 314
- avg() (in module audioop), 694
- avgpp() (in module audioop), 694

B

- b16decode() (in module base64), 252
- b16encode() (in module base64), 252
- b2a_base64() (in module binascii), 254
- b2a_hex() (in module binascii), 254
- b2a_hqx() (in module binascii), 254
- b2a_qp() (in module binascii), 254
- b2a_uu() (in module binascii), 253
- b32decode() (in module base64), 251
- b32encode() (in module base64), 251
- b64decode() (in module base64), 251
- b64encode() (in module base64), 251
- Babyl (class in mailbox), 225
- BabylMailbox (class in mailbox), 235
- BabylMessage (class in mailbox), 231
- backslashreplace_errors_errors() (in module codecs), 79
- backward() (in module turtle), 731
- backward_compatible (data in imageop), 697
- BadStatusLine (exception in httplib), 633
- Balloon (class in Tix), 726
- base64
 - encoding, 251
- base64 (standard module), **251**, 253
- BaseCGIHandler (class in wsgiref.handlers), 614
- BaseCookie (class in Cookie), 680
- BaseException (exception in exceptions), 18
- BaseHandler
 - class in urllib2, 623
 - class in wsgiref.handlers, 614
- BaseHTTPRequestHandler (class in Base-HTTPServer), 668
- BaseHTTPServer (standard module), **667**
- basename() (in module os.path), 325
- BaseResult (class in urlparse), 664
- basestring() (in module), 4
- basicConfig() (in module logging), 453
- BasicContext (class in decimal), 159
- Bastion() (in module Bastion), 863
- Bastion (standard module), **863**
- BastionClass (class in Bastion), 863
- baudrate() (in module curses), 473
- bdb (standard module), 805
- Beep() (in module winsound), 945
- beep() (in module curses), 473
- begin_fill() (in module turtle), 731
- below() (method), 491
- Benchmarking, 821
- benchmarking, 417
- bestreadsize() (CD player method), 917
- betavariate() (in module random), 171
- bgn_group() (form method), 921
- bias() (in module audioop), 694
- bidirectional() (in module unicodedata), 90
- BigEndianStructure (class in ctypes), 533
- Binary (class in msilib), 934
- binary
 - data, packing, 62
- binary semaphores, 536
- binascii (built-in module), **253**
- bind()
 - dispatcher method, 594
 - socket method, 581

- bind (widgets), 723
- bind_textdomain_codeset () (in module gettext), 739
- bindtextdomain () (in module gettext), 739
- binhex () (in module binhex), 253
- binhex (standard module), 253, **253**
- bisect () (in module bisect), 124
- bisect (standard module), **124**
- bisect_left () (in module bisect), 124
- bisect_right () (in module bisect), 124
- bit-string
 - operations, 26
- bitmap () (Dialog method), 938
- bkgd () (window method), 478
- bkgdset () (window method), 478
- block_size (data in hashlib), 320
- blocked_domains () (DefaultCookiePolicy method), 677
- BLOCKSIZE (data in cd), 916
- blocksize (data in sha), 322
- body () (NNTP method), 650
- body_encode () (Charset method), 205
- body_encoding (data in email.charset), 204
- body_line_iterator () (in module email.iterators), 209
- BOM (data in codecs), 80
- BOM_BE (data in codecs), 80
- BOM_LE (data in codecs), 80
- BOM_UTF16 (data in codecs), 80
- BOM_UTF16_BE (data in codecs), 80
- BOM_UTF16_LE (data in codecs), 80
- BOM_UTF32 (data in codecs), 80
- BOM_UTF32_BE (data in codecs), 80
- BOM_UTF32_LE (data in codecs), 80
- BOM_UTF8 (data in codecs), 80
- bool () (in module), 4
- Boolean
 - object, 25
 - operations, 23
 - type, 4
 - values, 44
- boolean () (in module xmlrpclib), 687
- BooleanType (data in types), 141
- border () (window method), 479
- bottom () (method), 491
- bottom_panel () (in module curses.panel), 491
- BoundaryError (exception in email.errors), 207
- BoundedSemaphore () (in module threading), 539
- box () (window method), 479
- break_long_words (TextWrapper attribute), 77
- BROWSER**, 600
- bsddb
 - built-in module, 372, 375, 378
 - extension module, **379**
- BsdDbShelf (class in shelve), 372
- btopen () (in module bsddb), 380
- buffer
 - object, 27
- buffer ()
 - built-in function, 27, 142
 - in module , 17
- buffer size, I/O, 10
- buffer_info () (array method), 126
- buffer_size (xmlparser attribute), 266
- buffer_text (xmlparser attribute), 266
- buffer_used (xmlparser attribute), 266
- BufferingHandler (class in logging), 466
- BufferType (data in types), 142
- bufsize () (audio device method), 710
- build_opener () (in module urllib2), 623
- built-in
 - constants, 3
 - exceptions, 3
 - functions, 3
 - types, 3, 23
- builtin_module_names (data in sys), 827
- BuiltinFunctionType (data in types), 142
- BuiltinMethodType (data in types), 142
- ButtonBox (class in Tix), 726
- byref () (in module ctypes), 528
- byte-code
 - file, 865, 867, 887
- byteorder (data in sys), 827
- bytes (UUID attribute), 659
- bytes_le (UUID attribute), 659
- byteswap () (array method), 126
- bz2 (built-in module), **346**
- BZ2Compressor (class in bz2), 347
- BZ2Decompressor (class in bz2), 347
- BZ2File (class in bz2), 346

C

C

- language, 25
- structures, 62
- C_BUILTIN (data in imp), 866
- c_byte (class in ctypes), 531
- c_char (class in ctypes), 531
- c_char_p (class in ctypes), 531
- c_double (class in ctypes), 531
- C_EXTENSION (data in imp), 866
- c_float (class in ctypes), 531
- c_int (class in ctypes), 531
- c_int16 (class in ctypes), 531
- c_int32 (class in ctypes), 531
- c_int64 (class in ctypes), 531
- c_int8 (class in ctypes), 531
- c_long (class in ctypes), 531

- c_longlong (class in ctypes), 531
- c_short (class in ctypes), 531
- c_size_t (class in ctypes), 532
- c_ubyte (class in ctypes), 532
- c_uint (class in ctypes), 532
- c_uint16 (class in ctypes), 532
- c_uint32 (class in ctypes), 532
- c_uint64 (class in ctypes), 532
- c_uint8 (class in ctypes), 532
- c_ulong (class in ctypes), 532
- c_ulonglong (class in ctypes), 532
- c_ushort (class in ctypes), 532
- c_void_p (class in ctypes), 532
- c_wchar (class in ctypes), 532
- c_wchar_p (class in ctypes), 532
- CAB (class in msilib), 936
- CacheFTPHandler (class in urllib2), 624
- calctime () (in module struct), 63
- Calendar (class in calendar), 113
- calendar () (in module calendar), 115
- calendar (standard module), **113**
- call ()
 - method, 558
 - in module subprocess, 572
- callable () (in module), 4
- CallableProxyType (data in weakref), 136
- can_change_color () (in module curses), 473
- can_fetch () (RobotFileParser method), 313
- cancel ()
 - scheduler method, 132
 - Timer method, 546
- CannotSendHeader (exception in httplib), 633
- CannotSendRequest (exception in httplib), 633
- capitalize ()
 - in module string, 50
 - string method, 29
- capwords () (in module string), 50
- cast () (in module ctypes), 528
- cat () (in module nis), 568
- catalog (data in cd), 916
- category () (in module unicodedata), 90
- cbreak () (in module curses), 473
- cd (built-in module), **915**
- CDLL (class in ctypes), 523
- CDROM (data in cd), 916
- ceil ()
 - in module math, 149
 - in module math, 25
- center ()
 - in module string, 52
 - string method, 29
- CFUNCTYPE () (in module ctypes), 526
- CGI
 - debugging, 608
 - exceptions, 609
 - protocol, 602
 - security, 607
 - tracebacks, 609
- cgi (standard module), **602**
- cgi_directories (CGIHTTPRequestHandler attribute), 671
- CGIHandler (class in wsgiref.handlers), 614
- CGIHTTPRequestHandler (class in CGI-HTTPServer), 671
- CGIHTTPServer (standard module), 667, **671**
- cgilib (standard module), **609**
- CGIXMLRPCRequestHandler (class in SimpleXML-RPCServer), 689
- chain () (in module itertools), 173
- chaining
 - comparisons, 24
- channels () (audio device method), 709
- CHAR_MAX (data in locale), 752
- character, 90
- CharacterDataHandler () (xmlparser method), 267
- characters () (ContentHandler method), 292
- CHARSET (data in mimify), 244
- Charset (class in email.charset), 203
- charset () (NullTranslations method), 742
- chdir () (in module os), 402
- check ()
 - IMAP4_stream method, 644
 - in module tabnanny, 885
- check_call () (in module subprocess), 573
- check_forms () (in module fl), 919
- check_output () (OutputChecker method), 784
- checkbox () (Dialog method), 939
- checkcache () (in module linecache), 338
- CheckList (class in Tix), 727
- checksum
 - Cyclic Redundancy Check, 344
 - MD5, 321
 - SHA, 322
- childerr (Popen4 attribute), 591
- childNodes (Node attribute), 275
- chmod () (in module os), 402
- choice () (in module random), 170
- choose_boundary () (in module mimetools), 239
- chown () (in module os), 403
- chr () (in module), 4
- chroot () (in module os), 402
- Chunk (class in chunk), 704
- chunk (standard module), **704**
- cipher
 - DES, 556
- circle () (in module turtle), 731
- Clamped (class in decimal), 162

Class browser, 733
 classmethod() (in module), 5
 classobj() (in module new), 143
 ClassType (data in types), 141
 clean() (Maildir method), 222
 clear()
 method, 116
 CookieJar method, 674
 dictionary method, 37
 Event method, 544
 in module turtle, 731
 Mailbox method, 221
 window method, 479
 clear_flags() (Context method), 160
 clear_history() (in module readline), 549
 clear_memo() (Pickler method), 362
 clear_session_cookies() (CookieJar method), 674
 clearcache() (in module linecache), 338
 ClearData() (Binary method), 936
 clearok() (window method), 479
 client_address (BaseHTTPRequestHandler attribute), 668
 clock() (in module time), 416
 clone()
 Generator method, 199
 Template method, 563
 cloneNode() (Node method), 276, 285
 Close()
 method, 945
 Binary method, 935
 close()
 method, 380, 461, 548, 558
 aifc method, 698, 699
 AU_read method, 700
 AU_write method, 701
 audio device method, 708, 931
 BaseHandler method, 626
 BZ2File method, 346
 CD player method, 917
 Chunk method, 704
 dispatcher method, 594
 FeedParser method, 197
 file method, 39
 FileHandler method, 462
 FTP method, 639
 HTMLParser method, 258
 HTTPResponse method, 635
 IMAP4_stream method, 644
 in module fileinput, 329
 in module os, 399
 IncrementalParser method, 296
 Mailbox method, 221
 Maildir method, 222
 MemoryHandler method, 466
 MH method, 225
 mixer device method, 710
 NTEventLogHandler method, 465
 Profile method, 819
 SGMLParser method, 260
 socket method, 582
 SocketHandler method, 463
 StringIO method, 74
 SysLogHandler method, 464
 TarFile method, 354
 Telnet method, 657
 TreeBuilder method, 301
 Wave_read method, 702
 Wave_write method, 703
 XMLTreeBuilder method, 302
 ZipFile method, 349
 close_when_done() (async_chat method), 596
 closed
 audio device attribute, 710
 file attribute, 41
 CloseKey() (in module _winreg), 941
 closelog() (in module syslog), 568
 closeport() (audio port method), 914
 closing() (in module contextlib), 838
 clrtoebot() (window method), 479
 clrtoeol() (window method), 479
 cmath (built-in module), **151**
 Cmd (class in cmd), 757
 cmd (standard module), **757**, 805
 cmdloop() (Cmd method), 757
 cmp()
 built-in function, 751
 in module , 5
 in module filecmp, 333
 cmp_op (data in dis), 889
 cmpfiles() (in module filecmp), 333
 code
 object, 44, 374
 code() (in module new), 143
 code
 ExpatriError attribute, 269
 standard module, **855**
 Codecs, 77
 decode, 77
 encode, 77
 codecs (standard module), **77**
 coded_value (Morsel attribute), 681
 codeop (standard module), **857**
 codepoint2name (data in htmlentitydefs), 264
 CODESET (data in locale), 752
 CodeType (data in types), 141
 coerce() (in module), 17

- `collapse_rfc2231_value()` (in module `email.utils`), 209
- `collect()` (in module `gc`), 843
- `collect_incoming_data()` (`async_chat` method), 596
- `collections` (standard module), **116**
- `color()`
 - in module `fl`, 920
 - in module `turtle`, 731
- `color_content()` (in module `curses`), 473
- `color_pair()` (in module `curses`), 473
- `coloursys` (standard module), **705**
- COLUMNS**, 478
- `combine()` (`datetime` method), 102
- `combining()` (in module `unicodedata`), 90
- `ComboBox` (class in `Tix`), 726
- `command` (`BaseHTTPRequestHandler` attribute), 668
- `CommandCompiler` (class in `codeop`), 857
- `commands` (standard module), **569**
- `COMMENT` (data in `tokenize`), 884
- `Comment()` (in module `xml.etree.ElementTree`), 299
- `comment`
 - `Cookie` attribute, 678
 - `ZipInfo` attribute, 351
- `comment_url` (`Cookie` attribute), 678
- `commenters` (`shlex` attribute), 760
- `CommentHandler()` (`xmlparser` method), 268
- `Commit()` (`Binary` method), 934
- `common` (`dircmp` attribute), 334
- Common Gateway Interface**, 602
- `common_dirs` (`dircmp` attribute), 334
- `common_files` (`dircmp` attribute), 334
- `common_funny` (`dircmp` attribute), 334
- `common_types` (data in `mimetypes`), 242, 243
- `commonprefix()` (in module `os.path`), 325
- `communicate()` (`Popen` method), 573
- `compare()`
 - `Context` method, 160
 - `Decimal` method, 157
 - `Differ` method, 72
- `comparing`
 - objects, 24
- `comparison`
 - operator, 24
- `COMPARISON_FLAGS` (data in `doctest`), 773
- `comparisons`
 - chaining, 24
- `Compile` (class in `codeop`), 857
- `compile()`
 - `AST` method, 876
 - built-in function, 44, 141, 875, 876
 - in module `,` 5
 - in module `compiler`, 897
 - in module `py_compile`, 887
 - in module `re`, 57
- `compile_command()`
 - in module `code`, 855
 - in module `codeop`, 857
- `compile_dir()` (in module `compileall`), 887
- `compile_path()` (in module `compileall`), 888
- `compileall` (standard module), **887**
- `compileast()` (in module `parser`), 875
- `compileFile()` (in module `compiler`), 898
- `compiler` (module), **897**
- `compiler.ast` (module), **898**
- `compiler.visitor` (module), **903**
- `complete()` (`Completer` method), 552
- `complete_statement()` (in module `sqlite3`), 386
- `completedefault()` (`Cmd` method), 758
- `complex()`
 - built-in function, 25
 - in module `,` 5
- complex number**
 - literals, 25
 - object, 25
- `ComplexType` (data in `types`), 141
- `compress()`
 - `BZ2Compressor` method, 347
 - `Compress` method, 344
 - in module `bz2`, 348
 - in module `jpeg`, 928
 - in module `zlib`, 343
- `compress_size` (`ZipInfo` attribute), 351
- `compress_type` (`ZipInfo` attribute), 351
- `CompressionError` (exception in `tarfile`), 353
- `compressobj()` (in module `zlib`), 343
- COMSPEC**, 412, 572
- `concat()` (in module `operator`), 184
- concatenation**
 - operation, 28
- `Condition()` (in module `threading`), 538
- `Condition` (class in `threading`), 542
- `condition()` (`Control` method), 938
- `ConfigParser`
 - class in `ConfigParser`, 310
 - standard module, **310**
- configuration**
 - file, 310
 - file, debugger, 807
 - file, path, 850
 - file, user, 851
- `confstr()` (in module `os`), 414
- `confstr_names` (data in `os`), 414
- `conjugate()` (complex number method), 25
- `connect()`
 - `dispatcher` method, 594
 - `FTP` method, 638
 - `HTTPResponse` method, 635

- in module sqlite3, 385
 - SMTP method, 652
 - socket method, 582
- connect_ex() (socket method), 582
- ConnectRegistry() (in module _winreg), 941
- constants
 - built-in, 3
- constructor() (in module copy_reg), 371
- container
 - iteration over, 26
- contains() (in module operator), 184
- content type
 - MIME, 241
- ContentHandler (class in xml.sax.handler), 289
- ContentTooShortError (exception in urllib), 620
- Context (class in decimal), 159
- context management protocol, 42
- context manager, 42
- context_diff() (in module difflib), 67
- contextlib (standard module), **837**
- contextmanager() (in module contextlib), 837
- Control
 - class in msilib, 938
 - class in Tix, 726
- control() (Dialog method), 938
- control (data in cd), 916
- controlnames (data in curses.ascii), 490
- controls() (mixer device method), 710
- ConversionError (exception in xdrlib), 317
- conversions
 - numeric, 25
- convert() (Charset method), 204
- convert_charref() (SGMLParser method), 261
- convert_codepoint() (SGMLParser method), 261
- convert_entityref() (SGMLParser method), 261
- Cookie
 - class in cookielib, 673
 - standard module, **680**
- CookieError (exception in Cookie), 680
- CookieJar (class in cookielib), 672
- cookiejar (UnknownHandler attribute), 628
- cookielib (standard module), **672**
- CookiePolicy (class in cookielib), 672
- Coordinated Universal Time, 415
- copy()
 - Compress method, 344
 - Context method, 160
 - Decompress method, 345
 - hash method, 320
 - hmac method, 321
 - IMAP4_stream method, 644
 - in module shutil, 339
 - md5 method, 322
 - sha method, 323
 - Template method, 563
- copy (standard module), **143**, 371
- copy()
 - dictionary method, 37
 - in copy, 143
- copy2() (in module shutil), 339
- copy_reg (standard module), **371**
- copybinary() (in module mimetools), 240
- copyfile() (in module shutil), 338
- copyfileobj() (in module shutil), 339
- copying files, 338
- copyliteral() (in module mimetools), 240
- copymessage() (Folder method), 239
- copymode() (in module shutil), 339
- copyright (data in sys), 828
- copystat() (in module shutil), 339
- copytree() (in module shutil), 339
- cos()
 - in module cmath, 152
 - in module math, 150
- cosh()
 - in module cmath, 152
 - in module math, 151
- count()
 - array method, 126
 - in module itertools, 173
 - in module string, 51
 - list method, 35
 - string method, 29
- countOf() (in module operator), 185
- countTestCases()
 - TestCase method, 798
 - TestSuite method, 798
- cPickle (built-in module), **370**, 371
- cProfile (standard module), **814**
- CPU time, 417
- CRC (ZipInfo attribute), 351
- crc32()
 - in module binascii, 254
 - in module zlib, 344
- crc_hqx() (in module binascii), 254
- create() (IMAP4_stream method), 644
- create_aggregate() (method), 387
- create_collation() (method), 387
- create_decimal() (Context method), 160
- create_function() (method), 387
- create_socket() (dispatcher method), 594
- create_string_buffer() (in module ctypes), 528
- create_system (ZipInfo attribute), 351
- create_unicode_buffer() (in module ctypes), 528
- create_version (ZipInfo attribute), 351
- createAttribute() (Document method), 278
- createAttributeNS() (Document method), 278

createComment () (Document method), 277
 createDocument () (DOMImplementation method), 274
 createDocumentType () (DOMImplementation method), 274
 createElement () (Document method), 277
 createElementNS () (Document method), 277
 CreateKey () (in module _winreg), 941
 createLock () (method), 461
 createparser () (in module cd), 915
 createProcessingInstruction () (Document method), 277
 CreateRecord () (in module msilib), 933
 createTextNode () (Document method), 277
 critical ()
 method, 455
 in module logging, 452
 CRNCYSTR (data in locale), 753
 crop () (in module imageop), 696
 cross () (in module audioop), 694
 crypt () (in module crypt), 556
 crypt (built-in module), 555, **556**
 crypt(3), 556, 557
 cryptography, 319
 cStringIO (built-in module), **75**
 csv, 303
 csv (standard module), **303**
 ctermid () (in module os), 396
 ctime ()
 date method, 100
 datetime method, 105
 in module time, 417
 ctrl () (in module curses.ascii), 490
 ctypes (standard module), **500**
 curdir (data in os), 414
 currency () (in module locale), 751
 CurrentByteIndex (xmlparser attribute), 267
 CurrentColumnNumber (xmlparser attribute), 267
 currentframe () (in module inspect), 850
 CurrentLineNumber (xmlparser attribute), 267
 currentThread () (in module threading), 538
 curs_set () (in module curses), 473
 curses (standard module), **472**
 curses.ascii (standard module), **488**
 curses.panel (standard module), **491**
 curses.textpad (standard module), **487**
 curses.wrapper (standard module), **488**
 cursor () (method), 386
 cursyncup () (window method), 479
 cwd () (FTP method), 639
 cycle () (in module itertools), 173
 Cyclic Redundancy Check, 344

D

D_FMT (data in locale), 752
 D_T_FMT (data in locale), 752
 data
 packing binary, 62
 tabular, 303
 data () (TreeBuilder method), 301
 data
 Binary attribute, 686
 Comment attribute, 279
 IterableUserDict attribute, 139
 MutableString attribute, 140
 ProcessingInstruction attribute, 280
 Text attribute, 280
 UserList attribute, 139
 database
 Unicode, 90
 databases, 382
 DatagramHandler (class in logging), 464
 DATASIZE (data in cd), 916
 date ()
 datetime method, 103
 NNTP method, 651
 date (class in datetime), 96, 98
 date_time (ZipInfo attribute), 350
 date_time_string () (BaseHTTPRequestHandler method), 670
 datetime
 built-in module, **95**
 class in datetime, 96, 101
 day
 date attribute, 99
 datetime attribute, 102
 DAY_1 . . . DAY_7 (data in locale), 752
 day_abbr (data in calendar), 116
 day_name (data in calendar), 116
 daylight (data in time), 417
 Daylight Saving Time, 416
 DbfilenameShelf (class in shelve), 372
 dbhash (standard module), 375, **378**
 dbm (built-in module), 372, 375, **376**, 377
 deactivate_form () (form method), 921
 debug ()
 method, 454
 in module doctest, 787
 in module logging, 452
 Template method, 563
 TestCase method, 797
 TestSuite method, 798
 debug
 IMAP4_stream attribute, 647
 shlex attribute, 761
 ZipFile attribute, 350
 debug=0 (TarFile attribute), 355

DEBUG_COLLECTABLE (data in gc), 844
 DEBUG_INSTANCES (data in gc), 844
 DEBUG_LEAK (data in gc), 844
 DEBUG_OBJECTS (data in gc), 844
 DEBUG_SAVEALL (data in gc), 844
 debug_src() (in module doctest), 787
 DEBUG_STATS (data in gc), 844
 DEBUG_UNCOLLECTABLE (data in gc), 844
 debugger, 735, 832
 configuration file, 807
 debugging, 805
 CGI, 608
 DebuggingServer (class in smtpd), 655
 DebugRunner (class in doctest), 788
 Decimal (class in decimal), 157
 decimal() (in module unicodedata), 90
 decimal (standard module), **153**
 DecimalException (class in decimal), 162
 decode
 Codecs, 77
 decode()
 method, 81
 Binary method, 686
 in module base64, 252
 in module mimetools, 239
 in module quopri, 255
 in module uu, 256
 IncrementalDecoder method, 82
 ServerProxy method, 686
 string method, 29
 decode_header() (in module email.header), 203
 decode_params() (in module email.utils), 209
 decode_rfc2231() (in module email.utils), 209
 DecodedGenerator (class in email.generator), 199
 decodestring()
 in module base64, 252
 in module quopri, 255
 decomposition() (in module unicodedata), 90
 decompress()
 BZ2Decompressor method, 348
 Decompress method, 345
 in module bz2, 348
 in module jpeg, 928
 in module zlib, 344
 decompressobj() (in module zlib), 344
 dedent() (in module textwrap), 76
 deepcopy() (in copy), 143
 def_prog_mode() (in module curses), 473
 def_shell_mode() (in module curses), 473
 default()
 ASTVisitor method, 903
 Cmd method, 758
 default_bufsize (data in xml.dom.pulldom), 287
 default_factory (data in collections), 120
 default_open() (BaseHandler method), 627
 DefaultContext (class in decimal), 159
 DefaultCookiePolicy (class in cookielib), 672
 defaultdict() (in module collections), 120
 DefaultHandler() (xmlparser method), 268
 DefaultHandlerExpand() (xmlparser method), 268
 defaults() (SafeConfigParser method), 311
 defaultTestLoader (data in unittest), 796
 defaultTestResult() (TestCase method), 798
 defects (data in email.message), 196
 defpath (data in os), 415
 degrees()
 in module math, 151
 in module turtle, 730
 RawPen method, 733
 del
 statement, 35, 37
 del_param() (Message method), 194
 delattr() (in module), 6
 delay() (in module turtle), 731
 delay_output() (in module curses), 473
 delayload (Cookie attribute), 675
 delch() (window method), 479
 dele() (POP3_SSL method), 641
 delete()
 FTP method, 639
 IMAP4_stream method, 644
 delete_object() (FORMS object method), 923
 deleteacl() (IMAP4_stream method), 644
 deletefolder() (MH method), 238
 DeleteKey() (in module _winreg), 941
 deleteln() (window method), 479
 deleteparser() (CD parser method), 918
 DeleteValue() (in module _winreg), 941
 delimiter (Dialect attribute), 306
 delitem() (in module operator), 185
 delslice() (in module operator), 185
 demo() (in module turtle), 732
 demo_app() (in module wsgiref.simple_server), 613
 DeprecationWarning (exception in exceptions), 21
 deque() (in module collections), 116
 dereference (TarFile attribute), 355
 derwin() (window method), 479
 DES
 cipher, 556
 description() (NNTP method), 650
 descriptions() (NNTP method), 649
 descriptor, file, 39
 Detach() (method), 945
 deterministic profiling, 811
 DEVICE (standard module), **927**
 devnull (data in os), 415
 dgettext() (in module gettext), 740

- Dialect (class in csv), 305
- dialect
 - csv reader attribute, 307
 - csv writer attribute, 307
- Dialog (class in msilib), 938
- dict () (in module), 6
- dictionary
 - object, 37
 - type, operations on, 37
- DictionaryType (data in types), 141
- DictMixin (class in UserDict), 139
- DictProxyType (data in types), 142
- DictReader (class in csv), 304
- DictType (data in types), 141
- DictWriter (class in csv), 305
- diff_files (dircmp attribute), 334
- Differ (class in difflib), 66, 72
- difflib (standard module), **65**
- digest ()
 - hash method, 320
 - hmac method, 321
 - md5 method, 322
 - sha method, 323
- digest_size
 - data in hashlib, 320
 - data in md5, 322
 - data in sha, 322
- digit () (in module unicodedata), 90
- digits (data in string), 47
- dir ()
 - FTP method, 639
 - in module , 6
- dircache (standard module), **340**
- dircmp (class in filecmp), 333
- Directory (class in msilib), 937
- directory
 - changing, 402
 - creating, 404
 - deleting, 339, 405
 - site-packages, 850
 - site-python, 850
 - traversal, 407
 - walking, 407
- DirList (class in Tix), 727
- dirname () (in module os.path), 326
- DirSelectBox (class in Tix), 727
- DirSelectDialog (class in Tix), 727
- DirTree (class in Tix), 727
- dis ()
 - in module dis, 888
 - in module pickletools, 896
- dis (standard module), **888**
- disable ()
 - in module gc, 843
 - in module logging, 452
- disassemble () (in module dis), 888
- discard ()
 - Mailbox method, 219
 - MH method, 224
- discard (Cookie attribute), 678
- discard_buffers () (async_chat method), 596
- disco () (in module dis), 889
- dispatch () (ASTVisitor method), 904
- dispatcher (class in asyncore), 593
- displayhook () (in module sys), 828
- dist () (in module platform), 494
- distb () (in module dis), 888
- distutils (standard module), **896**
- dither2grey2 () (in module imageop), 697
- dither2mono () (in module imageop), 696
- div () (in module operator), 183
- divide () (Context method), 161
- division
 - integer, 25
 - long integer, 25
- DivisionByZero (class in decimal), 162
- divmod ()
 - Context method, 161
 - in module , 6
- dl (extension module), **557**
- DllCanUnloadNow () (in module ctypes), 529
- DllGetClassObject () (in module ctypes), 529
- dllhandle (data in sys), 828
- dngettext () (in module gettext), 740
- do_command () (Textbox method), 487
- do_forms () (in module fl), 919
- do_GET () (SimpleHTTPRequestHandler method), 670
- do_HEAD () (SimpleHTTPRequestHandler method), 670
- do_POST () (CGIHTTPRequestHandler method), 671
- doc_header (Cmd attribute), 759
- DocCGIXMLRPCRequestHandler (class in DocXMLRPCServer), 691
- DocFileSuite () (in module doctest), 778
- docmd () (SMTP method), 652
- docstring (DocTest attribute), 781
- docstrings, 877
- DocTest (class in doctest), 781
- doctest (standard module), **764**
- DocTestFailure (exception in doctest), 788
- DocTestFinder (class in doctest), 782
- DocTestParser (class in doctest), 783
- DocTestRunner (class in doctest), 783
- DocTestSuite () (in module doctest), 779
- doctype () (XMLTreeBuilder method), 302
- documentation
 - generation, 763
 - online, 763

documentElement (Document attribute), 277
DocXMLRPCRequestHandler (class in DocXMLRPCServer), 691
DocXMLRPCServer
 class in DocXMLRPCServer, 691
 standard module, **691**
domain_initial_dot (Cookie attribute), 679
domain_return_ok() (CookiePolicy method), 675
domain_specified (Cookie attribute), 679
DomainLiberal (LWP_COOKIEJAR attribute), 678
DomainRFC2965Match (LWP_COOKIEJAR attribute), 678
DomainStrict (LWP_COOKIEJAR attribute), 678
DomainStrictNoDots (LWP_COOKIEJAR attribute), 677
DomainStrictNonDomain (LWP_COOKIEJAR attribute), 677
DOMEventStream (class in xml.dom.pulldom), 287
DOMException (exception in xml.dom), 280
DomstringSizeErr (exception in xml.dom), 280
done()
 in module turtle, 730
 Unpacker method, 316
DONT_ACCEPT_BLANKLINE (data in doctest), 772
DONT_ACCEPT_TRUE_FOR_1 (data in doctest), 772
doRollover()
 RotatingFileHandler method, 463
 TimedRotatingFileHandler method, 463
DOTALL (data in re), 57
doublequote (Dialect attribute), 306
doupdate() (in module curses), 474
down() (in module turtle), 731
drain() (audio device method), 931
dropwhile() (in module itertools), 174
dst()
 datetime method, 104
 time method, 107, 108
DTDHandler (class in xml.sax.handler), 289
dumbdbm (standard module), 375, **382**
DumbWriter (class in formatter), 912
dummy_thread (standard module), **546**
dummy_threading (standard module), **547**
dump()
 in module marshal, 374
 in module pickle, 361
 in module xml.etree.ElementTree, 299
 Pickler method, 362
dump_address_pair() (in module rfc822), 248
dump_stats() (Stats method), 816
dumps()
 in module marshal, 374
 in module pickle, 361
 in module xmlrpclib, 687
dup()
 in module os, 399
 in module posixfile, 564
dup2()
 in module os, 400
 in module posixfile, 564
DuplicateSectionError (exception in ConfigParser), 310

E

e
 data in cmath, 152
 data in math, 151
E2BIG (data in errno), 495
EACCES (data in errno), 495
EADDRINUSE (data in errno), 499
EADDRNOTAVAIL (data in errno), 499
EADV (data in errno), 497
EAFNOSUPPORT (data in errno), 499
EAGAIN (data in errno), 495
EAI_* (data in socket), 578
EALREADY (data in errno), 500
east_asian_width() (in module unicodedata), 90
EBADF (data in errno), 497
EBADF (data in errno), 495
EBADFD (data in errno), 498
EBADMSG (data in errno), 498
EBADR (data in errno), 497
EBADRQC (data in errno), 497
EBADSLT (data in errno), 497
EBFONT (data in errno), 497
EBUSY (data in errno), 495
ECHILD (data in errno), 495
echo() (in module curses), 474
echochar() (window method), 479
ECHRNG (data in errno), 496
ECOMM (data in errno), 498
ECONNABORTED (data in errno), 499
ECONNREFUSED (data in errno), 499
ECONNRESET (data in errno), 499
EDEADLK (data in errno), 496
EDEADLOCK (data in errno), 497
EDESTADDRREQ (data in errno), 498
edit() (Textbox method), 487
EDOM (data in errno), 496
EDOTDOT (data in errno), 498
EDQUOT (data in errno), 500
EEXIST (data in errno), 495
EFAULT (data in errno), 495
EFBIG (data in errno), 496
ehlo() (SMTP method), 653
EHOSTDOWN (data in errno), 499
EHOSTUNREACH (data in errno), 499
EIDRM (data in errno), 496
EILSEQ (data in errno), 498

EINPROGRESS (data in errno), 500
 EINTR (data in errno), 495
 EINVAL (data in errno), 495
 EIO (data in errno), 495
 EISCONN (data in errno), 499
 EISDIR (data in errno), 495
 EISNAM (data in errno), 500
 eject () (CD player method), 917
 EL2HLT (data in errno), 497
 EL2NSYNC (data in errno), 496
 EL3HLT (data in errno), 496
 EL3RST (data in errno), 496
 Element () (in module xml.etree.ElementTree), 299
 ElementDeclHandler () (xmlparser method), 267
 ElementTree (class in xml.etree.ElementTree), 300
 ELIBACC (data in errno), 498
 ELIBBAD (data in errno), 498
 ELIBEXEC (data in errno), 498
 ELIBMAX (data in errno), 498
 ELIBSCN (data in errno), 498
 Ellinghouse, Lance, 256
 ELLIPSIS (data in doctest), 773
 Ellipsis (data in), 22
 EllipsisType (data in types), 142
 ELNRNG (data in errno), 497
 ELOOP (data in errno), 496
 email (standard module), **189**
 email.charset (standard module), **203**
 email.encoders (standard module), **206**
 email.errors (standard module), **206**
 email.generator (standard module), **198**
 email.header (standard module), **201**
 email.iterators (standard module), **209**
 email.message (standard module), **190**
 email.mime (standard module), **199**
 email.mime.audio (standard module), **199**
 email.mime.base (standard module), **199**
 email.mime.image (standard module), **199**
 email.mime.message (standard module), **199**
 email.mime.multipart (standard module), **199**
 email.mime.nonmultipart (standard module), **199**
 email.mime.text (standard module), **199**
 email.parser (standard module), **196**
 email.utils (standard module), **207**
 EMFILE (data in errno), 495
 emit ()
 method, 462
 BufferingHandler method, 466
 DatagramHandler method, 464
 FileHandler method, 462
 HTTPHandler method, 466
 NTEventLogHandler method, 465
 RotatingFileHandler method, 463
 SMTPHandler method, 465
 SocketHandler method, 464
 StreamHandler method, 462
 SysLogHandler method, 464
 TimedRotatingFileHandler method, 463
 EMLINK (data in errno), 496
 Empty (exception in Queue), 133
 empty ()
 Queue method, 133
 scheduler method, 132
 EMPTY_NAMESPACE (data in xml.dom), 273
 emptyline () (Cmd method), 758
 EMSGSIZE (data in errno), 498
 EMULTIHOP (data in errno), 498
 enable ()
 in module cgitb, 610
 in module gc, 843
 enable_callback_tracebacks () (in module
 sqlite3), 386
 ENAMETOOLONG (data in errno), 496
 ENAVAIL (data in errno), 500
 enclose () (window method), 479
 encode
 Codecs, 77
 encode ()
 method, 81
 Binary method, 686
 Header method, 203
 in module base64, 252
 in module mimetools, 240
 in module quopri, 255
 in module uu, 256
 IncrementalEncoder method, 82
 ServerProxy method, 686
 string method, 29
 encode_7or8bit () (in module email.encoders), 206
 encode_base64 () (in module email.encoders), 206
 encode_noop () (in module email.encoders), 206
 encode_quopri () (in module email.encoders), 206
 encode_rfc2231 () (in module email.utils), 209
 encoded_header_len () (Charset method), 205
 EncodedFile () (in module codecs), 80
 encodePriority () (SysLogHandler method), 465
 encodestring ()
 in module base64, 252
 in module quopri, 255
 encoding
 base64, 251
 quoted-printable, 255
 encoding (file attribute), 41
 encodings.idna (standard module), **89**
 encodings.utf-8-sig (standard module), **90**
 encodings_map (data in mimetypes), 242
 end ()

- MatchObject method, 61
- TreeBuilder method, 301
- end_fill() (in module turtle), 731
- end_group() (form method), 921
- end_headers() (BaseHTTPRequestHandler method), 669
- end_marker() (MultiFile method), 246
- end_paragraph() (formatter method), 909
- EndCdataSectionHandler() (xmlparser method), 268
- EndDoctypeDeclHandler() (xmlparser method), 267
- endDocument() (ContentHandler method), 291
- endElement() (ContentHandler method), 292
- EndElementHandler() (xmlparser method), 267
- endElementNS() (ContentHandler method), 292
- endheaders() (HTTPResponse method), 635
- EndNamespaceDeclHandler() (xmlparser method), 268
- endpick() (in module gl), 926
- endpos (MatchObject attribute), 61
- endPrefixMapping() (ContentHandler method), 291
- endselect() (in module gl), 926
- endswith() (string method), 29
- endwin() (in module curses), 474
- ENETDOWN (data in errno), 499
- ENETRESET (data in errno), 499
- ENETUNREACH (data in errno), 499
- ENFILE (data in errno), 495
- ENOANO (data in errno), 497
- ENOBUFFS (data in errno), 499
- ENOCSSI (data in errno), 497
- ENODATA (data in errno), 497
- ENODEV (data in errno), 495
- ENOENT (data in errno), 494
- ENOEXEC (data in errno), 495
- ENOLCK (data in errno), 496
- ENOLINK (data in errno), 497
- ENOMEM (data in errno), 495
- ENOMSG (data in errno), 496
- ENONET (data in errno), 497
- ENOPKG (data in errno), 497
- ENOPROTOOPT (data in errno), 499
- ENOSPC (data in errno), 496
- ENOSR (data in errno), 497
- ENOSTR (data in errno), 497
- ENOSYS (data in errno), 496
- ENOTBLK (data in errno), 495
- ENOTCONN (data in errno), 499
- ENOTDIR (data in errno), 495
- ENOTEMPTY (data in errno), 496
- ENOTNAM (data in errno), 500
- ENOTSOCK (data in errno), 498
- ENOTTY (data in errno), 495
- ENOTUNIQ (data in errno), 498
- enter() (scheduler method), 132
- enterabs() (scheduler method), 131
- entities (DocumentType attribute), 277
- EntityDeclHandler() (xmlparser method), 268
- entitydefs (data in htmlentitydefs), 264
- EntityResolver (class in xml.sax.handler), 289
- enumerate()
 - in module , 7
 - in module fm, 924
 - in module threading, 538
- EnumKey() (in module _winreg), 941
- EnumValue() (in module _winreg), 942
- environ
 - data in os, 396
 - data in posix, 554
- environment variables
 - !protocol;_proxy, 624
 - AUDIODEV, 708
 - BROWSER, 600
 - COLUMNS, 478
 - COMSPEC, 412, 572
 - HOMEDRIVE, 326
 - HOMEPath, 326
 - HOME, 326, 851
 - KDEDIR, 601
 - LANGUAGE, 739, 741
 - LANG, 739, 741, 749, 750
 - LC_ALL, 739, 741
 - LC_MESSAGES, 739, 741
 - LINES, 478
 - LNAME, 472
 - LOGNAME, 397, 472
 - MIXERDEV, 708
 - PAGER, 807
 - PATH, 409, 411, 415, 607, 609
 - PYTHONDOCS, 764
 - PYTHONPATH, 607, 831
 - PYTHONSTARTUP, 550, 551, 851
 - PYTHONY2K, 415, 416
 - PYTHON_DOM, 273
 - TEMP, 336
 - TIX_LIBRARY, 725
 - TMPDIR, 336, 406
 - TMP, 336, 406
 - TZ, 419, 420
 - USERNAME, 472
 - USER, 472
 - Wimp\$ScrapDir, 336
 - ftp_proxy, 617
 - gopher_proxy, 617
 - http_proxy, 617, 631
 - deleting, 398

- setting, 397
- EnvironmentError (exception in exceptions), 18
- ENXIO (data in errno), 495
- eof (shlex attribute), 761
- EOFError (exception in exceptions), 18
- EOPNOTSUPP (data in errno), 499
- EOVERFLOW (data in errno), 498
- EPERM (data in errno), 494
- EPFNOSUPPORT (data in errno), 499
- epilogue (data in email.message), 195
- EPIPE (data in errno), 496
- epoch, 415
- EPROTO (data in errno), 498
- EPROTONOSUPPORT (data in errno), 499
- EPROTOTYPE (data in errno), 498
- eq () (in module operator), 183
- ERA (data in locale), 753
- ERA_D_FMT (data in locale), 753
- ERA_D_T_FMT (data in locale), 753
- ERA_YEAR (data in locale), 753
- ERANGE (data in errno), 496
- erase () (window method), 479
- erasechar () (in module curses), 474
- EREMCHG (data in errno), 498
- EREMOTE (data in errno), 497
- EREMOTEIO (data in errno), 500
- ERESTART (data in errno), 498
- EROFS (data in errno), 496
- ERR (data in curses), 483
- errcheck (.FuncPtr attribute), 525
- errcode (ServerProxy attribute), 686
- errmsg (ServerProxy attribute), 687
- errno
 - built-in module, 395, 578
 - standard module, **494**
- ERROR (data in cd), 916
- Error
 - class in mailbox, 234
 - exception in binascii, 255
 - exception in binhex, 253
 - exception in csv, 306
 - exception in locale, 749
 - exception in shutil, 339
 - exception in sunau, 700
 - exception in turtle, 732
 - exception in uu, 256
 - exception in wave, 702
 - exception in webbrowser, 600
 - exception in xdrlib, 317
- error ()
 - method, 455
 - ErrorHandler method, 293
 - Folder method, 238
 - in module logging, 452
 - MH method, 238
 - OpenerDirector method, 626
- error
 - exception in anydbm, 375
 - exception in audioop, 693
 - exception in cd, 916
 - exception in curses, 473
 - exception in dbhash, 379
 - exception in dbm, 377
 - exception in dl, 557
 - exception in dumbdbm, 382
 - exception in gdbm, 377
 - exception in getopt, 448
 - exception in imageop, 696
 - exception in imgfile, 927
 - exception in jpeg, 928
 - exception in nis, 568
 - exception in os, 395
 - exception in re, 59
 - exception in resource, 565
 - exception in rgbimg, 706
 - exception in select, 535
 - exception in socket, 577
 - exception in struct, 63
 - exception in sunaudiodev, 931
 - exception in thread, 537
 - exception in xml.parsers.expat, 264
 - exception in zipfile, 348
 - exception in zlib, 343
- error_body (BaseHandler attribute), 616
- error_headers (BaseHandler attribute), 616
- error_leader () (shlex method), 760
- error_message_format (BaseHTTPRequestHandler attribute), 668
- error_output () (BaseHandler method), 616
- error_perm (exception in ftplib), 637
- error_proto
 - exception in ftplib, 637
 - exception in poplib, 640
- error_reply (exception in ftplib), 637
- error_status (BaseHandler attribute), 616
- error_temp (exception in ftplib), 637
- ErrorByteIndex (xmlparser attribute), 266
- ErrorCode (xmlparser attribute), 266
- errorcode (data in errno), 494
- ErrorColumnNumber (xmlparser attribute), 266
- ErrorHandler (class in xml.sax.handler), 289
- errorlevel (TarFile attribute), 355
- ErrorLineNumber (xmlparser attribute), 266
- Errors
 - logging, 450
- errors (TestResult attribute), 799
- ErrorString () (in module xml.parsers.expat), 264
- escape ()

- in module cgi, 606
 - in module re, 59
 - in module xml.sax.saxutils, 294
- escape (shlex attribute), 761
- escapechar (Dialect attribute), 306
- escapedquotes (shlex attribute), 761
- ESHUTDOWN (data in errno), 499
- ESOCKTNOSUPPORT (data in errno), 499
- ESPIPE (data in errno), 496
- ESRCH (data in errno), 495
- ESRMNT (data in errno), 497
- ESTALE (data in errno), 500
- ESTRPIPE (data in errno), 498
- ETIME (data in errno), 497
- ETIMEDOUT (data in errno), 499
- Etiny () (Context method), 160
- ETOOMANYREFS (data in errno), 499
- Etop () (Context method), 160
- ETXTBSY (data in errno), 496
- EUCLEAN (data in errno), 500
- EUNATCH (data in errno), 497
- EUSERS (data in errno), 498
- eval ()
 - built-in function, 44, 50, 146, 875
 - in module , 7
- Event () (in module threading), 539
- Event (class in threading), 544
- event () (Control method), 938
- event scheduling, 131
- events (widgets), 723
- EWOLDBLOCK (data in errno), 496
- EX_CANTCREAT (data in os), 409
- EX_CONFIG (data in os), 410
- EX_DATAERR (data in os), 409
- EX_IOERR (data in os), 410
- EX_NOHOST (data in os), 409
- EX_NOINPUT (data in os), 409
- EX_NOPERM (data in os), 410
- EX_NOTFOUND (data in os), 410
- EX_NOUSER (data in os), 409
- EX_OK (data in os), 409
- EX_OSERR (data in os), 409
- EX_OSFILE (data in os), 409
- EX_PROTOCOL (data in os), 410
- EX_SOFTWARE (data in os), 409
- EX_TEMPFAIL (data in os), 410
- EX_UNAVAILABLE (data in os), 409
- EX_USAGE (data in os), 409
- Example (class in doctest), 781
- example
 - DocTestFailure attribute, 788
 - UnexpectedException attribute, 788
- examples (DocTest attribute), 781
- exc_clear () (in module sys), 829

- exc_info () (in module sys), 828
- exc_info (UnexpectedException attribute), 788
- exc_msg (Example attribute), 782
- exc_traceback (data in sys), 829
- exc_type (data in sys), 829
- exc_value (data in sys), 829
- excel (class in csv), 305
- excel_tab (class in csv), 305
- except
 - statement, 17
- excepthook ()
 - in module sys, 610
 - in module sys, 828
- Exception (exception in exceptions), 18
- exception ()
 - method, 455
 - in module logging, 452
- exceptions
 - built-in, 3
 - in CGI scripts, 609
- exceptions (standard module), 17
- EXDEV (data in errno), 495
- exec
 - statement, 44
- exec_prefix (data in sys), 829
- execfile ()
 - built-in function, 851
 - in module , 7
- execl () (in module os), 408
- execle () (in module os), 408
- execlp () (in module os), 408
- execlpe () (in module os), 408
- executable (data in sys), 829
- Execute () (Binary method), 935
- execute () (method), 386, 389
- executemany () (method), 386, 389
- executescript () (method), 386, 389
- execv () (in module os), 408
- execve () (in module os), 408
- execvp () (in module os), 408
- execvpe () (in module os), 408
- ExFileSelectBox (class in Tix), 727
- EXFULL (data in errno), 497
- exists () (in module os.path), 326
- exit ()
 - in module sys, 829
 - in module thread, 537
- exitfunc
 - data in sys, 829
 - in sys, 839
- exp ()
 - in module cmath, 152
 - in module math, 150
- expand () (MatchObject method), 60

- expand_tabs (TextWrapper attribute), 76
- expandNode () (DOMEventStream method), 287
- expandtabs ()
 - in module string, 50
 - string method, 29
- expanduser () (in module os.path), 326
- expandvars () (in module os.path), 326
- Expat, 264
- ExpatError (exception in xml.parsers.expat), 264
- expect () (Telnet method), 658
- expires (Cookie attribute), 678
- expovariate () (in module random), 171
- expr () (in module parser), 874
- expunge () (IMAP4_stream method), 644
- extend ()
 - method, 116
 - array method, 126
 - list method, 35
- extend_path () (in module pkgutil), 870
- extended slice
 - assignment, 35
 - operation, 28
- ExtendedContext (class in decimal), 159
- extendleft () (method), 117
- extensions_map (SimpleHTTPRequestHandler attribute), 670
- External Data Representation, 315, 360
- external_attr (ZipInfo attribute), 351
- ExternalClashError (class in mailbox), 234
- ExternalEntityParserCreate () (xmlparser method), 265
- ExternalEntityRefHandler () (xmlparser method), 268
- extra (ZipInfo attribute), 351
- extract () (TarFile method), 354
- extract_cookies () (CookieJar method), 673
- extract_stack () (in module traceback), 841
- extract_tb () (in module traceback), 840
- extract_version (ZipInfo attribute), 351
- extractall () (TarFile method), 354
- ExtractError (exception in tarfile), 353
- extractfile () (TarFile method), 354
- extsep (data in os), 414

F

- F_BAVAIL (data in statvfs), 332
- F_BFREE (data in statvfs), 332
- F_BLOCKS (data in statvfs), 332
- F_BSIZE (data in statvfs), 332
- F_FAVAIL (data in statvfs), 332
- F_FFREET (data in statvfs), 332
- F_FILES (data in statvfs), 332
- F_FLAG (data in statvfs), 333
- F_FRSIZE (data in statvfs), 332

- F_NAMEMAX (data in statvfs), 333
- F_OK (data in os), 402
- fabs () (in module math), 149
- fail () (TestCase method), 798
- failIf () (TestCase method), 797
- failIfAlmostEqual () (TestCase method), 797
- failIfEqual () (TestCase method), 797
- failUnless () (TestCase method), 797
- failUnlessAlmostEqual () (TestCase method), 797
- failUnlessEqual () (TestCase method), 797
- failUnlessRaises () (TestCase method), 797
- failureException (TestCase attribute), 798
- failures (TestResult attribute), 799
- False, 23, 44
- False
 - Built-in object, 23
 - data in , 22
- false, 23
- family (socket attribute), 584
- FancyURLOpener (class in urllib), 620
- fatalError () (ErrorHandler method), 293
- faultCode (ServerProxy attribute), 686
- faultString (ServerProxy attribute), 686
- fchdir () (in module os), 402
- FCICreate () (in module msilib), 933
- fcntl () (in module fcntl), 560
- fcntl (built-in module), 39, **560**
- fcntl () (in module fcntl), 563
- fdatasync () (in module os), 400
- fdopen () (in module os), 398
- Feature (class in msilib), 938
- feature_external_ges (data in xml.sax.handler), 290
- feature_external_pes (data in xml.sax.handler), 290
- feature_namespace_prefixes (data in xml.sax.handler), 290
- feature_namespaces (data in xml.sax.handler), 289
- feature_string_interning (data in xml.sax.handler), 290
- feature_validation (data in xml.sax.handler), 290
- feed ()
 - FeedParser method, 196
 - HTMLParser method, 258
 - IncrementalParser method, 296
 - SGMLParser method, 260
 - XMLTreeBuilder method, 302
- FeedParser (class in email.parser), 196
- Fetch () (Binary method), 935
- fetch () (IMAP4_stream method), 644
- field_size_limit () (in module csv), 304
- fields (UUID attribute), 659
- fifo (class in asynchat), 597

- file
 - .ini, 310
 - .pdbrc, 807
 - .pythonrc.py, 851
 - byte-code, 865, 867, 887
 - configuration, 310
 - copying, 338
 - debugger configuration, 807
 - large files, 554
 - mime.types, 242
 - object, 39
 - path configuration, 850
 - temporary, 334
 - user configuration, 851
- file ()
 - built-in function, 39
 - in module , 7
 - in module posixfile, 564
- file
 - class descriptor attribute, 886
 - function descriptor attribute, 887
- file control
 - UNIX, 560
- file descriptor, 39
- file name
 - temporary, 334
- file object
 - POSIX, 563
- file_open () (FileHandler method), 630
- file_size (ZipInfo attribute), 351
- filecmp (standard module), **333**
- fileConfig () (in module logging), 468
- FileCookieJar (class in cookielib), 672
- FileEntry (class in Tix), 727
- FileHandler
 - class in logging, 462
 - class in urllib2, 624
- FileInput (class in fileinput), 329
- fileinput (standard module), **328**
- filelineno () (in module fileinput), 329
- filename () (in module fileinput), 329
- filename
 - Cookie attribute, 675
 - DocTest attribute, 781
 - ZipInfo attribute, 350
- filename_only (data in tabnanny), 885
- filenames
 - pathname expansion, 336
 - wildcard expansion, 337
- fileno ()
 - audio device method, 708, 931
 - file method, 39
 - in module fileinput, 329
 - in module SocketServer, 666
 - mixer device method, 710
 - Profile method, 819
 - socket method, 582
 - Telnet method, 657
- fileopen () (in module posixfile), 564
- FileSelectBox (class in Tix), 727
- FileType (data in types), 142
- FileWrapper (class in wsgiref.util), 611
- fill ()
 - in module textwrap, 76
 - in module turtle, 731
 - TextWrapper method, 77
- Filter (class in logging), 468
- filter ()
 - method, 455, 461
 - Filter method, 468
 - in module , 7
 - in module curses, 474
 - in module fnmatch, 337
- filterwarnings () (in module warnings), 837
- find ()
 - method, 548
 - DocTestFinder method, 782
 - ElementTree method, 300
 - in module gettext, 741
 - in module string, 51
 - string method, 29
- find_first () (form method), 921
- find_last () (form method), 921
- find_longest_match () (SequenceMatcher method), 69
- find_module ()
 - in module imp, 865
 - NullImporter method, 867
 - zipimporter method, 869
- find_prefix_at_end () (in module asynchat), 597
- find_user_password () (HTTPPasswordMgr method), 628
- findall ()
 - ElementTree method, 300
 - in module re, 58
 - RegexObject method, 60
- findCaller () (method), 455
- findfactor () (in module audioop), 694
- findfile () (in module test.test_support), 804
- findfit () (in module audioop), 694
- findfont () (in module fm), 924
- finditer ()
 - in module re, 58
 - RegexObject method, 60
- findmatch () (in module mailcap), 218
- findmax () (in module audioop), 694
- findtext () (ElementTree method), 300
- finish () (in module SocketServer), 667

`finish_request()` (in module `SocketServer`), 666
`first()`
 method, 381
 dbhash method, 379
 fifo method, 597
`firstChild` (Node attribute), 275
`firstkey()` (in module `gdbm`), 378
`firstweekday()` (in module `calendar`), 115
`fix()` (in module `fpformat`), 93
`fix_sentence_endings` (`TextWrapper` attribute), 77
`FL` (standard module), **923**
`fl` (built-in module), **919**
`flag_bits` (`ZipInfo` attribute), 351
`flags()` (in module `posixfile`), 564
`flags` (`RegexObject` attribute), 60
`flash()` (in module `curses`), 474
`flatten()` (Generator method), 199
`flattening`
 objects, 359
`float()`
 built-in function, 25, 50
 in module , 8
`floating point`
 literals, 25
 object, 25
`FloatingPointError`
 exception in exceptions, 19
 exception in `fpectl`, 852
`FloatType` (data in types), 141
`flock()` (in module `fcntl`), 561
`floor()`
 in module `math`, 149
 in module `math`, 25
`floordiv()` (in module `operator`), 183
`flp` (standard module), **924**
`flush()`
 method, 461, 548
 audio device method, 932
 BufferingHandler method, 466
 BZ2Compressor method, 347
 Compress method, 344
 Decompress method, 345
 file method, 39
 Mailbox method, 221
 Maildir method, 222
 MemoryHandler method, 466
 MH method, 224
 StreamHandler method, 462
 writer method, 911
`flush_softspace()` (formatter method), 910
`flushheaders()` (`MimeWriter` method), 243
`flushinp()` (in module `curses`), 474
`FlushKey()` (in module `_winreg`), 942
`fm` (built-in module), **924**
`fmod()` (in module `math`), 149
`fnmatch()` (in module `fnmatch`), 337
`fnmatch` (standard module), **337**
`fnmatchcase()` (in module `fnmatch`), 337
`Folder` (class in `mhlib`), 237
`Font Manager`, IRIS, 924
`fontpath()` (in module `fm`), 924
`forget()` (in module `test.test_support`), 804
`fork()`
 in module `os`, 410
 in module `pty`, 560
`forkpty()` (in module `os`), 410
`Form` (class in `Tix`), 728
`format()`
 method, 462
 Formatter method, 467
 in module `locale`, 751
 PrettyPrinter method, 147
`format` (`Struct` attribute), 65
`format_exc()` (in module `traceback`), 840
`format_exception()` (in module `traceback`), 841
`format_exception_only()` (in module `traceback`), 841
`format_list()` (in module `traceback`), 841
`format_stack()` (in module `traceback`), 841
`format_string()` (in module `locale`), 751
`format_tb()` (in module `traceback`), 841
`formataddr()` (in module `email.utils`), 208
`formatargspec()` (in module `inspect`), 849
`formatargvalues()` (in module `inspect`), 849
`formatdate()` (in module `email.utils`), 208
`FormatError()` (in module `ctypes`), 529
`FormatError` (class in `mailbox`), 234
`formatException()` (Formatter method), 467
`formatmonth()`
 HTMLCalendar method, 114
 TextCalendar method, 114
`Formatter` (class in `logging`), 467
`formatter`
 HTMLParser attribute, 263
 standard module, 262, **909**
`formatTime()` (Formatter method), 467
`formatting, string (%)`, 32
`formatwarning()` (in module `warnings`), 837
`formatyear()`
 HTMLCalendar method, 114
 TextCalendar method, 114
`formatyearpage()` (HTMLCalendar method), 114
`FORMS Library`, 919
`forward()` (in module `turtle`), 731
`found_terminator()` (`async_chat` method), 596
`fp` (`AddressList` attribute), 250
`fpathconf()` (in module `os`), 400

- fpectl (extension module), **852**
- fpformat (standard module), **93**
- frame (ScrolledText attribute), 730
- FrameType (data in types), 142
- freeze_form() (form method), 921
- freeze_object() (FORMS object method), 923
- frexp() (in module math), 150
- from_address() (_CData method), 530
- from_param() (_CData method), 530
- from_plittable() (Charset method), 205
- frombuf() (TarInfo method), 355
- fromchild (Popen4 attribute), 591
- fromfd() (in module socket), 580
- fromfile() (array method), 126
- fromkeys() (dictionary method), 37
- fromlist() (array method), 126
- fromordinal()
 - date method, 99
 - datetime method, 102
- fromstring()
 - array method, 126
 - in module xml.etree.ElementTree, 299
- fromtimestamp()
 - date method, 99
 - datetime method, 101
- fromunicode() (array method), 126
- fromutc() (time method), 109
- frozenset() (in module), 8
- fstat() (in module os), 400
- fstatvfs() (in module os), 400
- fsync() (in module os), 400
- FTP, 620**
 - ftplib (standard module), 636
 - protocol, 620, 636
- FTP (class in ftplib), 637
- ftp_open() (FTPHandler method), 630
- ftp_proxy, 617
- FTPHandler (class in urllib2), 624
- ftplib (standard module), **636**
- ftpmirror.py, 637
- ftruncate() (in module os), 400
- Full (exception in Queue), 133
- full() (Queue method), 133
- func (callable attribute), 182
- func_code (function object attribute), 44
- function() (in module new), 143
- functions
 - built-in, 3
- FunctionTestCase (class in unittest), 796
- FunctionType (data in types), 141
- functools (standard module), **181**
- funny_files (dircmp attribute), 334
- FutureWarning (exception in exceptions), 21

G

- G.722, 699
- gaierror (exception in socket), 578
- gammavariate() (in module random), 171
- garbage (data in gc), 844
- gather() (Textbox method), 488
- gauss() (in module random), 171
- gc (extension module), **842**
- gdbm (built-in module), 372, 375, **377**
- ge() (in module operator), 183
- gen_uuid() (in module msilib), 934
- generate_tokens() (in module tokenize), 883
- Generator (class in email.generator), 198
- GeneratorExit (exception in exceptions), 19
- GeneratorType (data in types), 141
- genops() (in module pickletools), 896
- get()
 - AddressList method, 249
 - dictionary method, 37
 - in module webbrowser, 600
 - Mailbox method, 220
 - Message method, 192
 - mixer device method, 711
 - Queue method, 133
 - SafeConfigParser method, 312, 313
- get_all()
 - Headers method, 612
 - Message method, 192
- get_app() (WSGIServer method), 613
- get_begidx() (in module readline), 550
- get_body_encoding() (Charset method), 204
- get_boundary() (Message method), 194
- get_buffer()
 - Packer method, 315
 - Unpacker method, 316
- get_charset() (Message method), 191
- get_charsets() (Message method), 195
- get_close_matches() (in module difflib), 67
- get_code() (zipimporter method), 869
- get_completer() (in module readline), 550
- get_completer_delims() (in module readline), 550
- get_content_charset() (Message method), 195
- get_content_maintype() (Message method), 193
- get_content_subtype() (Message method), 193
- get_content_type() (Message method), 193
- get_count() (in module gc), 843
- get_current_history_length() (in module readline), 549
- get_data()
 - Request method, 625
 - zipimporter method, 869
- get_date() (MaildirMessage method), 227
- get_debug() (in module gc), 843

get_default_domain() (in module nis), 568
 get_default_type() (Message method), 193
 get_dialect() (in module csv), 304
 get_directory() (in module fl), 920
 get_doctest() (DocTestParser method), 783
 get_endidx() (in module readline), 550
 get_environ() (WSGIRequestHandler method), 613
 get_examples() (DocTestParser method), 783
 get_file()
 Babyl method, 225
 Mailbox method, 220
 Maildir method, 222
 mbox method, 223
 MH method, 224
 MMDF method, 226
 get_filename()
 in module fl, 920
 Message method, 194
 get_flags()
 MaildirMessage method, 227
 mboxMessage method, 229
 MMDFMessage method, 233
 get_folder()
 Maildir method, 222
 MH method, 224
 get_from()
 mboxMessage method, 228
 MMDFMessage method, 232
 get_full_url() (Request method), 625
 get_grouped_opcodes() (SequenceMatcher method), 70
 get_history_item() (in module readline), 549
 get_history_length() (in module readline), 549
 get_host() (Request method), 625
 get_ident() (in module thread), 537
 get_info() (MaildirMessage method), 227
 get_labels()
 Babyl method, 225
 BabylMessage method, 231
 get_line_buffer() (in module readline), 549
 get_magic() (in module imp), 865
 get_matching_blocks() (SequenceMatcher method), 70
 get_message() (Mailbox method), 220
 get_method() (Request method), 625
 get_mouse() (in module fl), 920
 get_nonstandard_attr() (Cookie method), 679
 get_nowait() (Queue method), 134
 get_objects() (in module gc), 843
 get_opcodes() (SequenceMatcher method), 70
 get_origin_req_host() (Request method), 625
 get_osfhandle() (in module msvcrt), 940
 get_output_charset() (Charset method), 205
 get_param() (Message method), 193
 get_params() (Message method), 193
 get_pattern() (in module fl), 920
 get_payload() (Message method), 191
 get_position() (Unpacker method), 316
 get_reclsrc() (mixer device method), 711
 get_referents() (in module gc), 844
 get_referrers() (in module gc), 843
 get_request() (in module SocketServer), 666
 get_rgbmode() (in module fl), 919
 get_scheme() (BaseHandler method), 615
 get_selector() (Request method), 625
 get_sequences()
 MH method, 224
 MHMessage method, 230
 get_socket() (Telnet method), 657
 get_source() (zipimporter method), 869
 get_starttag_text()
 HTMLParser method, 258
 SGMLParser method, 260
 get_stderr()
 BaseHandler method, 615
 WSGIRequestHandler method, 613
 get_stdin() (BaseHandler method), 615
 get_string() (Mailbox method), 220
 get_subdir() (MaildirMessage method), 227
 get_suffixes() (in module imp), 865
 get_terminator() (async_chat method), 596
 get_threshold() (in module gc), 843
 get_token() (shlex method), 760
 get_type() (Request method), 625
 get_unixfrom() (Message method), 191
 get_visible() (BabylMessage method), 231
 getacl() (IMAP4_stream method), 644
 getaddr() (AddressList method), 249
 getaddresses() (in module email.utils), 208
 getaddrinfo() (in module socket), 578
 getaddrlist() (AddressList method), 249
 getallmatchingheaders() (AddressList method), 249
 getannotation() (IMAP4_stream method), 644
 getargspec() (in module inspect), 848
 getargvalues() (in module inspect), 849
 getatime() (in module os.path), 326
 getattr() (in module), 8
 getAttribute() (Element method), 278
 getAttributeNode() (Element method), 278
 getAttributeNodeNS() (Element method), 278
 getAttributeNS() (Element method), 278
 GetBase() (xmlparser method), 265
 getbegyx() (window method), 479
 getboolean() (SafeConfigParser method), 312
 getByteStream() (InputSource method), 297
 getcaps() (in module mailcap), 218
 getch()

- in module msvcrt, 940
 - window method, 480
- getchannels() (audio configuration method), 914
- getCharacterStream() (InputSource method), 297
- getche() (in module msvcrt), 940
- getcheckinterval() (in module sys), 829
- getChildNodes() (Node method), 899
- getChildren() (Node method), 898
- getclasstree() (in module inspect), 848
- GetColumnInfo() (Binary method), 935
- getColumnNumber() (Locator method), 296
- getcomment() (in module fm), 924
- getcomments() (in module inspect), 848
- getcompname()
 - aifc method, 698
 - AU_read method, 700
 - Wave_read method, 702
- getcomptype()
 - aifc method, 698
 - AU_read method, 700
 - Wave_read method, 702
- getConfig() (audio port method), 915
- getContentHandler() (XMLReader method), 295
- getcontext()
 - in module decimal, 158
 - MH method, 238
- getctime() (in module os.path), 326
- getcurrent() (Folder method), 238
- getcwd() (in module os), 402
- getcwdu() (in module os), 402
- getdate() (AddressList method), 250
- getdate_tz() (AddressList method), 250
- getdecoder() (in module codecs), 78
- getdefaultencoding() (in module sys), 829
- getdefaultlocale() (in module locale), 750
- getdefaulttimeout() (in module socket), 581
- getdlopenflags() (in module sys), 830
- getdoc() (in module inspect), 848
- getDOMImplementation() (in module xml.dom), 273
- getDTDHandler() (XMLReader method), 295
- getEffectiveLevel() (method), 454
- getegid() (in module os), 396
- getElementsByTagName()
 - Document method, 278
 - Element method, 278
- getElementsByTagNameNS()
 - Document method, 278
 - Element method, 278
- getencoder() (in module codecs), 78
- getEncoding() (InputSource method), 297
- getencoding() (Message method), 240
- getEntityResolver() (XMLReader method), 296
- getenv() (in module os), 397
- getErrorHandler() (XMLReader method), 296
- geteuid() (in module os), 396
- getEvent() (DOMEventStream method), 287
- getEventCategory() (NTEventLogHandler method), 465
- getEventType() (NTEventLogHandler method), 465
- getException() (SAXException method), 289
- getfd() (audio port method), 914
- getFeature() (XMLReader method), 296
- GetFieldCount() (Binary method), 936
- getfile() (in module inspect), 848
- getfilesystemencoding() (in module sys), 830
- getfillable() (audio port method), 914
- getfilled() (audio port method), 914
- getfillpoint() (audio port method), 915
- getfirst() (FieldStorage method), 605
- getfirstmatchingheader() (AddressList method), 249
- getfloat() (SafeConfigParser method), 312
- getfloatmax() (audio configuration method), 914
- getfmts() (audio device method), 709
- getfontinfo() (in module fm), 925
- getfontname() (in module fm), 924
- getfqdn() (in module socket), 579
- getframeinfo() (in module inspect), 849
- getframerate()
 - aifc method, 698
 - AU_read method, 700
 - Wave_read method, 702
- getfullname() (Folder method), 238
- getgid() (in module os), 396
- getgrall() (in module grp), 556
- getgrgid() (in module grp), 556
- getgrnam() (in module grp), 556
- getgroups() (in module os), 396
- getheader()
 - AddressList method, 249
 - HTTPResponse method, 635
- getheaders() (HTTPResponse method), 635
- gethostbyaddr()
 - in module socket, 398
 - in module socket, 579
- gethostbyname() (in module socket), 579
- gethostbyname_ex() (in module socket), 579
- gethostname()
 - in module socket, 398
 - in module socket, 579
- getincrementaldecoder() (in module codecs), 79
- getincrementalencoder() (in module codecs), 78
- getinfo()
 - audio device method, 932
 - ZipFile method, 349
- getinnerframes() (in module inspect), 849
- GetInputContext() (xmlparser method), 265

getInt () (SafeConfigParser method), 312
 getItem () (in module operator), 185
 getiterator () (ElementTree method), 300
 getKey () (window method), 480
 getLast () (Folder method), 239
 GetLastError () (in module ctypes), 529
 getLength () (Attributes method), 298
 getLevelName () (in module logging), 453
 getline () (in module linecache), 338
 getLineNumber () (Locator method), 297
 getList () (FieldStorage method), 605
 getloadavg () (in module os), 414
 getlocale () (in module locale), 751
 getLogger () (in module logging), 451
 getLoggerClass () (in module logging), 451
 getlogin () (in module os), 396
 getmaintype () (Message method), 240
 getmark ()
 aifc method, 698
 AU_read method, 701
 Wave_read method, 703
 getmarkers ()
 aifc method, 698
 AU_read method, 701
 Wave_read method, 703
 getmaxyx () (window method), 480
 getmcolor () (in module fl), 920
 getmember () (TarFile method), 353
 getmembers ()
 in module inspect, 846
 TarFile method, 353
 getMessage ()
 LogRecord method, 468
 SAXException method, 289
 getmessagefilename () (Folder method), 238
 getMessageID () (NTEventLogHandler method), 465
 getmodule () (in module inspect), 848
 getmoduleinfo () (in module inspect), 847
 getmodulename () (in module inspect), 847
 getmouse () (in module curses), 474
 getmro () (in module inspect), 849
 getmtime () (in module os.path), 326
 getName () (Thread method), 545
 getname () (Chunk method), 704
 getNameByQName () (AttributesNS method), 298
 getnameinfo () (in module socket), 579
 getNames () (Attributes method), 298
 getnames () (TarFile method), 353
 getnchannels ()
 aifc method, 697
 AU_read method, 700
 Wave_read method, 702
 getnframes ()
 aifc method, 698
 AU_read method, 700
 Wave_read method, 702
 getnode, 660
 getnode () (in module uuid), 659
 getopt () (in module getopt), 448
 getopt (standard module), **447**
 GetoptError (exception in getopt), 448
 getouterframes () (in module inspect), 849
 getoutput () (in module commands), 569
 getpagesize () (in module resource), 567
 getparam () (Message method), 240
 getparams ()
 aifc method, 698
 AU_read method, 700
 in module al, 914
 Wave_read method, 702
 getparyx () (window method), 480
 getpass () (in module getpass), 472
 getpass (standard module), **472**
 getpath () (MH method), 238
 getpeername () (socket method), 582
 getpgid () (in module os), 397
 getpgrp () (in module os), 397
 getpid () (in module os), 397
 getplist () (Message method), 240
 getpos () (HTMLParser method), 258
 getppid () (in module os), 397
 getpreferredencoding () (in module locale), 751
 getprofile () (MH method), 238
 GetProperty () (Binary method), 935
 GetProperty () (XMLReader method), 296
 GetPropertyCount () (Binary method), 935
 getprotobyname () (in module socket), 579
 getPublicId ()
 InputSource method, 297
 Locator method, 297
 getpwall () (in module pwd), 555
 getpwnam () (in module pwd), 555
 getpwuid () (in module pwd), 555
 getQNameByName () (AttributesNS method), 298
 getQNames () (AttributesNS method), 298
 getqueuesize () (audio configuration method), 914
 getquota () (IMAP4_stream method), 644
 getquotaroot () (IMAP4_stream method), 644
 getrandbits () (in module random), 170
 getrawheader () (AddressList method), 249
 getreader () (in module codecs), 79
 getrecursionlimit () (in module sys), 830
 getrefcount () (in module sys), 830
 getresponse () (HTTPResponse method), 635
 getrlimit () (in module resource), 566
 getroot () (ElementTree method), 301
 getusage () (in module resource), 567
 getsampfmt () (audio configuration method), 914

- getsample () (in module audioop), 694
- getsampwidth ()
 - aifc method, 697
 - AU_read method, 700
 - Wave_read method, 702
- getsequences () (Folder method), 239
- getsequencesfilename () (Folder method), 238
- getservbyname () (in module socket), 579
- getservbyport () (in module socket), 580
- GetSetDescriptorType (data in types), 142
- getsid () (in module os), 398
- getsignal () (in module signal), 589
- getsize ()
 - Chunk method, 704
 - in module os.path, 326
- getsizes () (in module imgfile), 928
- getslice () (in module operator), 185
- getsockname () (socket method), 582
- getsockopt () (socket method), 582
- getsource () (in module inspect), 848
- getsourcefile () (in module inspect), 848
- getsourcelines () (in module inspect), 848
- getspall () (in module spwd), 555
- getspnam () (in module spwd), 555
- getstate () (in module random), 169
- getstatus ()
 - audio port method, 915
 - CD player method, 917
 - in module commands, 569
- getstatusoutput () (in module commands), 569
- getstr () (window method), 480
- getstrwidth () (in module fm), 925
- getSubject () (SMTPHandler method), 466
- getsubtype () (Message method), 240
- GetSummaryInformation () (Binary method), 934
- getSystemId ()
 - InputSource method, 297
 - Locator method, 297
- getsyx () (in module curses), 474
- gettarinfo () (TarFile method), 354
- gettempdir () (in module tempfile), 336
- gettempprefix () (in module tempfile), 336
- getTestCaseNames () (TestLoader method), 800
- gettext ()
 - GNUTranslations method, 743
 - in module gettext, 740
 - NullTranslations method, 742
- gettext (standard module), **739**
- gettimeout () (socket method), 583
- gettrackinfo () (CD player method), 917
- getType () (Attributes method), 298
- gettype () (Message method), 240
- getuid () (in module os), 397
- geturl () (ParseResult method), 663
- getuser () (in module getpass), 472
- getValue () (Attributes method), 298
- getvalue () (StringIO method), 74
- getValueByQName () (AttributesNS method), 298
- getweakrefcount () (in module weakref), 135
- getweakrefs () (in module weakref), 135
- getwelcome ()
 - FTP method, 638
 - NNTP method, 649
 - POP3_SSL method, 641
- getwidth () (audio configuration method), 914
- getwin () (in module curses), 474
- getwindowsversion () (in module sys), 830
- getwriter () (in module codecs), 79
- getyx () (window method), 480
- gid (TarInfo attribute), 356
- GL (standard module), **927**
- gl (built-in module), **925**
- glob ()
 - Directory method, 937
 - in module glob, 336
- glob (standard module), **336**, 337
- globals () (in module), 8
- globs (DocTest attribute), 781
- gmtime () (in module time), 417
- gname (TarInfo attribute), 356
- GNOME, 744
- gnu_getopt () (in module getopt), 448
- Gopher
 - protocol, 620, 640
- gopher_open () (GopherHandler method), 630
- gopher_proxy, 617
- GopherError (exception in urllib2), 623
- GopherHandler (class in urllib2), 624
- gopherlib (standard module), **640**
- got (DocTestFailure attribute), 788
- goto () (in module turtle), 732
- Graphical User Interface, 713
- Greenwich Mean Time, 415
- grey22grey () (in module imageop), 697
- grey2grey2 () (in module imageop), 697
- grey2grey4 () (in module imageop), 697
- grey2mono () (in module imageop), 696
- grey42grey () (in module imageop), 697
- group ()
 - MatchObject method, 60
 - NNTP method, 650
- groupby () (in module itertools), 174
- groupdict () (MatchObject method), 61
- groupindex (RegexObject attribute), 60
- groups () (MatchObject method), 60
- grp (built-in module), **556**
- gt () (in module operator), 183

`guess_all_extensions()` (in module `mimetypes`), 241
`guess_extension()`
 in module `mimetypes`, 241
 `MimeTypes` method, 243
`guess_scheme()` (in module `wsgiref.util`), 610
`guess_type()`
 in module `mimetypes`, 241
 `MimeTypes` method, 243
GUI, 713
`gzip` (standard module), **345**
`GzipFile` (class in `gzip`), 345

H

`halfdelay()` (in module `curses`), 475
`handle()`
 method, 455, 461
 `BaseHTTPRequestHandler` method, 669
 in module `SocketServer`, 667
 `WSGIRequestHandler` method, 613
`handle_accept()` (dispatcher method), 593
`handle_charref()`
 `HTMLParser` method, 258
 `SGMLParser` method, 261
`handle_close()`
 `async_chat` method, 596
 dispatcher method, 593
`handle_comment()`
 `HTMLParser` method, 259
 `SGMLParser` method, 261
`handle_connect()` (dispatcher method), 593
`handle_data()`
 `HTMLParser` method, 258
 `SGMLParser` method, 260
`handle_decl()`
 `HTMLParser` method, 259
 `SGMLParser` method, 261
`handle_endtag()`
 `HTMLParser` method, 258
 `SGMLParser` method, 260
`handle_entityref()`
 `HTMLParser` method, 259
 `SGMLParser` method, 261
`handle_error()`
 dispatcher method, 593
 in module `SocketServer`, 666
`handle_expt()` (dispatcher method), 593
`handle_image()` (`HTMLParser` method), 263
`handle_one_request()` (`BaseHTTPRequestHandler` method), 669
`handle_pi()` (`HTMLParser` method), 259
`handle_read()`
 `async_chat` method, 596
 dispatcher method, 593
`handle_request()`
 in module `SocketServer`, 666
 `SimpleXMLRPCRequestHandler` method, 691
`handle_startendtag()` (`HTMLParser` method), 258
`handle_starttag()`
 `HTMLParser` method, 258
 `SGMLParser` method, 260
`handle_write()`
 `async_chat` method, 596
 dispatcher method, 593
`handleError()`
 method, 461
 `SocketHandler` method, 463, 464
`handler()` (in module `cgitb`), 610
`has_colors()` (in module `curses`), 474
`has_data()` (`Request` method), 625
`has_extn()` (`SMTP` method), 653
`has_header()`
 `Request` method, 625
 `Sniffer` method, 305
`has_ic()` (in module `curses`), 474
`has_il()` (in module `curses`), 474
`has_ipv6` (data in socket), 578
`has_key()`
 method, 381
 dictionary method, 37
 in module `curses`, 475
 `Mailbox` method, 220
 `Message` method, 192
`has_nonstandard_attr()` (`Cookie` method), 679
`has_option()` (`SafeConfigParser` method), 311
`has_section()` (`SafeConfigParser` method), 311
`hasattr()` (in module), 8
`hasAttribute()` (`Element` method), 278
`hasAttributeNS()` (`Element` method), 278
`hasAttributes()` (`Node` method), 275
`hasChildNodes()` (`Node` method), 276
`hascompare` (data in `dis`), 889
`hasconst` (data in `dis`), 889
`hasFeature()` (`DOMImplementation` method), 274
`hasfree` (data in `dis`), 889
`hash()` (in module), 8
`hashlib` (built-in module), **319**
`hashopen()` (in module `bsddb`), 380
`hasjabs` (data in `dis`), 889
`hasjrel` (data in `dis`), 889
`haslocal` (data in `dis`), 889
`hasname` (data in `dis`), 889
`have_unicode` (data in `test.test.support`), 804
`head()` (`NNTP` method), 650
`Header` (class in `email.header`), 202
`header_encode()` (`Charset` method), 205
`header_encoding` (data in `email.charset`), 204

header_offset (ZipInfo attribute), 351
 HeaderParseError (exception in email.errors), 207
 Headers (class in wsgiref.headers), 611
 headers
 MIME, 241, 602
 headers
 AddressList attribute, 250
 BaseHTTPRequestHandler attribute, 668
 ServerProxy attribute, 687
 heading() (in module turtle), 732
 heapify() (in module heapq), 122
 heapmin() (in module msvcrt), 940
 heappop() (in module heapq), 122
 heappush() (in module heapq), 122
 heapq (standard module), **121**
 heapreplace() (in module heapq), 122
 hello() (SMTP method), 653
 help
 online, 763
 help()
 in module , 8
 NNTP method, 650
 herror (exception in socket), 578
 hex() (in module), 8
 hex (UUID attribute), 659
 hexadecimal
 literals, 25
 hexbin() (in module binhex), 253
 hexdigest()
 hash method, 320
 hmac method, 321
 md5 method, 322
 sha method, 323
 hexdigits (data in string), 47
 hexlify() (in module binascii), 254
 hexversion (data in sys), 830
 hidden() (method), 491
 hide() (method), 491
 hide_cookie2 (LWPCookieJar attribute), 676
 hide_form() (form method), 920
 hide_object() (FORMS object method), 923
 HierarchyRequestErr (exception in xml.dom), 280
 HIGHEST_PROTOCOL (data in pickle), 361
 hline() (window method), 480
 HList (class in Tix), 727
 hls_to_rgb() (in module colorsys), 705
 hmac (standard module), **321**
 HOME, 326, 851
 HOMEDRIVE, 326
 HOMEPATH, 326
 hook_compressed() (in module fileinput), 329
 hook_encoded() (in module fileinput), 330
 hosts (netrc attribute), 314
 hotshot (standard module), **819**
 hotshot.stats (standard module), **820**
 hour
 datetime attribute, 102
 time attribute, 106
 HRESULT (class in ctypes), 532
 hsv_to_rgb() (in module colorsys), 705
 HTML, 257, 262, 620
 HTMLCalendar (class in calendar), 114
 HtmlDiff (class in difflib), 66
 htмлentitydefs (standard module), **264**
 htмлlib (standard module), **262**, 620
 HTMLParseError
 exception in htмлlib, 263
 exception in HTMLParser, 258
 HTMLParser
 class in htмлlib, 263, 909
 class in HTMLParser, 257
 standard module, **257**
 htonl() (in module socket), 580
 htons() (in module socket), 580
 HTTP
 httplib (standard module), 632
 protocol, 602, 620, 632, 667
 http_error_301() (HTTPRedirectHandler method), 628
 http_error_302() (HTTPRedirectHandler method), 628
 http_error_303() (HTTPRedirectHandler method), 628
 http_error_307() (HTTPRedirectHandler method), 628
 http_error_401()
 HTTPBasicAuthHandler method, 629
 HTTPODigestAuthHandler method, 629
 http_error_407()
 ProxyBasicAuthHandler method, 629
 ProxyDigestAuthHandler method, 629
 http_error_auth_reged()
 AbstractBasicAuthHandler method, 629
 AbstractDigestAuthHandler method, 629
 http_error_default() (BaseHandler method), 627
 http_open() (HTTPHandler method), 629
 HTTP_PORT (data in httplib), 633
 http-proxy, 617, 631
 http_version (BaseHandler attribute), 617
 HTTPBasicAuthHandler (class in urllib2), 624
 HTTPConnection (class in httplib), 632
 HTTPCookieProcessor (class in urllib2), 624
 httpd, 667
 HTTPDefaultErrorHandler (class in urllib2), 623
 HTTPDigestAuthHandler (class in urllib2), 624
 HTTPError (exception in urllib2), 623
 HTTPException (exception in httplib), 633

HTTPHandler
 class in logging, 466
 class in urllib2, 624
 httplib (standard module), **632**
 HTTPPasswordMgr (class in urllib2), 624
 HTTPPasswordMgrWithDefaultRealm (class in urllib2), 624
 HTTPRedirectHandler (class in urllib2), 624
 HTTPResponse (class in httplib), 633
 https_open() (HTTPSHandler method), 629
 HTTPS_PORT (data in httplib), 633
 HTTPSConnection (class in httplib), 632
 HTTPServer (class in BaseHTTPServer), 668
 HTTPSHandler (class in urllib2), 624
 hypertext, 262
 hypot() (in module math), 150

I
 I (data in re), 57
 I/O control
 buffering, 10, 398, 582
 POSIX, 558
 tty, 558
 UNIX, 560
 iadd() (in module operator), 185
 iand() (in module operator), 185
 ibufcount() (audio device method), 932
 iconcat() (in module operator), 185
 id()
 in module , 8
 TestCase method, 798
 idcok() (window method), 480
 ident (data in cd), 916
 identchars (Cmd attribute), 758
 idiv() (in module operator), 185
 Idle, 733
 idlok() (window method), 480
 IEEE-754, 852
 if
 statement, 23
 ifilter() (in module itertools), 174
 ifilterfalse() (in module itertools), 175
 ifloordiv() (in module operator), 185
 iglob() (in module glob), 336
 ignorableWhitespace() (ContentHandler method), 292
 ignore_errors() (in module codecs), 79
 IGNORE_EXCEPTION_DETAIL (data in doctest), 773
 ignore_zeros (TarFile attribute), 355
 IGNORECASE (data in re), 57
 ihave() (NNTP method), 651
 ihooks (standard module), 3
 ilshift() (in module operator), 186
 imageop (built-in module), **696**

 imap() (in module itertools), 175
 IMAP4
 protocol, 642
 IMAP4 (class in imaplib), 642
 IMAP4.abort (exception in imaplib), 642
 IMAP4.error (exception in imaplib), 642
 IMAP4.readonly (exception in imaplib), 642
 IMAP4.SSL
 protocol, 642
 IMAP4_SSL (class in imaplib), 642
 IMAP4_stream
 protocol, 642
 IMAP4_stream (class in imaplib), 643
 imaplib (standard module), **642**
 imgfile (built-in module), **927**
 imghdr (standard module), **706**
 immedok() (window method), 480
 ImmutableSet (class in sets), 128
 imod() (in module operator), 186
 imp (built-in module), 3, **865**
 import
 statement, 3, 865
 Import module, 734
 ImportError (exception in exceptions), 19
 ImportWarning (exception in exceptions), 21
 ImproperConnectionState (exception in httplib), 633
 imul() (in module operator), 186
 in
 operator, 24, 28
 in_dll() (.CData method), 530
 in_table_a1() (in module stringprep), 92
 in_table_b1() (in module stringprep), 92
 in_table_c11() (in module stringprep), 92
 in_table_c11_c12() (in module stringprep), 92
 in_table_c12() (in module stringprep), 92
 in_table_c21() (in module stringprep), 92
 in_table_c21_c22() (in module stringprep), 92
 in_table_c22() (in module stringprep), 92
 in_table_c3() (in module stringprep), 92
 in_table_c4() (in module stringprep), 92
 in_table_c5() (in module stringprep), 92
 in_table_c6() (in module stringprep), 92
 in_table_c7() (in module stringprep), 92
 in_table_c8() (in module stringprep), 92
 in_table_c9() (in module stringprep), 93
 in_table_d1() (in module stringprep), 93
 in_table_d2() (in module stringprep), 93
 INADDR_* (data in socket), 578
 inch() (window method), 480
 Incomplete (exception in binascii), 255
 IncompleteRead (exception in httplib), 633
 IncrementalDecoder (class in codecs), 82
 IncrementalEncoder (class in codecs), 81

IncrementalParser (class in xml.sax.xmlreader), 294
 indent (Example attribute), 782
 indentation, 735
 Independent JPEG Group, 928
 index ()
 array method, 126
 in module operator, 184
 in module string, 51
 string method, 29
 index (data in cd), 916
 index () (list method), 35
 IndexError (exception in exceptions), 19
 indexOf () (in module operator), 185
 IndexSizeErr (exception in xml.dom), 280
 inet_aton () (in module socket), 580
 inet_ntoa () (in module socket), 580
 inet_ntop () (in module socket), 581
 inet_pton () (in module socket), 581
 Inexact (class in decimal), 162
 infile (shlex attribute), 761
 Infinity, 8, 50
 info ()
 method, 455
 in module logging, 452
 NullTranslations method, 742
 infolist () (ZipFile method), 349
 InfoSeek Corporation, 811
 ini file, 310
 init ()
 in module fm, 924
 in module mimetypes, 241
 init_builtin () (in module imp), 867
 init_color () (in module curses), 475
 init_database () (in module msilib), 934
 init_frozen () (in module imp), 867
 init_pair () (in module curses), 475
 inited (data in mimetypes), 241
 initial_indent (TextWrapper attribute), 77
 initscr () (in module curses), 475
 input ()
 built-in function, 833
 in module , 9
 in module fileinput, 328
 input_charset (data in email.charset), 204
 input_codec (data in email.charset), 204
 InputOnly (class in Tix), 728
 InputSource (class in xml.sax.xmlreader), 295
 InputType (data in cStringIO), 75
 insch () (window method), 480
 insdelln () (window method), 480
 insert ()
 array method, 126
 list method, 35
 insert_text () (in module readline), 549
 insertBefore () (Node method), 276
 insertln () (window method), 480
 insnstr () (window method), 480
 insort () (in module bisect), 124
 insort_left () (in module bisect), 124
 insort_right () (in module bisect), 124
 inspect (standard module), **844**
 insstr () (window method), 480
 install ()
 in module gettext, 741
 NullTranslations method, 743
 install_opener () (in module urllib2), 622
 instance () (in module new), 143
 instancemethod () (in module new), 143
 InstanceType (data in types), 142
 instr () (window method), 481
 instream (shlex attribute), 761
 int ()
 built-in function, 25
 in module , 9
 int (UUID attribute), 659
 Int2AP () (in module imaplib), 643
 integer
 division, 25
 division, long, 25
 literals, 25
 literals, long, 25
 object, 25
 types, operations on, 26
 Integrated Development Environment, 733
 Intel/DVI ADPCM, 693
 interact ()
 in module code, 855
 InteractiveConsole method, 856
 Telnet method, 657
 InteractiveConsole (class in code), 855
 InteractiveInterpreter (class in code), 855
 intern () (in module), 17
 internal_attr (ZipInfo attribute), 351
 Internaldate2tuple () (in module imaplib), 643
 internalSubset (DocumentType attribute), 277
 Internet, 599
 Internet Config, 617
 interpolation, string (%), 32
 InterpolationDepthError (exception in ConfigParser), 311
 InterpolationError (exception in ConfigParser), 311
 InterpolationMissingOptionError (exception in ConfigParser), 311
 InterpolationSyntaxError (exception in ConfigParser), 311
 interpreter prompts, 832

- interrupt () (method), 388
- interrupt_main () (in module thread), 537
- intro (Cmd attribute), 759
- IntType (data in types), 141
- InuseAttributeErr (exception in xml.dom), 280
- inv () (in module operator), 183
- InvalidAccessErr (exception in xml.dom), 280
- InvalidCharacterErr (exception in xml.dom), 280
- InvalidModificationErr (exception in xml.dom), 280
- InvalidOperation (class in decimal), 162
- InvalidStateErr (exception in xml.dom), 281
- InvalidURL (exception in httplib), 633
- invert () (in module operator), 183
- ioctl () (in module fcntl), 561
- IOError (exception in exceptions), 19
- ior () (in module operator), 186
- IP_* (data in socket), 578
- ipow () (in module operator), 186
- IPPORT_* (data in socket), 578
- IPPROTO_* (data in socket), 578
- IPV6_* (data in socket), 578
- irepeat () (in module operator), 186
- IRIS Font Manager, 924
- IRIX
 - threads, 538
- irshift () (in module operator), 186
- is
 - operator, 24
- is not
 - operator, 24
- is_ () (in module operator), 183
- is_blocked () (DefaultCookiePolicy method), 677
- is_builtin () (in module imp), 867
- IS_CHARACTER_JUNK () (in module difflib), 68
- is_data () (MultiFile method), 246
- is_empty () (fifo method), 597
- is_expired () (Cookie method), 679
- is_frozen () (in module imp), 867
- is_hop_by_hop () (in module wsgiref.util), 611
- is_jython (data in test.test.support), 804
- IS_LINE_JUNK () (in module difflib), 68
- is_linetouched () (window method), 481
- is_multipart () (Message method), 190
- is_not () (in module operator), 183
- is_not_allowed () (DefaultCookiePolicy method), 677
- is_package () (zipimporter method), 869
- is_resource_enabled () (in module test.test.support), 804
- is_tarfile () (in module tarfile), 352
- is_unverifiable () (Request method), 625
- is_wintouched () (window method), 481
- is_zipfile () (in module zipfile), 348
- isabs () (in module os.path), 326
- isAlive () (Thread method), 545
- isalnum ()
 - in module curses.ascii, 489
 - string method, 29
- isalpha ()
 - in module curses.ascii, 489
 - string method, 29
- isascii () (in module curses.ascii), 489
- isatty ()
 - Chunk method, 704
 - file method, 39
 - in module os, 400
- isblank () (in module curses.ascii), 489
- isblk () (TarInfo method), 356
- isbuiltin () (in module inspect), 847
- isCallable () (in module operator), 186
- ischr () (TarInfo method), 356
- isclass () (in module inspect), 847
- iscntrl () (in module curses.ascii), 490
- iscode () (in module inspect), 847
- iscomment () (AddressList method), 249
- isctrl () (in module curses.ascii), 490
- isDaemon () (Thread method), 545
- isdatadescriptor () (in module inspect), 847
- isdev () (TarInfo method), 356
- isdigit ()
 - in module curses.ascii, 490
 - string method, 30
- isdir ()
 - in module os.path, 326
 - TarInfo method, 356
- iselement () (in module xml.etree.ElementTree), 299
- isenabled () (in module gc), 843
- isEnabledFor () (method), 454
- isendwin () (in module curses), 475
- ISEOF () (in module token), 883
- isexpr ()
 - AST method, 876
 - in module parser, 875
- isfifo () (TarInfo method), 356
- isfile ()
 - in module os.path, 326
 - TarInfo method, 356
- isfirstline () (in module fileinput), 329
- iframe () (in module inspect), 847
- isfunction () (in module inspect), 847
- isgetsetdescriptor () (in module inspect), 848
- isgraph () (in module curses.ascii), 490
- isheader () (AddressList method), 249
- isinstance () (in module), 9
- iskeyword () (in module keyword), 883
- islast () (AddressList method), 249
- isleap () (in module calendar), 115

- `islice()` (in module `itertools`), 175
- `islink()` (in module `os.path`), 326
- `islnk()` (`TarInfo` method), 356
- `islower()`
 - in module `curses.ascii`, 490
 - string method, 30
- `isMappingType()` (in module `operator`), 187
- `ismemberdescriptor()` (in module `inspect`), 848
- `ismeta()` (in module `curses.ascii`), 490
- `ismethod()` (in module `inspect`), 847
- `ismethoddescriptor()` (in module `inspect`), 847
- `ismodule()` (in module `inspect`), 847
- `ismount()` (in module `os.path`), 327
- `ISNONTERMINAL()` (in module `token`), 883
- `isNumberType()` (in module `operator`), 187
- `isocalendar()`
 - date method, 100
 - datetime method, 105
- `isoformat()`
 - date method, 100
 - datetime method, 105
 - time method, 107
- `isolation_level` (attribute), 386
- `isowekday()`
 - date method, 100
 - datetime method, 105
- `isprint()` (in module `curses.ascii`), 490
- `ispunct()` (in module `curses.ascii`), 490
- `isqueued()` (in module `fl`), 920
- `isreadable()`
 - in module `pprint`, 146
 - `PrettyPrinter` method, 146
- `isrecursive()`
 - in module `pprint`, 146
 - `PrettyPrinter` method, 146
- `isreg()` (`TarInfo` method), 356
- `isReservedKey()` (`Morsel` method), 682
- `isroutine()` (in module `inspect`), 847
- `isSameNode()` (`Node` method), 276
- `isSequenceType()` (in module `operator`), 187
- `isSet()` (`Event` method), 544
- `isspace()`
 - in module `curses.ascii`, 490
 - string method, 30
- `isstdin()` (in module `fileinput`), 329
- `issubclass()` (in module), 9
- `issuer()` (method), 584
- `issuite()`
 - `AST` method, 876
 - in module `parser`, 876
- `issym()` (`TarInfo` method), 356
- `ISTERMINAL()` (in module `token`), 883
- `istitle()` (string method), 30
- `istraceback()` (in module `inspect`), 847
- `isub()` (in module `operator`), 186
- `isupper()`
 - in module `curses.ascii`, 490
 - string method, 30
- `isxdigit()` (in module `curses.ascii`), 490
- `item()`
 - `NamedNodeMap` method, 279
 - `NodeList` method, 276
- `itemgetter()` (in module `operator`), 187
- `items()`
 - dictionary method, 37
 - `Mailbox` method, 220
 - `Message` method, 192
 - `SafeConfigParser` method, 312, 313
- `itemsizes` (array attribute), 126
- `iter()` (in module), 9
- `IterableUserDict` (class in `UserDict`), 139
- iterator protocol, 26
- `iterdecode()` (in module `codecs`), 80
- `iterencode()` (in module `codecs`), 80
- `iteritems()`
 - dictionary method, 37
 - `Mailbox` method, 220
- `iterkeyrefs()` (`WeakKeyDictionary` method), 136
- `iterkeys()`
 - dictionary method, 37
 - `Mailbox` method, 220
- `itermonthdates()` (`Calendar` method), 113
- `itermonthdays()` (`Calendar` method), 113
- `itermonthdays2()` (`Calendar` method), 113
- `iterparse()` (in module `xml.etree.ElementTree`), 299
- `itertools` (standard module), **172**
- `intervaluerefs()` (`WeakValueDictionary` method), 136
- `intervalues()`
 - dictionary method, 37
 - `Mailbox` method, 220
- `iterweekdays()` (`Calendar` method), 113
- `itruediv()` (in module `operator`), 186
- `ixor()` (in module `operator`), 186
- `izip()` (in module `itertools`), 176

J

- Jansen, Jack, 256
- `java_ver()` (in module `platform`), 493
- JFIF, 928
- `join()`
 - in module `os.path`, 327
 - in module `string`, 51
 - `Queue` method, 134
 - string method, 30
 - `Thread` method, 545
- `joinfields()` (in module `string`), 51
- `jpeg` (built-in module), **928**

js_output ()
 BaseCookie method, 681
 Morsel method, 682
jumpahead () (in module random), 170

K

kbhit () (in module msvcrt), 940
KDEDIR, 601
key (Morsel attribute), 681
KeyboardInterrupt (exception in exceptions), 19
KeyError (exception in exceptions), 19
keyname () (in module curses), 475
keypad () (window method), 481
keyrefs () (WeakKeyDictionary method), 136
keys ()
 method, 381
 dictionary method, 37
 Mailbox method, 220
 Message method, 192
keyword (standard module), **883**
keywords (dict attribute), 182
kill () (in module os), 410
killchar () (in module curses), 475
killpg () (in module os), 410
knee (module), 868
knownfiles (data in mimetypes), 242
Kuchling, Andrew, 319
kwlist (data in keyword), 883

L

L (data in re), 57
LabelEntry (class in Tix), 726
LabelFrame (class in Tix), 726
LambdaType (data in types), 141
LANG, 739, 741, 749, 750
LANGUAGE, 739, 741
language
 C, 25
large files, 554
LargeZipFile (exception in zipfile), 348
last ()
 method, 381
 dbhash method, 379
 NNTP method, 650
last (MultiFile attribute), 246
last_traceback (data in sys), 831
last_type (data in sys), 831
last_value (data in sys), 831
lastChild (Node attribute), 275
lastcmd (Cmd attribute), 759
lastgroup (MatchObject attribute), 61
lastindex (MatchObject attribute), 61
lastpart () (MimeWriter method), 244
LC_ALL, 739, 741

LC_ALL (data in locale), 752
LC_COLLATE (data in locale), 752
LC_CTYPE (data in locale), 752
LC_MESSAGES, 739, 741
LC_MESSAGES (data in locale), 752
LC_MONETARY (data in locale), 752
LC_NUMERIC (data in locale), 752
LC_TIME (data in locale), 752
lchown () (in module os), 403
ldexp () (in module math), 150
ldgettext () (in module gettext), 740
ldngettext () (in module gettext), 740
le () (in module operator), 183
leapdays () (in module calendar), 115
leaveok () (window method), 481
left () (in module turtle), 731
left_list (dircmp attribute), 334
left_only (dircmp attribute), 334
len ()
 built-in function, 28, 37
 in module , 9
length
 NamedNodeMap attribute, 279
 NodeList attribute, 276
letters (data in string), 48
level (MultiFile attribute), 246
lexists () (in module os.path), 326
lgettext ()
 GNUTranslations method, 743
 in module gettext, 740
 NullTranslations method, 742
libc_ver () (in module platform), 494
library (data in dbm), 377
LibraryLoader (class in ctypes), 524
light-weight processes, 536
lin2adpcm () (in module audioop), 694
lin2alaw () (in module audioop), 694
lin2lin () (in module audioop), 694
lin2ulaw () (in module audioop), 694
line () (Dialog method), 938
line-buffered I/O, 10
line_num (csv reader attribute), 307
linecache (standard module), **338**
lineno () (in module fileinput), 329
lineno
 class descriptor attribute, 886
 DocTest attribute, 781
 Example attribute, 782
 ExpatriError attribute, 269
 function descriptor attribute, 887
 shlex attribute, 761
LINES, 478
linesep (data in os), 415
lineterminator (Dialect attribute), 306

- link() (in module os), 403
- linkname (TarInfo attribute), 355
- list
 - object, 27, 34
 - type, operations on, 35
- list()
 - IMAP4_stream method, 644
 - in module , 9
 - NNTP method, 649
 - POP3_SSL method, 641
 - TarFile method, 354
- list_dialects() (in module csv), 304
- list_folders()
 - Maildir method, 222
 - MH method, 224
- listallfolders() (MH method), 238
- listallsubfolders() (MH method), 238
- listdir()
 - in module dircache, 340
 - in module os, 403
- listen()
 - dispatcher method, 594
 - in module logging, 469
 - socket method, 582
- listfolders() (MH method), 238
- listmessages() (Folder method), 238
- ListNoteBook (class in Tix), 728
- listsubfolders() (MH method), 238
- ListType (data in types), 141
- literals
 - complex number, 25
 - floating point, 25
 - hexadecimal, 25
 - integer, 25
 - long integer, 25
 - numeric, 25
 - octal, 25
- LittleEndianStructure (class in ctypes), 533
- ljust()
 - in module string, 52
 - string method, 30
- LK_LOCK (data in msvcrt), 940
- LK_NBLCK (data in msvcrt), 940
- LK_NBRLCK (data in msvcrt), 940
- LK_RLCK (data in msvcrt), 940
- LK_UNLCK (data in msvcrt), 940
- LNAME, 472
- lngettext()
 - GNUTranslations method, 744
 - in module gettext, 740
 - NullTranslations method, 742
- load()
 - BaseCookie method, 681
 - FileCookieJar method, 674
 - in module hotshot.stats, 820
 - in module marshal, 374
 - in module pickle, 361
 - Unpickler method, 363
- load_compiled() (in module imp), 867
- load_dynamic() (in module imp), 867
- load_module()
 - in module imp, 866
 - zipimporter method, 869
- load_source() (in module imp), 867
- LoadError (exception in cookielib), 672
- LoadLibrary() (LibraryLoader method), 524
- loads()
 - in module marshal, 375
 - in module pickle, 361
 - in module xmlrpclib, 687
- loadTestsFromModule() (TestLoader method), 800
- loadTestsFromName() (TestLoader method), 800
- loadTestsFromNames() (TestLoader method), 800
- loadTestsFromTestCase() (TestLoader method), 800
- local (class in threading), 539
- localcontext() (in module decimal), 158
- LOCALE (data in re), 57
- locale (standard module), **749**
- localeconv() (in module locale), 749
- LocaleHTMLCalendar (class in calendar), 115
- LocaleTextCalendar (class in calendar), 114
- localName
 - Attr attribute, 279
 - Node attribute, 275
- locals() (in module), 9
- localtime() (in module time), 417
- Locator (class in xml.sax.xmlreader), 295
- Lock() (in module threading), 539
- lock()
 - Babyl method, 225
 - in module posixfile, 564
 - Mailbox method, 221
 - Maildir method, 222
 - mbox method, 223
 - MH method, 224
 - MMDF method, 226
 - mutex method, 133
- lock_held() (in module imp), 866
- locked() (lock method), 537
- lockf()
 - in module fcntl, 561
 - in module fcntl, 563
- locking() (in module msvcrt), 939
- LockType (data in thread), 537
- log()
 - method, 455

- in module cmath, 152
 - in module logging, 452
 - in module math, 150
- log10()
 - in module cmath, 152
 - in module math, 150
- log_date_time_string() (BaseHTTPRequestHandler method), 670
- log_error() (BaseHTTPRequestHandler method), 669
- log_exception() (BaseHandler method), 616
- log_message() (BaseHTTPRequestHandler method), 669
- log_request() (BaseHTTPRequestHandler method), 669
- logging
 - Errors, 450
- logging (standard module), **450**
- login()
 - FTP method, 638
 - IMAP4_stream method, 644
 - SMTP method, 653
- login_cram_md5() (IMAP4_stream method), 644
- LOGNAME, 397, 472
- lognormvariate() (in module random), 171
- logout() (IMAP4_stream method), 644
- LogRecord (class in logging), 468
- long
 - integer division, 25
 - integer literals, 25
- long()
 - built-in function, 25, 50
 - in module , 9
- long integer
 - object, 25
- longimagedata() (in module rgbimg), 706
- longname() (in module curses), 475
- longstoimage() (in module rgbimg), 706
- LongType (data in types), 141
- lookup()
 - in module codecs, 78
 - in module unicodedata, 90
- lookup_error() (in module codecs), 79
- LookupError (exception in exceptions), 18
- loop() (in module asyncore), 592
- lower()
 - in module string, 51
 - string method, 30
- lowercase (data in string), 48
- lseek() (in module os), 400
- lshift() (in module operator), 184
- lstat() (in module os), 403
- lstrip()
 - in module string, 51

- string method, 30
- lsub() (IMAP4_stream method), 644
- lt() (in module operator), 182
- Lundh, Fredrik, 928
- LWPCookieJar (class in cookielib), 675

M

- M (data in re), 57
- mac_ver() (in module platform), 494
- machine() (in module platform), 492
- macros (netrc attribute), 314
- Mailbox (class in mailbox), 219
- mailbox
 - module, **218**
 - standard module, 247
- mailcap (standard module), **218**
- Maildir (class in mailbox), 221
- MaildirMessage (class in mailbox), 226
- MailmanProxy (class in smtpd), 656
- main()
 - in module py_compile, 887
 - in module unittest, 796
- major() (in module os), 404
- make_cookies() (CookieJar method), 674
- make_file() (in module difflib), 66
- make_form() (in module fl), 919
- make_header() (in module email.header), 203
- make_msgid() (in module email.utils), 209
- make_parser() (in module xml.sax), 288
- make_server() (in module wsgiref.simple_server), 612
- make_table() (in module difflib), 66
- makedev() (in module os), 404
- makedirs() (in module os), 404
- makefile() (socket method), 582
- makefolder() (MH method), 238
- makeLogRecord() (in module logging), 453
- makePickle() (SocketHandler method), 464
- makeRecord() (method), 455
- makeSocket()
 - DatagramHandler method, 464
 - SocketHandler method, 464
- maketrans() (in module string), 50
- map() (in module), 10
- map_table_b2() (in module stringprep), 92
- map_table_b3() (in module stringprep), 92
- mapcolor() (in module fl), 920
- mapping
 - object, 37
 - types, operations on, 37
- mapping() (Control method), 938
- maps() (in module nis), 568
- marshal (built-in module), **373**
- marshalling

- objects, 359
- masking
 - operations, 26
- match ()
 - in module nis, 568
 - in module re, 58
 - RegexObject method, 59
- math (built-in module), 25, **149**, 152
- max ()
 - built-in function, 28
 - Context method, 161
 - Decimal method, 157
 - in module , 10
 - in module audioop, 695
- max
 - date attribute, 99
 - datetime attribute, 102
 - time attribute, 106
 - timedelta attribute, 97
- MAX_INTERPOLATION_DEPTH (data in ConfigParser), 311
- maxarray (Repr attribute), 147
- maxdeque (Repr attribute), 147
- maxdict (Repr attribute), 147
- maxfrozenset (Repr attribute), 147
- maxint (data in sys), 831
- MAXLEN (data in mimify), 244
- maxlevel (Repr attribute), 147
- maxlist (Repr attribute), 147
- maxlong (Repr attribute), 147
- maxother (Repr attribute), 148
- maxpp () (in module audioop), 695
- maxset (Repr attribute), 147
- maxstring (Repr attribute), 147
- maxtuple (Repr attribute), 147
- maxunicode (data in sys), 831
- MAXYEAR (data in datetime), 96
- MB_ICONASTERISK (data in winsound), 946
- MB_ICONEXCLAMATION (data in winsound), 946
- MB_ICONHAND (data in winsound), 946
- MB_ICONQUESTION (data in winsound), 946
- MB_OK (data in winsound), 946
- mbox (class in mailbox), 223
- mboxMessage (class in mailbox), 228
- md5 () (in module md5), 322
- md5 (built-in module), **321**
- MemberDescriptorType (data in types), 142
- memmove () (in module ctypes), 529
- MemoryError (exception in exceptions), 19
- MemoryHandler (class in logging), 466
- memset () (in module ctypes), 529
- Message
 - class in email.message, 190
 - class in mailbox, 226
 - class in mhlib, 237
 - class in mimetools, 239
 - class in rfc822, 247
 - in module mimetools, 669
- message digest, MD5, 319, 321
- message_from_file () (in module email.parser), 197
- message_from_string () (in module email.parser), 197
- MessageBeep () (in module winsound), 945
- MessageClass (BaseHTTPRequestHandler attribute), 669
- MessageError (exception in email.errors), 206
- MessageParseError (exception in email.errors), 206
- meta () (in module curses), 475
- Meter (class in Tix), 726
- method
 - object, 43
- methods
 - string, 29
- methods (class descriptor attribute), 886
- MethodType (data in types), 142
- MH
 - class in mailbox, 223
 - class in mhlib, 237
- mhlib (standard module), **237**
- MHMailbox (class in mailbox), 235
- MHMessage (class in mailbox), 230
- microsecond
 - datetime attribute, 102
 - time attribute, 106
- MIME
 - base64 encoding, 251
 - content type, 241
 - headers, 241, 602
 - quoted-printable encoding, 255
- mime_decode_header () (in module mimify), 244
- mime_encode_header () (in module mimify), 244
- MIMEApplication (class in email.mime.text), 200
- MIMEAudio (class in email.mime.text), 200
- MIMEBase (class in email.mime.text), 200
- MIMEImage (class in email.mime.text), 201
- MIMEMessage (class in email.mime.text), 201
- MIMEMultipart (class in email.mime.text), 200
- MIMENonMultipart (class in email.mime.text), 200
- MIMEText (class in email.mime.text), 201
- mimetools (standard module), **239**, 617
- MimeTypes (class in mimetypes), 242
- mimetypes (standard module), **241**
- MimeWriter
 - class in MimeWriter, 243
 - standard module, **243**
- mimify () (in module mimify), 244
- mimify (standard module), **244**

- min()
 - built-in function, 28
 - Context method, 161
 - Decimal method, 158
 - in module , 10
- min
 - date attribute, 99
 - datetime attribute, 102
 - time attribute, 106
 - timedelta attribute, 97
- minmax() (in module audioop), 694
- minor() (in module os), 404
- minus() (Context method), 161
- minute
 - datetime attribute, 102
 - time attribute, 106
- MINYEAR (data in datetime), 96
- mirrored() (in module unicodedata), 90
- misc_header (Cmd attribute), 759
- MissingSectionHeaderError (exception in ConfigParser), 311
- MIXERDEV, 708
- mkd() (FTP method), 639
- mkdir() (in module os), 404
- mkdtemp() (in module tempfile), 335
- mkfifo() (in module os), 404
- mknod() (in module os), 404
- mkstemp() (in module tempfile), 335
- mktemp() (in module tempfile), 335
- mktime() (in module time), 417
- mktime_tz()
 - in module email.utils, 208
 - in module rfc822, 248
- mmap() (in module mmap), 547
- mmap (built-in module), **547**
- MMDF (class in mailbox), 226
- MmdfMailbox (class in mailbox), 235
- MMDFMessage (class in mailbox), 232
- mod() (in module operator), 184
- mode
 - audio device attribute, 710
 - file attribute, 41
 - TarInfo attribute, 355
- modf() (in module math), 150
- modified() (RobotFileParser method), 313
- Modify() (Binary method), 935
- module
 - search path, 338, 831, 850
- module() (in module new), 143
- module
 - class descriptor attribute, 886
 - function descriptor attribute, 886
- ModuleFinder (class in modulefinder), 871
- modulefinder (standard module), **870**
- modules (data in sys), 831
- ModuleType (data in types), 142
- MON_1 ... MON_12 (data in locale), 753
- mono2grey() (in module imageop), 696
- month() (in module calendar), 115
- month
 - date attribute, 99
 - datetime attribute, 102
- month_abbr (data in calendar), 116
- month_name (data in calendar), 116
- monthcalendar() (in module calendar), 115
- monthdatescalendar() (Calendar method), 113
- monthdays2calendar() (Calendar method), 114
- monthdayscalendar() (Calendar method), 114
- montrange() (in module calendar), 115
- more() (simple_producer method), 597
- Morsel (class in Cookie), 681
- mouseinterval() (in module curses), 475
- mousemask() (in module curses), 475
- move()
 - method, 491, 548
 - in module shutil, 339
 - window method, 481
- movemessage() (Folder method), 239
- MozillaCookieJar (class in cookielib), 675
- msftoblock() (CD player method), 917
- msftoframe() (in module cd), 916
- msg() (Telnet method), 657
- msg (data in httpplib), 635
- MSG_* (data in socket), 578
- msi, 933
- msilib (standard module), **933**
- msvcrt (built-in module), **939**
- mt_interact() (Telnet method), 657
- mtime() (RobotFileParser method), 313
- mtime (TarInfo attribute), 355
- mul()
 - in module audioop, 695
 - in module operator, 184
- MultiCall (class in xmlrpclib), 687
- MultiFile (class in multifile), 245
- multifile (standard module), **245**
- MULTILINE (data in re), 57
- MultipartConversionError (exception in email.errors), 207
- multiply() (Context method), 161
- mutable
 - sequence types, 34
 - sequence types, operations on, 35
- MutableString (class in UserString), 140
- mutex
 - class in mutex, 132
 - standard module, **132**
- mvderwin() (window method), 481

mvwin() (window method), 481
myrights() (IMAP4_stream method), 645

N

name() (in module unicodedata), 90
name

- Attr attribute, 279
- audio device attribute, 710
- class descriptor attribute, 886
- Cookie attribute, 678
- data in os, 396
- DocTest attribute, 781
- DocumentType attribute, 277
- file attribute, 41
- function descriptor attribute, 887
- TarInfo attribute, 355

name2codepoint (data in htmlentitydefs), 264
NamedTemporaryFile() (in module tempfile), 335
NameError (exception in exceptions), 19

namelist() (ZipFile method), 349
nameprep() (in module encodings.idna), 89
namespace() (IMAP4_stream method), 645
NAMESPACE_DNS (data in uuid), 660
NAMESPACE_OID (data in uuid), 660
NAMESPACE_URL (data in uuid), 660
NAMESPACE_X500 (data in uuid), 660
NamespaceErr (exception in xml.dom), 281
namespaceURI (Node attribute), 275
NaN, 8, 50

NannyNag (exception in tabnanny), 885
napms() (in module curses), 475
ndiff() (in module difflib), 67
ne() (in module operator), 183
neg() (in module operator), 184
nested() (in module contextlib), 838
netrc

- class in netrc, 314
- standard module, **314**

NetrcParseError (exception in netrc), 314
netscape (LWPCookieJar attribute), 676
Network News Transfer Protocol, 647
new()

- in module hmac, 321
- in module md5, 322
- in module sha, 322

new (built-in module), **143**
new_alignment() (writer method), 911
new_font() (writer method), 911
new_margin() (writer method), 911
new_module() (in module imp), 866
new_panel() (in module curses.panel), 491
new_spacing() (writer method), 911
new_styles() (writer method), 911
newconfig() (in module al), 913

newgroups() (NNTP method), 649
newlines (file attribute), 41
newnews() (NNTP method), 649
newpad() (in module curses), 476
newwin() (in module curses), 476
next()

- method, 381
- csv reader method, 306
- dbhash method, 379
- file method, 40
- FormatError method, 234
- iterator method, 27
- MultiFile method, 246
- NNTP method, 650
- TarFile method, 354

nextfile() (in module fileinput), 329
nextkey() (in module gdbm), 378
nextpart() (MimeWriter method), 244
nextSibling (Node attribute), 275
ngettext()

- GNUTranslations method, 744
- in module gettext, 740
- NullTranslations method, 742

NI_* (data in socket), 578
nice() (in module os), 410
nis (extension module), **567**
NIST, 322
NL (data in tokenize), 884
nl() (in module curses), 476
nl_langinfo() (in module locale), 750
nlargest() (in module heapq), 122
nlst() (FTP method), 639
NNTP

- protocol, 647

NNTP (class in nntplib), 648
NNTPDataError (exception in nntplib), 649
NNTPError (exception in nntplib), 648
nntplib (standard module), **647**
NNTPPermanentError (exception in nntplib), 648
NNTPProtocolError (exception in nntplib), 649
NNTPReplyError (exception in nntplib), 648
NNTPTemporaryError (exception in nntplib), 648
nocbreak() (in module curses), 476
NoDataAllowedErr (exception in xml.dom), 281
Node (class in compiler.ast), 898
node() (in module platform), 492
nodelay() (window method), 481
nodeName (Node attribute), 275
nodeType (Node attribute), 275
nodeValue (Node attribute), 275
NODISC (data in cd), 916
noecho() (in module curses), 476
NOEXPR (data in locale), 753
nofill (HTMLParser attribute), 263

nok_builtin_names (RExec attribute), 861
 noload() (Unpickler method), 363
 NoModificationAllowedErr (exception in xml.dom), 281
 nonblock() (audio device method), 709
 None
 Built-in object, 23
 data in , 22
 NoneType (data in types), 141
 nonl() (in module curses), 476
 noop()
 IMAP4_stream method, 645
 POP3_SSL method, 641
 NoOptionError (exception in ConfigParser), 310
 noqiflush() (in module curses), 476
 noraw() (in module curses), 476
 normalize()
 Context method, 161
 Decimal method, 158
 in module locale, 751
 in module unicodedata, 90
 Node method, 276
 NORMALIZE_WHITESPACE (data in doctest), 773
 normalvariate() (in module random), 171
 normcase() (in module os.path), 327
 normpath() (in module os.path), 327
 NoSectionError (exception in ConfigParser), 310
 NoSuchMailboxError (class in mailbox), 234
 not
 operator, 24
 not in
 operator, 24, 28
 not_() (in module operator), 183
 NotANumber (exception in fpformat), 93
 notationDecl() (DTDHandler method), 293
 NotationDeclHandler() (xmlparser method), 268
 notations (DocumentType attribute), 277
 NotConnected (exception in httplib), 633
 Notebook (class in Tix), 728
 NotEmptyError (class in mailbox), 234
 NotFoundErr (exception in xml.dom), 281
 notify() (Condition method), 542
 notifyAll() (Condition method), 542
 notimeout() (window method), 481
 NotImplemented (data in), 22
 NotImplementedError (exception in exceptions), 19
 NotImplementedType (data in types), 142
 NotStandaloneHandler() (xmlparser method), 268
 NotSupportedErr (exception in xml.dom), 281
 noutrefresh() (window method), 481
 now() (datetime method), 101
 NSIG (data in signal), 589
 nsmaallest() (in module heapq), 123
 NTEventLogHandler (class in logging), 465
 ntohl() (in module socket), 580
 ntohs() (in module socket), 580
 ntransfercmd() (FTP method), 639
 NullFormatter (class in formatter), 911
 NullImporter (class in imp), 867
 NullWriter (class in formatter), 912
 numeric
 conversions, 25
 literals, 25
 object, 24, 25
 types, operations on, 25
 numeric() (in module unicodedata), 90
 Numerical Python, 14
 nurbscurve() (in module gl), 926
 nurbsurface() (in module gl), 926
 ndarray() (in module gl), 926

O
 O_APPEND (data in os), 401
 O_BINARY (data in os), 401
 O_CREAT (data in os), 401
 O_DSYNC (data in os), 401
 O_EXCL (data in os), 401
 O_EXLOCK (data in os), 401
 O_NDELAY (data in os), 401
 O_NOCTTY (data in os), 401
 O_NOINHERIT (data in os), 401
 O_NONBLOCK (data in os), 401
 O_RANDOM (data in os), 402
 O_RDONLY (data in os), 401
 O_RDWR (data in os), 401
 O_RSYNC (data in os), 401
 O_SEQUENTIAL (data in os), 402
 O_SHLOCK (data in os), 401
 O_SHORT_LIVED (data in os), 401
 O_SYNC (data in os), 401
 O_TEMPORARY (data in os), 402
 O_TEXT (data in os), 402
 O_TRUNC (data in os), 401
 O_WRONLY (data in os), 401
 object
 Boolean, 25
 buffer, 27
 code, 44, 374
 complex number, 25
 dictionary, 37
 file, 39
 floating point, 25
 integer, 25
 list, 27, 34
 long integer, 25
 mapping, 37

- method, 43
- numeric, 24, 25
- sequence, 27
- set, 36
- socket, 577
- string, 27
- traceback, 828, 840
- tuple, 27
- type, 15
- Unicode, 27
- xrange, 27, 34
- `object()` (in module), 10
- objects
 - comparing, 24
 - flattening, 359
 - marshalling, 359
 - persistent, 359
 - pickling, 359
 - serializing, 359
- `obufcount()` (audio device method), 710, 932
- `obuffree()` (audio device method), 710
- `oct()` (in module), 10
- octal
 - literals, 25
- `octdigits` (data in string), 48
- `offset` (ExpatError attribute), 269
- OK (data in curses), 483
- `ok_builtin_modules` (RExec attribute), 862
- `ok_file_types` (RExec attribute), 862
- `ok_path` (RExec attribute), 862
- `ok_posix_names` (RExec attribute), 862
- `ok_sys_names` (RExec attribute), 862
- `OleDLL` (class in ctypes), 523
- `onecmd()` (Cmd method), 758
- `open()`
 - IMAP4_stream method, 645
 - in module , 10
 - in module aifc, 697
 - in module anydbm, 375
 - in module cd, 916
 - in module codecs, 79
 - in module dbhash, 379
 - in module dbm, 377
 - in module dl, 557
 - in module dumbdbm, 382
 - in module gdbm, 377
 - in module gzip, 346
 - in module os, 400
 - in module ossaudiodev, 707
 - in module posixfile, 564
 - in module shelve, 371
 - in module sunau, 699
 - in module sunaudiodev, 931
 - in module tarfile, 352
 - in module wave, 702
 - in module webbrowser, 600, 601
 - OpenerDirector method, 626
 - TarFile method, 353
 - Telnet method, 657
 - Template method, 563
 - URLopener method, 621
- `open_new()` (in module webbrowser), 600, 602
- `open_new_tab()` (in module webbrowser), 600, 602
- `open_osfhandle()` (in module msvcrt), 940
- `open_unknown()` (URLopener method), 621
- `OpenDatabase()` (in module msilib), 933
- `opendir()` (in module dircache), 340
- `OpenerDirector` (class in urllib2), 623
- `openfolder()` (MH method), 238
- `openfp()`
 - in module sunau, 700
 - in module wave, 702
- OpenGL, 927
- `OpenKey()` (in module _winreg), 942
- `OpenKeyEx()` (in module _winreg), 942
- `openlog()` (in module syslog), 568
- `openmessage()` (Message method), 239
- `openmixer()` (in module ossaudiodev), 708
- `openport()` (in module al), 913
- `openpty()`
 - in module os, 400
 - in module pty, 560
- OpenSSL, 319
- `OpenView()` (Binary method), 934
- operation
 - concatenation, 28
 - extended slice, 28
 - repetition, 28
 - slice, 28
 - subscript, 28
- operations
 - bit-string, 26
 - Boolean, 23
 - masking, 26
 - shifting, 26
- operations on
 - dictionary type, 37
 - integer types, 26
 - list type, 35
 - mapping types, 37
 - mutable sequence types, 35
 - numeric types, 25
 - sequence types, 28, 35
- operator
 - `==`, 24
 - `and`, 23, 24
 - comparison, 24
 - `in`, 24, 28

- is, 24
- is not, 24
- not, 24
- not in, 24, 28
- or, 23, 24
- operator (built-in module), **182**
- opmap (data in dis), 889
- opname (data in dis), 889
- OptionMenu (class in Tix), 726
- options() (SafeConfigParser method), 311
- options (Example attribute), 782
- optionxform() (SafeConfigParser method), 312
- optparse (standard module), **420**
- or
 - operator, 23, 24
- or_() (in module operator), 184
- ord() (in module), 11
- ordered_attributes (xmlparser attribute), 266
- origin_server (BaseHandler attribute), 616
- os (standard module), 39, **395**, 553
- os.path (standard module), **325**
- os_environ (BaseHandler attribute), 615
- OSError (exception in exceptions), 19
- ossaudiodev (built-in module), **707**
- OSSAudioError (exception in ossaudiodev), 707
- output()
 - BaseCookie method, 681
 - Morsel method, 682
- output_charset() (NullTranslations method), 742
- output_charset (data in email.charset), 204
- output_codec (data in email.charset), 204
- output_difference() (OutputChecker method), 785
- OutputChecker (class in doctest), 784
- OutputString() (Morsel method), 682
- OutputType (data in cStringIO), 75
- Overflow (class in decimal), 163
- OverflowError (exception in exceptions), 19
- overlay() (window method), 481
- Overmars, Mark, 919
- overwrite() (window method), 481

P

- P_DETACH (data in os), 411
- P_NOWAIT (data in os), 411
- P_NOWAITO (data in os), 411
- P_OVERLAY (data in os), 411
- P_WAIT (data in os), 411
- pack()
 - in module struct, 63
 - MH method, 224
 - Struct method, 65
- pack_array() (Packer method), 316
- pack_bytes() (Packer method), 316
- pack_double() (Packer method), 315
- pack_farray() (Packer method), 316
- pack_float() (Packer method), 315
- pack_fopaque() (Packer method), 315
- pack_fstring() (Packer method), 315
- pack_into()
 - in module struct, 63
 - Struct method, 65
- pack_list() (Packer method), 316
- pack_opaque() (Packer method), 315
- pack_string() (Packer method), 315
- package, 850
- Packer (class in xdrlib), 315
- packing
 - binary data, 62
- packing (widgets), 719
- PAGER, 807
- pair_content() (in module curses), 476
- pair_number() (in module curses), 476
- PanedWindow (class in Tix), 728
- pardir (data in os), 414
- parent (BaseHandler attribute), 627
- parentNode (Node attribute), 275
- paretovariate() (in module random), 171
- Parse() (xmlparser method), 265
- parse()
 - DocTestParser method, 783
 - ElementTree method, 301
 - in module cgi, 606
 - in module compiler, 897
 - in module xml.dom.minidom, 283
 - in module xml.dom.pulldom, 287
 - in module xml.etree.ElementTree, 299
 - in module xml.sax, 288
 - Parser method, 197
 - RobotFileParser method, 313
 - XMLReader method, 295
- parse_and_bind() (in module readline), 549
- PARSE_COLNAMES (data in sqlite3), 385
- PARSE_DECLTYPES (data in sqlite3), 385
- parse_header() (in module cgi), 606
- parse_multipart() (in module cgi), 606
- parse_qs() (in module cgi), 606
- parse_qsl() (in module cgi), 606
- parseaddr()
 - in module email.utils, 208
 - in module rfc822, 248
- parsedate()
 - in module email.utils, 208
 - in module rfc822, 248
- parsedate_tz()
 - in module email.utils, 208
 - in module rfc822, 248
- ParseFile() (xmlparser method), 265

- parseFile() (in module compiler), 897
- ParseFlags() (in module imaplib), 643
- parseframe() (CD parser method), 918
- Parser (class in email.parser), 197
- parser (built-in module), **873**
- ParserCreate() (in module xml.parsers.expat), 264
- ParserError (exception in parser), 876
- ParseResult (class in urlparse), 664
- parsesequence() (Folder method), 239
- parsestr() (Parser method), 197
- parseString()
 - in module xml.dom.minidom, 283
 - in module xml.dom.pulldom, 287
 - in module xml.sax, 288
- parsing
 - Python source code, 873
 - URL, 661
- ParsingError (exception in ConfigParser), 311
- partial()
 - IMAP4_stream method, 645
 - in module functools, 181
- partition() (string method), 30
- pass_() (POP3_SSL method), 641
- PATH, 409, 411, 415, 607, 609
- path
 - configuration file, 850
 - module search, 338, 831, 850
 - operations, 325
- path
 - BaseHTTPRequestHandler attribute, 668
 - Cookie attribute, 678
 - data in os, 396
 - data in sys, 831
- Path browser, 733
- path_return_ok() (CookiePolicy method), 676
- pathconf() (in module os), 404
- pathconf_names (data in os), 404
- pathname2url() (in module urllib), 619
- pathsep (data in os), 414
- pattern (RegexObject attribute), 60
- pause() (in module signal), 589
- PAUSED (data in cd), 916
- Pdb (class in pdb), 805
- pdb (standard module), **805**
- Pen (class in turtle), 732
- PendingDeprecationWarning (exception in exceptions), 21
- Performance, 821
- Persist() (Binary method), 936
- persistence, 359
- persistent
 - objects, 359
- pformat()
 - in module pprint, 145
- PrettyPrinter method, 146
- pi
 - data in cmath, 152
 - data in math, 151
- pick() (in module gl), 926
- pickle() (in module copy_reg), 371
- pickle (standard module), 144, **359**, 370, 371, 374
- PickleError (exception in pickle), 362
- Pickler (class in pickle), 362
- pickletools (standard module), **896**
- pickling
 - objects, 359
- PicklingError (exception in pickle), 362
- pid
 - Popen4 attribute, 591
 - Popen attribute, 574
- PIL (the Python Imaging Library), 928
- pipe() (in module os), 401
- pipes (standard module), **562**
- PKG_DIRECTORY (data in imp), 866
- pkgutil (standard module), **870**
- platform() (in module platform), 492
- platform
 - data in sys, 831
 - standard module, **492**
- play() (CD player method), 917
- playabs() (CD player method), 917
- PLAYING (data in cd), 916
- PlaySound() (in module winsound), 945
- playtrack() (CD player method), 917
- playtrackabs() (CD player method), 917
- plock() (in module os), 410
- plus() (Context method), 161
- pm() (in module pdb), 806
- pnum (data in cd), 916
- POINTER() (in module ctypes), 529
- pointer() (in module ctypes), 529
- poll()
 - method, 536
 - in module select, 535
 - Popen4 method, 591
 - Popen method, 573
- pop()
 - method, 117
 - array method, 127
 - dictionary method, 37
 - fifo method, 597
 - list method, 35
 - Mailbox method, 221
 - MultiFile method, 246
- POP3
 - protocol, 640
- POP3 (class in poplib), 640
- POP3_SSL (class in poplib), 640

- pop_alignment() (formatter method), 910
- pop_font() (formatter method), 910
- pop_margin() (formatter method), 910
- pop_source() (shlex method), 760
- pop_style() (formatter method), 911
- Popen (class in subprocess), 571
- popen()
 - in module os, 398
 - in module os, 536
 - in module platform, 494
- popen2()
 - in module os, 399
 - in module popen2, 590
- popen2 (standard module), **590**
- Popen3 (class in popen2), 590
- popen3()
 - in module os, 399
 - in module popen2, 590
- Popen4 (class in popen2), 591
- popen4()
 - in module os, 399
 - in module popen2, 590
- popitem()
 - dictionary method, 37
 - Mailbox method, 221
- popleft() (method), 117
- poplib (standard module), **640**
- PopupMenu (class in Tix), 726
- port (Cookie attribute), 678
- port_specified (Cookie attribute), 679
- PortableUnixMailbox (class in mailbox), 235
- pos() (in module operator), 184
- pos (MatchObject attribute), 61
- position() (in module turtle), 732
- POSIX
 - file object, 563
 - I/O control, 558
 - threads, 537
- posix
 - built-in module, **553**
 - TarFile attribute, 354
- posixfile (built-in module), **563**
- post()
 - audio device method, 709
 - NNTP method, 650
- post_mortem() (in module pdb), 806
- postcmd() (Cmd method), 758
- postloop() (Cmd method), 758
- pow()
 - in module , 11
 - in module math, 150
 - in module operator, 184
- power() (Context method), 161
- pprint()
 - in module pprint, 145
 - PrettyPrinter method, 146
- pprint (standard module), **144**
- prcal() (in module calendar), 115
- preamble (data in email.message), 195
- precmd() (Cmd method), 758
- prefix
 - Attr attribute, 279
 - data in sys, 831
 - Node attribute, 275
- preloop() (Cmd method), 758
- preorder() (ASTVisitor method), 904
- prepare_input_source() (in module xml.sax.saxutils), 294
- prepend() (Template method), 563
- PrettyPrinter (class in pprint), 144
- preventremoval() (CD player method), 917
- previous()
 - method, 381
 - dbhash method, 379
- previousSibling (Node attribute), 275
- print
 - statement, 23
- print_callees() (Stats method), 817
- print_callers() (Stats method), 817
- print_directory() (in module cgi), 606
- print_environ() (in module cgi), 606
- print_environ_usage() (in module cgi), 606
- print_exc()
 - in module traceback, 840
 - Timer method, 821
- print_exception() (in module traceback), 840
- print_form() (in module cgi), 606
- print_last() (in module traceback), 840
- print_stack() (in module traceback), 840
- print_stats() (Stats method), 816
- print_tb() (in module traceback), 840
- printable (data in string), 48
- printdir() (ZipFile method), 349
- printf-style formatting, 32
- prmonth()
 - in module calendar, 115
 - TextCalendar method, 114
- process
 - group, 396, 397
 - id, 397
 - id of parent, 397
 - killing, 410
 - signalling, 410
- process_message() (SMTPServer method), 655
- process_request() (in module SocketServer), 667
- processes, light-weight, 536
- ProcessingInstruction() (in module xml.etree.ElementTree), 299

`processingInstruction()` (ContentHandler method), 292
`ProcessingInstructionHandler()` (xmlparser method), 267
`processor()` (in module platform), 492
 processor time, 417
`Profile` (class in hotshot), 819
`profile` (standard module), **814**
 profile function, 539, 832
 profiler, 832
 profiling, deterministic, 811
`prompt` (Cmd attribute), 758
`prompt_user_passwd()` (FancyURLopener method), 621
 prompts, interpreter, 832
`propagate` (data in logging), 454
`property()` (in module), 11
`property_declaration_handler` (data in xml.sax.handler), 290
`property_dom_node` (data in xml.sax.handler), 290
`property_lexical_handler` (data in xml.sax.handler), 290
`property_xml_string` (data in xml.sax.handler), 291
`proto` (socket attribute), 584
 protocol
 CGI, 602
 context management, 42
 FTP, 620, 636
 Gopher, 620, 640
 HTTP, 602, 620, 632, 667
 IMAP4, 642
 IMAP4_SSL, 642
 IMAP4_stream, 642
 iterator, 26
 NNTP, 647
 POP3, 640
 SMTP, 651
 Telnet, 656
`PROTOCOL_VERSION` (IMAP4_stream attribute), 647
`protocol_version` (BaseHTTPRequestHandler attribute), 669
`proxy()` (in module weakref), 135
`proxyauth()` (IMAP4_stream method), 645
`ProxyBasicAuthHandler` (class in urllib2), 624
`ProxyDigestAuthHandler` (class in urllib2), 624
`ProxyHandler` (class in urllib2), 624
`ProxyType` (data in weakref), 136
`ProxyTypes` (data in weakref), 136
`prstr()` (in module fm), 924
`pryear()` (TextCalendar method), 114
`ps1` (data in sys), 832
`ps2` (data in sys), 832
`pstats` (standard module), **815**

`pthread`, 537
`ptime` (data in cd), 916
`pty` (standard module), 400, **560**
`publicId` (DocumentType attribute), 277
`PullDOM` (class in xml.dom.pulldom), 287
`punctuation` (data in string), 48
`PureProxy` (class in smtpd), 656
`push()`
 `async_chat` method, 596
 `fifo` method, 597
 `InteractiveConsole` method, 856
 `MultiFile` method, 246
`push_alignment()` (formatter method), 910
`push_font()` (formatter method), 910
`push_margin()` (formatter method), 910
`push_source()` (shlex method), 760
`push_style()` (formatter method), 910
`push_token()` (shlex method), 760
`push_with_producer()` (async_chat method), 596
`pushbutton()` (Dialog method), 938
`put()` (Queue method), 133
`put_nowait()` (Queue method), 133
`putch()` (in module msvcrt), 940
`putenv()` (in module os), 397
`putheader()` (HTTPResponse method), 635
`putp()` (in module curses), 476
`putrequest()` (HTTPResponse method), 635
`putsequences()` (Folder method), 239
`putwin()` (window method), 482
`pwd()` (FTP method), 639
`pwd` (built-in module), 326, **554**
`pwlcurve()` (in module gl), 926
`py_compile` (standard module), **887**
`PY_COMPILED` (data in imp), 866
`PY_FROZEN` (data in imp), 867
`py_object` (class in ctypes), 532
`PY_RESOURCE` (data in imp), 866
`PY_SOURCE` (data in imp), 866
`pyclbr` (standard module), **886**
`PyCompileError` (exception in py_compile), 887
`PyDLL` (class in ctypes), 524
`pydoc` (standard module), **763**
`pyexpat` (built-in module), 264
`PYFUNCTYPE()` (in module ctypes), 526
`PyOpenGL`, 927
 Python Editor, 733
 Python Enhancement Proposals
 PEP 0205, 136
 PEP 0273, 869
 PEP 0302, 869
 PEP 0343, 838
 PEP 236, 5
 PEP 246, 391
 PEP 249, 383, 385

- PEP 282, 453
- PEP 292, 48
- PEP 302, 338, 867
- PEP 305, 303
- PEP 333, 610–614, 616
- PEP 338, 872
- PEP 8, 210
- Python Imaging Library, 928
- python_build() (in module platform), 493
- python_compiler() (in module platform), 493
- PYTHON_DOM, 273
- python_version() (in module platform), 493
- python_version_tuple() (in module platform), 493
- PYTHONDOCS, 764
- PYTHONPATH, 607, 831
- PYTHONSTARTUP, 550, 551, 851
- PYTHONY2K, 415, 416
- PyZipFile (class in zipfile), 348

Q

- qdevice() (in module fl), 920
- qenter() (in module fl), 920
- qiflush() (in module curses), 476
- QName (class in xml.etree.ElementTree), 301
- qread() (in module fl), 920
- qreset() (in module fl), 920
- qsize() (Queue method), 133
- qtest() (in module fl), 920
- quantize()
 - Context method, 161
 - Decimal method, 158
- QueryInfoKey() (in module _winreg), 942
- queryparams() (in module al), 913
- QueryValue() (in module _winreg), 943
- QueryValueEx() (in module _winreg), 943
- Queue
 - class in Queue, 133
 - standard module, **133**
- quick_ratio() (SequenceMatcher method), 71
- quit()
 - FTP method, 639
 - NNTP method, 651
 - POP3_SSL method, 641
 - SMTP method, 654
- quopri (standard module), **255**
- quote()
 - in module email.utils, 207
 - in module rfc822, 248
 - in module urllib, 619
- QUOTE_ALL (data in csv), 305
- QUOTE_MINIMAL (data in csv), 305
- QUOTE_NONE (data in csv), 305
- QUOTE_NONNUMERIC (data in csv), 305

- quote_plus() (in module urllib), 619
- quoteattr() (in module xml.sax.saxutils), 294
- quotechar (Dialect attribute), 306
- quoted-printable
 - encoding, 255
- quotes (shlex attribute), 761
- quoting (Dialect attribute), 306

R

- r_eval() (RExec method), 860
- r_exec() (RExec method), 861
- r_execfile() (RExec method), 861
- r_import() (RExec method), 861
- R_OK (data in os), 402
- r_open() (RExec method), 861
- r_reload() (RExec method), 861
- r_unload() (RExec method), 861
- radians()
 - in module math, 151
 - in module turtle, 730
- RadioButtonGroup (class in msilib), 938
- radiogroup() (Dialog method), 938
- RADIXCHAR (data in locale), 753
- raise
 - statement, 17
- randint() (in module random), 170
- random() (in module random), 170
- random (standard module), **169**
- randrange() (in module random), 170
- range() (in module), 12
- ratecv() (in module audioop), 695
- ratio() (SequenceMatcher method), 70
- raw() (in module curses), 476
- raw_input()
 - built-in function, 833
 - in module , 12
 - InteractiveConsole method, 857
- RawConfigParser (class in ConfigParser), 310
- RawPen (class in turtle), 732
- re
 - MatchObject attribute, 61
 - standard module, 34, 47, **52**, 337
- read()
 - method, 548, 584
 - array method, 127
 - audio device method, 708, 932
 - BZ2File method, 347
 - Chunk method, 704
 - file method, 40
 - HTTPResponse method, 635
 - IMAP4_stream method, 645
 - in module imgfile, 928
 - in module os, 401
 - MimeTypes method, 243

- MultiFile method, 246
- RobotFileParser method, 313
- SafeConfigParser method, 311
- StreamReader method, 84
- ZipFile method, 349
- read_all() (Telnet method), 656
- read_byte() (method), 548
- read_eager() (Telnet method), 657
- read_history_file() (in module readline), 549
- read_init_file() (in module readline), 549
- read_lazy() (Telnet method), 657
- read_mime_types() (in module mimetypes), 241
- read_sb_data() (Telnet method), 657
- read_some() (Telnet method), 657
- read_token() (shlex method), 760
- read_until() (Telnet method), 656
- read_very_eager() (Telnet method), 657
- read_very_lazy() (Telnet method), 657
- readable()
 - async_chat method, 596
 - dispatcher method, 593
- readda() (CD player method), 917
- reader() (in module csv), 303
- ReadError (exception in tarfile), 353
- readfp()
 - MimeTypes method, 243
 - SafeConfigParser method, 312
- readframes()
 - aifc method, 698
 - AU_read method, 701
 - Wave_read method, 703
- readline()
 - method, 548
 - BZ2File method, 347
 - file method, 40
 - IMAP4_stream method, 645
 - MultiFile method, 245
 - StreamReader method, 84
- readline (built-in module), **549**
- readlines()
 - BZ2File method, 347
 - file method, 40
 - MultiFile method, 245
 - StreamReader method, 84
- readlink() (in module os), 404
- readmodule() (in module pycldr), 886
- readmodule_ex() (in module pycldr), 886
- readsamps() (audio port method), 914
- readscaled() (in module imgfile), 928
- READY (data in cd), 916
- Real Media File Format, 704
- real_quick_ratio() (SequenceMatcher method), 71
- realpath() (in module os.path), 327
- reason (data in httplib), 636
- recontrols() (mixer device method), 711
- recent() (IMAP4_stream method), 645
- rectangle() (in module curses.textpad), 487
- recv()
 - dispatcher method, 594
 - socket method, 582
- recv_into() (socket method), 583
- recvfrom() (socket method), 582
- recvfrom_into() (socket method), 583
- redirect_request() (HTTPRedirectHandler method), 628
- redisplay() (in module readline), 549
- redraw_form() (form method), 920
- redraw_object() (FORMS object method), 923
- redrawln() (window method), 482
- redrawwin() (window method), 482
- reduce() (in module), 12
- ref (class in weakref), 135
- ReferenceError
 - exception in exceptions, 20
 - exception in weakref, 136
- ReferenceType (data in weakref), 136
- refilemessages() (Folder method), 239
- refill_buffer() (async_chat method), 597
- refresh() (window method), 482
- register()
 - method, 536
 - in module atexit, 839
 - in module codecs, 77
 - in module webbrowser, 600
- register_adapter() (in module sqlite3), 386
- register_converter() (in module sqlite3), 386
- register_dialect() (in module csv), 304
- register_error() (in module codecs), 79
- register_function()
 - SimpleXMLRPCRequestHandler method, 690
 - SimpleXMLRPCServer method, 689
- register_instance()
 - SimpleXMLRPCRequestHandler method, 690
 - SimpleXMLRPCServer method, 689
- register_introspection_functions() (SimpleXMLRPCRequestHandler method), 689 691
- register_multicall_functions() (SimpleXMLRPCRequestHandler method), 689, 691
- register_optionflag() (in module doctest), 775
- registerDOMImplementation() (in module xml.dom), 273
- RegLoadKey() (in module _winreg), 942
- relative
 - URL, 661
- release()
 - method, 461

- Condition method, 542
 - in module platform, 493
 - lock method, 537
 - Semaphore method, 543
 - Timer method, 540, 541
- release_lock() (in module imp), 866
- reload()
 - built-in function, 831, 866, 868
 - in module , 13
- remainder() (Context method), 161
- remainder_near()
 - Context method, 162
 - Decimal method, 158
- remove()
 - method, 117
 - array method, 127
 - in module os, 405
 - list method, 35
 - Mailbox method, 219
 - MH method, 224
- remove_flag()
 - MaildirMessage method, 227
 - mboxMessage method, 229
 - MMDFMessage method, 233
- remove_folder()
 - Maildir method, 222
 - MH method, 224
- remove_history_item() (in module readline), 549
- remove_label() (BabylMessage method), 231
- remove_option() (SafeConfigParser method), 312
- remove_pyc() (Directory method), 937
- remove_section() (SafeConfigParser method), 312
- remove_sequence() (MHMessage method), 230
- removeAttribute() (Element method), 278
- removeAttributeNode() (Element method), 278
- removeAttributeNS() (Element method), 278
- removecallback() (CD parser method), 918
- removeChild() (Node method), 276
- removedirs() (in module os), 405
- removeFilter() (method), 455, 461
- removeHandler() (method), 455
- removemessages() (Folder method), 239
- rename()
 - FTP method, 639
 - IMAP4_stream method, 645
 - in module os, 405
- renames() (in module os), 405
- reorganize() (in module gdbm), 378
- repeat()
 - in module itertools, 176
 - in module operator, 185
 - Timer method, 821
- repetition
 - operation, 28
- replace()
 - method, 491
 - date method, 100
 - datetime method, 104
 - in module string, 52
 - string method, 30
 - time method, 107
- replace_errors() (in module codecs), 79
- replace_header() (Message method), 193
- replace_history_item() (in module readline), 549
- replace_whitespace (TextWrapper attribute), 77
- replaceChild() (Node method), 276
- ReplacePackage() (in module modulefinder), 871
- report()
 - dircmp method, 333
 - ModuleFinder method, 871
- REPORT_CDIF (data in doctest), 773
- report_failure() (DocTestRunner method), 784
- report_full_closure() (dircmp method), 334
- REPORT_NDIFF (data in doctest), 773
- REPORT_ONLY_FIRST_FAILURE (data in doctest), 773
- report_partial_closure() (dircmp method), 333
- report_start() (DocTestRunner method), 784
- report_success() (DocTestRunner method), 784
- REPORT_UDIFF (data in doctest), 773
- report_unbalanced() (SGMLParser method), 261
- report_unexpected_exception() (DocTestRunner method), 784
- REPORTING_FLAGS (data in doctest), 774
- Repr (class in repr), 147
- repr()
 - in module , 13
 - in module repr, 147
 - Repr method, 148
- repr (standard module), **147**
- repr1() (Repr method), 148
- Request (class in urllib2), 623
- request() (HTTPResponse method), 635
- request_queue_size (data in SocketServer), 666
- request_uri() (in module wsgiref.util), 610
- request_version (BaseHTTPRequestHandler attribute), 668
- RequestHandlerClass (data in SocketServer), 666
- requires() (in module test.test.support), 804
- reserved (ZipInfo attribute), 351
- RESERVED_FUTURE (data in uuid), 660
- RESERVED_MICROSOFT (data in uuid), 660
- RESERVED_NCS (data in uuid), 660
- reset()
 - audio device method, 709
 - DOMEventStream method, 287

- HTMLParser method, 258
- in module `dircache`, 340
- in module `turtle`, 731
- IncrementalDecoder method, 82
- IncrementalEncoder method, 82
- IncrementalParser method, 296
- Packer method, 315
- SGMLParser method, 260
- StreamReader method, 84
- StreamWriter method, 83
- Template method, 563
- Unpacker method, 316
- `reset_prog_mode()` (in module `curses`), 477
- `reset_shell_mode()` (in module `curses`), 477
- `resetbuffer()` (`InteractiveConsole` method), 857
- `resetlocale()` (in module `locale`), 751
- `resetparser()` (`CD` parser method), 918
- `resetwarnings()` (in module `warnings`), 837
- `resize()`
 - method, 548
 - in module `ctypes`, 529
- `resolution`
 - date attribute, 99
 - datetime attribute, 102
 - time attribute, 106
 - timedelta attribute, 97
- `resolveEntity()` (`EntityResolver` method), 293
- `resource` (built-in module), **565**
- `ResourceDenied` (exception in `test.test_support`), 804
- `response()` (`IMAP4_stream` method), 645
- `ResponseNotReady` (exception in `httplib`), 633
- `responses`
 - `BaseHTTPRequestHandler` attribute, 669
 - data in `httplib`, 634
- `restore()` (in module `difflib`), 68
- `restype` (`_FuncPtr` attribute), 525
- `retr()` (`POP3_SSL` method), 641
- `retrbinary()` (`FTP` method), 638
- `retrieve()` (`URLopener` method), 621
- `retrlines()` (`FTP` method), 638
- `return_ok()` (`CookiePolicy` method), 675
- `returncode` (`Popen` attribute), 574
- `returns_unicode` (`xmlparser` attribute), 266
- `reverse()`
 - array method, 127
 - in module `audioop`, 695
 - list method, 35
- `reverse_order()` (`Stats` method), 816
- `reversed()` (in module), 13
- `revert()` (`FileCookieJar` method), 674
- `rewind()`
 - `aifc` method, 698
 - `AU_read` method, 701
 - `Wave_read` method, 703
- `rewindbody()` (`AddressList` method), 249
- `RExec` (class in `rexec`), 860
- `rexec` (standard module), 3, **860**
- RFC
 - RFC 1014, 315
 - RFC 1321, 319, 321
 - RFC 1521, 253, 255
 - RFC 1522, 255
 - RFC 1524, 218
 - RFC 1725, 640
 - RFC 1730, 642
 - RFC 1738, 663
 - RFC 1766, 750, 751
 - RFC 1808, 663
 - RFC 1832, 315
 - RFC 1866, 262
 - RFC 1869, 651, 652
 - RFC 1894, 213
 - RFC 2045, 189, 193, 194, 201, 246
 - RFC 2046, 189, 201
 - RFC 2047, 189, 201–203
 - RFC 2060, 642, 646
 - RFC 2068, 680
 - RFC 2104, 321
 - RFC 2109, 672, 673, 680, 681
 - RFC 2231, 189, 194, 201, 209, 210
 - RFC 2396, 662, 663
 - RFC 2553, 577
 - RFC 2616, 611, 620, 627, 628
 - RFC 2774, 634
 - RFC 2817, 634
 - RFC 2821, 189
 - RFC 2822, 189–191, 197–199, 201–203, 207–209, 226, 247–249, 418, 655
 - RFC 2964, 673
 - RFC 2965, 623, 625, 672, 673
 - RFC 3229, 634
 - RFC 3454, 92
 - RFC 3490, 89
 - RFC 3492, 89
 - RFC 3548, 251, 252
 - RFC 4122, 658, 660
 - RFC 821, 651, 652
 - RFC 822, 201, 247, 310, 418, 635, 653, 654, 743
 - RFC 854, 656
 - RFC 959, 636
 - RFC 977, 647
- `rfc2109` (`Cookie` attribute), 678
- `rfc2109_as_netscape` (`LWPCookieJar` attribute), 677
- `rfc2965` (`LWPCookieJar` attribute), 676
- `rfc822` (standard module), 239, **247**
- `RFC_4122` (data in `uuid`), 660
- `rfile` (`BaseHTTPRequestHandler` attribute), 668

- rfind()
 - in module string, 51
 - string method, 31
- rgb_to_hls() (in module colorsys), 705
- rgb_to_hsv() (in module colorsys), 705
- rgb_to_yiq() (in module colorsys), 705
- rgbimg (built-in module), **705**
- right() (in module turtle), 731
- right_list (dircmp attribute), 334
- right_only (dircmp attribute), 334
- rindex()
 - in module string, 51
 - string method, 31
- rjust()
 - in module string, 52
 - string method, 31
- rlcompleter (standard module), **551**
- rlecode_hqx() (in module binascii), 254
- rledecode_hqx() (in module binascii), 254
- RLIMIT_AS (data in resource), 566
- RLIMIT_CORE (data in resource), 566
- RLIMIT_CPU (data in resource), 566
- RLIMIT_DATA (data in resource), 566
- RLIMIT_FSIZE (data in resource), 566
- RLIMIT_MEMLOCK (data in resource), 566
- RLIMIT_NOFILE (data in resource), 566
- RLIMIT_NPROC (data in resource), 566
- RLIMIT_OFIL (data in resource), 566
- RLIMIT_RSS (data in resource), 566
- RLIMIT_STACK (data in resource), 566
- RLIMIT_VMEM (data in resource), 566
- RLock() (in module threading), 539
- rmd() (FTP method), 639
- rmdir() (in module os), 405
- RMFF**, 704
- rms() (in module audioop), 695
- rmtree() (in module shutil), 339
- rnopen() (in module bsddb), 380
- RobotFileParser (class in robotparser), 313
- robotparser (standard module), **313**
- robots.txt, 313
- rotate() (method), 117
- RotatingFileHandler (class in logging), 462
- round() (in module), 14
- Rounded (class in decimal), 163
- row_factory (attribute), 388
- rowcount (attribute), 390
- rpartition() (string method), 31
- rpc_paths (SimpleXMLRPCServer attribute), 689
- rpop() (POP3.SSL method), 641
- rset() (POP3.SSL method), 641
- rshift() (in module operator), 184
- rsplit()
 - in module string, 51
- string method, 31
- rstrip()
 - in module string, 52
 - string method, 31
- RTLD_LAZY (data in dl), 557
- RTLD_NOW (data in dl), 557
- ruler (Cmd attribute), 759
- run()
 - BaseHandler method, 615
 - DocTestRunner method, 784
 - in module cProfile, 814
 - in module pdb, 806
 - Profile method, 820
 - scheduler method, 132
 - TestCase method, 797
 - TestSuite method, 798
 - Thread method, 545
 - Trace method, 824
- Run script, 734
- run_docstring_examples() (in module doctest), 778
- run_module() (in module runpy), 871
- run_script() (ModuleFinder method), 871
- run_suite() (in module test.test_support), 804
- run_unittest() (in module test.test_support), 804
- runcall()
 - in module pdb, 806
 - Profile method, 820
- runcode() (InteractiveConsole method), 856
- runtcx()
 - in module cProfile, 815
 - Profile method, 820
 - Trace method, 824
- runeval() (in module pdb), 806
- runfunc() (Trace method), 824
- runpy (standard module), **871**
- runsource() (InteractiveConsole method), 856
- RuntimeError (exception in exceptions), 20
- RuntimeWarning (exception in exceptions), 21
- RUSAGE_BOTH (data in resource), 567
- RUSAGE_CHILDREN (data in resource), 567
- RUSAGE_SELF (data in resource), 567

S

- S (data in re), 57
- s_eval() (RExec method), 861
- s_exec() (RExec method), 861
- s_execfile() (RExec method), 861
- S_IFMT() (in module stat), 330
- S_IMODE() (in module stat), 330
- s_import() (RExec method), 861
- S_ISBLK() (in module stat), 330
- S_ISCHR() (in module stat), 330
- S_ISDIR() (in module stat), 330

- S_ISFIFO() (in module stat), 330
- S_ISLNK() (in module stat), 330
- S_ISREG() (in module stat), 330
- S_ISSOCK() (in module stat), 330
- s_reload() (RExec method), 861
- s_unload() (RExec method), 861
- safe_substitute() (Template method), 49
- SafeConfigParser (class in ConfigParser), 310
- saferepr() (in module pprint), 146
- same_files (dircmp attribute), 334
- same_quantum()
 - Context method, 162
 - Decimal method, 158
- samefile() (in module os.path), 327
- sameopenfile() (in module os.path), 327
- samestat() (in module os.path), 327
- sample() (in module random), 170
- save() (FileCookieJar method), 674
- save_bgn() (HTMLParser method), 263
- save_end() (HTMLParser method), 263
- SaveKey() (in module _winreg), 943
- SAX2DOM (class in xml.dom.pulldom), 287
- SAXException (exception in xml.sax), 288
- SAXNotRecognizedException (exception in xml.sax), 288
- SAXNotSupportedException (exception in xml.sax), 289
- SAXParseException (exception in xml.sax), 288
- scale() (in module imageop), 696
- scalefont() (in module fm), 924
- scanf() (in module re), 61
- sched (standard module), **131**
- scheduler (class in sched), 131
- schema (data in msilib), 939
- sci() (in module fpformat), 93
- script_from_examples() (in module doctest), 786
- scroll() (window method), 482
- ScrolledText (standard module), **729**
- scrollok() (window method), 482
- search
 - path, module, 338, 831, 850
- search()
 - IMAP4_stream method, 645
 - in module re, 58
 - RegexObject method, 59
- SEARCH_ERROR (data in imp), 867
- second
 - datetime attribute, 102
 - time attribute, 106
- section_divider() (MultiFile method), 246
- sections() (SafeConfigParser method), 311
- secure (Cookie attribute), 678
- Secure Hash Algorithm, 322
- secure hash algorithm, SHA1, SHA224, SHA256, SHA384, SHA512, 319
- security
 - CGI, 607
- seed() (in module random), 169
- seek()
 - method, 548
 - BZ2File method, 347
 - CD player method, 917
 - Chunk method, 704
 - file method, 40
 - MultiFile method, 246
- SEEK_CUR
 - data in os, 402
 - data in posixfile, 563
- SEEK_END
 - data in os, 402
 - data in posixfile, 563
- SEEK_SET
 - data in os, 402
 - data in posixfile, 563
- seekblock() (CD player method), 917
- seektrack() (CD player method), 918
- Select (class in Tix), 726
- select()
 - IMAP4_stream method, 645
 - in module gl, 926
 - in module select, 535
- select (built-in module), **535**
- Semaphore() (in module threading), 539
- Semaphore (class in threading), 543
- semaphores, binary, 536
- send()
 - DatagramHandler method, 464
 - dispatcher method, 594
 - HTTPResponse method, 635
 - IMAP4_stream method, 645
 - socket method, 583
 - SocketHandler method, 464
- send_error() (BaseHTTPRequestHandler method), 669
- send_flowling_data() (writer method), 912
- send_header() (BaseHTTPRequestHandler method), 669
- send_hor_rule() (writer method), 912
- send_label_data() (writer method), 912
- send_line_break() (writer method), 912
- send_literal_data() (writer method), 912
- send_paragraph() (writer method), 912
- send_query() (in module gopherlib), 640
- send_response() (BaseHTTPRequestHandler method), 669
- send_selector() (in module gopherlib), 640
- sendall() (socket method), 583

sendcmd() (FTP method), 638
 sendfile() (BaseHandler method), 616
 sendmail() (SMTP method), 653
 sendto() (socket method), 583
 sep (data in os), 414
 sequence
 iteration, 26
 object, 27
 types, mutable, 34
 types, operations on, 28, 35
 types, operations on mutable, 35
 sequence (data in msilib), 939
 sequence2ast() (in module parser), 874
 sequenceIncludes() (in module operator), 185
 SequenceMatcher (class in difflib), 65, 69
 SerialCookie (class in Cookie), 680
 serializing
 objects, 359
 serve_forever() (in module SocketServer), 666
 server
 WWW, 602, 667
 server() (method), 584
 server_activate() (in module SocketServer), 667
 server_address (data in SocketServer), 666
 server_bind() (in module SocketServer), 667
 server_software (BaseHandler attribute), 615
 server_version
 BaseHTTPRequestHandler attribute, 668
 SimpleHTTPRequestHandler attribute, 670
 ServerProxy (class in xmlrpclib), 684
 Set (class in sets), 128
 set
 object, 36
 set()
 Event method, 544
 in module , 14
 mixer device method, 711
 Morsel method, 682
 SafeConfigParser method, 312, 313
 set_allowed_domains() (DefaultCookiePolicy method), 677
 set_app() (WSGIServer method), 613
 set_authorizer() (method), 388
 set_blocked_domains() (DefaultCookiePolicy method), 677
 set_boundary() (Message method), 194
 set_call_back() (FORMS object method), 922
 set_charset() (Message method), 191
 set_completer() (in module readline), 550
 set_completer_delims() (in module readline), 550
 set_conversion_mode() (in module ctypes), 529
 set_cookie() (CookieJar method), 674
 set_cookie_if_ok() (CookieJar method), 674
 set_current() (Feature method), 938
 set_date() (MaildirMessage method), 227
 set_debug() (in module gc), 843
 set_debuglevel()
 FTP method, 637
 HTTPResponse method, 635
 NNTP method, 649
 POP3_SSL method, 641
 SMTP method, 652
 Telnet method, 657
 set_default_type() (Message method), 193
 set_event_call_back() (in module fl), 919
 set_flags()
 MaildirMessage method, 227
 mboxMessage method, 229
 MMDFMessage method, 233
 set_form_position() (form method), 920
 set_from()
 mboxMessage method, 229
 MMDFMessage method, 232
 set_graphics_mode() (in module fl), 919
 set_history_length() (in module readline), 549
 set_info() (MaildirMessage method), 227
 set_labels() (BabylMessage method), 231
 set_location() (method), 381
 set_nonstandard_attr() (Cookie method), 679
 set_ok() (CookiePolicy method), 675
 set_option_negotiation_callback() (Telnet method), 658
 set_output_charset() (NullTranslations method), 743
 set_param() (Message method), 194
 set_pasv() (FTP method), 638
 set_payload() (Message method), 191
 set_policy() (CookieJar method), 674
 set_position() (Unpacker method), 316
 set_pre_input_hook() (in module readline), 550
 set_proxy() (Request method), 625
 set_recsrc() (mixer device method), 711
 set_seq1() (SequenceMatcher method), 69
 set_seq2() (SequenceMatcher method), 69
 set_seqs() (SequenceMatcher method), 69
 set_sequences()
 MH method, 224
 MHMessage method, 230
 set_server_documentation() (DocXMLRPCRequestHandler method), 692
 set_server_name() (DocXMLRPCRequestHandler method), 692
 set_server_title() (DocXMLRPCRequestHandler method), 692
 set_spacing() (formatter method), 911
 set_startup_hook() (in module readline), 549
 set_subdir() (MaildirMessage method), 227

set_terminator() (async_chat method), 597
 set_threshold() (in module gc), 843
 set_trace() (in module pdb), 806
 set_type() (Message method), 194
 set_unittest_reportflags() (in module doctest), 780
 set_unixfrom() (Message method), 191
 set_url() (RobotFileParser method), 313
 set_userptr() (method), 491
 set_visible() (BabylMessage method), 231
 setacl() (IMAP4_stream method), 645
 setannotation() (IMAP4_stream method), 645
 setattr() (in module), 14
 setAttribute() (Element method), 279
 setAttributeNode() (Element method), 279
 setAttributeNodeNS() (Element method), 279
 setAttributeNS() (Element method), 279
 SetBase() (xmlparser method), 265
 setblocking() (socket method), 583
 setByteStream() (InputSource method), 297
 setcbreak() (in module tty), 560
 setchannels() (audio configuration method), 914
 setCharacterStream() (InputSource method), 297
 setcheckinterval() (in module sys), 832
 setcomptype()
 aifc method, 699
 AU_write method, 701
 Wave_write method, 703
 setconfig() (audio port method), 915
 setContentHandler() (XMLReader method), 295
 setcontext()
 in module decimal, 158
 MH method, 238
 setcurrent() (Folder method), 238
 setDaemon() (Thread method), 545
 setdefault() (dictionary method), 37
 setdefaultencoding() (in module sys), 832
 setdefaulttimeout() (in module socket), 581
 setdlopenflags() (in module sys), 832
 setDocumentLocator() (ContentHandler method), 291
 setDTDHandler() (XMLReader method), 295
 setgid() (in module os), 397
 setEncoding() (InputSource method), 297
 setEntityResolver() (XMLReader method), 296
 setErrorHandler() (XMLReader method), 296
 seteuid() (in module os), 397
 setFeature() (XMLReader method), 296
 setfillpoint() (audio port method), 915
 setfirstweekday() (in module calendar), 115
 setfloatmax() (audio configuration method), 914
 setfmt() (audio device method), 709
 setfont() (in module fm), 924
 setFormatter() (method), 461
 setframerate()
 aifc method, 698
 AU_write method, 701
 Wave_write method, 703
 setgid() (in module os), 397
 setgroups() (in module os), 397
 setheading() (in module turtle), 732
 setinfo() (audio device method), 932
 SetInteger() (Binary method), 936
 setitem() (in module operator), 185
 setlast() (Folder method), 239
 setLevel() (method), 454, 461
 setliteral() (SGMLParser method), 260
 setLocale() (XMLReader method), 296
 setlocale() (in module locale), 749
 setLoggerClass() (in module logging), 453
 setlogmask() (in module syslog), 568
 setmark() (aifc method), 699
 setMaxConns() (CacheFTPHandler method), 630
 setmode() (in module msvcrt), 940
 setName() (Thread method), 545
 setnchannels()
 aifc method, 698
 AU_write method, 701
 Wave_write method, 703
 setnframes()
 aifc method, 698
 AU_write method, 701
 Wave_write method, 703
 setnomoretags() (SGMLParser method), 260
 setoption() (in module jpeg), 928
 setparameters() (audio device method), 709
 setparams()
 aifc method, 699
 AU_write method, 701
 in module al, 914
 Wave_write method, 703
 setpath() (in module fm), 924
 setpgid() (in module os), 397
 setpgrp() (in module os), 397
 setpos()
 aifc method, 698
 AU_read method, 701
 Wave_read method, 703
 setprofile()
 in module sys, 832
 in module threading, 539
 SetProperty() (Binary method), 935
 SetProperty() (XMLReader method), 296
 setPublicId() (InputSource method), 297
 setqueuesize() (audio configuration method), 914
 setquota() (IMAP4_stream method), 646
 setraw() (in module tty), 559
 setrecursionlimit() (in module sys), 832

- setregid() (in module os), 397
- setreuid() (in module os), 397
- setrlimit() (in module resource), 566
- sets (standard module), **128**
- setsampfmt() (audio configuration method), 914
- setsampwidth()
 - aifc method, 698
 - AU_write method, 701
 - Wave_write method, 703
- setscrreg() (window method), 482
- setsid() (in module os), 398
- setslice() (in module operator), 185
- setsockopt() (socket method), 583
- setstate() (in module random), 170
- SetStream() (Binary method), 936
- SetString() (Binary method), 936
- setSystemId() (InputSource method), 297
- setsysx() (in module curses), 477
- setTarget() (MemoryHandler method), 466
- setTimeout() (CacheFTPHandler method), 630
- settimeout() (socket method), 583
- settrace()
 - in module sys, 832
 - in module threading, 539
- settsdump() (in module sys), 832
- setuid() (in module os), 398
- setUp() (TestCase method), 796
- setup()
 - in module SocketServer, 667
 - in module turtle, 730
- setup_environ() (BaseHandler method), 616
- setup_testing_defaults() (in module `wsgiref.util`), 611
- setupterm() (in module curses), 477
- SetValue() (in module `_winreg`), 943
- SetValueEx() (in module `_winreg`), 944
- setwidth() (audio configuration method), 914
- setx() (in module turtle), 732
- sety() (in module turtle), 732
- SGML, **259**
- sgmllib (standard module), **259**, 262
- SGMLParseError (exception in sgmllib), 260
- SGMLParser
 - class in sgmllib, 259
 - in module sgmllib, 262
- sha (built-in module), **322**
- Shelf (class in shelve), 372
- shelve (standard module), **371**, 374
- shift_path_info() (in module `wsgiref.util`), 611
- shifting
 - operations, 26
- shlex
 - class in shlex, 759
 - standard module, **759**
- shortDescription() (TestCase method), 798
- shouldFlush()
 - BufferingHandler method, 466
 - MemoryHandler method, 466
- show() (method), 492
- show_choice() (in module fl), 919
- show_file_selector() (in module fl), 920
- show_form() (form method), 920
- show_input() (in module fl), 920
- show_message() (in module fl), 919
- show_object() (FORMS object method), 923
- show_question() (in module fl), 919
- showsyntaxerror() (InteractiveConsole method), **856**
- showtraceback() (InteractiveConsole method), 856
- showwarning() (in module warnings), 836
- shuffle() (in module random), 170
- shutdown()
 - IMAP4_stream method, 646
 - in module logging, 453
 - socket method, 584
- shutil (standard module), **338**
- SIG* (data in signal), 589
- SIG_DFL (data in signal), 588
- SIG_IGN (data in signal), 588
- signal() (in module signal), 589
- signal (built-in module), 538, **588**
- Simple Mail Transfer Protocol, 651
- simple_producer (class in `asynchat`), 597
- SimpleCookie (class in `Cookie`), 680
- simplefilter() (in module warnings), 837
- SimpleHandler (class in `wsgiref.handlers`), 614
- SimpleHTTPRequestHandler (class in `SimpleHTTPServer`), 670
- SimpleHTTPServer (standard module), 667, **670**
- SimpleXMLRPCRequestHandler (class in `SimpleXMLRPCServer`), 689
- SimpleXMLRPCServer
 - class in `SimpleXMLRPCServer`, 688
 - standard module, **688**
- sin()
 - in module `cmath`, 152
 - in module `math`, 151
- sinh()
 - in module `cmath`, 152
 - in module `math`, 151
- site (standard module), **850**
- site-packages
 - directory, 850
- site-python
 - directory, 850
- sitcustomize (module), 851
- size()
 - method, 548

- FTP method, 639
- size (TarInfo attribute), 355
- sizeof () (in module ctypes), 529
- sizeofimage () (in module rgbimg), 706
- SKIP (data in doctest), 773
- skip () (Chunk method), 705
- skipinitialspace (Dialect attribute), 306
- skippedEntity () (ContentHandler method), 293
- slave () (NNTP method), 650
- sleep () (in module time), 417
- slice
 - assignment, 35
 - operation, 28
- slice ()
 - built-in function, 142, 895
 - in module , 14
- SliceType (data in types), 142
- SmartCookie (class in Cookie), 680
- SMTP
 - protocol, 651
- SMTP (class in smtplib), 651
- SMTPAuthenticationError (exception in smtplib), 652
- SMTPConnectError (exception in smtplib), 652
- smtpd (standard module), **655**
- SMTPDataError (exception in smtplib), 652
- SMTPException (exception in smtplib), 651
- SMTPHandler (class in logging), 465
- SMTPHeloError (exception in smtplib), 652
- smtplib (standard module), **651**
- SMTPRecipientsRefused (exception in smtplib), 652
- SMTPResponseException (exception in smtplib), 652
- SMTPSenderRefused (exception in smtplib), 652
- SMTPServer (class in smtpd), 655
- SMTPServerDisconnected (exception in smtplib), 651
- SND_ALIAS (data in winsound), 945
- SND_ASYNC (data in winsound), 946
- SND_FILENAME (data in winsound), 945
- SND_LOOP (data in winsound), 946
- SND_MEMORY (data in winsound), 946
- SND_NODEFAULT (data in winsound), 946
- SND_NOSTOP (data in winsound), 946
- SND_NOWAIT (data in winsound), 946
- SND_PURGE (data in winsound), 946
- sndhdr (standard module), **707**
- sniff () (Sniffer method), 305
- Sniffer (class in csv), 305
- SO_* (data in socket), 578
- SOCK_DGRAM (data in socket), 578
- SOCK_RAW (data in socket), 578
- SOCK_RDM (data in socket), 578
- SOCK_SEQPACKET (data in socket), 578
- SOCK_STREAM (data in socket), 578
- socket
 - object, 577
- socket ()
 - IMAP4_stream method, 646
 - in module socket, 580
- socket
 - built-in module, 39, **577**, 599
 - data in SocketServer, 666
- socket () (in module socket), 536
- socket_type (data in SocketServer), 666
- SocketHandler (class in logging), 463
- socketpair () (in module socket), 580
- SocketServer (standard module), **664**
- SocketType (data in socket), 581
- softspace (file attribute), 41
- SOL_* (data in socket), 578
- SOMAXCONN (data in socket), 578
- sort ()
 - IMAP4_stream method, 646
 - list method, 35
- sort_stats () (Stats method), 816
- sorted () (in module), 14
- sortTestMethodsUsing (TestLoader attribute), 800
- source
 - Example attribute, 781
 - shlex attribute, 761
- sourcehook () (shlex method), 760
- span () (MatchObject method), 61
- spawn () (in module pty), 560
- spawnl () (in module os), 410
- spawnle () (in module os), 410
- spawnlp () (in module os), 410
- spawnlpe () (in module os), 410
- spawnv () (in module os), 411
- spawnve () (in module os), 411
- spawnvp () (in module os), 411
- spawnvpe () (in module os), 411
- specified_attributes (xmlparser attribute), 266
- speed ()
 - audio device method, 709
 - in module turtle, 731
- split ()
 - in module os.path, 327
 - in module re, 58
 - in module shlex, 759
 - in module string, 51
 - RegexObject method, 60
 - string method, 31
- splitdrive () (in module os.path), 327
- splitext () (in module os.path), 327
- splitfields () (in module string), 51
- splitlines () (string method), 31

SplitResult (class in urlparse), 664
 splitunc () (in module os.path), 327
 sprintf-style formatting, 32
 spwd (built-in module), **555**
 sqlite3 (built-in module), **383**
 sqrt ()
 Context method, 162
 Decimal method, 158
 in module cmath, 152
 in module math, 150
 ssl ()
 IMAP4_stream method, 647
 in module socket, 580
 ST_ETIME (data in stat), 331
 ST_ETIME (data in stat), 331
 ST_DEV (data in stat), 331
 ST_GID (data in stat), 331
 ST_INO (data in stat), 331
 ST_MODE (data in stat), 331
 ST_MTIME (data in stat), 331
 ST_NLINK (data in stat), 331
 ST_SIZE (data in stat), 331
 ST_UID (data in stat), 331
 stack () (in module inspect), 850
 stack viewer, 735
 stack_size ()
 in module thread, 537
 in module threading, 539
 stackable
 streams, 77
 standard_b64decode () (in module base64), 251
 standard_b64encode () (in module base64), 251
 StandardError (exception in exceptions), 18
 standend () (window method), 482
 stdout () (window method), 482
 starmap () (in module itertools), 176
 start ()
 MatchObject method, 61
 Profile method, 820
 Thread method, 545
 TreeBuilder method, 301
 start_color () (in module curses), 477
 start_component () (Directory method), 937
 start_new_thread () (in module thread), 537
 startbody () (MimeWriter method), 243
 StartCdataSectionHandler () (xmlparser
 method), 268
 StartDoctypeDeclHandler () (xmlparser
 method), 267
 startDocument () (ContentHandler method), 291
 startElement () (ContentHandler method), 292
 StartElementHandler () (xmlparser method), 267
 startElementNS () (ContentHandler method), 292
 startfile () (in module os), 412
 startmultipartbody () (MimeWriter method),
 243
 StartNamespaceDeclHandler () (xmlparser
 method), 268
 startPrefixMapping () (ContentHandler method),
 291
 startswith () (string method), 31
 startTest () (TestResult method), 799
 starttls () (SMTP method), 653
 stat ()
 in module os, 405
 NNTP method, 650
 POP3_SSL method, 641
 stat (standard module), **330**, 406
 stat_float_times () (in module os), 406
 statement
 assert, 18
 del, 35, 37
 except, 17
 exec, 44
 if, 23
 import, 3, 865
 print, 23
 raise, 17
 try, 17
 while, 23
 staticmethod () (in module), 14
 Stats (class in pstats), 815
 status () (IMAP4_stream method), 646
 status (data in httplib), 636
 statvfs () (in module os), 406
 statvfs (standard module), **332**, 406
 StdButtonBox (class in Tix), 726
 stderr
 data in sys, 832
 Popen attribute, 574
 stdin
 data in sys, 832
 Popen attribute, 573
 stdout
 data in sys, 832
 Popen attribute, 574
 Stein, Greg, 898
 stereocontrols () (mixer device method), 711
 STILL (data in cd), 916
 stop ()
 CD player method, 918
 Profile method, 820
 TestResult method, 799
 StopIteration (exception in exceptions), 20
 stopListening () (in module logging), 469
 stopTest () (TestResult method), 799
 storbinary () (FTP method), 638
 store () (IMAP4_stream method), 646

- storlines() (FTP method), 638
- str()
 - in module , 15
 - in module locale, 752
- strcoll() (in module locale), 751
- StreamError (exception in tarfile), 353
- StreamHandler (class in logging), 462
- StreamReader (class in codecs), 83
- StreamReaderWriter (class in codecs), 84
- StreamRecoder (class in codecs), 85
- streams, 77
 - stackable, 77
- StreamWriter (class in codecs), 83
- strerror() (in module os), 398
- strftime()
 - date method, 101
 - datetime method, 105
 - in module time, 417
 - time method, 107
- strict_domain (LWPCookieJar attribute), 677
- strict_errors() (in module codecs), 79
- strict_ns_domain (LWPCookieJar attribute), 677
- strict_ns_set_initial_dollar (LWPCookieJar attribute), 677
- strict_ns_set_path (LWPCookieJar attribute), 677
- strict_ns_unverifiable (LWPCookieJar attribute), 677
- strict_rfc2965_unverifiable (LWPCookieJar attribute), 677
- string
 - documentation, 877
 - formatting, 32
 - interpolation, 32
 - methods, 29
 - object, 27
- string
 - MatchObject attribute, 61
 - standard module, 34, **47**, 752, 754
- string_at() (in module ctypes), 529
- StringIO
 - class in StringIO, 74
 - standard module, **74**
- stringprep (standard module), **91**
- StringType (data in types), 141
- StringTypes (data in types), 142
- strip()
 - in module string, 52
 - string method, 31
- strip_dirs() (Stats method), 815
- stripspaces (Textbox attribute), 488
- strptime()
 - datetime method, 102
 - in module time, 418
- Struct (class in struct), 65
- struct (built-in module), **62**, 584
- struct_time (data in time), 419
- Structure (class in ctypes), 533
- structures
 - C, 62
- strxfrm() (in module locale), 751
- sub()
 - in module operator, 184
 - in module re, 58
 - RegexObject method, 60
- subdirs (dircmp attribute), 334
- SubElement() (in module xml.etree.ElementTree), 299
- subn()
 - in module re, 59
 - RegexObject method, 60
- Subnormal (class in decimal), 163
- subpad() (window method), 482
- subprocess (standard module), **571**
- subscribe() (IMAP4_stream method), 646
- subscript
 - assignment, 35
 - operation, 28
- subsequent_indent (TextWrapper attribute), 77
- substitute() (Template method), 48
- subtract() (Context method), 162
- subversion (data in sys), 827
- subwin() (window method), 482
- suffix_map (data in mimetypes), 242
- suite() (in module parser), 874
- suiteClass (TestLoader attribute), 801
- sum() (in module), 15
- summarize() (DocTestRunner method), 784
- sunau (standard module), **699**
- SUNAUDIODEV (standard module), 931, **932**
- sunaudiodev (built-in module), **931**, 932
- super() (in module), 15
- super (class descriptor attribute), 886
- supports_unicode_filenames (data in os.path), 328
- swapcase()
 - in module string, 52
 - string method, 32
- sym() (method), 558
- sym_name (data in symbol), 882
- symbol (standard module), **882**
- symbol table, 3
- symlink() (in module os), 406
- sync()
 - method, 381, 383
 - audio device method, 709
 - dbhash method, 379
 - in module gdbm, 378

- Shelf method, 371
- syncdown() (window method), 482
- syncok() (window method), 482
- syncup() (window method), 482
- SyntaxErr (exception in xml.dom), 281
- SyntaxError (exception in exceptions), 20
- SyntaxWarning (exception in exceptions), 21
- sys (built-in module), **827**
- sys_version (BaseHTTPRequestHandler attribute), 668
- sysconf() (in module os), 414
- sysconf_names (data in os), 414
- syslog() (in module syslog), 568
- syslog (built-in module), **568**
- SysLogHandler (class in logging), 464
- system()
 - in module os, 412
 - in module platform, 493
- system.listMethods() (ServerProxy method), 685
- system.methodHelp() (ServerProxy method), 685
- system.methodSignature() (ServerProxy method), 685
- system_alias() (in module platform), 493
- SystemError (exception in exceptions), 20
- SystemExit (exception in exceptions), 20
- systemId (DocumentType attribute), 277
- SystemRandom (class in random), 171

T

- T_FMT (data in locale), 752
- T_FMT_AMPM (data in locale), 752
- tabnanny (standard module), **885**
- tabular
 - data, 303
- tagName (Element attribute), 278
- takewhile() (in module itertools), 177
- tan()
 - in module cmath, 152
 - in module math, 151
- tanh()
 - in module cmath, 152
 - in module math, 151
- TAR_GZIPPED (data in tarfile), 353
- TAR_PLAIN (data in tarfile), 353
- TarError (exception in tarfile), 353
- TarFile (class in tarfile), 352, 353
- tarfile (standard module), **351**
- TarFileCompat (class in tarfile), 352
- target (ProcessingInstruction attribute), 280
- TarInfo (class in tarfile), 355
- task_done() (Queue method), 134
- tb_lineno() (in module traceback), 841
- tcdrain() (in module termios), 559
- tcflow() (in module termios), 559
- tcflush() (in module termios), 559
- tcgetattr() (in module termios), 558
- tcgetpgrp() (in module os), 401
- Tcl() (in module Tkinter), 714
- TCP_* (data in socket), 578
- tcsendbreak() (in module termios), 559
- tcsetattr() (in module termios), 559
- tcsetpgrp() (in module os), 401
- tearDown() (TestCase method), 796
- tee() (in module itertools), 177
- tell()
 - method, 548
 - aifc method, 698, 699
 - AU_read method, 701
 - AU_write method, 701
 - BZ2File method, 347
 - Chunk method, 704
 - file method, 40
 - MultiFile method, 246
 - Wave_read method, 703
 - Wave_write method, 703
- Telnet (class in telnetlib), 656
- telnetlib (standard module), **656**
- TEMP, 336
- tempdir (data in tempfile), 336
- tempfile (standard module), **334**
- Template
 - class in pipes, 562
 - class in string, 48
- template
 - data in tempfile, 336
 - string attribute, 49
- tempnam() (in module os), 406
- temporary
 - file, 334
 - file name, 334
- TemporaryFile() (in module tempfile), 334
- termattrs() (in module curses), 477
- termios (built-in module), **558**
- termname() (in module curses), 477
- test()
 - in module cgi, 606
 - mutex method, 132
- test
 - DocTestFailure attribute, 788
 - standard module, **801**
 - UnexpectedException attribute, 788
- test.test_support (standard module), **803**
- testandset() (mutex method), 132
- TestCase (class in unittest), 795
- TestFailed (exception in test.test_support), 804
- testfile() (in module doctest), 776
- TESTFN (data in test.test_support), 804
- TestLoader (class in unittest), 796

- testMethodPrefix (TestLoader attribute), 800
- testmod() (in module doctest), 777
- TestResult (class in unittest), 796
- tests (data in imghdr), 706
- TestSkipped (exception in test.test.support), 804
- testsource() (in module doctest), 787
- testsRun (TestResult attribute), 799
- TestSuite (class in unittest), 796
- testzip() (ZipFile method), 349
- text() (Dialog method), 938
- text (data in msilib), 939
- text_factory (attribute), 388
- Textbox (class in curses.textpad), 487
- TextCalendar (class in calendar), 114
- textdomain() (in module gettext), 740
- TextTestRunner (class in unittest), 796
- textwrap (standard module), **75**
- TextWrapper (class in textwrap), 76
- THOUSEP (data in locale), 753
- Thread (class in threading), 539, 544
- thread() (IMAP4_stream method), 646
- thread (built-in module), **536**
- threading (standard module), **538**
- threads
 - IRIX, 538
 - POSIX, 537
- tie() (in module fl), 920
- tigetflag() (in module curses), 477
- tigetnum() (in module curses), 477
- tigetstr() (in module curses), 477
- time()
 - datetime method, 103
 - in module time, 419
- time
 - built-in module, **415**
 - class in datetime, 96, 105
- Time2Internaldate() (in module imaplib), 643
- timedelta (class in datetime), 96, 97
- TimedRotatingFileHandler (class in logging), 463
- timegm() (in module calendar), 115
- timeit() (Timer method), 821
- timeit (standard module), **821**
- timeout() (window method), 483
- timeout (exception in socket), 578
- Timer
 - class in threading, 539, 546
 - class in timeit, 821
- times() (in module os), 412
- timetuple()
 - date method, 100
 - datetime method, 104
- timetz() (datetime method), 103
- timezone (data in time), 419
- title()
 - in module turtle, 730
 - string method, 32
- Tix, 725
- Tix
 - class in Tix, 725
 - standard module, **725**
- tix_addbitmapdir() (tixCommand method), 729
- tix_cget() (tixCommand method), 729
- tix_configure() (tixCommand method), 729
- tix_filedialog() (tixCommand method), 729
- tix_getbitmap() (tixCommand method), 729
- tix_getimage() (tixCommand method), 729
- TIX.LIBRARY, 725**
- tix_option_get() (tixCommand method), 729
- tix_resetoptions() (tixCommand method), 729
- tixCommand (class in Tix), 728
- Tk, 713
- Tk (class in Tkinter), 714
- Tk Option Data Types, 722
- Tkinter, 713
- Tkinter (standard module), **713**
- TList (class in Tix), 727
- TMP, 336, 406
- TMP_MAX (data in os), 407
- TMPDIR, 336, 406
- tmpfile() (in module os), 399
- tmpnam() (in module os), 407
- to_eng_string()
 - Context method, 162
 - Decimal method, 158
- to_integral()
 - Context method, 162
 - Decimal method, 158
- to_sci_string() (Context method), 162
- toSplittable() (Charset method), 204
- ToASCII() (in module encodings.idna), 89
- tobuf() (TarInfo method), 355
- tochild (Popen4 attribute), 591
- today()
 - date method, 99
 - datetime method, 101
- tofile() (array method), 127
- togglepause() (CD player method), 918
- tok_name (data in token), 883
- token
 - shlex attribute, 761
 - standard module, **883**
- token eater() (in module tabnanny), 885
- tokenize() (in module tokenize), 884
- tokenize (standard module), **883**
- tolist()
 - array method, 127
 - AST method, 876

tomono() (in module audioop), 695
 toordinal()
 date method, 100
 datetime method, 105
 top()
 method, 492
 POP3_SSL method, 641
 top_panel() (in module curses.panel), 491
 toprettyxml() (Node method), 284
 tostereo() (in module audioop), 695
 tostring()
 array method, 127
 in module xml.etree.ElementTree, 300
 total_changes (attribute), 388
 totuple() (AST method), 876
 touchline() (window method), 483
 touchwin() (window method), 483
 ToUnicode() (in module encodings.idna), 89
 tounicode() (array method), 127
 tovideo() (in module imageop), 696
 towards() (in module turtle), 732
 toxml() (Node method), 284
 tparm() (in module curses), 477
 Trace (class in trace), 824
 trace() (in module inspect), 850
 trace (standard module), **823**
 trace function, 539, 832
 traceback
 object, 828, 840
 traceback (standard module), **840**
 traceback_limit (BaseHandler attribute), 616
 tracebacklimit (data in sys), 833
 tracebacks
 in CGI scripts, 609
 TracebackType (data in types), 142
 tracer() (in module turtle), 731
 transfercmd() (FTP method), 638
 translate()
 in module fnmatch, 337
 in module string, 52
 string method, 32
 translation() (in module gettext), 741
 Tree (class in Tix), 727
 TreeBuilder (class in xml.etree.ElementTree), 301
 True, 23, 44
 True (data in), 22
 true, 23
 truediv() (in module operator), 184
 truncate() (file method), 40
 truth
 value, 23
 truth() (in module operator), 183
 try
 statement, 17
 ttob()
 in module imgfile, 928
 in module rgbimg, 706
 tty
 I/O control, 558
 tty (standard module), **559**
 ttyname() (in module os), 401
 tuple
 object, 27
 tuple() (in module), 15
 tuple2ast() (in module parser), 875
 TupleType (data in types), 141
 turnoff_sigfpe() (in module fpectl), 852
 turnon_sigfpe() (in module fpectl), 852
 Turtle (class in turtle), 732
 turtle (standard module), **730**
 Tutt, Bill, 898
 type
 Boolean, 4
 object, 15
 operations on dictionary, 37
 operations on list, 35
 type()
 built-in function, 44, 141
 in module , 15
 type
 socket attribute, 584
 TarInfo attribute, 355
 typeahead() (in module curses), 477
 typecode (array attribute), 126
 typed_subpart_iterator() (in module email.iterators), 209
 TypeError (exception in exceptions), 20
 types
 built-in, 3, 23
 mutable sequence, 34
 operations on integer, 26
 operations on mapping, 37
 operations on mutable sequence, 35
 operations on numeric, 25
 operations on sequence, 28, 35
 types (standard module), 44, **140**
 types_map (data in mimetypes), 242
 TypeType (data in types), 141
 TZ, 419, 420
 tzinfo
 class in datetime, 96
 datetime attribute, 102
 time attribute, 106
 tzname()
 datetime method, 104
 time method, 107, 108
 tzname (data in time), 419
 tzset() (in module time), 419

U

U (data in re), 57

u-LAW, 693, 699, 707, 931

ucd_3_2_0 (data in unicodedata), 91

ugettext ()

 GNUTranslations method, 744

 NullTranslations method, 742

uid () (IMAP4_stream method), 646

uid (TarInfo attribute), 356

uidl () (POP3_SSL method), 641

ulaw2lin () (in module audioop), 695

umask () (in module os), 398

uname ()

 in module os, 398

 in module platform, 493

uname (TarInfo attribute), 356

UnboundLocalError (exception in exceptions), 20

UnboundMethodType (data in types), 142

unbuffered I/O, 10

UNC paths

 and os.makedirs (), 404

unconsumed_tail (attribute), 344

unctrl ()

 in module curses, 477

 in module curses.ascii, 490

Underflow (class in decimal), 163

undoc_header (Cmd attribute), 759

unescape () (in module xml.sax.saxutils), 294

UnexpectedException (exception in doctest), 788

unfreeze_form () (form method), 921

unfreeze_object () (FORMS object method), 923

ungetch ()

 in module curses, 478

 in module msvcrt, 940

ungetmouse () (in module curses), 478

ungettext ()

 GNUTranslations method, 744

 NullTranslations method, 742

unhexlify () (in module binascii), 254

unichr () (in module), 15

UNICODE (data in re), 57

Unicode, 77, 90

 database, 90

 object, 27

unicode () (in module), 16

unicodedata (standard module), 90

UnicodeDecodeError (exception in exceptions), 21

UnicodeEncodeError (exception in exceptions), 21

UnicodeError (exception in exceptions), 21

UnicodeTranslateError (exception in exceptions), 21

UnicodeType (data in types), 141

UnicodeWarning (exception in exceptions), 21

unidata_version (data in unicodedata), 91

unified_diff () (in module difflib), 68

uniform () (in module random), 170

UnimplementedFileMode (exception in httpplib), 633

Union (class in ctypes), 533

unittest (standard module), 789

UNIX

 file control, 560

 I/O control, 560

unixfrom (AddressList attribute), 250

UnixMailbox (class in mailbox), 234

unknown_charref () (SGMLParser method), 261

unknown_endtag () (SGMLParser method), 261

unknown_entityref () (SGMLParser method), 261

unknown_open ()

 BaseHandler method, 627

 HTTPErrorProcessor method, 630

 UnknownHandler method, 630

unknown_starttag () (SGMLParser method), 261

UnknownHandler (class in urllib2), 624

UnknownProtocol (exception in httpplib), 633

UnknownTransferEncoding (exception in httpplib), 633

unlink ()

 in module os, 407

 Node method, 284

unlock ()

 Babyl method, 225

 Mailbox method, 221

 Maildir method, 222

 mbox method, 223

 MH method, 224

 MMDF method, 226

 mutex method, 133

unmimify () (in module mimic), 244

unpack ()

 in module struct, 63

 Struct method, 65

unpack_array () (Unpacker method), 317

unpack_bytes () (Unpacker method), 317

unpack_double () (Unpacker method), 316

unpack_farray () (Unpacker method), 317

unpack_float () (Unpacker method), 316

unpack_fopaque () (Unpacker method), 317

unpack_from ()

 in module struct, 63

 Struct method, 65

unpack_fstring () (Unpacker method), 316

unpack_list () (Unpacker method), 317

unpack_opaque () (Unpacker method), 317

unpack_string () (Unpacker method), 317

Unpacker (class in xdrlib), 315

unparsedEntityDecl () (DTDHandler method), 293

UnparsedEntityDeclHandler() (xmlparser method), 267
 Unpickler (class in pickle), 362
 UnpicklingError (exception in pickle), 362
 unqdevice() (in module fl), 920
 unquote()
 in module email.utils, 207
 in module rfc822, 248
 in module urllib, 619
 unquote_plus() (in module urllib), 619
 unregister() (method), 536
 unregister_dialect() (in module csv), 304
 unsetenv() (in module os), 398
 unsubscribe() (IMAP4_stream method), 647
 untokenize() (in module tokenize), 884
 untouchwin() (window method), 483
 unused_data (attribute), 344
 up() (in module turtle), 731
 update()
 dictionary method, 37
 hash method, 320
 hmac method, 321
 Mailbox method, 221
 Maildir method, 222
 md5 method, 322
 sha method, 323
 update_panels() (in module curses.panel), 491
 update_visible() (BabylMessage method), 231
 update_wrapper() (in module functools), 181
 upper()
 in module string, 52
 string method, 32
 uppercase (data in string), 48
 urandom() (in module os), 415
 URL, 313, 602, 617, 661, 667
 parsing, 661
 relative, 661
 url (ServerProxy attribute), 686
 url2pathname() (in module urllib), 619
 urlcleanup() (in module urllib), 619
 urldefrag() (in module urlparse), 663
 urlencode() (in module urllib), 619
 URLError (exception in urllib2), 623
 urljoin() (in module urlparse), 663
 urllib (standard module), **617**, 632
 urllib2 (standard module), **622**
 urlopen()
 in module urllib, 617
 in module urllib2, 622
 URLOpener (class in urllib), 619
 urlparse() (in module urlparse), 661
 urlparse (standard module), 621, **661**
 urlretrieve() (in module urllib), 618
 urlsafe_b64decode() (in module base64), 251
 urlsafe_b64encode() (in module base64), 251
 urlsplit() (in module urlparse), 662
 urlunparse() (in module urlparse), 662
 urlunsplit() (in module urlparse), 663
 urn (UUID attribute), 659
 use_default_colors() (in module curses), 478
 use_env() (in module curses), 478
 use_rawinput (Cmd attribute), 759
 UseForeignDTD() (xmlparser method), 265
 USER, 472
 user
 configuration file, 851
 effective id, 396
 id, 397
 id, setting, 398
 user() (POP3_SSL method), 641
 user (standard module), **851**
 UserDict
 class in UserDict, 138
 standard module, **138**
 UserList
 class in UserList, 139
 standard module, **139**
 USERNAME, 472
 userptr() (method), 492
 UserString
 class in UserString, 140
 standard module, **140**
 UserWarning (exception in exceptions), 21
 UTC, 415
 utcfromtimestamp() (datetime method), 102
 utcnow() (datetime method), 101
 utcoffset()
 datetime method, 104
 time method, 107
 utctimetuple() (datetime method), 104
 utime() (in module os), 407
 uu (standard module), 253, **256**
 UUID (class in uuid), 659
 uuid (built-in module), **658**
 uuid1, 660
 uuid1() (in module uuid), 660
 uuid3, 660
 uuid3() (in module uuid), 660
 uuid4, 660
 uuid4() (in module uuid), 660
 uuid5, 660
 uuid5() (in module uuid), 660
 UUIDCreate() (in module msilib), 933

V
 validator() (in module wsgiref.validate), 614
 value
 truth, 23

- value
 - _SimpleCDATA attribute, 531
 - Cookie attribute, 678
 - Morsel attribute, 681
- value_decode() (BaseCookie method), 681
- value_encode() (BaseCookie method), 681
- ValueError (exception in exceptions), 21
- valuerefs() (WeakValueDictionary method), 136
- values
 - Boolean, 44
- values()
 - dictionary method, 37
 - Mailbox method, 220
 - Message method, 192
- variant (UUID attribute), 659
- varray() (in module gl), 926
- vars() (in module), 16
- vbar (ScrolledText attribute), 730
- VERBOSE (data in re), 58
- verbose
 - data in tabnanny, 885
 - data in test.test_support, 804
- verify() (SMTP method), 653
- verify_request() (in module SocketServer), 667
- version() (in module platform), 493
- version
 - Cookie attribute, 678
 - data in curses, 483
 - data in httplib, 636
 - data in marshal, 375
 - data in sys, 833
 - URLopener attribute, 621
 - UUID attribute, 659
- version_info (data in sys), 833
- version_string() (BaseHTTPRequestHandler method), 670
- vline() (window method), 483
- vnarray() (in module gl), 926
- voidcmd() (FTP method), 638
- volume (ZipInfo attribute), 351
- vonmisesvariate() (in module random), 171

W

- W_OK (data in os), 402
- wait()
 - Condition method, 542
 - Event method, 544
 - in module os, 412
 - Popen4 method, 591
 - Popen method, 573
- wait3() (in module os), 413
- wait4() (in module os), 413
- waitpid() (in module os), 412
- walk()
 - in module compiler, 897
 - in module compiler.visitor, 903
 - in module os, 407
 - in module os.path, 328
 - Message method, 195
- want (Example attribute), 781
- warn() (in module warnings), 836
- warn_explicit() (in module warnings), 836
- Warning (exception in exceptions), 21
- warning()
 - method, 455
 - ErrorHandler method, 293
 - in module logging, 452
- warnings, 834
- warnings (standard module), **834**
- warnoptions (data in sys), 833
- wasSuccessful() (TestResult method), 799
- wave (standard module), **702**
- WCONTINUED (data in os), 413
- WCOREDUMP() (in module os), 413
- WeakKeyDictionary (class in weakref), 136
- weakref (extension module), **134**
- WeakValueDictionary (class in weakref), 136
- webbrowser (standard module), **599**
- weekday()
 - date method, 100
 - datetime method, 105
 - in module calendar, 115
- weekheader() (in module calendar), 115
- weibullvariate() (in module random), 171
- WEXITSTATUS() (in module os), 413
- wfile (BaseHTTPRequestHandler attribute), 668
- what()
 - in module imghdr, 706
 - in module sndhdr, 707
- whathdr() (in module sndhdr), 707
- whichdb() (in module whichdb), 376
- whichdb (standard module), **376**
- while
 - statement, 23
- whitespace
 - data in string, 48
 - shlex attribute, 761
- whitespace_split (shlex attribute), 761
- whseed() (in module random), 171
- WichmannHill (class in random), 171
- width() (in module turtle), 731
- width (TextWrapper attribute), 76
- WIFCONTINUED() (in module os), 413
- WIFEXITED() (in module os), 413
- WIFSIGNALED() (in module os), 413
- WIFSTOPPED() (in module os), 413
- Wimp\$ScrapDir, 336
- win32_ver() (in module platform), 493

WinDLL (class in ctypes), 523
 window() (method), 492
 window manager (widgets), 721
 window_height() (in module turtle), 732
 window_width() (in module turtle), 732
 Windows ini file, 310
 WindowsError (exception in exceptions), 21
 WinError() (in module ctypes), 529
 WINFUNCTYPE() (in module ctypes), 526
 WinSock, 536
 winsound (built-in module), **945**
 winver (data in sys), 833
 WNOHANG (data in os), 413
 wordchars (shlex attribute), 761
 World Wide Web, 313, 599, 617, 661
 wrap()
 in module textwrap, 75
 TextWrapper method, 77
 wrapper() (in module curses.wrapper), 488
 wraps() (in module functools), 181
 writable()
 async_chat method, 597
 dispatcher method, 593
 write()
 method, 548, 584
 array method, 127
 audio device method, 708, 932
 BZ2File method, 347
 ElementTree method, 301
 file method, 41
 Generator method, 199
 in module imgfile, 928
 in module os, 401
 in module turtle, 731
 InteractiveConsole method, 856
 SafeConfigParser method, 312
 StreamWriter method, 83
 Telnet method, 657
 ZipFile method, 349
 write_byte() (method), 549
 write_history_file() (in module readline), 549
 writeall() (audio device method), 708
 writeframes()
 aifc method, 699
 AU_write method, 701
 Wave_write method, 703
 writeframesraw()
 aifc method, 699
 AU_write method, 701
 Wave_write method, 703
 writelines()
 BZ2File method, 347
 file method, 41
 StreamWriter method, 83
 writepy() (PyZipFile method), 350
 writer() (in module csv), 304
 writer (formatter attribute), 909
 writerow() (csv writer method), 307
 writerows() (csv writer method), 307
 writesamps() (audio port method), 915
 writestr() (ZipFile method), 350
 writexml() (Node method), 284
 WrongDocumentErr (exception in xml.dom), 281
 wsgi_file_wrapper (BaseHandler attribute), 616
 wsgi_multiprocess (BaseHandler attribute), 615
 wsgi_multithread (BaseHandler attribute), 615
 wsgi_run_once (BaseHandler attribute), 615
 wsgiref (module), **610**
 wsgiref.handlers (module), **614**
 wsgiref.headers (module), **611**
 wsgiref.simple_server (module), **612**
 wsgiref.util (module), **610**
 wsgiref.validate (module), **613**
 WSGIRequestHandler (class in wsgiref.simple_-.server), 613
 WSGIServer (class in wsgiref.simple_server), 613
 WSTOPSIG() (in module os), 413
 wstring_at() (in module ctypes), 530
 WTERMSIG() (in module os), 413
 WUNTRACED (data in os), 413
 WWW, 313, 599, 617, 661
 server, 602, 667

X

X (data in re), 58
 X_OK (data in os), 402
 xatom() (IMAP4_stream method), 647
 XDR, 315, 360
 xdrlib (standard module), **315**
 xgtitle() (NNTP method), 651
 xhdr() (NNTP method), 650
 XHTML, 257
 XHTML_NAMESPACE (data in xml.dom), 274
 XML() (in module xml.etree.ElementTree), 300
 xml.dom (standard module), **272**
 xml.dom.minidom (standard module), **282**
 xml.dom.pulldom (standard module), **287**
 xml.etree.ElementTree (standard module), **298**
 xml.parsers.expat (standard module), **264**
 xml.sax (standard module), **288**
 xml.sax.handler (standard module), **289**
 xml.sax.saxutils (standard module), **293**
 xml.sax.xmlreader (standard module), **294**
 XML_NAMESPACE (data in xml.dom), 274
 xmlcharrefreplace_errors_errors() (in module codecs), 79
 XmlDeclHandler() (xmlparser method), 267
 XMLFilterBase (class in xml.sax.saxutils), 294

- XMLGenerator (class in xml.sax.saxutils), 294
- XMLID () (in module xml.etree.ElementTree), 300
- XMLNS_NAMESPACE (data in xml.dom), 274
- XMLParserType (data in xml.parsers.expat), 264
- XMLReader (class in xml.sax.xmlreader), 294
- xmlrpclib (standard module), **684**
- XMLTreeBuilder (class in xml.etree.ElementTree), 302
- xor () (in module operator), 184
- xover () (NNTP method), 651
- xpath () (NNTP method), 651
- xrange
 - object, 27, 34
- xrange ()
 - built-in function, 27, 142
 - in module , 16
- XRangeType (data in types), 142
- xreadlines ()
 - BZ2File method, 347
 - file method, 40

Y

- Y2K, 415
- year
 - date attribute, 99
 - datetime attribute, 102
- Year 2000, 415
- Year 2038, 415
- yeardatescalendar () (Calendar method), 114
- yeardays2calendar () (Calendar method), 114
- yeardayscalendar () (Calendar method), 114
- YESEXPR (data in locale), 753
- yi_q_to_rgb () (in module colorsys), 705

Z

- ZeroDivisionError (exception in exceptions), 21
- zfill ()
 - in module string, 52
 - string method, 32
- zip () (in module), 16
- ZIP_DEFLATED (data in zipfile), 348
- ZIP_STORED (data in zipfile), 348
- ZipFile (class in zipfile), 348, 349
- zipfile (standard module), **348**
- zipimport (standard module), **868**
- zipimporter (class in zipimport), 869
- ZipImportError (exception in zipimport), 869
- ZipInfo (class in zipfile), 348
- zlib (built-in module), **343**